



ORACLE
PRESS



CORE **JAVA**

Volume II: Advanced Features

TWELFTH EDITION

ORACLE

Cay S. Horstmann

About This eBook

ePUB is an open, industry-standard format for eBooks. However, support of ePUB and its many features varies across reading devices and applications. Use your device or app settings to customize the presentation to your liking. Settings that you can customize often include font, font size, single or double column, landscape or portrait mode, and figures that you can click or tap to enlarge. For additional information about the settings and features on your reading device or app, visit the device manufacturer's Web site.

Many titles include programming code or configuration examples. To optimize the presentation of these elements, view the eBook in single-column, landscape mode and adjust the font size to the smallest setting. In addition to presenting code and configurations in the reflowable text format, we have included images of the code that mimic the presentation found in the print book; therefore, where the reflowable format may compromise the presentation of the code listing, you will see a “Click here to view code image” link. Click the link to view the print-fidelity code image. To return to the previous page viewed, click the Back button on your device or app.

Core Java

Volume II: Advanced Features

Twelfth Edition

Core Java

Volume II: Advanced Features

Twelfth Edition

Cay S. Horstmann



**Boston • Columbus • New York • San Francisco • Amsterdam • Cape
Town**
**Dubai • London • Madrid • Milan • Munich • Paris • Montreal •
Toronto • Delhi • Mexico City**
São Paulo • Sydney • Hong Kong • Seoul • Singapore • Taipei • Tokyo

Cover image: Leyland/Shutterstock

[Figure 11.51](#): Shao.Chun Wang/123RF

[Figure 9.2](#): Screenshot © Eclipse Foundation

[Figure 10.4](#): Screenshot © 1999 . 2022 HHD Software Ltd

[Figures 4.1, 4.2, 4.3, 4.4, 4.5, 5.3, 5.4](#), and [12.4](#): Screenshot © Microsoft 2022

[Figures 3.3, 4.9, and 8.2](#): Screenshot © Mozilla Foundation

[Figure 4.7](#): Screenshot © 2022 USPS

[Figures 4.6, 5.6, 7.1, 7.2, 7.3, 7.4, 7.5, 7.6, 10.3, 10.9, 11.1, 11.2, 11.3, 1.4, 11.5, 11.7, 11.8, 11.9, 11.10, 11.14, 11.15, 11.16, 11.17, 11.18, 11.19, 11.20, 11.21, 11.22, 11.23, 11.24, 11.25, 11.26, 11.28, 11.29, 11.30, 11.39, 11.44, 11.47, 11.54, 11.55, 11.56, 11.60, and 11.62](#): Screenshot © 2022 Oracle

The author and publisher have taken care in the preparation of this book, but make no expressed or implied warranty of any kind and assume no responsibility for errors or omissions. No liability is assumed for incidental or consequential damages in connection with or arising out of the use of the information or programs contained herein.

The views expressed in this book are those of the author and do not necessarily reflect the views of Oracle.

For information about buying this title in bulk quantities, or for special sales opportunities (which may include electronic versions; custom cover designs; and content particular to your business, training goals, marketing focus, or branding interests), please contact our corporate sales department at corpsales@pearsoned.com or (800) 382-3419.

For government sales inquiries, please contact governmentsales@pearsoned.com.

For questions about sales outside the United States, please contact international@pearsoned.com.

Visit us on the Web: informit.com

Library of Congress Preassigned Control Number: 2022930917

Copyright © 2022 Pearson Education Inc.

Portions copyright © 1996-2013 Oracle and/or its affiliates. All Rights Reserved.

Oracle America Inc. does not make any representations or warranties as to the accuracy, adequacy or completeness of any information contained in this work, and is not responsible for any errors or omissions.

Microsoft and/or its respective suppliers make no representations about the suitability of the information contained in the documents and related graphics published as part of the services for any purpose. All such documents and related graphics are provided "as is" without warranty of any kind. Microsoft and/or its respective suppliers hereby disclaim all warranties and conditions with regard to this information, including all warranties and conditions of merchantability, whether express, implied or statutory, fitness for a particular purpose, title and non-infringement. In no event shall Microsoft and/or its respective suppliers be liable for any special, indirect or consequential damages or any damages whatsoever resulting from loss of use, data or profits, whether in an action of contract, negligence or other tortious action, arising out of or in connection with the use or performance of information available from the services. The documents and related graphics contained herein could include technical inaccuracies or typographical errors. Changes are periodically added to the information herein. Microsoft and/or its respective suppliers may make improvements and/or changes in the product(s) and/or the program(s) described herein at any time. Partial screen shots may be viewed in full within the software version specified.

Microsoft® Windows®, and Microsoft Office® are registered trademarks of the Microsoft Corporation in the U.S.A. and other countries. This book is not sponsored or endorsed by or affiliated with the Microsoft Corporation.

All rights reserved. This publication is protected by copyright, and permission must be obtained from the publisher prior to any prohibited reproduction, storage in a retrieval system, or transmission in any form or by any means, electronic, mechanical, photocopying, recording, or likewise. For information regarding permissions, request forms and the appropriate contacts within the Pearson Education Global Rights & Permissions Department, please visit www.pearson.com/permissions/.

ISBN-13: 978-0-13-787107-0

ISBN-10: 0-13-787107-4

ScoutAutomatedPrintCode

Pearson's Commitment to Diversity, Equity, and Inclusion

Pearson is dedicated to creating bias-free content that reflects the diversity of all learners. We embrace the many dimensions of diversity, including but not limited to race, ethnicity, gender, socioeconomic status, ability, age, sexual orientation, and religious or political beliefs.

Education is a powerful force for equity and change in our world. It has the potential to deliver opportunities that improve lives and enable economic mobility. As we work with authors to create content for every product and service, we acknowledge our responsibility to demonstrate inclusivity and incorporate diverse scholarship so that everyone can achieve their potential through learning. As the world's leading learning company, we have a duty to help drive change and live up to our purpose to help more people create a better life for themselves and to create a better world.

Our ambition is to purposefully contribute to a world where:

- Everyone has an equitable and lifelong opportunity to succeed through learning.
- Our educational products and services are inclusive and represent the rich diversity of learners.
- Our educational content accurately reflects the histories and experiences of the learners we serve.
- Our educational content prompts deeper discussions with learners and motivates them to expand their own learning (and worldview).

While we work hard to present unbiased content, we want to hear from you about any concerns or needs with this Pearson product so that we can investigate and address them.

- ▶ Please contact us with concerns about any potential bias at <https://www.pearson.com/report-bias.html>.

Contents

Preface

Acknowledgments

Chapter 1: Streams

- 1.1 From Iterating to Stream Operations
- 1.2 Stream Creation
- 1.3 The `filter`, `map`, and `flatMap` Methods
- 1.4 Extracting Substreams and Combining Streams
- 1.5 Other Stream Transformations
- 1.6 Simple Reductions
- 1.7 The Optional Type
 - 1.7.1 Getting an Optional Value
 - 1.7.2 Consuming an Optional Value
 - 1.7.3 Pipelining Optional Values
 - 1.7.4 How Not to Work with Optional Values
 - 1.7.5 Creating Optional Values
 - 1.7.6 Composing Optional Value Functions with `flatMap`
 - 1.7.7 Turning an Optional into a Stream
- 1.8 Collecting Results
- 1.9 Collecting into Maps
- 1.10 Grouping and Partitioning
- 1.11 Downstream Collectors
- 1.12 Reduction Operations

1.13 Primitive Type Streams

1.14 Parallel Streams

Chapter 2: Input and Output

2.1 Input/Output Streams

 2.1.1 Reading and Writing Bytes

 2.1.2 The Complete Stream Zoo

 2.1.3 Combining Input/Output Stream Filters

 2.1.4 Text Input and Output

 2.1.5 How to Write Text Output

 2.1.6 How to Read Text Input

 2.1.7 Saving Objects in Text Format

 2.1.8 Character Encodings

2.2 Reading and Writing Binary Data

 2.2.1 The DataInput and DataOutput Interfaces

 2.2.2 Random-Access Files

 2.2.3 ZIP Archives

2.3 Object Input/Output Streams and Serialization

 2.3.1 Saving and Loading Serializable Objects

 2.3.2 Understanding the Object Serialization File Format

 2.3.3 Modifying the Default Serialization Mechanism

 2.3.4 The `readResolve` and `writeReplace` Methods

 2.3.5 Versioning

 2.3.6 Using Serialization for Cloning

 2.3.7 Deserialization and Security

2.4 Working with Files

 2.4.1 Paths

 2.4.2 Reading and Writing Files

 2.4.3 Creating Files and Directories

 2.4.4 Copying, Moving, and Deleting Files

 2.4.5 Getting File Information

- 2.4.6 Visiting Directory Entries
- 2.4.7 Using Directory Streams
- 2.4.8 ZIP File Systems
- 2.5 Memory-Mapped Files
 - 2.5.1 Memory-Mapped File Performance
 - 2.5.2 The Buffer Data Structure
- 2.6 File Locking
- 2.7 Regular Expressions
 - 2.7.1 The Regular Expression Syntax
 - 2.7.2 Matching an Entire String
 - 2.7.3 Finding All Matches in a String
 - 2.7.4 Groups
 - 2.7.5 Splitting along Delimiters
 - 2.7.6 Replacing Matches
 - 2.7.7 Flags

Chapter 3: XML

- 3.1 Introducing XML
- 3.2 The Structure of an XML Document
- 3.3 Parsing an XML Document
- 3.4 Validating XML Documents
 - 3.4.1 Document Type Definitions
 - 3.4.2 XML Schema
 - 3.4.3 A Practical Example
- 3.5 Locating Information with XPath
- 3.6 Using Namespaces
- 3.7 Streaming Parsers
 - 3.7.1 Using the SAX Parser
 - 3.7.2 Using the StAX Parser
- 3.8 Generating XML Documents
 - 3.8.1 Documents without Namespaces

- 3.8.2 Documents with Namespaces
 - 3.8.3 Writing Documents
 - 3.8.4 Writing an XML Document with StAX
 - 3.8.5 An Example: Generating an SVG File
- 3.9 XSL Transformations

Chapter 4: Networking

- 4.1 Connecting to a Server
 - 4.1.1 Using Telnet
 - 4.1.2 Connecting to a Server with Java
 - 4.1.3 Socket Timeouts
 - 4.1.4 Internet Addresses
- 4.2 Implementing Servers
 - 4.2.1 Server Sockets
 - 4.2.2 Serving Multiple Clients
 - 4.2.3 Half-Close
 - 4.2.4 Interruptible Sockets
- 4.3 Getting Web Data
 - 4.3.1 URLs and URIs
 - 4.3.2 Using a URLConnection to Retrieve Information
 - 4.3.3 Posting Form Data
- 4.4 The HTTP Client
 - 4.4.1 The HttpClient Class
 - 4.4.2 The HttpRequest class and Body Publishers
 - 4.4.3 The HttpResponse Interface and Body Handlers
 - 4.4.4 Asynchronous Processing
- 4.5 Sending E-Mail

Chapter 5: Database Programming

- 5.1 The Design of JDBC
 - 5.1.1 JDBC Driver Types

- 5.1.2 Typical Uses of JDBC
- 5.2 The Structured Query Language
- 5.3 JDBC Configuration
 - 5.3.1 Database URLs
 - 5.3.2 Driver JAR Files
 - 5.3.3 Starting the Database
 - 5.3.4 Registering the Driver Class
 - 5.3.5 Connecting to the Database
- 5.4 Working with JDBC Statements
 - 5.4.1 Executing SQL Statements
 - 5.4.2 Managing Connections, Statements, and Result Sets
 - 5.4.3 Analyzing SQL Exceptions
 - 5.4.4 Populating a Database
- 5.5 Query Execution
 - 5.5.1 Prepared Statements
 - 5.5.2 Reading and Writing LOBs
 - 5.5.3 SQL Escapes
 - 5.5.4 Multiple Results
 - 5.5.5 Retrieving Autogenerated Keys
- 5.6 Scrollable and Updatable Result Sets
 - 5.6.1 Scrollable Result Sets
 - 5.6.2 Updatable Result Sets
- 5.7 Row Sets
 - 5.7.1 Constructing Row Sets
 - 5.7.2 Cached Row Sets
- 5.8 Metadata
- 5.9 Transactions
 - 5.9.1 Programming Transactions with JDBC
 - 5.9.2 Save Points
 - 5.9.3 Batch Updates
 - 5.9.4 Advanced SQL Types

5.10 Connection Management in Web and Enterprise Applications

Chapter 6: The Date and Time API

- 6.1 The Time Line
- 6.2 Local Dates
- 6.3 Date Adjusters
- 6.4 Local Time
- 6.5 Zoned Time
- 6.6 Formatting and Parsing
- 6.7 Interoperating with Legacy Code

Chapter 7: Internationalization

- 7.1 Locales
 - 7.1.1 Why Locales?
 - 7.1.2 Specifying Locales
 - 7.1.3 The Default Locale
 - 7.1.4 Display Names
- 7.2 Number Formats
 - 7.2.1 Formatting Numeric Values
 - 7.2.2 The DecimalFormat Class
 - 7.2.3 Currencies
- 7.3 Date and Time
- 7.4 Collation and Normalization
- 7.5 Message Formatting
 - 7.5.1 Formatting Numbers and Dates
 - 7.5.2 Choice Formats
- 7.6 Text Input and Output
 - 7.6.1 Text Files
 - 7.6.2 Line Endings
 - 7.6.3 The Console
 - 7.6.4 Log Files

- 7.6.5 The UTF-8 Byte Order Mark
- 7.6.6 Character Encoding of Source Files
- 7.7 Resource Bundles
 - 7.7.1 Locating Resource Bundles
 - 7.7.2 Property Files
 - 7.7.3 Bundle Classes
- 7.8 A Complete Example

Chapter 8: Scripting, Compiling, and Annotation Processing

- 8.1 Scripting for the Java Platform
 - 8.1.1 Getting a Scripting Engine
 - 8.1.2 Script Evaluation and Bindings
 - 8.1.3 Redirecting Input and Output
 - 8.1.4 Calling Scripting Functions and Methods
 - 8.1.5 Compiling a Script
 - 8.1.6 An Example: Scripting GUI Events
- 8.2 The Compiler API
 - 8.2.1 Invoking the Compiler
 - 8.2.2 Launching a Compilation Task
 - 8.2.3 Capturing Diagnostics
 - 8.2.4 Reading Source Files from Memory
 - 8.2.5 Writing Byte Codes to Memory
 - 8.2.6 An Example: Dynamic Java Code Generation
- 8.3 Using Annotations
 - 8.3.1 An Introduction into Annotations
 - 8.3.2 An Example: Annotating Event Handlers
- 8.4 Annotation Syntax
 - 8.4.1 Annotation Interfaces
 - 8.4.2 Annotations
 - 8.4.3 Annotating Declarations
 - 8.4.4 Annotating Type Uses

- 8.4.5 Annotating this
- 8.5 Standard Annotations
 - 8.5.1 Annotations for Compilation
 - 8.5.2 Meta-Annotations
- 8.6 Source-Level Annotation Processing
 - 8.6.1 Annotation Processors
 - 8.6.2 The Language Model API
 - 8.6.3 Using Annotations to Generate Source Code
- 8.7 Bytecode Engineering
 - 8.7.1 Modifying Class Files
 - 8.7.2 Modifying Bytecodes at Load Time

Chapter 9: The Java Platform Module System

- 9.1 The Module Concept
- 9.2 Naming Modules
- 9.3 The Modular “Hello, World!” Program
- 9.4 Requiring Modules
- 9.5 Exporting Packages
- 9.6 Modular JARs
- 9.7 Modules and Reflective Access
- 9.8 Automatic Modules
- 9.9 The Unnamed Module
- 9.10 Command-Line Flags for Migration
- 9.11 Transitive and Static Requirements
- 9.12 Qualified Exporting and Opening
- 9.13 Service Loading
- 9.14 Tools for Working with Modules

Chapter 10: Security

- 10.1 Class Loaders
 - 10.1.1 The Class-Loading Process

- 10.1.2 The Class Loader Hierarchy
- 10.1.3 Using Class Loaders as Namespaces
- 10.1.4 Writing Your Own Class Loader
- 10.1.5 Bytecode Verification
- 10.2 User Authentication
 - 10.2.1 The JAAS Framework
 - 10.2.2 JAAS Login Modules
- 10.3 Digital Signatures
 - 10.3.1 Message Digests
 - 10.3.2 Message Signing
 - 10.3.3 Verifying a Signature
 - 10.3.4 The Authentication Problem
 - 10.3.5 Certificate Signing
 - 10.3.6 Certificate Requests
 - 10.3.7 Code Signing
- 10.4 Encryption
 - 10.4.1 Symmetric Ciphers
 - 10.4.2 Key Generation
 - 10.4.3 Cipher Streams
 - 10.4.4 Public Key Ciphers

Chapter 11: Advanced Swing and Graphics

- 11.1 Tables
 - 11.1.1 A Simple Table
 - 11.1.2 Table Models
 - 11.1.3 Working with Rows and Columns
 - 11.1.3.1 Column Classes
 - 11.1.3.2 Accessing Table Columns
 - 11.1.3.3 Resizing Columns
 - 11.1.3.4 Resizing Rows
 - 11.1.3.5 Selecting Rows, Columns, and Cells

- 11.1.3.6 Sorting Rows
- 11.1.3.7 Filtering Rows
- 11.1.3.8 Hiding and Displaying Columns

- 11.1.4 Cell Rendering and Editing
 - 11.1.4.1 Rendering Cells
 - 11.1.4.2 Rendering the Header
 - 11.1.4.3 Editing Cells
 - 11.1.4.4 Custom Editors

11.2 Trees

- 11.2.1 Simple Trees
 - 11.2.1.1 Editing Trees and Tree Paths
- 11.2.2 Node Enumeration
- 11.2.3 Rendering Nodes
- 11.2.4 Listening to Tree Events
- 11.2.5 Custom Tree Models

11.3 Advanced AWT

- 11.3.1 The Rendering Pipeline
- 11.3.2 Shapes
 - 11.3.2.1 The Shape Class Hierarchy
 - 11.3.2.2 Using the Shape Classes
- 11.3.3 Areas
- 11.3.4 Strokes
- 11.3.5 Paint
- 11.3.6 Coordinate Transformations
- 11.3.7 Clipping
- 11.3.8 Transparency and Composition

11.4 Raster Images

- 11.4.1 Readers and Writers for Images
 - 11.4.1.1 Obtaining Readers and Writers for Image File Types

11.4.1.2 Reading and Writing Files with Multiple Images

11.4.2 Image Manipulation

11.4.2.1 Constructing Raster Images

11.4.2.2 Filtering Images

11.5 Printing

11.5.1 Graphics Printing

11.5.2 Multiple-Page Printing

11.5.3 Print Services

11.5.4 Stream Print Services

11.5.5 Printing Attributes

Chapter 12: Native Methods

12.1 Calling a C Function from a Java Program

12.2 Numeric Parameters and Return Values

12.3 String Parameters

12.4 Accessing Fields

12.4.1 Accessing Instance Fields

12.4.2 Accessing Static Fields

12.5 Encoding Signatures

12.6 Calling Java Methods

12.6.1 Instance Methods

12.6.2 Static Methods

12.6.3 Constructors

12.6.4 Alternative Method Invocations

12.7 Accessing Array Elements

12.8 Handling Errors

12.9 Using the Invocation API

12.10 A Complete Example: Accessing the Windows Registry

12.10.1 Overview of the Windows Registry

12.10.2 A Java Platform Interface for Accessing the Registry

12.10.3 Implementation of Registry Access Functions as Native Methods

12.11 Foreign Functions: A Glimpse into the Future

Index

Preface

To the Reader

The book you have in your hands is the second volume of the twelfth edition of *Core Java*, fully updated for Java 17. The first volume covers the essential features of the language; this volume deals with the advanced topics that a programmer needs to know for professional software development. Thus, as with the first volume and the previous editions of this book, we are still targeting programmers who want to put Java technology to work in real projects.

As is the case with any book, errors and inaccuracies are inevitable. Should you find any in this book, we would very much like to hear about them. Of course, we would prefer to hear about them only once. For this reason, we have put up a web site at <http://horstmann.com/corejava> with a FAQ, bug fixes, and workarounds. Strategically placed at the end of the bug report web page (to encourage you to read the previous reports) is a form that you can use to report bugs or problems and to send suggestions for improvements for future editions.

About This Book

The chapters in this book are, for the most part, independent of each other. You should be able to delve into whatever topic interests you the most and read the chapters in any order.

In **Chapter 1**, you will learn all about the Java stream library that brings a modern flavor to processing data, by specifying what you want without describing in detail how the result should be obtained. This allows the

stream library to focus on an optimal evaluation strategy, which is particularly advantageous for optimizing concurrent computations.

The topic of **Chapter 2** is input and output handling (I/O). In Java, all input and output is handled through input/output streams. These streams (not to be confused with those in **Chapter 1**) let you deal, in a uniform manner, with communications among various sources of data, such as files, network connections, or memory blocks. We include detailed coverage of the reader and writer classes that make it easy to deal with Unicode. We show you what goes on under the hood when you use the object serialization mechanism, which makes saving and loading objects easy and convenient. We then move on to regular expressions and working with files and paths. Throughout this chapter, you will find welcome enhancements in recent Java versions.

Chapter 3 covers XML. We show you how to parse XML files, how to generate XML, and how to use XSL transformations. As a useful example, we show you how to specify the layout of a Swing form in XML. We also discuss the XPath API, which makes finding needles in XML haystacks much easier.

Chapter 4 covers the networking API. Java makes it phenomenally easy to do complex network programming. We show you how to make network connections to servers, how to implement your own servers, and how to make HTTP connections. This chapter includes coverage of the new HTTP client.

Chapter 5 covers database programming. The focus is on JDBC, the Java database connectivity API that lets Java programs connect to relational databases. We show you how to write useful programs to handle realistic database chores, using a core subset of the JDBC API. (A complete treatment of the JDBC API would require a book almost as big as this one.)

Java had two prior attempts at libraries for handling date and time. The third one was the charm in Java 8. In **Chapter 6**, you will learn how to deal with the complexities of calendars and time zones, using the new date and time library.

Chapter 7 discusses a feature that we believe can only grow in importance: internationalization. The Java programming language is one of the few languages designed from the start to handle Unicode, but the internationalization support on the Java platform goes much further. As a result, you can internationalize Java applications so that they cross not only platforms but country boundaries as well. For example, we show you how to write a retirement calculator that uses either English, German, or Chinese languages.

Chapter 8 discusses three techniques for processing code. The scripting and compiler APIs allow your program to call code in scripting languages such as JavaScript or Groovy, and to compile Java code. Annotations allow you to add arbitrary information (sometimes called metadata) to a Java program. We show you how annotation processors can harvest these annotations at the source or class file level, and how annotations can be used to influence the behavior of classes at runtime. Annotations are only useful with tools, and we hope that our discussion will help you select useful annotation processing tools for your needs.

In **Chapter 9**, you will learn about the Java Platform Module System that was introduced in Java 9 to facilitate an orderly evolution of the Java platform and core libraries. This module system provides encapsulation for packages and a mechanism for describing module requirements. You will learn the properties of modules so that you can decide whether to use them in your own applications. Even if you decide not to, you need to know the new rules so that you can interact with the Java platform and other modularized libraries.

Chapter 10 takes up the Java security model, user authentication, and the cryptographic functions in the Java security library. You will learn about important features such as message and code signing, authorization and authentication, and encryption. We conclude with examples that use the AES and RSA encryption algorithms.

Chapter 11 contains all the Swing material that didn't make it into Volume I, especially the important but complex tree and table components. We also cover the Java 2D API, which you can use to create realistic drawings and special effects. Of course, not many programmers need to program Swing

user interfaces these days, so we pay particular attention to features that are useful for images that can be generated on a server.

Chapter 12 takes up native methods, which let you call methods written for a specific machine such as the Microsoft Windows API. Obviously, this feature is controversial: Use native methods, and the cross-platform nature of Java vanishes. Nonetheless, every serious programmer writing Java applications for specific platforms needs to know these techniques. At times, you need to turn to the operating system’s API for your target platform when you interact with a device or service that is not supported by Java. We illustrate this by showing you how to access the registry API in Windows from a Java program.

As always, all chapters have been completely revised for the latest version of Java. Outdated material has been removed, and the new APIs up to Java 17 are covered in detail.

Conventions

As is common in many computer books, we use monospace type to represent computer code.



Note

Notes are tagged with “note” icons that look like this.



Tip

Tips are tagged with “tip” icons that look like this.



Caution

When there is danger ahead, we warn you with a "caution" icon.



C++ Note

There are a number of C++ notes that explain the difference between the Java programming language and C++. You can skip them if you aren't interested in C++.

Java comes with a large programming library, or Application Programming Interface (API). When using an API call for the first time, we add a short summary description at the end of the section. These descriptions are a bit more informal but, we hope, also a little more informative than those in the official online API documentation. The names of interfaces are in italics, just like in the official documentation. The number after a class, interface, or method name is the JDK version in which the feature was introduced.

Application Programming Interface 1.2

Programs whose source code is included in the companion code for this book are listed as examples, for instance

Listing 1.1 ScriptTest.java

You can download the companion code from
<http://horstmann.com/corejava>.

Register your copy of *Core Java, Volume II: Advanced Features, Twelfth Edition*, on the InformIT site for convenient access to updates and/or corrections as they become available. To start the registration process, go to informit.com/register and log in or create an account. Enter the product ISBN (9780137871070) and click Submit. Look on the Registered Products tab for an Access Bonus Content

link next to this product, and follow that link to access any available bonus materials. If you would like to be notified of exclusive offers on new editions and updates, please check the box to receive email from us.

Acknowledgments

Writing a book is always a monumental effort, and rewriting doesn't seem to be much easier, especially with such a rapid rate of change in Java technology. Making a book a reality takes many dedicated people, and it is my great pleasure to acknowledge the contributions of the entire *Core Java* team.

A large number of individuals at Pearson provided valuable assistance, but they managed to stay behind the scenes. I'd like them all to know how much I appreciate their efforts. As always, my warm thanks go to my editor, Greg Doench, for steering the book through the writing and production process, and for allowing me to be blissfully unaware of the existence of all those folks behind the scenes. I am very grateful to Julie Nahil for production support, and to Dmitry Kirsanov and Alina Kirsanova for copyediting and typesetting the manuscript.

Thanks to the many readers of earlier editions who reported embarrassing errors and made lots of thoughtful suggestions for improvement. I am particularly grateful to the excellent reviewing team that went over the manuscript with an amazing eye for detail and saved me from many more embarrassing errors.

Reviewers of this and earlier editions include Chuck Allison (Utah Valley University), Lance Andersen (Oracle), Gail Anderson (Anderson Software Group), Paul Anderson (Anderson Software Group), Alec Beaton (IBM), Cliff Berg, Andrew Binstock (Oracle), Joshua Bloch, David Brown, Corky Cartwright, Frank Cohen (PushToTest), Chris Crane (devXsolution), Dr. Nicholas J. De Lillo (Manhattan College), Rakesh Dhoopar (Oracle), Robert Evans (Senior Staff, The Johns Hopkins University Applied Physics Lab), David Geary (Clarity Training), Jim Gish (Oracle), Brian Goetz

(Oracle), Angela Gordon, Dan Gordon (Electric Cloud), Rob Gordon, John Gray (University of Hartford), Cameron Gregory (olabs.com), Steve Haines, Marty Hall (coreservlets.com, Inc.), Vincent Hardy (Adobe Systems), Dan Harkey (San Jose State University), William Higgins (IBM), Marc Hoffmann (mtrail), Vladimir Ivanovic (PointBase), Jerry Jackson (CA Technologies), Heinz Kabutz (Java Specialists), Stepan V. Kalinin (I-Teco/Servionica LTD), Tim Kimmet (Walmart), Chris Laffra, Charlie Lai (Apple), Angelika Langer, Jeff Langr (Langr Software Solutions), Doug Langston, Hang Lau (McGill University), Mark Lawrence, Doug Lea (SUNY Oswego), Gregory Longshore, Bob Lynch (Lynch Associates), Philip Milne (consultant), Mark Morrissey (The Oregon Graduate Institute), Mahesh Neelakanta (Florida Atlantic University), José Paumard (Oracle), Hao Pham, Paul Phlion, Blake Ragsdell, Ylber Ramadani (Ryerson University), Stuart Reges (University of Arizona), Simon Ritter (Azul Systems), Rich Rosen (Interactive Data Corporation), Peter Sanders (ESSI University, Nice, France), Dr. Paul Sanghera (San Jose State University and Brooks College), Paul Sevinc (Teamup AG), Devang Shah (Sun Microsystems), Yoshiki Shibata, Richard Slywczak (NASA/Glenn Research Center), Bradley A. Smith, Steven Stelting (Oracle), Christopher Taylor, Luke Taylor (Valtech), George Thiruvathukal, Kim Topley (StreamingEdge), Janet Traub, Paul Tyma (consultant), Christian Ullenboom, Peter van der Linden, Burt Walsh, Joe Wang (Oracle), Dan Xu (Oracle), and John Zavgren (Oracle).

*Cay Horstmann
Berlin, Germany
January 2022*

Chapter 1. Streams

In this chapter

- 1.1 From Iterating to Stream Operations
- 1.2 Stream Creation
- 1.3 The `filter`, `map`, and `flatMap` Methods
- 1.4 Extracting Substreams and Combining Streams
- 1.5 Other Stream Transformations
- 1.6 Simple Reductions
- 1.7 The Optional Type
- 1.8 Collecting Results
- 1.9 Collecting into Maps
- 1.10 Grouping and Partitioning
- 1.11 Downstream Collectors
- 1.12 Reduction Operations
- 1.13 Primitive Type Streams
- 1.14 Parallel Streams

Compared to collections, streams provide a view of data that lets you specify computations at a higher conceptual level. With a stream, you specify what you want to have done, not how to do it. You leave the scheduling of operations to the implementation. For example, suppose you

want to compute the average of a certain property. You specify the source of data and the property, and the stream library can then optimize the computation, for example by using multiple threads for computing sums and counts and combining the results.

In this chapter, you will learn how to use the Java stream library, which was introduced in Java 8, to process collections in a “what, not how” style.

1.1 From Iterating to Stream Operations

When you process a collection, you usually iterate over its elements and do some work with each of them. For example, suppose we want to count all long words in a book. First, let’s put them into a list:

[Click here to view code image](#)

```
var contents = Files.readString(Path.of("alice.txt")); // Read
file into string
List<String> words = List.of(contents.split("\\PL+"));
// Split into words; nonletters are delimiters
```

Now we are ready to iterate:

[Click here to view code image](#)

```
int count = 0;
for (String w : words)
{
    if (w.length() > 12) count++;
}
```

With streams, the same operation looks like this:

[Click here to view code image](#)

```
long count = words.stream()
    .filter(w -> w.length() > 12)
    .count();
```

Now you don't have to scan the loop for evidence of filtering and counting. The method names tell you right away what the code intends to do. Moreover, where the loop prescribes the order of operations in complete detail, a stream is able to schedule the operations any way it wants, as long as the result is correct.

Simply changing `stream` to `parallelStream` allows the stream library to do the filtering and counting in parallel.

[Click here to view code image](#)

```
long count = words.parallelStream()
    .filter(w -> w.length() > 12)
    .count();
```

Streams follow the “what, not how” principle. In our stream example, we describe what needs to be done: get the long words and count them. We don't specify in which order, or in which thread, this should happen. In contrast, the loop at the beginning of this section specifies exactly how the computation should work, and thereby forgoes any chances of optimization.

A stream seems superficially similar to a collection, allowing you to transform and retrieve data. But there are significant differences:

1. A stream does not store its elements. They may be stored in an underlying collection or generated on demand.
2. Stream operations don't mutate their source. For example, the `filter` method does not remove elements from a stream but yields a new stream in which they are not present.
3. Stream operations are *lazy* when possible. This means they are not executed until their result is needed. For example, if you only ask for the first five long words instead of all, the `filter` method will stop filtering after the fifth match. As a consequence, you can even have infinite streams!

Let us have another look at the example. The `stream` and `parallelStream` methods yield a *stream* for the `words` list. The

`filter` method returns another stream that contains only the words of length greater than 12. The `count` method reduces that stream to a result.

This workflow is typical when you work with streams. You set up a pipeline of operations in three stages:

1. Create a stream.
2. Specify *intermediate operations* for transforming the initial stream into others, possibly in multiple steps.
3. Apply a *terminal operation* to produce a result. This operation forces the execution of the lazy operations that precede it. Afterwards, the stream can no longer be used.

In the example in [Listing 1.1](#), the stream is created with the `stream` or `parallelStream` methods. The `filter` method transforms it, and `count` is the terminal operation.

In the next section, you will see how to create a stream. The subsequent three sections deal with stream transformations. They are followed by five sections on terminal operations.

Listing 1.1 streams/CountLongWords.java

[Click here to view code image](#)

```
1 package streams;
2
3 import java.io.*;
4 import java.nio.file.*;
5 import java.util.*;
6
7 /**
8 * @version 1.02 2019-08-28
9 * @author Cay Horstmann
10 */
11 public class CountLongWords
12 {
13     public static void main(String[] args) throws IOException
```

```

14      {
15          var contents = Files.readString(
16              Path.of("../gutenberg/alice30.txt"));
17          List<String> words = List.of(contents.split("\\PL+"));
18
19          long count = 0;
20          for (String w : words)
21          {
22              if (w.length() > 12) count++;
23          }
24          System.out.println(count);
25
26          count = words.stream().filter(w -> w.length() >
27              12).count();
27          System.out.println(count);
28
29          count = words.parallelStream().filter(w -> w.length() >
30              12).count();
30          System.out.println(count);
31      }
32  }

```

java.util.stream.Stream<T> 8

- Stream<T> filter(Predicate<? super T> p)
yields a stream containing all elements of this stream fulfilling p.
- long count()
yields the number of elements of this stream. This is a terminal operation.

java.util.Collection<E> 1.2

- default Stream<E> stream()
- default Stream<E> parallelStream()

yield a sequential or parallel stream of the elements in this collection.

1.2 Stream Creation

You have already seen that you can turn any collection into a stream with the `stream` method of the `Collection` interface. If you have an array, use the static `Stream.of` method instead.

[Click here to view code image](#)

```
Stream<String> words = Stream.of(contents.split("\\PL+"));
// split returns a String[] array
```

The `of` method has a varargs parameter, so you can construct a stream from any number of arguments:

[Click here to view code image](#)

```
Stream<String> song = Stream.of("gently", "down", "the",
"stream");
```

Use `Arrays.stream(array, from, to)` to make a stream from a part of an array.

To make a stream with no elements, use the static `Stream.empty` method:

[Click here to view code image](#)

```
Stream<String> silence = Stream.empty();
// Generic type <String> is inferred; same as Stream.
<String>empty()
```

The Stream interface has two static methods for making infinite streams. The generate method takes a function with no arguments (or, technically, an object of the Supplier<T> interface). Whenever a stream value is needed, that function is called to produce a value. You can get a stream of constant values as

[Click here to view code image](#)

```
Stream<String> echos = Stream.generate(() -> "Echo");
```

or a stream of random numbers as

[Click here to view code image](#)

```
Stream<Double> randoms = Stream.generate(Math::random);
```

To produce sequences such as 0 1 2 3 . . . , use the iterate method instead. It takes a “seed” value and a function (technically, a UnaryOperator<T>) and repeatedly applies the function to the previous result. For example,

[Click here to view code image](#)

```
Stream<BigInteger> integers
    = Stream.iterate(BigInteger.ZERO, n ->
        n.add(BigInteger.ONE));
```

The first element in the sequence is the seed BigInteger.ZERO. The second element is f(seed) which yields 1 (as a big integer). The next element is f(f(seed)) which yields 2, and so on.

To produce a finite stream instead, add a predicate that specifies when the iteration should finish:

[Click here to view code image](#)

```
var limit = new BigInteger("10000000");
Stream<BigInteger> integers
    = Stream.iterate(BigInteger.ZERO,
```

```
n -> n.compareTo(limit) < 0,  
n -> n.add(BigInteger.ONE));
```

As soon as the predicate rejects an iteratively generated value, the stream ends.

Finally, the `Stream.ofNullable` method makes a really short stream from an object. The stream has length 0 if the object is `null` or length 1 otherwise, containing just the object. This is mostly useful in conjunction with `flatMap`—see [Section 1.7.7, “Turning an Optional into a Stream,”](#) on p. 23 for an example.



Note

A number of methods in the Java API yield streams. For example, the `String` class has a `lines` method that yields a stream of the lines contained in the string:

[Click here to view code image](#)

```
Stream<String> greetings = "Hello\nGuten Tag\nBonjour".lines()
```

The `Pattern` class has a method `splitAsStream` that splits a `CharSequence` by a regular expression. You can use the following statement to split a string into words:

[Click here to view code image](#)

```
Stream<String> words =  
Pattern.compile("\\PL+").splitAsStream(contents);
```

The `Scanner.tokens` method yields a stream of tokens of a scanner. Another way to get a stream of words from a string is

[Click here to view code image](#)

```
Stream<String> words = new Scanner(contents).tokens();
```

The static `Files.lines` method returns a `Stream` of all lines in a file:

[Click here to view code image](#)

```
try (Stream<String> lines = Files.lines(path))  
{  
    Process lines  
}
```

To view the contents of one of the streams introduced in this section, use the `toList` method, which collects the stream's elements in a list. Like `count`, `toList` is a terminal operation. If the stream is infinite, first truncate it with the `limit` method:

[Click here to view code image](#)

```
System.out.println(Stream.generate(Math::random).limit(10).toList());
```



Note

If you have an `Iterable` that is not a collection, you can turn it into a stream by calling

[Click here to view code image](#)

```
StreamSupport.stream(iterablespliterator(), false);
```

If you have an `Iterator` and want a stream of its results, use

[Click here to view code image](#)

```
StreamSupport.stream(Spliterators.spliteratorUnknownSize(  
    iterator, Spliterator.ORDERED), false);
```



Caution

It is very important that you don't modify the collection backing a stream while carrying out a stream operation. Remember that streams

don't collect their data—the data is always in a separate collection. If you modify that collection, the outcome of the stream operations becomes undefined. The JDK documentation refers to this requirement as *noninterference*.

To be exact, since intermediate stream operations are lazy, it is possible to mutate the collection up to the point where the terminal operation executes. For example, the following, while certainly not recommended, will work:

[Click here to view code image](#)

```
List<String> wordList = . . .;
Stream<String> words = wordList.stream();
wordList.add("END");
long n = words.distinct().count();
```

But this code is wrong:

[Click here to view code image](#)

```
Stream<String> words = wordList.stream();
words.forEach(s -> {if (s.length() < 12) wordList.remove(s);});
// ERROR--interference
```

The example program in [Listing 1.2](#) shows the various ways of creating a stream.

Listing 1.2 streams/CreatingStreams.java

[Click here to view code image](#)

```
1 package streams;
2
3 import java.io.*;
4 import java.math.*;
5 import java.nio.file.*;
6 import java.util.*;
7 import java.util.regex.Pattern;
8 import java.util.stream.*;
```

```
9
10  /**
11   * @version 1.03  2021-09-06
12   * @author Cay Horstmann
13   */
14  public class CreatingStreams
15  {
16      public static <T> void show(String title, Stream<T>
17      stream)
18      {
19          final int SIZE = 10;
20          List<T> firstElements = stream
21              .limit(SIZE + 1)
22              .toList();
23          System.out.print(title + ": ");
24          for (int i = 0; i < firstElements.size(); i++)
25          {
26              if (i > 0) System.out.print(", ");
27              if (i < SIZE)
28                  System.out.print(firstElements.get(i));
29              else System.out.print("...");
30          }
31          System.out.println();
32      }
33
34      public static void main(String[] args) throws IOException
35      {
36          Path path = Path.of("../gutenberg/alice30.txt");
37          var contents = Files.readString(path);
38
39          Stream<String> words =
40          Stream.of(contents.split("\\PL+"));
41          show("words", words);
42          Stream<String> song = Stream.of("gently", "down",
43          "the", "stream");
44          show("song", song);
45          Stream<String> silence = Stream.empty();
46          show("silence", silence);
47      }
48  }
```

```
43
44     Stream<String> echos = Stream.generate(() -> "Echo");
45     show("echos", echos);
46
47     Stream<Double> randoms =
48         Stream.generate(Math::random);
49
50     Stream<BigInteger> integers =
51         Stream.iterate(BigInteger.ONE,
52             n -> n.add(BigInteger.ONE));
53     show("integers", integers);
54
55     Stream<String> greetings = "Hello\nGuten
Tag\nBonjour".lines();
56     show("greetings", greetings);
57
58     Stream<String> wordsAnotherWay =
59         Pattern.compile("\PL+").splitAsStream(contents);
60     show("wordsAnotherWay", wordsAnotherWay);
61
62     try (Stream<String> lines = Files.lines(path))
63     {
64         show("lines", lines);
65     }
66
67     Iterable<Path> iterable =
68         FileSystems.getDefault().getRootDirectories();
69     Stream<Path> rootDirectories =
70         StreamSupport.stream(iterablespliterator(), false);
71     show("rootDirectories", rootDirectories);
72
73     Iterator<Path> iterator =
74         Path.of("/usr/share/dict/words").iterator();
75     Stream<Path> pathComponents =
76         StreamSupport.stream(Spliterators.spliteratorUnknownSize(
77             iterator, Spliterator.ORDERED), false);
78     show("pathComponents", pathComponents);
```

```
73      }
74 }
```

java.util.stream.Stream 8

- static <T> Stream<T> of(T... values)
yields a stream whose elements are the given values.
 - static <T> Stream<T> empty()
yields a stream with no elements.
 - static <T> Stream<T> generate(Supplier<T> s)
yields an infinite stream whose elements are constructed by repeatedly invoking the function s.
 - static <T> Stream<T> iterate(T seed,
UnaryOperator<T> f)
 - static <T> Stream<T> iterate(T seed,
Predicate<? super T> hasNext,
UnaryOperator<T> f)
- yield a stream whose elements are seed, f invoked on seed, f invoked on the preceding element, and so on. The first method yields an infinite stream. The stream of the second method comes to an end before the first element that doesn't fulfill the hasNext predicate.
- static <T> Stream<T> ofNullable(T t) 9
returns an empty stream if t is null or a stream containing t otherwise.

java.util.Spliterators 8

- static <T> Spliterator<T>
spliteratorUnknownSize(Iterator<? extends T>
iterator, int characteristics)

turns an iterator into a splittable iterator of unknown size with the given characteristics (a bit pattern containing constants such as Spliterator.ORDERED).

java.util.Arrays 1.2

- static <T> Stream<T> stream(T[] array, int startInclusive, int endExclusive) 8

yields a stream whose elements are the specified range of the array.

java.lang.String

- static Stream<String> lines() 11

yields a stream whose elements are the lines of this string.

java.util.regex.Pattern 1.4

- Stream<String> splitAsStream(CharSequence input) 8

yields a stream whose elements are the parts of the input that are delimited by this pattern.

java.nio.file.Files 7

- static Stream<String> lines(Path path) 8
- static Stream<String> lines(Path path, Charset cs) 8

yield a stream whose elements are the lines of the specified file, with the UTF-8 charset or the given charset.

java.util.stream.StreamSupport 8

- static <T> Stream<T> stream(Spliterator<T> spliterator, boolean parallel)

yields a stream containing the values produced by the given splittable iterator.

java.lang.Iterable 5

- Spliterator<T> spliterator() 8

yields a splittable iterator for this Iterable. The default implementation does not split and does not report a size.

java.util.Scanner 5

- `public Stream<String> tokens() 9`
yields a stream of strings returned by calling the `next` method of this scanner.

java.util.function.Supplier<T> 8

- `T get()`
supplies a value.

1.3 The `filter`, `map`, and `flatMap` Methods

A stream transformation produces a stream whose elements are derived from those of another stream. You have already seen the `filter` transformation that yields a new stream with those elements that match a certain condition. Here, we transform a stream of strings into another stream containing only long words:

[Click here to view code image](#)

```
List<String> words = . . .;
Stream<String> longWords = words.stream().filter(w ->
    w.length() > 12);
```

The argument of `filter` is a `Predicate<T>`—that is, a function from `T` to `boolean`.

Often, you want to transform the values in a stream in some way. Use the `map` method and pass the function that carries out the transformation. For example, you can transform all words to lowercase like this:

[Click here to view code image](#)

```
Stream<String> lowercaseWords =  
words.stream().map(String::toLowerCase);
```

Here, we used map with a method reference. Often, you will use a lambda expression instead:

[Click here to view code image](#)

```
Stream<String> firstLetters = words.stream().map(s ->  
s.substring(0, 1));
```

The resulting stream contains the first letter of each word.

When you use map, a function is applied to each element, and the result is a new stream with the results. Occasionally, you are faced with a mapping function that generates an optional result, or more than one result. As an example, consider a method `codePoints` that yields all code points of a string. For example, `codePoints("Hello 🌎")` would consist of "H", "e", "l", "l", "o", " ", "🌐". Note that the globe symbol (U+1F310) consists of two char values, so the `codePoints` method has to do some heavy lifting to make this happen. We will look at a couple of implementations momentarily.

How should `codePoints` collect its multiple results? For the stream API, it is most natural if the method returns a `Stream<String>`.

Now let's map such a `codePoints` method on a stream of strings:

[Click here to view code image](#)

```
Stream<Stream<String>> result = words.stream().map(w ->  
codePoints(w));
```

You will get a stream of streams, like [. . . ["y", "o", "u", "r"], ["b", "o", "a", "t"], . . .]. To flatten it out to a single stream [. . . "y", "o", "u", "r", "b", "o", "a", "t", . . .], use the `flatMap` method instead of `map`:

[Click here to view code image](#)

```
Stream<String> flatResult = words.stream().flatMap(w ->
    codePoints(w));
    // Calls codePoints on each word and flattens the results
```

Now that you have seen how to use the `codePoints` method, how do you write it? The `String` class has a `codePoints` method that yields a stream of *integer* code points:

[Click here to view code image](#)

```
"Hello 🌎".codePoints() // A stream of integers 72, 101, 108,
108, 111, 32, 127760
```

Next, we need to transform each of the integers to a string containing the Unicode character with the given code point. Unfortunately, there is a technical difficulty. The `codePoints` method produces an `IntStream`, which is a little different from a `Stream<Integer>`, as you will see in [Section 1.13, “Primitive Type Streams,”](#) on p. 43. Instead of `map`, you use the `mapToObj` method to transform the elements. Perhaps surprisingly, there is no convenient method for turning an integer codepoint into a string. Here is the best I could come up with:

[Click here to view code image](#)

```
public static Stream<String> codePoints(String s)
{
    return s.codePoints().mapToObj(cp -> new String(new int [] {
        cp }, 0, 1));
}
```

When using `flatMap`, you provide a method that produces a new stream for every stream element. As you have seen, that can be tedious. It can also be a little inefficient. The `mapMulti` method offers an alternative. Instead of producing a stream of results, you generate the results and pass them to a collector—an object of a class implementing the functional interface `Consumer`. For each result, invoke the collector’s `accept` method.

Let's do this with an example. The following loop produces the code points of a string s:

[Click here to view code image](#)

```
int i = 0;
while (i < s.length())
{
    int cp = sentence.codePointAt(i);
    // Do something with cp
    if (Character.isSupplementaryCodePoint(cp)) i += 2;
    else i++;
}
```

When calling `mapMulti`, you provide a function that is invoked with the stream element and the collector. In your function, pass your results to the collector.

[Click here to view code image](#)

```
Stream<String> result = words.stream().mapMulti((s, collector)
->
{
    int i = 0;
    while (i < s.length())
    {
        int cp = sentence.codePointAt(i);
        collector.accept(cp);
        if (Character.isSupplementaryCodePoint(cp)) i += 2;
        else i++;
    }
});
```

java.util.stream.Stream

- `Stream<T> filter(Predicate<? super T> predicate)`

yields a stream containing the elements of this stream that fulfill the predicate.

- <R> Stream<R> map(Function<? super T, ? extends R> mapper)

yields a stream containing the results of applying mapper to the elements of this stream.

- <R> Stream<R> flatMap(Function<? super T, ? extends Stream<? extends R>> mapper)

yields a stream obtained by concatenating the results of applying mapper to the elements of this stream. (Note that each mapper result is a stream.)

- <R> Stream<R> mapMulti(BiConsumer<? super T, ? super Consumer<R>> mapper) 16

For each stream element, the mapper is invoked, and all elements passed to the Consumer during invocation are added to the result stream.

1.4 Extracting Substreams and Combining Streams

The call `stream.limit(n)` returns a new stream that ends after n elements (or when the original stream ends if it is shorter). This method is particularly useful for cutting infinite streams down to size. For example,

[Click here to view code image](#)

```
Stream<Double> randoms =  
    Stream.generate(Math::random).limit(100);
```

yields a stream with 100 random numbers.

The call `stream.skip(n)` does the exact opposite. It discards the first `n` elements. This is handy in our book reading example where, due to the way the `split` method works, the first element is an unwanted empty string. We can make it go away by calling `skip`:

[Click here to view code image](#)

```
Stream<String> words =  
Stream.of(contents.split("\\PL+")).skip(1);
```

The `stream.takeWhile(predicate)` call takes all elements from the stream while the predicate is `true`, and then stops.

For example, suppose we use the `codePoints` method of the preceding section to split a string into characters, and we want to collect all initial digits. The `takeWhile` method can do this:

[Click here to view code image](#)

```
Stream<String> initialDigits = codePoints(str).takeWhile(  
s -> "0123456789".contains(s));
```

The `dropWhile` method does the opposite, dropping elements while a condition is `true` and yielding a stream of all elements starting with the first one for which the condition was `false`. For example,

[Click here to view code image](#)

```
Stream<String> withoutInitialWhiteSpace =  
codePoints(str).dropWhile(  
s -> s.strip().length() == 0);
```

You can concatenate two streams with the static `concat` method of the `Stream` class:

[Click here to view code image](#)

```
Stream<String> combined = Stream.concat(  
codePoints("Hello"), codePoints("World"));
```

```
// Yields the stream ["H", "e", "l", "l", "o", "W", "o",
"r", "l", "d"]
```

Of course, the first stream should not be infinite—otherwise the second one wouldn't ever get a chance.

`java.util.stream.Stream` 8

- `Stream<T> limit(long maxSize)`
yields a stream with up to `maxSize` of the initial elements from this stream.
- `Stream<T> skip(long n)`
yields a stream whose elements are all but the initial `n` elements of this stream.
- `Stream<T> takeWhile(Predicate<? super T> predicate)`⁹
yields a stream whose elements are the initial elements of this stream that fulfill the predicate.
- `Stream<T> dropWhile(Predicate<? super T> predicate)`⁹
yields a stream whose elements are the elements of this stream except for the initial ones that do not fulfill the predicate.
- `static <T> Stream<T> concat(Stream<? extends T> a, Stream<? extends T> b)`
yields a stream whose elements are the elements of `a` followed by the elements of `b`.

1.5 Other Stream Transformations

The `distinct` method returns a stream that yields elements from the original stream, in the same order, except that duplicates are suppressed. The duplicates need not be adjacent.

[Click here to view code image](#)

```
Stream<String> uniqueWords
    = Stream.of("merrily", "merrily", "merrily",
"gently").distinct();
    // Only one "merrily" is retained
```

For sorting a stream, there are several variations of the `sorted` method. One works for streams of `Comparable` elements, and another accepts a `Comparator`. Here, we sort strings so that the longest ones come first:

[Click here to view code image](#)

```
Stream<String> longestFirst
    =
words.stream().sorted(Comparator.comparing(String::length).reversed());
```

As with all stream transformations, the `sorted` method yields a new stream whose elements are the elements of the original stream in sorted order.

Of course, you can sort a collection without using streams. The `sorted` method is useful when the sorting process is part of a stream pipeline.

Finally, the `peek` method yields another stream with the same elements as the original, but a function is invoked every time an element is retrieved. That is handy for debugging:

[Click here to view code image](#)

```
Object[] powers = Stream.iterate(1.0, p -> p * 2)
    .peek(e -> System.out.println("Fetching " + e))
```

```
.limit(20).toArray();
```

When an element is actually accessed, a message is printed. This way you can verify that the infinite stream returned by `iterate` is processed lazily.



Tip

When you use a debugger to debug a stream computation, you can set a breakpoint in a method that is called from one of the transformations. With most IDEs, you can also set breakpoints in lambda expressions. If you just want to know what happens at a particular point in the stream pipeline, add

[Click here to view code image](#)

```
.peek(x ->
{
    return;
})
```

and set a breakpoint on the second line.

java.util.stream.Stream 8

- `Stream<T> distinct()`
yields a stream of the distinct elements of this stream.
- `Stream<T> sorted()`
- `Stream<T> sorted(Comparator<? super T> comparator)`

yield a stream whose elements are the elements of this stream in sorted order. The first method requires that the elements are instances of a class implementing `Comparable`.

- Stream<T> peek(Consumer<? super T> action)
yields a stream with the same elements as this stream, passing each element to action as it is consumed.

1.6 Simple Reductions

Now that you have seen how to create and transform streams, we will finally get to the most important point—getting answers from the stream data. The methods covered in this section are called *reductions*. Reductions are *terminal operations*. They reduce the stream to a nonstream value that can be used in your program.

You have already seen a simple reduction: the `count` method that returns the number of elements of a stream.

Other simple reductions are `max` and `min` that return the largest or smallest value. There is a twist—these methods return an `Optional<T>` value that either wraps the answer or indicates that there is none (because the stream happened to be empty). In the olden days, it was common to return `null` in such a situation. But that can lead to null pointer exceptions when it happens in an incompletely tested program. The `Optional` type is a better way of indicating a missing return value. We discuss the `Optional` type in detail in the next section. Here is how you can get the maximum of a stream:

[Click here to view code image](#)

```
Optional<String> largest =
words.max(String::compareToIgnoreCase);
System.out.println("largest: " + largest.orElse(""));
```

The `findFirst` returns the first value in a nonempty collection. It is often useful when combined with `filter`. For example, here we find the first word that starts with the letter Q, if it exists:

[Click here to view code image](#)

```
Optional<String> startsWithQ  
= words.filter(s -> s.startsWith("Q")).findFirst();
```

If you are OK with any match, not just the first one, use the `findAny` method. This is effective when you parallelize the stream, since the stream can report any match that it finds instead of being constrained to the first one.

[Click here to view code image](#)

```
Optional<String> startsWithQ  
= words.parallel().filter(s -> s.startsWith("Q")).findAny();
```

If you just want to know if there is a match, use `anyMatch`. That method takes a predicate argument, so you won't need to use `filter`.

[Click here to view code image](#)

```
boolean aWordStartsWithQ  
= words.parallel().anyMatch(s -> s.startsWith("Q"));
```

There are methods `allMatch` and `noneMatch` that return `true` if all or no elements match a predicate. These methods also benefit from being run in parallel.

java.util.stream.Stream

- `Optional<T> max(Comparator<? super T> comparator)`
- `Optional<T> min(Comparator<? super T> comparator)`

yield a maximum or minimum element of this stream, using the ordering defined by the given comparator, or an empty `Optional` if this stream is empty. These are terminal operations.

- `Optional<T> findFirst()`
- `Optional<T> findAny()`

yield the first, or any, element of this stream, or an empty `Optional` if this stream is empty. These are terminal operations.

- `boolean anyMatch(Predicate<? super T> predicate)`
- `boolean allMatch(Predicate<? super T> predicate)`
- `boolean noneMatch(Predicate<? super T> predicate)`

return `true` if any, all, or none of the elements of this stream match the given predicate. These are terminal operations.

1.7 The Optional Type

An `Optional<T>` object is a wrapper for either an object of type `T` or no object. In the former case, we say that the value is *present*. The `Optional<T>` type is intended as a safer alternative for a reference of type `T` that either refers to an object or is `null`. But it is only safer if you use it right. The next three sections shows you how.

1.7.1 Getting an Optional Value

The key to using `Optional` effectively is to use a method that either *produces an alternative* if the value is not present, or *consumes the value* only if it is present.

In this section, we look at the first strategy. Often, there is a default that you want to use when there was no match, perhaps the empty string:

[Click here to view code image](#)

```
String result = optionalString.orElse("");
// The wrapped string, or "" if none
```

You can also invoke code to compute the default:

[Click here to view code image](#)

```
String result = optionalString.orElseGet(() ->
System.getProperty("myapp.default"));
// The function is only called when needed
```

Or you can throw an exception if there is no value:

[Click here to view code image](#)

```
String result =
optionalString.orElseThrow(IllegalStateException::new);
// Supply a method that yields an exception object
```

java.util.Optional 8

- `T orElse(T other)`
yields the value of this Optional, or `other` if this Optional is empty.
- `T orElseGet(Supplier<? extends T> other)`
yields the value of this Optional, or the result of invoking `other` if this Optional is empty.
- `<X extends Throwable> T
orElseThrow(Supplier<? extends X>
exceptionSupplier)`
yields the value of this Optional, or throws the result of invoking `exceptionSupplier` if this Optional is empty.

1.7.2 Consuming an Optional Value

In the preceding section, you saw how to produce an alternative if no value is present. The other strategy for working with optional values is to consume the value only if it is present.

The `ifPresent` method accepts a function. If the optional value exists, it is passed to that function. Otherwise, nothing happens.

[Click here to view code image](#)

```
optionalValue.ifPresent(v -> Process v);
```

For example, if you want to add the value to a set if it is present, call

[Click here to view code image](#)

```
optionalValue.ifPresent(v -> results.add(v));
```

or simply

[Click here to view code image](#)

```
optionalValue.ifPresent(results::add);
```

If you want to take one action if the `Optional` has a value and another action if it doesn't, use `ifPresentOrElse`:

[Click here to view code image](#)

```
optionalValue.ifPresentOrElse(
    v -> System.out.println("Found " + v),
    () -> logger.warning("No match"));
```

java.util.Optional 8

- `void ifPresent(Consumer<? super T> action)`

If this `Optional` is nonempty, passes its value to `action`.

- `void ifPresentOrElse(Consumer<? super T> action, Runnable emptyAction) 9`

If this `Optional` is nonempty, passes its value to `action`, else invokes `emptyAction`.

1.7.3 Pipelining Optional Values

In the preceding sections, you saw how to get a value out of an `Optional` object. Another useful strategy is to keep the `Optional` intact. You can transform the value inside an `Optional` by using the `map` method:

[Click here to view code image](#)

```
Optional<String> transformed =  
    optionalString.map(String::toUpperCase);
```

If `optionalString` is empty, then `transformed` is also empty.

Here is another example. We add a result to a list if it is present:

[Click here to view code image](#)

```
optionalValue.map(results::add);
```

If `optionalValue` is empty, nothing happens.



Note

This `map` method is the analog of the `map` method of the `Stream` interface that you have seen in [Section 1.3, “The filter, map, and flatMap Methods,”](#) on p. 11. Simply imagine an optional value as a stream of size zero or one. The result again has size zero or one, and in the latter case, the function has been applied.

Similarly, you can use the `filter` method to only consider `Optional` values that fulfill a certain property before or after transforming it. If the property is not fulfilled, the pipeline yields an empty result:

[Click here to view code image](#)

```
Optional<String> transformed = optionalString
    .filter(s -> s.length() >= 8)
    .map(String::toUpperCase);
```

You can substitute an alternative `Optional` for an empty `Optional` with the `or` method. The alternative is computed lazily.

[Click here to view code image](#)

```
Optional<String> result = optionalString.or(() -> // Supply an
Optional
alternatives.stream().findFirst());
```

If `optionalString` has a value, then `result` is `optionalString`. If not, the lambda expression is evaluated, and its result is used.

`java.util.Optional` 8

- `<U> Optional<U> map(Function<? super T, ? extends U> mapper)`

yields an `Optional` whose value is obtained by applying the given function to the value of this `Optional` if present, or an empty `Optional` otherwise.

- `Optional<T> filter(Predicate<? super T> predicate)`

yields an `Optional` with the value of this `Optional` if it fulfills the given predicate, or an empty `Optional` otherwise.

- `Optional<T> or(Supplier<? extends Optional<? extends T>> supplier)` ⁹

yields this `Optional` if it is nonempty, or the one produced by the supplier otherwise.

1.7.4 How Not to Work with `Optional` Values

If you don't use `Optional` values correctly, you have no benefit over the "something or null" approach of the past.

The `get` method gets the wrapped element of an `Optional` value if it exists, or throws a `NoSuchElementException` if it doesn't. Therefore,

[Click here to view code image](#)

```
Optional<T> optionalValue = . . .;
optionalValue.get().someMethod()
```

is no safer than

[Click here to view code image](#)

```
T value = . . .;
value.someMethod();
```

The `isPresent` and `isEmpty` methods report whether or not an `Optional<T>` object has a value. But

[Click here to view code image](#)

```
if (optionalValue.isPresent())
optionalValue.get().someMethod();
```

is no easier than

[Click here to view code image](#)

```
if (value != null) value.someMethod();
```



Note

Java 10 introduced `orElseThrow`, a scarier-sounding synonym for the `get` method. When you call `optionalValue.orElseThrow().someMethod()`, it becomes explicit that an exception will occur if the `optionalValue` is empty. The hope is that programmers will only use `orElseThrow` when it is absolutely clear that this cannot happen.

Here are a few more tips for the proper use of the `Optional` type:

- A variable of type `Optional` should *never* be `null`.
- Don't use fields of type `Optional`. The cost is an additional object. Inside a class, use `null` for an absent field. To discourage `Optional` fields, the class is not serializable.
- Method parameters of type `Optional` are questionable. They make the call unpleasant in the common case where the requested value is present. Instead, consider two overloaded versions of the method, with and without the parameter. (On the other hand, returning an `Optional` is fine. It is the proper way to indicate that a function may not have a result.)
- Don't put `Optional` objects in a set, and don't use them as keys for a map. Collect the values instead.

`java.util.Optional` 8

- `T get()`
- `T orElseThrow() 10`

yield the value of this `Optional`, or throw a `NoSuchElementException` if it is empty.

- boolean isEmpty() 11
- boolean isPresent()

return true if this Optional is empty or not empty.

1.7.5 Creating Optional Values

So far, we have discussed how to consume an Optional object someone else created. If you want to write a method that creates an Optional object, there are several static methods for that purpose, including `Optional.of(result)` and `Optional.empty()`. For example,

[Click here to view code image](#)

```
public static Optional<Double> inverse(Double x)
{
    return x == 0 ? Optional.empty() : Optional.of(1 / x);
}
```

The `ofNullable` method is intended as a bridge from possibly null values to optional values. `Optional.ofNullable(obj)` returns `Optional.of(obj)` if `obj` is not null and `Optional.empty()` otherwise.

java.util.Optional 8

- static <T> Optional<T> of(T value)
- static <T> Optional<T> ofNullable(T value)

yield an Optional with the given value. If `value` is null, the first method throws a `NullPointerException` and the second method yields an empty Optional.

- static <T> Optional<T> empty()

yields an empty `Optional`.

1.7.6 Composing Optional Value Functions with `flatMap`

Suppose you have a method `f` yielding an `Optional<T>`, and the target type `T` has a method `g` yielding an `Optional<U>`. If they were normal methods, you could compose them by calling `s.f().g()`. But that composition doesn't work since `s.f()` has type `Optional<T>`, not `T`. Instead, call

[Click here to view code image](#)

```
Optional<U> result = s.f().flatMap(T::g);
```

If `s.f()` is present, then `g` is applied to it. Otherwise, an empty `Optional<U>` is returned.

Clearly, you can repeat that process if you have more methods or lambdas that yield `Optional` values. You can then build a pipeline of steps, simply by chaining calls to `flatMap`, that will succeed only when all parts do.

For example, consider the safe `inverse` method of the preceding section. Suppose we also have a safe square root:

[Click here to view code image](#)

```
public static Optional<Double> squareRoot(Double x)
{
    return x < 0 ? Optional.empty() : Optional.of(Math.sqrt(x));
}
```

Then you can compute the square root of the `inverse` as

[Click here to view code image](#)

```
Optional<Double> result =
inverse(x).flatMap(MyMath::squareRoot);
```

or, if you prefer,

[Click here to view code image](#)

```
Optional<Double> result  
=  
Optional.of(-4.0).flatMap(Demo::inverse).flatMap(Demo::squareRoot);
```

If either the `inverse` method or the `squareRoot` returns `Optional.empty()`, the result is empty.



Note

You have already seen a `flatMap` method in the `Stream` interface (see [Section 1.3, “The filter, map, and flatMap Methods,”](#) on p. 11). That method maps a stream-yielding method to all elements of a stream, and then flattens out the resulting stream of streams. The `Optional.flatMap` method works in the same way. By mapping an optional-yielding method to an optional, you get an optional of optional, which is then flattened out.

`java.util.Optional` 8

- `<U> Optional<U> flatMap(Function<? super T, ? extends Optional<? extends U>> mapper)`

yields the result of applying `mapper` to the value in this `Optional` if present, or an empty optional otherwise.

1.7.7 Turning an `Optional` into a Stream

The `stream` method turns an `Optional<T>` into a `Stream<T>` with zero or one element. Sure, why not, but why would you ever want that?

This becomes useful with methods that return an `Optional` result. Suppose you have a stream of user IDs and a method

[Click here to view code image](#)

```
Optional<User> lookup(String id)
```

How do you get a stream of users, skipping those IDs that are invalid?

Of course, you can filter out the invalid IDs and then apply `get` to the remaining ones:

[Click here to view code image](#)

```
Stream<String> ids = . . .;
Stream<User> users = ids.map(Users::lookup)
    .filter(Optional::isPresent)
    .map(Optional::get);
```

But that uses the `isPresent` and `get` methods that we warned about. It is more elegant to call

[Click here to view code image](#)

```
Stream<User> users = ids.map(Users::lookup)
    .flatMap(Optional::stream);
```

Each call to `stream` returns a stream with zero or one element. The `flatMap` method combines them all. That means the nonexistent users are simply dropped.



Note

In this section, we consider the happy scenario in which we have a method that returns an `Optional` value. These days, many methods return `null` when there is no valid result. Suppose

`Users.classicLookup(id)` returns a `User` object or null, not an `Optional<User>`. Then you can of course filter out the null values:

[Click here to view code image](#)

```
Stream<User> users = ids.map(Users::classicLookup)
    .filter(Objects::nonNull);
```

But if you prefer the `flatMap` approach, you can use

[Click here to view code image](#)

```
Stream<User> users = ids.flatMap(
    id -> Stream.ofNullable(Users.classicLookup(id)));
```

or

[Click here to view code image](#)

```
Stream<User> users = ids.map(Users::classicLookup)
    .flatMap(Stream::ofNullable);
```

The call `Stream.ofNullable(obj)` yields an empty stream if `obj` is null or a stream just containing `obj` otherwise.

The example program in [Listing 1.3](#) demonstrates the `Optional` API.

Listing 1.3 optional/OptionalTest.java

[Click here to view code image](#)

```
1 package optional;
2
3 import java.io.*;
4 import java.nio.file.*;
5 import java.util.*;
6
7 /**
8 * @version 1.02 2019-08-28
9 * @author Cay Horstmann
```

```
10  */
11 public class OptionalTest
12 {
13     public static void main(String[] args) throws IOException
14     {
15         var contents = Files.readString(
16             Path.of("../gutenberg/alice30.txt"));
17         List<String> wordList =
18 List.of(contents.split("\\PL+"));
19         Optional<String> optionalValue = wordList.stream()
20             .filter(s -> s.contains("fred"))
21             .findFirst();
22         System.out.println(optionalValue.orElse("No word") + " "
23 contains fred);
24
25         Optional<String> optionalString = Optional.empty();
26         String result = optionalString.orElse("N/A");
27         System.out.println("result: " + result);
28         result = optionalString.orElseGet(() ->
29 Locale.getDefault().getDisplayName());
30         System.out.println("result: " + result);
31     try
32     {
33         result =
34 optionalString.orElseThrow(IllegalStateException::new);
35         System.out.println("result: " + result);
36     }
37     catch (Throwable t)
38     {
39         t.printStackTrace();
40
41         optionalValue = wordList.stream()
42             .filter(s -> s.contains("red"))
43             .findFirst();
44         optionalValue.ifPresent(s -> System.out.println(s + " "
45 contains red));
46     }
47 }
```

```
43
44     var results = new HashSet<String>();
45     optionalValue.ifPresent(results::add);
46     Optional<Boolean> added =
47         optionalValue.map(results::add);
48     System.out.println(added);
49
50     System.out.println(inverse(4.0).flatMap(OptionalTest::squareRoot)
51 );
52     System.out.println(inverse(-1.0).flatMap(OptionalTest::squareRoot)
53 );
54     System.out.println(inverse(0.0).flatMap(OptionalTest::squareRoot)
55 );
56
57     public static Optional<Double> inverse(Double x)
58     {
59         return x == 0 ? Optional.empty() : Optional.of(1 / x);
60     }
61
62     public static Optional<Double> squareRoot(Double x)
63     {
64         return x < 0 ? Optional.empty() :
65             Optional.of(Math.sqrt(x));
66     }

```

java.util.Optional 8

- <U> Optional<U> flatMap(Function<? super T,Optional<U>> mapper) 9
yields the result of applying mapper to the value of this Optional, or an empty Optional if this Optional is empty.

1.8 Collecting Results

When you are done with a stream, you will often want to look at the results. You can call the `iterator` method, which yields an old-fashioned iterator that you can use to visit the elements.

Alternatively, you can call the `forEach` method to apply a function to each element:

[Click here to view code image](#)

```
stream.forEach(System.out::println);
```

On a parallel stream, the `forEach` method traverses elements in arbitrary order. If you want to process them in stream order, call `forEachOrdered` instead. Of course, you might then give up some or all of the benefits of parallelism.

But more often than not, you will want to collect the result in a data structure. You have already seen the `toList` method that yields a list of the stream elements.

Call `toArray` to get an array of the stream elements.

Since it is not possible to create a generic array at runtime, the expression `stream.toArray()` returns an `Object[]` array. If you want an array of the correct type, pass in the array constructor:

[Click here to view code image](#)

```
String[] result = stream.toArray(String[]::new);  
// stream.toArray() has type Object[]
```

For collecting stream elements to another target, there is a convenient `collect` method that takes an instance of the `Collector` interface. A *collector* is an object that accumulates elements and produces a result. The `Collectors` class provides a large number of factory methods for common collectors. Before the `toList` method was added in Java 16, you had to use the collector produced by `Collectors.toList()`:

[Click here to view code image](#)

```
List<String> result = stream.collect(Collectors.toList());
```

Similarly, here is how you can collect stream elements into a set:

[Click here to view code image](#)

```
Set<String> result = stream.collect(Collectors.toSet());
```

These calls give you a list or set, but you cannot make any further assumptions. The collection might not be mutable, serializable, or thread-safe. If you want to control which kind of collection you get, use the following call instead:

[Click here to view code image](#)

```
TreeSet<String> result =  
stream.collect(Collectors.toCollection(TreeSet::new));
```

Suppose you want to collect all strings in a stream by concatenating them. You can call

[Click here to view code image](#)

```
String result = stream.collect(Collectors.joining());
```

If you want a delimiter between elements, pass it to the `joining` method:

[Click here to view code image](#)

```
String result = stream.collect(Collectors.joining(", "));
```

If your stream contains objects other than strings, you need to first convert them to strings, like this:

[Click here to view code image](#)

```
String result =
stream.map(Object::toString).collect(Collectors.joining(", "));
```

If you want to reduce the stream results to a sum, count, average, maximum, or minimum, use one of the `summarizing(Int|Long[Double])` methods. These methods take a function that maps the stream objects to numbers and yield a result of type `(Int|Long[Double])SummaryStatistics`, simultaneously computing the sum, count, average, maximum, and minimum.

[Click here to view code image](#)

```
IntSummaryStatistics summary = stream.collect(
    Collectors.summarizingInt(String::length));
double averageWordLength = summary.getAverage();
double maxWordLength = summary.getMax();
```

The example program in [Listing 1.4](#) shows how to collect elements from a stream.

Listing 1.4 collecting/CollectingResults.java

[Click here to view code image](#)

```
1 package collecting;
2
3 import java.io.*;
4 import java.nio.file.*;
5 import java.util.*;
6 import java.util.stream.*;
7
8 /**
```

```
9   * @version 1.02 2019-08-28
10  * @author Cay Horstmann
11  */
12 public class CollectingResults
13 {
14     public static Stream<String> noVowels() throws IOException
15     {
16         var contents = Files.readString(
17             Path.of("../gutenberg/alice30.txt"));
18
19         List<String> wordList =
20             List.of(contents.split("\\PL+"));
21         Stream<String> words = wordList.stream();
22         return words.map(s -> s.replaceAll("[aeiouAEIOU]",
23                                         ""));
23
24     public static <T> void show(String label, Set<T> set)
25     {
26         System.out.print(label + ": " +
27             set.getClass().getName());
27         System.out.println("["
28             +
29             set.stream().limit(10).map(Object::toString).collect(Collectors.j
30             oining(", "))
31             +
32         "]");
32
33     public static void main(String[] args) throws IOException
34     {
35         Iterator<Integer> iter = Stream.iterate(0, n -> n +
36             1).limit(10).iterator();
37         while (iter.hasNext())
38             System.out.println(iter.next());
39
40         Object[] numbers = Stream.iterate(0, n -> n +
41             1).limit(10).toArray();
42         System.out.println("Object array:" + numbers);
43 }
```

```
40         // Note it's an Object[] array
41
42     try
43     {
44         var number = (Integer) numbers[0]; // OK
45         System.out.println("number: " + number);
46         System.out.println("The following statement throws
an exception:");
47         var numbers2 = (Integer[]) numbers; // Throws
exception
48     }
49     catch (ClassCastException e)
50     {
51         System.out.println(e);
52     }
53
54     Integer[] numbers3 = Stream.iterate(0, n -> n + 1)
55         .limit(10)
56         .toArray(Integer[]::new);
57     System.out.println("Integer array: " + numbers3);
58     // Note it's an Integer[] array
59
60     Set<String> noVowelSet =
noVowels().collect(Collectors.toSet());
61     show("noVowelSet", noVowelSet);
62
63     TreeSet<String> noVowelTreeSet = noVowels().collect(
64         Collectors.toCollection(TreeSet::new));
65     show("noVowelTreeSet", noVowelTreeSet);
66
67     String result =
noVowels().limit(10).collect(Collectors.joining());
68     System.out.println("Joining: " + result);
69     result = noVowels().limit(10)
70         .collect(Collectors.joining(", "));
71     System.out.println("Joining with commas: " + result);
72
73     IntSummaryStatistics summary = noVowels().collect(
```

```
74     Collectors.summarizingInt(String::length));
75     double averageWordLength = summary.getAverage();
76     double maxWordLength = summary.getMax();
77     System.out.println("Average word length: " +
averageWordLength);
78     System.out.println("Max word length: " +
maxWordLength);
79     System.out.println("forEach:");
80     noVowels().limit(10).forEach(System.out::println);
81 }
82 }
```

java.util.stream.BaseStream 8

- `Iterator<T> iterator()`
yields an iterator for obtaining the elements of this stream. This is a terminal operation.

java.util.stream.Stream 8

- `List<T> toList() 16`
yields a list of the elements in this stream.
- `void forEach(Consumer<? super T> action)`
invokes `action` on each element of the stream.
- `Object[] toArray()`
- `<A> A[] toArray(IntFunction<A[]> generator)`
yield an array of objects, or of type `A` when passed a constructor reference `A[] ::new`. These are terminal operations.

- `<R,A> R collect(Collector<? super T,A,R> collector)`

collects the elements in this stream, using the given collector. The `Collectors` class has factory methods for many collectors.

java.util.stream.Collectors 8

- `static <T> Collector<T,?,List<T>> toList()`
- `static <T> Collector<T,?,List<T>> toUnmodifiableList() 10`
- `static <T> Collector<T,?,Set<T>> toSet()`
- `static <T> Collector<T,?,Set<T>> toUnmodifiableSet() 10`

yield collectors that collect elements in a list or set.

- `static <T,C extends Collection<T>> Collector<T,?,C> toCollection(Supplier<C> collectionFactory)`

yields a collector that collects elements into an arbitrary collection. Pass a constructor reference such as `TreeSet::new`.

- `static Collector<CharSequence,?,String> joining()`
- `static Collector<CharSequence,?,String> joining(CharSequence delimiter)`
- `static Collector<CharSequence,?,String> joining(CharSequence delimiter, CharSequence prefix, CharSequence suffix)`

yield a collector that joins strings. The delimiter is placed between strings, and the prefix and suffix before the first and after the last string. When not specified, these are empty.

- static <T>
Collector<T, ?, IntSummaryStatistics>
summarizingInt(ToIntFunction<? super T>
mapper)
- static <T>
Collector<T, ?, LongSummaryStatistics>
summarizingLong(ToLongFunction<? super T>
mapper)
- static <T>
Collector<T, ?, DoubleSummaryStatistics>
summarizingDouble(ToDoubleFunction<? super
T> mapper)

yield collectors that produce an (Int|Long|Double)SummaryStatistics object, from which you can obtain the count, sum, average, maximum, and minimum of the results of applying mapper to each element.

IntSummaryStatistics 8

LongSummaryStatistics 8

DoubleSummaryStatistics 8

- long getCount()

yields the count of the summarized elements.
- (int|long|double) getSum()
• double getAverage()

yield the sum or average of the summarized elements, or zero if there are no elements.
- (int|long|double) getMax()
• (int|long|double) getMin()

yield the maximum or minimum of the summarized elements, or `(Integer|Long|Double).(MAX|MIN)_VALUE` if there are no elements.

1.9 Collecting into Maps

Suppose you have a `Stream<Person>` and want to collect the elements into a map so that later you can look up people by their ID. The `Collectors.toMap` method has two function arguments that produce the map's keys and values. For example,

[Click here to view code image](#)

```
public record Person(int id, String name) {}  
.  
.  
.  
Map<Integer, String> idToName = people.collect(  
    Collectors.toMap(Person::id, Person::name));
```

In the common case when the values should be the actual elements, use `Function.identity()` for the second function.

[Click here to view code image](#)

```
Map<Integer, Person> idToPerson = people.collect(  
    Collectors.toMap(Person::id, Function.identity()));
```

If there is more than one element with the same key, there is a conflict, and the collector will throw an `IllegalStateException`. You can override that behavior by supplying a third function argument that resolves the conflict and determines the value for the key, given the existing and the new value. Your function could return the existing value, the new value, or a combination of them.

Here, we construct a map that contains, for each language in the available locales, as key its name in your default locale (such as "German"), and as value its localized name (such as "Deutsch").

[Click here to view code image](#)

```
Stream<Locale> locales =  
Stream.of(Locale.getAvailableLocales());  
Map<String, String> languageNames = locales.collect(  
    Collectors.toMap(  
        Locale::getDisplayLanguage,  
        loc -> loc.getDisplayLanguage(loc),  
        (existingValue, newValue) -> existingValue));
```

We don't care that the same language might occur twice (for example, German in Germany and in Switzerland), so we just keep the first entry.



Note

In this chapter, I use the `Locale` class as a source of an interesting data set. See [Chapter 7](#) for more information on working with locales.

Now suppose we want to know all languages in a given country. Then we need a `Map<String, Set<String>>`. For example, the value for "Switzerland" is the set [French, German, Italian]. At first, we store a singleton set for each language. Whenever a new language is found for a given country, we form the union of the existing and the new set.

[Click here to view code image](#)

```
Map<String, Set<String>> countryLanguageSets = locales.collect(  
    Collectors.toMap(  
        Locale::getDisplayCountry,  
        l -> Collections.singleton(l.getDisplayLanguage()),  
        (a, b) ->  
            { // Union of a and b  
                var union = new HashSet<String>(a);  
                union.addAll(b);
```

```
        return union;
    } );
}
```

You will see a simpler way of obtaining this map in the next section.

If you want a TreeMap, supply the constructor as the fourth argument. You must provide a merge function. Here is one of the examples from the beginning of the section, now yielding a TreeMap:

[Click here to view code image](#)

```
Map<Integer, Person> idToPerson = people.collect(
    Collectors.toMap(
        Person::id,
        Function.identity(),
        (existingValue, newValue) -> { throw new
            IllegalStateException(); },
        TreeMap::new));

```



Note

For each of the `toMap` methods, there is an equivalent `toConcurrentMap` method that yields a concurrent map. A single concurrent map is used in the parallel collection process. When used with a parallel stream, a shared map is more efficient than merging maps. Note that elements are no longer collected in stream order, but that doesn't usually make a difference.

The program in [Listing 1.5](#) gives examples of collecting stream results into maps.

Listing 1.5 collecting/CollectingIntoMaps.java

[Click here to view code image](#)

```
1 package collecting;
2
3 import java.io.*;
4 import java.util.*;
5 import java.util.function.*;
6 import java.util.stream.*;
7
8 /**
9  * @version 1.01 2021-09-06
10 * @author Cay Horstmann
11 */
12 public class CollectingIntoMaps
13 {
14
15     public record Person(int id, String name) {}
16
17     public static Stream<Person> people()
18     {
19         return Stream.of(new Person(1001, "Peter"), new
Person(1002, "Paul"),
20                         new Person(1003, "Mary"));
21     }
22
23     public static void main(String[] args) throws IOException
24     {
25         Map<Integer, String> idToName = people().collect(
26             Collectors.toMap(Person::id, Person::name));
27         System.out.println("idToName: " + idToName);
28
29         Map<Integer, Person> idToPerson = people().collect(
30             Collectors.toMap(Person::id, Function.identity()));
31         System.out.println("idToPerson: " +
idToPerson.getClass().getName()
32                         + idToPerson);
33
34         idToPerson = people().collect(
35             Collectors.toMap(Person::id, Function.identity(),
36                             (existingValue, newValue) -> { throw new
```

```

IllegalStateException(); },
37             TreeMap::new));
38         System.out.println("idToPerson: " +
idToPerson.getClass().getName()
39             + idToPerson);
40
41         Stream<Locale> locales =
Stream.of(Locale.getAvailableLocales());
42         Map<String, String> languageNames = locales.collect(
43             Collectors.toMap(
44                 Locale::getDisplayLanguage,
45                 l -> l.getDisplayLanguage(),
46                 (existingValue, newValue) -> existingValue));
47         System.out.println("languageNames: " + languageNames);
48
49         locales = Stream.of(Locale.getAvailableLocales());
50         Map<String, Set<String>> countryLanguageSets =
locales.collect(
51             Collectors.toMap(
52                 Locale::getDisplayCountry,
53                 l -> Set.of(l.getDisplayLanguage()),
54                 (a, b) ->
55                     { // union of a and b
56                         Set<String> union = new HashSet<>(a);
57                         union.addAll(b);
58                         return union;
59                     }));
60         System.out.println("countryLanguageSets: " +
countryLanguageSets);
61     }
62 }
```

java.util.stream.Collectors 8

- static <T,K,U> Collector<T,?,Map<K,U>>
 toMap(Function<? super T,>? extends K>

- ```
keyMapper, Function<? super T,? extends U>
valueMapper)
• static <T,K,U> Collector<T,?,Map<K,U>>
toMap(Function<? super T,? extends K>
keyMapper, Function<? super T,? extends U>
valueMapper, BinaryOperator<U>
mergeFunction)
• static <T,K,U,M extends Map<K,U>>
Collector<T,?,M> toMap(Function<? super T,?
extends K> keyMapper, Function<? super T,?
extends U> valueMapper, BinaryOperator<U>
mergeFunction, Supplier<M> mapSupplier)
• static <T,K,U> Collector<T,?,Map<K,U>>
toUnmodifiableMap(Function<? super T,?
extends K> keyMapper, Function<? super T,?
extends U> valueMapper) 10
• static <T,K,U> Collector<T,?,Map<K,U>>
toUnmodifiableMap(Function<? super T,?
extends K> keyMapper, Function<? super T,?
extends U> valueMapper, BinaryOperator<U>
mergeFunction) 10
• static <T,K,U>
Collector<T,?,ConcurrentMap<K,U>>
toConcurrentMap(Function<? super T,? extends
K> keyMapper, Function<? super T,? extends
U> valueMapper)
• static <T,K,U>
Collector<T,?,ConcurrentMap<K,U>>
toConcurrentMap(Function<? super T,? extends
K> keyMapper, Function<? super T,? extends
U> valueMapper, BinaryOperator<U>
mergeFunction)
• static <T,K,U,M extends ConcurrentHashMap<K,U>>
Collector<T,?,M> toConcurrentMap(Function<?
```

```
super T,? extends K> keyMapper, Function<?
super T,? extends U> valueMapper,
BinaryOperator<U> mergeFunction, Supplier<M>
mapSupplier)
```

yield a collector that produces a map, unmodifiable map, or concurrent map. The `keyMapper` and `valueMapper` functions are applied to each collected element, yielding a key/value entry of the resulting map. By default, an `IllegalStateException` is thrown when two elements give rise to the same key. You can instead supply a `mergeFunction` that merges values with the same key. By default, the result is a `HashMap` or `ConcurrentHashMap`. You can instead supply a `mapSupplier` that yields the desired map instance.

## 1.10 Grouping and Partitioning

In the preceding section, you saw how to collect all languages in a given country. But the process was a bit tedious. You had to generate a singleton set for each map value and then specify how to merge the existing and new values. Forming groups of values with the same characteristic is very common, so the `groupingBy` method supports it directly.

Let's look at the problem of grouping locales by country. First, form this map:

[Click here to view code image](#)

```
Map<String, List<Locale>> countryToLocales = locales.collect(
 Collectors.groupingBy(Locale::getCountry));
```

The function `Locale::getCountry` is the *classifier function* of the grouping. You can now look up all locales for a given country code, for example

[Click here to view code image](#)

```
List<Locale> swissLocales = countryToLocales.get("CH");
// Yields locales de_CH, fr_CH, it_CH, and maybe more
```

---



## Note

A quick refresher on locales: Each locale has a language code (such as `en` for English) and a country code (such as `US` for the United States). The locale `en_US` describes English in the United States, and `en_IE` is English in Ireland. Some countries have multiple locales. For example, `ga_IE` is Gaelic in Ireland, and, as the preceding example shows, the JDK knows at least three locales in Switzerland.

---

When the classifier function is a predicate function (that is, a function returning a `boolean` value), the stream elements are partitioned into two lists: those where the function returns `true` and the complement. In this case, it is more efficient to use `partitioningBy` instead of `groupingBy`. For example, here we split all locales into those that use English and all others:

[Click here to view code image](#)

```
Map<Boolean, List<Locale>> englishAndOtherLocales =
locales.collect(
 Collectors.partitioningBy(l ->
 l.getLanguage().equals("en")));
List<Locale> englishLocales = englishAndOtherLocales.get(true);
```

---



## Note

If you call the `groupingByConcurrent` method, you get a concurrent map that, when used with a parallel stream, is concurrently populated. This is entirely analogous to the `toConcurrentMap` method.

---

## **java.util.stream.Collectors 8**

- static <T, K> Collector<T, ?, Map<K, List<T>>>  
groupingBy(Function<? super T, ? extends K>  
classifier)
- static <T, K>  
Collector<T, ?, ConcurrentMap<K, List<T>>>  
groupingByConcurrent(Function<? super T, ?  
extends K> classifier)

yield a collector that produces a map or concurrent map whose keys are the results of applying `classifier` to all collected elements, and whose values are lists of elements with the same key.

- static <T>  
Collector<T, ?, Map<Boolean, List<T>>>  
partitioningBy(Predicate<? super T>  
predicate)

yields a collector that produces a map whose keys are true/false, and whose values are lists of the elements that fulfill/do not fulfill the predicate.

## **1.11 Downstream Collectors**

The `groupingBy` method yields a map whose values are lists. If you want to process those lists in some way, supply a *downstream collector*. For example, if you want sets instead of lists, you can use the `Collectors.toSet` collector that you saw in the preceding section:

[Click here to view code image](#)

```
Map<String, Set<Locale>> countryToLocaleSet = locales.collect(
 groupingBy(Locale::getCountry, toSet()));
```

---



## Note

In this example, as well as the remaining examples of this section, I assume a static import of `java.util.stream.Collectors.*` to make the expressions easier to read.

---

Several collectors are provided for reducing collected elements to numbers:

- `counting` produces a count of the collected elements. For example,  
[Click here to view code image](#)

```
Map<String, Long> countryToLocaleCounts = locales.collect(
 groupingBy(Locale::getCountry, counting()));
```

counts how many locales there are for each country.

- `summing(Int|Long[Double])` and `averaging(Int|Long[Double])` take a function argument, apply the function to the downstream elements, and produce their sum or average. For example,

[Click here to view code image](#)

```
public record City(String name, String state, int population)
{ }
.
. . .
Map<String, Integer> stateToCityPopulation = cities.collect(
 groupingBy(City::state, averagingInt(City::population)));
```

computes the average of populations per state in a stream of cities.

- `maxBy` and `minBy` take a comparator and produce maximum and minimum of the downstream elements. For example,

[Click here to view code image](#)

```
Map<String, Optional<City>> stateToLargestCity =
 cities.collect(
 groupingBy(City::state,
 maxBy(Comparator.comparing(City::population))));
```

produces the largest city per state.

The `collectingAndThen` collector adds a final processing step behind a collector. For example, if you want to know how many distinct results there are, collect them into a set and then compute the size:

[Click here to view code image](#)

```
Map<Character, Integer> stringCountsByStartingLetter =
 strings.collect(
 groupingBy(s -> s.charAt(0),
 collectingAndThen(toSet(), Set::size)));
```

The mapping collector does the opposite. It applies a function to each collected element and passes the results to a downstream collector.

[Click here to view code image](#)

```
Map<Character, Set<Integer>> stringLengthsByStartingLetter =
 strings.collect(
 groupingBy(s -> s.charAt(0),
 mapping(String::length, toSet())));
```

Here, we group strings by their first character. Within each group, we produce the lengths and collect them in a set.

The mapping method also yields a nicer solution to a problem from the preceding section—gathering a set of all languages in a country.

[Click here to view code image](#)

```
Map<String, Set<String>> countryToLanguages = locales.collect(
 groupingBy(Locale::getDisplayCountry,
```

```
mapping(Locale::getDisplayLanguage,
 toSet())));
```

There is a `flatMapting` method as well, for use with functions that return streams.

If the grouping or mapping function has return type `int`, `long`, or `double`, you can collect elements into a summary statistics object, as discussed in [Section 1.8, “Collecting Results,”](#) on p. 26. For example,

[Click here to view code image](#)

```
Map<String, IntSummaryStatistics> stateToCityPopulationSummary
= cities.collect(
 groupingBy(City::state,
 summarizingInt(City::population)));
```

Then you can get the sum, count, average, minimum, and maximum of the function values from the summary statistics objects of each group.

The filtering collector applies a filter to each group, for example:

[Click here to view code image](#)

```
Map<String, Set<City>> largeCitiesByState
= cities.collect(
 groupingBy(City::state,
 filtering(c -> c.population() > 500000,
 toSet()))); // States without large cities have
empty sets
```

Finally, you can use the `teeing` collector to branch into two parallel downstream collections. This is useful whenever you need to compute more than one result from a stream. Suppose you want to collect city names and also compute their average population. You can't read a stream twice, but `teeing` lets you carry out two computations. Specify two downstream collectors and a function that combines the results.

[Click here to view code image](#)

```
record Pair<S, T>(S first, T second) {}
Pair<List<String>, Double> result = cities.filter(c ->
c.state().equals("NV"))
.collect(teeing(
 mapping(City::name, toList()), // First downstream
 collector
 averagingDouble(City::population), // Second downstream
 collector
 (list, avg) -> new Result(list, avg))); // Combining
function
```

---



## Note

There are also three versions of a reducing method that apply general reductions, as described in the next section.

---

Composing collectors is powerful, but it can lead to very convoluted expressions. The best use is with groupingBy or partitioningBy to process the “downstream” map values. Otherwise, simply apply methods such as map, reduce, count, max, or min directly on streams.

The example program in [Listing 1.6](#) demonstrates downstream collectors.

---

### **Listing 1.6** collecting/DownstreamCollectors.java

[Click here to view code image](#)

```
1 package collecting;
2
3 import static java.util.stream.Collectors.*;
4
5 import java.io.*;
6 import java.nio.file.*;
7 import java.util.*;
8 import java.util.stream.*;
```

```
10 /**
11 * @version 1.01 2021-09-06
12 * @author Cay Horstmann
13 */
14 public class DownstreamCollectors
15 {
16 public record City(String name, String state, int
population) {}
17
18 public static Stream<City> readCities(String filename)
throws IOException
19 {
20 return Files.lines(Path.of(filename))
21 .map(l -> l.split(", "))
22 .map(a -> new City(a[0], a[1],
Integer.parseInt(a[2])));
23 }
24
25 public static void main(String[] args) throws IOException
26 {
27 Stream<Locale> locales =
Stream.of(Locale.getAvailableLocales());
28 Map<String, Set<Locale>> countryToLocaleSet =
locales.collect(groupingBy(
29 Locale::getCountry, toSet()));
30 System.out.println("countryToLocaleSet: " +
countryToLocaleSet);
31
32 locales = Stream.of(Locale.getAvailableLocales());
33 Map<String, Long> countryToLocaleCounts =
locales.collect(groupingBy(
34 Locale::getCountry, counting()));
35 System.out.println("countryToLocaleCounts: " +
countryToLocaleCounts);
36
37 Stream<City> cities = readCities("cities.txt");
38 Map<String, Integer> stateToCityPopulation =
cities.collect(groupingBy(
```

```
39 City::state, summingInt(City::population)));
40 System.out.println("stateToCityPopulation: " +
stateToCityPopulation);
41
42 cities = readCities("cities.txt");
43 Map<String, Optional<String>> stateToLongestCityName =
cities
44 .collect(groupingBy(City::state,
45 mapping(City::name,
maxBy(Comparator.comparing(String::length))))) ;
46 System.out.println("stateToLongestCityName: " +
stateToLongestCityName);
47
48 locales = Stream.of(Locale.getAvailableLocales());
49 Map<String, Set<String>> countryToLanguages =
locales.collect(groupingBy(
50 Locale::getDisplayCountry,
mapping(Locale::getDisplayLanguage, toSet())));
51 System.out.println("countryToLanguages: " +
countryToLanguages);
52
53 cities = readCities("cities.txt");
54 Map<String, IntSummaryStatistics>
stateToCityPopulationSummary = cities
55 .collect(groupingBy(City::state,
summarizingInt(City::population)));
56
System.out.println(stateToCityPopulationSummary.get("NY"));
57
58 cities = readCities("cities.txt");
59 Map<String, String> stateToCityNames =
cities.collect(groupingBy(
60 City::state,
61 reducing("", City::name, (s, t) -> s.length() == 0 ? t
: s + ", " + t)));
62
63 cities = readCities("cities.txt");
64 stateToCityNames = cities.collect(groupingBy(City::state,
```

```

65 mapping(City::name, joining(", ")));
66 System.out.println("stateToCityNames: " +
stateToCityNames);
67
68 cities = readCities("cities.txt");
69 record Pair<S, T>(S first, T second) {}
70 Pair<List<String>, Double> result = cities.filter(c ->
c.state().equals("NV"))
71 .collect(teeing(
72 mapping(City::name, toList()),
73 averagingDouble(City::population),
74 (names, avg) -> new Pair<>(names, avg)));
75 System.out.println(result);
76 }
77 }
```

---

## **java.util.stream.Collectors 8**

- `public static <T,K,A,D> Collector<T,?,Map<K,D>> groupingBy(Function<? super T,? extends K> classifier, Collector<? super T,A,D> downstream)`

yields a collector that produces a map. The keys are the results of applying `classifier` to all collected elements. The values are the results of collecting elements with the same key, using the `downstream` collector.

- `static <T> Collector<T,?,Long> counting()`

yields a collector that counts the collected elements.

- `static <T> Collector<T,?,Integer> summingInt(ToIntFunction<? super T> mapper)`

- static <T> Collector<T, ?, Long>  
summingLong(ToLongFunction<? super T>  
mapper)
- static <T> Collector<T, ?, Double>  
summingDouble(ToDoubleFunction<? super T>  
mapper)

yield a collector that computes the sum of the results of applying mapper to the collected elements.

- static <T> Collector<T, ?, Optional<T>>  
maxBy(Comparator<? super T> comparator)
- static <T> Collector<T, ?, Optional<T>>  
minBy(Comparator<? super T> comparator)

yield a collector that computes the maximum or minimum of the collected elements, using the ordering specified by comparator.

- static <T, A, R, RR> Collector<T, A, RR>  
collectingAndThen(Collector<T, A, R>  
downstream, Function<R, RR> finisher)

yields a collector that sends elements to the downstream collector and then applies the finisher function to its result.

- static <T, U, A, R> Collector<T, ?, R>  
mapping(Function<? super T, ? extends U>  
mapper, Collector<? super U, A, R> downstream)

yields a collector that calls mapper on each element and passes the results to the downstream collector.

- static <T, U, A, R> Collector<T, ?, R>  
flatMapping(Function<? super T, ? extends Stream<? extends U>>  
mapper, Collector<? super U, A, R> downstream)

yields a collector that calls mapper on each element and passes the elements of the results to the downstream collector.

- `static <T,A,R> Collector<T,?,R> filtering(Predicate<? super T> predicate, Collector<? super T,A,R> downstream)`

yields a collector that passes the elements fulfilling the predicate to the downstream collector.

## 1.12 Reduction Operations

The `reduce` method is a general mechanism for computing a value from a stream. The simplest form takes a binary function and keeps applying it, starting with the first two elements. It's easy to explain this if the function is the sum:

[Click here to view code image](#)

```
List<Integer> values = . . .;
Optional<Integer> sum = values.stream().reduce((x, y) -> x +
y);
```

In this case, the `reduce` method computes  $v_0 + v_1 + v_2 + \dots$ , where  $v_i$  are the stream elements. The method returns an `Optional` because there is no valid result if the stream is empty.



### Note

In this case, you can write `reduce(Integer::sum)` instead of `reduce((x, y) -> x + y)`.

---

More generally, you can use any operation that combines a partial result  $x$  with the next value  $y$  to yield a new partial result.

Here is another way of looking at reductions. Given a reduction operation  $op$ , the reduction yields  $v_0 \ op \ v_1 \ op \ v_2 \ op \dots$ , where  $v_i \ op \ v_{i+1}$  denotes the function call  $op(v_i, v_{i+1})$ . There are many operations that might be useful in practice—such as sum, product, string concatenation, maximum and minimum, set union or intersection.

If you want to use reduction with parallel streams, the operation must be *associative*: It shouldn't matter in which order you combine the elements. In math notation,  $(x \ op \ y) \ op \ z$  must be equal to  $x \ op \ (y \ op \ z)$ . An example of an operation that is not associative is subtraction. For example,  $(6 - 3) - 2 \neq 6 - (3 - 2)$ .

Often, there is an *identity*  $e$  such that  $e \ op \ x = x$ , and that element can be used as the start of the computation. For example, 0 is the identity for addition, and you can use the second form of `reduce`:

[Click here to view code image](#)

```
List<Integer> values = . . .;
Integer sum = values.stream().reduce(0, (x, y) -> x + y);
// Computes 0 + v0 + v1 + v2 + . . .
```

The identity value is returned if the stream is empty, and you no longer need to deal with the `Optional` class.

Now suppose you have a stream of objects and want to form the sum of some property, such as lengths in a stream of strings. You can't use the simple form of `reduce`. It requires a function  $(T, T) \rightarrow T$ , with the same types for the arguments and the result, but in this situation you have two types: The stream elements have type `String`, and the accumulated result is an integer. There is a form of `reduce` that can deal with this situation.

First, you supply an “accumulator” function  $(total, word) \rightarrow total + word.length()$ . That function is called repeatedly, forming the cumulative total. But when the computation is parallelized, there will be multiple computations of this kind, and you need to combine their results. You supply a second function for that purpose. The complete call is

[Click here to view code image](#)

```
int result = words.reduce(0,
 (total, word) -> total + word.length(),
 (total1, total2) -> total1 + total2);
```

---



## Note

In practice, you probably won't use the `reduce` method a lot. It is usually easier to map to a stream of numbers and use one of its methods to compute sum, maximum, or minimum. (We discuss streams of numbers in [Section 1.13, “Primitive Type Streams,”](#) on p. 43.) In this particular example, you could have called `words.mapToInt(String::length).sum()`, which is both simpler and more efficient since it doesn't involve boxing.

---



## Note

There are times when `reduce` is not general enough. For example, suppose you want to collect the results in a `BitSet`. If the collection is parallelized, you can't put the elements directly into a single `BitSet` because a `BitSet` object is not thread-safe. For that reason, you can't use `reduce`. Each segment needs to start out with its own empty set, and `reduce` only lets you supply one identity value. Instead, use the three-argument form of `collect`. Its arguments are:

1. A *supplier* to construct new instances of the target object
2. An *accumulator* that adds an element to the target
3. A *combiner* that merges two target objects into one

Here is how the `collect` method works for a bit set:

[Click here to view code image](#)

```
BitSet result = stream.collect(BitSet::new, BitSet::set,
 BitSet::or);
```

---

### ***java.util.Stream 8***

- `Optional<T> reduce(BinaryOperator<T> accumulator)`
- `T reduce(T identity, BinaryOperator<T> accumulator)`
- `<U> U reduce(U identity, BiFunction<U, ? super T, U> accumulator, BinaryOperator<U> combiner)`

form a cumulative total of the stream elements with the given accumulator function. If `identity` is provided, then it is the first value to be accumulated. If `combiner` is provided, it can be used to combine totals of segments that are accumulated separately.

- `<R> R collect(Supplier<R> supplier,  
 BiConsumer<R, ? super T> accumulator,  
 BiConsumer<R, R> combiner)`

collects elements in a result of type `R`. On each segment, `supplier` is called to provide an initial result, `accumulator` is called to mutably add elements to it, and `combiner` is called to combine two results.

## **1.13 Primitive Type Streams**

So far, we have collected integers in a `Stream<Integer>`, even though it is clearly inefficient to wrap each integer into a wrapper object. The same is true for the other primitive types—`double`, `float`, `long`, `short`,

char, byte, and boolean. The stream library has specialized types IntStream, LongStream, and DoubleStream that store primitive values directly, without using wrappers. If you want to store short, char, byte, and boolean, use an IntStream; for float, use a DoubleStream.

To create an IntStream, call the IntStream.of and Arrays.stream methods:

[Click here to view code image](#)

```
IntStream stream = IntStream.of(1, 1, 2, 3, 5);
stream = Arrays.stream(values, from, to); // values is an int[]
array
```

As with object streams, you can also use the static generate and iterate methods. In addition, IntStream and LongStream have static methods range and rangeClosed that generate integer ranges with step size one:

[Click here to view code image](#)

```
IntStream zeroToNinetyNine = IntStream.range(0, 100); // Upper
bound is excluded
IntStream zeroToHundred = IntStream.rangeClosed(0, 100); //
Upper bound is included
```

The CharSequence interface has methods codePoints and chars that yield an IntStream of the Unicode codes of the characters or of the code units in the UTF-16 encoding. (See [Chapter 2](#) for the sordid details.)

[Click here to view code image](#)

```
String sentence = "\uD835\uDD46 is the set of octonions.";
// \uD835\uDD46 is the UTF-16 encoding of the letter ☉,
unicode U+1D546

IntStream codes = sentence.codePoints();
// The stream with hex values 1D546 20 69 73 20 . . .
```

When you have a stream of objects, you can transform it to a primitive type stream with the `mapToInt`, `mapToLong`, or `mapToDouble` methods. For example, if you have a stream of strings and want to process their lengths as integers, you might as well do it in an `IntStream`:

[Click here to view code image](#)

```
Stream<String> words = . . .;
IntStream lengths = words.mapToInt(String::length);
```

To convert a primitive type stream to an object stream, use the `boxed` method:

[Click here to view code image](#)

```
Stream<Integer> integers = IntStream.range(0, 100).boxed();
```

Generally, the methods on primitive type streams are analogous to those on object streams. Here are the most notable differences:

- The `toArray` methods return primitive type arrays.
- Methods that yield an optional result return an `OptionalInt`, `OptionalLong`, or `OptionalDouble`. These classes are analogous to the `Optional` class, but they have methods `getAsInt`, `getAsLong`, and `getAsDouble` instead of the `get` method.
- There are methods `sum`, `average`, `max`, and `min` that return the sum, count, average, maximum, and minimum. These methods are not defined for object streams.
- The `summaryStatistics` method yields an object of type `IntSummaryStatistics`, `LongSummaryStatistics`, or `DoubleSummaryStatistics` that can simultaneously report the sum, count, average, maximum, and minimum of the stream.



## Note

The `Random` class has methods `ints`, `longs`, and `doubles` that return primitive type streams of random numbers. If you need

random numbers in parallel streams, use the `SplittableRandom` class instead.

---

The program in [Listing 1.7](#) gives examples for the API of primitive type streams.

---

### **Listing 1.7** streams/PrimitiveTypeStreams.java

---

[Click here to view code image](#)

```
1 package streams;
2
3 import java.io.*;
4 import java.nio.file.*;
5 import java.util.stream.*;
6
7 /**
8 * @version 1.02 2021-09-09
9 * @author Cay Horstmann
10 */
11 public class PrimitiveTypeStreams
12 {
13 public static void show(String title, IntStream stream)
14 {
15 final int SIZE = 10;
16 int[] firstElements = stream.limit(SIZE + 1).toArray();
17 System.out.print(title + ": ");
18 for (int i = 0; i < firstElements.length; i++)
19 {
20 if (i > 0) System.out.print(", ");
21 if (i < SIZE) System.out.print(firstElements[i]);
22 else System.out.print("...");
23 }
24 System.out.println();
25 }
26
27 public static void main(String[] args) throws IOException
```

```

28 {
29 IntStream is1 = IntStream.generate(() -> (int)
30 (Math.random() * 100));
31 show("is1", is1);
32 IntStream is2 = IntStream.range(5, 10);
33 show("is2", is2);
34 IntStream is3 = IntStream.rangeClosed(5, 10);
35 show("is3", is3);
36
37 Path path = Path.of("../gutenberg/alice30.txt");
38 var contents = Files.readString(path);
39
40 Stream<String> words =
41 Stream.of(contents.split("\\PL+"));
42 IntStream is4 = words.mapToInt(String::length);
43 show("is4", is4);
44 String sentence = "\uD835\uDD46 is the set of
45 octonions.";
46 System.out.println(sentence);
47 IntStream codes = sentence.codePoints();
48 System.out.println(codes.mapToObj(c -> "%X
49 ".formatted(c)).collect(
50 Collectors.joining()));
51
52 }

```

---

## ***java.util.stream.IntStream 8***

- static IntStream range(int startInclusive,  
int endExclusive)

- `static IntStream rangeClosed(int startInclusive, int endInclusive)`  
yield an IntStream with the integers in the given range.
- `static IntStream of(int... values)`  
yields an IntStream with the given elements.
- `int[] toArray()`  
yields an array with the elements of this stream.
- `int sum()`
- `OptionalDouble average()`
- `OptionalInt max()`
- `OptionalInt min()`
- `IntSummaryStatistics summaryStatistics()`  
yield the sum, count, average, maximum, or minimum of the elements in this stream, or an object from which all four of these values can be obtained.
- `Stream<Integer> boxed()`  
yields a stream of wrapper objects for the elements in this stream.

## ***java.util.stream.LongStream*** 8

- `static LongStream range(long startInclusive, long endExclusive)`
- `static LongStream rangeClosed(long startInclusive, long endInclusive)`  
yield a LongStream with the integers in the given range.

- `static LongStream of(long... values)`  
yields a LongStream with the given elements.
- `long[] toArray()`  
yields an array with the elements of this stream.
  - `long sum()`
  - `OptionalDouble average()`
  - `OptionalLong max()`
  - `OptionalLong min()`
  - `LongSummaryStatistics summaryStatistics()`  
yield the sum, count, average, maximum, or minimum of the elements in this stream, or an object from which all four of these values can be obtained.
- `Stream<Long> boxed()`  
yields a stream of wrapper objects for the elements in this stream.

## ***java.util.stream.DoubleStream 8***

- `static DoubleStream of(double... values)`  
yields a DoubleStream with the given elements.
- `double[] toArray()`  
yields an array with the elements of this stream.
  - `double sum()`
  - `OptionalDouble average()`
  - `OptionalDouble max()`
  - `OptionalDouble min()`

- `DoubleSummaryStatistics summaryStatistics()`  
yields the sum, count, average, maximum, or minimum of the elements in this stream, or an object from which all four of these values can be obtained.
- `Stream<Double> boxed()`  
yields a stream of wrapper objects for the elements in this stream.

## ***java.lang(CharSequence* 1.0)**

- `IntStream codePoints() 8`  
yields a stream of all Unicode code points of this string.

## ***java.util.random.RandomGenerator* 17**

- `IntStream ints()`
- `IntStream ints(int randomNumberOrigin, int randomNumberBound)`
- `IntStream ints(long streamSize)`
- `IntStream ints(long streamSize, int randomNumberOrigin, int randomNumberBound)`
- `LongStream longs()`
- `LongStream longs(long randomNumberOrigin, long randomNumberBound)`
- `LongStream longs(long streamSize)`
- `LongStream longs(long streamSize, long randomNumberOrigin, long randomNumberBound)`
- `DoubleStream doubles()`

- `DoubleStream doubles(double randomNumberOrigin, double randomNumberBound)`
- `DoubleStream doubles(long streamSize)`
- `DoubleStream doubles(long streamSize, double randomNumberOrigin, double randomNumberBound)`

yield streams of random numbers. If `streamSize` is provided, the stream is finite with the given number of elements. When bounds are provided, the elements are between `randomNumberOrigin` (inclusive) and `randomNumberBound` (exclusive).

## **`java.util.Optional(Int|Long|Double)` 8**

- `static Optional(Int|Long|Double) of((int|long|double) value)`  
yields an optional object with the supplied primitive type value.
- `(int|long|double) getAs(Int|Long|Double)()`  
yields the value of this optional object, or throws a `NoSuchElementException` if it is empty.
- `(int|long|double) orElse((int|long|double) other)`  
`(int|long|double) orElseGet((Int|Long|Double)Supplier other)`  
yield the value of this optional object, or the alternative value if this object is empty.
- `void ifPresent((Int|Long|Double)Consumer consumer)`

If this optional object is not empty, passes its value to consumer.

### **java.util.(Int|Long|Double)SummaryStatistics 8**

- long getCount()
- (int|long|double) getSum()
- double getAverage()
- (int|long|double) getMax()
- (int|long|double) getMin()

yield the count, sum, average, maximum, and minimum of the collected elements.

## **1.14 Parallel Streams**

Streams make it easy to parallelize bulk operations. The process is mostly automatic, but you need to follow a few rules. First of all, you must have a parallel stream. You can get a parallel stream from any collection with the `Collection.parallelStream()` method:

[Click here to view code image](#)

```
Stream<String> parallelWords = words.parallelStream();
```

Moreover, the `parallel` method converts any sequential stream into a parallel one.

[Click here to view code image](#)

```
Stream<String> parallelWords = Stream.of(wordArray).parallel();
```

As long as the stream is in parallel mode when the terminal method executes, all intermediate stream operations will be parallelized.

When stream operations run in parallel, the intent is that the same result is returned as if they had run serially. It is important that the operations are *stateless* and can be executed in an arbitrary order.

Here is an example of something you cannot do. Suppose you want to count all short words in a stream of strings:

[Click here to view code image](#)

```
var shortWords = new int[12];
words.parallelStream().forEach(
 s -> { if (s.length() < 12) shortWords[s.length()]++; });
// ERROR--race condition!
System.out.println(Arrays.toString(shortWords));
```

This is very, very bad code. The function passed to `forEach` runs concurrently in multiple threads, each updating a shared array. As you saw in [Chapter 12](#) of Volume I, that's a classic *race condition*. If you run this program multiple times, you are quite likely to get a different sequence of counts in each run—each of them wrong.

It is your responsibility to ensure that any functions you pass to parallel stream operations are safe to execute in parallel. The best way to do that is to stay away from mutable state. In this example, you can safely parallelize the computation if you group strings by length and count them:

[Click here to view code image](#)

```
Map<Integer, Long> shortWordCounts
= words.parallelStream()
.filter(s -> s.length() < 12)
.collect(groupingBy(
 String::length,
 counting()));
```

By default, streams that arise from ordered collections (arrays and lists), from ranges, generators, and iterators, or from calling `Stream.sorted`, are *ordered*. Results are accumulated in the order of the original elements,

and are entirely predictable. If you run the same operations twice, you will get exactly the same results.

Ordering does not preclude efficient parallelization. For example, when computing `stream.map(fun)`, the stream can be partitioned into  $n$  segments, each of which is concurrently processed. Then the results are reassembled in order.

Some operations can be more effectively parallelized when the ordering requirement is dropped. By calling the `Stream.unordered` method, you indicate that you are not interested in ordering. One operation that can benefit from this is `Stream.distinct`. On an ordered stream, `distinct` retains the first of all equal elements. That impedes parallelization—the thread processing a segment can't know which elements to discard until the preceding segment has been processed. If it is acceptable to retain *any* of the unique elements, all segments can be processed concurrently (using a shared set to track duplicates).

You can also speed up the `limit` method by dropping ordering. If you just want any  $n$  elements from a stream and you don't care which ones you get, call

[Click here to view code image](#)

```
Stream<String> sample =
words.parallelStream().unordered().limit(n);
```

As discussed in [Section 1.9, “Collecting into Maps,”](#) on p. 31, merging maps is expensive. For that reason, the `Collectors.groupingByConcurrent` method uses a shared concurrent map. To benefit from parallelism, the order of the map values will not be the same as the stream order.

[Click here to view code image](#)

```
Map<Integer, List<String>> result =
words.parallelStream().collect(
 Collectors.groupingByConcurrent(String::length));
 // Values aren't collected in stream order
```

Of course, you won't care if you use a downstream collector that is independent of the ordering, such as

[Click here to view code image](#)

```
Map<Integer, Long> wordCounts
 = words.parallelStream()
 .collect(
 groupingByConcurrent(
 String::length,
 counting()));
```

Don't turn all your streams into parallel streams in the hope of speeding up operations. Keep these issues in mind:

- There is a substantial overhead to parallelization that will only pay off for very large data sets.
- Parallelizing a stream is only a win if the underlying data source can be effectively split into multiple parts.
- The thread pool that is used by parallel streams can be starved by blocking operations such as file I/O or network access.

Parallel streams work best with huge in-memory collections of data and computationally intensive processing.

---



### Tip

Prior to Java 9, parallelizing the stream returned by the `Files.lines` method made no sense. The data was not splittable—you had to read the first half of the file before the second half. Now the method uses a memory-mapped file, and splitting is effective. If you process the lines of a huge file, parallelizing the stream may improve performance.

---



## Note

By default, parallel streams use the global fork-join pool returned by `ForkJoinPool.commonPool`. That is fine if your operations don't block and you don't share the pool with other tasks. There is a trick to substitute a different pool. Place your operations inside the `submit` method of a custom pool:

[Click here to view code image](#)

```
ForkJoinPool customPool = . . .;
result = customPool.submit(() ->
 stream.parallel().map(. . .).collect(. . .)).get();
```

Or, asynchronously:

[Click here to view code image](#)

```
CompletableFuture.supplyAsync(() ->
 stream.parallel().map(. . .).collect(. . .),
 customPool).thenAccept(result -> . . .);
```

---



## Note

If you want to parallelize stream computations based on random numbers, don't start out with a stream obtained from the `Random.ints`, `Random.longs`, or `Random.doubles` methods. Those streams don't split. Instead, use the `ints`, `longs`, or `doubles` methods of the `SplittableRandom` class.

---

The example program in [Listing 1.8](#) demonstrates how to work with parallel streams.

---

**Listing 1.8** parallel/ParallelStreams.java

---

[Click here to view code image](#)

```
1 package parallel;
2
3 import static java.util.stream.Collectors.*;
4
5 import java.io.*;
6 import java.nio.file.*;
7 import java.util.*;
8 import java.util.stream.*;
9
10 /**
11 * @version 1.02 2019-08-28
12 * @author Cay Horstmann
13 */
14 public class ParallelStreams
15 {
16 public static void main(String[] args) throws IOException
17 {
18 var contents = Files.readString(
19 Path.of("../gutenberg/alice30.txt"));
20 List<String> wordList = List.of(contents.split("\\PL+"));
21
22 // Very bad code ahead
23 var shortWords = new int[10];
24 wordList.parallelStream().forEach(s ->
25 {
26 if (s.length() < 10) shortWords[s.length()]++;
27 });
28 System.out.println(Arrays.toString(shortWords));
29
30 // Try again--the result will likely be different (and
31 // also wrong)
32 Arrays.fill(shortWords, 0);
33 wordList.parallelStream().forEach(s ->
34 {
35 if (s.length() < 10) shortWords[s.length()]++;
36 });
37 }
38 }
```

```

36 System.out.println(Arrays.toString(shortWords));
37
38 // Remedy: Group and count
39 Map<Integer, Long> shortWordCounts =
wordList.parallelStream()
 .filter(s -> s.length() < 10)
 .collect(groupingBy(String::length, counting()));
42
43 System.out.println(shortWordCounts);
44
45 // Downstream order not deterministic
46 Map<Integer, List<String>> result =
wordList.parallelStream().collect(
47 Collectors.groupingByConcurrent(String::length));
48
49 System.out.println(result.get(14));
50
51 result = wordList.parallelStream().collect(
52 Collectors.groupingByConcurrent(String::length));
53
54 System.out.println(result.get(14));
55
56 Map<Integer, Long> wordCounts =
wordList.parallelStream().collect(
57 groupingByConcurrent(String::length, counting()));
58
59 System.out.println(wordCounts);
60 }
61 }
```

---

***java.util.stream.BaseStream<T, S extends  
BaseStream<T, S>> 8***

- S parallel()

yields a parallel stream with the same elements as this stream.

- `S.unordered()`

yields an unordered stream with the same elements as this stream.

### ***java.util.Collection<E> 1.2***

- `Stream<E>.parallelStream()` 8

yields a parallel stream with the elements of this collection.

In this chapter, you have learned how to put the stream library of Java 8 to use. The next chapter covers another important topic: processing input and output.

---

# Chapter 2. Input and Output

---

## In this chapter

- [2.1 Input/Output Streams](#)
- [2.2 Reading and Writing Binary Data](#)
- [2.3 Object Input/Output Streams and Serialization](#)
- [2.4 Working with Files](#)
- [2.5 Memory-Mapped Files](#)
- [2.6 File Locking](#)
- [2.7 Regular Expressions](#)

In this chapter, we cover the Java Application Programming Interfaces (APIs) for input and output. You will learn how to access files and directories and how to read and write data in binary and text format. This chapter also shows you the object serialization mechanism that lets you store objects as easily as you can store text or numeric data. Next, we will turn to working with files and directories. We finish the chapter with a discussion of regular expressions, even though they are not actually related to input and output. We couldn't find a better place to handle that topic, and apparently neither could the Java team—the regular expression API specification was attached to a specification request for “new I/O” features.

## 2.1 Input/Output Streams

In the Java API, an object from which we can read a sequence of bytes is called an *input stream*. An object to which we can write a sequence of bytes is called an *output stream*. These sources and destinations of byte sequences can be—and often are—files, but they can also be network connections and even blocks of memory. The abstract classes `InputStream` and `OutputStream` are the basis for a hierarchy of input/output (I/O) classes.

---



### Note

These input/output streams are unrelated to the streams that you saw in the preceding chapter. For clarity, we will use the terms input stream, output stream, or input/output stream whenever we discuss streams that are used for input and output.

---

Byte-oriented input/output streams are inconvenient for processing information stored in Unicode (recall that Unicode uses multiple bytes per character). Therefore, a separate hierarchy provides classes, inheriting from the abstract `Reader` and `Writer` classes, for processing Unicode characters. These classes have read and write operations that are based on two-byte `char` values (that is, UTF-16 code units) rather than `byte` values.

#### 2.1.1 Reading and Writing Bytes

The `InputStream` class has an abstract method:

```
abstract int read()
```

This method reads one byte and returns the byte that was read, or `-1` if it encounters the end of the input source. The designer of a concrete input stream class overrides this method to provide useful functionality. For example, in the `FileInputStream` class, this method reads one byte from a file. `System.in` is a predefined object of a subclass of `InputStream` that allows you to read information from “standard input,” that is, the console or a redirected file.

The `InputStream` class also has nonabstract methods to read an array of bytes or to skip a number of bytes. Since Java 9, there is a very useful method to read all bytes of a stream:

[Click here to view code image](#)

```
byte[] bytes = in.readAllBytes();
```

There are also methods to read a given number of bytes—see the API notes.

These methods call the abstract `read` method, so subclasses need to override only one method.

Similarly, the `OutputStream` class defines the abstract method

[Click here to view code image](#)

```
abstract void write(int b)
```

which writes one byte to an output location.

If you have an array of bytes, you can write them all at once:

[Click here to view code image](#)

```
byte[] values = . . .;
out.write(values);
```

The `transferTo` method transfers all bytes from an input stream to an output stream:

```
in.transferTo(out);
```

Both the `read` and `write` methods *block* until the byte is actually read or written. This means that if the input stream cannot immediately be accessed (usually because of a busy network connection), the current thread blocks. This gives other threads the chance to do useful work while the method is waiting for the input stream to become available again.

The `available` method lets you check the number of bytes that are currently available for reading. This means a fragment like the following is unlikely to block:

[Click here to view code image](#)

```
int bytesAvailable = in.available();
if (bytesAvailable > 0)
{
 var data = new byte[bytesAvailable];
 in.read(data);
}
```

When you have finished reading or writing to an input/output stream, close it by calling the `close` method. This call frees up the operating system resources that are in limited supply. If an application opens too many input/output streams without closing them, system resources can become depleted. Closing an output stream also *flushes* the buffer used for the output stream: Any bytes that were temporarily placed in a buffer so that they could be delivered as a larger packet are sent off. In particular, if you do not close a file, the last packet of bytes might never be delivered. You can also manually flush the output with the `flush` method.

Even if an input/output stream class provides concrete methods to work with the raw `read` and `write` functions, application programmers rarely use them. The data that you are interested in probably contain numbers, strings, and objects, not raw bytes.

Instead of working with bytes, you can use one of many input/output classes that build upon the basic `InputStream` and `OutputStream` classes.

### **java.io.InputStream 1.0**

- abstract int read()

reads a byte of data and returns the byte read; returns `-1` at the end of the input stream.

- `int read(byte[] b)`

reads into an array of bytes and returns the actual number of bytes read, or `-1` at the end of the input stream; this method reads at most `b.length` bytes.

- `int read(byte[] b, int off, int len)`
- `int readNBytes(byte[] b, int off, int len)` 9

read up to `len` bytes, if available without blocking (`read`), or blocking until all values have been read (`readNBytes`). Values are placed into `b`, starting at `off`. Returns the actual number of bytes read, or `-1` at the end of the input stream.

- `byte[] readAllBytes()` 9

yields an array of all bytes that can be read from this stream.

- `long transferTo(OutputStream out)` 9

transfers all bytes from this input stream to the given output stream, returning the number of bytes transferred. Neither stream is closed.

- `long skip(long n)`

attempts to skip `n` bytes in the input stream, returns the actual number of bytes skipped (which, for any reason, may be less than `n`).

- `long skipNBytes(long n)` 12

skips `n` bytes in the input stream, returns the actual number of bytes skipped (which may be less than `n` if the end of the input stream was encountered).

- `int available()`

returns the number of bytes available, without blocking (recall that blocking means that the current thread loses its turn).

- `void close()`  
closes the input stream.
- `void mark(int readlimit)`  
puts a marker at the current position in the input stream (not all streams support this feature). If more than `readlimit` bytes have been read from the input stream, the stream is allowed to forget the marker.
- `void reset()`  
returns to the last marker. Subsequent calls to `read` reread the bytes. If there is no current marker, the input stream is not reset.
- `boolean markSupported()`  
returns `true` if the input stream supports marking.
- `static InputStream nullInputStream()` 11  
returns an input stream with no bytes.


## **java.io.OutputStream 1.0**

- `abstract void write(int n)`  
writes a byte of data.
- `void write(byte[] b)`
- `void write(byte[] b, int off, int len)`  
write all bytes, or `len` bytes starting at `off`, in the array `b`.


- `void close()`  
flushes and closes the output stream.
- `void flush()`  
flushes the output stream—that is, sends any buffered data to its destination.
- `static OutputStream nullOutputStream()` 11  
returns an output stream that discards all bytes.

## 2.1.2 The Complete Stream Zoo

Unlike C, which gets by just fine with a single type `FILE*`, Java has a whole zoo of more than 60 (!) different input/output stream types (see [Figures 2.1](#) and [2.2](#)).



**Figure 2.1** Input and output stream hierarchy



**Figure 2.2** Reader and writer hierarchy

Let's divide the animals in the input/output stream zoo by how they are used. There are separate hierarchies for classes that process bytes and characters. As you saw, the `InputStream` and `OutputStream` classes let you read and write individual bytes and arrays of bytes. These classes form the basis of the hierarchy shown in [Figure 2.1](#). To read and write strings and numbers, you need more capable subclasses. For example,

`DataInputStream` and `DataOutputStream` let you read and write all the primitive Java types in binary format. Finally, there are input/output streams that do useful stuff; for example, the `ZipInputStream` and `ZipOutputStream` let you read and write files in the familiar ZIP compression format.

For Unicode text, on the other hand, you can use subclasses of the abstract classes `Reader` and `Writer` (see [Figure 2.2](#)). The basic methods of the `Reader` and `Writer` classes are similar to those of `InputStream` and `OutputStream`.

```
abstract int read()
abstract void write(int c)
```

The `read` method returns either a UTF-16 code unit (as an integer between 0 and 65535) or -1 when you have reached the end of the file. The `write` method is called with a Unicode code unit. (See Volume I, [Chapter 3](#) for a discussion of Unicode code units.)

There are four additional interfaces: `Closeable`, `Flushable`, `Readable`, and `Appendable` (see [Figure 2.3](#)). The first two interfaces are very simple, with methods


[Click here to view code image](#)

```
void close() throws IOException
```

and

```
void flush()
```

respectively. The classes `InputStream`, `OutputStream`, `Reader`, and `Writer` all implement the `Closeable` interface.



**Figure 2.3** The `Closeable`, `Flushable`, `Readable`, and `Appendable` interfaces



## Note

The `java.io.Closeable` interface extends the `java.lang.AutoCloseable` interface. Therefore, you can use the `try-with-resources` statement with any `Closeable`. Why have two interfaces? The `close` method of the `Closeable` interface only throws an `IOException`, whereas the `AutoCloseable.close` method may throw any exception.

---

Output Stream and Writer implement the Flushable interface.

The `Readable` interface has a single method

```
int read(CharBuffer cb)
```

The `CharBuffer` class has methods for sequential and random read/write access. It represents an in-memory buffer or a memory-mapped file. (See [Section 2.5.2, “The Buffer Data Structure,”](#) on p. 139 for details.)

The `Appendable` interface has two methods for appending single characters and character sequences:

[Click here to view code image](#)

```
Appendable append(char c)
Appendable append(CharSequence s)
```

The `CharSequence` interface describes basic properties of a sequence of `char` values. It is implemented by `String`, `CharBuffer`, `StringBuilder`, and `StringBuffer`.

Of the input/output stream classes, only `Writer` implements `Appendable`.

#### **`java.io.Closeable` 5.0**

- `void close()`  
closes this `Closeable`. This method may throw an `IOException`.

#### **`java.io.Flushable` 5.0**

- `void flush()`  
flushes this `Flushable`.

## ***java.lang.Readable*** 5.0

- int read(CharBuffer cb)

attempts to read as many char values into cb as it can hold. Returns the number of values read, or -1 if no further values are available from this Readable.

## ***java.lang.Appendable*** 5.0

- Appendable append(char c)
- Appendable append(CharSequence cs)

append the given code unit, or all code units in the given sequence, to this Appendable; return this.

## ***java.lang.CharSequence*** 1.4

- char charAt(int index)  
returns the code unit at the given index.
- int length()  
returns the number of code units in this sequence.
- CharSequence subSequence(int startIndex, int endIndex)

returns a CharSequence consisting of the code units stored from index startIndex to endIndex - 1.

- String `toString()`

returns a string consisting of the code units of this sequence.

### 2.1.3 Combining Input/Output Stream Filters

`FileInputStream` and `FileOutputStream` give you input and output streams attached to a disk file. You need to pass the file name or full path name of the file to the constructor. For example,

[Click here to view code image](#)

```
var fin = new FileInputStream("employee.dat");
```

looks in the user directory for a file named `employee.dat`.



#### Tip

All the classes in `java.io` interpret relative path names as starting from the user's working directory. You can get this directory by a call to `System.getProperty("user.dir")`.

---

---



#### Caution

Since the backslash character is the escape character in Java strings, be sure to use `\\" for Windows-style path names (for example, C:\\Windows\\win.ini). In Windows, you can also use a single forward slash (C:/Windows/win.ini) because most Windows file-handling system calls will interpret forward slashes as file separators. However, this is not`

recommended—the behavior of the Windows system functions is subject to change. Instead, for portable programs, use the file separator character for the platform on which your program runs. It is available as the constant string `java.io.File.separator`.

---

Like the abstract `InputStream` and `OutputStream` classes, these classes only support reading and writing at the byte level. That is, we can only read bytes and byte arrays from the object `fin`.

[Click here to view code image](#)

```
byte b = (byte) fin.read();
```

As you will see in the next section, if we just had a `DataInputStream`, we could read numeric types:

[Click here to view code image](#)

```
DataInputStream din = . . .;
double x = din.readDouble();
```

But just as the `FileInputStream` has no methods to read numeric types, the `DataInputStream` has no method to get data from a file.

Java uses a clever mechanism to separate two kinds of responsibilities. Some input streams (such as the `FileInputStream` and the input stream returned by the `openStream` method of the `URL` class) can retrieve bytes from files and other more exotic locations. Other input streams (such as the `DataInputStream`) can assemble bytes into more useful data types. The Java programmer has to combine the two. For example, to be able to read numbers from a file, first create a `FileInputStream` and then pass it to the constructor of a `DataInputStream`.

[Click here to view code image](#)

```
var fin = new FileInputStream("employee.dat");
var din = new DataInputStream(fin);
double x = din.readDouble();
```

If you look at [Figure 2.1](#) again, you can see the classes `FilterInputStream` and `FilterOutputStream`. The subclasses of these classes are used to add capabilities to input/output streams that process bytes.

You can add multiple capabilities by nesting the filters. For example, by default, input streams are not buffered. That is, every call to `read` asks the operating system to dole out yet another byte. It is more efficient to request blocks of data instead and store them in a buffer. If you want buffering *and* the data input methods for a file, use the following rather monstrous sequence of constructors:

[Click here to view code image](#)

```
var din = new DataInputStream(
 new BufferedInputStream(
 new FileInputStream("employee.dat")));
```

Notice that we put the `DataInputStream` *last* in the chain of constructors because we want to use the `DataInputStream` methods, and we want *them* to use the buffered `read` method.

Sometimes you'll need to keep track of the intermediate input streams when chaining them together. For example, when reading input, you often need to peek at the next byte to see if it is the value that you expect. Java provides the `PushbackInputStream` for this purpose.

[Click here to view code image](#)

```
var pbin = new PushbackInputStream(
 new BufferedInputStream(
 new FileInputStream("employee.dat")));
```

Now you can speculatively read the next byte

```
int b = pbin.read();
```

and throw it back if it isn't what you wanted.

```
if (b != '<') pbin.unread(b);
```

However, reading and unread are the *only* methods that apply to a pushback input stream. If you want to look ahead and also read numbers, then you need both a pushback input stream and a data input stream reference.


[Click here to view code image](#)

```
var pbin = new PushbackInputStream(
 new BufferedInputStream(
 new FileInputStream("employee.dat")));
var din = new DataInputStream(pbin);
```

Of course, in the input/output libraries of other programming languages, niceties such as buffering and lookahead are automatically taken care of—so it is a bit of a hassle to resort, in Java, to combining stream filters. However, the ability to mix and match filter classes to construct useful sequences of input/output streams does give you an immense amount of flexibility. For example, you can read numbers from a compressed ZIP file by using the following sequence of input streams (see [Figure 2.4](#)):

[Click here to view code image](#)

```
var zin = new ZipInputStream(new
 FileInputStream("employee.zip"));
var din = new DataInputStream(zin);
```



**Figure 2.4** A sequence of filtered input streams

(See [Section 2.2.3, “ZIP Archives,”](#) on p. 85 for more on Java’s handling of ZIP files.)

#### **java.io.FileInputStream 1.0**

- `FileInputStream(String name)`
- `FileInputStream(File file)`

create a new file input stream using the file whose path name is specified by the name string or the `file` object. (The `File` class is described at the end of this chapter.) Path names that are not absolute are resolved relative to the working directory that was set when the VM started.

#### **java.io.FileOutputStream 1.0**

- `FileOutputStream(String name)`
- `FileOutputStream(String name, boolean append)`
- `FileOutputStream(File file)`
- `FileOutputStream(File file, boolean append)`

create a new file output stream specified by the name string or the `file` object. (The `File` class is described at the end of this chapter.) If the `append` parameter is `true`, an existing file with the same name will not be deleted and data will be added at the end of the file. Otherwise, this method deletes any existing file with the same name.

## **`java.io.BufferedInputStream` 1.0**

- `BufferedInputStream(InputStream in)`

creates a buffered input stream. A buffered input stream reads bytes from a stream without causing a device access every time. When the buffer is empty, a new block of data is read into the buffer.

## **`java.io.BufferedOutputStream` 1.0**

- `BufferedOutputStream(OutputStream out)`

creates a buffered output stream. A buffered output stream collects bytes to be written without causing a device access every time. When the buffer fills up or when the stream is flushed, the data are written.

## **java.io.PushbackInputStream 1.0**

- PushbackInputStream(InputStream in)
- PushbackInputStream(InputStream in, int size)

construct an input stream with one-byte lookahead or a pushback buffer of specified size.

- void unread(int b)

pushes back a byte, which is retrieved again by the next call to read.

### **2.1.4 Text Input and Output**

When saving data, you have the choice between binary and text formats. For example, if the integer 1234 is saved in binary, it is written as the sequence of bytes 00 00 04 D2 (in hexadecimal notation). In text format, it is saved as the string "1234". Although binary I/O is fast and efficient, it is not easily readable by humans. We first discuss text I/O and cover binary I/O in [Section 2.2, “Reading and Writing Binary Data,”](#) on p. [78](#).

When saving text strings, you need to consider the *character encoding*. In the UTF-16 encoding that Java uses internally, the string "José" is encoded as 00 4A 00 6F 00 73 00 E9 (in hex). However, many programs expect that text files use a different encoding. In UTF-8, the encoding most commonly used on the Internet, the string would be written as 4A 6F 73 C3 A9, without the zero bytes for the first three letters and with two bytes for the é character.

The `OutputStreamWriter` class turns an output stream of Unicode code units into a stream of bytes, using a chosen character encoding. Conversely, the `InputStreamReader` class turns an input stream that

contains bytes (specifying characters in some character encoding) into a reader that emits Unicode code units.

For example, here is how you make an input reader that reads keystrokes from the console and converts them to Unicode:

[Click here to view code image](#)

```
var in = new InputStreamReader(System.in);
```

This input stream reader assumes the default character encoding used by the host system. On desktop operating systems, that can be an archaic encoding such as Windows 1252 or MacRoman. You should always choose a specific encoding in the constructor for the `InputStreamReader`, for example:

[Click here to view code image](#)

```
var in = new InputStreamReader(new FileInputStream("data.txt"),
StandardCharsets.UTF_8);
```

See [Section 2.1.8, “Character Encodings,”](#) on p. [75](#) for more information on character encodings.

The `Reader` and `Writer` classes have only basic methods to read and write individual characters. As with streams, you use subclasses for processing strings and numbers.

## 2.1.5 How to Write Text Output

For text output, use a `PrintWriter`. That class has methods to print strings and numbers in text format. In order to print to a file, construct a `PrintStream` from a file name and a character encoding:

[Click here to view code image](#)

```
var out = new PrintWriter("employee.txt",
StandardCharsets.UTF_8);
```

To write to a print writer, use the same `print`, `println`, and `printf` methods that you used with `System.out`. You can use these methods to

print numbers (int, short, long, float, double), characters, boolean values, strings, and objects.

For example, consider this code:

[Click here to view code image](#)

```
String name = "Harry Hacker";
double salary = 75000;
out.print(name);
out.print(' ');
out.println(salary);
```

This writes the characters

```
Harry Hacker 75000.0
```

to the writer `out`. The characters are then converted to bytes and end up in the file `employee.txt`.

The `println` method adds the correct end-of-line character for the target system ("\r\n" on Windows, "\n" on UNIX) to the line. This is the string obtained by the call `System.getProperty("line.separator")`.

If the writer is set to *autoflush mode*, all characters in the buffer are sent to their destination whenever `println` is called. (Print writers are always buffered.) By default, autoflushing is *not* enabled. You can enable or disable autoflushing by using the `PrintWriter(Writer writer, boolean autoFlush)` constructor:

[Click here to view code image](#)

```
var out = new PrintWriter(
 new OutputStreamWriter(
 new FileOutputStream("employee.txt"),
 StandardCharsets.UTF_8),
 true); // autoflush
```

The print methods don't throw exceptions. You can call the checkError method to see if something went wrong with the output stream.

---



## Note

Java veterans might wonder whatever happened to the PrintStream class and to System.out. In Java 1.0, the PrintStream class simply truncated all Unicode characters to ASCII characters by dropping the top byte. (At the time, Unicode was still a 16-bit encoding.) Clearly, that was not a clean or portable approach, and it was fixed with the introduction of readers and writers in Java 1.1. For compatibility with existing code, System.in, System.out, and System.err are still input/output streams, not readers and writers. But now the PrintStream class internally converts Unicode characters to the default host encoding in the same way the PrintWriter does. Objects of type PrintStream act exactly like print writers when you use the print and println methods, but unlike print writers they allow you to output raw bytes with the write(int) and write(byte[]) methods.

---

### **java.io.PrintWriter 1.1**

- PrintWriter(OutputStream out)
- PrintWriter(Writer writer)  
    create a new PrintWriter that writes to the given writer.
- PrintWriter(String filename, String encoding)
- PrintWriter(File file, String encoding)

create a new `PrintWriter` that writes to the given file, using the given character encoding.

- `void print(Object obj)`  
prints an object by printing the string resulting from `toString`.
- `void print(String s)`  
prints a string containing Unicode code units.
- `void println(String s)`  
prints a string followed by a line terminator. Flushes the output stream if it is in autoflush mode.
- `void print(char[] s)`  
prints all Unicode code units in the given array.
- `void print(char c)`  
prints a Unicode code unit.
- `void print(int i)`
- `void print(long l)`
- `void print(float f)`
- `void print(double d)`
- `void print(boolean b)`  
print the given value in text format.
- `void printf(String format, Object... args)`  
prints the given values as specified by the format string. See Volume I, [Chapter 3](#) for the specification of the format string.
- `boolean checkError()`

returns `true` if a formatting or output error occurred. Once the output stream has encountered an error, it is tainted and all calls to `checkError` return `true`.

## 2.1.6 How to Read Text Input

The easiest way to process arbitrary text is the `Scanner` class that we used extensively in Volume I. You can construct a `Scanner` from any input stream.

Alternatively, you can read a short text file into a string like this:

[Click here to view code image](#)

```
String content = Files.readString(path, charset);
```

But if you want the file as a sequence of lines, call

[Click here to view code image](#)

```
List<String> lines = Files.readAllLines(path, charset);
```

If the file is large, process the lines lazily as a `Stream<String>`:

[Click here to view code image](#)

```
try (Stream<String> lines = Files.lines(path, charset))
{
 . . .
}
```

You can also use a scanner to read *tokens*—strings that are separated by a delimiter. The default delimiter is whitespace. You can change the delimiter to any regular expression. For example,

[Click here to view code image](#)

```
Scanner in = . . .;
in.useDelimiter("\PL+");
```

accepts any non-Unicode letters as delimiters. The scanner then accepts tokens consisting only of Unicode letters.

Calling the `next` method yields the next token:

[Click here to view code image](#)

```
while (in.hasNext())
{
 String word = in.next();
 . . .
}
```

Alternatively, you can obtain a stream of all tokens as

[Click here to view code image](#)

```
Stream<String> words = in.tokens();
```

In early versions of Java, the only game in town for processing text input was the `BufferedReader` class. Its `readLine` method yields a line of text, or `null` when no more input is available. A typical input loop looks like this:

[Click here to view code image](#)

```
InputStream inputStream = . . .;
try (var in = new BufferedReader(new
InputStreamReader(inputStream, charset)))
{
 boolean done = false;
 while (!done)
 {
 String line = in.readLine();
 if (line == null) done = true;
 else
 {
 do something with line
 }
 }
}
```

```
 }
}
```

Nowadays, the `BufferedReader` class also has a `lines` method that yields a `Stream<String>`. However, unlike a `Scanner`, a `BufferedReader` has no methods for reading numbers.

## 2.1.7 Saving Objects in Text Format

In this section, we discuss an example program that stores an array of `Employee` records in a text file. Each record is stored in a separate line. Instance fields are separated from each other by delimiters. A vertical bar (|) is used as a delimiter. (A colon (:) is another popular choice. Part of the fun is that everyone uses a different delimiter.) Naturally, we punt on the issue of what might happen if a | actually occurs in one of the strings we save.

Here is a sample set of records:

[Click here to view code image](#)

```
Harry Hacker|35500|1989-10-01
Carl Cracker|75000|1987-12-15
Tony Tester|38000|1990-03-15
```

Writing records is simple. Since we write to a text file, we use the `PrintWriter` class. We simply write all fields, followed by either a | or, for the last field, a newline character. This work is done in the following `writeData` method that we add to our `Employee` class:

[Click here to view code image](#)

```
public static void writeEmployee(PrintWriter out, Employee e)
{
 out.println(e.getName() + " | " + e.getSalary() + " | " +
 e.getHireDay());
}
```

To read records, we read in a line at a time and separate the fields. We use a scanner to read each line and then split the line into tokens with the `String.split` method.

[Click here to view code image](#)

```
public static Employee readEmployee(Scanner in)
{
 String line = in.nextLine();
 String[] tokens = line.split("\\\\|");
 String name = tokens[0];
 double salary = Double.parseDouble(tokens[1]);
 LocalDate hireDate = LocalDate.parse(tokens[2]);
 int year = hireDate.getYear();
 int month = hireDate.getMonthValue();
 int day = hireDate.getDayOfMonth();
 return new Employee(name, salary, year, month, day);
}
```

The parameter of the `split` method is a regular expression describing the separator. We discuss regular expressions in more detail at the end of this chapter. As it happens, the vertical bar character has a special meaning in regular expressions, so it needs to be escaped with a `\` character. That character needs to be escaped by another `\`, yielding the "`\\\\|`" expression.

The complete program is in [Listing 2.1](#). The static method

[Click here to view code image](#)

```
void writeData(Employee[] e, PrintWriter out)
```

first writes the length of the array, then writes each record. The static method

[Click here to view code image](#)

```
Employee[] readData(Scanner in)
```

first reads in the length of the array, then reads in each record. This turns out to be a bit tricky:

[Click here to view code image](#)

```
int n = in.nextInt();
in.nextLine(); // consume newline
var employees = new Employee[n];
for (int i = 0; i < n; i++)
{
 employees[i] = new Employee();
 employees[i].readData(in);
}
```

The call to `nextInt` reads the array length but not the trailing newline character. We must consume the newline so that the `readData` method can get the next input line when it calls the `nextLine` method.

---

### **Listing 2.1** `textFile/TextFileTest.java`

---

[Click here to view code image](#)

```
1 package textFile;
2
3 import java.io.*;
4 import java.nio.charset.*;
5 import java.time.*;
6 import java.util.*;
7
8 /**
9 * @version 1.15 2018-03-17
10 * @author Cay Horstmann
11 */
12 public class TextFileTest
13 {
14 public static void main(String[] args) throws IOException
15 {
16 var staff = new Employee[3];
17
18 staff[0] = new Employee("Carl Cracker", 75000, 1987, 12,
19);
```

```
19 staff[1] = new Employee("Harry Hacker", 50000, 1989, 10,
20);
21
22 // save all employee records to the file employee.dat
23 try (var out = new PrintWriter("employee.dat",
24 StandardCharsets.UTF_8))
25 {
26 writeData(staff, out);
27 }
28
29 // retrieve all records into a new array
30 try (var in = new Scanner(
31 new FileInputStream("employee.dat"), "UTF_8"))
32 {
33 Employee[] newStaff = readData(in);
34
35 // print the newly read employee records
36 for (Employee e : newStaff)
37 System.out.println(e);
38 }
39
40 /**
41 * Writes all employees in an array to a print writer
42 * @param employees an array of employees
43 * @param out a print writer
44 */
45 private static void writeData(Employee[] employees,
PrintWriter out)
46 throws IOException
47 {
48 // write number of employees
49 out.println(employees.length);
50
51 for (Employee e : employees)
52 writeEmployee(out, e);
```

```
53 }
54
55 /**
56 * Reads an array of employees from a scanner
57 * @param in the scanner
58 * @return the array of employees
59 */
60 private static Employee[] readData(Scanner in)
61 {
62 // retrieve the array size
63 int n = in.nextInt();
64 in.nextLine(); // consume newline
65
66 var employees = new Employee[n];
67 for (int i = 0; i < n; i++)
68 {
69 employees[i] = readEmployee(in);
70 }
71 return employees;
72 }
73
74 /**
75 * Writes employee data to a print writer
76 * @param out the print writer
77 */
78 public static void writeEmployee(PrintWriter out, Employee
e)
79 {
80 out.println(e.getName() + "|" + e.getSalary() + "|" +
e.getHireDay());
81 }
82
83 /**
84 * Reads employee data from a buffered reader
85 * @param in the scanner
86 */
87 public static Employee readEmployee(Scanner in)
88 {
```

```

89 String line = in.nextLine();
90 String[] tokens = line.split("\\\\|");
91 String name = tokens[0];
92 double salary = Double.parseDouble(tokens[1]);
93 LocalDate hireDate = LocalDate.parse(tokens[2]);
94 int year = hireDate.getYear();
95 int month = hireDate.getMonthValue();
96 int day = hireDate.getDayOfMonth();
97 return new Employee(name, salary, year, month, day);
98 }
99 }
```

---

## 2.1.8 Character Encodings

Input and output streams are for sequences of bytes, but in many cases you will work with texts—that is, sequences of characters. It then matters how characters are encoded into bytes.

Java uses the Unicode standard for characters. Each character, or “code point,” has a 21-bit integer number. There are different *character encodings*—methods for packaging those 21-bit numbers into bytes.

The most common encoding is UTF-8, which encodes each Unicode code point into a sequence of one to four bytes (see [Table 2.1](#)). UTF-8 has the advantage that the characters of the traditional ASCII character set, which contains all characters used in English, only take up one byte each.

**Table 2.1** UTF-8 Encoding

| Character Range | Encoding                                                                                                                                                                                                                                                         |
|-----------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 0 . . . 7F      | 0a <sub>6</sub> a <sub>5</sub> a <sub>4</sub> a <sub>3</sub> a <sub>2</sub> a <sub>1</sub> a <sub>0</sub>                                                                                                                                                        |
| 80 . . . 7FF    | 110a <sub>10</sub> a <sub>9</sub> a <sub>8</sub> a <sub>7</sub> a <sub>6</sub> 10a <sub>5</sub> a <sub>4</sub> a <sub>3</sub> a <sub>2</sub> a <sub>1</sub> a <sub>0</sub>                                                                                       |
| 800 . . . FFFF  | 1110a <sub>15</sub> a <sub>14</sub> a <sub>13</sub> a <sub>12</sub> 10a <sub>11</sub> a <sub>10</sub> a <sub>9</sub> a <sub>8</sub> a <sub>7</sub> a <sub>6</sub><br>10a <sub>5</sub> a <sub>4</sub> a <sub>3</sub> a <sub>2</sub> a <sub>1</sub> a <sub>0</sub> |

| Character Range | Encoding                                                                                                                                                                                  |
|-----------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 10000. .        | 11110a <sub>20</sub> a <sub>19</sub> a <sub>18</sub> 10a <sub>17</sub> a <sub>16</sub> a <sub>15</sub> a <sub>14</sub> a <sub>13</sub> a <sub>12</sub>                                    |
| .10FFFF         | 10a <sub>11</sub> a <sub>10</sub> a <sub>9</sub> a <sub>8</sub> a <sub>7</sub> a <sub>6</sub> 10a <sub>5</sub> a <sub>4</sub> a <sub>3</sub> a <sub>2</sub> a <sub>1</sub> a <sub>0</sub> |

Another common encoding is UTF-16, which encodes each Unicode code point into one or two 16-bit values (see [Table 2.2](#)). This is the encoding used in Java strings. Actually, there are two forms of UTF-16, called “big-endian” and “little-endian.” Consider the 16-bit value 0x2122. In the big-endian format, the more significant byte comes first: 0x21 followed by 0x22. In the little-endian format, it is the other way around: 0x22 0x21. To indicate which of the two is used, a file can start with the “byte order mark,” the 16-bit quantity 0xFEFF. A reader can use this value to determine the byte order and then discard it.

**Table 2.2** UTF-16 Encoding

| Character Range | Encoding                                                                                                                                                                                                                                              |
|-----------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 0. . . .FFFF    | a <sub>15</sub> a <sub>14</sub> a <sub>13</sub> a <sub>12</sub> a <sub>11</sub> a <sub>10</sub> a <sub>9</sub> a <sub>8</sub> a <sub>7</sub> a <sub>6</sub> a <sub>5</sub> a <sub>4</sub> a <sub>3</sub> a <sub>2</sub> a <sub>1</sub> a <sub>0</sub> |
|                 | 110110b <sub>19</sub> b <sub>18</sub> b <sub>17</sub> b <sub>16</sub> a <sub>15</sub> a <sub>14</sub> a <sub>13</sub> a <sub>12</sub> a <sub>11</sub> a <sub>10</sub>                                                                                 |
| 10000. .        | 110111a <sub>9</sub> a <sub>8</sub> a <sub>7</sub> a <sub>6</sub> a <sub>5</sub> a <sub>4</sub> a <sub>3</sub> a <sub>2</sub> a <sub>1</sub> a <sub>0</sub>                                                                                           |
| .10FFFF         |                                                                                                                                                                                                                                                       |

where  $b_{19}b_{18}b_{17}b_{16} = a_{20}a_{19}a_{18}a_{17}a_{16} - 1$



## Caution

Some programs, including Microsoft Notepad, add a byte order mark at the beginning of UTF-8 encoded files. Clearly, this is unnecessary since there are no byte ordering issues in UTF-8. But the Unicode standard allows it, and even suggests that it’s a pretty good idea since it leaves little doubt about the encoding. It is

supposed to be removed when reading a UTF-8 encoded file. Sadly, Java does not do that, and bug reports against this issue are closed as “will not fix.” Your best bet is to strip out any leading \uFEFF that you find in your input.

---

In addition to the UTF encodings, there are partial encodings that cover a character range suitable for a given user population. For example, ISO 8859-1 is a one-byte code that includes accented characters used in Western European languages. Shift-JIS is a variable-length code for Japanese characters. A large number of these encodings are still in widespread use.

There is no reliable way to automatically detect the character encoding from a stream of bytes. Some API methods let you use the “default charset”—the character encoding preferred by the operating system of the computer. Is that the same encoding that is used by your source of bytes? These bytes may well originate from a different part of the world. Therefore, you should always explicitly specify the encoding. For example, when reading a web page, check the Content-Type header.

---



## Note

The platform encoding is returned by the static method `Charset.defaultCharset` as well as the system property `native.encoding`. If you use the `Console` class for user interaction, invoke its `charset` method to find the console character set.

The static method `Charset.availableCharsets` returns all available `Charset` instances, as a map from canonical names to `Charset` objects.

---



## Caution

The Oracle implementation of Java has a system property `file.encoding` for overriding the platform default. This is not an officially supported property, and it is not consistently followed by all parts of Oracle's implementation of the Java library. You should not set it.

---

The `StandardCharsets` class has static variables of type `Charset` for the character encodings that every Java virtual machine must support:

[Click here to view code image](#)

```
StandardCharsets.UTF_8
StandardCharsets.UTF_16
StandardCharsets.UTF_16BE
StandardCharsets.UTF_16LE
StandardCharsets.ISO_8859_1
StandardCharsets.US_ASCII
```

To obtain the `Charset` for another encoding, use the static `forName` method:

[Click here to view code image](#)

```
Charset shiftJIS = Charset.forName("Shift-JIS");
```

Use the `Charset` object when reading or writing text. For example, you can turn an array of bytes into a string as

[Click here to view code image](#)

```
var str = new String(bytes, StandardCharsets.UTF_8);
```



### Tip

As of Java 10, all methods in the `java.io` package allow you to specify a character encoding with a `Charset` object or a string.

---

---

Choose the `StandardCharsets` constants, so that any spelling errors are caught at compile time.

---



### Caution

Some methods (such as the `String(byte[])` constructor) use the default platform encoding if you don't specify any; others (such as `Files.readAllLines`) use UTF-8.

---



### Note

Beyond Java 17, UTF-8 will become the JDK default, no matter what the platform encoding is. Until this happy event, be sure to specify `StandardCharsets.UTF_8` for all character encodings—unless you know that you need a different encoding which you then have to specify explicitly.

---

## 2.2 Reading and Writing Binary Data

Text format is convenient for testing and debugging because it is humanly readable, but it is not as efficient as transmitting data in binary format. In the following sections, you will learn how to perform input and output with binary data.

### 2.2.1 The `DataInput` and `DataOutput` Interfaces

The `DataOutput` interface defines the following methods for writing a number, a character, a boolean value, or a string in binary format:

|                         |                          |
|-------------------------|--------------------------|
| <code>writeChars</code> | <code>writeFloat</code>  |
| <code>writeByte</code>  | <code>writeDouble</code> |

|            |              |
|------------|--------------|
| writeInt   | writeChar    |
| writeShort | writeBoolean |
| writeLong  | writeUTF     |

For example, `writeInt` always writes an integer as a 4-byte binary quantity regardless of the number of digits, and `writeDouble` always writes a `double` as an 8-byte binary quantity. The resulting output is not human-readable, but it will use the same space for each value of a given type and reading it back in will be faster than parsing text.

---



### Note

There are two different methods of storing integers and floating-point numbers in memory, depending on the processor you are using. Suppose, for example, you are working with a 4-byte `int`, such as the decimal number 1234, or 4D2 in hexadecimal ( $1234 = 4 \times 256 + 13 \times 16 + 2$ ). This value can be stored in such a way that the first of the four bytes in memory holds the most significant byte (MSB) of the value: 00 00 04 D2. This is the so-called big-endian method. Or, we can start with the least significant byte (LSB) first: D2 04 00 00. This is called, naturally enough, the little-endian method. For example, the SPARC uses big-endian; the Pentium, little-endian. This can lead to problems. When a file is saved from C or C++ file, the data are saved exactly as the processor stores them. That makes it challenging to move even the simplest data files from one platform to another. In Java, all values are written in the big-endian fashion, regardless of the processor. That makes Java data files platform-independent.

---

The `writeUTF` method writes string data using a modified version of the 8-bit Unicode Transformation Format. Instead of simply using the standard UTF-8 encoding, sequences of Unicode code units are first represented in UTF-16, and then the result is encoded using the UTF-8 rules. This modified encoding is different for characters with codes higher than

`0xFFFF`. It is used for backward compatibility with virtual machines that were built when Unicode had not yet grown beyond 16 bits.

Since nobody else uses this modification of UTF-8, you should only use the `writeUTF` method to write strings intended for a Java virtual machine—for example, in a program that generates bytecodes. Use the `writeChars` method for other purposes.

To read the data back in, use the following methods defined in the `DataInput` interface:

[Click here to view code image](#)

|                        |                          |
|------------------------|--------------------------|
| <code>readInt</code>   | <code>readDouble</code>  |
| <code>readShort</code> | <code>readChar</code>    |
| <code>readLong</code>  | <code>readBoolean</code> |
| <code>readFloat</code> | <code>readUTF</code>     |

The `DataInputStream` class implements the `DataInput` interface. To read binary data from a file, combine a `DataInputStream` with a source of bytes such as a `FileInputStream`:

[Click here to view code image](#)

```
var in = new DataInputStream(new
FileInputStream("employee.dat"));
```

Similarly, to write binary data, use the `DataOutputStream` class that implements the `DataOutput` interface:

[Click here to view code image](#)

```
var out = new DataOutputStream(new
FileOutputStream("employee.dat"));
```

## ***java.io.DataInput 1.0***

- `boolean readBoolean()`

- `byte readByte()`
  - `char readChar()`
  - `double readDouble()`
  - `float readFloat()`
  - `int readInt()`
  - `long readLong()`
  - `short readShort()`
- read in a value of the given type.
- `void readFully(byte[] b)`  
reads bytes into the array `b`, blocking until all bytes are read.
  - `void readFully(byte[] b, int off, int len)`  
places up to `len` bytes into the array `b`, starting at `off`, blocking until all bytes are read.
  - `String readUTF()`  
reads a string of characters in the “modified UTF-8” format.
  - `int skipBytes(int n)`  
skips `n` bytes, blocking until all bytes are skipped.

## ***java.io.DataOutput 1.0***

- `void writeBoolean(boolean b)`
- `void writeByte(int b)`
- `void writeChar(int c)`
- `void writeDouble(double d)`

- void writeFloat(float f)
  - void writeInt(int i)
  - void writeLong(long l)
  - void writeShort(int s)
- write a value of the given type.
- void writeChars(String s)
- writes all characters in the string.
- void writeUTF(String s)
- writes a string of characters in the “modified UTF-8” format.

## 2.2.2 Random-Access Files

The `RandomAccessFile` class lets you read or write data anywhere in a file. Disk files are random-access, but input/output streams that communicate with a network socket are not. You can open a random-access file either for reading only or for both reading and writing; specify the option by using the string "`r`" (for read access) or "`rw`" (for read/write access) as the second argument in the constructor.

[Click here to view code image](#)

```
var in = new RandomAccessFile("employee.dat", "r");
var inOut = new RandomAccessFile("employee.dat", "rw");
```

When you open an existing file as a `RandomAccessFile`, it does not get deleted.

A random-access file has a *file pointer* that indicates the position of the next byte to be read or written. The `seek` method can be used to set the file pointer to an arbitrary byte position within the file. The argument to `seek` is a `long` integer between zero and the length of the file in bytes.

The `getFilePointer` method returns the current position of the file pointer.

The `RandomAccessFile` class implements both the `DataInput` and `DataOutput` interfaces. To read and write from a random-access file, use methods such as `readInt/writeInt` and `readChar/writeChar` that we discussed in the preceding section.

Let's walk through an example program that stores employee records in a random-access file. Each record will have the same size. This makes it easy to read an arbitrary record. Suppose you want to position the file pointer to the third record. Simply set the file pointer to the appropriate byte position and start reading.

[Click here to view code image](#)

```
long n = 3;
in.seek((n - 1) * RECORD_SIZE);
var e = new Employee();
e.readData(in);
```

If you want to modify the record and save it back into the same location, remember to set the file pointer back to the beginning of the record:

[Click here to view code image](#)

```
in.seek((n - 1) * RECORD_SIZE);
e.writeData(out);
```

To determine the total number of bytes in a file, use the `length` method. The total number of records is the length divided by the size of each record.

[Click here to view code image](#)

```
long nbytes = in.length(); // length in bytes
int nrecords = (int) (nbytes / RECORD_SIZE);
```

Integers and floating-point values have a fixed size in binary format, but we have to work harder for strings. We provide two helper methods to write and read strings of a fixed size.

The `writeFixedString` writes the specified number of code units, starting at the beginning of the string. If there are too few code units, the method pads the string, using zero values.

[Click here to view code image](#)

```
public static void writeFixedString(String s, int size,
DataOutput out)
 throws IOException
{
 for (int i = 0; i < size; i++)
 {
 char ch = 0;
 if (i < s.length()) ch = s.charAt(i);
 out.writeChar(ch);
 }
}
```

The `readFixedString` method reads characters from the input stream until it has consumed `size` code units or until it encounters a character with a zero value. Then, it skips past the remaining zero values in the input field. For added efficiency, this method uses the `StringBuilder` class to read in a string.

[Click here to view code image](#)

```
public static String readFixedString(int size, DataInput in)
 throws IOException
{
 var b = new StringBuilder(size);
 int i = 0;
 var done = false;
 while (!done && i < size)
 {
 char ch = in.readChar();
 i++;
 if (ch == 0) done = true;
 else b.append(ch);
 }
}
```

```

 in.skipBytes(2 * (size - i));
 return b.toString();
 }
}

```

We placed the `writeFixedString` and `readFixedString` methods inside the `DataIO` helper class.

To write a fixed-size record, we simply write all fields in binary.

[Click here to view code image](#)

```

DataIO.writeFixedString(e.getName(), Employee.NAME_SIZE, out);
out.writeDouble(e.getSalary());
LocalDate hireDay = e.getHireDay();
out.writeInt(hireDay.getYear());
out.writeInt(hireDay.getMonthValue());
out.writeInt(hireDay.getDayOfMonth());

```

Reading the data back is just as simple.

[Click here to view code image](#)

```

String name = DataIO.readFixedString(Employee.NAME_SIZE, in);
double salary = in.readDouble();
int y = in.readInt();
int m = in.readInt();
int d = in.readInt();

```

Let us compute the size of each record. We will use 40 characters for the name strings. Therefore, each record will contain 100 bytes:

- 40 characters = 80 bytes for the name
- 1 double = 8 bytes for the salary
- 3 int = 12 bytes for the date

The program shown in [Listing 2.2](#) writes three records into a data file and then reads them from the file in reverse order. To do this efficiently requires random access—we need to get to the last record first.

---

**Listing 2.2** randomAccess/RandomAccessTest.java

---

[Click here to view code image](#)

```
1 package randomAccess;
2
3 import java.io.*;
4 import java.time.*;
5
6 /**
7 * @version 1.14 2018-05-01
8 * @author Cay Horstmann
9 */
10 public class RandomAccessTest
11 {
12 public static void main(String[] args) throws IOException
13 {
14 var staff = new Employee[3];
15
16 staff[0] = new Employee("Carl Cracker", 75000, 1987,
12, 15);
17 staff[1] = new Employee("Harry Hacker", 50000, 1989,
10, 1);
18 staff[2] = new Employee("Tony Tester", 40000, 1990, 3,
15);
19
20 try (var out = new DataOutputStream(new
FileOutputStream("employee.dat")))
21 {
22 // save all employee records to the file
employee.dat
23 for (Employee e : staff)
24 writeData(out, e);
25 }
26
27 try (var in = new RandomAccessFile("employee.dat",
"r"))
28 {
```

```
29 // retrieve all records into a new array
30
31 // compute the array size
32 int n = (int)(in.length() / Employee.RECORD_SIZE);
33 var newStaff = new Employee[n];
34
35 // read employees in reverse order
36 for (int i = n - 1; i >= 0; i--)
37 {
38 newStaff[i] = new Employee();
39 in.seek(i * Employee.RECORD_SIZE);
40 newStaff[i] = readData(in);
41 }
42
43 // print the newly read employee records
44 for (Employee e : newStaff)
45 System.out.println(e);
46 }
47 }
48
49 /**
50 * Writes employee data to a data output
51 * @param out the data output
52 * @param e the employee
53 */
54 public static void writeData(DataOutput out, Employee e)
throws IOException
55 {
56 DataIO.writeFixedString(e.getName(),
Employee.NAME_SIZE, out);
57 out.writeDouble(e.getSalary());
58
59 LocalDate hireDay = e.getHireDay();
60 out.writeInt(hireDay.getYear());
61 out.writeInt(hireDay.getMonthValue());
62 out.writeInt(hireDay.getDayOfMonth());
63 }
64
```

```

65 /**
66 * Reads employee data from a data input
67 * @param in the data input
68 * @return the employee
69 */
70 public static Employee readData(DataInput in) throws
71 IOException
71 {
72 String name =
73 DataIO.readFixedString(Employee.NAME_SIZE, in);
73 double salary = in.readDouble();
74 int y = in.readInt();
75 int m = in.readInt();
76 int d = in.readInt();
77 return new Employee(name, salary, y, m - 1, d);
78 }
79 }

```

---

## **java.io.RandomAccessFile 1.0**

- `RandomAccessFile(String file, String mode)`
- `RandomAccessFile(File file, String mode)`

open the given file for random access. The mode string is "r" for read-only mode, "rw" for read/write mode, "rws" for read/write mode with synchronous disk writes of data and metadata for every update, and "rwd" for read/write mode with synchronous disk writes of data only.

- `long getFilePointer()`  
returns the current location of the file pointer.
- `void seek(long pos)`  
sets the file pointer to pos bytes from the beginning of the file.

- `long length()`  
returns the length of the file in bytes.

### 2.2.3 ZIP Archives

ZIP archives store one or more files in a (usually) compressed format. Each ZIP archive has a header with information such as the name of each file and the compression method that was used. In Java, you can use a `ZipInputStream` to read a ZIP archive. You need to look at the individual *entries* in the archive. The `getNextEntry` method returns an object of type `ZipEntry` that describes the entry. Read from the stream until the end, which is actually the end of the current entry. Then call `closeEntry` to read the next entry. Do not close `zin` until you read the last entry. Here is a typical code sequence to read through a ZIP file:

[Click here to view code image](#)

```
var zin = new ZipInputStream(new FileInputStream(zipname));
boolean done = false;
while (!done)
{
 ZipEntry entry = zin.getNextEntry();
 if (entry == null) done = true;
 else
 {
 read the contents of zin
 zin.closeEntry();
 }
}
zin.close();
```

To write a ZIP file, use a `ZipOutputStream`. For each entry that you want to place into the ZIP file, create a `ZipEntry` object. Pass the file name to the `ZipEntry` constructor; it sets the other parameters such as file date and decompression method. You can override these settings if you like.

Then, call the `putNextEntry` method of the `ZipOutputStream` to begin writing a new file. Send the file data to the ZIP output stream. When done, call `closeEntry`. Repeat for all the files you want to store. Here is a code skeleton:

[Click here to view code image](#)

```
var fout = new FileOutputStream("test.zip");
var zout = new ZipOutputStream(fout);
for all files
{
 var ze = new ZipEntry(filename);
 zout.putNextEntry(ze);
 send data to zout
 zout.closeEntry();
}
zout.close();
```

---



## Note

JAR files (which were discussed in Volume I, [Chapter 4](#)) are simply ZIP files with a special entry—the so-called manifest. Use the `JarInputStream` and `JarOutputStream` classes to read and write the manifest entry.

---

ZIP input streams are a good example of the power of the stream abstraction. When you read data stored in compressed form, you don't need to worry that the data are being decompressed as they are being requested. Moreover, the source of the bytes in a ZIP stream need not be a file—the ZIP data can come from a network connection.

---



## Note

[Section 2.4.8, “ZIP File Systems,”](#) on p. 130 shows how to access a ZIP archive without a special API, using the `FileSystem`

class of Java 7.

---

### **java.util.zip.ZipInputStream 1.1**

- `ZipInputStream(InputStream in)`  
creates a ZipInputStream that allows you to inflate data from the given InputStream.
- `ZipEntry getNextEntry()`  
returns a ZipEntry object for the next entry, or null if there are no more entries.
- `void closeEntry()`  
closes the current open entry in the ZIP file. You can then read the next entry by using `getNextEntry()`.

### **java.util.zip.ZipOutputStream 1.1**

- `ZipOutputStream(OutputStream out)`  
creates a ZipOutputStream that you can use to write compressed data to the specified OutputStream.
- `void putNextEntry(ZipEntry ze)`  
writes the information in the given ZipEntry to the output stream and positions the stream for the data. The data can then be written by calling the `write()` method.
- `void closeEntry()`

closes the currently open entry in the ZIP file. Use the putNextEntry method to start the next entry.

- `void setLevel(int level)`

sets the default compression level of subsequent DEFLATED entries to a value from Deflater.NO\_COMPRESSION to Deflater.BEST\_COMPRESSION. The default value is Deflater.DEFAULT\_COMPRESSION. Throws an IllegalArgumentException if the level is not valid.

- `void setMethod(int method)`

sets the default compression method for this ZipOutputStream for any entries that do not specify a method; can be either DEFLATED or STORED.

## **`java.util.zip.ZipEntry` 1.1**

- `ZipEntry(String name)`

constructs a ZIP entry with a given name.

- `long getCrc()`

returns the CRC32 checksum value for this ZipEntry.

- `String getName()`

returns the name of this entry.

- `long getSize()`

returns the uncompressed size of this entry, or -1 if the uncompressed size is not known.

- `boolean isDirectory()`

returns true if this entry is a directory.

- `void setMethod(int method)`

sets the compression method for the entry to DEFLATED or STORED.

- `void setSize(long size)`

sets the size of this entry. Only required if the compression method is STORED.

- `void setCrc(long crc)`

sets the CRC32 checksum of this entry. Use the CRC32 class to compute this checksum. Only required if the compression method is STORED.

## **`java.util.zip.ZipFile` 1.1**

- `ZipFile(String name)`

- `ZipFile(File file)`

create a ZipFile for reading from the given string or File object.

- `Enumeration entries()`

returns an Enumeration object that enumerates the ZipEntry objects that describe the entries of the ZipFile.

- `ZipEntry getEntry(String name)`

returns the entry corresponding to the given name, or null if there is no such entry.

- `InputStream getInputStream(ZipEntry ze)`

returns an `InputStream` for the given entry.

- `String getName()`

returns the path of this ZIP file.

## 2.3 Object Input/Output Streams and Serialization

Using a fixed-length record format is a good choice if you need to store data of the same type. However, objects that you create in an object-oriented program are rarely all of the same type. For example, you might have an array called `staff` that is nominally an array of `Employee` records but contains objects that are actually instances of a subclass such as `Manager`.

It is certainly possible to come up with a data format that allows you to store such polymorphic collections—but, fortunately, we don’t have to. The Java language supports a very general mechanism, called *object serialization*, that makes it possible to write any object to an output stream and read it again later. (You will see in this chapter where the term “serialization” comes from.)

### 2.3.1 Saving and Loading Serializable Objects

To save object data, you first need to open an `ObjectOutputStream` object:

[Click here to view code image](#)

```
var out = new ObjectOutputStream(new
FileOutputStream("employee.dat"));
```

Now, to save an object, simply use the `writeObject` method of the `ObjectOutputStream` class as in the following fragment:

[Click here to view code image](#)

```
var harry = new Employee("Harry Hacker", 50000, 1989, 10, 1);
var boss = new Manager("Carl Cracker", 80000, 1987, 12, 15);
out.writeObject(harry);
out.writeObject(boss);
```

To read the objects back in, first get an `ObjectInputStream` object:

[Click here to view code image](#)

```
var in = new ObjectInputStream(new
FileInputStream("employee.dat"));
```

Then, retrieve the objects in the same order in which they were written, using the `readObject` method:

[Click here to view code image](#)

```
var e1 = (Employee) in.readObject();
var e2 = (Employee) in.readObject();
```

There is, however, one change you need to make to any class that you want to save to an output stream and restore from an object input stream. The class must implement the `Serializable` interface:

[Click here to view code image](#)

```
class Employee implements Serializable { . . . }
```

The `Serializable` interface has no methods, so you don't need to change your classes in any way. In this regard, it is similar to the `Cloneable` interface that we discussed in Volume I, [Chapter 6](#). However, to make a class cloneable, you still had to override the `clone` method of the `Object` class. To make a class serializable, you do not need to do anything else.



**Note**

You can write and read only *objects* with the `writeObject/readObject` methods. For primitive type values, use methods such as `writeInt/readInt` or `writeDouble/readDouble`. (The object input/output stream classes implement the `DataInput/DataOutput` interfaces.)

---

Behind the scenes, an `ObjectOutputStream` looks at all the fields of the objects and saves their contents. For example, when writing an `Employee` object, the name, date, and salary fields are written to the output stream.

However, there is one important situation to consider: What happens when one object is shared by several objects as part of their state?

To illustrate the problem, let us make a slight modification to the `Manager` class. Let's assume that each manager has a secretary:


[Click here to view code image](#)

```
class Manager extends Employee
{
 private Employee secretary;
 . .
}
```

Each `Manager` object now contains a reference to an `Employee` object that describes the secretary. Of course, two managers can share the same secretary, as is the case in [Figure 2.5](#) and the following code:

[Click here to view code image](#)

```
var harry = new Employee("Harry Hacker", . . .);
var carl = new Manager("Carl Cracker", . . .);
carl.setSecretary(harry);
var tony = new Manager("Tony Tester", . . .);
tony.setSecretary(harry);
```




**Figure 2.5** Two managers can share a mutual employee.

Saving such a network of objects is a challenge. Of course, we cannot save and restore the memory addresses for the secretary objects. When an object is reloaded, it will likely occupy a completely different memory address than it originally did.

Instead, each object is saved with the *serial number*—hence the name *object serialization* for this mechanism. Here is the algorithm:

1. Associate a serial number with each object reference that you encounter (as shown in [Figure 2.6](#)).
2. When encountering an object reference for the first time, save the object data to the output stream.

3. If it has been saved previously, just write “same as the previously saved object with serial number  $x$ .”



**Figure 2.6** An example of object serialization

When reading the objects back, the procedure is reversed.

1. When an object is specified in an object input stream for the first time, construct it, initialize it with the stream data, and remember the association between the serial number and the object reference.

- When the tag “same as the previously saved object with serial number *x*” is encountered, retrieve the object reference for the sequence number.
- 



### Note

In this chapter, we will use serialization to save a collection of objects to a disk file and retrieve it exactly as we stored it. Another very important application is the transmittal of a collection of objects across a network connection to another computer. Just as raw memory addresses are meaningless in a file, they are also meaningless when you communicate with a different processor. By replacing memory addresses with serial numbers, serialization permits the transport of object collections from one machine to another.

---

---



### Caution

As you will see in the following section, the object stream contains the names of the classes, superclasses, and fields of all serialized objects. For inner classes, some of these names are synthesized by the compiler, and the naming convention may change from one compiler to another. If that occurs, deserialization fails. Therefore, you need to be cautious with serializing inner classes.

Static inner classes, including inner enumerations and records, are safe to serialize.

---

[Listing 2.3](#) is a program that saves and reloads a network of Employee and Manager objects (some of which share the same employee as a secretary). Note that the secretary object is unique after reloading—when newStaff[1] gets a raise, that is reflected in the secretary fields of the managers.

---

**Listing 2.3** serial/ObjectStreamTest.java

---

[Click here to view code image](#)

```
1 package serial;
2
3 import java.io.*;
4
5 /**
6 * @version 1.12 2021-09-10
7 * @author Cay Horstmann
8 */
9 class ObjectStreamTest
10 {
11 public static void main(String[] args) throws IOException,
12 ClassNotFoundException
13 {
14 var harry = new Employee("Harry Hacker", 50000, 1989,
15, 1);
16 var carl = new Manager("Carl Cracker", 80000, 1987, 12,
17);
18 carl.setSecretary(harry);
19 var tony = new Manager("Tony Tester", 40000, 1990, 3,
20);
21 tony.setSecretary(harry);
22
23 var staff = new Employee[3];
24
25 staff[0] = carl;
26 staff[1] = harry;
27 staff[2] = tony;
28
29 // save all employee records to the file employee.ser
30 try (var out = new ObjectOutputStream(new
31 FileOutputStream("employee.ser")))
32 {
33 out.writeObject(staff);
34 }
```

```
30
31 try (var in = new ObjectInputStream(new
32 FileInputStream("employee.ser")))
33 {
34 // retrieve all records into a new array
35 var newStaff = (Employee[]) in.readObject();
36
37 // raise secretary's salary
38 newStaff[1].raiseSalary(10);
39
40 // print the newly read employee records
41 for (Employee e : newStaff)
42 System.out.println(e);
43 }
44 }
45 }
```

---

### **java.io.ObjectOutputStream 1.1**

- `ObjectOutputStream(OutputStream out)`  
creates an `ObjectOutputStream` so you can write objects to the specified `OutputStream`.
- `void writeObject(Object obj)`  
writes the specified object to the `ObjectOutputStream`. This method saves the class of the object, the signature of the class, and the values of any nonstatic, nontransient fields of the class and its superclasses.

### **java.io.ObjectInputStream 1.1**

- `ObjectInputStream(InputStream in)`  
creates an `ObjectInputStream` to read back object information from the specified `InputStream`.
- `Object readObject()`  
reads an object from the `ObjectInputStream`. In particular, this method reads back the class of the object, the signature of the class, and the values of the nontransient and nonstatic fields of the class and all its superclasses. It does deserializing so that multiple object references can be recovered.

### 2.3.2 Understanding the Object Serialization File Format

Object serialization saves object data in a particular file format. Of course, you can use the `writeObject/readObject` methods without having to know the exact sequence of bytes that represents objects in a file. Nonetheless, we found studying the data format extremely helpful for gaining insight into the object serialization process. As the details are somewhat technical, feel free to skip this section if you are not interested in the implementation.

Every file begins with the two-byte “magic number”

AC ED

followed by the version number of the object serialization format, which is currently

00 05

(We use hexadecimal numbers throughout this section to denote bytes.) Then, it contains a sequence of objects, in the order in which they were saved.

String objects are saved as

- 72
- Two-byte length
- Characters in the “modified UTF-8” format

For example, the string “Harry” is saved as

```
74 00 05 Harry
```

When an object is saved, the class of that object must be saved as well. The class descriptor has the following format:

- 72
- 2-byte length of class name
- Class name
- 8-byte fingerprint
- 1-byte flag
- 2-byte count of instance field descriptors
- Instance field descriptors
- 78 (end marker)
- Superclass descriptor (70 if none)

The fingerprint is obtained by ordering the descriptions of the class, superclass, interfaces, field types, and method signatures in a canonical way, and then applying the Secure Hash Algorithm version 1 (SHA-1) to that data.

SHA-1 gives a “fingerprint” of a block of information. This fingerprint is always a 20-byte data packet, regardless of the size of the original data. It is created by a clever sequence of bit operations on the data that makes it extremely likely that the fingerprint will change if the information is altered in any way. The serialization mechanism uses only the first eight bytes of the SHA-1 code as a class fingerprint. It is still very likely that the class fingerprint will change if the instance fields or methods change.

When reading an object, its fingerprint is compared against the current fingerprint of the class. If they don't match, it means the class definition has changed after the object was written, and an exception is generated. Of course, in practice, classes do evolve, and it might be necessary for a program to read in older versions of objects. We will discuss this in [Section 2.3.5, “Versioning,”](#) on p. 107.

The flag byte is composed of the bit masks, defined in `java.io.ObjectStreamConstants`, shown in [Table 2.3](#).

**Table 2.3** Bit Masks

| Name              | Value | Description                                                  |
|-------------------|-------|--------------------------------------------------------------|
| SC_WRITE_METHOD   | 1     | Class defines <code>writeObject</code> method.               |
| SC_SERIALIZABLE   | 2     | Class implements <code>Serializable</code> .                 |
| SC_EXTERNALIZABLE | 4     | Class implements <code>Externalizable</code> .               |
| SC_BLOCK_DATA     | 8     | Opaque data written as “block data” (default since JDK 1.2). |
| SC_ENUM           | 16    | Class is an enumeration.                                     |

The classes that we write implement the `Serializable` interface and will have a flag value of 02. The serializable `java.util.Date` class defines its own `readObject/writeObject` methods and has a flag of 03. We discuss the `Externalizable` interface later in this chapter.

Each instance field descriptor has the format:

- 1-byte type code
- 2-byte length of field name
- Field name
- Class name (if the field is an object)

The type code is one of the following:

|   |         |
|---|---------|
| B | byte    |
| C | char    |
| D | double  |
| F | float   |
| I | int     |
| J | long    |
| L | object  |
| S | short   |
| Z | boolean |
| [ | array   |

When the type code is L, the field name is followed by the field type. Class and field name strings do not start with the string code 74, but field types do. Field types use a slightly different encoding of their names—namely, the format used by native methods.

For example, the salary field of the Employee class is encoded as

```
D 00 06 salary
```

Here is the complete class descriptor of the Employee class, contained in the serial package in our example program:

```
72 00 0F
serial.Employee
74 1E C8 E6 C3 F8 B8 Fingerprint and flags
77 02
00 03 Number of instance fields
D 00 06 salary Instance field type and name
L 00 07 hireDay Instance field type and name
74 00 10 Instance field class name:
```

|                    |                              |
|--------------------|------------------------------|
| Ljava/util/Date;   | java.util.Date               |
| L 00 04 name       | Instance field type and name |
| 74 00 12           | Instance field class name:   |
| Ljava/lang/String; | java.lang.String             |
| 78                 | End marker                   |
| 70                 | No superclass                |

These descriptors are fairly long. If the *same* class descriptor is needed again in the file, an abbreviated form is used:

- 71
- 4-byte serial number

The serial number refers to the previous explicit class descriptor. We discuss the numbering scheme later.

An object is stored as

- 73
- Class descriptor
- Object data

For example, here is how the instance fields of an Employee object are stored:

|                                     |                                     |
|-------------------------------------|-------------------------------------|
| 40 E8 6A 00 00 00 00 00             | salary field value:<br>double       |
| 73                                  | hireDay field value: new<br>object  |
| 71 00 7E 00 08                      | Existing class<br>java.util.Date    |
| 77 08 00 00 00 91 19 97<br>3D 80 78 | External storage (details<br>later) |
| 74 00 0C Harry Hacker               | name field value: String            |

As you can see, the data file contains enough information to restore the `Employee` object. (In this example, we store the hireday as a `Date` instead of a `LocalDate`, since the `LocalDate` class has a more complex serialization.)

Arrays are saved in the following format:

- 75
- Class descriptor
- 4-byte number of elements
- Elements

The array class name in the class descriptor is in the same format as that used by native methods (which is slightly different from the format used by class names in other class descriptors). In this format, class names start with an L and end with a semicolon.

For example, an array of three `Employee` objects starts out like this:

|                      |                                      |
|----------------------|--------------------------------------|
| 75                   | Array                                |
| 72 00 0B [LEmployee; | New class, string length, class name |
| Employee [ ]         |                                      |
| 40 05 D6 7E 3B       | Fingerprint and flags                |
| BB F2 50 02          |                                      |
| 00 00                | Number of instance fields            |
| 78                   | End marker                           |
| 70                   | No superclass                        |
| 00 00 00 03          | Number of array entries              |

Note that the fingerprint for an array of `Employee` objects is different from a fingerprint of the `Employee` class itself.

All objects (including arrays and strings) and all class descriptors are given serial numbers as they are saved in the output file. The numbers start at 00 7E 00 00.

We already saw that a full class descriptor for any given class occurs only once. Subsequent descriptors refer to it. For example, in our previous example, a repeated reference to the Date class was coded as

```
71 00 7E 00 08
```

The same mechanism is used for objects. If a reference to a previously saved object is written, it is saved in exactly the same way—that is, 71 followed by the serial number. It is always clear from the context whether a particular serial reference denotes a class descriptor or an object.

Some classes (such as the Date class) store object state in an opaque binary block, encoded as

- 77 (short block) or 7A (long block)
- 1-byte or 4-byte block length
- Block contents
- 78

Finally, a null reference is stored as

```
70
```

Here is the commented output of the ObjectStreamTest program of the preceding section. Run the program, look at a hex dump of its data file employee.ser, and compare it with the commented listing. The most important lines are toward the end of the output. They show a reference to a previously saved object.

|                    |                                      |
|--------------------|--------------------------------------|
| AC ED 00 05        | File header                          |
| 75                 | Array staff (serial #1)              |
| 72 00 12           | New class, string length, class name |
| [Lserial.Employee; | Employee [] (serial #0)              |
| 40 05 D6 7E 3B BB  | Fingerprint and flags                |
| F2 50 02           |                                      |

|                                    |                                                                 |
|------------------------------------|-----------------------------------------------------------------|
| 00 00                              | Number of instance fields                                       |
| 78                                 | End marker                                                      |
| 70                                 | No superclass                                                   |
| 00 00 00 03                        | Number of array entries                                         |
| 73                                 | staff[0]—new object (serial #7)                                 |
| 72 00 0E<br>serial.Manager         | New class, string length, class name<br>(serial #2)             |
| 2F FF 1F 1D E8 7A<br>A9 74 02      | Fingerprint and flags                                           |
| 00 01                              | Number of instance fields                                       |
| L 00 09 secretary                  | Instance field type and name                                    |
| 74 00 11<br>Lserial/Employee;      | Instance field class name: String<br>(serial #3)                |
| 78                                 | End marker                                                      |
| 72 00 0F<br>serial.Employee        | Superclass: new class, string length,<br>class name (serial #4) |
| 74 1E C8 E6 C3 F8<br>B8 77 02      | Fingerprint and flags                                           |
| 00 03                              | Number of instance fields                                       |
| D 00 06 salary                     | Instance field type and name                                    |
| L 00 07 hireDay                    | Instance field type and name                                    |
| 74 00 10<br>Ljava/util/Date;       | Instance field class name: String<br>(serial #5)                |
| L 00 04 name                       | Instance field type and name                                    |
| 74 00 12<br>Ljava/lang/String<br>; | Instance field class name: String<br>(serial #6)                |
| 78                                 | End marker                                                      |
| 70                                 | No superclass                                                   |
| 40 F3 88 00 00 00                  | salary field value: double                                      |

00 00

73                   hireDay field value: new object  
(serial #9)

72 00 0E           New class, string length, class name  
java.util.Date     (serial #8)

68 6A 81 01 4B 59  
74 19 03           Fingerprint and flags

00 00              No instance fields

78                  End marker

70                  No superclass

77 08              External storage, number of bytes

00 00 00 83 E7 4B  
7D 80              Opaque bytes

78                  End marker

74 00 0C Carl     name field value: String (serial #10)  
Cracker

73                  secretary field value: new object  
(serial #11)

71 00 7E 00 04   existing class (use serial #4)

40 E8 6A 00 00 00  
00 00              salary field value: double

73                  hireDay field value: new object  
(serial #12)

71 00 7E 00 08   Existing class (use serial #8)

77 08              External storage, number of bytes

00 00 00 91 19 97  
3D 80              Opaque bytes

78                  End marker

74 00 0C Harry    name field value: String (serial #13)  
Hacker

71 00 7E 00 0B    staff[1]: existing object (use serial

|                   |                                                            |
|-------------------|------------------------------------------------------------|
|                   | #11)                                                       |
| 73                | staff[2]: new object (serial #14)                          |
| 71 00 7E 00 02    | Existing class (use serial #2)                             |
| 40 E3 88 00 00 00 | salary field value: double                                 |
| 00 00             |                                                            |
| 73                | hireDay field value: new object<br>(serial #15)            |
| 71 00 7E 00 08    | Existing class (use serial #8)                             |
| 77 08             | External storage, number of bytes                          |
| 00 00 00 94 6B 50 |                                                            |
| 89 80             | Opaque bytes                                               |
| 78                | End marker                                                 |
| 74 00 0B Tony     |                                                            |
| Tester            | name field value: String (serial #16)                      |
| 71 00 7E 00 0B    | secretary field value: existing object<br>(use serial #11) |

Of course, studying these codes can be about as exciting as reading a phone book. It is not important to know the exact file format (unless you are trying to create an evil effect by modifying the data), but it is still instructive to know that the serialized format has a detailed description of all the objects it contains, with sufficient detail to allow reconstruction of both objects and arrays of objects.

What you should remember is this:

- The serialized format contains the types and instance fields of all objects.
- Each object is assigned a serial number.
- Repeated occurrences of the same object are stored as references to that serial number.

### 2.3.3 Modifying the Default Serialization Mechanism

Certain instance fields should never be serialized—for example, values that store handles to files or windows that are only meaningful to native methods. Such information is guaranteed to be useless when you reload an object at a later time or transport it to a different machine. Also, it is quite common for objects to store cached values for efficiency. There is no need to save those. Java has an easy mechanism to prevent fields from ever being serialized: Mark them with the keyword `transient`. You also need to tag fields as `transient` if they belong to nonserializable classes. Transient fields are always skipped when objects are serialized.

---



### Note

If the superclass of a serializable class is not serializable, it must have an accessible no-argument constructor. Consider this example:

[Click here to view code image](#)

```
class Person // Not serializable
class Employee extends Person implements Serializable
```

When an `Employee` object is deserialized, its instance fields are read from the object input stream, but the `Person` instance fields are set by the `Person` constructor.

---

The serialization mechanism provides a way for individual classes to customize default read and write behavior. A serializable class can define methods with the signature

[Click here to view code image](#)

```
@Serial private void readObject(ObjectInputStream in)
throws IOException, ClassNotFoundException;
@Serial private void writeObject(ObjectOutputStream out)
throws IOException;
```

Then, the instance fields are no longer automatically serialized—these methods are called instead.

Note the `@Serial` annotation. The methods for tweaking serialization don't belong to interfaces. Therefore, you can't use the `@Override` annotation to have the compiler check the method declarations. The `@Serial` annotation is meant to enable the same checking for serialization methods. Up to Java 17, the `javac` compiler doesn't do such checking, but that might change in the future. The IntelliJ IDE uses the annotation.

Here is a typical example for customization. A number of classes in the `java.awt.geom` package, such as `Point2D.Double`, are not serializable. Now, suppose you want to serialize a class `LabeledPoint` that stores a `String` and a `Point2D.Double`. First, you need to mark the `Point2D.Double` field as `transient` to avoid a `NotSerializableException`.

[Click here to view code image](#)

```
public class LabeledPoint implements Serializable
{
 private String label;
 private transient Point2D.Double point;
 . . .
}
```

In the `writeObject` method, first write the object descriptor and the `String` field, `label`, by calling the `defaultWriteObject` method. This is a special method of the `ObjectOutputStream` class that can only be called from within a `writeObject` method of a serializable class. Then we write the point coordinates, using the standard `DataOutput` calls.

[Click here to view code image](#)

```
private void writeObject(ObjectOutputStream out) throws
IOException
{
 out.defaultWriteObject();
 out.writeDouble(point.getX());
 out.writeDouble(point.getY());
}
```

In the `readObject` method, we reverse the process:

[Click here to view code image](#)

```
private void readObject(ObjectInputStream in)
 throws IOException, ClassNotFoundException
{
 in.defaultReadObject();
 double x = in.readDouble();
 double y = in.readDouble();
 point = new Point2D.Double(x, y);
}
```

Another example is the `HashSet` class that supplies its own `readObject` and `writeObject` methods. Instead of saving the internal structure of the hash table, the `writeObject` method simply saves the capacity, load factor, size, and elements. The `readObject` method reads back the capacity and load factor, constructs a new table, and inserts the elements.

The `readObject` and `writeObject` methods only need to save and load their data. They do not concern themselves with superclass data or any other class information.

The `Date` class uses this approach. Its `writeObject` method saves the milliseconds since the “epoch” (January 1, 1970). The data structure that caches calendar data is not saved. For that reason, the serialized `Date` instances in [Section 2.3.2, “Understanding the Object Serialization File Format,”](#) on p. 94 consist of an opaque data block.

---



## Caution

Just like a constructor, the `readObject` method operates on partially initialized objects. If you call a non-final method inside `readObject` that is overridden in a subclass, it may access uninitialized data.



## Note

If a serializable class defines a field

[Click here to view code image](#)

```
@Serial private static final ObjectStreamField[]
serialPersistentFields
```

then serialization uses those field descriptors instead of the non-transient non-static fields. There is also an API for setting the field values before serialization, or reading them after deserialization. This is useful for preserving a legacy layout after a class has evolved. For example, the `BigDecimal` class uses this mechanism to serialize its instances in a format that no longer reflects the instance fields.

---

Instead of letting the serialization mechanism save and restore object data, a class can define its own mechanism. To do this, a class must implement the `Externalizable` interface. This, in turn, requires it to define two methods:

[Click here to view code image](#)

```
public void readExternal(ObjectInput in) throws IOException,
ClassNotFoundException;
public void writeExternal(ObjectOutput out) throws IOException;
```

Unlike the `readObject` and `writeObject` methods, these methods are fully responsible for saving and restoring the entire object, *including the superclass data*. When writing an object, the serialization mechanism merely records the class of the object in the output stream. When reading an externalizable object, the object input stream creates an object with the no-argument constructor and then calls the `readExternal` method.

You can encrypt the data or use a format that is more efficient than the serialization format.

In this example, the `LabeledPixel` class extends the serializable `Point` class, but it takes over the serialization of the class and superclass. The fields of the object are not stored in the standard serialization format. Instead, the data are placed in an opaque block.

[Click here to view code image](#)

```
public class LabeledPixel extends Point implements
Externalizable
{
 private String label;

 public LabeledPixel() {} // required for externalizable
class

 public void writeExternal(ObjectOutput out) throws
IOException
 {
 out.writeInt((int) getX());
 out.writeInt((int) getY());
 out.writeUTF(label);
 }

 public void readExternal(ObjectInput in)
 throws IOException, ClassNotFoundException
 {
 int x = in.readInt();
 int y = in.readInt();
 setLocation(x, y);
 label = in.readUTF();
 }
 . . .
}
```



## Caution

Unlike the `readObject` and `writeObject` methods, which are private and can only be called by the serialization mechanism, the `readExternal` and `writeExternal` methods are public. In particular, `readExternal` potentially permits modification of the state of an existing object.

---

---



### Note

You cannot customize the serialization of enumerations and records. If you define `readObject/writeObject` or `readExternal/writeExternal` methods, they are not used for serialization.

---

#### 2.3.4 The `readResolve` and `writeReplace` Methods

You have to pay particular attention to serializing and deserializing objects whose identity matters. This happens when you are implementing singletons or classes with a limited number of instances.

If you use the `enum` construct of the Java language, you need not worry about serialization—it just works. However, suppose you maintain legacy code that contains an enumerated type such as

[Click here to view code image](#)

```
public class Orientation
{
 public static final Orientation HORIZONTAL = new
Orientation(1);
 public static final Orientation VERTICAL = new
Orientation(2);

 private int value;
```

```
private Orientation(int v)
{
 value = v;
}
```

This idiom was common before enumerations were added to the Java language. Note that the constructor is private. Thus, no objects can be created beyond `Orientation.HORIZONTAL` and `Orientation.VERTICAL`. In particular, you can use the `==` operator to test for object equality:

[Click here to view code image](#)

```
if (orientation == Orientation.HORIZONTAL) . . .
```

The default serialization mechanism is not appropriate. Suppose we write a value of type `Orientation` and read it in again:

[Click here to view code image](#)

```
Orientation original = Orientation.HORIZONTAL;
ObjectOutputStream out = . . .;
out.writeObject(original);
out.close();
ObjectInputStream in = . . .;
var saved = (Orientation) in.read();
```

Now the test

[Click here to view code image](#)

```
if (saved == Orientation.HORIZONTAL) . . .
```

will fail. In fact, the `saved` value is a completely new object of the `Orientation` type that is not equal to any of the predefined constants. Even though the constructor is private, the serialization mechanism can create new objects!

You can solve this problem with another special serialization method, called `readResolve`. If the `readResolve` method is defined, it is called after the object is deserialized. It must return an object which then becomes the return value of the `readObject` method. In our case, the `readResolve` method will inspect the `value` field and return the appropriate enumerated constant:

[Click here to view code image](#)

```
@Serial private Object readResolve() throws
ObjectStreamException
{
 if (value == 1) return Orientation.HORIZONTAL;
 else if (value == 2) return Orientation.VERTICAL;
 else throw new ObjectStreamException(); // this shouldn't
happen
}
```

---



### Tip

With a singleton class, you also have to be careful that deserialization doesn't produce a second instance. Use an enumeration to avoid this problem:

[Click here to view code image](#)

```
public enum MySingleton
{
 INSTANCE;
 MySingleton() { . . . } // automatically private
 // instance fields
 // methods
}
```

Since enumerations are properly serialized, you are guaranteed a single `MySingleton.INSTANCE`.

---

Sometimes, the `readResolve` method is used in conjunction with yet another special method:

[Click here to view code image](#)

```
@Serial private Object writeReplace() throws
ObjectStreamException
```

The `writeReplace` produces an object to be written to the object stream *instead of* the current one. The replacement object must be serializable or externalizable. When reading the object stream, the replacement object is deserialized and its `readResolve` method is called to recreate the original object.

---



### Note

Unlike the `readObject` and `writeObject` methods, which must be private, or the `readExternal/writeExternal` methods, which must be public, the `readResolve` and `writeReplace` methods can have any access modifier.

---

Here is an example to show the mechanics. The `writeReplace` method of the `ColoredPoint` class produces a replacement object of a nested class `Ser`. For maximum convenience, the example uses a record. The `readResolve` method of the replacement class reconstructs the original `ColoredPoint` object.

[Click here to view code image](#)

```
public class ColoredPoint implements Serializable
{
 private Color color;
 private Point location;

 public ColoredPoint(Color color, int x, int y)
 {
 this.color = color;
 }
```

```

 this.location = new Point(x, y);
 }

 @Serial private Object writeReplace() throws
ObjectStreamException
{
 return new Ser(color.getRGB(), location.x, location.y);
}

private record Ser(int rgba, int x, int y) implements
Serializable
{
 @Serial private Object readResolve() throws
ObjectStreamException
{
 return new ColoredPoint(new Color(rgba), x, y);
}
}
}

```

Why go through the trouble? The default serialization would have saved two objects instead of three integers. You could have achieved the same savings with `readExternal/writeExternal` methods, but those methods must be public.

The `LocalDate` class, as well as the other classes in the `java.time` package, use this strategy. For that reason, the serialization example uses `Date` objects. I didn't want to explain the presence of `Ser` objects in the object stream.

---



## Note

Unlike the `readObject` and `writeObject` methods, the `readResolve` and `writeReplace` methods need not be private.

---

## 2.3.5 Versioning

If you use serialization to save objects, you need to consider what happens when your program evolves. Can version 1.1 read the old files? Can the users who still use 1.0 read the files that the new version is producing? Clearly, it would be desirable if object files could cope with the evolution of classes.

At first glance, it seems that this would not be possible. When a class definition changes in any way, its SHA fingerprint also changes, and you know that object input streams will refuse to read in objects with different fingerprints. However, a class can indicate that it is *compatible* with an earlier version of itself. To do this, you must first obtain the fingerprint of the *earlier* version of the class. Use the standalone `serialver` program that is part of the JDK to obtain this number. For example, running

[Click here to view code image](#)

```
serialver serial.Employee
```

prints

[Click here to view code image](#)

```
serial.Employee: static final long serialVersionUID =
8367346051156850807L;
```

All *later* versions of the class must define the `serialVersionUID` constant to the same fingerprint as the original.

[Click here to view code image](#)

```
class Employee implements Serializable // version 1.1
{
 . . .
 @Serial public static final long serialVersionUID =
8367346051156850807L;
}
```


When a class has a static data member named `serialVersionUID`, it will not compute the fingerprint manually but will use that value instead.

Once that static data member has been placed inside a class, the serialization system is now willing to read in different versions of objects of that class.


If only the methods of the class change, there is no problem with reading the new object data. However, if the instance fields change, you may have problems. For example, the old file object may have more or fewer instance fields than the one in the program, or the types of the instance fields may be different. In that case, the object input stream makes an effort to convert the serialized object to the current version of the class.

The object input stream compares the instance fields of the current version of the class with those of the version in the serialized object. Of course, the object input stream considers only the nontransient and nonstatic instance fields. If two fields have matching names but different types, the object input stream makes no effort to convert one type to the other—the objects are incompatible. If the serialized object has instance fields that are not present in the current version, the object input stream ignores the additional data. If the current version has instance fields that are not present in the serialized object, the added fields are set to their default (null for objects, zero for numbers, and false for boolean values).

Here is an example. Suppose we have saved a number of employee records on disk, using the original version (1.0) of the class. Now we change the `Employee` class to version 2.0 by adding a instance field called `department`. [Figure 2.7](#) shows what happens when a 1.0 object is read into a program that uses 2.0 objects. The `department` field is set to null. [Figure 2.8](#) shows the opposite scenario: A program using 1.0 objects reads a 2.0 object. The additional `department` field is ignored.



**Figure 2.7** Reading an object with fewer instance fields



**Figure 2.8** Reading an object with more instance fields

Is this process safe? It depends. Dropping a instance field seems harmless—the recipient still has all the data that it knows how to manipulate. Setting a instance field to `null` might not be so safe. Many classes work hard to initialize all instance fields in all constructors to non-`null` values, so that

the methods don't have to be prepared to handle `null` data. It is up to the class designer to implement additional code in the `readObject` method to fix version incompatibilities or to make sure the methods are robust enough to handle `null` data.

---



### Tip

Before you add a `serialVersionUID` field to a class, ask yourself why you made your class serializable. If serialization is used only for short-term persistence, such as distributed method calls in an application server, there is no need to worry about versioning and the `serialVersionUID`. The same applies if you extend a class that happens to be serializable, but you have no intent to ever persist its instances. If your IDE gives you pesky warnings, change the IDE preferences to turn them off, or add an annotation `@SuppressWarnings("serial")`. This is safer than adding a `serialVersionUID` that you may later forget to change.

---



### Note

Enumerations and records ignore the `serialVersionUID` field. An enumeration always has a `serialVersionUID` of `0L`. You can declare the `serialVersionUID` of a record, but the IDs don't have to match for deserialization.

---



### Note

In this section, you saw what happens when the reader's version of a class has instance fields that aren't present in the object stream. It is also possible during class evolution for a superclass to be added. Then a reader using the new version may read an object stream in which the

instance fields of the superclass are not set. By default, those instance fields are set to their zero/null default. That may leave the superclass in an unsafe state. The superclass can defend against that problem by defining an initialization method

```
@Serial private void readObjectNoData() throws
ObjectStreamException
```

The method should either set the same state as the no-argument constructor or throw an `InvalidObjectException`. It is only called in the unusual circumstance that an object stream is read which contains an instance of a subclass with missing superclass data.

---

### 2.3.6 Using Serialization for Cloning

There is an amusing use for the serialization mechanism: It gives you an easy way to clone an object, provided the class is serializable. Simply serialize it to an output stream and then read it back in. The result is a new object that is a deep copy of the existing object. You don't have to write the object to a file—you can use a `ByteArrayOutputStream` to save the data into a byte array.

As Listing 2.4 shows, to get `clone` for free, simply extend the `Serializable` class, and you are done.

You should be aware that this method, although clever, will usually be much slower than a `clone` method that explicitly constructs a new object and copies or clones the instance fields.

---

#### **Listing 2.4** `serialClone/SerialCloneTest.java`

---

[Click here to view code image](#)

```
1 package serialClone;
2
3 /**
4 * @version 1.22 2018-05-01
5 * @author Cay Horstmann
```

```
6 */
7
8 import java.io.*;
9 import java.time.*;
10
11 public class SerialCloneTest
12 {
13 public static void main(String[] args) throws
14 CloneNotSupportedException
15 {
16 var harry = new Employee("Harry Hacker", 35000, 1989,
17 10, 1);
18 // clone harry
19 var harry2 = (Employee) harry.clone();
20
21 // mutate harry
22 harry.raiseSalary(10);
23
24 // now harry and the clone are different
25 System.out.println(harry);
26 System.out.println(harry2);
27 }
28 /**
29 * A class whose clone method uses serialization.
30 */
31 class SerialCloneable implements Cloneable, Serializable
32 {
33 public Object clone() throws CloneNotSupportedException
34 {
35 try {
36 // save the object to a byte array
37 var bout = new ByteArrayOutputStream();
38 try (var out = new ObjectOutputStream(bout))
39 {
40 out.writeObject(this);
41 }
42 }
43 catch (IOException e)
44 {
45 throw new CloneNotSupportedException("Error cloning object");
46 }
47 }
48 }
```

```
42
43 // read a clone of the object from the byte array
44 try (var bin = new
45 ByteArrayInputStream(bout.toByteArray()))
46 {
47 var in = new ObjectInputStream(bin);
48 return in.readObject();
49 }
50 catch (IOException | ClassNotFoundException e)
51 {
52 var e2 = new CloneNotSupportedException();
53 e2.initCause(e);
54 throw e2;
55 }
56 }
57 }
58
59 /**
60 * The familiar Employee class, redefined to extend the
61 * Serializable class.
62 */
63 class Employee extends Serializable
64 {
65 private String name;
66 private double salary;
67 private LocalDate hireDay;
68
69 public Employee(String n, double s, int year, int month,
int day)
70 {
71 name = n;
72 salary = s;
73 hireDay = LocalDate.of(year, month, day);
74 }
75
76 public String getName()
77 {
```

```

78 return name;
79 }
80
81 public double getSalary()
82 {
83 return salary;
84 }
85
86 public LocalDate getHireDay()
87 {
88 return hireDay;
89 }
90
91 /**
92 Raises the salary of this employee.
93 @param byPercent the percentage of the raise
94 */
95 public void raiseSalary(double byPercent)
96 {
97 double raise = salary * byPercent / 100;
98 salary += raise;
99 }
100
101 public String toString()
102 {
103 return getClass().getName()
104 + "[name=" + name
105 + ",salary=" + salary
106 + ",hireDay=" + hireDay
107 + "]";
108 }
109 }
```

---

### 2.3.7 Deserialization and Security

During deserialization of a serializable class, objects are created without invoking any constructor of the class. Even if the class has a no-argument

constructor, it is not used. The field values are set directly from the values of the object input stream.

---



## Note

For serializable *records*, deserialization calls the canonical constructor, passing it the values of the components from the object input stream. (As a consequence, cyclic references in records are not restored.)

---

Bypassing constructors is a security risk. An attacker can craft bytes describing an invalid object that could have never been constructed. Suppose, for example, that the Employee constructor throws an exception when called with a negative salary. We would like to think that this means that no Employee object can have a negative salary. But, as you saw in the preceding section, it is not difficult to inspect the bytes for a serialized object and modify some of them. By doing so, one can craft bytes for an employee with a negative salary and then deserialize them.

A serializable class can optionally implement the `ObjectInputValidation` interface and define a `validateObject` method to check whether its objects are properly deserialized. For example, the Employee class can check that salaries are not negative:

[Click here to view code image](#)

```
public void validateObject() throws InvalidObjectException
{
 System.out.println("validateObject");
 if (salary < 0)
 throw new InvalidObjectException("salary < 0");
}
```

Unfortunately, the method is not invoked automatically. To invoke it, you must also provide the following method:

[Click here to view code image](#)

```
@Serial private void readObject(ObjectInputStream in)
 throws IOException, ClassNotFoundException
{
 in.registerValidation(this, 0);
 in.defaultReadObject();
}
```

The object is then scheduled for validation, and the `validateObject` method is called when this object and all dependent objects have been loaded. The second parameter lets you specify a priority. Validation requests with higher priorities are done first.

There are other security risks. Adversaries can create data structures that consume enough resources to crash a virtual machine. More insidiously, any class on the class path can be deserialized. Hackers have been devious about piecing together “gadget chains”, sequences of operations in various utility classes that use reflection and culminate in calling methods such as `Runtime.exec` with a string of their choice.

Any application that receives serialized data from untrusted sources over a network connection is vulnerable to such attacks. For example, some servers serialize session data and deserialize whatever data is returned in the HTTP session cookie.

You should avoid situations in which arbitrary data from untrusted sources are deserialized. In the example of session data, the server should sign the data, and only deserialize data with a valid signature.

JEP 290 and 415 provide a *serialization filter* mechanism to harden applications from such attacks. The filters can see the names of deserialized classes and several metrics (stream size, array sizes, total number of references, longest chain of references). Based on those data, the deserialization can be aborted.

In its simplest form, you provide a pattern describing the valid and invalid classes. For example, if you start our sample serialization demo as

[Click here to view code image](#)

```
java -Djdk.serialFilter='serial.*;java.**;!*'
serial.ObjectStreamTest
```

then the objects will be loaded. The filter allows all classes in the `serial` package and all classes whose package name starts with `java`, but no others. If you don't allow `java.**`, or at least `java.util.Date`, deserialization fails.

You can place the filter pattern into a configuration file and specify multiple filters for different purposes. You can also implement your own filters. See <https://docs.oracle.com/en/java/javase/17/core/serialization-filtering1.html> for details.

## 2.4 Working with Files

You have learned how to read and write data from a file. However, there is more to file management than reading and writing. The `Path` interface and `Files` class encapsulate the functionality required to work with the file system on the user's machine. For example, the `Files` class can be used to remove or rename a file, or to find out when a file was last modified. In other words, the input/output stream classes are concerned with the contents of files, whereas the classes that we discuss here are concerned with the storage of files on a disk.

The `Path` interface and `Files` class were added in Java 7. They are much more convenient to use than the `File` class which dates back all the way to JDK 1.0. We expect them to be very popular with Java programmers and discuss them in depth.

### 2.4.1 Paths

A `Path` is a sequence of directory names, optionally followed by a file name. The first component of a path may be a *root component* such as `/` or `C:\`. The permissible root components depend on the file system. A path that starts with a root component is *absolute*. Otherwise, it is *relative*. For

example, here we construct an absolute and a relative path. For the absolute path, we assume a UNIX-like file system.

[Click here to view code image](#)

```
Path absolute = Path.of("/home", "harry");
Path relative = Path.of("myprog", "conf", "user.properties");
```

The static `Path.of` method receives one or more strings, which it joins with the path separator of the default file system (/ for a UNIX-like file system, \ for Windows). It then parses the result, throwing an `InvalidPathException` if the result is not a valid path in the given file system. The result is a `Path` object.

The `get` method can get a single string containing multiple components. For example, you can read a path from a configuration file like this:

[Click here to view code image](#)

```
String baseDir = props.getProperty("base.dir");
 // May be a string such as /opt/myprog or c:\Program
 Files\myprog
Path basePath = Path.of(baseDir); // OK that baseDir has
separators
```

---



## Note

A path does not have to correspond to a file that actually exists. It is merely an abstract sequence of names. As you will see in the next section, when you want to create a file, you first make a path and then call a method to create the corresponding file.

---

It is very common to combine or *resolve* paths. The call `p.resolve(q)` returns a path according to these rules:

- If `q` is absolute, then the result is `q`.

- Otherwise, the result is “p then q,” according to the rules of the file system.

For example, suppose your application needs to find its working directory relative to a given base directory that is read from a configuration file, as in the preceding example.

[Click here to view code image](#)

```
Path workRelative = Path.of("work");
Path workPath = basePath.resolve(workRelative);
```

There is a shortcut for the `resolve` method that takes a string instead of a path:

[Click here to view code image](#)

```
Path workPath = basePath.resolve("work");
```

There is a convenience method `resolveSibling` that resolves against a path’s parent, yielding a sibling path. For example, if `workPath` is `/opt/myapp/work`, the call

[Click here to view code image](#)

```
Path tempPath = workPath.resolveSibling("temp");
```

creates `/opt/myapp/temp`.

The opposite of `resolve` is `relativize`. The call `p.relativize(r)` yields the path `q` which, when resolved with `p`, yields `r`. For example, relativizing `/home/harry` against `/home/fred/input.txt` yields `../fred/input.txt`. Here, we assume that `..` denotes the parent directory in the file system.

The `normalize` method removes any redundant `.` and `..` components (or whatever the file system may deem redundant). For example, normalizing the path `/home/harry/..../fred/./input.txt` yields `/home/fred/input.txt`.

The `toAbsolutePath` method yields the absolute path of a given path, starting at a root component, such as `/home/fred/input.txt` or `c:\Users\fred\input.txt`.

The `Path` interface has many useful methods for taking paths apart. This code sample shows some of the most useful ones:

[Click here to view code image](#)

```
Path p = Path.of("/home", "fred", "myprog.properties");
Path parent = p.getParent(); // the path /home/fred
Path file = p.getFileName(); // the path myprog.properties
Path root = p.getRoot(); // the path /
```

As you have already seen in Volume I, you can construct a `Scanner` from a `Path` object:

[Click here to view code image](#)

```
var in = new Scanner(Path.of("/home/fred/input.txt"));
```



### Note

Occasionally, you may need to interoperate with legacy APIs that use the `File` class instead of the `Path` interface. The `Path` interface has a `toFile` method, and the `File` class has a `toPath` method.

---

### `java.nio.file.Paths` 7

- `static Path get(String first, String... more)`

makes a path by joining the given strings.

## ***java.nio.file.Path***

- Path resolve(Path other)
- Path resolve(String other)

If other is absolute, return other; otherwise, return the path obtained by joining this and other.

- Path resolveSibling(Path other)
- Path resolveSibling(String other)

If other is absolute, return other; otherwise, return the path obtained by joining the parent of this and other.

- Path relativize(Path other)

returns the relative path that, when resolved with this, yields other.

- Path normalize()

removes redundant path elements such as . and ..

- Path toAbsolutePath()

returns an absolute path that is equivalent to this path.

- Path getParent()

returns the parent, or null if this path has no parent.

- Path getFileName()

returns the last component of this path, or null if this path has no components.

- Path getRoot()

returns the root component of this path, or null if this path has no root components.

- `toFile()`

makes a `File` from this path.

### **java.io.File 1.0**

- `Path toPath() 7`

makes a `Path` from this file.

## **2.4.2 Reading and Writing Files**

The `Files` class makes quick work of common file operations. For example, you can easily read the entire contents of a file as a byte array, string, list of lines, or stream of lines:

[Click here to view code image](#)

```
byte[] bytes = Files.readAllBytes(path);
String content = Files.readString(path, charset);
List<String> lines = Files.readAllLines(path, charset);
Stream<String> lineStream = Files.lines(path, charset);
```

Conversely, for writing:

[Click here to view code image](#)

```
Files.write(path, bytes);
Files.writeString(path, content, charset);
Path.write(path, lines, charset);
```

To append to a given file, use

[Click here to view code image](#)

```
Files.write(path, content, charset, StandardOpenOption.APPEND);
```

The call

[Click here to view code image](#)

```
long pos = Files.mismatch(path1, path2);
```

yields the position of the first byte where the file contents differ.

To get the MIME type of a file (such as "text/html" or "image/png"), call

[Click here to view code image](#)

```
String mimeType = Files.probeContentType(path);
```

The exact behavior depends on the Java implementation. Each implementation has a collection of `FileTypeDetector` instances that are tried in unspecified order. Each detector may examine the file extension, OS-specific metadata, or the first few bytes of the contents.

The following methods allow you to interact with an API that uses the classic input/output streams or readers/writers:

[Click here to view code image](#)

```
InputStream in = Files.newInputStream(path);
OutputStream out = Files.newOutputStream(path);
Reader in = Files.newBufferedReader(path, charset);
Writer out = Files.newBufferedWriter(path, charset);
```

These convenience methods save you from dealing with `FileInputStream`, `FileOutputStream`, `BufferedReader`, or `BufferedWriter`.

**java.nio.file.Files** 7

- static byte[] readAllBytes(Path path)
- static String readString(Path path, Charset charset)
- static List<String> readAllLines(Path path, Charset charset)

read the contents of a file.

- static Path write(Path path, byte[] contents, OpenOption... options)
- static Path write(Path path, String contents, Charset charset, OpenOption... options)
- static Path writeString(Path path, CharSequence contents, Charset cs, OpenOption... options) 11
- static Path write(Path path, Iterable<? extends CharSequence> contents, Charset cs, OpenOption options)

write the given contents to a file and return path.

- static long mismatch(Path path, Path path2) 12

returns the position of the first byte where the file contents differ.

- static String probeContentType(Path path) 12

returns the best guess of the installed file type detectors for the MIME type of the file contents, or null if the type could not be determined.

- static InputStream newInputStream(Path path, OpenOption... options)

- static OutputStream newOutputStream(Path path, OpenOption... options)
- static BufferedReader newBufferedReader(Path path, Charset charset)
- static BufferedWriter newBufferedWriter(Path path, Charset charset, OpenOption... options)

open a file for reading or writing.

### 2.4.3 Creating Files and Directories

To create a new directory, call

[Click here to view code image](#)

```
Files.createDirectory(path);
```

All but the last component in the path must already exist. To create intermediate directories as well, use

[Click here to view code image](#)

```
Files.createDirectories(path);
```

You can create an empty file with

[Click here to view code image](#)

```
Files.createFile(path);
```

The call throws an exception if the file already exists. The check for existence and creation are atomic. If the file doesn't exist, it is created before anyone else has a chance to do the same.

There are convenience methods for creating a temporary file or directory in a given or system-specific location.

[Click here to view code image](#)

```
Path newPath = Files.createTempFile(dir, prefix, suffix);
Path newPath = Files.createTempFile(prefix, suffix);
Path newPath = Files.createTempDirectory(dir, prefix);
Path newPath = Files.createTempDirectory(prefix);
```

Here, `dir` is a `Path`, and `prefix/suffix` are strings which may be null. For example, the call `Files.createTempFile(null, ".txt")` might return a path such as `/tmp/1234405522364837194.txt`.

When you create a file or directory, you can specify attributes, such as owners or permissions. However, the details depend on the file system, and we won't cover them here.

### **java.nio.file.Files 7**

- `static Path createFile(Path path, FileAttribute<?>... attrs)`
- `static Path createDirectory(Path path, FileAttribute<?>... attrs)`
- `static Path createDirectories(Path path, FileAttribute<?>... attrs)`

create a file or directory. The `createDirectories` method creates any intermediate directories as well.

- `static Path createTempFile(String prefix, String suffix, FileAttribute<?>... attrs)`
- `static Path createTempFile(Path parentDir, String prefix, String suffix, FileAttribute<?>... attrs)`
- `static Path createTempDirectory(String prefix, FileAttribute<?>... attrs)`

- static Path createTempDirectory(Path parentDir, String prefix, FileAttribute<? >... attrs)

create a temporary file or directory, in a location suitable for temporary files or in the given parent directory. Return the path to the created file or directory.

#### 2.4.4 Copying, Moving, and Deleting Files

To copy a file from one location to another, simply call

[Click here to view code image](#)

```
Files.copy(fromPath, toPath);
```

To move the file (that is, copy and delete the original), call

[Click here to view code image](#)

```
Files.move(fromPath, toPath);
```

The copy or move will fail if the target exists. If you want to overwrite an existing target, use the REPLACE\_EXISTING option. If you want to copy all file attributes, use the COPY\_ATTRIBUTES option. You can supply both like this:

[Click here to view code image](#)

```
Files.copy(fromPath, toPath,
 StandardCopyOption.REPLACE_EXISTING,
 StandardCopyOption.COPY_ATTRIBUTES);
```

You can specify that a move should be atomic. Then you are assured that either the move completed successfully, or the source continues to be present. Use the ATOMIC\_MOVE option:

[Click here to view code image](#)

```
Files.move(fromPath, toPath, StandardCopyOption.ATOMIC_MOVE);
```

You can also copy an input stream to a Path, which just means saving the input stream to disk. Similarly, you can copy a Path to an output stream. Use the following calls:

[Click here to view code image](#)

```
Files.copy(inputStream, toPath);
Files.copy(fromPath, outputStream);
```

As with the other calls to `copy`, you can supply copy options as needed.

Finally, to delete a file, simply call

```
Files.delete(path);
```

This method throws an exception if the file doesn't exist, so instead you may want to use

[Click here to view code image](#)

```
boolean deleted = Files.deleteIfExists(path);
```

The deletion methods can also be used to remove an empty directory.

See [Table 2.4](#) for a summary of the options that are available for file operations.

**Table 2.4** Standard Options for File Operations

| Option                                                                                                                                            | Description                                          |
|---------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------|
| <b>StandardOpenOption; use with <code>newBufferedWriter</code>, <code>newInputStream</code>, <code>newOutputStream</code>, <code>write</code></b> |                                                      |
| READ                                                                                                                                              | Open for reading                                     |
| WRITE                                                                                                                                             | Open for writing                                     |
| APPEND                                                                                                                                            | If opened for writing, append to the end of the file |

| Option                    | Description                                                                                                    |
|---------------------------|----------------------------------------------------------------------------------------------------------------|
| TRUNCATE<br>_EXISTIN<br>G | If opened for writing, remove existing contents                                                                |
| CREATE_N<br>EW            | Create a new file and fail if it exists                                                                        |
| CREATE                    | Atomically create a new file if it doesn't exist                                                               |
| DELETE_O<br>N_CLOSE       | Make a “best effort” to delete the file when it is closed                                                      |
| SPARSE                    | A hint to the file system that this file will be sparse                                                        |
| DSYNC or<br>SYNC          | Requires that each update to the file data or data and metadata be written synchronously to the storage device |

#### **StandardCopyOption; use with `copy`, `move`**

|                      |                                 |
|----------------------|---------------------------------|
| ATOMIC_M<br>OVE      | Move the file atomically        |
| COPY_ATT<br>RIBUTES  | Copy the file attributes        |
| REPLACE_<br>EXISTING | Replace the target if it exists |

#### **LinkOption; use with all of the above methods and `exists`, `isDirectory`, `isRegularFile`**

|                    |                              |
|--------------------|------------------------------|
| NOFOLLOW<br>_LINKS | Do not follow symbolic links |
|--------------------|------------------------------|

#### **FileVisitOption; use with `find`, `walk`, `walkFileTree`**

|                  |                       |
|------------------|-----------------------|
| FOLLOW_L<br>INKS | Follow symbolic links |
|------------------|-----------------------|

```
java.nio.file.Files 7
```

- static Path copy(Path from, Path to, CopyOption... options)

- static Path move(Path from, Path to, CopyOption... options)

copy or move from to the given target location and return to.

- static long copy(InputStream from, Path to, CopyOption... options)

- static long copy(Path from, OutputStream to, CopyOption... options)

copy from an input stream to a file, or from a file to an output stream, returning the number of bytes copied.

- static void delete(Path path)

- static boolean deleteIfExists(Path path)

delete the given file or empty directory. The first method throws an exception if the file or directory doesn't exist. The second method returns false in that case.

## 2.4.5 Getting File Information

The following static methods return a boolean value to check a property of a path:

- exists
- isHidden
- isReadable, isWritable, isExecutable
- isRegularFile, isDirectory, isSymbolicLink

The size method returns the number of bytes in a file.

[Click here to view code image](#)

```
long fileSize = Files.size(path);
```

The `getOwner` method returns the owner of the file, as an instance of `java.nio.file.attribute.UserPrincipal`.

All file systems report a set of basic attributes, encapsulated by the `BasicFileAttributes` interface, which partially overlaps with that information. The basic file attributes are

- The times at which the file was created, last accessed, and last modified, as instances of the class `java.nio.file.attribute.FileTime`
- Whether the file is a regular file, a directory, a symbolic link, or none of these
- The file size
- The file key—an object of some class, specific to the file system, that may or may not uniquely identify a file

To get these attributes, call

[Click here to view code image](#)

```
BasicFileAttributes attributes = Files.readAttributes(path,
BasicFileAttributes.class);
```

If you know that the user's file system is POSIX-compliant, you can instead get an instance of `PosixFileAttributes`:

[Click here to view code image](#)

```
PosixFileAttributes attributes = Files.readAttributes(path,
PosixFileAttributes.class);
```

Then you can find out the group owner and the owner, group, and world access permissions of the file. We won't dwell on the details since so much of this information is not portable across operating systems.

**java.nio.file.Files 7**

- static boolean exists(Path path)
- static boolean isHidden(Path path)
- static boolean isReadable(Path path)
- static boolean isWritable(Path path)
- static boolean isExecutable(Path path)
- static boolean isRegularFile(Path path)
- static boolean isDirectory(Path path)
- static boolean isSymbolicLink(Path path)

check for the given property of the file given by the path.

- static long size(Path path)  
gets the size of the file in bytes.
- A readAttributes(Path path, Class<A> type,  
LinkOption... options)  
reads the file attributes of type A.

## ***java.nio.file.attribute.BasicFileAttributes 7***

- FileTime creationTime()
- FileTime lastAccessTime()
- FileTime lastModifiedTime()
- boolean isRegularFile()
- boolean isDirectory()
- boolean isSymbolicLink()
- long size()
- Object fileKey()

get the requested attribute.

## 2.4.6 Visiting Directory Entries

The static `Files.list` method returns a `Stream<Path>` that reads the entries of a directory. The directory is read lazily, making it possible to efficiently process directories with huge numbers of entries.

Since reading a directory involves a system resource that needs to be closed, you should use a `try` block:

[Click here to view code image](#)

```
try (Stream<Path> entries = Files.list(pathToDirectory))
{
 . . .
}
```

The `list` method does not enter subdirectories. To process all descendants of a directory, use the `Files.walk` method instead.

[Click here to view code image](#)

```
try (Stream<Path> entries = Files.walk(pathToRoot))
{
 // Contains all descendants, visited in depth-first order
}
```

Here is a sample traversal of the unzipped `src.zip` tree:

[Click here to view code image](#)

```
java
java.nio
java.nio/DirectCharBufferU.java
java.nio/ByteBufferAsShortBufferRL.java
java.nio/MappedByteBuffer.java
. . .
```

```
java/nio/ByteBufferAsDoubleBufferB.java
java/nio/charset
java/nio/charset/CoderMalfunctionError.java
java/nio/charset/CharsetDecoder.java
java/nio/charset/UnsupportedCharsetException.java
java/nio/charset/spi
java/nio/charset/spi/CharsetProvider.java
java/nio/charset/StandardCharsets.java
java/nio/charset/Charset.java
.
.
.
java/nio/charset/CoderResult.java
java/nio/HeapFloatBufferR.java
.
```

As you can see, whenever the traversal yields a directory, it is entered before continuing with its siblings.

You can limit the depth of the tree that you want to visit by calling `Files.walk(pathToRoot, depth)`. Both `walk` methods have a varargs parameter of type `FileVisitOption...`, but there is only one option you can supply: `FOLLOW_LINKS` to follow symbolic links.

---



## Note

If you filter the paths returned by `walk` and your filter criterion involves the file attributes stored with a directory, such as size, creation time, or type (file, directory, symbolic link), then use the `find` method instead of `walk`. Call that method with a predicate function that accepts a path and a `BasicFileAttributes` object. The only advantage is efficiency. Since the directory is being read anyway, the attributes are readily available.

---

This code fragment uses the `Files.walk` method to copy one directory to another:

[Click here to view code image](#)

```

Files.walk(source).forEach(p ->
{
 try
 {
 Path q = target.resolve(source.relativize(p));
 if (Files.isDirectory(p))
 Files.createDirectory(q);
 else
 Files.copy(p, q);
 }
 catch (IOException e)
 {
 throw new UncheckedIOException(ex);
 }
}) ;

```

Unfortunately, you cannot easily use the `Files.walk` method to delete a tree of directories since you need to delete the children before deleting the parent. The next section shows you how to overcome that problem.

## 2.4.7 Using Directory Streams

As you saw in the preceding section, the `Files.walk` method produces a `Stream<Path>` that traverses the descendants of a directory. Sometimes, you need more fine-grained control over the traversal process. In that case, use the `Files.newDirectoryStream` object instead. It yields a `DirectoryStream`. Note that this is not a subinterface of `java.util.stream.Stream` but an interface that is specialized for directory traversal. It is a subinterface of `Iterable` so that you can use directory stream in an enhanced `for` loop. Here is the usage pattern:

[Click here to view code image](#)

```

try (DirectoryStream<Path> entries =
Files.newDirectoryStream(dir))
{
 for (Path entry : entries)

```

```

 Process entries
}

```

The `try-with-resources` block ensures that the directory stream is properly closed.

There is no specific order in which the directory entries are visited.

You can filter the files with a glob pattern:

[Click here to view code image](#)

```

try (DirectoryStream<Path> entries =
 Files.newDirectoryStream(dir, "*.java"))

```

[Table 2.5](#) shows all glob patterns.

**Table 2.5** Glob Patterns

| Pattern | Description                                                                 | Example                                                                       |
|---------|-----------------------------------------------------------------------------|-------------------------------------------------------------------------------|
| *       | Matches zero or more characters of a path component.                        | *.java matches all Java files in the current directory.                       |
| **      | Matches zero or more characters, crossing directory boundaries.             | **.java matches all Java files in any subdirectory.                           |
| ?       | Matches one character.                                                      | ????.java matches all four-character (not counting the extension) Java files. |
| [ . ]   | Matches a set of characters. You can use hyphens [0-9] and negation [!0-9]. | Test [0-9A-F].java matches Testx.java, where x is one hexadecimal digit.      |
| { . }   | Matches alternatives, separated by commas.                                  | *.{java, class} matches all Java and class files.                             |

| Pattern | Description                            | Example                                          |
|---------|----------------------------------------|--------------------------------------------------|
| \       | Escapes any of the above as well as \. | * \ ** matches all files with a * in their name. |

---



## Caution

If you use the glob syntax on Windows, you have to escape backslashes *twice*—once for the glob syntax, and once for the Java string syntax: `Files.newDirectoryStream(dir, "C:\\\\\\")`.

---

If you want to visit all descendants of a directory, call the `walkFileTree` method instead and supply an object of type `FileVisitor`. That object gets notified

- When a file is encountered: `FileVisitResult visitFile(T path, BasicFileAttributes attrs)`
- Before a directory is processed: `FileVisitResult preVisitDirectory(T dir, IOException e)`
- After a directory is processed: `FileVisitResult postVisitDirectory(T dir, IOException e)`
- When an error occurred trying to visit a file or directory, such as trying to open a directory without the necessary permissions:  
`FileVisitResult visitFileFailed(T path, IOException e)`

In each case, you can specify whether you want to

- Continue visiting the next file: `FileVisitResult.CONTINUE`
- Continue the walk, but without visiting the entries in this directory: `FileVisitResult.SKIP_SUBTREE`

- Continue the walk, but without visiting the siblings of this file:  
`FileVisitResult.SKIP_SIBLINGS`
- Terminate the walk: `FileVisitResult.TERMINATE`

If any of the methods throws an exception, the walk is also terminated, and that exception is thrown from the `walkFileTree` method.

---



## Note

The `FileVisitor` interface is a generic type, but it isn't likely that you'll ever want something other than a `FileVisitor<Path>`. The `walkFileTree` method is willing to accept a `FileVisitor<? super Path>`, but `Path` does not have an abundance of supertypes.

---

A convenience class `SimpleFileVisitor` implements the `FileVisitor` interface. All methods except `visitFileFailed` do nothing and continue. The `visitFileFailed` method throws the exception that caused the failure, thereby terminating the visit.

For example, here is how to print out all subdirectories of a given directory:

[Click here to view code image](#)

```
Files.walkFileTree(Path.of("/"), new SimpleFileVisitor<Path>()
{
 public FileVisitResult preVisitDirectory(Path path,
 BasicFileAttributes attrs)
 throws IOException
 {
 System.out.println(path);
 return FileVisitResult.CONTINUE;
 }

 public FileVisitResult postVisitDirectory(Path dir,
 IOException e)
```

```

 {
 return FileVisitResult.CONTINUE;
 }

 public FileVisitResult visitFileFailed(Path path, IOException
e) throws IOException
 {
 return FileVisitResult.SKIP_SUBTREE;
 }
});

```

Note that we need to override `postVisitDirectory` and `visitFileFailed`. Otherwise, the visit would fail as soon as it encounters a directory that it's not allowed to open or a file it's not allowed to access.

Also note that the attributes of the path are passed as a parameter to the `preVisitDirectory` and `visitFile` methods. The visitor already had to make an OS call to get the attributes, since it needs to distinguish between files and directories. This way, you don't need to make another call.

The other methods of the `FileVisitor` interface are useful if you need to do some work when entering or leaving a directory. For example, when you delete a directory tree, you need to remove the current directory after you have removed all of its files. Here is the complete code for deleting a directory tree:

[Click here to view code image](#)

```

// Delete the directory tree starting at root
Files.walkFileTree(root, new SimpleFileVisitor<Path>()
{
 public FileVisitResult visitFile(Path file,
BasicFileAttributes attrs)
 throws IOException
 {
 Files.delete(file);
 return FileVisitResult.CONTINUE;
 }
});

```

```
}

 public FileVisitResult postVisitDirectory(Path dir,
 IOException e) throws IOException
 {
 if (e != null) throw e;
 Files.delete(dir);
 return FileVisitResult.CONTINUE;
 }
});
```

## **java.nio.file.Files** 7

- static DirectoryStream<Path>  
newDirectoryStream(Path path)
- static DirectoryStream<Path>  
newDirectoryStream(Path path, String glob)  
  
get an iterator over the files and directories in a given directory.  
The second method only accepts those entries matching the given  
glob pattern.
- static Path walkFileTree(Path start,  
FileVisitor<? super Path> visitor)  
  
walks all descendants of the given path, applying the visitor to all  
descendants.

## **java.nio.file.SimpleFileVisitor<T>** 7

- static FileVisitResult visitFile(T path,  
BasicFileAttributes attrs)

is called when a file or directory is visited; returns one of CONTINUE, SKIP\_SUBTREE, SKIP\_SIBLINGS, or TERMINATE. The default implementation does nothing and continues.

- static FileVisitResult preVisitDirectory(T dir, BasicFileAttributes attrs)
- static FileVisitResult postVisitDirectory(T dir, IOException exc)

are called before and after visiting a directory. The default implementation does nothing and continues.

- static FileVisitResult visitFileFailed(T path, IOException e)

is called if an exception was thrown in an attempt to get information about the given file. The default implementation rethrows the exception, which causes the visit to terminate with that exception. Override the method if you want to continue.

## 2.4.8 ZIP File Systems

The Paths class looks up paths in the default file system—the files on the user’s local disk. You can have other file systems. One of the more useful ones is a *ZIP file system*. If zipfile is the name of a ZIP file, then the call

[Click here to view code image](#)

```
FileSystem fs = FileSystems.newFileSystem(Path.of(zipfile));
```

establishes a file system that contains all files in the ZIP archive. It’s an easy matter to copy a file out of that archive if you know its name:

[Click here to view code image](#)

```
Files.copy(fs.getPath(sourceName), targetPath);
```

Here, `fs.getPath` is the analog of `Path.of` for an arbitrary file system.

To list all files in a ZIP archive, walk the file tree:

[Click here to view code image](#)

```
FileSystem fs = FileSystems.newFileSystem(Path.of(zipname));
Files.walkFileTree(fs.getPath("/"), new SimpleFileVisitor<Path>
()
{
 public FileVisitResult visitFile(Path file,
BasicFileAttributes attrs)
 throws IOException
 {
 System.out.println(file);
 return FileVisitResult.CONTINUE;
 }
}) ;
```

That is nicer than the API described in [Section 2.2.3, “ZIP Archives,”](#) on p. 85 which required a set of new classes just to deal with ZIP archives.

### **java.nio.file.FileSystem** 7

- static FileSystem newFileSystem(Path path) 13  
returns the file system created by the first file system provider that accepts the given path. By default, there is a provider for ZIP file systems that accepts files whose names end in `.zip` or `.jar`.

### **java.nio.file.FileSystem** 7

- static Path getPath(String first, String... more)

makes a path by joining the given strings.

## 2.5 Memory-Mapped Files

Most operating systems can take advantage of a virtual memory implementation to “map” a file, or a region of a file, into memory. Then the file can be accessed as if it were an in-memory array, which is much faster than the traditional file operations.

### 2.5.1 Memory-Mapped File Performance

At the end of this section, you can find a program that computes the CRC32 checksum of a file using traditional file input and a memory-mapped file. On one machine, we got the timing data shown in [Table 2.6](#) when computing the checksum of the 49MB file `src.zip` in the `lib` directory of the JDK.

**Table 2.6** Timing Data for File Operations

| Method                | Time        |
|-----------------------|-------------|
| Plain input stream    | 110 seconds |
| Buffered input stream | 9.9 seconds |
| Random access file    | 102 seconds |
| Memory-mapped file    | 7.2 seconds |

As you can see, on this particular machine, memory mapping is a bit faster than using buffered sequential input and dramatically faster than using a `RandomAccessFile`.

Of course, the exact values will differ greatly from one machine to another, but it is obvious that the performance gain, compared to random access, can be substantial. For sequential reading of files of moderate size, on the other hand, there is no reason to use memory mapping.

The `java.nio` package makes memory mapping quite simple. Here is what you do.

First, get a *channel* for the file. A channel is an abstraction for a disk file that lets you access operating system features such as memory mapping, file locking, and fast data transfers between files.

[Click here to view code image](#)

```
FileChannel channel = FileChannel.open(path, options);
```

Then, get a `ByteBuffer` from the channel by calling the `map` method of the `FileChannel` class. Specify the area of the file that you want to map and a *mapping mode*. Three modes are supported:

- `FileChannel.MapMode.READ_ONLY`: The resulting buffer is read-only. Any attempt to write to the buffer results in a `ReadOnlyBufferException`.
- `FileChannel.MapMode.READ_WRITE`: The resulting buffer is writable, and the changes will be written back to the file at some time. Note that other programs that have mapped the same file might not see those changes immediately. The exact behavior of simultaneous file mapping by multiple programs depends on the operating system.
- `FileChannel.MapMode.PRIVATE`: The resulting buffer is writable, but any changes are private to this buffer and not propagated to the file.

For example,

[Click here to view code image](#)

```
MappedByteBuffer buffer =
channel.map(FileChannel.MapMode.READ_ONLY, 0, channel.size());
```

Once you have the buffer, you can read and write data using the methods of the `ByteBuffer` class and the `Buffer` superclass.

Buffers support both sequential and random data access. A buffer has a *position* that is advanced by `get` and `put` operations. For example, you

can sequentially traverse all bytes in the buffer as

[Click here to view code image](#)

```
while (buffer.hasRemaining())
{
 byte b = buffer.get();
 . . .
}
```

Alternatively, you can use random access:

[Click here to view code image](#)

```
for (int i = 0; i < buffer.limit(); i++)
{
 byte b = buffer.get(i);
 . . .
}
```

You can also read and write arrays of bytes with the methods

[Click here to view code image](#)

```
get(byte[] bytes)
get(byte[] bytes, int offset, int length)
```

Finally, there are methods

[Click here to view code image](#)

|          |           |
|----------|-----------|
| getInt   | getChar   |
| getLong  | getFloat  |
| getShort | getDouble |

to read primitive-type values that are stored as *binary* values in the file. As we already mentioned, Java uses big-endian ordering for binary data. However, if you need to process a file containing binary numbers in little-endian order, simply call

[Click here to view code image](#)

```
buffer.order(ByteOrder.LITTLE_ENDIAN);
```

To find out the current byte order of a buffer, call

[Click here to view code image](#)

```
ByteOrder b = buffer.order();
```

To write numbers to a buffer, use one of the methods

[Click here to view code image](#)

|          |           |
|----------|-----------|
| putInt   | putChar   |
| putLong  | putFloat  |
| putShort | putDouble |

At some point, and certainly when the channel is closed, these changes are written back to the file.

[Listing 2.5](#) computes the 32-bit cyclic redundancy checksum (CRC32) of a file. That checksum is often used to determine whether a file has been corrupted. Corruption of a file makes it very likely that the checksum has changed. The `java.util.zip` package contains a class `CRC32` that computes the checksum of a sequence of bytes, using the following loop:

[Click here to view code image](#)

```
var crc = new CRC32();
while (more bytes)
 crc.update(next byte);
long checksum = crc.getValue();
```

The details of the CRC computation are not important. We just use it as an example of a useful file operation. (In practice, you would read and update data in larger blocks, not a byte at a time. Then the speed differences are not as dramatic.)

Run the program as

[Click here to view code image](#)

```
java memoryMap.MemoryMapTest filename
```

---

**Listing 2.5** memoryMap/MemoryMapTest.java

---

[Click here to view code image](#)

```
1 package memoryMap;
2
3 import java.io.*;
4 import java.nio.*;
5 import java.nio.channels.*;
6 import java.nio.file.*;
7 import java.util.zip.*;
8
9 /**
10 * This program computes the CRC checksum of a file in four
ways.

11 * Usage: java memoryMap.MemoryMapTest filename
12 * @version 1.03 2018-05-01
13 * @author Cay Horstmann
14 */
15 public class MemoryMapTest
16 {
17 public static long checksumInputStream(Path filename)
throws IOException
18 {
19 try (InputStream in = Files.newInputStream(filename))
20 {
21 var crc = new CRC32();
22 boolean done = false;
23 while (!done)
24 {
25 int c = in.read();
26 if (c == -1) done = true;
27 else crc.update(c);
28 }
29 return crc.getValue();
30 }
31 }
32 }
```

```
30 }
31 }
32
33 public static long checksumBufferedInputStream(Path
filename) throws IOException
34 {
35 try (var in = new
BufferedInputStream(Files.newInputStream(filename)))
36 {
37 var crc = new CRC32();
38
39 boolean done = false;
40 while (!done)
41 {
42 int c = in.read();
43 if (c == -1) done = true;
44 else crc.update(c);
45 }
46 return crc.getValue();
47 }
48 }
49
50 public static long checksumRandomAccessFile(Path filename)
throws IOException
51 {
52 try (var file = new RandomAccessFile(filename.toFile(),
"r"))
53 {
54 long length = file.length();
55 var crc = new CRC32();
56
57 for (long p = 0; p < length; p++)
58 {
59 int c = file.readByte();
60 crc.update(c);
61 }
62 return crc.getValue();
63 }
64 }
```

```
64 }
65
66 public static long checksumMappedFile(Path filename) throws
67 IOException
68 {
69 try (FileChannel channel = FileChannel.open(filename))
70 {
71 var crc = new CRC32();
72 int length = (int) channel.size();
73 MappedByteBuffer buffer =
74 channel.map(FileChannel.MapMode.READ_ONLY, 0, length);
75
76 for (int p = 0; p < length; p++)
77 {
78 int c = buffer.get(p);
79 crc.update(c);
80 }
81 }
82
83 public static void main(String[] args) throws IOException
84 {
85 System.out.println("Input Stream:");
86 long start = System.currentTimeMillis();
87 Path filename = Path.of(args[0]);
88 long crcValue = checksumInputStream(filename);
89 long end = System.currentTimeMillis();
90 System.out.println(Long.toHexString(crcValue));
91 System.out.println((end - start) + " milliseconds");
92
93 System.out.println("Buffered Input Stream:");
94 start = System.currentTimeMillis();
95 crcValue = checksumBufferedInputStream(filename);
96 end = System.currentTimeMillis();
97 System.out.println(Long.toHexString(crcValue));
98 System.out.println((end - start) + " milliseconds");
99 }
```

```
100 System.out.println("Random Access File:");
101 start = System.currentTimeMillis();
102 crcValue = checksumRandomAccessFile(filename);
103 end = System.currentTimeMillis();
104 System.out.println(Long.toHexString(crcValue));
105 System.out.println((end - start) + " milliseconds");
106
107 System.out.println("Mapped File:");
108 start = System.currentTimeMillis();
109 crcValue = checksumMappedFile(filename);
110 end = System.currentTimeMillis();
111 System.out.println(Long.toHexString(crcValue));
112 System.out.println((end - start) + " milliseconds");
113 }
114 }
```

---

### **java.io.FileInputStream 1.0**

- `FileChannel getChannel()` 1.4  
returns a channel for accessing this input stream.

### **java.io.FileOutputStream 1.0**

- `FileChannel getChannel()` 1.4  
returns a channel for accessing this output stream.

### **java.io.RandomAccessFile 1.0**

- `FileChannel getChannel()` 1.4

returns a channel for accessing this file.

## **java.nio.channels.FileChannel 1.4**

- static FileChannel open(Path path, OpenOption... options) 7

opens a file channel for the given path. By default, the channel is opened for reading. The parameter `options` is one of the values `WRITE`, `APPEND`, `TRUNCATE_EXISTING`, `CREATE` in the `StandardOpenOption` enumeration.

- MappedByteBuffer map(FileChannel.MapMode mode, long position, long size)

maps a region of the file to memory. The parameter `mode` is one of the constants `READ_ONLY`, `READ_WRITE`, or `PRIVATE` in the `FileChannel.MapMode` class.

## **java.nio.Buffer 1.4**

- boolean hasRemaining()

returns `true` if the current buffer position has not yet reached the buffer's limit position.

- int limit()

returns the limit position of the buffer—that is, the first position at which no more values are available.

## **java.nio.ByteBuffer** 1.4

- `byte get()`

gets a byte from the current position and advances the current position to the next byte.

- `byte get(int index)`

gets a byte from the specified index.

- `ByteBuffer put(byte b)`

puts a byte at the current position and advances the current position to the next byte. Returns a reference to this buffer.

- `ByteBuffer put(int index, byte b)`

puts a byte at the specified index. Returns a reference to this buffer.

- `ByteBuffer get(byte[] destination)`

- `ByteBuffer get(byte[] destination, int offset, int length)`

fill a byte array, or a region of a byte array, with bytes from the buffer, and advance the current position by the number of bytes read. If not enough bytes remain in the buffer, then no bytes are read, and a `BufferUnderflowException` is thrown. Return a reference to this buffer.

- `ByteBuffer put(byte[] source)`

- `ByteBuffer put(byte[] source, int offset, int length)`

put all bytes from a byte array, or the bytes from a region of a byte array, into the buffer, and advance the current position by the number of bytes read. If not enough bytes remain in the buffer,

then no bytes are written, and a `BufferOverflowException` is thrown. Return a reference to this buffer.

- `Xxx getXxx()`
- `Xxx getXxx(int index)`
- `ByteBuffer putXxx(Xxx value)`
- `ByteBuffer putXxx(int index, Xxx value)`

get or put a binary number. `Xxx` is one of `Int`, `Long`, `Short`, `Char`, `Float`, or `Double`.

- `ByteBuffer order(ByteOrder order)`
- `ByteOrder order()`

set or get the byte order. The value for `order` is one of the constants `BIG_ENDIAN` or `LITTLE_ENDIAN` of the `ByteOrder` class.

- `static ByteBuffer allocate(int capacity)`  
constructs a buffer with the given capacity.

- `static ByteBuffer wrap(byte[] values)`  
constructs a buffer that is backed by the given array.

- `CharBuffer asCharBuffer()`

constructs a character buffer that is backed by this buffer. Changes to the character buffer will show up in this buffer, but the character buffer has its own position, limit, and mark.

## `java.nio.CharBuffer 1.4`

- `char get()`

- `CharBuffer get(char[] destination)`
- `CharBuffer get(char[] destination, int offset, int length)`

get one `char` value, or a range of `char` values, starting at the buffer's position and moving the position past the characters that were read. The last two methods return this.

- `CharBuffer put(char c)`
- `CharBuffer put(char[] source)`
- `CharBuffer put(char[] source, int offset, int length)`
- `CharBuffer put(String source)`
- `CharBuffer put(CharBuffer source)`

put one `char` value, or a range of `char` values, starting at the buffer's position and advancing the position past the characters that were written. When reading from a `CharBuffer`, all remaining characters are read. All methods return this.

## 2.5.2 The Buffer Data Structure

When you use memory mapping, you make a single buffer that spans the entire file or the area of the file that you're interested in. You can also use buffers to read and write more modest chunks of information.

In this section, we briefly describe the basic operations on `Buffer` objects. A buffer is an array of values of the same type. The `Buffer` class is an abstract class with concrete subclasses `ByteBuffer`, `CharBuffer`, `DoubleBuffer`, `FloatBuffer`, `IntBuffer`, `LongBuffer`, and `ShortBuffer`.




## Note

The `StringBuffer` class is not related to these buffers.

In practice, you will most commonly use `ByteBuffer` and `CharBuffer`. As shown in [Figure 2.9](#), a buffer has

- A *capacity* that never changes
- A *position* at which the next value is read or written
- A *limit* beyond which reading and writing is meaningless
- Optionally, a *mark* for repeating a read or write operation



**Figure 2.9** A buffer

These values fulfill the condition

$$0 \leq \text{mark} \leq \text{position} \leq \text{limit} \leq \text{capacity}$$

The principal purpose of a buffer is a “write, then read” cycle. At the outset, the buffer’s position is 0 and the limit is the capacity. Keep calling `put` to add values to the buffer. When you run out of data or reach the capacity, it is time to switch to reading.

Call `flip` to set the limit to the current position and the position to 0. Now keep calling `get` while the remaining method (which returns  $limit - position$ ) is positive. When you have read all values in the buffer, call `clear` to prepare the buffer for the next writing cycle. The `clear` method resets the position to 0 and the limit to the capacity.

If you want to reread the buffer, use `rewind` or `mark/reset` (see the API notes for details).

To get a buffer, call a static method such as `ByteBuffer.allocate` or `ByteBuffer.wrap`.

Then, you can fill a buffer from a channel, or write its contents to a channel. For example,

[Click here to view code image](#)

```
ByteBuffer buffer = ByteBuffer.allocate(RECORD_SIZE);
channel.read(buffer);
channel.position(newpos);
buffer.flip();
channel.write(buffer);
```

This can be a useful alternative to a random-access file.

#### **java.nio.Buffer 1.4**

- `Buffer clear()`

prepares this buffer for writing by setting the position to 0 and the limit to the capacity; returns `this`.

- `Buffer flip()`

prepares this buffer for reading after writing, by setting the limit to the position and the position to 0; returns `this`.

- `Buffer rewind()`

prepares this buffer for rereading the same values by setting the position to 0 and leaving the limit unchanged; returns this.

- `Buffer mark()`

sets the mark of this buffer to the position; returns this.

- `Buffer reset()`

sets the position of this buffer to the mark, thus allowing the marked portion to be read or written again; returns this.

- `int remaining()`

returns the remaining number of readable or writable values—that is, the difference between the limit and position.

- `int position()`

- `void position(int newValue)`

get and set the position of this buffer.

- `int capacity()`

returns the capacity of this buffer.

## 2.6 File Locking

When multiple simultaneously executing programs need to modify the same file, they need to communicate in some way, or the file can easily become damaged. File locks can solve this problem. A file lock controls access to a file or a range of bytes within a file.

Suppose your application saves a configuration file with user preferences. If a user invokes two instances of the application, it could happen that both of them want to write the configuration file at the same time. In that situation, the first instance should lock the file. When the second instance finds the

file locked, it can decide to wait until the file is unlocked or simply skip the writing process.

To lock a file, call either the `lock` or `tryLock` methods of the `FileChannel` class.

[Click here to view code image](#)

```
FileChannel = FileChannel.open(path);
FileLock lock = channel.lock();
```

or

[Click here to view code image](#)

```
FileLock lock = channel.tryLock();
```

The first call blocks until the lock becomes available. The second call returns immediately, either with the lock or with null if the lock is not available. The file remains locked until the channel is closed or the `release` method is invoked on the lock.

You can also lock a portion of the file with the call

[Click here to view code image](#)

```
FileLock lock(long start, long size, boolean shared)
```

or

[Click here to view code image](#)

```
FileLock tryLock(long start, long size, boolean shared)
```

The `shared` flag is `false` to lock the file for both reading and writing. It is `true` for a *shared* lock, which allows multiple processes to read from the file, while preventing any process from acquiring an exclusive lock. Not all operating systems support shared locks. You may get an exclusive lock even if you just asked for a shared one. Call the `isShared` method of the `FileLock` class to find out which kind you have.

---



## Note

If you lock the tail portion of a file and the file subsequently grows beyond the locked portion, the additional area is not locked. To lock all bytes, use a size of `Long.MAX_VALUE`.

---

Be sure to unlock the lock when you are done. As always, this is best done with a `try-with-resources` statement:

[Click here to view code image](#)

```
try (FileLock lock = channel.lock())
{
 access the locked file or segment
}
```

Keep in mind that file locking is system-dependent. Here are some points to watch for:

- On some systems, file locking is merely *advisory*. If an application fails to get a lock, it may still write to a file that another application has currently locked.
- On some systems, you cannot simultaneously lock a file and map it into memory.
- File locks are held by the entire Java virtual machine. Concurrent tasks on the same virtual machine can't each acquire a lock on the same file. The `lock` and `tryLock` methods will throw an `OverlappingFileLockException` if the virtual machine already holds another overlapping lock on the same file.
- On some systems, closing a channel releases all locks on the underlying file held by the Java virtual machine. You should therefore avoid multiple channels on the same locked file.
- Locking files on a networked file system is highly system-dependent and should probably be avoided.

## **java.nio.channels.FileChannel 1.4**

- `FileLock lock()`  
acquires an exclusive lock on the entire file. This method blocks until the lock is acquired.
- `FileLock tryLock()`  
acquires an exclusive lock on the entire file, or returns `null` if the lock cannot be acquired.
- `FileLock lock(long position, long size, boolean shared)`
- `FileLock tryLock(long position, long size, boolean shared)`  
acquire a lock on a region of the file. The first method blocks until the lock is acquired, and the second method returns `null` if the lock cannot be acquired. The parameter `shared` is `true` for a shared lock, `false` for an exclusive lock.

## **java.nio.channels.FileLock 1.4**

- `void close() 1.7`  
releases this lock.

## **2.7 Regular Expressions**

Regular expressions are used to specify string patterns. You can use regular expressions whenever you need to locate strings that match a particular

pattern. For example, one of our sample programs locates all hyperlinks in an HTML file by looking for strings of the pattern `<a href=". . .">`.

Of course, when specifying a pattern, the `. . .` notation is not precise enough. You need to specify exactly what sequence of characters is a legal match, using a special syntax to describe a pattern.

In the following sections, we cover the regular expression syntax used by the Java API and discuss how to put regular expressions to work.

### 2.7.1 The Regular Expression Syntax

Let us start with a simple example. The regular expression

`[Jj]ava.+`

matches any string of the following form:

- The first letter is a `J` or `j`.
- The next three letters are `ava`.
- The remainder of the string consists of one or more arbitrary characters.

For example, the string `"javanese"` matches this particular regular expression, but the string `"Core Java"` does not.

As you can see, you need to know a bit of syntax to understand the meaning of a regular expression. Fortunately, for most purposes, a few straightforward constructs are sufficient.

In a regular expression, a character denotes itself unless it is one of the reserved characters

`. * + ? { | ( ) [ \ ^ $`

For example, the regular expression `Java` only matches the string `Java`.

The symbol `.` matches any single character. For example, `.a.a` matches `Java` and `data`.

The `*` symbol indicates that the preceding constructs may be repeated 0 or more times; for a `+`, it is 1 or more times. A suffix of `?` indicates that a construct is optional (0 or 1 times). For example, `be+s?` matches `be`, `bee`, and `bees`. You can specify other multiplicities with `{ }` —see [Table 2.7](#).

**Table 2.7** Regular Expression Syntax

| Expression                                                                                                                                     | Description                                                                                                                                                                                                        | Example                                                |
|------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------|
| <b>Characters</b>                                                                                                                              |                                                                                                                                                                                                                    |                                                        |
| <code>c</code> , not one of <code>.</code>                                                                                                     |                                                                                                                                                                                                                    |                                                        |
| <code>*</code> <code>+</code> <code>?</code> <code>{</code> <code>}</code> <code> </code><br><code>( )</code> <code>[ ]</code> <code>\^</code> | The character <code>c</code>                                                                                                                                                                                       | <code>J</code>                                         |
| <code>\$</code>                                                                                                                                |                                                                                                                                                                                                                    |                                                        |
| <code>.</code>                                                                                                                                 | Any character except line terminators, or any character if the DOTALL flag is set                                                                                                                                  |                                                        |
| <code>\x{p}</code>                                                                                                                             | The Unicode code point with hex code <code>p</code>                                                                                                                                                                | <code>\x{1D546}</code>                                 |
| <code>\uhhhh</code> ,<br><code>\xhh</code> , <code>\0o</code> ,<br><code>\0oo</code> , <code>\0ooo</code>                                      | The UTF-16 code unit with the given hex or octal value                                                                                                                                                             | <code>\uFEFF</code>                                    |
| <code>\a</code> , <code>\e</code> , <code>\f</code> ,<br><code>\n</code> , <code>\r</code> , <code>\t</code>                                   | Alert ( <code>\x{7}</code> ), escape ( <code>\x{1B}</code> ), form feed ( <code>\x{B}</code> ), newline ( <code>\x{A}</code> ), <code>\n</code> carriage return ( <code>\x{D}</code> ), tab ( <code>\x{9}</code> ) |                                                        |
| <code>\cc</code> , where <code>c</code> is in <code>[A-Z]</code> or one of <code>@_</code> <code>[ \^_?]</code>                                | The control character corresponding to the character <code>c</code>                                                                                                                                                | <code>\cH</code> is a backspace ( <code>\x{8}</code> ) |
| <code>\c</code> , where <code>c</code> is not in <code>[A-Za-z0-9]</code>                                                                      | The character <code>c</code>                                                                                                                                                                                       | <code>\\"</code>                                       |

| Expression                                                                                                     | Description                                                                                                                            | Example                                                                                                                 |
|----------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------|
| <code>\Q... \E</code>                                                                                          | Everything between the start and the end of the quotation                                                                              | <code>\Q( . . . ) \E</code> matches the string <code>( . . . )</code>                                                   |
| <b>Character Classes</b>                                                                                       |                                                                                                                                        |                                                                                                                         |
| <code>[C<sub>1</sub>C<sub>2</sub>...]</code> , where $C_i$ are characters, ranges $c-d$ , or character classes | Any of the characters represented by $C_1$ , $C_2$ , ...                                                                               | <code>[0-9+-]</code>                                                                                                    |
| <code>[^...]</code>                                                                                            | Complement of a character class                                                                                                        | <code>[^\d\s]</code>                                                                                                    |
| <code>[... &amp; &amp; ...]</code>                                                                             | Intersection of character classes                                                                                                      | <code>[ \p{L} &amp;&amp; [ ^A-Za-z ] ]</code>                                                                           |
| <code>\p{...}, \P{...}</code>                                                                                  | A predefined character class (see <a href="#">Table 2.8</a> ); its complement                                                          | <code>\p{L}</code> matches a Unicode letter, and so does <code>\p{L}</code> —you can omit braces around a single letter |
| <code>\d, \D</code>                                                                                            | Digits ( <code>[0-9]</code> , or <code>\p{Digit}</code> when the UNICODE_CHARACTER_CLASS flag is set); the complement                  | <code>\d+</code> is a sequence of digits                                                                                |
| <code>\w, \W</code>                                                                                            | Word characters ( <code>[a-zA-Z0-9_]</code> , or Unicode word characters when the UNICODE_CHARACTER_CLASS flag is set); the complement |                                                                                                                         |

| Expression                                                    | Description                                                                                                                    | Example                                                                              |
|---------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------|
| $\backslash s, \backslash S$                                  | Spaces ([<br>\\n\\r\\t\\f\\x{B}], or<br>\\p{IsWhite_Space} when the<br>UNICODE_CHARACTER_CLASS flag is set); the<br>complement | $\backslash s^*, \backslash s^*$ is a comma<br>surrounded by optional<br>white space |
| $\backslash h, \backslash v, \backslash H,$<br>$\backslash V$ | Horizontal whitespace, vertical<br>whitespace, their complements                                                               |                                                                                      |
| <b>Sequences and Alternatives</b>                             |                                                                                                                                |                                                                                      |
| $XY$                                                          | Any string from X, followed<br>by any string from Y                                                                            | $[1-9][0-9]^*$ is a<br>positive number<br>without leading zero                       |
| $X Y$                                                         | Any string from X or Y                                                                                                         | http ftp                                                                             |
| <b>Grouping</b>                                               |                                                                                                                                |                                                                                      |
| $(X)$                                                         | Captures the match of X                                                                                                        | '( [^']* )' captures<br>the quoted text                                              |
| $\backslash n$                                                | The $n$ th group                                                                                                               | $(["]^*)^*\backslash 1$ matches<br>'Fred' or "Fred"<br>but not "Fred'                |
| $(?<name>X)$                                                  | Captures the match of X with<br>the given name                                                                                 | $'(?<id>[A-Za-z0-9]+)'$ captures<br>the match with name<br>id                        |
| $\backslash k<name>$                                          | The group with the given<br>name                                                                                               | $\backslash k<id>$ matches the<br>group with name id                                 |
| $(?:X)$                                                       | Use parentheses without<br>capturing X                                                                                         | In<br>$(?:http ftp)://$<br>$(.*),$ the match after<br>$://$ is $\backslash 1$        |

| Expression                                                                               | Description                                                                          | Example                                     |
|------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------|---------------------------------------------|
| $(?f_1 f_2 \dots : X),$<br>$(?f_1 \dots - f_k \dots : X),$ with<br>$f_i$ in<br>[dimsuUx] | Matches, but does not capture,<br>$X$ with the given flags on or<br>off (after $-$ ) | $(?i:jpe?g)$ is a<br>case-insensitive match |
| Other $(? \dots)$                                                                        | See the Pattern API<br>documentation                                                 |                                             |

## Quantifiers

|                                                                           |                                                                                  |                                                                                                         |
|---------------------------------------------------------------------------|----------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------|
| $X?$                                                                      | Optional $X$                                                                     | \+? is an optional + sign                                                                               |
| $X^*, X^+$                                                                | 0 or more $X$ , 1 or more $X$                                                    | [1-9] [0-9]^+ is an integer $\geq 10$                                                                   |
| $X\{n\}, X\{n, \}, n$ times $X$ , at least $n$ times $X$ ,<br>$X\{m, n\}$ | between $m$ and $n$ times $X$                                                    | [0-7] {1, 3} are one to three octal digits                                                              |
| $Q?,$ where $Q$ is a quantified expression                                | Reluctant quantifier, attempting the shortest match before trying longer matches | .^*(<.+?>).^* captures the shortest sequence enclosed in angle brackets                                 |
| $Q^+,$ where $Q$ is a quantified expression                               | Possessive quantifier, taking the longest match without backtracking             | '[^']*'+ matches strings enclosed in single quotes and fails quickly on strings without a closing quote |

## Boundary Matches

|                |                                                                                       |                                          |
|----------------|---------------------------------------------------------------------------------------|------------------------------------------|
| $^$ $\$$       | Beginning, end of input (or beginning, end of line in multiline mode)                 | $^Java\$$ matches the input or line Java |
| $\A$ $\Z$ $\z$ | Beginning of input, end of input, absolute end of input (unchanged in multiline mode) |                                          |

| Expression | Description                     | Example                        |
|------------|---------------------------------|--------------------------------|
| \b \B      | Word boundary, nonword boundary | \bJava\b matches the word Java |
| \R         | A Unicode line break            |                                |
| \G         | The end of the previous match   |                                |

A `|` denotes an alternative: `.(oo|ee)f` matches `beef` or `woof`. Note the parentheses—without them, `.oo|eef` would be the alternative between `.oo` and `eef`. Parentheses are also used for grouping—see [Section 2.7.4, “Groups,”](#) on p. 151.

A *character class* is a set of character alternatives enclosed in brackets, such as `[Jj]`, `[0-9]`, `[A-Za-z]`, or `[^0-9]`. Inside a character class, the `-` denotes a range (all characters whose Unicode values fall between the two bounds). However, a `-` that is the first or last character in a character class denotes itself. A `^` as the first character in a character class denotes the complement (all characters except those specified).

There are many *predefined character classes* such as `\d` (digits) or `\p{Sc}` (Unicode currency symbols). See [Tables 2.7](#) and [2.8](#).

**Table 2.8** Predefined Character Classes `\p{...}`

| Name                                                                            | Description                                                                                                                                                                                                                     |
|---------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>posixClass</code>                                                         | <code>posixClass</code> is one of Lower, Upper, Alpha, Digit, Alnum, Punct, Graph, Print, Cntrl, XDigit, Space, Blank, ASCII, interpreted as POSIX or Unicode class, depending on the <code>UNICODE_CHARACTER_CLASS</code> flag |
| <code>IsScript,</code><br><code>sc=Script,</code><br><code>script=Script</code> | A script accepted by <code>Character.UnicodeScript.forName(t)</code>                                                                                                                                                            |

| Name                                                                                                                                                          | Description                                                                                                                                                                                            |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>InBlock</code> ,<br><code>blk=Block</code> ,<br><code>block=Block</code>                                                                                | A block accepted by<br><code>Character.UnicodeBlock.forName</code>                                                                                                                                     |
| <code>Category</code> ,<br><code>InCategory</code> ,<br><code>gc=Category</code> ,<br><code>general_ca</code><br><code>tegory=Cat</code><br><code>gory</code> | A one- or two-letter name for a Unicode general category                                                                                                                                               |
| <code>IsProperty</code>                                                                                                                                       | <code>Property</code> is one of Alphabetic, Ideographic, Letter, Lowercase, Uppercase, Titlecase, Punctuation, Control, White_Space, Digit, Hex_Digit, Join_Control, Noncharacter_Code_Point, Assigned |
| <code>javaMethod</code>                                                                                                                                       | Invokes the method <code>Character.isMethod</code> (must not be deprecated)                                                                                                                            |

The characters ^ and \$ match the beginning and end of input.

If you need to have a literal . \* + ? { | ( ) [ \ ^ \$, precede it by a backslash. Inside a character class, you only need to escape [ and \, provided you are careful about the positions of ] - ^-. For example, [ ] ^-] is a class containing all three of them.

Alternatively, surround a string with \Q and \E. For example, \(\$0\.99\) and \Q(\$0.99)\E both match the string (\$0.99).



### Tip

If you have a string that may contain some of the many special characters in the regular expression syntax, you can escape them all by calling `Parse.quote(str)`. This simply surrounds the

string with \Q and \E, but it takes care of the special case where str may contain \E.

---

Unfortunately, the regular expression syntax is not completely standardized between various programs and libraries; there is a consensus on the basic constructs but many maddening differences in the details. The Java regular expression classes use a syntax that is similar to, but not quite the same as, the one used in the Perl language. [Table 2.7](#) shows all constructs of the Java syntax. For more information on the regular expression syntax, consult the API documentation for the `Pattern` class or the book *Mastering Regular Expressions* by Jeffrey E. F. Friedl (O'Reilly and Associates, 2006).

## 2.7.2 Matching an Entire String

Generally, there are two ways to use a regular expression: Either you want to find out whether a string conforms to the expression, or you want to find all matches of a regular expressions in a string.

In the first case, simply use the static `matches` method:

[Click here to view code image](#)

```
String regex = "-]?\d+";
CharSequence input = . . .;
if (Pattern.matches(regex, input))
{
 . . .
}
```

If you need to use the same regular expression many times, it is more efficient to compile it. Then, create a `Matcher` for each input:

[Click here to view code image](#)

```
Pattern pattern = Pattern.compile(regex);
Matcher matcher = pattern.matcher(input);
if (matcher.matches()) . . .
```

If the match succeeds, you can retrieve the location of matched groups—see the following section.

If you want to match elements in a collection or stream, turn the pattern into a predicate:

[Click here to view code image](#)

```
Stream<String> strings = . . .;
List<String> result =
 strings.filter(pattern.asPredicate()).toList();
```

The result contains all strings that contain a match of the regular expression.

To match the entire string, use `pattern.asMatchPredicate()` instead.

### 2.7.3 Finding All Matches in a String

In this section, we consider the other common use case for regular expressions—finding all matches in an input. Use this loop:

[Click here to view code image](#)

```
String input = . . .;
Matcher matcher = pattern.matcher(input);
while (matcher.find())
{
 String match = matcher.group();
 int matchStart = matcher.start();
 int matchEnd = matcher.end();
 . . .
}
```

In this way, you can process each match in turn. As shown in the code fragment, you can get the matched string as well as its position in the input string.

More elegantly, you can call the results method to get a Stream<MatchResult>. The MatchResult interface has methods group, start, and end, just like Matcher. (In fact, the Matcher class implements this interface.) Here is how you get a list of all matches:

[Click here to view code image](#)

```
List<String> matches = pattern.matcher(input)
 .results()
 .map(Matcher::group)
 .toList();
```

If you have the data in a file, then you can use the Scanner.findAll method to get a Stream<MatchResult>, without first having to read the contents into a string. You can pass a Pattern or a pattern string:

[Click here to view code image](#)

```
Scanner in = new Scanner(path, "UTF_8");
Stream<String> words = in.findAll("\\pL+")
 .map(MatchResult::group);
```

**Listing 2.6** puts this mechanism to work. It locates all hypertext references in a web page and prints them. To run the program, supply a URL on the command line, such as

[Click here to view code image](#)

```
java match.HrefMatch http://horstmann.com
```

---

### **Listing 2.6** match/HrefMatch.java

---

[Click here to view code image](#)

```
1 package match;
2
3 import java.io.*;
4 import java.net.*;
5 import java.nio.charset.*;
```

```
6 import java.util.regex.*;
7
8 /**
9 * This program displays all URLs in a web page by matching a
10 * regular expression that
11 * describes the HTML tag. Start the program as

12 * java match.HrefMatch URL
13 * @version 1.04 2019-08-28
14 * @author Cay Horstmann
15 */
16 public class HrefMatch
17 {
18
19 try
20 {
21 // get URL string from command line or use default
22 String urlString;
23 if (args.length > 0) urlString = args[0];
24 else urlString = "http://openjdk.java.net/";
25
26 // read contents of URL
27 InputStream in = new URL(urlString).openStream();
28 var input = new String(in.readAllBytes(),
29 StandardCharsets.UTF_8);
30
31 // search for all occurrences of pattern
32 String patternString = "<a\\s+href\\s*=\\s*(\"[^\""]*\"|"
33 "[^\\s\"]*)\\s*>";
34 Pattern pattern = Pattern.compile(patternString,
35 Pattern.CASE_INSENSITIVE);
36 pattern.matcher(input)
37 .results()
38 .map(MatchResult::group)
39 .forEach(System.out::println);
40 }
41 catch (IOException | PatternSyntaxException e)
```

```
39 {
40 e.printStackTrace();
41 }
42 }
43 }
```

---

## 2.7.4 Groups

It is common to use groups for extracting components of a match. For example, suppose you have a line item in the invoice with item name, quantity, and unit price such as

[Click here to view code image](#)

```
Blackwell Toaster USD29.95
```

Here is a regular expression with groups for each component:

[Click here to view code image](#)

```
(\p{Alnum}+ (\s+ \p{Alnum}+)*) \s+ ([A-Z]{3}) ([0-9.]*)
```

After matching, you can extract the nth group from the matcher as

[Click here to view code image](#)

```
String contents = matcher.group(n);
```

Groups are ordered by their opening parenthesis, starting at 1. (Group 0 is the entire input.) In this example, here is how to take the input apart:

[Click here to view code image](#)

```
Matcher matcher = pattern.matcher(input);
if (matcher.matches())
{
 item = matcher.group(1);

 currency = matcher.group(3);
```

```
 price = matcher.group(4);
}
```

We aren't interested in group 2; it only arose from the parentheses that were required for the repetition. For greater clarity, you can use a noncapturing group:

[Click here to view code image](#)

```
(\p{Alnum}+(:\s+\p{Alnum}+)*)\s+([A-Z]{3})([0-9.]*)
```

Or, even better, capture by name:

[Click here to view code image](#)

```
(?<item>\p{Alnum}+(\s+\p{Alnum}+)*)\s+(?<currency>[A-Z]{3})(?
<price>[0-9.]*)
```

Then, you can retrieve the items by name:

[Click here to view code image](#)

```
item = matcher.group("item");
```

With the `start` and `end` methods, you can get the group positions in the input:

[Click here to view code image](#)

```
int itemStart = matcher.start("item");
int itemEnd = matcher.end("item");
```



## Caution

Retrieving groups by name only works with a `Matcher`, not with a `MatchResult`.

---



## Note

When you have a group inside a repetition, such as `(\s+\p{Alnum}+)*` in the example above, it is not possible to get all of its matches. The `group` method only yields the last match, which is rarely useful. You need to capture the entire expression with another group.

---



## Tip

You can add comments to regular expressions. A comment starts with `#` and extends until the end of the line. This works particularly well with text blocks:

```
var regex = """
([1-9]|1[0-2]) #hours
:([0-5][0-9]) #minutes
[ap]m""";
```

---

[Listing 2.7](#) prompts for a pattern, then for strings to match. It prints out whether or not the input matches the pattern. If the input matches and the pattern contains groups, the program prints the group boundaries as parentheses, for example:

```
((11):(59))am
```

---

### **Listing 2.7** regex/RegexTest.java

---

[Click here to view code image](#)

```
1 package regex;
2
3 /**
4 * This program tests regular expression matching. Enter a
```

```
pattern and strings to match,
5 * or hit Cancel to exit. If the pattern contains groups, the
group boundaries are displayed
6 * in the match.
7 * @version 1.03 2018-05-01
8 * @author Cay Horstmann
9 */
10
11 import java.util.*;
12 import java.util.regex.*;
13
14 public class RegexTest
15 {
16 public static void main(String[] args) throws
PatternSyntaxException
17 {
18 var in = new Scanner(System.in);
19 System.out.println("Enter pattern: ");
20 String patternString = in.nextLine();
21
22 Pattern pattern = Pattern.compile(patternString);
23
24 while (true)
25 {
26 System.out.println("Enter string to match: ");
27 String input = in.nextLine();
28 if (input == null || input.equals("")) return;
29 Matcher matcher = pattern.matcher(input);
30 if (matcher.matches())
31 {
32 System.out.println("Match");
33 int g = matcher.groupCount();
34 if (g > 0)
35 {
36 for (int i = 0; i < input.length(); i++)
37 {
38 // Print any empty groups
39 for (int j = 1; j <= g; j++)
40 {
41 System.out.print(matcher.group(j));
42 }
43 }
44 }
45 }
46 }
47 }
48 }
```

```

40 if (i == matcher.start(j) && i ==
matcher.end(j))
41 System.out.print("()");
42 // Print (for non-empty groups starting
here
43 for (int j = 1; j <= g; j++)
44 if (i == matcher.start(j) && i !=
matcher.end(j))
45 System.out.print('(');
46 System.out.print(input.charAt(i));
47 // Print) for non-empty groups ending here
48 for (int j = 1; j <= g; j++)
49 if (i + 1 != matcher.start(j) && i + 1 ==
matcher.end(j))
50 System.out.print(')');
51 }
52 System.out.println();
53 }
54 }
55 else
56 System.out.println("No match");
57 }
58 }
59 }
```

---

## 2.7.5 Splitting along Delimiters

Sometimes, you want to break an input along matched delimiters and keep everything else. The `Pattern.split` method automates this task. You obtain an array of strings, with the delimiters removed:

[Click here to view code image](#)

```

String input = . . .;
Pattern commas = Pattern.compile("\s*,\s*");
String[] tokens = commas.split(input);
// "1, 2, 3" turns into ["1", "2", "3"]
```

If there are many tokens, you can fetch them lazily:

[Click here to view code image](#)

```
Stream<String> tokens = commas.splitAsStream(input);
```

If you don't care about precompiling the pattern or lazy fetching, you can just use the `String.split` method:

[Click here to view code image](#)

```
String[] tokens = input.split("\s*,\s*");
```

If the input is in a file, use a scanner:

[Click here to view code image](#)

```
Scanner in = new Scanner(path, "UTF_8");
in.useDelimiter("\s*,\s*");
Stream<String> tokens = in.tokens();
```

## 2.7.6 Replacing Matches

If you want to replace all matches of a regular expression with a string, call `replaceAll` on the matcher:

[Click here to view code image](#)

```
Matcher matcher = commas.matcher(input);
String result = matcher.replaceAll(",");
// Normalizes the commas
```

Or, if you don't care about precompiling, use the `replaceAll` method of the `String` class.

[Click here to view code image](#)

```
String result = input.replaceAll("\s*,\s*", ",");
```

The replacement string can contain group numbers `$n` or names `${name}`. They are replaced with the contents of the corresponding captured groups.

[Click here to view code image](#)

```
String result = "3:45".replaceAll(
 "(\\d{1,2}):(?<minutes>\\d{2})",
 "$1 hours and ${minutes} minutes");
// Sets result to "3 hours and 45 minutes"
```

You can use `\` to escape `$` and `\` in the replacement string, or you can call the `Matcher.quoteReplacement` convenience method:

[Click here to view code image](#)

```
matcher.replaceAll(Matcher.quoteReplacement(str))
```

If you want to carry out a more complex operation than splicing in group matches, then you can provide a replacement function instead of a replacement string. The function accepts a `MatchResult` and yields a string. For example, here we replace all words with at least four letters with their uppercase version:

[Click here to view code image](#)

```
String result = Pattern.compile("\\pL{4,}")
.matcher("Mary had a little lamb")
.replaceAll(m -> m.group().toUpperCase());
// Yields "MARY had a LITTLE LAMB"
```

The `replaceFirst` method replaces only the first occurrence of the pattern.

## 2.7.7 Flags

Several *flags* change the behavior of regular expressions. You can specify them when you compile the pattern:

[Click here to view code image](#)

```
Pattern pattern = Pattern.compile(regex,
 Pattern.CASE_INSENSITIVE | Pattern.UNICODE_CHARACTER_CLASS);
```

Or you can specify them inside the pattern:

[Click here to view code image](#)

```
String regex = "(?iU:expression)";
```

Here are the flags:

- `Pattern.CASE_INSENSITIVE` or `i`: Match characters independently of the letter case. By default, this flag takes only US ASCII characters into account.
- `Pattern.UNICODE_CASE` or `u`: When used in combination with `CASE_INSENSITIVE`, use Unicode letter case for matching.
- `Pattern.UNICODE_CHARACTER_CLASS` or `U`: Select Unicode character classes instead of POSIX. Implies `UNICODE_CASE`.
- `Pattern.MULTILINE` or `m`: Make `^` and `$` match the beginning and end of a line, not the entire input.
- `Pattern.UNIX_LINES` or `d`: Only '`\n`' is a line terminator when matching `^` and `$` in multiline mode.
- `Pattern.DOTALL` or `s`: Make the `.` symbol match all characters, including line terminators.
- `Pattern.COMMENTS` or `x`: Whitespace and comments (from `#` to the end of a line) are ignored.
- `Pattern.LITERAL`: The pattern is taken literally and must be matched exactly, except possibly for letter case.
- `Pattern.CANON_EQ`: Take canonical equivalence of Unicode characters into account. For example, `u` followed by `”` (diaeresis) matches `ü`.

The last two flags cannot be specified inside a regular expression.

## **java.util.regex.Pattern 1.4**

- static Pattern compile(String expression)
- static Pattern compile(String expression, int flags)

compile the regular expression string into a pattern object for fast processing of matches. The flags parameter has one or more of the bits CASE\_INSENSITIVE, UNICODE\_CASE, MULTILINE, UNIX\_LINES, DOTALL, and CANON\_EQ set.

- Matcher matcher(CharSequence input)

returns a matcher object that you can use to locate the matches of the pattern in the input.

- String[] split(CharSequence input)
- String[] split(CharSequence input, int limit)
- Stream<String> splitAsStream(CharSequence input) 8

split the input string into tokens, with the pattern specifying the form of the delimiters. Return an array or stream of tokens. The delimiters are not part of the tokens. The second form has a parameter limit denoting the maximum number of strings to produce. If limit - 1 matching delimiters have been found, then the last entry of the returned array contains the remaining unsplit input. If limit is  $\leq 0$ , then the entire input is split. If limit is 0, then trailing empty strings are not placed in the returned array.

## **java.util.regex.Matcher 1.4**

- `boolean matches()`  
returns `true` if the input matches the pattern.
- `boolean lookingAt()`  
returns `true` if the beginning of the input matches the pattern.
- `boolean find()`
- `boolean find(int start)`  
attempt to find the next match and return `true` if another match is found.
- `int start()`
- `int end()`  
return the start or past-the-end position of the current match.
- `String group()`  
returns the current match.
- `int groupCount()`  
returns the number of groups in the input pattern.
- `int start(int groupIndex)`
- `int start(String name) 8`
- `int end(int groupIndex)`
- `int end(String name) 8`  
return the start or past-the-end position of a group in the current match. The group is specified by an index starting with 1, or 0 to indicate the entire match, or by a string identifying a named group.
- `String group(int groupIndex)`

- `String group(String name)` 7  
return the string matching a given group, denoted by an index starting with 1, or 0 to indicate the entire match, or by a string identifying a named group.
- `String replaceAll(String replacement)`
- `String replaceFirst(String replacement)`  
return a string obtained from the matcher input by replacing all matches, or the first match, with the replacement string. The replacement string can contain references to pattern groups as `$n`. Use `\$` to include a `$` symbol.
- `static String quoteReplacement(String str)` 5.0  
quotes all `\` and `$` in `str`.
- `String replaceAll(Function<MatchResult, String> replacer)` 9  
replaces every match with the result of the `replacer` function applied to the `MatchResult`.
- `Stream<MatchResult> results()` 9  
yields a stream of all match results.

## **`java.util.regex.MatchResult`** 5

- `String group()`
- `String group(int group)`  
yield the matched string or the string matched by the given group.
- `int start()`

- int end()
- int start(int group)
- int end(int group)

yield the start and end offsets of the matched string or the string matched by the given group.

### **java.util.Scanner 5.0**

- Stream<MatchResult> findAll(Pattern pattern)  
9

yields a stream of all matches of the given pattern in the input produced by this scanner.

You have now seen how to carry out input and output operations in Java, and had an overview of the regular expression package that was a part of the “new I/O” specification. In the next chapter, we turn to the processing of XML data.

---

# Chapter 3. XML

---

## In this chapter

- [3.1 Introducing XML](#)
- [3.2 The Structure of an XML Document](#)
- [3.3 Parsing an XML Document](#)
- [3.4 Validating XML Documents](#)
- [3.5 Locating Information with XPath](#)
- [3.6 Using Namespaces](#)
- [3.7 Streaming Parsers](#)
- [3.8 Generating XML Documents](#)
- [3.9 XSL Transformations](#)

The preface of the book *Essential XML* by Don Box et al. (Addison-Wesley, 2000) stated only half-jokingly: “The Extensible Markup Language (XML) has replaced Java, Design Patterns, and Object Technology as the software industry’s solution to world hunger.” This kind of hype is long gone but, as you will see in this chapter, XML is still a very useful technology for describing structured information. XML tools make it easy to process and transform that information. However, XML is not a silver bullet. You need domain-specific standards and code libraries to use it effectively. Moreover, far from making Java obsolete, XML works very well with Java. Since the late 1990s, IBM, Apache, and others have been instrumental in producing high-quality Java libraries for XML processing. Many of these libraries have now been integrated into the Java platform.

This chapter introduces XML and covers the XML features of the Java library. As always, we'll point out along the way when using XML is justified—and when you have to take it with a grain of salt and try solving your problems the old-fashioned way: through good design and code.

## 3.1 Introducing XML

In [Chapter 9](#) of Volume I, you have seen the use of *property files* to describe the configuration of a program. A property file contains a set of name/value pairs, such as

```
fontname=Times Roman
fontsize=12
windowsize=400 200
color=0 50 100
```

You can use the `Properties` class to read in such a file with a single method call. That's a nice feature, but it doesn't really go far enough. In many cases, the information you want to describe has more structure than the property file format can comfortably handle. Consider the `fontname`/`fontsize` entries in the example. It would be more object-oriented to have a single entry:

```
font=Times Roman 12
```

But then, parsing the font description gets ugly as you have to figure out when the font name ends and the font size starts.

Property files have a single flat hierarchy. You can often see programmers work around that limitation with key names like

```
title.fontname=Helvetica
title.fontsize=36
body.fontname=Times Roman
body.fontsize=12
```

Another shortcoming of the property file format is the requirement that keys must be unique. To store a sequence of values, you need another workaround, such as

```
menu.item.1=Times Roman
menu.item.2=Helvetica
menu.item.3=Goudy Old Style
```

The XML format solves these problems. It can express hierarchical structures and is thus more flexible than the flat table structure of a property file.

An XML file for describing a program configuration might look like this:

```
<config>
 <entry id="title">

 <name>Helvetica</name>
 <size>36</size>

 </entry>
 <entry id="body">

 <name>Times Roman</name>
 <size>12</size>

 </entry>
 <entry id="background">
 <color>
 <red>0</red>
 <green>50</green>
 <blue>100</blue>
 </color>
 </entry>
</config>
```

[Click here to view code image](#)

The XML format allows you to express the hierarchy and record repeated elements without contortions.

The format of an XML file is straightforward. It looks similar to an HTML file. There is a good reason for that—both XML and HTML are descendants of the venerable Standard Generalized Markup Language (SGML).

SGML has been around since the 1970s for describing the structure of complex documents. It has been used with success in some industries that require ongoing maintenance of massive documentation—in particular, the aircraft industry. However, SGML is quite complex, so it has never caught on in a big way. Much of that complexity arises because SGML has two conflicting goals. SGML wants to make sure that documents are formed according to the rules for their document type, but it also wants to make data entry easy by allowing shortcuts that reduce typing. XML was designed as a simplified version of SGML for use on the Internet. As is often true, simpler is better, and XML has enjoyed the immediate and enthusiastic reception that has eluded SGML for so long.

---



## Note

You can find a very nice version of the XML standard, with annotations by Tim Bray, at [www.xml.com/axml/axml.html](http://www.xml.com/axml/axml.html).

---

Even though XML and HTML have common roots, there are important differences between the two.

- Unlike HTML, XML is case-sensitive. For example, `<H1>` and `<h1>` are different XML tags.
- In HTML, you can omit end tags, such as `</p>` or `</li>`, if it is clear from the context where a paragraph or list item ends. In XML, you can never omit an end tag.
- In XML, elements that have a single tag without a matching end tag must end in a `/`, as in ``. That way, the parser knows not to look for a `</img>` tag.
- In XML, attribute values must be enclosed in quotation marks. In HTML, quotation marks are optional. For example, `` is legal HTML but not legal XML. In XML, you have to use quotation marks: `width="300"`.
- In HTML, you can have attribute names without values, such as `<input type="radio" name="language" value="Java" checked>`. In XML, all attributes must have values, such as `checked="true"` or (ugh) `checked="checked"`.

- There are XML formulations for HTML versions 4 and 5 that are known as XHTML.

## 3.2 The Structure of an XML Document

An XML document should start with a header such as

```
<?xml version="1.0"?>
```

or

```
<?xml version="1.0" encoding="UTF-8"?>
```

[Click here to view code image](#)

Strictly speaking, a header is optional, but it is highly recommended.

---



### Note

Since SGML was created for processing of real documents, XML files are called *documents* even though many of them describe data sets that one would not normally call documents.

---

The header can be followed by a *document type definition* (DTD), such as

[Click here to view code image](#)

```
<!DOCTYPE web-app PUBLIC
 "-//Sun Microsystems, Inc.//DTD Web Application 2.2//EN"
 "http://java.sun.com/j2ee/dtds/web-app_2_2.dtd">
```

DTDs are an important mechanism to ensure the correctness of a document, but they are not required. We will discuss them later in this chapter.

Finally, the body of the XML document contains the *root element*, which can contain other elements. For example,

```
<?xml version="1.0"?>
<!DOCTYPE config . . .>
<config>
 <entry id="title">

 <name>Helvetica</name>
 <size>36</size>

 </entry>
 . . .
</config>
```

An element can contain *child elements*, text, or both. In the preceding example, the `font` element has two child elements, `name` and `size`. The `name` element contains the text "Helvetica".

---



### Tip

It is best to structure your XML documents so that an element contains *either* child elements *or* text. Here's an example of what you should avoid:

```

 Helvetica
 <size>36</size>

```

This is called *mixed content* in the XML specification. As you will see later in this chapter, you can simplify parsing if you avoid mixed content.

---

XML elements can contain attributes, such as

```
<size unit="pt">36</size>
```

There is some disagreement among XML designers about when to use elements and when to use attributes. For example, it would seem easier to describe a font as

[Click here to view code image](#)

```

```

compared to

```

 <name>Helvetica</name>
 <size>36</size>

```

However, attributes are much less flexible. Suppose you want to add units to the size value. If you use attributes, you will have to add the unit to the attribute value:

[Click here to view code image](#)

```

```

Ugh! Now you have to parse the string "36 pt", just the kind of hassle that XML was designed to avoid. Adding an attribute to the size element is much cleaner:

```

 <name>Helvetica</name>
 <size unit="pt">36</size>

```

A commonly used rule of thumb is that attributes should be used only to modify the interpretation of a value, not to specify values. If you find yourself engaged in a metaphysical discussion about whether a particular setting is a modification of the interpretation of a value or not, just say "no" to attributes and use elements throughout. Many useful XML documents don't use attributes at all.



### Note

In HTML, the rule for attribute usage is simple: If it isn't displayed on the web page, it's an attribute. For example, consider the hyperlink

[Click here to view code image](#)

```
Java Technology
```

The string Java Technology is displayed on the web page, but the URL of the link is not a part of the displayed page. However, the rule isn't all that helpful for most XML files because the data in an XML file aren't normally meant to be viewed by humans.

---

Elements and text are the "bread and butter" of XML documents. Here are a few other markup instructions that you might encounter:

- *Character references* have the form &#decimalValue; or &#xhexValue;. For example, the é character can be denoted with either of the following:  
é &#233; &#xE9;
- *Entity references* have the form &name;. The entity references  
&lt; &gt; &amp; &quot; &apos;

have predefined meanings: the less-than, greater-than, ampersand, quotation mark, and apostrophe characters. You can define other entity references in a DTD.

- *CDATA sections* are delimited by <! [CDATA [ and ] ]>. They are a special form of character data. You can use them to include strings that contain characters such as < > & without having them interpreted as markup, for example:

[Click here to view code image](#)

```
<! [CDATA[< > are my favorite delimiters]]>
```

CDATA sections cannot contain the string ] ]>. Use this feature with caution! It is too often used as a back door for smuggling legacy data into XML documents.

- *Processing instructions* are instructions for applications that process XML documents. They are delimited by <? and ?>, for example

[Click here to view code image](#)

```
<?xml-stylesheet href="mystyle.css" type="text/css"?>
```

Every XML document starts with a processing instruction

```
<?xml version="1.0"?>
```

- *Comments* are delimited by `<!--` and `-->`, for example

```
<!-- This is a comment. -->
```

Comments should not contain the string `--`. Comments should only be information for human readers. They should never contain hidden commands; use processing instructions for commands.

### 3.3 Parsing an XML Document

To process an XML document, you need to *parse* it. A parser is a program that reads a file, confirms that the file has the correct format, breaks it up into the constituent elements, and lets a programmer access those elements. The Java library supplies two kinds of XML parsers:

- Tree parsers, such as a Document Object Model (DOM) parser, that read an XML document into a tree structure.
- Streaming parsers, such as a Simple API for XML (SAX) parser, that generate events as they read an XML document.

DOM parsers are easier to use for most purposes, so we explain them first. You may consider a streaming parser if you process very long documents whose tree structures would use up a lot of memory, or if you are only interested in a few elements and don't care about their context. For more information, see [Section 3.7, “Streaming Parsers,”](#) on p. 203.

The DOM parser interface is standardized by the World Wide Web Consortium (W3C). The `org.w3c.dom` package contains the definitions of interface types such as `Document` and `Element`. Different suppliers, such as the Apache Organization and IBM, have written DOM parsers whose classes implement these interfaces. The Java API for XML Processing (JAXP) library actually makes it possible to plug in any of these parsers. But the JDK also comes with a DOM parser that is derived from the Apache parser.

To read an XML document, you need a `DocumentBuilder` object that you get from a `DocumentBuilderFactory` like this:

[Click here to view code image](#)

```
DocumentBuilderFactory factory =
DocumentBuilderFactory.newInstance();
DocumentBuilder builder = factory.newDocumentBuilder();
```

You can now read a document from a file:

[Click here to view code image](#)

```
File f = . . .;
Document doc = builder.parse(f);
```

Alternatively, you can use a URL:

[Click here to view code image](#)

```
URL u = . . .;
Document doc = builder.parse(u.toString());
```

You can even specify an arbitrary input stream:

[Click here to view code image](#)

```
InputStream in = . . .;
Document doc = builder.parse(in);
```

---




## Note

If you use an input stream as an input source, the parser will not be able to locate other files that are referenced relative to the location of the document, such as a DTD in the same directory. You can install an "entity resolver" to overcome that problem. See  
[www.xml.com/pub/a/2004/03/03/catalogs.html](http://www.xml.com/pub/a/2004/03/03/catalogs.html) or  
[www.ibm.com/developerworks/xml/library/x-mxd3.html](http://www.ibm.com/developerworks/xml/library/x-mxd3.html) for more information.

---

A Document object is an in-memory representation of the tree structure of an XML document. It is composed of objects whose classes implement the Node interface and its various subinterfaces. Figure 3.1 shows the inheritance hierarchy of the subinterfaces.



**Figure 3.1** The Node interface and its subinterfaces

Start analyzing the contents of a document by calling the `getDocumentElement` method. It returns the root element.

[Click here to view code image](#)

```
Element root = doc.getDocumentElement();
```

For example, if you are processing a document

```
<?xml version="1.0"?>

```

```
 . . .

```

then calling `getDocumentElement` returns the `font` element.

The `getTagName` method returns the tag name of an element. In the preceding example, `root.getTagName()` returns the string "font".

To get an element's children (which may be subelements, text, comments, or other nodes), use the `getChildNodes` method. That method returns a collection of type `NodeList`. That type was standardized before the standard Java collections, so it has a different access protocol. The `item` method gets the item with a given index, and the `getLength` method gives the total count of the items. You can enumerate all children like this:

[Click here to view code image](#)

```
NodeList children = root.getChildNodes();
for (int i = 0; i < children.getLength(); i++)
{
 Node child = children.item(i);
 . . .
}
```

Be careful when analyzing children. Suppose, for example, that you are processing the document

```

 <name>Helvetica</name>
 <size>36</size>


```

You would expect the `font` element to have two children, but the parser reports five:

- The whitespace between `<font>` and `<name>`
- The `name` element
- The whitespace between `</name>` and `<size>`
- The `size` element

- The whitespace between `</size>` and `</font>`

[Figure 3.2](#) shows the DOM tree.



**Figure 3.2** A simple DOM tree

If you expect only subelements, you can ignore the whitespace:

[Click here to view code image](#)

```

for (int i = 0; i < children.getLength(); i++)
{
 Node child = children.item(i);
 if (child instanceof Element childElement)
 {
 . . .
 }
}

```

Now you look at only two elements, with tag names `name` and `size`.

As you will see in the next section, you can do even better if your document has a DTD. Then the parser knows which elements don't have text nodes as children, and it can suppress the whitespace for you.

When analyzing the `name` and `size` elements, you want to retrieve the text strings that they contain. Those text strings are themselves contained in child nodes of type `Text`. You know that these `Text` nodes are the only children, so you can use the `getFirstChild` method without having to traverse another `NodeList`. Then, use the `getData` method to retrieve the string stored in a `Text` node:

[Click here to view code image](#)

```
for (int i = 0; i < children.getLength(); i++)
{
 Node child = children.item(i);
 if (child instanceof Element childElement)
 {
 var textNode = (Text) childElement.getFirstChild();
 String text = textNode.getData().strip();
 if (childElement.getTagName().equals("name"))
 name = text;
 else if (childElement.getTagName().equals("size"))
 size = Integer.parseInt(text);
 }
}
```



### Tip

It is a good idea to call `trim` on the return value of the `getData` method. If the author of an XML file puts the beginning and the ending tags on separate lines, such as

```
<size>
 36
</size>
```

then the parser will include all line breaks and spaces in the text node data. Calling the `trim` method removes the whitespace surrounding the actual data.

---

You can also get the last child with the `getLastChild` method, and the next sibling of a node with `getNextSibling`. Therefore, another way of traversing a node's children is

[Click here to view code image](#)

```
for (Node childNode = element.getFirstChild();
 childNode != null;
 childNode = childNode.getNextSibling())
{
 . . .
}
```

To enumerate the attributes of a node, call the `getAttributes` method. It returns a `NamedNodeMap` object that contains `Node` objects describing the attributes. You can traverse the nodes in a `NamedNodeMap` the same way as in a `NodeList`. Then, call the `getNodeName` and `getNodeValue` methods to get the attribute names and values.

[Click here to view code image](#)

```
NamedNodeMap attributes = element.getAttributes();
for (int i = 0; i < attributes.getLength(); i++)
{
 Node attribute = attributes.item(i);
 String name = attribute.getNodeName();
 String value = attribute.getNodeValue();
 . . .
}
```

Alternatively, if you know the name of an attribute, you can retrieve the corresponding value directly:

[Click here to view code image](#)

```
String unit = element.getAttribute("unit");
```

You have now seen how to analyze a DOM tree. The program in Listing 3.1 puts these techniques to work by converting an XML document to JSON format.

The tree display clearly shows how child elements are surrounded by text containing whitespace and comments. You can clearly see the newline and return characters as \n.

You don't have to be familiar with JSON to understand how the program works with the DOM tree. Simply observe the following:

- We use a `DocumentBuilder` to read a `Document` from a file.
- For each element, we print the tag name, attributes, and elements.
- For character data, we produce a string with the data. If the data comes from a comment, we add a "Comment :" prefix.

---

**Listing 3.1** dom/JSONConverter.java

---

[Click here to view code image](#)

```
1 package dom;
2
3 import java.io.*;
4 import java.util.*;
5
6 import javax.xml.parsers.*;
7
8 import org.w3c.dom.*;
9 import org.xml.sax.*;
10
11 /**
12 * This program displays an XML document as a tree in JSON
13 * format.
14 * @version 1.21 2021-05-30
15 * @author Cay Horstmann
16 */
17 public class JSONConverter
18 {
19 public static void main(String[] args)
20 throws SAXException, IOException,
```

```
ParserConfigurationException
20 {
21 String filename;
22 if (args.length == 0)
23 {
24 try (var in = new Scanner(System.in))
25 {
26 System.out.print("Input file: ");
27 filename = in.nextLine();
28 }
29 }
30 else
31 filename = args[0];
32 DocumentBuilderFactory factory =
33 DocumentBuilderFactory.newInstance();
34
35 Document doc = builder.parse(filename);
36 Element root = doc.getDocumentElement();
37 System.out.println(convert(root, 0));
38 }
39
40 public static StringBuilder convert(Node node, int level)
41 {
42 if (node instanceof Element elem)
43 {
44 return elementObject(elem, level);
45 }
46 else if (node instanceof CharacterData cd)
47 {
48 return characterString(cd, level);
49 }
50 else
51 {
52 return pad(new StringBuilder(), level).append(
53 jsonEscape(node.getClass().getName()));
54 }
55 }
56
57 private static Map<Character, String> replacements =
```

```
Map.of('\b', "\\b", '\f', "\\f",
58 '\n', "\\n", '\r', "\\r", '\t', "\\t", '\"', "\\\"", '\\',
"\\\\\\");
59
60 private static StringBuilder jsonEscape(String str)
61 {
62 var result = new StringBuilder("\\\"");
63 for (int i = 0; i < str.length(); i++)
64 {
65 char ch = str.charAt(i);
66 String replacement = replacements.get(ch);
67 if (replacement == null) result.append(ch);
68 else result.append(replacement);
69 }
70 result.append("\\\"");
71 return result;
72 }
73
74 private static StringBuilder characterString(CharacterData
node, int level)
75 {
76 var result = new StringBuilder();
77 StringBuilder data = jsonEscape(node.getData());
78 if (node instanceof Comment) data.insert(1, "Comment: ");
79 pad(result, level).append(data);
80 return result;
81 }
82
83 private static StringBuilder elementObject(Element elem, int
level)
84 {
85 var result = new StringBuilder();
86 pad(result, level).append("{\\n");
87 pad(result, level + 1).append("\\\"name\\\": ");
88 result.append(jsonEscape(elem.getTagName()));
89 NamedNodeMap attrs = elem.getAttributes();
90 if (attrs.getLength() > 0)
91 {
92 pad(result.append(",\\n"), level +
```

```
1).append("\"attributes\": \"");
93 result.append(attributeObject(attrs));
94 }
95 NodeList children = elem.getChildNodes();
96 if (children.getLength() > 0)
97 {
98 pad(result.append(",\n"), level +
1).append("\"children\": [\n");
99 for (int i = 0; i < children.getLength(); i++)
100 {
101 if (i > 0) result.append(",\n");
102 result.append(convert(children.item(i), level + 2));
103 }
104 result.append("\n");
105 pad(result, level + 1).append("]\n");
106 }
107 pad(result, level).append("}");
108 return result;
109 }
110
111 private static StringBuilder pad(StringBuilder builder, int
level)
112 {
113 for (int i = 0; i < level; i++) builder.append(" ");
114 return builder;
115 }
116
117 private static StringBuilder attributeObject(NamedNodeMap
attrs)
118 {
119 var result = new StringBuilder("{}");
120 for (int i = 0; i < attrs.getLength(); i++)
121 {
122 if (i > 0) result.append(", ");
123
result.append(jsonEscape(attrs.item(i).getNodeName()));
124 result.append(": ");
125
result.append(jsonEscape(attrs.item(i).getNodeValue()));


```

```
126 }
127 result.append("}");
128 return result;
129 }
130 }
```

---

#### **javax.xml.parsers.DocumentBuilderFactory 1.4**

- static DocumentBuilderFactory newInstance()  
returns an instance of the DocumentBuilderFactory class.
- DocumentBuilder newDocumentBuilder()  
returns an instance of the DocumentBuilder class.

#### **javax.xml.parsers.DocumentBuilder 1.4**

- Document parse(File f)
- Document parse(String url)
- Document parse(InputStream in)  
parse an XML document from the given file, URL, or input stream and  
return the parsed document.

#### **org.w3c.dom.Document 1.4**

- Element getDocumentElement()  
returns the root element of the document.

## ***org.w3c.dom.Element*** 1.4

- `String getTagName()`  
returns the name of the element.
- `String getAttribute(String name)`  
returns the value of the attribute with the given name, or an empty string if there is no such attribute.

## ***org.w3c.dom.Node*** 1.4

- `NodeList getChildNodes()`  
returns a node list that contains all children of this node.
- `Node getFirstChild()`
- `Node getLastChild()`  
get the first or last child node of this node, or `null` if this node has no children.
- `Node getNextSibling()`
- `Node getPreviousSibling()`  
get the next or previous sibling of this node, or `null` if this node has no siblings.
- `Node getParentNode()`  
gets the parent of this node, or `null` if this node is the document node.
- `NamedNodeMap getAttributes()`  
returns a node map that contains `Attr` nodes that describe all attributes of this node.

- `String getNodeName()`  
returns the name of this node. If the node is an `Attr` node, the name is the attribute name.
- `String getNodeValue()`  
returns the value of this node. If the node is an `Attr` node, the value is the attribute value.

#### ***org.w3c.dom.CharacterData 1.4***

- `String getData()`  
returns the text stored in this node.

#### ***org.w3c.dom.NodeList 1.4***

- `int getLength()`  
returns the number of nodes in this list.
- `Node item(int index)`  
returns the node with the given index. The index is between 0 and `getLength() - 1`.

#### ***org.w3c.dom.NamedNodeMap 1.4***

- `int getLength()`  
returns the number of nodes in this map.

- `Node item(int index)`  
returns the node with the given index. The index is between 0 and `getLength()` – 1.

## 3.4 Validating XML Documents

In the previous section, you saw how to traverse the tree structure of a DOM document. However, with that approach, you'll have to do quite a bit of tedious programming and error checking. It's not just having to deal with whitespace between elements; you will also need to check whether the document contains the nodes that you expect. For example, suppose you are reading this element:

```

 <name>Helvetica</name>
 <size>36</size>

```

You get the first child. Oops . . . it is a text node containing whitespace "\n". You skip text nodes and find the first element node. Then, you need to check that its tag name is "name" and that it has one child node of type Text. You move on to the next nonwhitespace child and make the same check. What if the author of the document switched the order of the children or added another child element? It is tedious to code all this error checking—but reckless to skip the checks.

Fortunately, one of the major benefits of an XML parser is that it can automatically verify that a document has the correct structure. That makes parsing much simpler. For example, if you know that the `font` fragment has passed validation, you can simply get the two grandchildren, cast them as `Text` nodes, and get the text data, without any further checking.

To specify the document structure, you can supply a DTD or an XML Schema definition. A DTD or schema contains rules that explain how a document should be formed, by specifying the legal child elements and attributes for each element. For example, a DTD might contain a rule:

```
<!ELEMENT font (name,size)>
```

This rule expresses that a `font` element must always have two children, which are `name` and `size` elements. The XML Schema language expresses the same constraint as

[Click here to view code image](#)

```
<xsd:element name="font">
 <xsd:sequence>
 <xsd:element name="name" type="xsd:string"/>
 <xsd:element name="size" type="xsd:int"/>
 </xsd:sequence>
</xsd:element>
```

XML Schema can express more sophisticated validation conditions (such as the fact that the `size` element must contain an integer) than can DTDs. Unlike the DTD syntax, the XML Schema syntax itself uses XML, which is a benefit if you need to process schema files.

In the next section, we will discuss DTDs in detail, then briefly cover the basics of XML Schema support. Finally, we will present a complete application that demonstrates how validation simplifies XML programming.

### 3.4.1 Document Type Definitions

There are several methods for supplying a DTD. You can include a DTD in an XML document like this:

```
<?xml version="1.0"?>
<!DOCTYPE config [
 <!ELEMENT config . . .>
 more rules
 . . .
]>
<config>
 . . .
</config>
```

As you can see, the rules are included inside a DOCTYPE declaration, in a block delimited by [ . . . ]. The document type must match the name of the root element, such as config in our example.

Supplying a DTD inside an XML document is somewhat uncommon because DTDs can grow lengthy. It makes more sense to store the DTD externally. The SYSTEM declaration can be used for that purpose. Specify a URL that contains the DTD, for example:

[Click here to view code image](#)

```
<!DOCTYPE config SYSTEM "config.dtd">
```

or

[Click here to view code image](#)

```
<!DOCTYPE config SYSTEM "http://myserver.com/config.dtd">
```

---



## Caution

If you use a relative URL for the DTD (such as "config.dtd"), give the parser a File or URL object, not an InputStream. If you must parse from an input stream, supply an entity resolver (see the following note).

---

The mechanism for identifying well-known DTDs has its origin in SGML. Here is an example:

[Click here to view code image](#)

```
<!DOCTYPE web-app
PUBLIC "-//Sun Microsystems, Inc.//DTD Web Application 2.2//EN"
"http://java.sun.com/j2ee/dtds/web-app_2_2.dtd">
```

If an XML processor knows how to locate the DTD with the public identifier, it need not go to the URL.



## Note

The system identifier URL of a DTD may not actually be working, or be purposefully slowed down. An example for the latter is the system identifier of the XHTML 1.0 Strict DTD,

<http://www.w3.org/TR/xhtml1/DTD/xhtml1-strict.dtd>. If you parse an XHTML file, it may take a minute or two for the DTD to be served.

The remedy is to use an *entity resolver* that maps public identifiers to local files. Prior to Java 9, you had to provide an object of a class that implements the EntityResolver interface and provides a resolveEntity method.

Nowadays, you can use *XML catalogs* to manage the mapping. Provide one or more *catalog files* of the form

[Click here to view code image](#)

```
<?xml version="1.0"?>
<!DOCTYPE catalog PUBLIC "-//OASIS//DTD XML Catalogs V1.0//EN"
 "http://www.oasis-
open.org/committees/entity/release/1.0/catalog.dtd">
<catalog xmlns="urn:oasis:names:tc:entity:xmlns:xml:catalog"
prefer="public">
 <public publicId=". . ." uri=". . ."/>
 . . .
</catalog>
```

Then construct and install a resolver like this:

[Click here to view code image](#)

```
builder.setEntityResolver(CatalogManager.catalogResolver(
 CatalogFeatures.defaults(),
 Path.of("catalog.xml").toAbsolutePath().toUri()));
```

See [Listing 3.6](#) for a complete example.

Instead of setting the catalog file locations in your program, you can specify them on the command line with the `javax.xml.catalog.files` system property. Provide absolute file URLs separated by semicolons.

---

Now that you have seen how the parser locates the DTD, let us consider the various kinds of rules.

The ELEMENT rule specifies what children an element can have. Use a regular expression, made up of the components shown in [Table 3.1](#).

**Table 3.1** Rules for Element Content

Rule	Meaning
$E^*$	0 or more occurrences of $E$
$E^+$	1 or more occurrences of $E$
$E^?$	0 or 1 occurrences of $E$
$E_1   E_2   \dots   E_n$	One of $E_1, E_2, \dots, E_n$
$E_1, E_2, \dots, E_n$	$E_1$ followed by $E_2, \dots, E_n$
#PCDATA	Text
(#PCDATA   $E_1   E_2   \dots   E_n$ ) *	0 or more occurrences of text and $E_1, E_2, \dots, E_n$ in any order (mixed content)
ANY	Any children allowed
EMPTY	No children allowed

Here are several simple but typical examples. The following rule states that a `menu` element contains 0 or more `item` elements:

```
<!ELEMENT menu (item)*>
```

This set of rules states that a font is described by a `name` followed by a `size`, each of which contain text:

```
<!ELEMENT font (name,size)>
<!ELEMENT name (#PCDATA)>
```

```
<!ELEMENT size (#PCDATA)>
```

The abbreviation PCDATA denotes *parsed character data*. It is "parsed" because the parser interprets the text string, looking for < characters that denote the start of a new tag, or & characters that denote the start of an entity.

An element specification can contain regular expressions that are nested and complex. For example, here is a rule that describes the makeup of a chapter in a book:

[Click here to view code image](#)

```
<!ELEMENT chapter (intro, (heading, (para|image|table|note)+)++)
```

Each chapter starts with an introduction, which is followed by one or more sections consisting of a heading and one or more paragraphs, images, tables, or notes.

However, in one common case you can't define the rules to be as flexible as you might like. Whenever an element can contain text, there are only two valid cases. Either the element contains nothing but text, such as

```
<!ELEMENT name (#PCDATA)>
```

or the element contains *any combination of text and tags in any order*, such as

[Click here to view code image](#)

```
<!ELEMENT para (#PCDATA|em|strong|code)*>
```

It is not legal to specify any other types of rules that contain #PCDATA. For example, the following is illegal:

[Click here to view code image](#)

```
<!ELEMENT captionedImage (image, #PCDATA)>
```

You have to rewrite such a rule, either by introducing another caption element or by allowing any combination of image elements and text.

This restriction simplifies the job of the XML parser when parsing *mixed content* (a mixture of tags and text). Since you lose some control by allowing

mixed content, it is best to design DTDs so that all elements contain either other elements or nothing but text.

---



## Note

Actually, it isn't quite true that you can specify arbitrary regular expressions of elements in a DTD rule. An XML parser may reject certain complex rule sets that lead to nondeterministic parsing. For example, a regular expression  $((x, y) \mid (x, z))$  is nondeterministic. When the parser sees  $x$ , it doesn't know which of the two alternatives to take. This expression can be rewritten in a deterministic form as  $(x, (y \mid z))$ . However, some expressions can't be reformulated, such as  $((x, y)^* \mid x?)$ . The parser in the Java XML library gives no warnings when presented with an ambiguous DTD; it simply picks the first matching alternative when parsing, which causes it to reject some correct inputs. The parser is well within its rights to do so because the XML standard allows a parser to assume that the DTD is unambiguous.

---

You can also specify rules to describe the legal attributes of elements. The general syntax is

`<!ATTLIST element attribute type default>`

[Table 3.2](#) shows the legal attribute types, and [Table 3.3](#) shows the syntax for the defaults.

**Table 3.2** Attribute Types

Type	Meaning
CDATA	Any character string
$(A_1 \mid A_2 \mid \dots \mid A_n)$	One of the string attributes $A_1, A_2, \dots, A_n$
NMTOKEN, NMTOKENS	One or more name tokens
ID	A unique ID
IDREF, IDREFS	One or more references to a unique ID

Type	Meaning
ENTITY, ENTITIES	One or more unparsed entities

**Table 3.3** Attribute Defaults

Default	Meaning
#REQUIRED	Attribute is required.
#IMPLIED	Attribute is optional.
<i>A</i>	Attribute is optional; the parser reports it to be <i>A</i> if it is not specified.
#FIXED <i>A</i>	The attribute must either be unspecified or <i>A</i> ; in either case, the parser reports it to be <i>A</i> .

Here are two typical attribute specifications:

[Click here to view code image](#)

```
<!ATTLIST font style (plain|bold|italic|bold-italic) "plain">
<!ATTLIST size unit CDATA #IMPLIED>
```

The first specification describes the `style` attribute of a `font` element. There are four legal attribute values, and the default value is `plain`. The second specification expresses that the `unit` attribute of the `size` element can contain any character data sequence.



### Note

It is generally recommended the use of elements, not attributes, to describe data. Thus, the font style should be a separate element, such as `<font><style>plain</style>...</font>`.

However, attributes have an undeniable advantage for enumerated types because the parser can verify that the values are legal. For example, if the font style is an attribute, the parser checks that it is

one of the four allowed values, and supplies a default if no value was given.

---

The handling of a CDATA attribute value is subtly different from the processing of #PCDATA that you have seen before, and quite unrelated to the <! [CDATA[ . . . ]]> sections. The attribute value is first *normalized*—that is, the parser processes character and entity references (such as &#233; or &lt;) and replaces whitespace with spaces.

An NMOKEN (or name token) is similar to CDATA, but most nonalphanumeric characters and internal whitespace are disallowed, and the parser removes leading and trailing whitespace. NMOKENS is a whitespace-separated list of name tokens.

The ID construct is quite useful. An ID is a name token that must be unique in the document—the parser checks the uniqueness. You will see an application in the next sample program. An IDREF is a reference to an ID that exists in the same document, which the parser also checks. IDREFS is a whitespace-separated list of ID references.

An ENTITY attribute value refers to an "unparsed external entity." That is a holdover from SGML that is rarely used in practice. The annotated XML specification at [www.xml.com/axml/axml.html](http://www.xml.com/axml/axml.html) has an example.

A DTD can also define *entities*, or abbreviations that are replaced during parsing. You can find a good example for the use of entities in the user interface descriptions of the Firefox browser. Those descriptions are formatted in XML and contain entity definitions such as

```
<!ENTITY back.label "Back">
```

Elsewhere, text can contain an entity reference, for example:

[Click here to view code image](#)

```
<menuitem label="&back.label;"/>
```

The parser replaces the entity reference with the replacement string. To internationalize the application, only the string in the entity definition needs to

be changed. Other uses of entities are more complex and less common; look at the XML specification for details.

This concludes the introduction to DTDs. Now that you have seen how to use DTDs, you can configure your parser to take advantage of them.

First, tell the document builder factory to turn on validation:

```
factory.setValidating(true);
```

All builders produced by this factory validate their input against a DTD. The most useful benefit of validation is ignoring whitespace in element content. For example, consider the XML fragment

```

 <name>Helvetica</name>
 <size>36</size>

```

A nonvalidating parser reports the whitespace between the `font`, `name`, and `size` elements because it has no way of knowing if the children of `font` are

```
(name, size)
(#PCDATA, name, size) *
```

or perhaps

ANY

Once the DTD specifies that the children are `(name, size)`, the parser knows that the whitespace between them is not text. Call

[Click here to view code image](#)

```
factory.setIgnoringElementContentWhitespace(true);
```

and the builder will stop reporting the whitespace in text nodes. That means you can now *rely on* the fact that a `font` node has two children. You no longer need to program a tedious loop:

[Click here to view code image](#)

```
for (int i = 0; i < children.getLength(); i++)
{
 Node child = children.item(i);
 if (child instanceof Element childElement)
 {
 if (childElement.getTagName().equals("name")) . . .;
 else if (childElement.getTagName().equals("size")) . . .;
 }
}
```

Instead, you can simply access the first and second child:

[Click here to view code image](#)

```
var nameElement = (Element) children.item(0);
var sizeElement = (Element) children.item(1);
```

That is why DTDs are so useful. You don't overload your program with rule-checking code—the parser has already done that work by the time you get the document.

When the parser reports an error, your application will want to do something about it—log it, show it to the user, or throw an exception to abandon the parsing. Therefore, you should install an error handler whenever you use validation. Supply an object that implements the `ErrorHandler` interface. That interface has three methods:

[Click here to view code image](#)

```
void warning(SAXParseException e)
void error(SAXParseException e)
void fatalError(SAXParseException e)
```

Install the error handler with the `setErrorHandler` method of the `DocumentBuilder` class:

[Click here to view code image](#)

```
builder.setErrorHandler(handler);
```

---

## **javax.xml.parsers.DocumentBuilder 1.4**

- `void setEntityResolver(EntityResolver resolver)`  
sets the resolver to locate entities that are referenced in the XML documents being parsed.
- `void setErrorHandler(ErrorHandler handler)`  
sets the handler to report errors and warnings that occur during parsing.

## **org.xml.sax.EntityResolver 1.4**

- `public InputSource resolveEntity(String publicID, String systemID)`  
returns an input source that contains the data referenced by the given ID(s), or `null` to indicate that this resolver doesn't know how to resolve the particular name. The `publicID` parameter may be `null` if no public ID was supplied.

## **org.xml.sax.InputSource 1.4**

- `InputSource(InputStream in)`
- `InputSource(Reader in)`
- `InputSource(String systemID)`  
construct an input source from a stream, reader, or system ID (usually a relative or absolute URL).

## **org.xml.sax.ErrorHandler 1.4**

- void fatalError(SAXParseException e)
- void error(SAXParseException e)
- void warning(SAXParseException e)

Override these methods to provide handlers for fatal errors, nonfatal errors, and warnings.

#### **org.xml.sax.SAXParseException** 1.4

- int getLineNumber()
- int getColumnNumber()

return the line and column numbers of the end of the processed input that caused the exception.

#### **javax.xml.catalog.CatalogManager** 9

- static CatalogResolver catalogResolver(CatalogFeatures features, URI... uris)

produces a resolver that uses the catalog files located at the provided URIs. This class implements EntityResolver as well as the resolver classes used by StAX, schema validation, and XSL transforms.

#### **javax.xml.catalog.CatalogFeatures** 9

- static CatalogFeatures defaults()  
yields an instance with default settings.

## **javax.xml.parsers.DocumentBuilderFactory 1.4**

- boolean isValidation()
- void setValidation(boolean value)

get or set the validating property of the factory. If set to true, the parsers that this factory generates validate their input.

- boolean isIgnoringElementContentWhitespace()
- void setIgnoringElementContentWhitespace(boolean value)

get or set the ignoringElementContentWhitespace property of the factory. If set to true, the parsers that this factory generates ignore whitespace between element nodes that don't have mixed content (i.e., a mixture of elements and #PCDATA).

### **3.4.2 XML Schema**

XML Schema is quite a bit more complex than the DTD syntax, so we will only cover the basics. For more information, we recommend the tutorial at [www.w3.org/TR/xmlschema-0](http://www.w3.org/TR/xmlschema-0).

To reference a schema file in a document, add attributes to the root element, for example:

[Click here to view code image](#)

```
<?xml version="1.0"?>
<config xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
 xsi:noNamespaceSchemaLocation="config.xsd">
 . . .
</config>
```

This declaration states that the schema file config.xsd should be used to validate the document. If your document uses namespaces, the syntax is a bit

more complex—see the XML Schema tutorial for details. (The prefix `xsi` is a *namespace alias*; see [Section 3.6, “Using Namespaces,”](#) on p. 199 for more information.)

A schema defines a *type* for each element and attribute. A *simple type* is a string, perhaps with restrictions on its contents. Everything else is a *complex type*. An element with a simple type can have no attributes and no child elements. Otherwise, it must have a complex type. Conversely, attributes always have a simple type.

Some simple types are built into XML Schema, including

```
xsd:string
xsd:int
xsd:boolean
```

---



### Note

We use the prefix `xsd:` to denote the XML Schema Definition namespace. Some authors use the prefix `xs:` instead.

---

You can define your own simple types. For example, here is an enumerated type:

[Click here to view code image](#)

```
<xsd:simpleType name="StyleType">
 <xsd:restriction base="xsd:string">
 <xsd:enumeration value="PLAIN" />
 <xsd:enumeration value="BOLD" />
 <xsd:enumeration value="ITALIC" />
 <xsd:enumeration value="BOLD_ITALIC" />
 </xsd:restriction>
</xsd:simpleType>
```

When you define an element, you specify its type:

[Click here to view code image](#)

```
<xsd:element name="name" type="xsd:string"/>
<xsd:element name="size" type="xsd:int"/>
<xsd:element name="style" type="StyleType"/>
```

The type constrains the element content. For example, the elements

```
<size>10</size>
<style>PLAIN</style>
```

will validate correctly, but the elements

```
<size>default</size>
<style>SLANTED</style>
```

will be rejected by the parser.

You can compose types into complex types, for example:

[Click here to view code image](#)

```
<xsd:complexType name="FontType">
 <xsd:sequence>
 <xsd:element ref="name"/>
 <xsd:element ref="size"/>
 <xsd:element ref="style"/>
 </xsd:sequence>
</xsd:complexType>
```

A `FontType` is a sequence of `name`, `size`, and `style` elements. In this type definition, we use the `ref` attribute and refer to definitions that are located elsewhere in the schema. You can also nest definitions, like this:

[Click here to view code image](#)

```
<xsd:complexType name="FontType">
 <xsd:sequence>
 <xsd:element name="name" type="xsd:string"/>
 <xsd:element name="size" type="xsd:int"/>
 <xsd:element name="style">
 <xsd:simpleType>
```

```

<xsd:restriction base="xsd:string">
 <xsd:enumeration value="PLAIN" />
 <xsd:enumeration value="BOLD" />
 <xsd:enumeration value="ITALIC" />
 <xsd:enumeration value="BOLD_ITALIC" />
</xsd:restriction>
</xsd:simpleType>
</xsd:element>
</xsd:sequence>
</xsd:complexType>

```

Note the *anonymous type definition* of the `style` element.

The `xsd:sequence` construct is the equivalent of the concatenation notation in DTDs. The `xsd:choice` construct is the equivalent of the `|` operator. For example,

[Click here to view code image](#)

```

<xsd:complexType name="contactinfo">
 <xsd:choice>
 <xsd:element ref="email"/>
 <xsd:element ref="phone"/>
 </xsd:choice>
</xsd:complexType>

```

This is the equivalent of the DTD type `email | phone`.

To allow repeated elements, use the `minoccurs` and `maxoccurs` attributes. For example, the equivalent of the DTD type `item*` is

[Click here to view code image](#)

```

<xsd:element name="item" type=". . ." minoccurs="0"
maxoccurs="unbounded">

```

To specify attributes, add `xsd:attribute` elements to `complexType` definitions:

[Click here to view code image](#)

```
<xsd:element name="size">
 <xsd:complexType>
 . . .
 <xsd:attribute name="unit" type="xsd:string" use="optional"
 default="cm"/>
 </xsd:complexType>
</xsd:element>
```

This is the equivalent of the DTD statement

[Click here to view code image](#)

```
<!ATTLIST size unit CDATA #IMPLIED "cm">
```

Enclose element and type definitions of your schema inside an `xsd:schema` element:

[Click here to view code image](#)

```
<xsd:schema xmlns:xsd="http://www.w3.org/2001/XMLSchema">
 . . .
</xsd:schema>
```

Parsing an XML file with a schema is similar to parsing a file with a DTD, but with two differences:

1. You need to turn on support for namespaces, even if you don't use them in your XML files.

[Click here to view code image](#)

```
factory.setNamespaceAware(true);
```

2. You need to prepare the factory for handling schemas, with the following magic incantation:

[Click here to view code image](#)

```
final String JAXP_SCHEMA_LANGUAGE =
 "http://java.sun.com/xml/jaxp/properties/schemaLanguage";
final String W3C_XML_SCHEMA =
 "http://www.w3.org/2001/XMLSchema";
factory.setAttribute(JAXP_SCHEMA_LANGUAGE, W3C_XML_SCHEMA);
```

### 3.4.3 A Practical Example

In this section, we work through a practical example that shows the use of XML in a realistic setting.

Suppose an application needs configuration data that specifies arbitrary objects, not just text strings. We provide two mechanisms for instantiating the object: with a constructor, and with a factory method. Here is how to make a `Color` object using a constructor:

[Click here to view code image](#)

```
<construct class="java.awt.Color">
 <int>55</int>
 <int>200</int>
 <int>100</int>
</construct>
```

Here is an example with a factory method:

[Click here to view code image](#)

```
<factory class="java.util.logging.Logger" method="getLogger">
 <string>com.horstmann.corejava</string>
</factory>
```

If the factory method name is omitted, it defaults to `getInstance`.

As you can see, there are elements for describing strings and integers. We also support the `boolean` type, and other primitive types can be added in the same way.

Just to show off the syntax, there is a second mechanism for primitive types:

```
<value type="int">30</value>
```

A configuration is a sequence of entries. Each entry has an ID and an object:

[Click here to view code image](#)

```
<config>
 <entry id="background">
```

```

<construct class="java.awt.Color">
 <value type="int">55</value>
 <value type="int">200</value>
 <value type="int">100</value>
</construct>
</entry>
. . .
</config>
```

The parser checks that IDs are unique.

The program in [Listing 3.2](#) shows how to parse a configuration file. A sample configuration is defined in [Listing 3.3](#).

The program uses the schema instead of the DTD if you choose a file that contains the string `-schema`.

The DTD, shown in [Listing 3.4](#), is straightforward.

[Listing 3.5](#) contains the equivalent schema. In the schema, we can provide additional checking: an `int` or `boolean` element can only contain integer or boolean content. Note the use of the `xsd:group` construct to define parts of complex types that are used repeatedly.

This example is a typical use of XML. The XML format is robust enough to express complex relationships. The XML parser adds value by taking over the routine job of validity checking and supplying defaults.

### **Listing 3.2** `read/XMLReadTest.java`

[Click here to view code image](#)

```

1 package read;
2
3 import java.io.*;
4 import java.lang.reflect.*;
5 import java.util.*;
6
7 import javax.xml.parsers.*;
8
9 import org.w3c.dom.*;
```

```
10 import org.xml.sax.*;
11
12 /**
13 * This program shows how to use an XML file to describe Java
14 * objects
15 * @version 1.0 2018-04-03
16 * @author Cay Horstmann
17 */
18 public class XMLReadTest
19 {
20 public static void main(String[] args) throws
21 ParserConfigurationException, 20 SAXException, IOException,
22 ReflectiveOperationException
23 {
24 String filename;
25 if (args.length == 0)
26 {
27 try (var in = new Scanner(System.in))
28 {
29 System.out.print("Input file: ");
30 filename = in.nextLine();
31 }
32 else
33 filename = args[0];
34
35 DocumentBuilderFactory factory =
36 DocumentBuilderFactory.newInstance();
37 factory.setValidating(true);
38
39 if (filename.contains("-schema"))
40 {
41 factory.setNamespaceAware(true);
42 final String JAXP_SCHEMA_LANGUAGE =
43 "http://java.sun.com/xml/jaxp/properties/schemaLanguage";
44 final String W3C_XML_SCHEMA =
45 "http://www.w3.org/2001/XMLSchema";
46 factory.setAttribute(JAXP_SCHEMA_LANGUAGE,
```

```
W3C_XML_SCHEMA);
44 }
45
46 factory.setIgnoringElementContentWhitespace(true);
47
48 DocumentBuilder builder = factory.newDocumentBuilder();
49
50 builder.setErrorHandler(new ErrorHandler()
51 {
52 public void warning(SAXParseException e) throws
SAXException
53 {
54 System.err.println("Warning: " + e.getMessage());
55 }
56
57 public void error(SAXParseException e) throws
SAXException
58 {
59 System.err.println("Error: " + e.getMessage());
60 System.exit(0);
61 }
62
63 public void fatalError(SAXParseException e) throws
SAXException
64 {
65 System.err.println("Fatal error: " +
e.getMessage());
66 System.exit(0);
67 }
68 });
69
70 Document doc = builder.parse(filename);
71 Map<String, Object> config =
parseConfig(doc.getDocumentElement());
72 System.out.println(config);
73 }
74
75 private static Map<String, Object> parseConfig(Element e)
76 throws ReflectiveOperationException
77 {
```

```
78 var result = new HashMap<String, Object>();
79 NodeList children = e.getChildNodes();
80 for (int i = 0; i < children.getLength(); i++)
81 {
82 var child = (Element) children.item(i);
83 String name = child.getAttribute("id");
84 Object value = parseObject((Element)
child.getFirstChild());
85 result.put(name, value);
86 }
87 return result;
88 }
89
90 private static Object parseObject(Element e)
91 throws ReflectiveOperationException
92 {
93 String tagName = e.getTagName();
94 if (tagName.equals("factory")) return parseFactory(e);
95 else if (tagName.equals("construct")) return
parseConstruct(e);
96 else
97 {
98 String childData = ((CharacterData)
e.getFirstChild()).getData();
99 if (tagName.equals("int"))
100 return Integer.valueOf(childData);
101 else if (tagName.equals("boolean"))
102 return Boolean.valueOf(childData);
103 else
104 return childData;
105 }
106 }
107
108 private static Object parseFactory(Element e)
109 throws ReflectiveOperationException
110 {
111 String className = e.getAttribute("class");
112 String methodName = e.getAttribute("method");
113 Object[] args = parseArgs(e.getChildNodes());
```

```
114 Class<?>[] parameterTypes = getParameterTypes(args);
115 Method method =
116 Class.forName(className).getMethod(methodName, parameterTypes);
117 return method.invoke(null, args);
118 }
119 private static Object parseConstruct(Element e)
120 throws ReflectiveOperationException
121 {
122 String className = e.getAttribute("class");
123 Object[] args = parseArgs(e.getChildNodes());
124 Class<?>[] parameterTypes = getParameterTypes(args);
125 Constructor<?> constructor =
126 Class.forName(className).getConstructor(parameterTypes);
127 return constructor.newInstance(args);
128 }
129 private static Object[] parseArgs(NodeList elements)
130 throws ReflectiveOperationException
131 {
132 var result = new Object[elements.getLength()];
133 for (int i = 0; i < result.length; i++)
134 result[i] = parseObject((Element) elements.item(i));
135 return result;
136 }
137
138 private static Map<Class<?>, Class<?>> toPrimitive = Map.of(
139 Integer.class, int.class,
140 Boolean.class, boolean.class);
141
142 private static Class<?>[] getParameterTypes(Object[] args)
143 {
144 var result = new Class<?>[args.length];
145 for (int i = 0; i < result.length; i++)
146 {
147 Class<?> cl = args[i].getClass();
148 result[i] = toPrimitive.get(cl);
149 if (result[i] == null) result[i] = cl;
150 }

```

```
151 return result;
152 }
153 }
```

---

### **Listing 3.3** read/config.xml

[Click here to view code image](#)

```
1 <?xml version="1.0"?>
2 <!DOCTYPE config SYSTEM "config.dtd">
3 <config>
4 <entry id="background">
5 <construct class="java.awt.Color"> 6 <int>55</int>
6 <int>200</int>
7 <int>100</int>
8 </construct>
9 </entry>
10 <entry id="currency">
11 <factory class="java.util.Currency">
12 <string>USD</string>
13 </factory>
14 </entry>
15 </config>
```

---

### **Listing 3.4** read/config.dtd

[Click here to view code image](#)

```
1 <!ELEMENT config (entry)*>
2
3 <!ELEMENT entry (string|int|boolean|construct|factory)>
4 <!ATTLIST entry id ID #IMPLIED>
5
6 <!ELEMENT construct (string|int|boolean|construct|factory)*>
7 <!ATTLIST construct class CDATA #IMPLIED>
8
9 <!ELEMENT factory (string|int|boolean|construct|factory)*>
10 <!ATTLIST factory class CDATA #IMPLIED>
11 <!ATTLIST factory method CDATA "getInstance">
```

```
12
13 <!ELEMENT string (#PCDATA)>
14 <!ELEMENT int (#PCDATA)>
15 <!ELEMENT boolean (#PCDATA)>
```

---

---

### **Listing 3.5** read/config.xsd

---

[Click here to view code image](#)

```
1 <xsd:schema xmlns:xsd="http://www.w3.org/2001/XMLSchema">
2 <xsd:element name="config">
3 <xsd:complexType>
4 <xsd:sequence>
5 <xsd:element name="entry" minOccurs="0"
maxOccurs="unbounded">
6 <xsd:complexType>
7 <xsd:group ref="Object"/>
8 <xsd:attribute name="id" type="xsd:ID"/>
9 </xsd:complexType>
10 </xsd:element>
11 </xsd:sequence>
12 </xsd:complexType>
13 </xsd:element>
14
15 <xsd:element name="construct">16 <xsd:complexType>
16 <xsd:group ref="Arguments"/>
17 <xsd:attribute name="class" type="xsd:string"/>
18 </xsd:complexType>
19 </xsd:element>
20
21
22 <xsd:element name="factory">
23 <xsd:complexType>
24 <xsd:group ref="Arguments"/>
25 <xsd:attribute name="class" type="xsd:string"/>
26 <xsd:attribute name="method" type="xsd:string"
default="getInstance"/>
27 </xsd:complexType>
28 </xsd:element>
29
```

```

30 <xsd:group name="Object">
31 <xsd:choice>
32 <xsd:element ref="construct"/>
33 <xsd:element ref="factory"/>
34 <xsd:element name="string" type="xsd:string"/>
35 <xsd:element name="int" type="xsd:int"/>
36 <xsd:element name="boolean" type="xsd:boolean"/>
37 </xsd:choice>
38 </xsd:group>
39
40 <xsd:group name="Arguments">
41 <xsd:sequence>
42 <xsd:group ref="Object" minOccurs="0"
maxOccurs="unbounded"/>
43 </xsd:sequence>
44 </xsd:group>
45 </xsd:schema>

```

---

## 3.5 Locating Information with XPath

If you want to locate a specific piece of information in an XML document, it can be a bit of a hassle to navigate the nodes of the DOM tree. The XPath language makes it simple to access tree nodes. For example, suppose you have this XHTML document:

```

<html>
 <head>
 . . .
 <title>. . .</title>
 . . .
 </head>
 . . .
</html>

```

You can get the title text by evaluating the XPath expression

```
/html/head/title/text()
```

That's a lot simpler than the plain DOM approach:

1. Get the document root.
2. Get the first child and cast it as an Element.
3. Locate the `title` element among its children.
4. Get its first child and cast it as a `CharacterData` node.
5. Get its data.

An XPath can describe *a set of nodes* in an XML document. For example, the XPath

```
/html/body/form
```

describes the set of all `form` elements that are children of the `body` element in an XHTML file. You can select a particular element with the `[]` operator:

```
/html/body/form[1]
```

is the first form. (The index values start at 1.)

Use the `@` operator to get attribute values. The XPath expression

```
/html/body/form[1]/@action
```

describes the `action` attribute of the first table. The XPath expression

```
/html/body/form/@action
```

describes all `action` attribute nodes of all `form` elements that are children of the `body` element.

There are a number of useful XPath functions. For example,

```
count(/html/body/form)
```

returns the number of `form` children of the `body` element. There are many more elaborate XPath expressions; see the specification at

[www.w3c.org/TR/xpath](http://www.w3c.org/TR/xpath) or the online tutorial at [www.zvon.org/xxl/XPathTutorial/General/examples.html](http://www.zvon.org/xxl/XPathTutorial/General/examples.html).

To evaluate XPath expressions, first create an `XPath` object from an `XPathFactory`:

[Click here to view code image](#)

```
XPathFactory xpfactory = XPathFactory.newInstance();
path = xpfactory.newXPath();
```

Then, call the `evaluate` method to evaluate XPath expressions:

[Click here to view code image](#)

```
String username = path.evaluate("/html/head/title/text()", doc);
```

You can use the same `XPath` object to evaluate multiple expressions.

This form of the `evaluate` method returns a string result. It is suitable for retrieving text, such as the text child of the `title` element in the preceding example. If an XPath expression yields multiple nodes, make a call such as the following:

[Click here to view code image](#)

```
XPathNodes result = path.evaluateExpression("/html/body/form",
doc, XPathNodes.class);
```

The `XPathNodes` class is similar to a `NodeList`, but it extends the `Iterable` interface, allowing you to use an enhanced `for` loop.

This method was added in Java 9. In older releases, use the following call instead:

[Click here to view code image](#)

```
var nodes = (NodeList) path.evaluate("/html/body/form", doc,
XPathConstants.NODESET);
```

If the result is a single node, use one of the following calls:

[Click here to view code image](#)

```
Node node = path.evaluateExpression("/html/body/form[1]", doc,
Node.class);
node = (Node) path.evaluate("/html/body/form[1]", doc,
XPathConstants.NODE);
```

If the result is a number, use:

[Click here to view code image](#)

```
int count = path.evaluateExpression("count(/html/body/form)", doc,
Integer.class);
count = ((Number) path.evaluate("count(/html/body/form)", doc,
XPathConstants.NUMBER)).intValue();
```

You don't have to start the search at the document root; you can start at any node or node list. For example, if you have a node from a previous evaluation, you can call

[Click here to view code image](#)

```
String result = path.evaluate(expression, node);
```

If you do not know the result of evaluating an XPath expression (perhaps because it comes from a user), then call

[Click here to view code image](#)

```
XPathEvaluationResult<?> result =
path.evaluateExpression(expression, doc);
```

The expression `result.type()` is one of the constants

```
STRING
NODESET
NODE
NUMBER
BOOLEAN
```

of the `XPathEvaluationResult.XPathResultType` enumeration. Call `result.value()` to get the value.

The program in [Listing 3.6](#) demonstrates evaluation of arbitrary XPath expressions. Load an XML file and type an expression. The result of the expression is displayed.

---

### **Listing 3.6** xpath/XPathTest.java

---

[Click here to view code image](#)

```
1 package xpath;
2
3 import java.io.*;
4 import java.nio.file.*;
5 import java.util.*;
6
7 import javax.xml.catalog.*;
8 import javax.xml.parsers.*;
9 import javax.xml.xpath.*;
10
11 import org.w3c.dom.*;
12 import org.xml.sax.*;
13
14 /**
15 * This program evaluates XPath expressions.
16 * @version 1.1 2018-04-06
17 * @author Cay Horstmann
18 */
19 public class XPathTest
20 {
21 public static void main(String[] args) throws Exception
22 {
23 DocumentBuilderFactory factory =
24 DocumentBuilderFactory.newInstance();
25 DocumentBuilder builder = factory.newDocumentBuilder();
26 // Avoid a delay in parsing an XHTML file--see the first
27 // note in
28 // Section 3.4.1
```

```
28 builder.setEntityResolver(CatalogManager.catalogResolver(29 CatalogFeatures.defaults(),30)31 Path.of("xpath/catalog.xml").toAbsolutePath().toUri()));32 XPathFactory xpfactory = XPathFactory.newInstance();33 XPath path = xpfactory.newXPath();34 try (var in = new Scanner(System.in))35 {36 String filename;37 if (args.length == 0)38 {39 System.out.print("Input file: ");40 filename = in.nextLine();41 }42 else43 filename = args[0];44 }45 Document doc = builder.parse(filename);46 boolean done = false;47 while (!done)48 {49 System.out.print("XPath expression (empty line to50 exit): ");51 String expression = in.nextLine();52 if (expression.strip().isEmpty()) done = true;53 else54 {55 try56 {57 XPathEvaluationResult<?> result58 = path.evaluateExpression(expression, doc);59 if (result.type() ==60 XPathEvaluationResult.XPathResultType.NODESET)61 {62 for (Node n : (XPathNodes) result.value())63 System.out.println(description(n));64 }65 else if (result.type() ==
```

```
XPathEvaluationResult.XPathResultType.NODE)
64 System.out.println((Node) result.value());
65 else
66 System.out.println(result.value());
67 }
68 catch (XPathExpressionException e)
69 {
70 System.out.println(e.getMessage());
71 }
72 }
73 }
74 }
75 }
76
77 public static String description(Node n)
78 {
79 if (n instanceof Element) return "Element " +
n.getNodeName();
80 else if (n instanceof Attr) return "Attribute " + n;
81 else return n.toString();
82 }
83 }
```

---

## **javax.xml.xpath.XPathFactory 5.0**

- static XPathFactory newInstance()  
returns an XPathFactory instance for creating XPath objects.
- XPath newXpath()  
constructs an XPath object for evaluating XPath expressions.

## **javax.xml.xpath.XPath 5.0**

- `String evaluate(String expression, Object startingPoint)`

evaluates an expression, beginning at the given starting point. The starting point can be a node or node list. If the result is a node or node set, the returned string consists of the data of all text node children.

- `Object evaluate(String expression, Object startingPoint, QName resultType)`

evaluates an expression, beginning at the given starting point. The starting point can be a node or node list. The `resultType` is one of the constants `STRING`, `NODE`, `NODESET`, `NUMBER`, or `BOOLEAN` in the `XPathConstants` class. The return value is a `String`, `Node`, `NodeList`, `Number`, or `Boolean`.

- `<T> T evaluateExpression(String expression, Object item, Class<T> type)` <sup>9</sup>

evaluates the given expression and yields the result as a value of the given type.

- `XPathEvaluationResult<?> evaluateExpression(String expression, InputSource source)` <sup>9</sup>

evaluates the given expression.

#### **`javax.xml.xpath.XPathEvaluationResult<T>` <sup>9</sup>**

- `XPathEvaluationResult.XPathResultType type()`

returns one of the enumeration constants `STRING`, `NODESET`, `NODE`, `NUMBER`, `BOOLEAN`.

- `T value()`

returns the result value.

## 3.6 Using Namespaces

The Java language uses packages to avoid name clashes. Programmers can use the same name for different classes as long as they aren't in the same package. XML has a similar *namespace* mechanism for element and attribute names.

A namespace is identified by a Uniform Resource Identifier (URI), such as

[Click here to view code image](#)

```
http://www.w3.org/2001/XMLSchema
uuid:1c759aed-b748-475c-ab68-10679700c4f2
urn:com:books-r-us
```

The HTTP URL form is the most common. Note that the URL is just used as an identifier string, not as a locator for a document. For example, the namespace identifiers

[Click here to view code image](#)

```
http://www.horstmann.com/corejava
http://www.horstmann.com/corejava/index.html
```

denote *different* namespaces, even though a web server would serve the same document for both URLs.

There need not be any document at a namespace URL—the XML parser doesn't attempt to find anything at that location. However, as a help to programmers who encounter a possibly unfamiliar namespace, it is customary to place a document explaining the purpose of the namespace at the URL location. For example, if you point your browser to the namespace URL for the XML Schema namespace (<http://www.w3.org/2001/XMLSchema>), you will find a document describing the XML Schema standard.

Why use HTTP URLs for namespace identifiers? It is easy to ensure that they are unique. If you choose a real URL, the host part's uniqueness is guaranteed by the domain name system. Your organization can then arrange for the uniqueness of the remainder of the URL. This is the same rationale that underlies the use of reversed domain names in Java package names.

Of course, although long namespace identifiers are good for uniqueness, you don't want to deal with long identifiers any more than you have to. In the Java programming language, you use the `import` mechanism to specify the long names of packages, and then use just the short class names. In XML, there is a similar mechanism:

[Click here to view code image](#)

```
<element xmlns="namespaceURI">
 children
</element>
```

The element and its children are now part of the given namespace.

A child can provide its own namespace, for example:

[Click here to view code image](#)

```
<element xmlns="namespaceURI1">
 <child xmlns="namespaceURI2">
 grandchildren
 </child>
 more children
</element>
```

Then the first child and the grandchildren are part of the second namespace.

This simple mechanism works well if you need only a single namespace or if the namespaces are naturally nested. Otherwise, you will want to use a second mechanism that has no analog in Java. You can have a *prefix* for a namespace—a short identifier that you choose for a particular document. Here is a typical example—the `xsd` prefix in an XML Schema file:

[Click here to view code image](#)

```
<xsd:schema xmlns:xsd="http://www.w3.org/2001/XMLSchema">
 <xsd:element name="config"/>
 . . .
</xsd:schema>
```

The attribute

```
xmlns:prefix="namespaceURI"
```

defines a namespace and a prefix. In our example, the prefix is the string xsd. Thus, xsd:schema really means schema in the namespace <http://www.w3.org/2001/XMLSchema>.

---



## Note

Only child elements inherit the namespace of their parent. Attributes without an explicit prefix are never part of a namespace. Consider this contrived example:

[Click here to view code image](#)

```
<configuration xmlns="http://www.horstmann.com/corejava"
 xmlns:si="http://www.bipm.fr/enus/3_SI/si.html">
 <size value="210" si:unit="mm"/>
 . . .
</configuration>
```

In this example, the elements configuration and size are part of the namespace with URI

<http://www.horstmann.com/corejava>. The attribute

si:unit is part of the namespace with URI

[http://www.bipm.fr/enus/3\\_SI/si.html](http://www.bipm.fr/enus/3_SI/si.html). However, the attribute value is not part of any namespace.

---

You can control how the parser deals with namespaces. By default, the DOM parser of the Java XML library is not namespace-aware.

To turn on namespace handling, call the setNamespaceAware method of the DocumentBuilderFactory:

[Click here to view code image](#)

```
DocumentBuilderFactory factory =
DocumentBuilderFactory.newInstance();
factory.setNamespaceAware(true);
```

Now, all builders the factory produces support namespaces.

Alternatively, since Java 13, call

[Click here to view code image](#)

```
DocumentBuilderFactory factory =
 DocumentBuilderFactory.newInstance();
```

Each node created by a builder has three properties:

- The *qualified name*, with a prefix, returned by `getNodeName`, `getTagName`, and so on
- The namespace URI, returned by the `getNamespaceURI` method
- The *local name*, without a prefix or a namespace, returned by the `getLocalName` method

Here is an example. Suppose the parser sees the following element:

[Click here to view code image](#)

```
<xsd:schema xmlns:xsd="http://www.w3.org/2001/XMLSchema">
```

It then reports the following:

- Qualified name = `xsd:schema`
- Namespace URI = <http://www.w3.org/2001/XMLSchema>
- Local name = `schema`



### Note

If namespace awareness is turned off, `getNamespaceURI` and `getLocalName` return null.

---

#### **`org.w3c.dom.Node` 1.4**

- `String getLocalName()`

returns the local name (without prefix), or `null` if the parser is not namespace-aware.

- `String getNamespaceURI()`

returns the namespace URI, or `null` if the node is not part of a namespace or if the parser is not namespace-aware.

#### **`javax.xml.parsers.DocumentBuilderFactory` 1.4**

- `static DocumentBuilderFactory newNSInstance() 13`  
yields a factory whose builders are namespace-aware.
- `boolean isNamespaceAware()`
- `void setNamespaceAware(boolean value)`  
get or set the `namespaceAware` property of the factory. If set to `true`, the parsers that this factory generates are namespace-aware.

## **3.7 Streaming Parsers**

The DOM parser reads an XML document in its entirety into a tree data structure. For most practical applications, DOM works fine. However, it can be inefficient if the document is large and if your processing algorithm is simple enough that you can analyze nodes on the fly, without having to see all of the tree structure. In these cases, you should use a streaming parser.

In the following sections, we discuss the streaming parsers supplied by the Java library: the venerable SAX parser and the more modern StAX parser that was added to Java 6. The SAX parser uses event callbacks, and the StAX parser provides an iterator through the parsing events. The latter is usually a bit more convenient.

### **3.7.1 Using the SAX Parser**

The SAX parser reports events as it parses the components of the XML input, but it does not store the document in any way—it is up to the event handlers to build a data structure. In fact, the DOM parser is built on top of the SAX parser. It builds the DOM tree as it receives the parser events.

Whenever you use a SAX parser, you need a handler that defines the event actions for the various parse events. The `ContentHandler` interface defines several callback methods that the parser executes as it parses the document. Here are the most important ones:

- `startElement` and `endElement` are called each time a start tag or end tag is encountered.
- `characters` is called whenever character data are encountered.
- `startDocument` and `endDocument` are called once each, at the start and the end of the document.

For example, when parsing the fragment

```

 <name>Helvetica</name>
 <size units="pt">36</size>

```

the parser makes the following callbacks:

1. `startElement`, element name: `font`
2. `startElement`, element name: `name`
3. `characters`, content: `Helvetica`
4. `endElement`, element name: `name`
5. `startElement`, element name: `size`, attributes: `units="pt"`
6. `characters`, content: `36`
7. `endElement`, element name: `size`
8. `endElement`, element name: `font`

Your handler needs to override these methods and have them carry out whatever action you want to carry out as you parse the file. The program at the

end of this section prints all links <a href=". . ."> in an HTML file. It simply overrides the `startElement` method of the handler to check for links with name `a` and an attribute with name `href`. This is potentially useful for implementing a "web crawler"—a program that reaches more and more web pages by following links.

---



## Note

HTML doesn't have to be valid XML, and many web pages deviate so much from proper XML that the example programs will not be able to parse them. However, many pages authored by the W3C are written in XHTML (an HTML dialect that is proper XML). You can use those pages to test the example program. For example, if you run

[Click here to view code image](#)

```
java SAXTest http://www.w3c.org/Consortium
```

you will see a list of the URLs of all links on that page.

---

The sample program is a good example for the use of SAX. We don't care at all in which context the `a` elements occur, and there is no need to store a tree structure.

Here is how you get a SAX parser:

[Click here to view code image](#)

```
SAXParserFactory factory = SAXParserFactory.newInstance();
SAXParser parser = factory.newSAXParser();
```

You can now process a document:

[Click here to view code image](#)

```
parser.parse(source, handler);
```

Here, `source` can be a file, URL string, or input stream. The `handler` belongs to a subclass of `DefaultHandler`. The `DefaultHandler` class defines do-nothing methods for the four interfaces:

```
ContentHandler
DTDHandler
EntityResolver
ErrorHandler
```

The example program defines a handler that overrides the `startElement` method of the `ContentHandler` interface to watch out for elements with an `href` attribute:

[Click here to view code image](#)

```
var handler = new DefaultHandler()
{
 public void startElement(String namespaceURI, String lname,
 String qname,
 Attributes attrs) throws SAXException
 {
 if (lname.equalsIgnoreCase("a") && attrs != null)
 {
 for (int i = 0; i < attrs.getLength(); i++)
 {
 String aname = attrs.getLocalName(i);
 if (aname.equalsIgnoreCase("href"))
 System.out.println(attrs.getValue(i));
 }
 }
 }
};
```

The `startElement` method has three parameters that describe the element name. The `qname` parameter reports the qualified name of the form `prefix:localname`. If namespace processing is turned on, then the `namespaceURI` and `lname` parameters provide the namespace and local (unqualified) name.

As with the DOM parser, namespace processing is turned off by default. To activate namespace processing, call the `setNamespaceAware` method of the factory class. Alternatively, as of Java 13, make a namespace-aware factory with `newNSInstance`:

[Click here to view code image](#)

```
SAXParserFactory factory = SAXParserFactory.newInstance();
SAXParser saxParser = factory.newSAXParser();
```

In this program, we cope with another common issue. An XHTML file starts with a tag that contains a DTD reference, and the parser will want to load it. Understandably, the W3C isn't too happy to serve billions of copies of files such as [www.w3.org/TR/xhtml1/DTD/xhtml1-strict.dtd](http://www.w3.org/TR/xhtml1/DTD/xhtml1-strict.dtd). At one point, they refused altogether, but at the time of this writing, they serve the DTD at a glacial pace. If you don't need to validate the document, just call

[Click here to view code image](#)

```
factory.setFeature("http://apache.org/xml/features/nonvalidating/load-external-dtd", false);
```

[Listing 3.7](#) contains the code for the web crawler program. Later in this chapter, you will see another interesting use of SAX. An easy way of turning a non-XML data source into XML is to report the SAX events that an XML parser would report. See [Section 3.9, “XSL Transformations,”](#) on p. 223 for details.

---

### **Listing 3.7** sax/SAXTest.java

---

[Click here to view code image](#)

```
1 package sax;
2
3 import java.io.*;
4 import java.net.*;
5 import javax.xml.parsers.*;
6 import org.xml.sax.*;
7 import org.xml.sax.helpers.*;
8
9 /**
10 * This program demonstrates how to use a SAX parser. The
11 * program prints all
12 * hyperlinks of an XHTML web page.

13 * Usage: java sax.SAXTest URL
```

```
13 * @version 1.01 2018-05-01
14 * @author Cay Horstmann
15 */
16 public class SAXTest
17 {
18 public static void main(String[] args) throws Exception
19 {
20 String url;
21 if (args.length == 0)
22 {
23 url = "http://www.w3c.org";
24 System.out.println("Using " + url);
25 }
26 else url = args[0];
27
28 var handler = new DefaultHandler()
29 {
30 public void startElement(String namespaceURI, String
lname,
31 String qname, Attributes attrs)
32 {
33 if (lname.equals("a") && attrs != null)
34 {
35 for (int i = 0; i < attrs.getLength(); i++)
36 {
37 String aname = attrs.getLocalName(i);
38 if (aname.equals("href"))
39 System.out.println(attrs.getValue(i));
40 }
41 }
42 }
43 };
44
45 SAXParserFactory factory = SAXParserFactory.newInstance();
46 factory.setNamespaceAware(true);
47 factory.setFeature(
48 "http://apache.org/xml/features/nonvalidating/load-
external-dtd",
49 false);
```

```
50 SAXParser saxParser = factory.newSAXParser();
51 InputStream in = new URL(url).openStream();
52 saxParser.parse(in, handler);
53 }
54 }
```

---

## **javax.xml.parsers.SAXParserFactory 1.4**

- static SAXParserFactory newInstance()
- static SAXParserFactory newNSInstance() **13**

return an instance of the SAXParserFactory class. The second method yields a namespace-aware instance.
- SAXParser newSAXParser()

returns an instance of the SAXParser class.
- boolean isNamespaceAware()
- void setNamespaceAware(boolean value)

get or set the namespaceAware property of the factory. If set to true, the parsers that this factory generates are namespace-aware.
- boolean isValidating()
- void setValidating(boolean value)

get or set the validating property of the factory. If set to true, the parsers that this factory generates validate their input.

## **javax.xml.parsers.SAXParser 1.4**

- void parse(File f, DefaultHandler handler)
- void parse(String url, DefaultHandler handler)

- `void parse(InputStream in, DefaultHandler handler)`

parse an XML document from the given file, URL, or input stream and report parse events to the given handler.

#### ***org.xml.sax.ContentHandler*** 1.4

- `void startDocument()`
- `void endDocument()`

are called at the start or the end of the document.

- `void startElement(String uri, String lname, String qname, Attributes attr)`
- `void endElement(String uri, String lname, String qname)`

are called at the start or the end of an element. If the parser is namespace-aware, they report the URI of the namespace, the local name without prefix, and the qualified name with prefix.

- `void characters(char[] data, int start, int length)`

is called when the parser reports character data.

#### ***org.xml.sax.Attributes*** 1.4

- `int getLength()`  
returns the number of attributes stored in this attribute collection.
- `String getLocalName(int index)`

returns the local name (without prefix) of the attribute with the given index, or the empty string if the parser is not namespace-aware.

- `String getURI(int index)`

returns the namespace URI of the attribute with the given index, or the empty string if the node is not part of a namespace or if the parser is not namespace-aware.

- `String getQName(int index)`

returns the qualified name (with prefix) of the attribute with the given index, or the empty string if the qualified name is not reported by the parser.

- `String getValue(int index)`
- `String getValue(String qname)`
- `String getValue(String uri, String lname)`

return the attribute value from a given index, qualified name, or namespace URI + local name. Return null if the value doesn't exist.

### 3.7.2 Using the StAX Parser

The StAX parser is a "pull parser." Instead of installing an event handler, you simply iterate through the events, using this basic loop:

[Click here to view code image](#)

```
InputStream in = url.openStream();
XMLInputFactory factory = XMLInputFactory.newInstance();
XMLStreamReader parser = factory.createXMLStreamReader(in);
while (parser.hasNext())
{
 int event = parser.next();
 Call parser methods to obtain event details
}
```

For example, when parsing the fragment

```

 <name>Helvetica</name>
 <size units="pt">36</size>

```

the parser yields the following events:

1. START\_ELEMENT, element name: font
2. CHARACTERS, content: white space
3. START\_ELEMENT, element name: name
4. CHARACTERS, content: Helvetica
5. END\_ELEMENT, element name: name
6. CHARACTERS, content: white space
7. START\_ELEMENT, element name: size
8. CHARACTERS, content: 36
9. END\_ELEMENT, element name: size
10. CHARACTERS, content: white space
11. END\_ELEMENT, element name: font

To analyze the attribute values, call the appropriate methods of the `XMLStreamReader` class. For example,

[Click here to view code image](#)

```
String units = parser.getAttributeValue(null, "units");
```

gets the `units` attribute of the current element.

By default, namespace processing is enabled. You can deactivate it by modifying the factory:

[Click here to view code image](#)

```
XMLInputFactory factory = XMLInputFactory.newInstance();
factory.setProperty(XMLInputFactory.IS_NAMESPACE_AWARE, false);
```

[Listing 3.8](#) contains the code for the web crawler program implemented with the StAX parser. As you can see, the code is simpler than the equivalent SAX code because you don't have to worry about event handling.

---

### **Listing 3.8** stax/StAXTest.java

---

[Click here to view code image](#)

```
1 package stax;
2
3 import java.io.*;
4 import java.net.*;
5 import javax.xml.stream.*;
6
7 /**
8 * This program demonstrates how to use a StAX parser. The
9 * program prints all
10 * hyperlinks of an XHTML web page.

11 * Usage: java stax.StAXTest URL
12 * @author Cay Horstmann
13 * @version 1.1 2018-05-01
14 */
15 public class StAXTest
16 {
17 public static void main(String[] args) throws Exception
18 {
19 String urlString;
20 if (args.length == 0)
21 {
22 urlString = "http://www.w3c.org";
23 System.out.println("Using " + urlString);
24 }
25 else urlString = args[0];
26 var url = new URL(urlString);
27 InputStream in = url.openStream();
28 XMLInputFactory factory = XMLInputFactory.newInstance();
29 XMLStreamReader parser =
factory.createXMLStreamReader(in);
30 while (parser.hasNext())
31 {
```

```

31 int event = parser.next();
32 if (event == XMLStreamConstants.START_ELEMENT)
33 {
34 if (parser.getLocalName().equals("a"))
35 {
36 String href = parser.getAttributeValue(null,
37 "href");
38 if (href != null)
39 System.out.println(href);
40 }
41 }
42 }
43 }
```

## **javax.xml.stream.XMLInputFactory 6**

- static XMLInputFactory newInstance()  
returns an instance of the XMLInputFactory class.
- void setProperty(String name, Object value)  
sets a property for this factory, or throws an  
IllegalArgumentException if the property is not supported or  
cannot be set to the given value. The JDK implementation supports the  
following Boolean-valued properties:

"javax.xml.stream.  
isValidating"      When false (the default), the document  
is not validated. Not required by the  
specification.

"javax.xml.stream.  
isNamespaceAware"      When true (the default), namespaces are  
processed. Not required by the  
specification.

"javax.xml.stream.  
isCoalescing"      When false (the default), adjacent  
character data are not coalesced.

"javax.xml.stream."      When true (the default), entity references

`isReplacingEntityR` are replaced and reported as character data.  
`eferences"`

`"javax.xml.stream.isSupportingExternalEntities"` When true (the default), external entities are resolved. The specification gives no default for this property.

`"javax.xml.stream.supportDTD"` When true (the default), DTDs are reported as events.

- `XMLStreamReader`  
`createXMLStreamReader(InputStream in)`
- `XMLStreamReader`  
`createXMLStreamReader(InputStream in, String characterEncoding)`
- `XMLStreamReader`      `createXMLStreamReader(Reader in)`
- `XMLStreamReader`      `createXMLStreamReader(Source in)`

create a parser that reads from the given stream, reader, or JAXP source.

## ***javax.xml.stream.XMLStreamReader*** 6

- `boolean hasNext()`  
returns true if there is another parse event.
- `int next()`  
sets the parser state to the next parse event and returns one of the following constants: START\_ELEMENT, END\_ELEMENT, CHARACTERS, START\_DOCUMENT, END\_DOCUMENT, CDATA, COMMENT, SPACE (ignorable whitespace), PROCESSING\_INSTRUCTION, ENTITY\_REFERENCE, DTD.

- boolean isStartElement()
 

return true if the current event is a start element, end element, character data, or whitespace.
- QName getName()
 

get the name of the element in a START\_ELEMENT or END\_ELEMENT event.
- String getText()
 

returns the characters of a CHARACTERS, COMMENT, or CDATA event, the replacement value for an ENTITY\_REFERENCE, or the internal subset of a DTD.
- int getAttributeCount()
  - QName getAttributeName(int index)
 

get the attribute count and the names and values of the attributes, provided the current event is START\_ELEMENT.
  - String getAttributeValue(String namespaceURI, String name)
 

gets the value of the attribute with the given name, provided the current event is START\_ELEMENT. If namespaceURI is null, the namespace is not checked.

## 3.8 Generating XML Documents

You now know how to write Java programs that read XML. Let us now turn to the opposite process: producing XML output. Of course, you could write an XML file simply by making a sequence of `print` calls, printing the elements, attributes, and text content, but that would not be a good idea. The code is rather tedious, and you can easily make mistakes if you don't pay attention to special symbols (such as "`"` or `<`") in the attribute values and text content.

A better approach is to build up a DOM tree with the contents of the document and then write out the tree contents. The following sections discuss the details.

### 3.8.1 Documents without Namespaces

To build a DOM tree, you start out with an empty document. You can get an empty document by calling the `newDocument` method of the `DocumentBuilder` class:

[Click here to view code image](#)

```
Document doc = builder.newDocument();
```

Use the `createElement` method of the `Document` class to construct the elements of your document:

[Click here to view code image](#)

```
Element rootElement = doc.createElement(rootName);
Element childElement = doc.createElement(childName);
```

Use the `createTextNode` method to construct text nodes:

[Click here to view code image](#)

```
Text textNode = doc.createTextNode(textContents);
```

Add the root element to the document, and add the child nodes to their parents:

[Click here to view code image](#)

```
doc.appendChild(rootElement);
rootElement.appendChild(childElement);
childElement.appendChild(textNode);
```

As you build up the DOM tree, you may also need to set element attributes. Simply call the `setAttribute` method of the `Element` class:

[Click here to view code image](#)

```
rootElement.setAttribute(name, value);
```

### 3.8.2 Documents with Namespaces

If you use namespaces, the procedure for creating a document is slightly different.

First, set the builder factory to be namespace-aware, then create the builder:

[Click here to view code image](#)

```
DocumentBuilderFactory factory =
DocumentBuilderFactory.newInstance();
factory.setNamespaceAware(true);
builder = factory.newDocumentBuilder();
```

Then use `createElementNS` instead of `createElement` to create any nodes:

[Click here to view code image](#)

```
String namespace = "http://www.w3.org/2000/svg";
Element rootElement = doc.createElementNS(namespace, "svg");
```

If your node has a qualified name with a namespace prefix, then any necessary `xmlns`-prefixed attributes are created automatically. For example, if you need SVG inside XHTML, you can construct an element like this:

[Click here to view code image](#)

```
Element svgElement = doc.createElement(namespace, "svg:svg")
```

When the element is written, it turns into

[Click here to view code image](#)

```
<svg:svg xmlns:svg="http://www.w3.org/2000/svg">
```

If you need to set element attributes whose names are in a namespace, use the `setAttributeNS` method of the `Element` class:

[Click here to view code image](#)

```
rootElement.setAttributeNS(namespace, qualifiedName, value);
```

### 3.8.3 Writing Documents

Somewhat curiously, it is not so easy to write a DOM tree to an output stream. The easiest approach is to use the Extensible Stylesheet Language Transformations (XSLT) API. For more information about XSLT, turn to [Section 3.9, “XSL Transformations,”](#) on p. 223. Right now, consider the code that follows a magic incantation to produce XML output.

We apply the do-nothing transformation to the document and capture its output. To include a `DOCTYPE` node in the output, we also need to set the `SYSTEM` and `PUBLIC` identifiers as output properties.

[Click here to view code image](#)

```
// construct the do-nothing transformation
Transformer t = TransformerFactory.newInstance().newTransformer();
// set output properties to get a DOCTYPE node
t.setOutputProperty(OutputKeys.DOCTYPE_SYSTEM, systemIdentifier);
t.setOutputProperty(OutputKeys.DOCTYPE_PUBLIC, publicIdentifier);
// set indentation
t.setOutputProperty(OutputKeys.INDENT, "yes");
t.setOutputProperty(OutputKeys.METHOD, "xml");
t.setOutputProperty("{http://xml.apache.org/xslt}indent-amount",
"2");
// apply the do-nothing transformation and send the output to a
file
t.transform(new DOMSource(doc), new StreamResult(new
FileOutputStream(file)));
```

Another approach is to use the `LSSerializer` interface. To get an instance, you have to use the following magic incantation:

[Click here to view code image](#)

```
DOMImplementation impl = doc.getImplementation();
var implLS = (DOMImplementationLS) impl.getFeature("LS", "3.0");
LSSerializer ser = implLS.createLSSerializer();
```

If you want spaces and line breaks, set this flag:

[Click here to view code image](#)

```
ser.getDomConfig().setParameter("format-pretty-print", true);
```

Then it's simple enough to convert a document to a string:

[Click here to view code image](#)

```
String str = ser.writeToString(doc);
```

If you want to write the output directly to a file, you need an LSSOutput:

[Click here to view code image](#)

```
LSSOutput out = implLS.createLSSOutput();
out.setEncoding("UTF-8");
out.setByteStream(Files.newOutputStream(path));
ser.write(doc, out);
```

#### **javax.xml.parsers.DocumentBuilder 1.4**

- Document newDocument()  
returns an empty document.

#### **org.w3c.dom.Document 1.4**

- Element createElement(String name)
- Element createElementNS(String uri, String qname)

create an element with the given name.

- `Text createTextNode(String data)`

creates a text node with the given data.

#### ***org.w3c.dom.Node* 1.4**

- `Node appendChild(Node child)`

appends a node to the list of children of this node. Returns the appended node.

#### ***org.w3c.dom.Element* 1.4**

- `void setAttribute(String name, String value)`
- `void setAttributeNS(String uri, String qname, String value)`

set the attribute with the given name to the given value. If the qualified name has an alias prefix, then `uri` must not be null.

#### ***javax.xml.transform.TransformerFactory* 1.4**

- `static TransformerFactory newInstance()`

returns an instance of the `TransformerFactory` class.

- `Transformer newTransformer()`

returns an instance of the `Transformer` class that carries out an identity (do-nothing) transformation.

---

## **javax.xml.transform.Transformer 1.4**

- `void setOutputProperty(String name, String value)`

sets an output property. See [www.w3.org/TR/xslt#output](http://www.w3.org/TR/xslt#output) for a listing of the standard output properties. The most useful ones are shown here:

doctype-public	The public ID to be used in the DOCTYPE declaration
doctype-system	The system ID to be used in the DOCTYPE declaration
indent	"yes" or "no"
method	"xml", "html", "text", or a custom string

- `void transform(Source from, Result to)`

transforms an XML document.

---

## **javax.xml.transform.dom.DOMSource 1.4**

- `DOMSource(Node n)`

constructs a source from the given node. Usually, n is a document node.

---

## **javax.xml.transform.stream.StreamResult 1.4**

- `StreamResult(File f)`
- `StreamResult(OutputStream out)`

- StreamResult(Writer out)
- StreamResult(String systemID)  
construct a stream result from a file, stream, writer, or system ID (usually a relative or absolute URL).

### 3.8.4 Writing an XML Document with StAX

In the preceding section, you saw how to produce an XML document by writing a DOM tree. If you have no other use for the DOM tree, that approach is not very efficient.

The StAX API lets you write an XML tree directly. Construct an `XMLStreamWriter` from an `OutputStream`:

[Click here to view code image](#)

```
XMLOutputFactory factory = XMLOutputFactory.newInstance();
XMLStreamWriter writer = factory.createXMLStreamWriter(out);
```

To produce the XML header, call

```
writer.writeStartDocument();
```

Then call

[Click here to view code image](#)

```
writer.writeStartElement(name);
```

Add attributes by calling

[Click here to view code image](#)

```
writer.writeAttribute(name, value);
```

Now you can add child elements by calling `writeStartElement` again, or write characters with

```
writer.writeCharacters(text);
```

When you have written all child nodes, call

```
writer.writeEndElement();
```

This causes the current element to be closed.

To write an element without children (such as <img . . ./>), use the call

[Click here to view code image](#)

```
writer.writeEmptyElement(name);
```

Finally, at the end of the document, call

```
writer.writeEndDocument();
```

This call closes any open elements.

You still need to close the XMLStreamWriter, and you need to do it manually since the XMLStreamWriter interface does not extend the AutoCloseable interface.

As with the DOM/XSLT approach, you don't have to worry about escaping characters in attribute values and character data. However, it is possible to produce malformed XML, such as a document with multiple root nodes. Also, the current version of StAX has no support for producing indented output.

The program in [Listing 3.9](#) shows you both approaches for writing XML.

---

**Listing 3.9** write/XMLWriteTest.java

---

[Click here to view code image](#)

```
1 package write;
2
3 import java.io.*;
4 import java.nio.file.*;
5 import java.util.*;
6
7 import javax.xml.parsers.*;
```

```
8 import javax.xml.stream.*;
9 import javax.xml.transform.*;
10 import javax.xml.transform.dom.*;
11 import javax.xml.transform.stream.*;
12
13 import org.w3c.dom.*;
14
15 /**
16 * This program shows how to write an XML file. It produces
17 * modern art in SVG
18 * @version 1.13 2021-09-03
19 * @author Cay Horstmann
20 */
21 public class XMLWriteTest
22 {
23 public static void main(String[] args) throws Exception
24 {
25 Document doc = newDrawing(600, 400);
26 writeDocument(doc, "drawing1.svg");
27 writeNewDrawing(600, 400, "drawing2.svg");
28 }
29
30 private static Random generator = new Random();
31
32 /**
33 * Creates a new random drawing.
34 * @param drawingWidth the width of the drawing in pixels
35 * @param drawingHeight the width of the drawing in pixels
36 * @return the DOM tree of the SVG document
37 */
38 public static Document newDrawing(int drawingWidth, int
39 drawingHeight)
40 throws ParserConfigurationException
41 {
42 DocumentBuilderFactory factory =
43 DocumentBuilderFactory.newInstance();
44 factory.setNamespaceAware(true);
45 DocumentBuilder builder = factory.newDocumentBuilder();
```

```
44 String namespace = "http://www.w3.org/2000/svg";
45 Document doc = builder.newDocument();
46 Element svgElement = doc.createElementNS(namespace,
47 "svg");
48 doc.appendChild(svgElement);
49 svgElement.setAttribute("width", "" + drawingWidth);
50 svgElement.setAttribute("height", "" + drawingHeight);
51 int n = 10 + generator.nextInt(20);
52 for (int i = 1; i <= n; i++)
53 {
54 int x = generator.nextInt(drawingWidth);
55 int y = generator.nextInt(drawingHeight);
56 int width = generator.nextInt(drawingWidth - x);
57 int height = generator.nextInt(drawingHeight - y);
58 int r = generator.nextInt(256);
59 int g = generator.nextInt(256);
60 int b = generator.nextInt(256);
61
62 Element rectElement = doc.createElementNS(namespace,
63 "rect");
64 rectElement.setAttribute("x", "" + x);
65 rectElement.setAttribute("y", "" + y);
66 rectElement.setAttribute("width", "" + width);
67 rectElement.setAttribute("height", "" + height);
68 rectElement.setAttribute("fill",
69 "#%02x%02x%02x".formatted(r, g, b));
70 svgElement.appendChild(rectElement);
71 }
72
73 /**
74 * Saves a document using DOM/XSLT.
75 * @param doc the document to be written
76 * @param filename the name of the destination file
77 */
78 public static void writeDocument(Document doc, String
79 filename)
80 throws TransformerException, IOException
```

```
80 {
81 Transformer t =
82 TransformerFactory.newInstance().newTransformer();
83 t.setOutputProperty(OutputKeys.DOCTYPE_SYSTEM,
84 "http://www.w3.org/TR/2000/CR-SVG-20000802/DTD/svg-
85 20000802.dtd");
86 t.setOutputProperty(OutputKeys.DOCTYPE_PUBLIC,
87 "-//W3C//DTD SVG 20000802//EN");
88 t.setOutputProperty(OutputKeys.INDENT, "yes");
89 t.setOutputProperty(OutputKeys.METHOD, "xml");
90 t.setOutputProperty("{http://xml.apache.org/xslt}indent-
91 amount", "2");
92
93 /**
94 * Uses StAX to write an SVG document with a random drawing.
95 * @param drawingWidth the width of the drawing in pixels
96 * @param drawingHeight the width of the drawing in pixels
97 * @param filename the name of the destination file
98 */
99 public static void writeNewDrawing(int drawingWidth, int
100 drawingHeight,
101 String filename) throws XMLStreamException,
102 IOException
103 {
104 XMLOutputFactory factory =
105 XMLOutputFactory.newInstance();
106 XMLStreamWriter writer = factory.createXMLStreamWriter(
107 Files.newOutputStream(Path.of(filename)));
108 writer.writeStartDocument();
109 writer.writeDTD(""""
110 <!DOCTYPE svg PUBLIC "-//W3C//DTD SVG 20000802//EN"
111 "http://www.w3.org/TR/2000/CR-SVG-20000802/DTD/svg-
112 20000802.dtd">
113 """);
114 writer.writeStartElement("svg");
```

```

writer.writeDefaultNamespace("http://www.w3.org/2000/svg");
112 writer.writeAttribute("width", "" + drawingWidth);
113 writer.writeAttribute("height", "" + drawingHeight);
114 int n = 10 + generator.nextInt(20);
115 for (int i = 1; i <= n; i++)
116 {
117 int x = generator.nextInt(drawingWidth);
118 int y = generator.nextInt(drawingHeight);
119 int width = generator.nextInt(drawingWidth - x);
120 int height = generator.nextInt(drawingHeight - y);
121 int r = generator.nextInt(256);
122 int g = generator.nextInt(256);
123 int b = generator.nextInt(256);
124 writer.writeEmptyElement("rect");
125 writer.writeAttribute("x", "" + x);
126 writer.writeAttribute("y", "" + y);
127 writer.writeAttribute("width", "" + width);
128 writer.writeAttribute("height", "" + height);
129 writer.writeAttribute("fill",
"#" + "%02x" + "%02x" + "%02x".formatted(r, g, b));
130 }
131 writer.writeEndDocument(); // closes svg element
132 }
133 }
```

---

## **javax.xml.stream.XMLOutputFactory 6**

- static XMLOutputFactory newInstance()  
returns an instance of the XMLOutputFactory class.
- XMLStreamWriter  
createXMLStreamWriter(OutputStream stream)
- XMLStreamWriter  
createXMLStreamWriter(OutputStream stream,  
String encoding)

- `XMLStreamWriter createXMLStreamWriter(Writer writer)`
- `XMLStreamWriter createXMLStreamWriter(Result result)`

create a writer that writes to the given stream, writer, or JAXP result.

## ***javax.xml.stream.XMLStreamWriter*** 6

- `void writeStartDocument()`
- `void writeStartDocument(String xmlVersion)`
- `void writeStartDocument(String encoding, String xmlVersion)`

write the XML processing instruction at the top of the document. Note that the `encoding` parameter is only used to write the attribute. It does not set the character encoding of the output.

- `void setDefaultNamespace(String namespaceURI)`
- `void setPrefix(String prefix, String namespaceURI)`

set the default namespace or the namespace associated with a prefix. The declaration is scoped to the current element or, if no element has been written, to the document root.

- `void writeStartElement(String localName)`
- `void writeStartElement(String namespaceURI, String localName)`

write a start tag, replacing the `namespaceURI` with the associated prefix.

- `void writeEndElement()`

closes the current element.

- `void writeEndDocument()`  
closes all open elements.
- `void writeEmptyElement(String localName)`
- `void writeEmptyElement(String namespaceURI, String localName)`  
write a self-closing tag, replacing the namespaceURI with the associated prefix.
- `void writeAttribute(String localName, String value)`
- `void writeAttribute(String namespaceURI, String localName, String value)`  
write an attribute for the current element, replacing the namespaceURI with the associated prefix.
- `void writeCharacters(String text)`  
writes character data.
- `void writeCData(String text)`  
writes a CDATA block.
- `void writeDTD(String dtd)`  
writes the dtd string, which is assumed to contain a DOCTYPE declaration.
- `void writeComment(String comment)`  
writes a comment.
- `void close()`  
closes this writer.

### 3.8.5 An Example: Generating an SVG File

[Listing 3.9](#) on p. 218 is a typical program that produces XML output. The program draws a modernist painting—a random set of colored rectangles (see [Figure 3.3](#)). To save our masterpiece, we use the Scalable Vector Graphics (SVG) format. SVG is an XML format to describe complex graphics in a device-independent fashion. You can find more information about SVG at [www.w3.org/Graphics/SVG](http://www.w3.org/Graphics/SVG). To view SVG files, simply use any modern browser.

The program demonstrates two ways of producing XML: by constructing and saving a DOM tree, and by directly writing the XML with the StAX API.

We don't need to go into details about SVG; for our purposes, we just need to know how to express a set of colored rectangles. Here is a sample:

[Click here to view code image](#)

```
<?xml version="1.0" encoding="UTF-8"?>
<!DOCTYPE svg PUBLIC "-//W3C//DTD SVG 20000802//EN"
 "http://www.w3.org/TR/2000/CR-SVG-20000802/DTD/svg-
20000802.dtd">
<svg xmlns="http://www.w3.org/2000/svg" width="300" height="150">
 <rect x="231" y="61" width="9" height="12" fill="#6e4a13"/>
 <rect x="107" y="106" width="56" height="5" fill="#c406be"/>
 . . .
</svg>
```



### Figure 3.3 Generating modern art

As you can see, each rectangle is described as a `rect` node. The position, width, height, and fill color are attributes. The fill color is an RGB value in hexadecimal.

---



#### Note

SVG uses attributes heavily. In fact, some attributes are quite complex. For example, here is a path element:

[Click here to view code image](#)

```
<path d="M 100 100 L 300 100 L 200 300 z">
```


The `M` denotes a "moveto" command, `L` is "lineto," and `z` is "closepath" (!). Apparently, the designers of this data format didn't have much confidence in using XML for structured data. In your own XML formats, you might want to use elements instead of complex attributes.

---

## 3.9 XSL Transformations

The XSL Transformations (XSLT) mechanism allows you to specify rules for transforming XML documents into other formats, such as plain text, XHTML, or any other XML format. XSLT is commonly used to translate from one machine-readable XML format to another, or to translate XML into a presentation format for human consumption.

You need to provide an XSLT stylesheet that describes the conversion of XML documents into some other format. An XSLT processor reads an XML document and the stylesheet and produces the desired output (see [Figure 3.4](#)).



**Figure 3.4** Applying XSL transformations

The XSLT specification is quite complex, and entire books have been written on the subject. We can't possibly discuss all the features of XSLT, so we will just work through a representative example. You can find more information in the book *Essential XML* by Don Box et al. The XSLT specification is available at [www.w3.org/TR/xslt](http://www.w3.org/TR/xslt).

Suppose we want to transform XML files with employee records into HTML documents. Consider this input file:

[Click here to view code image](#)

```

<staff>
 <employee>
 <name>Carl Cracker</name>
 <salary>75000.0</salary>
 <hiredate year="1987" month="12" day="15"/>
 </employee>
 <employee>
 <name>Harry Hacker</name>
 <salary>50000.0</salary>
 <hiredate year="1989" month="10" day="1"/>
 </employee>
 <employee>
 <name>Tony Tester</name>

```

```

<salary>40000.0</salary>
<hiredate year="1990" month="3" day="15"/>
</employee>
</staff>

```

The desired output is an HTML table:

[Click here to view code image](#)

```

<table border="1">
<tr>
<td>Carl Cracker</td><td>$75000.0</td><td>1987-12-15</td>
</tr>
<tr>
<td>Harry Hacker</td><td>$50000.0</td><td>1989-10-1</td>
</tr>
<tr>
<td>Tony Tester</td><td>$40000.0</td><td>1990-3-15</td>
</tr>
</table>

```

A stylesheet with transformation templates has this form:

[Click here to view code image](#)

```

<?xml version="1.0" encoding="ISO-8859-1"?>
<xsl:stylesheet
 xmlns:xsl="http://www.w3.org/1999/XSL/Transform"
 version="1.0">
 <xsl:output method="html"/>
 template1
 template2
 . . .
</xsl:stylesheet>

```

In our example, the `xsl:output` element specifies the method as HTML. Other valid method settings are `xml` and `text`.

Here is a typical template:

[Click here to view code image](#)

```
<xsl:template match="/staff/employee">
 <tr><xsl:apply-templates/></tr>
</xsl:template>
```

The value of the `match` attribute is an XPath expression. The template states: Whenever you see a node in the XPath set `/staff/employee`, do the following:

1. Emit the string `<tr>`.
2. Keep applying templates as you process its children.
3. Emit the string `</tr>` after you are done with all children.

In other words, this template generates the HTML table row markers around every employee record.

The XSLT processor starts processing by examining the root element. Whenever a node matches one of the templates, it applies the template. (If multiple templates match, the best matching one is used; see the specification at [www.w3.org/TR/xslt](http://www.w3.org/TR/xslt) for the gory details.) If no template matches, the processor carries out a default action. For text nodes, the default is to include the contents in the output. For elements, the default action is to create no output but to keep processing the children.

Here is a template for transforming `name` nodes in an employee file:

[Click here to view code image](#)

```
<xsl:template match="/staff/employee/name">
 <td><xsl:apply-templates/></td>
</xsl:template>
```

As you can see, the template produces the `<td> . . . </td>` delimiters, and it asks the processor to recursively visit the children of the `name` element. There is just one child—the text node. When the processor visits that node, it emits the text contents (provided, of course, that there is no other matching template).

You have to work a little harder if you want to copy attribute values into the output. Here is an example:

[Click here to view code image](#)

```
<xsl:template match="/staff/employee/hiredate">
 <td><xsl:value-of select="@year"/>-<xsl:value-of
 select="@month"/>-<xsl:value-of select="@day"/></td>
</xsl:template>
```

When processing a `hiredate` node, this template emits

1. The string `<td>`
2. The value of the `year` attribute
3. A hyphen
4. The value of the `month` attribute
5. A hyphen
6. The value of the `day` attribute
7. The string `</td>`

The `xsl:value-of` statement computes the string value of a node set. The node set is specified by the XPath value of the `select` attribute. In this case, the path is relative to the currently processed node. The node set is converted to a string by concatenation of the string values of all nodes. The string value of an attribute node is its value. The string value of a text node is its contents. The string value of an element node is the concatenation of the string values of its child nodes (but not its attributes).

[Listing 3.10](#) contains the stylesheet for turning an XML file with employee records into an HTML table.

[Listing 3.11](#) shows a different set of transformations. The input is the same XML file, and the output is plain text in the familiar property file format:

[Click here to view code image](#)

```
employee.1.name=Carl Cracker
employee.1.salary=75000.0
employee.1.hiredate=1987-12-15
employee.2.name=Harry Hacker
employee.2.salary=50000.0
employee.2.hiredate=1989-10-1
```

```
employee.3.name=Tony Tester
employee.3.salary=40000.0
employee.3.hiredate=1990-3-15
```

That example uses the `position()` function which yields the position of the current node as seen from its parent. We thus get an entirely different output simply by switching the stylesheet. This means you can safely use XML to describe your data; if some applications need the data in another format, just use XSLT to generate the alternative format.

It is simple to generate XSL transformations on the Java platform. Set up a transformer factory for each stylesheet. Then, get a transformer object and tell it to transform a source to a result:

[Click here to view code image](#)

```
var styleSheet = new File(filename);
var styleSource = new StreamSource(styleSheet);
Transformer t =
TransformerFactory.newInstance().newTransformer(styleSource);
t.transform(source, result);
```

The parameters of the `transform` method are objects of classes that implement the `Source` and `Result` interfaces. Several classes implement the `Source` interface:

```
DOMSource
SAXSource
StAXSource
StreamSource
```

You can construct a `StreamSource` from a file, stream, reader, or URL, and a `DOMSource` from the node of a DOM tree. For example, in the preceding section, we invoked the identity transformation as

[Click here to view code image](#)

```
t.transform(new DOMSource(doc), result);
```

In our example program, we do something slightly more interesting. Instead of starting out with an existing XML file, we produce a SAX XML reader that gives the illusion of parsing an XML file by emitting appropriate SAX events. Actually, our XML reader reads a flat file, as described in [Chapter 1](#). The input file looks like this:

[Click here to view code image](#)

```
Carl Cracker|75000.0|1987|12|15
Harry Hacker|50000.0|1989|10|1
Tony Tester|40000.0|1990|3|15
```

Our XML reader generates SAX events as it processes the input. Here is a part of the `parse` method of the `EmployeeReader` class that implements the `XMLReader` interface:

[Click here to view code image](#)

```
var attributes = new AttributesImpl();
handler.startDocument();
handler.startElement("", "staff", "staff", attributes);
boolean done = false;
while (!done)
{
 String line = in.readLine();
 if (line == null) done = true;
 else
 {
 handler.startElement("", "employee", "employee",
attributes);
 var tokenizer = new StringTokenizer(line, "|");
 handler.startElement("", "name", "name", attributes);
 String s = tokenizer.nextToken();
 handler.characters(s.toCharArray(), 0, s.length());
 handler.endElement("", "name", "name");
 . .
 handler.endElement("", "employee", "employee");
 }
}
handler.endElement("", rootElement, rootElement);
handler.endDocument();
```

The SAXSource for the transformer is constructed from the XML reader:

[Click here to view code image](#)

```
t.transform(new SAXSource(new EmployeeReader(),
 new InputSource(new FileInputStream(filename))), result);
```

This is an ingenious trick to convert non-XML legacy data into XML. Of course, most XSLT applications will already have XML input data, and you can simply invoke the `transform` method on a StreamSource:

[Click here to view code image](#)

```
t.transform(new StreamSource(file), result);
```

The transformation result is an object of a class that implements the `Result` interface. The Java library supplies three classes:

```
DOMResult
SAXResult
StreamResult
```

To store the result in a DOM tree, use a `DocumentBuilder` to generate a new document node and wrap it into a `DOMResult`:

[Click here to view code image](#)

```
Document doc = builder.newDocument();
t.transform(source, new DOMResult(doc));
```

To save the output in a file, use a `StreamResult`:

[Click here to view code image](#)

```
t.transform(source, new StreamResult(file));
```

[Listing 3.12](#) contains the complete source code.

---

**Listing 3.10** transform/makehtml.xsl

---

[Click here to view code image](#)

```
1 <?xml version="1.0" encoding="ISO-8859-1"?>
2
3 <xsl:stylesheet
4 xmlns:xsl="http://www.w3.org/1999/XSL/Transform"
5 version="1.0">
6
7 <xsl:output method="html"/>
8
9 <xsl:template match="/staff">
10 <table border="1"><xsl:apply-templates/></table>
11 </xsl:template>
12
13 <xsl:template match="/staff/employee">
14 <tr><xsl:apply-templates/></tr>
15 </xsl:template>
16
17 <xsl:template match="/staff/employee/name">
18 <td><xsl:apply-templates/></td>
19 </xsl:template>
20
21 <xsl:template match="/staff/employee/salary">
22 <td>$<xsl:apply-templates/></td>
23 </xsl:template>
24
25 <xsl:template match="/staff/employee/hiredate">
26 <td><xsl:value-of select="@year"/>-<xsl:value-of
27 select="@month"/>-<xsl:value-of select="@day"/></td>
28 </xsl:template>
29
30 </xsl:stylesheet>
```

---

### **Listing 3.11 transform/makeprop.xsl**

[Click here to view code image](#)

```
1 <?xml version="1.0"?>
2
3 <xsl:stylesheet
```

```
4 xmlns:xsl="http://www.w3.org/1999/XSL/Transform"
5 version="1.0">
6
7 <xsl:output method="text" omit-xml-declaration="yes"/>
8
9 <xsl:template match="/staff/employee">
10 employee.<xsl:value-of select="position()" />.
11 name=<xsl:value-of select="name/text()"/>
12 employee.<xsl:value-of select="position()" />.
13 salary=<xsl:value-of select="salary/text()"/>
14 employee.<xsl:value-of select="position()" />.
15 hiredate=<xsl:value-of select="hiredate/@year" />-
16 <xsl:value-of select="hiredate/@month" />-
17 <xsl:value-of select="hiredate/@day" />
18 </xsl:template>
19
20 </xsl:stylesheet>
```

---

### **Listing 3.12** transform/TransformTest.java

[Click here to view code image](#)

```
1 package transform;
2
3 import java.io.*;
4 import java.nio.file.*;
5 import java.util.*;
6 import javax.xml.transform.*;
7 import javax.xml.transform.sax.*;
8 import javax.xml.transform.stream.*;
9 import org.xml.sax.*;
10 import org.xml.sax.helpers.*;
11
12 /**
13 * This program demonstrates XSL transformations. It applies a
14 * transformation to a set of
15 * employee records. The records are stored in the file
16 * employee.dat and turned into XML
17 * format. Specify the stylesheet on the command line, e.g.

```

```
16 * java transform.TransformTest transform/makeprop.xsl
17 * @version 1.05 2021-09-21
18 * @author Cay Horstmann
19 */
20 public class TransformTest
21 {
22 public static void main(String[] args) throws Exception
23 {
24 Path path;
25 if (args.length > 0) path = Path.of(args[0]);
26 else path = Path.of("transform", "makehtml.xsl");
27 try (InputStream styleIn = Files.newInputStream(path))
28 {
29 var styleSource = new StreamSource(styleIn);
30
31 Transformer t =
32 TransformerFactory.newInstance().newTransformer(styleSource);
33 t.setOutputProperty(OutputKeys.INDENT, "yes");
34 t.setOutputProperty(OutputKeys.METHOD, "xml");
35 t.setOutputProperty(
36 "{http://xml.apache.org/xslt}indent-amount", "2");
37 try (InputStream docIn =
38 Files.newInputStream(Path.of("transform", "employee.dat")))
39 {
40 t.transform(new SAXSource(new EmployeeReader(), new
41 InputSource(docIn)),
42 new StreamResult(System.out));
43 }
44 }
45 /**
46 * This class reads the flat file employee.dat and reports SAX
47 * parser events to act as if it
48 * was parsing an XML file.
49 */
50 class EmployeeReader implements XMLReader
51 {
```

```
51 private ContentHandler handler;
52
53 public void parse(InputSource source) throws IOException,
54 SAXException
54 {
55 InputStream stream = source.getByteStream();
56 var in = new BufferedReader(new
57 InputStreamReader(stream));
58 var atts = new AttributesImpl();
59
60 if (handler == null) throw new SAXException("No content
61 handler");
62
63 handler.startDocument();
64 handler.startElement("", "staff", "staff", atts);
65 boolean done = false;
66 while (!done)
67 {
68 String line = in.readLine();
69 if (line == null) done = true;
70 else
71 handler.startElement("", "employee", "employee",
72 atts);
73 var t = new StringTokenizer(line, "|");
74
75 handler.startElement("", "name", "name", atts);
76 String s = t.nextToken();
77 handler.characters(s.toCharArray(), 0,
78 s.length());
79 handler.endElement("", "name", "name");
80
81 handler.startElement("", "salary", "salary",
82 atts);
83 s = t.nextToken();
84 handler.characters(s.toCharArray(), 0,
85 s.length());
86 handler.endElement("", "salary", "salary");
87 atts.addAttribute("", "year", "year", "CDATA",
88 "
```

```
t.nextToken();
84 atts.addAttribute("", "month", "month", "CDATA",
t.nextToken();
85 atts.addAttribute("", "day", "day", "CDATA",
t.nextToken();
86 handler.startElement("", "hiredate", "hiredate",
atts);
87 handler.endElement("", "hiredate", "hiredate");
88 atts.clear();
89
90 handler.endElement("", "employee", "employee");
91 }
92 }
93
94 handler.endElement("", "staff", "staff");
95 handler.endDocument();
96 }
97
98 public void setContentHandler(ContentHandler newValue)
99 {
100 handler = newValue;
101 }
102
103 public ContentHandler getContentHandler()
104 {
105 return handler;
106 }
107
108 // the following methods are just do-nothing implementations
109 public void parse(String systemId) throws IOException,
SAXException {}
110 public void setErrorHandler(ErrorHandler handler) {}
111 public ErrorHandler getErrorHandler() { return null; }
112 public void setDTDHandler(DTDHandler handler) {}
113 public DTDHandler getDTDHandler() { return null; }
114 public void setEntityResolver(EntityResolver resolver) {}
115 public EntityResolver getEntityResolver() { return null; }
116 public void setProperty(String name, Object value) {}
117 public Object getProperty(String name) { return null; }
```

```
118 public void setFeature(String name, boolean value) { }
119 public boolean getFeature(String name) { return false; }
120 }
```

---

#### **javax.xml.transform.TransformerFactory 1.4**

- `Transformer newTransformer(Source styleSheet)`  
returns an instance of the `Transformer` class that reads a stylesheet from the given source.

#### **javax.xml.transform.stream.StreamSource 1.4**

- `StreamSource(File f)`
- `StreamSource(InputStream in)`
- `StreamSource(Reader in)`
- `StreamSource(String systemID)`  
construct a stream source from a file, stream, reader, or system ID (usually a relative or absolute URL).

#### **javax.xml.transform.sax.SAXSource 1.4**

- `SAXSource(XMLReader reader, InputSource source)`  
constructs a SAX source that obtains data from the given input source and uses the given reader to parse the input.

#### **org.xml.sax.XMLReader 1.4**

- `void setContentHandler(ContentHandler handler)`  
sets the handler that is notified of parse events as the input is parsed.
- `void parse(InputSource source)`  
parses the input from the given input source and sends parse events to the content handler.

#### **javax.xml.transform.dom.DOMResult 1.4**

- `DOMResult (Node n)`  
constructs a source from the given node. Usually, `n` is a new document node.

#### **org.xml.sax.helpers.AttributesImpl 1.4**

- `void addAttribute(String uri, String lname, String qname, String type, String value)`  
adds an attribute to this attribute collection. The `lname` parameter is the local name without prefix, and `qname` is the qualified name with prefix. The `type` parameter is one of "CDATA", "ID", "IDREF", "IDREFS", "NMTOKEN", "NMTOKENS", "ENTITY", "ENTITIES", or "NOTATION".
- `void clear()`  
removes all attributes from this attribute collection.

This example concludes our discussion of XML support in the Java library. You should now have a good perspective on the major strengths of XML—in particular, its automated parsing and validation as well as its powerful

transformation mechanism. Of course, all this technology is only going to work for you if you design your XML formats well. You need to make sure that the formats are rich enough to express all your business needs, that they are stable over time, and that your business partners are willing to accept your XML documents. Those issues can be far more challenging than dealing with parsers, DTDs, or transformations.

In the next chapter, we will discuss network programming on the Java platform, starting with the basics of network sockets and moving on to higher-level protocols for e-mail and the World Wide Web.

---

# Chapter 4. Networking

---

## In this chapter

- [4.1 Connecting to a Server](#)
- [4.2 Implementing Servers](#)
- [4.3 Getting Web Data](#)
- [4.4 The HTTP Client](#)
- [4.5 Sending E-Mail](#)

We begin this chapter by reviewing basic networking concepts, then move on to writing Java programs that connect to network services. We will show you how network clients and servers are implemented. Finally, you will see how to send e-mail from a Java program and how to harvest information from a web server.

## 4.1 Connecting to a Server

In the following sections, you will connect to a server, first by hand and with telnet, and then with a Java program.

### 4.1.1 Using Telnet

The telnet program is a great debugging tool for network programming. You should be able to launch it by typing `telnet` from a command shell.



Note

In Windows, you need to activate telnet. Go to the Control Panel, select Programs, click Turn Windows Features On or Off, and select the Telnet client checkbox. The Windows firewall also blocks quite a few network ports that we use in this chapter; you might need an administrator account to unblock them.

---

You may have used telnet to connect to a remote computer, but you can use it to communicate with other services provided by Internet hosts as well. Here is an example of what you can do. Type


```
telnet time-a.nist.gov 13
```

As [Figure 4.1](#) shows, you should get back a line like this:

[Click here to view code image](#)

```
57488 16-04-10 04:23:00 50 0 0 610.5 UTC(NIST) *
```

[Click here to view code image](#)

A screenshot of a terminal window titled "Terminal". The window shows the command "telnet time-a.nist.gov 13" being run, followed by the server's response: "Trying 129.6.15.28...", "Connected to time-a.nist.gov.", "Escape character is '^]'.", and finally the timestamp "57488 16-04-10 04:23:00 50 0 0 610.5 UTC(NIST) \*". The window has a standard Windows-style title bar and scroll bars.

```
~$ telnet time-a.nist.gov 13
Trying 129.6.15.28...
Connected to time-a.nist.gov.
Escape character is '^]'.

57488 16-04-10 04:23:00 50 0 0 610.5 UTC(NIST) *
Connection closed by foreign host.
~$
```

**Figure 4.1** Output of the “time of day” service

What is going on? You have connected to the “time of day” service that most UNIX machines constantly run. The particular server that you connected to is operated by the National Institute of Standards and Technology and gives the measurement of a Cesium atomic clock. (Of course, the reported time is not completely accurate due to network delays.)


By convention, the “time of day” service is always attached to “port” number 13.



### Note

In network parlance, a port is not a physical device, but an abstraction facilitating communication between a server and a client (see [Figure 4.2](#)).

[Click here to view code image](#)



**Figure 4.2** A client connecting to a server port

The server software is continuously running on the remote machine, waiting for any network traffic that wants to chat with port 13. When the operating system on the remote computer receives a network package that contains a request to connect to port number 13, it wakes up the listening server process and establishes the connection. The connection stays up until it is terminated by one of the parties.

When you began the telnet session with `time-a.nist.gov` at port 13, a piece of network software knew enough to convert the string "`time-a.nist.gov`" to its correct Internet Protocol (IP) address, 129.6.15.28. The telnet software then sent a connection request to that address, asking for a connection to port 13. Once the connection was established, the remote program sent back a line of data and closed the connection. In general, of course, clients and servers engage in a more extensive dialog before one or the other closes the connection.

Here is another experiment along the same lines—but a bit more interesting. Type

```
telnet horstmann.com 80
```

Then type very carefully the following:

```
GET / HTTP/1.1
Host: horstmann.com
blank line
```

That is, hit the Enter key twice at the end.

[Figure 4.3](#) shows the response. It should look eerily familiar—you got a page of HTML-formatted text, namely Cay Horstmann's home page.

[Click here to view code image](#)



A screenshot of a terminal window titled "Terminal". The window shows the output of a telnet session to the port 80 of the host "horstmann.com". The session starts with the command "\$ telnet horstmann.com 80", followed by the server's response: "Trying 67.210.118.65...", "Connected to horstmann.com.", "Escape character is '^]'.", "GET / HTTP/1.1", and "Host: horstmann.com". The server then sends an HTTP response header, followed by the HTML content of the page, which includes the XML declaration, DOCTYPE, and the HTML document structure with a title and a link to a stylesheet.

```
$ telnet horstmann.com 80
Trying 67.210.118.65...
Connected to horstmann.com.
Escape character is '^]'.
GET / HTTP/1.1
Host: horstmann.com

HTTP/1.1 200 OK
Date: Sun, 10 Apr 2016 04:36:27 GMT
Server: Apache/2.2.24 (Unix) mod_ssl/2.2.24 OpenSSL/0.9.8e-fips-rhel5 mod_auth_p
assthrough/2.1 mod_bwlimited/1.4 mod_fcgid/2.3.6 Sun-ONE-ASP/4.0.3
Last-Modified: Thu, 17 Mar 2016 18:32:18 GMT
ETag: "2590e1c-1c47-52e42d9a8f080"
Accept-Ranges: bytes
Content-Length: 7239
Content-Type: text/html

<?xml version="1.0" encoding="UTF-8"?>
<!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Strict//EN" "http://www.w3.org/TR/x
html1/DTD/xhtml1-strict.dtd">
<html xmlns="http://www.w3.org/1999/xhtml"><head>
 <title>Cay Horstmann's Home Page</title>
 <link href="styles.css" rel="stylesheet" type="text/css"/>
```

**Figure 4.3** Using telnet to access an HTTP port

This is exactly the same process that your web browser goes through to get a web page. It uses HTTP to request web pages from servers. Of course, the browser displays the HTML code more nicely.



### Note

The `Host` key/value pair is required when you connect to a web server that hosts multiple domains at the same IP address. You can omit it if the server hosts a single domain.

#### 4.1.2 Connecting to a Server with Java

Our first network program in [Listing 4.1](#) will do the same thing we did using telnet—connect to a port and print out what it finds.

##### **Listing 4.1** socket/SocketTest.java

[Click here to view code image](#)

```

1 package socket;
2
3 import java.io.*;
4 import java.net.*;
5 import java.nio.charset.*;
6 import java.util.*;
7
8 /**
9 * This program makes a socket connection to the atomic clock in
Boulder, Colorado, and
10 * prints the time that the server sends.
11 * @version 1.22 2018-03-17
12 * @author Cay Horstmann
13 */
14 public class SocketTest
15 {
16 public static void main(String[] args) throws IOException
17 {
18 try (var s = new Socket("time-a.nist.gov", 13);
19 var in = new Scanner(s.getInputStream(),
StandardCharsets.UTF_8))
20 {
21 while (in.hasNextLine())
22 {
23 String line = in.nextLine();
24 System.out.println(line);
25 }
26 }
27 }
28 }
```

---

The key statements of this simple program are these:

[Click here to view code image](#)

```
var s = new Socket("time-a.nist.gov", 13);
InputStream inStream = s.getInputStream();
```

The first line opens a *socket*, which is a network software abstraction that enables communication out of and into this program. We pass the remote address and the port number to the socket constructor. If the connection fails, an

`UnknownHostException` is thrown. If there is another problem, an `IOException` occurs. Since `UnknownHostException` is a subclass of `IOException` and this is a sample program, we just catch the superclass.

Once the socket is open, the `getInputStream` method in `java.net.Socket` returns an `InputStream` object that you can use just like any other stream. Once you have grabbed the stream, this program simply prints each input line to standard output. This process continues until the stream is finished and the server disconnects.

This program works only with very simple servers, such as a “time of day” service. In more complex networking programs, the client sends request data to the server, and the server might not immediately disconnect at the end of a response. You will see how to implement that behavior in several examples throughout this chapter.

The `Socket` class is pleasant and easy to use because the Java library hides the complexities of establishing a networking connection and sending data across it. The `java.net` package essentially gives you the same programming interface you would use to work with a file.

---



## Note

In this book, we cover only the Transmission Control Protocol (TCP). The Java platform also supports the User Datagram Protocol (UDP), which can be used to send packets (also called *datagrams*) with much less overhead than TCP. The drawback is that packets need not be delivered in sequential order to the receiving application and can even be dropped altogether. It is up to the recipient to put the packets in order and to request retransmission of missing packets. UDP is well suited for applications in which missing packets can be tolerated—for example, for audio or video streams or continuous measurements.

---

### `java.net.Socket` 1.0

- `Socket(String host, int port)`

constructs a socket to connect to the given host and port.

- `InputStream getInputStream()`
  - `OutputStream getOutputStream()`
- get the stream to read data from the socket or write data to the socket.

### 4.1.3 Socket Timeouts

Reading from a socket blocks until data are available. If the host is unreachable, your application waits for a long time and you are at the mercy of the underlying operating system to eventually time out.

You can decide what timeout value is reasonable for your particular application. Then, call the `setSoTimeout` method to set a timeout value (in milliseconds).

[Click here to view code image](#)

```
var s = new Socket(. . .);
s.setSoTimeout(10000); // time out after 10 seconds
```

If the timeout value has been set for a socket, all subsequent read operations throw a `SocketTimeoutException` when the timeout has been reached before the operation has completed its work. You can catch that exception and react to the timeout.

[Click here to view code image](#)

```
try
{
 InputStream in = s.getInputStream(); // read from in
 . . .
}
catch (SocketTimeoutException e)
{
 react to timeout
}
```

There is no timeout for write operations.

There is one additional timeout issue that you need to address. The constructor

```
Socket(String host, int port)
```

can block indefinitely until an initial connection to the host is established.

You can overcome this problem by first constructing an unconnected socket and then connecting it with a timeout:

[Click here to view code image](#)

```
var s = new Socket();
s.connect(new InetSocketAddress(host, port), timeout);
```

See [Section 4.2.4, “Interruptible Sockets,”](#) on p. 252 for how to allow users to interrupt a socket connection at any time.

### **java.net.Socket 1.0**

- **Socket() 1.1**  
creates a socket that has not yet been connected.
- **void connect(SocketAddress address) 1.4**  
connects this socket to the given address.
- **void connect(SocketAddress address, int timeoutInMilliseconds) 1.4**  
connects this socket to the given address, or returns if the time interval expired.
- **void setSoTimeout(int timeoutInMilliseconds) 1.1**  
sets the blocking time for read requests on this socket. If the timeout is reached, a `SocketTimeoutException` is raised.
- **boolean isConnected() 1.4**  
returns `true` if the socket is connected.
- **boolean isClosed() 1.4**  
returns `true` if the socket is closed.

#### 4.1.4 Internet Addresses

Usually, you don't have to worry too much about Internet addresses—the numerical host addresses that consist of 4 bytes (or, with IPv6, 16 bytes) such as 129.6.15.28. However, you can use the `InetAddress` class if you need to convert between host names and Internet addresses.

The `java.net` package supports IPv6 Internet addresses, provided the host operating system does.

The static `getByName` method returns an `InetAddress` object of a host. For example,

[Click here to view code image](#)

```
InetAddress address = InetAddress.getByName("time-a.nist.gov");
```

returns an `InetAddress` object that encapsulates the sequence of four bytes 129.6.15.28. You can access the bytes with the `getAddress` method.

[Click here to view code image](#)

```
byte[] addressBytes = address.getAddress();
```

Some host names with a lot of traffic correspond to multiple Internet addresses, to facilitate load balancing. For example, at the time of this writing, the host name `google.com` corresponds to twelve different Internet addresses. One of them is picked at random when the host is accessed. You can get all hosts with the `getAllByName` method.

[Click here to view code image](#)

```
InetAddress[] addresses = InetAddress.getAllByName(host);
```

Finally, you sometimes need the address of the local host. If you simply ask for the address of `localhost`, you always get the local loopback address 127.0.0.1, which cannot be used by others to connect to your computer. Instead, use the static `getLocalHost` method to get the address of your local host.

[Click here to view code image](#)

```
InetAddress address = InetAddress.getLocalHost();
```

[Listing 4.2](#) is a simple program that prints the Internet address of your local host if you do not specify any command-line parameters, or all Internet addresses of another host if you specify the host name on the command line, such as

[Click here to view code image](#)

```
java inetAddress/InetAddressTest www.horstmann.com
```

---

### **Listing 4.2** `inetAddress/InetAddressTest.java`

---

[Click here to view code image](#)

```
1 package inetAddress;
2
3 import java.io.*;
4 import java.net.*;
5
6 /**
7 * This program demonstrates the InetAddress class. Supply a host
8 * name as command-line
9 * argument, or run without command-line arguments to see the
10 address of the local host.
11 *
12 public class InetAddressTest
13 {
14 public static void main(String[] args) throws IOException
15 {
16 if (args.length > 0)
17 {
18 String host = args[0];
19 InetAddress[] addresses = InetAddress.getAllByName(host);
20 for (InetAddress a : addresses)
21 System.out.println(a);
22 }
23 else
24 {
25 InetAddress localHostAddress = InetAddress.getLocalHost();
26 System.out.println(localHostAddress);
27 }
```

```
28 }
29 }
```

---

### **java.net.InetAddress 1.0**

- static InetAddress getByName(String host)  
construct an InetAddress, or an array of all Internet addresses, for the given host name.
- static InetAddress getLocalHost()  
constructs an InetAddress for the local host.
- byte[] getAddress()  
returns an array of bytes that contains the numerical address.
- String getHostAddress()  
returns a string with decimal numbers, separated by periods, for example "129.6.15.28".
- String getHostName()  
returns the host name.

## **4.2 Implementing Servers**

Now that we have implemented a basic network client that receives data from the Internet, let's program a simple server that can send information to clients.

### **4.2.1 Server Sockets**

A server program, when started, waits for a client to attach to its port. For our example program, we chose port number 8189, which is not used by any of the

standard services. The `ServerSocket` class establishes a socket. In our case, the command

[Click here to view code image](#)

```
var s = new ServerSocket(8189);
```

establishes a server that monitors port 8189. The command

```
Socket incoming = s.accept();
```

tells the program to wait indefinitely until a client connects to that port. Once someone connects to this port by sending the correct request over the network, this method returns a `Socket` object that represents the connection that was made. You can use this object to get input and output streams, as is shown in the following code:

[Click here to view code image](#)

```
InputStream inStream = incoming.getInputStream();
OutputStream outStream = incoming.getOutputStream();
```

Everything that the server sends to the server output stream becomes the input of the client program, and all the output from the client program ends up in the server input stream.

In all the examples in this chapter, we transmit text through sockets. We therefore turn the streams into scanners and writers.

[Click here to view code image](#)

```
var in = new Scanner(inStream, StandardCharsets.UTF_8);
var out = new PrintWriter(new OutputStreamWriter(outStream,
StandardCharsets.UTF_8),
true /* autoFlush */);
```

Let's send the client a greeting:

[Click here to view code image](#)

```
out.println("Hello! Enter BYE to exit.");
```

When you use telnet to connect to this server program at port 8189, you will see this greeting on the terminal screen.

In this simple server, we just read the client's input, a line at a time, and echo it. This demonstrates that the program receives the input. An actual server would obviously compute and return an answer depending on the input.

[Click here to view code image](#)

```
String line = in.nextLine();
out.println("Echo: " + line);
if (line.strip().equals("BYE")) done = true;
```

In the end, we close the incoming socket.

```
incoming.close();
```

That is all there is to it. Every server program, such as an HTTP web server, continues performing this loop:

1. It receives a command from the client ("get me this information") through an incoming data stream.
2. It decodes the client command.
3. It gathers the information that the client requested.
4. It sends the information to the client through the outgoing data stream.

[Listing 4.3](#) is the complete program.

---

### **Listing 4.3** server/EchoServer.java

---

[Click here to view code image](#)

```
1 package server;
2
3 import java.io.*;
4 import java.net.*;
5 import java.nio.charset.*;
6 import java.util.*;
7
8 /**
9 * This program implements a simple server that listens to port
```

```
8189 and echoes back all
10 * client input.
11 * @version 1.22 2018-03-17
12 * @author Cay Horstmann
13 */
14 public class EchoServer
15 {
16 public static void main(String[] args) throws IOException
17 {
18 // establish server socket
19 try (var s = new ServerSocket(8189))
20 {
21 // wait for client connection
22 try (Socket incoming = s.accept())
23 {
24 InputStream inStream = incoming.getInputStream();
25 OutputStream outStream = incoming.getOutputStream();
26
27 try (var in = new Scanner(inStream,
28 StandardCharsets.UTF_8))
29 {
30 var out = new PrintWriter(
31 new OutputStreamWriter(outStream,
32 StandardCharsets.UTF_8),
33 true /* autoFlush */);
34
35 out.println("Hello! Enter BYE to exit.");
36
37 boolean done = false;
38 while (!done && in.hasNextLine())
39 {
40 String line = in.nextLine();
41 out.println("Echo: " + line);
42 if (line.strip().equals("BYE")) done = true;
43 }
44 }
45 }
46 }
47 }
```

---

To try it out, compile and run the program. Then use telnet to connect to the server `localhost` (or IP address `127.0.0.1`) and port `8189`.

If you are connected directly to the Internet, anyone in the world can access your echo server, provided they know your IP address and the magic port number.

When you connect to the port, you will see the message shown in [Figure 4.4](#):

[Click here to view code image](#)



The screenshot shows a terminal window titled "Terminal". The menu bar includes "File", "Edit", "View", "Terminal", "Tabs", and "Help". The command `telnet localhost 8189` is entered, followed by the server's response: "Trying 127.0.0.1... Connected to localhost. Escape character is '^]'. Hello! Enter BYE to exit. Hello Sailor! Echo: Hello Sailor! BYE Echo: BYE Connection closed by foreign host." The prompt `~$` is visible at the bottom.

**Figure 4.4** Accessing an echo server

Hello! Enter BYE to exit.

Type anything and watch the input echo on your screen. Type `BYE` (all uppercase letters) to disconnect. The server program will terminate as well.

#### **java.net.ServerSocket 1.0**

- `ServerSocket(int port)`

creates a server socket that monitors a port.

- `Socket accept()`

waits for a connection. This method blocks (i.e., idles) the current thread until the connection is made. The method returns a `Socket` object through which the program can communicate with the connecting client.

- `void close()`

closes the server socket.

### 4.2.2 Serving Multiple Clients

There is one problem with the simple server in the preceding example. Suppose we want to allow multiple clients to connect to our server at the same time. Typically, a server runs constantly on a server computer, and clients from all over the Internet might want to use it at the same time. Without support for multiple connections, any one client can monopolize the service by connecting to it for a long time. We can do much better through the magic of threads.

Every time we know the program has established a new socket connection—that is, every time the call to `accept()` returns a socket—we will launch a new thread to take care of the connection between the server and *that* client. The main program will just go back and wait for the next connection. For this to happen, the main loop of the server should look like this:

[Click here to view code image](#)

```
while (true)
{
 Socket incoming = s.accept();
 var r = new ThreadedEchoHandler(incoming);
 var t = new Thread(r);
 t.start();
}
```

The `ThreadedEchoHandler` class implements `Runnable` and contains the communication loop with the client in its `run` method.

[Click here to view code image](#)

```


class ThreadedEchoHandler implements Runnable
{
 . . .
 public void run()
 {
 try (InputStream inStream = incoming.getInputStream();
 OutputStream outStream = incoming.getOutputStream())
 {
 Process input and send response
 }
 catch(IOException e)
 {
 Handle exception
 }
 }
}

```

When each connection starts a new thread, multiple clients can connect to the server at the same time. You can easily check this out.

1. Compile and run the server program ([Listing 4.4](#)).
2. Open several telnet windows as we have in [Figure 4.5](#).

[Click here to view code image](#)



**Figure 4.5** Several telnet windows communicating simultaneously

3. Switch between windows and type commands. Note that you can communicate through all of them simultaneously.
4. When done, switch to the window from which you launched the server program and press Ctrl+C to kill it.



### Note

In this program, we spawn a separate thread for each connection. This approach is not satisfactory for high-performance servers. You can achieve greater server throughput by using features of the `java.nio` package. See

[www.ibm.com/developerworks/java/library/j-javaio](http://www.ibm.com/developerworks/java/library/j-javaio)  
for more information.

---

#### **Listing 4.4** threaded/ThreadedEchoServer.java

[Click here to view code image](#)

```
1 package threaded;
2
3 import java.io.*;
4 import java.net.*;
5 import java.nio.charset.*;
6 import java.util.*;
7
8 /**
9 * This program implements a multithreaded server that listens to
10 port 8189 and echoes back
11 * all client input.11 * @author Cay Horstmann
12 * @version 1.23 2018-03-17
13 */
14 public class ThreadedEchoServer
15 {
16 public static void main(String[] args)
17 {
18 try (var s = new ServerSocket(8189))
19 {
20 int i = 1;
21
22 while (true)
23 {
24 Socket incoming = s.accept();
25 System.out.println("Spawning " + i);
26 Runnable r = new ThreadedEchoHandler(incoming);
27 var t = new Thread(r);
28 t.start();
29 i++;
30 }
31 }
32 catch (IOException e)
33 {
```

```
34 e.printStackTrace();
35 }
36 }
37 }
38
39 /**
40 * This class handles the client input for one server socket
41 * connection.
42 */
43 class ThreadedEchoHandler implements Runnable
44 {
45 private Socket incoming;
46
47 /**
48 Constructs a handler.
49 @param incomingSocket the incoming socket
50 */
51 public ThreadedEchoHandler(Socket incomingSocket)
52 {
53 incoming = incomingSocket;
54 }
55
56 public void run()
57 {
58 try (InputStream inStream = incoming.getInputStream();
59 OutputStream outStream = incoming.getOutputStream();
60 var in = new Scanner(inStream, StandardCharsets.UTF_8);
61 var out = new PrintWriter(
62 new OutputStreamWriter(outStream,
63 StandardCharsets.UTF_8),
64 true /* autoFlush */))
65 {
66 out.println("Hello! Enter BYE to exit.");
67 boolean done = false;
68 while (!done && in.hasNextLine())
69 {
70 String line = in.nextLine();
71 out.println("Echo: " + line);
72 if (line.strip().equals("BYE"))
73 done = true;
74 }
75 }
76 }
77 }
```

```
73 done = true;
74 }
75 }
76 catch (IOException e)
77 {
78 e.printStackTrace();
79 }
80 }
81 }
```

---

### 4.2.3 Half-Close

The *half-close* allows one end of a socket connection to terminate its output while still receiving data from the other end.

Here is a typical situation. Suppose you transmit data to the server but you don't know at the outset how much data you have. With a file, you'd just close the file at the end of the data. However, if you close a socket, you immediately disconnect from the server and cannot read the response.

The half-close solves this problem. You can close the output stream of a socket, thereby indicating to the server the end of the requested data, but keep the input stream open.

The client side looks like this:

[Click here to view code image](#)

```
try (var socket = new Socket(host, port))
{
 var in = new Scanner(socket.getInputStream(),
StandardCharsets.UTF_8);
 var writer = new PrintWriter(socket.getOutputStream());
 // send request data
 writer.print(. . .);
 writer.flush();
 socket.shutdownOutput();
 // now socket is half-closed
 // read response data
 while (in.hasNextLine() != null)
 {
 String line = in.nextLine();
```

```
 . . .
}
```

The server side simply reads input until the end of the input stream is reached. Then it sends the response.

Of course, this protocol is only useful for one-shot services such as HTTP where the client connects, issues a request, catches the response, and then disconnects.

#### **java.net.Socket 1.0**

- `void shutdownOutput () 1.3`  
sets the output stream to “end of stream.”
- `void shutdownInput () 1.3`  
sets the input stream to “end of stream.”
- `boolean isOutputShutdown () 1.4`  
returns `true` if output has been shut down.
- `boolean isInputShutdown () 1.4`  
returns `true` if input has been shut down.

#### **4.2.4 Interruptible Sockets**

When you connect to a socket, the current thread blocks until the connection has been established or a timeout has elapsed. Similarly, when you read data through a socket, the current thread blocks until the operation is successful or has timed out. (There is no timeout for writing data.)

In interactive applications, you would like to give users an option to simply cancel a socket connection that does not appear to produce results. However, if a thread blocks on an unresponsive socket, you cannot unblock it by calling `interrupt`.

To interrupt a socket operation, use a `SocketChannel`, a feature of the `java.nio` package. Open the `SocketChannel` like this:

[Click here to view code image](#)

```
SocketChannel channel = SocketChannel.open(new
InetSocketAddress(host, port));
```

A channel does not have associated streams. Instead, it has `read` and `write` methods that make use of `Buffer` objects. (See [Chapter 1](#) for more information about NIO buffers.) These methods are declared in the interfaces `ReadableByteChannel` and `WritableByteChannel`.

If you don't want to deal with buffers, you can use the `Scanner` class to read from a `SocketChannel` because `Scanner` has a constructor with a `ReadableByteChannel` parameter:

[Click here to view code image](#)

```
var in = new Scanner(channel, StandardCharsets.UTF_8);
```

To turn a channel into an output stream, use the static `Channels.newOutputStream` method.

[Click here to view code image](#)


```
OutputStream outStream = Channels.newOutputStream(channel);
```

That's all you need to do. Whenever a thread is interrupted during an open, read, or write operation, the operation does not block, but is terminated with an exception.

The program in [Listing 4.5](#) contrasts interruptible and blocking sockets. A server sends numbers and pretends to be stuck after the tenth number. Click on either button, and a thread is started that connects to the server and prints the output. The first thread uses an interruptible socket; the second thread uses a blocking socket. If you click the Cancel button within the first ten numbers, you can interrupt either thread.

However, after the first ten numbers, you can only interrupt the first thread. The second thread keeps blocking until the server finally closes the connection (see [Figure 4.6](#)).

[Click here to view code image](#)



**Figure 4.6** Interrupting a socket

---

**Listing 4.5** interruptible/InterruptibleSocketTest.java

---

[Click here to view code image](#)

```
1 package interruptible;
2
3 import java.awt.*;
4 import java.awt.event.*;
5 import java.util.*;
6 import java.net.*;
7 import java.io.*;
8 import java.nio.charset.*;
9 import java.nio.channels.*;
10 import javax.swing.*;
11
12 /**
13 * This program shows how to interrupt a socket channel.
14 * @author Cay Horstmann
15 * @version 1.05 2018-03-17
16 */
17 public class InterruptibleSocketTest
18 {
```

```
19 public static void main(String[] args)
20 {
21 EventQueue.invokeLater(() ->
22 {
23 var frame = new InterruptibleSocketFrame();
24 frame.setTitle("InterruptibleSocketTest");
25 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
26 frame.setVisible(true);
27 });
28 }
29 }
30
31 class InterruptibleSocketFrame extends JFrame
32 {
33 private Scanner in;
34 private JButton interruptibleButton;
35 private JButton blockingButton;
36 private JButton cancelButton;
37 private JTextArea messages;
38 private TestServer server;
39 private Thread connectThread;
40
41 public InterruptibleSocketFrame()
42 {
43 var northPanel = new JPanel();
44 add(northPanel, BorderLayout.NORTH);
45
46 final int TEXT_ROWS = 20;
47 final int TEXT_COLUMNS = 60;
48 messages = new JTextArea(TEXT_ROWS, TEXT_COLUMNS);
49 add(new JScrollPane(messages));50
50 interruptibleButton = new JButton("Interruptible");
51 blockingButton = new JButton("Blocking");
52
53
54 northPanel.add(interruptibleButton);
55 northPanel.add(blockingButton);
56
57 interruptibleButton.addActionListener(event ->
58 {
59 interruptibleButton.setEnabled(false);
60 blockingButton.setEnabled(false);
61 });
62 }
63 }
```

```
61 cancelButton.setEnabled(true);
62 connectThread = new Thread(() ->
63 {
64 try
65 {
66 connectInterruptibly();
67 }
68 catch (IOException e)
69 {
70
71 messages.append("\nInterruptibleSocketTest.connectInterruptibly: " +
e);
72 }
73 connectThread.start();
74 });
75
76 blockingButton.addActionListener(event ->
77 {
78 interruptibleButton.setEnabled(false);
79 blockingButton.setEnabled(false);
80 cancelButton.setEnabled(true);
81 connectThread = new Thread(() ->
82 {
83 try
84 {
85 connectBlocking();
86 }
87 catch (IOException e)
88 {
89
90 messages.append("\nInterruptibleSocketTest.connectBlocking: " + e);
91 }
92 connectThread.start();
93 });
94
95 cancelButton = new JButton("Cancel");
96 cancelButton.setEnabled(false);
97 northPanel.add(cancelButton);
98 cancelButton.addActionListener(event ->99 {
```

```
100 connectThread.interrupt();
101 cancelButton.setEnabled(false);
102 });
103 server = new TestServer();
104 new Thread(server).start();
105 pack();
106 }
107
108 /**
109 * Connects to the test server, using interruptible I/O
110 */
111 public void connectInterruptibly() throws IOException
112 {
113 messages.append("Interruptible:\n");
114 try (SocketChannel channel
115 = SocketChannel.open(new
InetSocketAddress("localhost", 8189)))
116 {
117 in = new Scanner(channel, StandardCharsets.UTF_8);
118 while (!Thread.currentThread().isInterrupted())
119 {
120 messages.append("Reading ");
121 if (in.hasNextLine())
122 {
123 String line = in.nextLine();
124 messages.append(line);
125 messages.append("\n");
126 }
127 }
128 }
129 finally
130 {
131 EventQueue.invokeLater(() ->
132 {
133 messages.append("Channel closed\n");
134 interruptibleButton.setEnabled(true);
135 blockingButton.setEnabled(true);
136 });
137 }
138 }
139
```

```
140 /**
141 * Connects to the test server, using blocking I/O
142 */
143 public void connectBlocking() throws IOException
144 {
145 messages.append("Blocking:\n");146 try (var sock = new
146 Socket("localhost", 8189))
147 {
148 in = new Scanner(sock.getInputStream(),
149 StandardCharsets.UTF_8);
150 while (!Thread.currentThread().isInterrupted())
151 {
152 messages.append("Reading ");
153 if (in.hasNextLine())
154 {
155 String line = in.nextLine();
156 messages.append(line);
157 messages.append("\n");
158 }
159 }
160 finally
161 {
162 EventQueue.invokeLater(() ->
163 {
164 messages.append("Socket closed\n");
165 interruptibleButton.setEnabled(true);
166 blockingButton.setEnabled(true);
167 });
168 }
169 }
170 }
171 /**
172 * A multithreaded server that listens to port 8189 and sends
173 * numbers to the client,
174 * simulating a hanging server after 10 numbers.
175 */
176 class TestServer implements Runnable
177 {
178 public void run()
179 {
```

```
179 try (var s = new ServerSocket(8189))
180 {
181 while (true)
182 {
183 Socket incoming = s.accept();
184 Runnable r = new TestServerHandler(incoming);
185 new Thread(r).start();
186 }
187 }
188 catch (IOException e)
189 {
190 messages.append("\nTestServer.run: " + e);
191 }
192 }
193 }
194195 /**
196 * This class handles the client input for one server socket
connection.
197 */
198 class TestServerHandler implements Runnable
199 {
200 private Socket incoming;
201 private int counter;
202
203 /**
204 * Constructs a handler.
205 * @param i the incoming socket
206 */
207 public TestServerHandler(Socket i)
208 {
209 incoming = i;
210 }
211
212 public void run()
213 {
214 try
215 {
216 try
217 {
218 OutputStream outStream = incoming.getOutputStream();
219 var out = new PrintWriter(
```

```
220 new OutputStreamWriter(outStream,
221 StandardCharsets.UTF_8),
222 true /* autoFlush */);
223 while (counter < 100)
224 {
225 counter++;
226 if (counter <= 10) out.println(counter);
227 Thread.sleep(100);
228 }
229 finally
230 {
231 incoming.close();
232 messages.append("Closing server\n");
233 }
234 }
235 catch (Exception e)
236 {
237 messages.append("\nTestServerHandler.run: " + e);
238 }
239 }
240 }
241 }
```

#### **java.net.InetSocketAddress 1.4**

- `InetSocketAddress(String hostname, int port)`  
constructs an address object with the given host and port, resolving the host name during construction. If the host name cannot be resolved, the address object's `unresolved` property is set to `true`.
- `boolean isUnresolved()`  
returns `true` if this address object could not be resolved.

#### **java.nio.channels.SocketChannel 1.4**

- static SocketChannel open(SocketAddress address)  
opens a socket channel and connects it to a remote address.

### **java.nio.channels.Channels 1.4**

- static **InputStream**  
newInputStream(ReadableByteChannel channel)  
constructs an input stream that reads from the given channel.
- static **OutputStream**  
newOutputStream(WritableByteChannel channel)  
constructs an output stream that writes to the given channel.

## **4.3 Getting Web Data**

To access web servers in a Java program, you will want to work at a higher level than socket connections and HTTP requests. In the following sections, we discuss the classes that the Java library provides for this purpose.

### **4.3.1 URLs and URIs**

The URL and URLConnection classes encapsulate much of the complexity of retrieving information from a remote site. You can construct a URL object from a string:

```
var url = new URL(urlString);
```

If you simply want to fetch the contents of the resource, use the `openStream` method of the URL class. This method yields an `InputStream` object. Use it in the usual way—for example, to construct a `Scanner`:

[Click here to view code image](#)

```
InputStream inStream = url.openStream();
var in = new Scanner(inStream, StandardCharsets.UTF_8);
```

The `java.net` package makes a useful distinction between URLs (uniform resource *locators*) and URIs (uniform resource *identifiers*).

A URI is a purely syntactical construct that contains the various parts of the string specifying a web resource. A URL is a special kind of URI, namely one with sufficient information to *locate* a resource. Other URIs, such as

`mailto:cay@horstmann.com`

are not locators—there is no data to locate from this identifier. Such a URI is called a URN (uniform resource *name*).

In the Java library, the `URI` class has no methods for accessing the resource that the identifier specifies—its sole purpose is parsing. In contrast, the `URL` class can open a stream to the resource. For that reason, the `URL` class only works with schemes that the Java library knows how to handle, such as `http:`, `https:`, `ftp:`, the local file system (`file:`), and JAR files (`jar:`).

To see why parsing is not trivial, consider how complex URIs can be. For example,

[Click here to view code image](#)

```
http://google.com?q=Beach+Chalet
ftp://username:password@ftp.yourserver.com/pub/file.txt
```

The URI specification gives the rules for the makeup of these identifiers. A URI has the syntax

`[scheme:] schemeSpecificPart[#fragment]`

Here, the `[ . . . ]` denotes an optional part, and the `:` and `#` are included literally in the identifier.

If the `scheme:` part is present, the URI is called *absolute*. Otherwise, it is called *relative*.

An absolute URI is *opaque* if the *schemeSpecificPart* does not begin with a / such as

```
mailto:cay@horstmann.com
```

All absolute nonopaque URIs and all relative URIs are *hierarchical*. Examples are

[Click here to view code image](#)

```
http://horstmann.com/index.html
.../..../java/net/Socket.html#Socket()
```

The *schemeSpecificPart* of a hierarchical URI has the structure

```
[//authority] [path] [?query]
```

where, again, [ . . . ] denotes optional parts.

For server-based URIs, the *authority* part has the form

```
[user-info@]host[:port]
```

The *port* must be an integer.

RFC 2396, which standardizes URIs, also supports a registry-based mechanism in which the *authority* has a different format, but this is not in common use.

One of the purposes of the `URI` class is to parse an identifier and break it up into its components. You can retrieve them with the methods

```
getScheme
getSchemeSpecificPart
getAuthority
getUserInfo
getHost
getPort
getPath
getQuery
getFragment
```

The other purpose of the `URI` class is the handling of absolute and relative identifiers. If you have an absolute URI such as

[Click here to view code image](#)

`http://docs.mycompany.com/api/java/net/ServerSocket.html`

and a relative URI such as

[Click here to view code image](#)

`.../java/net/Socket.html#Socket()`

then you can combine the two into an absolute URI.

[Click here to view code image](#)

`http://docs.mycompany.com/api/java/net/Socket.html#Socket()`

This process is called *resolving* a relative URL.

The opposite process is called *relativization*. For example, suppose you have a *base* URI

[Click here to view code image](#)

`http://docs.mycompany.com/api`

and a URI

[Click here to view code image](#)

`http://docs.mycompany.com/api/java/lang/String.html`

Then the relativized URI is

`java/lang/String.html`

The `URI` class supports both of these operations:

[Click here to view code image](#)

```
relative = base.relativize(combined);
combined = base.resolve(relative);
```

### 4.3.2 Using a URLConnection to Retrieve Information

If you want additional information about a web resource, you should use the `URLConnection` class, which gives you much more control than the basic `URL` class.

When working with a `URLConnection` object, you must carefully schedule your steps.

1. Call the `openConnection` method of the `URL` class to obtain the `URLConnection` object:

[Click here to view code image](#)

```
URLConnection connection = url.openConnection();
```

2. Set any request properties, using the methods

```
setDoInput
setDoOutput
setIfModifiedSince
setUseCaches
setAllowUserInteraction
setRequestProperty
setConnectTimeout
setReadTimeout
```

We discuss these methods later in this section and in the API notes.

3. Connect to the remote resource by calling the `connect` method:

```
connection.connect();
```

Besides making a socket connection to the server, this method also queries the server for *header information*.

4. After connecting to the server, you can query the header information. Two methods, `getHeaderFieldKey` and `getHeaderField`, enumerate all fields of the header. The method `getHeaderFields` gets a standard `Map` object containing the header fields. For your convenience, the following methods query standard fields:

```
getContentType
getContentLength
```

```
getContentEncoding
getDate
getExpiration
getLastModified
```

- Finally, you can access the resource data. Use the `getInputStream` method to obtain an input stream for reading the information. (This is the same input stream that the `openStream` method of the `URL` class returns.) The other method, `getContent`, isn't very useful in practice. The objects that are returned by standard content types such as `text/plain` and `image/gif` require classes in the `com.sun` hierarchy for processing. You could register your own content handlers, but we do not discuss this technique in our book.
- 



## Caution

Some programmers form a wrong mental image when using the `URLConnection` class, thinking that the `getInputStream` and `getOutputStream` methods are similar to those of the `Socket` class. But that isn't quite true. The `URLConnection` class does quite a bit of magic behind the scenes—in particular, the handling of request and response headers. For that reason, it is important that you follow the setup steps for the connection.

---

Let us now look at some of the `URLConnection` methods in detail. Several methods set properties of the connection before connecting to the server. The most important ones are `setDoInput` and `setDoOutput`. By default, the connection yields an input stream for reading from the server but no output stream for writing. If you want an output stream (for example, for posting data to a web server), you need to call

```
connection.setDoOutput(true);
```

Next, you may want to set some of the request headers. The request headers are sent together with the request command to the server. Here is an example:

[Click here to view code image](#)

```
GET www.server.com/index.html HTTP/1.0
Referer: http://www.somewhere.com/links.html
Proxy-Connection: Keep-Alive
User-Agent: Mozilla/5.0 (X11; U; Linux i686; en-US; rv:1.8.1.4)
Host: www.server.com
Accept: text/html, image/gif, image/jpeg, image/png, */
Accept-Language: en
Accept-Charset: iso-8859-1,* ,utf-8
Cookie: orangemilano=192218887821987
```

The `setIfModifiedSince` method tells the connection that you are only interested in data modified since a certain date.

Finally, you can use the catch-all `setRequestProperty` method to set any name/value pair that is meaningful for the particular protocol. For the format of the HTTP request headers, see RFC 2616. Some of these parameters are not well documented and are passed around by word of mouth from one programmer to the next. For example, if you want to access a password-protected web page, you must do the following:

1. Concatenate the user name, a colon, and the password.

[Click here to view code image](#)

```
String input = username + ":" + password;
```

2. Compute the Base64 encoding of the resulting string. (The Base64 encoding encodes a sequence of bytes into a sequence of printable ASCII characters.)

[Click here to view code image](#)

```
Base64.Encoder encoder = Base64.getEncoder();
String encoding = encoder.encodeToString(input.getBytes(StandardCharsets.UTF_8));
```

3. Call the `setRequestProperty` method with a name of "Authorization" and the value "Basic " + encoding.

[Click here to view code image](#)

```
connection.setRequestProperty("Authorization", "Basic " +
encoding);
```



## Tip

You just saw how to access a password-protected web page. To access a password-protected file by FTP, use an entirely different method:  
Construct a URL of the form

[Click here to view code image](#)

```
ftp://username:password@ftp.yourserver.com/pub/file.txt
```

---

Once you call the `connect` method, you can query the response header information. First, let's see how to enumerate all response header fields. The implementors of this class felt a need to express their individuality by introducing yet another iteration protocol. The call

[Click here to view code image](#)

```
String key = connection.getHeaderFieldKey(n);
```

gets the nth key from the response header, where n starts from 1! It returns null if n is zero or greater than the total number of header fields. There is no method to return the number of fields; you simply keep calling `getHeaderFieldKey` until you get null. Similarly, the call

[Click here to view code image](#)

```
String value = connection.getHeaderField(n);
```

returns the nth value.

The method `getHeaderFields` returns a Map of response header fields.

[Click here to view code image](#)

```
Map<String, List<String>> headerFields = connection.getHeaderFields();
```

Here is a set of response header fields from a typical HTTP request:

[Click here to view code image](#)

```
Date: Wed, 27 Aug 2008 00:15:48 GMT
```

```
Server: Apache/2.2.2 (Unix)
```

```
Last-Modified: Sun, 22 Jun 2008 20:53:38 GMT
Accept-Ranges: bytes
Content-Length: 4813
Connection: close
Content-Type: text/html
```

---



## Note

You can obtain the response status line (such as "HTTP/1.1 200 OK") as `connection.getHeaderField(0)` or `headerFields.get(null)`.

---

As a convenience, six methods query the values of the most common header types and convert them to numeric types when appropriate. [Table 4.1](#) shows these convenience methods. The methods with return type `long` return the number of seconds since January 1, 1970 GMT.

**Table 4.1** Convenience Methods for Response Header Values

Key Name	Method Name	Return Type
Date	getDate	long
Expires	getExpiration	long
Last-Modified	getLastModified	long
Content-Length	getContentLength	int
Content-Type	getContentType	String
Content-Encoding	getContentEncoding	String

The program in [Listing 4.6](#) lets you experiment with URL connections. Supply a URL and an optional user name and password on the command line when running the program, for example:

[Click here to view code image](#)

```
java urlConnection.URLConnectionTest http://www.yourserver.com user
password
```

The program prints

- All keys and values of the header
- The return values of the six convenience methods in [Table 4.1](#)
- The first ten lines of the requested resource

---

**Listing 4.6** urlConnection/URLConnectionTest.java

---

[Click here to view code image](#)

```
1 package urlConnection;
2
3 import java.io.*;
4 import java.net.*;
5 import java.nio.charset.*;
6 import java.util.*;
7
8 /**
9 * This program connects to an URL and displays the response
10 header data and the first
11 * 10 lines of the requested data.
12 *
13 * Supply the URL and an optional username and password (for HTTP
14 basic authentication) on
15 * the command line.
16 *
17 public class URLConnectionTest
18 {
19 public static void main(String[] args)
20 {
21 try
22 {
23 String urlName;
24 if (args.length > 0) urlName = args[0];
25 else urlName = "http://horstmann.com";
26
27 var url = new URL(urlName);
28 URLConnection connection = url.openConnection();
29
30 // set username, password if specified on command line
31
32 if (args.length > 2)
```

```
33 {
34 String username = args[1];
35 String password = args[2];
36 String input = username + ":" + password;
37 Base64.Encoder encoder = Base64.getEncoder();
38 String encoding =
encoder.encodeToString(input.getBytes(StandardCharsets.UTF_8));
39 connection.setRequestProperty("Authorization", "Basic
" + encoding);
40 }
41
42 connection.connect();
43
44 // print header fields
45
46 Map<String, List<String>> headers =
connection.getHeaderFields();
47 for (Map.Entry<String, List<String>> entry :
headers.entrySet())
48 {
49 String key = entry.getKey();
50 for (String value : entry.getValue())
51 System.out.println(key + ": " + value);
52 }
53
54 // print convenience functions
55
56 System.out.println("-----");57
System.out.println("getContentType: " + connection.getContentType());
58 System.out.println("getContentLength: " +
connection.getContentLength());
59 System.out.println("getContentEncoding: " +
connection.getContentEncoding());
60 System.out.println("getDate: " + connection.getDate());
61 System.out.println("getExpiration: " +
connection.getExpiration());
62 System.out.println("getLastModified: " +
connection.getLastModified());
63 System.out.println("-----");
64
65 String encoding = connection.getContentEncoding();
```

```
66 if (encoding == null) encoding = "UTF-8";
67 try (var in = new Scanner(connection.getInputStream(),
68 encoding))
68 {
69 // print first ten lines of contents
70
71 for (int n = 1; in.hasNextLine() && n <= 10; n++)
72 System.out.println(in.nextLine());
73 if (in.hasNextLine()) System.out.println("... .");
74 }
75 }
76 catch (IOException e)
77 {
78 e.printStackTrace();
79 }
80 }
81 }
```

---

### **java.net.URL 1.0**

- `InputStream openStream()`  
opens an input stream for reading the resource data.
- `URLConnection openConnection()`  
returns a `URLConnection` object that manages the connection to the resource.

### **java.netURLConnection 1.0**

- `void setDoInput(boolean doInput)`
- `boolean getDoInput()`  
If `doInput` is `true`, the user can receive input from this `URLConnection`.

- `void setDoOutput(boolean doOutput)`
- `boolean getDoOutput()`

If `doOutput` is `true`, the user can send output to this `URLConnection`.

- `void setIfModifiedSince(long time)`
- `long getIfModifiedSince()`

The `ifModifiedSince` property configures this `URLConnection` to fetch only data modified since a given time. The time is given in seconds since midnight, GMT, January 1, 1970.

- `void setConnectTimeout(int timeout) 5.0`
- `int getConnectTimeout() 5.0`

set or get the timeout for the connection (in milliseconds). If the timeout has elapsed before a connection was established, the `connect` method of the associated input stream throws a `SocketTimeoutException`.

- `void setReadTimeout(int timeout) 5.0`
- `int getReadTimeout() 5.0`

set or get the timeout for reading data (in milliseconds). If the timeout has elapsed before a read operation was successful, the `read` method throws a `SocketTimeoutException`.

- `void setRequestProperty(String key, String value)`  
sets a request header field.
- `Map<String, List<String>> getRequestProperties() 1.4`  
returns a map of request properties. All values for the same key are placed in a list.
- `void connect()`  
connects to the remote resource and retrieves the response header information.
- `Map<String, List<String>> getHeaderFields() 1.4`

returns a map of response headers. All values for the same key are placed in a list.

- `String getHeaderFieldKey(int n)`

gets the key for the nth response header field, or null if n is  $\leq 0$  or greater than the number of response header fields.

- `String getHeaderField(int n)`

gets value of the nth response header field, or null if n is  $\leq 0$  or greater than the number of response header fields.

- `int getContentLength()`

gets the content length if available, or -1 if unknown.

- `String getContentType()`

gets the content type, such as `text/plain` or `image/gif`.

- `String getContentEncoding()`

gets the content encoding, such as `gzip`. This value is not commonly used, because the default identity encoding is not supposed to be specified with a `Content-Encoding` header.

- `long getDate()`

- `long getExpiration()`

- `long getLastModified()`

get the date of creation, expiration, and last modification of the resource. The dates are specified as seconds since midnight, GMT, January 1, 1970.

- `InputStream getInputStream()`

- `OutputStream getOutputStream()`

return a stream for reading from the resource or writing to the resource.

- `Object getContent()`

selects the appropriate content handler to read the resource data and convert it into an object. This method is not useful for reading standard

types such as `text/plain` or `image/gif` unless you install your own content handler.

### 4.3.3 Posting Form Data

In the preceding section, you saw how to read data from a web server. Now we will show you how your programs can send data back to a web server and to programs that the web server invokes.

To send information from a web browser to the web server, a user fills out a *form*, like the one in Figure 4.7.

[Click here to view code image](#)

The screenshot shows a Mozilla Firefox browser window displaying the 'ZIP Code™ Lookup' page on the USPS website. The URL in the address bar is `https://tools.usps.com/zip-code-lookup.htm?byaddress`. The page title is 'ZIP Code™ Lookup | USPS - Mozilla Firefox'. The main content area is titled 'Look Up a ZIP Code™' and features a 'ZIP Code™ by Address' form. The form includes fields for 'Company' (empty), 'Street Address' (containing '1 Main Street'), 'Apt/Suite/Other' (empty), 'City' (containing 'San Francisco'), 'State' (containing 'CA - California'), and 'ZIP Code™' (containing 'Enter ZIP Code™'). A large blue 'Find' button is at the bottom of the form. The page footer contains the 'USPS.COM' logo and links for 'HELPFUL LINKS', 'ON ABOUT.USPS.COM', 'OTHER USPS SITES', and 'LEGAL INFORMATION'.


**Figure 4.7** An HTML form

When the user clicks the Submit button, the text in the text fields and the settings of any checkboxes, radio buttons, and other input elements are sent back to the web server. The web server invokes a program that processes the user input.

Many technologies enable web servers to invoke programs. Among the best known ones are Java servlets, JavaServer Faces, Microsoft Active Server Pages (ASP), and Common Gateway Interface (CGI) scripts.

The server-side program processes the form data and produces another HTML page that the web server sends back to the browser. This sequence is illustrated in [Figure 4.8](#). The response page can contain new information (for example, in an information-search program) or just an acknowledgment. The web browser then displays the response page.

[Click here to view code image](#)



**Figure 4.8** Data flow during execution of a server-side program

We do not discuss the implementation of server-side programs in this book. Our interest is merely in writing client programs that interact with existing server-side

programs.

When form data are sent to a web server, it does not matter whether the data are interpreted by a servlet, a CGI script, or some other server-side technology. The client sends the data to the web server in a standard format, and the web server takes care of passing it on to the program that generates the response.

Two commands, called GET and POST, are commonly used to send information to a web server.

In the GET command, you simply attach query parameters to the end of the URL. The URL has the form

`http://host/path?query`

Each parameter has the form *name=value*. Parameters are separated by & characters. Parameter values are encoded using the *URL encoding* scheme, following these rules:

- Leave the characters A through Z, a through z, 0 through 9, and . - ~ \_ unchanged.
- Replace all spaces with + characters.
- Encode all other characters into UTF-8 and encode each byte by a %, followed by a two-digit hexadecimal number.

For example, to transmit San Francisco, CA, you use San+Francisco%2c+CA, as the hexadecimal number 2c is the UTF-8 code of the ',', character.

This encoding keeps any intermediate programs from messing with spaces and other special characters.

At the time of this writing, the Google Maps site ([www.google.com/maps](http://www.google.com/maps)) accepts query parameters with names q and hl whose values are the location query and the human language of the response. To get a map of 1 Market Street in San Francisco, with a response in German, use the following URL:

[Click here to view code image](#)

`http://www.google.com/maps?q=1+Market+Street+San+Francisco&hl=de`

Very long query strings can look unattractive in browsers, and older browsers and proxies have a limit on the number of characters that you can include in a GET request. For that reason, a POST request is often used for forms with a lot of data. In a POST request, you do not attach parameters to a URL; instead, you get an output stream from the `URLConnection` and write name/value pairs to the output stream. You still have to URL-encode the values and separate them with & characters.

Let us look at this process in detail. To post data to a server-side program, first establish a `URLConnection`:

[Click here to view code image](#)

```
var url = new URL("http://host/path");
URLConnection connection = url.openConnection();
```

Then, call the `setDoOutput` method to set up the connection for output:

```
connection.setDoOutput(true);
```

Next, call `getOutputStream` to get a stream through which you can send data to the server. If you are sending text to the server, it is convenient to wrap that stream into a `PrintWriter`.

[Click here to view code image](#)

```
var out = new PrintWriter(connection.getOutputStream(),
StandardCharsets.UTF_8);
```

Now you are ready to send data to the server:

[Click here to view code image](#)

```
out.print(name1 + "=" + URLEncoder.encode(value1,
StandardCharsets.UTF_8) + "&");
out.print(name2 + "=" + URLEncoder.encode(value2,
StandardCharsets.UTF_8));
```

Close the output stream:


```
out.close();
```

Finally, call `getInputStream` and read the server response.

Let's run through a practical example. The web site at <https://tools.usps.com/zip-code-lookup.htm?byaddress> contains a form to find the zip code for a street address (see Figure 4.7 on p. 270). To use this form in a Java program, you need to know the URL and the parameters of the POST request.

You could get that information by looking at the HTML code of the form, but it is usually easier to "spy" on a request with a network monitor. Most browsers have a network monitor as part of their development toolkit. For example, Figure 4.9 shows a screen capture of the Firefox network monitor when submitting data to our example web site. You can find out the submission URL as well as the parameter names and values.

[Click here to view code image](#)



**Figure 4.9** Monitoring the submission of a form

When posting form data, the HTTP header includes the content type:

[Click here to view code image](#)

```
Content-Type: application/x-www-form-urlencoded
```

You can also post data in other formats. For example, when sending data in JavaScript Object Notation (JSON), set the content type to application/json.

The header for a POST must also include the content length, for example

```
Content-Length: 124
```

The program in Listing 4.7 sends POST form data to any server-side program. Place the data into a .properties file such as the following:

[Click here to view code image](#)

```
url=https://tools.usps.com/tools/app/ziplookup/zipByAddress
User-Agent=HTTPPie/0.9.2
address1=1 Market Street
address2=
city=San Francisco
state=CA
companyName=
. . .
```

The program removes the url and User-Agent entries and sends all others to the doPost method.

In the doPost method, we first open the connection and set the user agent. (The zip code service does not work with the default User-Agent request parameter which contains the string Java, perhaps because the postal service doesn't want to serve programmatic requests.)

Then we call setDoOutput(true), and open the output stream. We then enumerate all keys and values. For each of them, we send the key, = character, value, and & separator character:

[Click here to view code image](#)

```
out.print(key);
out.print('=');
out.print(URLEncoder.encode(value, StandardCharsets.UTF_8));
if (more pairs) out.print('&');
```

When switching from writing to reading any part of the response, the actual interaction with the server happens. The Content-Length header is set to the size of the output. The Content-Type header is set to application/x-www-form-urlencoded unless a different content type was specified. The headers and data are sent to the server. Then the response headers and server response are read and can be queried. In our example program, this switch happens in the call to `connection.getContentEncoding()`.

There is one twist with reading the response. If a server-side error occurs, the call to `connection.getInputStream()` throws a `FileNotFoundException`. However, the server still sends an error page back to the browser (such as the ubiquitous “Error 404—page not found”). To capture this error page, call the `getErrorStream` method:

[Click here to view code image](#)

```
InputStream err = connection.getErrorStream();
```

---



## Note

The `getErrorStream` method, as well as several other methods in this program, belong to the `HttpURLConnection` subclass of `URLConnection`. If you make a request to an URL that starts with `http://` or `https://`, you can cast the resulting connection object to `HttpURLConnection`.

---

When you send POST data to a server, it can happen that the server-side program responds with a *redirect*: a different URL that should be called to get the actual information. The server could do that because the information is available elsewhere, or to provide a bookmarkable URL. The `HttpURLConnection` class can handle redirects in most cases.

---



## Note

If cookies need to be sent from one site to another in a redirect, you can configure the global cookie handler like this:

[Click here to view code image](#)

```
CookieHandler.setDefault(new CookieManager(null,
CookiePolicy.ACCEPT_ALL));
```

Then cookies will be properly included in the redirect.

---

Even though redirects are usually automatically handled, there are some situations where you need to do them yourself. Automatic redirects between HTTP and HTTPS are not supported for security reasons. Redirects can also fail for more subtle reasons. For example, an earlier version of the zip code service used a redirect. Recall that we set the User-Agent request parameter so that the post office didn't think we made a request via the Java API. While it is possible to set the user agent to a different string in the initial request, that setting is not used in automatic redirects. Instead, automatic redirects always send a generic user agent string that contains the word Java.

In such situations, you can manually carry out the redirects. Before connecting the server, turn off automatic redirects:

[Click here to view code image](#)

```
connection.setInstanceFollowRedirects(false);
```

After making the request, get the response code:

[Click here to view code image](#)

```
int responseCode = connection.getResponseCode();
```

Check if it is one of

[Click here to view code image](#)

```
HttpURLConnection.HTTP_MOVED_PERM
HttpURLConnection.HTTP_MOVED_TEMP
HttpURLConnection.HTTP_SEE_OTHER
```

In that case, get the Location response header to obtain the URL for the redirect. Then disconnect and make another connection to the new URL:

[Click here to view code image](#)

```
String location = connection.getHeaderField("Location");
if (location != null)
```

```

{
 URL base = connection.getURL();
 connection.disconnect();
 connection = (HttpURLConnection) new URL(base,
location).openConnection();
 . . .
}

```

The techniques that this program illustrates can be useful whenever you need to query information from an existing web site. Simply find out the parameters that you need to send, and then strip out the HTML tags and other unnecessary information from the reply.

---

### **Listing 4.7** post/PostTest.java

---

[Click here to view code image](#)

```

1 package post;
2
3 import java.io.*;
4 import java.net.*;
5 import java.nio.charset.*; 6 import java.nio.file.*;
7 import java.util.*;
8
9 /**
10 * This program demonstrates how to use the URLConnection class for
a POST request.
11 * @version 1.43 2021-06-17
12 * @author Cay Horstmann
13 */
14 public class PostTest
15 {
16 public static void main(String[] args) throws IOException
17 {
18 String propsFilename = args.length > 0 ? args[0] :
"post/post.properties";
19 var props = new Properties();
20 try (Reader in = Files.newBufferedReader(
21 Path.of(propsFilename), StandardCharsets.UTF_8))
22 {
23 props.load(in);

```

```
24 }
25 String urlString = props.remove("url").toString();
26 Object userAgent = props.remove("User-Agent");
27 Object redirects = props.remove("redirects");
28 CookieHandler.setDefault(new CookieManager(null,
CookiePolicy.ACCEPT_ALL));
29 String result = doPost(new URL(urlString), props,
30 userAgent == null ? null : userAgent.toString(),
31 redirects == null ? -1 :
Integer.parseInt(redirects.toString()));
32 System.out.println(result);
33 }
34
35 /**
36 * Do an HTTP POST.
37 * @param url the URL to post to
38 * @param nameValuePairs the query parameters
39 * @param userAgent the user agent to use, or null for the
default user agent
40 * @param redirects the number of redirects to follow manually,
or -1 for automatic
41 * @param
42 * @return the data returned from the server
43 */
44 public static String doPost(URL url, Map<Object, Object>
nameValuePairs, String userAgent,
45 int redirects) throws IOException
46 {
47 var connection = (HttpURLConnection) url.openConnection();
48 if (userAgent != null)
49 connection.setRequestProperty("User-Agent", userAgent);
50
51 if (redirects >= 0)52
connection.setInstanceFollowRedirects(false);
53
54 connection.setDoOutput(true);
55
56 try (var out = new
PrintWriter(connection.getOutputStream()))
57 {
58 boolean first = true;
```

```
59 for (Map.Entry<Object, Object> pair :
nameValuePairs.entrySet())
60 {
61 if (first) first = false;
62 else out.print('&');
63 String name = pair.getKey().toString();
64 String value = pair.getValue().toString();
65 out.print(name);
66 out.print('=');
67 out.print(URLEncoder.encode(value,
StandardCharsets.UTF_8));
68 }
69 }
70 String encoding = connection.getContentEncoding();
71 if (encoding == null) encoding = "UTF-8";
72
73 if (redirects > 0)
74 {
75 int responseCode = connection.getResponseCode();
76 if (responseCode == HttpURLConnection.HTTP_MOVED_PERM
77 || responseCode ==
HttpURLConnection.HTTP_MOVED_TEMP
78 || responseCode ==
HttpURLConnection.HTTP_SEE_OTHER)
79 {
80 String location = connection.getHeaderField("Location");
81 if (location != null)
82 {
83 URL base = connection.getURL();
84 connection.disconnect();
85 return doPost(new URL(base, location), nameValuePairs,
userAgent,
86 redirects - 1);
87 }
88 }
89 }
90 else if (redirects == 0)
91 {
92 throw new IOException("Too many redirects");
93 }
94 }
```

```
95 var response = new StringBuilder();
96 try (var in = new Scanner(connection.getInputStream(),
97 encoding)) {
98 while (in.hasNextLine())
99 {
100 response.append(in.nextLine());
101 response.append("\n");
102 }
103 }
104 catch (IOException e)
105 {
106 InputStream err = connection.getErrorStream();
107 if (err == null) throw e;
108 try (var in = new Scanner(err))
109 {
110 response.append(in.nextLine());
111 response.append("\n");
112 }
113 }
114
115 return response.toString();
116 }
117 }
```

---

### **java.net.HttpURLConnection 1.0**

- `InputStream getErrorStream()`

returns a stream from which you can read web server error messages.

### **java.net.URLEncoder 1.0**

- `static String encode(String s, String encoding)` 1.4

returns the URL-encoded form of the string `s`, using the given character encoding scheme. (The recommended scheme is "UTF-8".) In URL

encoding, the characters A–Z, a–z, 0–9, – \_ . ~ are left unchanged. Space is encoded into +, and all other characters are encoded into sequences of encoded bytes of the form %XY, where 0xXY is the hexadecimal value of the byte.

### **java.net.URLDecoder** 1.2

- static string decode(String s, String encoding) 1.4  
returns the decoding of the URL encoded string s under the given character encoding scheme.

## 4.4 The HTTP Client

The `URLConnection` class was designed before HTTP was the universal protocol of the Web. It provides support for a number of protocols, but its HTTP support is somewhat cumbersome. When the decision was made to support HTTP/2, it became clear that it would be best to provide a modern client interface instead of reworking the existing API. The `HttpClient` provides a more convenient API and HTTP/2 support. In Java 9 and 10, the API classes are located in the `jdk.incubator.http` package, to give the API a chance to evolve as a result of user feedback. As of Java 11, the `HttpClient` is in the `java.net.http` package.



### Note

With Java 9 and 10, you need to run your program with the command-line option

[Click here to view code image](#)

```
--add-modules jdk.incubator.httpclient
```

---

The HTTP client API provides a simpler mechanism for connecting to a web server than the `URLConnection` class with its rather fussy set of stages.

#### 4.4.1 The `HttpClient` Class

An `HttpClient` can issue requests and receive responses. You get a client by calling

[Click here to view code image](#)

```
HttpClient client = HttpClient.newHttpClient()
```

Alternatively, if you need to configure the client, you use a builder API, like this:

[Click here to view code image](#)

```
HttpClient client = HttpClient.newBuilder()
 .followRedirects(HttpClient.Redirect.ALWAYS)
 .build();
```

That is, you get a builder, call methods to customize the item that is going to be built, and then call the `build` method to finalize the building process. This is a common pattern for constructing immutable objects.

#### 4.4.2 The `HttpRequest` class and Body Publishers

You also follow the builder pattern for formulating requests. Here is a GET request:

[Click here to view code image](#)

```
HttpRequest request = HttpRequest.newBuilder()
 .uri(new URI("http://horstmann.com"))
 .GET()
 .build();
```

The URI is the “uniform resource identifier” which is, when using HTTP, the same as a URL. However, in Java, the `URL` class has methods for actually opening a connection to a URL, whereas the `URI` class is only concerned with the syntax (scheme, host, port, path, query, fragment, and so on).

With a POST request, you need a “body publisher” that turns the request data into the data that is being posted. There are body publishers for strings, byte arrays, and files. For example, if your request is in JSON, you just provide the JSON string to a string body publisher.

[Click here to view code image](#)

```
HttpRequest request = HttpRequest.newBuilder()
 .uri(new URI(url))
 .header("Content-Type", "application/json")
 .POST(HttpRequest.BodyPublishers.ofString(jsonString))
 .build();
```

It is unfortunate that the API does not support the required formatting for common content types. The sample program in [Listing 4.8](#) provides body publishers for form data and file uploads.

Java 16 adds a builder for filtering the headers of an existing HttpRequest. You provide the request and a function that receives the header names and values, returning true for those that should be retained. For example, here we modify the content type:

[Click here to view code image](#)

```
HttpRequest request2 = HttpRequest.newBuilder(request,
 (name, value) -> !name.equalsIgnoreCase("Content-Type")) // Remove old content type
 .header("Content-Type", "application/xml") // Add new content type
 .build();
```

#### 4.4.3 The `HttpResponse` Interface and Body Handlers

When sending the request, you have to tell the client how to handle the response. If you just want the body as a string, send the request with a `HttpResponse.BodyHandlers.ofString()`, like this:

[Click here to view code image](#)

```
HttpResponse<String> response = client.send(request,
 HttpResponse.BodyHandlers.ofString());
```

`HttpResponse` is a generic interface whose type parameter denotes the type of the response body. You get the response body string simply as

[Click here to view code image](#)

```
String bodyString = response.body();
```

There are other response body handlers that get the response as a byte array or input stream. `BodyHandlers.ofFile(filePath)` yields a handler that saves the response to the given file, and `BodyHandlers.ofFileDownload(directoryPath)` saves the response in the given directory, using the file name from the Content-Disposition header. Finally, the handler obtained from `BodyHandlers.discard()` simply discards the response.

Processing the contents of the response is not considered part of the API. For example, if you receive JSON data, you need a JSON library to parse the contents.

The `HttpResponse` object also yields the status code and the response headers.

[Click here to view code image](#)

```
int status = response.statusCode();
HttpHeaders responseHeaders = response.headers();
```

You can turn the `HttpHeaders` object into a map:

[Click here to view code image](#)

```
Map<String, List<String>> headerMap = responseHeaders.map();
```

The map values are lists since in HTTP, each key can have multiple values.

If you just want the value of a particular key, and you know that there won't be multiple values, call the `firstValue` method:

[Click here to view code image](#)

```
Optional<String> lastModified = headerMap.firstValue("Last-
Modified");
```

You get the response value or an empty optional if none was supplied.

#### 4.4.4 Asynchronous Processing

You can process the response asynchronously. When building the client, provide an executor:

[Click here to view code image](#)

```
ExecutorService executor = Executors.newCachedThreadPool();
HttpClient client =
HttpClient.newBuilder().executor(executor).build();
```

Build a request and then invoke the `sendAsync` method on the client. You receive a `CompletableFuture<HttpResponse<T>>`, where `T` is the type of the body handler. Use the `CompletableFuture` API as described in [Chapter 12](#) of Volume I:

[Click here to view code image](#)

```
HttpRequest request =
HttpRequest.newBuilder().uri(uri).GET().build();
client.sendAsync(request, HttpResponse.BodyHandlers.ofString())
thenAccept(response -> . . .);
```



#### Tip

To enable logging for the `HttpClient`, add this line to `net.properties` in your JDK:

[Click here to view code image](#)

```
jdk.httpclient.HttpClient.log=all
```

Instead of `all`, you can specify a comma-separated list of headers, requests, content, errors, ssl, trace, and frames, optionally followed by `:control`, `:data`, `:window`, or `:all`. Don't use any spaces.

Then, set the logging level for the logger with name `jdk.httpclient.HttpClient` to `INFO`, for example by adding this line to the `logging.properties` file in your JDK:

[Click here to view code image](#)

```
jdk.httpclient.HttpClient.level=INFO
```

---

---

### **Listing 4.8** client/HttpClientTest.java

---

[Click here to view code image](#)

```
1 package client;
2
3 import java.io.*;
4 import java.math.*;
5 import java.net.*;
6 import java.nio.charset.*;
7 import java.nio.file.*;
8 import java.util.*;
9
10 import java.net.http.*;
11 import java.net.http.HttpRequest.*;
12
13 class MoreBodyPublishers
14 {
15 public static BodyPublisher ofFormData(Map<Object, Object> data)
16 {
17 boolean first = true;
18 var builder = new StringBuilder();
19 for (Map.Entry<Object, Object> entry : data.entrySet())
20 {
21 if (first) first = false;
22 else builder.append("&");
23
24 builder.append(URLEncoder.encode(entry.getKey().toString(),
25 StandardCharsets.UTF_8));
26 builder.append("=");
27
28 builder.append(URLEncoder.encode(entry.getValue().toString(),
29 StandardCharsets.UTF_8));
30 }
31 return BodyPublishers.ofString(builder.toString());
32 }
33
34 private static byte[] bytes(String s) { return
```

```
s.getBytes(StandardCharsets.UTF_8); }
```

```
3334 public static BodyPublisher ofMimeMultipartData(Map<Object,
```

```
Object> data, String boundary)
```

```
35 throws IOException
```

```
36 {
```

```
37 var byteArrays = new ArrayList<byte[]>();
```

```
38 byte[] separator = bytes(" -- " + boundary + "\nContent-
```

```
Disposition: form-data; name=");
```

```
39 for (Map.Entry<Object, Object> entry : data.entrySet())
```

```
40 {
```

```
41 byteArrays.add(separator);
```

```
42
```

```
43 if (entry.getValue() instanceof Path path)
```

```
44 {
```

```
45 String mimeType = Files.probeContentType(path);
```

```
46 byteArrays.add(bytes("\\" + entry.getKey() + "\\;
```

```
filename=\\\"
```

```
47 + path.getFileName() + "\\\"\\nContent-Type: " + mimeType +
```

```
"\\n\\n"));
```

```
48 byteArrays.add(Files.readAllBytes(path));
```

```
49 }
```

```
50 else
```

```
51 byteArrays.add(bytes("\\" + entry.getKey() + "\\\"\\n\\n" +
```

```
entry.getValue() + "\\n"));
```

```
52 }
```

```
53 byteArrays.add(bytes(" -- " + boundary + "--));
```

```
54 return BodyPublishers.ofByteArrays(byteArrays);
```

```
55 }
```

```
56
```

```
57 public static BodyPublisher ofSimpleJSON(Map<Object, Object>
```

```
data)
```

```
58 {
```

```
59 var builder = new StringBuilder();
```

```
60 builder.append("{");
```

```
61 var first = true;
```

```
62 for (Map.Entry<Object, Object> entry : data.entrySet())
```

```
63 {
```

```
64 if (first) first = false;
```

```
65 else
```

```
66 builder.append(",");
```

```
67 }
```

```
builder.append(jsonEscape(entry.getKey().toString())).append(": ")
68 .append(jsonEscape(entry.getValue().toString())));
69 }
70 builder.append("}");
71 return BodyPublishers.ofString(builder.toString());
72 }
73
74 private static Map<Character, String> replacements =
Map.of('\b', "\\b", '\f', "\\f",
75 '\n', "\\n", '\r', "\\r", '\t', "\\t", '\'', "\\\\"", '\\',
"\\\\\\");
76
77 private static StringBuilder jsonEscape(String str)
78 {
79 var result = new StringBuilder("\\\"");
80 for (int i = 0; i < str.length(); i++)
81 {
82 char ch = str.charAt(i);83 String replacement
= replacements.get(ch);
83 if (replacement == null) result.append(ch);
84 else result.append(replacement);
85 }
86 }
87 result.append("\\\"");
88 return result;
89 }
90 }
91
92 public class HttpClientTest
93 {
94 public static void main(String[] args)
95 throws IOException, URISyntaxException,
InterruptedException
96 {
97 System.setProperty("jdk.httpclient.HttpClient.log",
"headers,errors");
98 String propsFilename = args.length > 0 ? args[0] :
"client/post.properties";
99 Path propsPath = Path.of(propsFilename);
100 var props = new Properties();101 try (Reader in =
Files.newBufferedReader(propsPath, StandardCharsets.UTF_8))
102 {
```

```
103 props.load(in);
104 }
105 String urlString = "" + props.remove("url");
106 String contentType = "" + props.remove("Content-Type");
107 if (contentType.equals("multipart/form-data"))
108 {
109 var generator = new Random();
110 String boundary = new BigInteger(256,
111 generator).toString();
112 contentType += ";boundary=" + boundary;
113 props.replaceAll((k, v) ->
114 v.toString().startsWith("file://")
115 ?
116 propsPath.getParent().resolve(Path.of(v.toString().substring(7)))
117 : v);
118 }
119 }
120
121 public static String doPost(String url, String contentType,
122 Map<Object, Object> data)
123 throws IOException, URISyntaxException,
124 InterruptedException
125 {
126 HttpClient client = HttpClient.newBuilder()
127 .followRedirects(HttpClient.Redirect.ALWAYS).build();
128
129 BodyPublisher publisher = null;
130 if (contentType.startsWith("multipart/form-data"))
131 {
132 String boundary =
133 contentType.substring(contentType.lastIndexOf("=") + 1);131
134 publisher = MoreBodyPublishers.ofMimeMultipartData(data, boundary);
135 }
136 else if (contentType.equals("application/x-www-form-
137 urlencoded"))
138 publisher = MoreBodyPublishers.ofFormData(data);
139 else
140 {
141 contentType = "application/json";
```

```
138 publisher = MoreBodyPublishers.ofSimpleJSON(data);
139 }
140
141 HttpRequest request = HttpRequest.newBuilder()
142 .uri(new URI(url))
143 .header("Content-Type", contentType)
144 .POST(publisher)
145 .build();
146 HttpResponse<String> response
147 = client.send(request,
148 HttpResponse.BodyHandlers.ofString());
149 return response.body();
150 }
```

---

### **java.net.http.HttpClient 11**

- static HttpClient newHttpClient()  
yields an HttpClient with a default configuration.
  - static HttpClient.Builder newBuilder()  
yields a builder for building an HttpClient.
  - <T> HttpResponse<T> send(HttpRequest request,  
HttpResponse.BodyHandler<T> responseBodyHandler)
  - <T> CompletableFuture<HttpResponse<T>>  
sendAsync(HttpRequest request,  
HttpResponse.BodyHandler<T> responseBodyHandler)
- make a synchronous or asynchronous request and process the response body with the given handler.

### **java.net.http.HttpClient.Builder 11**

- HttpClient build()

yields an `HttpClient` with the properties configured by this builder.

- `HttpClient.Builder followRedirects(HttpClient.Redirect policy)`  
sets the redirect policy to one of the values ALWAYS, NEVER, or NORMAL (only refuse redirects from HTTPS to HTTP) of the `HttpClient.Redirect` enumeration.
- `HttpClient.Builder executor(Executor executor)`  
sets the executor for asynchronous requests.

## `java.net.http.HttpRequest` 11

- `HttpRequest.Builder newBuilder()`  
returns a builder for building an `HttpRequest`.
- `HttpRequest.Builder newBuilder(HttpServletRequest request, BiPredicate<String, String> filter)` 16  
returns a builder for building a request with the same properties as the provided one, with only the headers that are accepted by the filter.

## `java.net.http.HttpRequest.Builder` 11

- `HttpRequest build()`  
yields an `HttpRequest` with the properties configured by this builder.
- `HttpRequest.Builder uri(URI uri)`  
sets the URI for this request.
- `HttpRequest.Builder header(String name, String value)`

sets a request header for this request.

- `HttpRequest.Builder GET()`
- `HttpRequest.Builder DELETE()`
- `HttpRequest.Builder POST(HttpRequest.BodyPublisher bodyPublisher)`
- `HttpRequest.Builder PUT(HttpRequest.BodyPublisher bodyPublisher)`

set the request method and body for this request.

## **`java.net.http.HttpResponse<T>`** 11

- `T body()`  
yields the body of this response.
- `int statusCode()`  
yields the status code for this response.
- `HttpHeaders headers()`  
yields the response headers.

## **`java.net.http.HttpHeaders`** 11

- `Map<String, List<String>> map()`  
yields a Map of these headers.
- `Optional<String> firstValue(String name)`  
The first value with the given name in these headers, if present.

## 4.5 Sending E-Mail

In the past, it was simple to write a program that sends e-mail by making a socket connection to port 25, the SMTP port, of a mail server. The Simple Mail Transport Protocol (SMTP) describes the format for e-mail messages. Once you are connected to the server, send a mail header (in the SMTP format, which is easy to generate), followed by the mail message.

Here are the details:

1. Open a socket to your host.

[Click here to view code image](#)

```
var s = new Socket("mail.yourserver.com", 25); // 25 is SMTP
var out = new PrintWriter(s.getOutputStream(),
StandardCharsets.UTF_8);
```

2. Send the following information to the print stream:

[Click here to view code image](#)

*HELO sending host MAIL FROM: sender e-mail address RCPT TO:  
recipient e-mail address DATA Subject: subject (blank line) mail  
message (any number of lines) . QUIT*

The SMTP specification (RFC 821) states that lines must be terminated with \r followed by \n.

It used to be that SMTP servers were often willing to route e-mail from anyone. However, in these days of spam floods, most servers have built-in checks and only accept requests from users or IP address ranges that they trust. Authentication usually happens over secure socket connections.

Implementing these authentication schemes manually would be very tedious. Instead, we will show you how to use the JavaMail API to send e-mail from a Java program.

Download JavaMail from [www.oracle.com/technetwork/java/javamail](http://www.oracle.com/technetwork/java/javamail) and unzip it somewhere on your hard disk.

To use JavaMail, you need to set up some properties that depend on your mail server. For example, with GMail, you use

[Click here to view code image](#)

```
mail.transport.protocol=smt�ps
mail.smt�ps.auth=true
mail.smt�ps.host=smtp.gmail.com
mail.smt�ps.user=accountname@gmail.com
```

Our sample program reads these from a property file.

For security reasons, we don't put the password into the property file but instead prompt for it.

Read in the property file, then get a mail session like this:

[Click here to view code image](#)

```
Session mailSession = Session.getDefaultInstance(props);
```

Make a message with the desired sender, recipient, subject, and message text:

[Click here to view code image](#)

```
var message = new MimeMessage(mailSession);
message.setFrom(new InternetAddress(from));
message.addRecipient(RecipientType.TO, new InternetAddress(to));
message.setSubject(subject);
message.setText(builder.toString());
```

Then send it off:

[Click here to view code image](#)

```
Transport tr = mailSession.getTransport();
tr.connect(null, password);
tr.sendMessage(message, message.getAllRecipients());
tr.close();
```

The program in [Listing 4.9](#) reads the message from a text file of the format

*Sender*

*Recipient*

*Subject*

*Message text (any number of lines)*

To run the program, download the JavaMail implementation from <https://javaee.github.io/javamail>. You also need the JAR file for the Java Activation Framework—get it from <https://www.oracle.com/java/technologies/downloads.html> or search on Maven Central. Then run

[Click here to view code image](#)

```
java -classpath .:javax.mail.jar:activation-1.1.1.jar
path/to/message.txt
```

At the time of this writing, GMail does not check the veracity of the information—you can supply any sender you like. (Keep this in mind the next time you get an e-mail message from president@whitehouse.gov inviting you to a black-tie affair on the front lawn.)

---



### Tip

If you can't figure out why your mail connection isn't working, call

```
mailSession.setDebug(true);
```

and check out the messages. Also, the JavaMail API FAQ has some useful debugging hints.

---

### **Listing 4.9** mail/MailTest.java

[Click here to view code image](#)

```
1 package mail;
2
3 import java.io.*;
4 import java.nio.charset.*;
```

```
5 import java.nio.file.*;
6 import java.util.*;
7 import javax.mail.*;
8 import javax.mail.internet.*;
9 import javax.mail.internet.MimeMessage.RecipientType;
10
11 /**
12 * This program shows how to use JavaMail to send mail messages.
13 * @author Cay Horstmann
14 * @version 1.02 2021-06-17
15 */
16 public class MailTest
17 {
18 public static void main(String[] args) throws
19 MessagingException, IOException
20 {
21 var props = new Properties();
22 try (Reader in = Files.newBufferedReader(Path.of("mail",
23 "mail.properties"), StandardCharsets.UTF_8))
24 {
25 props.load(in);
26 }
27 List<String> lines = Files.readAllLines(Path.of(args[0]),
28 StandardCharsets.UTF_8);
29
30 String from = lines.get(0);
31 String to = lines.get(1);
32 String subject = lines.get(2);
33
34 var builder = new StringBuilder();
35 for (int i = 3; i < lines.size(); i++)
36 {
37 builder.append(lines.get(i));
38 builder.append("\n");
39 }
40
41 Console console = System.console();
42 var password = new String(console.readPassword("Password:
43 "));
44
45 Session mailSession = Session.getDefaultInstance(props);
```

```
43 // mailSession.setDebug(true);
44 var message = new MimeMessage(mailSession);
45 message.setFrom(new InternetAddress(from));
46 message.addRecipient(RecipientType.TO, new
InternetAddress(to));
47 message.setSubject(subject);
48 message.setText(builder.toString());
49 Transport tr = mailSession.getTransport();
50 try
51 {
52 tr.connect(null, password);
53 tr.sendMessage(message, message.getAllRecipients());
54 }
55 finally
56 {
57 tr.close();
58 }
59 }
60 }
```

---

In this chapter, you have seen how to write network clients and servers in Java and how to harvest information from web servers. The next chapter covers database connectivity. You will learn how to work with relational databases in Java, using the JDBC API.

---

# Chapter 5. Database Programming

---

## In this chapter

- [5.1 The Design of JDBC](#)
- [5.2 The Structured Query Language](#)
- [5.3 JDBC Configuration](#)
- [5.4 Working with JDBC Statements](#)
- [5.5 Query Execution](#)
- [5.6 Scrollable and Updatable Result Sets](#)
- [5.7 Row Sets](#)
- [5.8 Metadata](#)
- [5.9 Transactions](#)
- [5.10 Connection Management in Web and Enterprise Applications](#)

In 1996, Sun released the first version of the JDBC API. This API lets programmers connect to a database to query or update it using the Structured Query Language (SQL). (SQL, usually pronounced “sequel,” is an industry standard for relational database access.) JDBC has since become one of the most commonly used APIs in the Java library.

JDBC has been updated several times. As this book is published, JDBC 4.3, the version included with Java 9, is the most current version.

In this chapter, I will explain the key ideas behind JDBC. I will introduce you to (or refresh your memory of) SQL, the industry-standard Structured Query

Language for relational databases. The chapter has enough details and examples to let you start using JDBC for common programming situations.

---



### Note

According to Oracle, JDBC is a trademarked term and not an acronym for Java Database Connectivity. It was named to be reminiscent of ODBC, a standard database API pioneered by Microsoft and since incorporated into the SQL standard.

---

## 5.1 The Design of JDBC

From the start, the developers of the Java technology were aware of the potential that Java showed for working with databases. In 1995, they began work on extending the standard Java library to deal with SQL access to databases. What they first hoped to do was to extend Java so that a program could talk to any random database using only “pure” Java. It didn’t take them long to realize that this is an impossible task: There are simply too many databases out there, using too many protocols. Moreover, although database vendors were all in favor of Java providing a standard network protocol for database access, they were only in favor of it if Java used *their* network protocol.

What all the database vendors and tool vendors *did* agree on was that it would be useful for Java to provide a pure Java API for SQL access along with a driver manager to allow third-party drivers to connect to specific databases. Database vendors could provide their own drivers to plug into the driver manager. There would then be a simple mechanism for registering third-party drivers with the driver manager.

This organization follows the very successful model of Microsoft’s ODBC which provided a C programming language interface for database access. Both JDBC and ODBC are based on the same idea: Programs written according to the API talk to the driver manager, which, in turn, uses a driver to talk to the actual database.

This means the JDBC API is all that most programmers will ever have to deal with.

### 5.1.1 JDBC Driver Types

The JDBC specification classifies drivers into the following *types*:

- A *type 1 driver* translates JDBC to ODBC and relies on an ODBC driver to communicate with the database. Early versions of Java included one such driver, the *JDBC/ODBC bridge*. However, the bridge requires deployment and proper configuration of an ODBC driver. When JDBC was first released, the bridge was handy for testing, but it was never intended for production use. At this point, many better drivers are available, and the JDK no longer provides the JDBC/ODBC bridge.
- A *type 2 driver* is written partly in Java and partly in native code; it communicates with the client API of a database. To use such a driver, you must install some platform-specific code onto the client in addition to a Java library.
- A *type 3 driver* is a pure Java client library that uses a database-independent protocol to communicate database requests to a server component, which then translates the requests into a database-specific protocol. This simplifies deployment because the platform-specific code is located only on the server.
- A *type 4 driver* is a pure Java library that translates JDBC requests directly to a database-specific protocol.



#### Note

The JDBC specification is available at

<https://jcp.org/aboutJava/communityprocess/mrel/jsr221/index3.html>.

---

Most database vendors supply either a type 3 or type 4 driver with their database. Furthermore, a number of third-party companies specialize in producing drivers with better standards conformance, support for more platforms, better performance, or, in some cases, simply better reliability than the drivers provided by the database vendors.

In summary, the ultimate goal of JDBC is to make possible the following:

- Programmers can write applications in the Java programming language to access any database using standard SQL statements (or even specialized extensions of SQL) while still following Java language conventions.
  - Database vendors and database tool vendors can supply the low-level drivers. Thus, they can optimize their drivers for their specific products.
- 




### Note

If you are curious as to why Java just didn't adopt the ODBC model, the reason, as given at the JavaOne conference in 1996, was this:

- ODBC is hard to learn.
  - ODBC has a few commands with lots of complex options. The preferred style in the Java programming language is to have simple and intuitive methods, but to have lots of them.
  - ODBC relies on the use of `void*` pointers and other C features that are not natural in the Java programming language.
  - An ODBC-based solution is inherently less safe and harder to deploy than a pure Java solution.
- 

### 5.1.2 Typical Uses of JDBC


The traditional client/server model has a rich GUI on the client and a database on the server (see [Figure 5.1](#)). In this model, a JDBC driver is deployed on the client.



**Figure 5.1** A traditional client/server application

However, nowadays it is far more common to have a three-tier model where the client application does not make database calls. Instead, it calls on a middleware layer on the server that in turn makes the database queries. The three-tier model has a couple of advantages. It separates *visual presentation* (on the client) from the *business logic* (in the middle tier) and the raw data (in the database). Therefore, it becomes possible to access the same data and the same business rules from multiple clients, such as a Java desktop application, a web browser, or a mobile app.

Communication between the client and the middle tier typically occurs through HTTP. JDBC manages the communication between the middle tier and the back-end database. [Figure 5.2](#) shows the basic architecture.



**Figure 5.2** A three-tier application

## 5.2 The Structured Query Language

JDBC lets you communicate with databases using SQL, which is the command language for essentially all modern relational databases. Desktop databases usually have a GUI that lets users manipulate the data directly, but server-based databases are accessed purely through SQL.

The JDBC package can be thought of as nothing more than an API for communicating SQL statements to databases. We will briefly introduce SQL in this section. If you have never seen SQL before, you might not find this material sufficient. If so, turn to one of the many learning resources on the topic; I recommend *Learning SQL* by Alan Beaulieu (O'Reilly, 2009) or the online book *Learn SQL The Hard Way* at <http://sql.learncodethehardway.org>.

You can think of a database as a bunch of named tables with rows and columns. Each column has a *column name*. Each row contains a set of related data.

As an example database for this book, we use a set of database tables that describe a collection of classic computer science books (see [Tables 5.1](#) through [5.4](#)).

**Table 5.1** The Authors Table

<b>Author_ID</b>	<b>Name</b>	<b>Fname</b>
ALEX	Alexander	Christopher
BROO	Brooks	Frederick P.
...	...	...

**Table 5.2** The Books Table

<b>Title</b>	<b>ISBN</b>	<b>Publisher_ID</b>	<b>Price</b>
A Guide to the SQL Standard	0-201-96426-0	0201	47.95
A Pattern Language: Towns, Buildings, Construction	0-19-501919-9	019	65.00
...	...	...	...


**Table 5.3** The BooksAuthors Table

<b>ISBN</b>	<b>Author_ID</b>	<b>Seq_No</b>
0-201-96426-0	DATE	1
0-201-96426-0	DARW	2
0-19-501919-9	ALEX	1
...	...	...

**Table 5.4** The Publishers Table

<b>Publisher_ID</b>	<b>Name</b>	<b>URL</b>
0201	Addison-Wesley	<a href="http://www.aw-bc.com">www.aw-bc.com</a>
0407	John Wiley & Sons	<a href="http://www.wiley.com">www.wiley.com</a>
...	...	...

**Figure 5.3** shows a view of the Books table. **Figure 5.4** shows the result of *joining* this table with the Publishers table. The Books and the Publishers tables each contain an identifier for the publisher. When we join both tables on the publisher code, we obtain a *query result* made up of values from the joined tables. Each row in the result contains the information about a book, together with the publisher name and web page URL. Note that the publisher names and URLs are duplicated across several rows because we have several books with the same publisher.




The screenshot shows a Windows-style application window titled "COREJAVA: Books". The menu bar includes File, Edit, View, Tools, Window, and Help. Below the menu is a toolbar with various icons for file operations like Open, Save, Print, and Search. The main area is a grid-based table with the following columns: Title, ISBN, Publisher\_ID, and Price. The table contains 20 rows of book data. The first few rows are:

Title	ISBN	Publisher_ID	Price
UNIX System Administration Handbook	0-13-020601-6	013	68.00
The C Programming Language	0-13-110362-8	013	42.00
A Pattern Language: Towns, Buildings, Construction	0-19-501919-9	019	65.00
Introduction to Automata Theory, Languages, and Computation	0-201-44124-1	0201	105.00
Design Patterns	0-201-63361-2	0201	54.99
The C++ Programming Language	0-201-70073-5	0201	64.99
The Mythical Man-Month	0-201-83595-9	0201	29.95
Computer Graphics: Principles and Practice	0-201-84840-6	0201	79.99
The Art of Computer Programming vol. 1	0-201-89683-4	0201	59.99
The Art of Computer Programming vol. 2	0-201-89684-2	0201	59.99
The Art of Computer Programming vol. 3	0-201-89685-0	0201	59.99
A Guide to the SQL Standard	0-201-96426-0	0201	47.95
Introduction to Algorithms	0-262-03293-7	0262	80.00
Applied Cryptography	0-471-11709-9	0471	60.00
JavaScript: The Definitive Guide	0-596-00048-0	0596	44.95
The Cathedral and the Bazaar	0-596-00108-8	0596	16.95
The Soul of a New Machine	0-679-60261-5	0679	18.95
The Codebreakers	0-684-83130-9	07434	70.00
Cuckoo's Egg	0-7434-1146-3	07434	13.95
The UNIX Hater's Handbook	1-56884-203-1	0471	16.95

At the bottom, it says "Record 1 of 20" and has navigation buttons for previous, next, and last records.

**Figure 5.3** Sample table containing books



**Figure 5.4** Two tables joined together

The benefit of joining tables is avoiding unnecessary duplication of data in the database tables. For example, a naive database design might have had columns for the publisher name and URL right in the `Books` table. But then the database itself, and not just the query result, would have many duplicates of these entries. If a publisher's web address changed, *all* entries would need to be updated. Clearly, this is somewhat error-prone. In the relational model, we distribute data into multiple tables so that no information is unnecessarily duplicated. For example, each publisher's URL is contained only once in the publisher table. If the information needs to be combined, the tables are joined.

In the figures, you can see a graphical tool to inspect and link the tables. Many vendors have tools to express queries in a simple form by connecting column names and filling information into forms. Such tools are often called *query by example* (QBE) tools. In contrast, a query that uses SQL is written out in text, using SQL syntax, for example:

[Click here to view code image](#)

```
SELECT Books.Title, Books.Publisher_Id, Books.Price,
Publishers.Name, Publishers.URL
FROM Books, Publishers
WHERE Books.Publisher_Id = Publishers.Publisher_Id
```

In the remainder of this section, you will learn how to write such queries. If you are already familiar with SQL, just skip this section.

By convention, SQL keywords are written in capital letters, although this is not necessary.

The SELECT statement is quite flexible. You can simply select all rows in the Books table with the following query:

```
SELECT * FROM Books
```

The FROM clause is required in every SQL SELECT statement. It tells the database which tables to examine to find the data.

You can choose the columns that you want:

```
SELECT ISBN, Price, Title
FROM Books
```

You can restrict the rows in the answer with the WHERE clause:

```
SELECT ISBN, Price, Title
FROM Books
WHERE Price <= 29.95
```

Be careful with the “equals” comparison. SQL uses = and <>, rather than == or != as in the Java programming language, for equality testing.



## Note

Some database vendors support the use of != for inequality testing. This is not standard SQL, so I recommend against such use. != operator (SQL)

---

The WHERE clause can also use pattern matching by means of the LIKE operator. The wildcard characters are not the usual \* and ?, however. Use a % for zero or more characters and an underscore for a single character. For example,

```
SELECT ISBN, Price, Title
FROM Books
WHERE Title NOT LIKE '%n_x%'
```

excludes books with titles that contain words such as Unix or Linux.

Note that strings are enclosed in single quotes, not double quotes. A single quote inside a string is represented by a pair of single quotes. For example,

```
SELECT Title
FROM Books
WHERE Title LIKE '%''%'
```

reports all titles that contain a single quote.

You can select data from multiple tables:

[Click here to view code image](#)

```
SELECT * FROM Books, Publishers
```

Without a WHERE clause, this query is not very interesting. It lists *all combinations* of rows from both tables. In our case, where Books has 20 rows and Publishers has 8 rows, the result is a set of rows with  $20 \times 8$  entries and lots of duplications. We really want to constrain the query to say that we are only interested in *matching* books with their publishers:

[Click here to view code image](#)

```
SELECT * FROM Books, Publishers
WHERE Books.Publisher_Id = Publishers.Publisher_Id
```

This query result has 20 rows, one for each book, because each book has one publisher in the Publisher table.

Whenever you have multiple tables in a query, the same column name can occur in two different places. That happened in our example. There is a column called Publisher\_Id in both the Books and the Publishers tables. When an ambiguity would otherwise result, you must prefix each column name with the name of the table to which it belongs, such as Books.Publisher\_Id.

You can use SQL to change the data inside a database as well. For example, suppose you want to reduce by \$5.00 the current price of all books that have “C++” in their title:

```
UPDATE Books
SET Price = Price - 5.00
WHERE Title LIKE '%C++%'
```

Similarly, to delete all C++ books, use a DELETE query:

```
DELETE FROM Books
WHERE Title LIKE '%C++%'
```

SQL comes with built-in functions for taking averages, finding maximums and minimums in a column, and so on, which we do not discuss here.

Typically, to insert values into a table, you can use the INSERT statement:

[Click here to view code image](#)

```
INSERT INTO Books
VALUES ('A Guide to the SQL Standard', '0-201-96426-0', '0201',
47.95)
```

You need a separate `INSERT` statement for every row being inserted in the table.

Of course, before you can query, modify, and insert data, you must have a place to store data. Use the `CREATE TABLE` statement to make a new table. Specify the name and data type for each column. For example,

```
CREATE TABLE Books
(
 Title CHAR(60),
 ISBN CHAR(13),
 Publisher_Id CHAR(6),
 Price DECIMAL(10,2)
)
```

[Table 5.5](#) shows the most common SQL data types.

**Table 5.5** Common SQL Data Types

Data Types	Description
INTEGER or INT	Typically, a 32-bit integer
SMALLINT	Typically, a 16-bit integer
NUMERIC ( $m, n$ ), DECIMAL ( $m, n$ ) or DEC ( $m, n$ )	Fixed-point decimal number with $m$ total digits and $n$ digits after the decimal point
FLOAT ( $n$ )	A floating-point number with $n$ binary digits of precision
REAL	Typically, a 32-bit floating-point number
DOUBLE	Typically, a 64-bit floating-point number
CHARACTER ( $n$ ) or CHAR ( $n$ )	Fixed-length string of length $n$
VARCHAR ( $n$ )	Variable-length strings of maximum length $n$
BOOLEAN	A Boolean value
DATE	Calendar date, implementation-dependent
TIME	Time of day, implementation-dependent

Data Types	Description
TIMESTAMP	Date and time of day, implementation-dependent
BLOB	A binary large object
CLOB	A character large object

In this book, we do not discuss the additional clauses, such as keys and constraints, that you can use with the CREATE TABLE statement.

## 5.3 JDBC Configuration

Of course, you need a database program for which a JDBC driver is available. There are many excellent choices, such as IBM DB2, Microsoft SQL Server, MySQL, Oracle, and PostgreSQL.

You must also create a database for your experimental use. We assume you name it COREJAVA. Create a new database, or have your database administrator create one with the appropriate permissions. You need to be able to create, update, and drop tables in the database.

If you have never installed a client/server database before, you might find setting up the database to be somewhat complex—diagnosing causes of failure can be difficult. It might be best to seek expert help if your setup is not working correctly.

If this is your first experience with databases, I recommend that you use the Apache Derby database, which is available from <http://db.apache.org/derby>.

You need to gather a number of items before you can write your first database program. The following sections cover these items.

### 5.3.1 Database URLs

When connecting to a database, you must use various database-specific parameters such as host names, port numbers, and database names.

JDBC uses a syntax similar to that of ordinary URLs to describe data sources. Here are examples of the syntax:

[Click here to view code image](#)

```
jdbc:derby://localhost:1527/COREJAVA;create=true
jdbc:postgresql:COREJAVA
```

These JDBC URLs specify a Derby database and a PostgreSQL database named COREJAVA.

The general syntax is

```
jdbc:subprotocol:other stuff
```

where a subprotocol selects the specific driver for connecting to the database.

The format for the *other stuff* depends on the subprotocol used. You will need to look up your vendor's documentation for the specific format.

### 5.3.2 Driver JAR Files

You need to obtain the JAR file in which the driver for your database is located. If you use Derby, you need the file `derbyclient.jar`. With another database, you need to locate the appropriate driver. For example, the PostgreSQL drivers are available at <http://jdbc.postgresql.org>.

Include the driver JAR file on the class path when running a program that accesses the database. (You don't need the JAR file for compiling.)

When you launch programs from the command line, simply use the command

[Click here to view code image](#)

```
java -classpath driverPath::. ProgramName
```

On Windows, use a semicolon to separate the current directory (denoted by the `.` character) from the driver JAR location.

### 5.3.3 Starting the Database

The database server needs to be started before you can connect to it. The details depend on your database.

With the Derby database, follow these steps:

1. Open a command shell and change to a directory that will hold the database files.
2. Locate the file `derbyrun.jar`. With some versions of the JDK, it is contained in the `jdk/db/lib` directory. If it's not there, install Apache Derby and locate the JAR file in the installation directory. We will denote the directory containing `lib/derbyrun.jar` with `derby`.
3. Run the command

[Click here to view code image](#)

```
java -jar derby/lib/derbyrun.jar server start
```

4. Double-check that the database is working correctly. Create a file `ij.properties` that contains these lines:

[Click here to view code image](#)

```
ij.driver=org.apache.derby.jdbc.ClientDriver
ij.protocol=jdbc:derby://localhost:1527/
ij.database=COREJAVA;create=true
```

From another command shell, run Derby's interactive scripting tool (called `ij`) by executing

[Click here to view code image](#)

```
java -jar derby/lib/derbyrun.jar ij -p ij.properties
```

Now you can issue SQL commands such as

[Click here to view code image](#)

```
CREATE TABLE Greetings (Message CHAR(20));
INSERT INTO Greetings VALUES ('Hello, World!');
SELECT * FROM Greetings;
DROP TABLE Greetings;
```

Note that each command must be terminated by a semicolon. To exit, type

```
EXIT;
```

5. When you are done using the database, stop the server with the command  
[Click here to view code image](#)

```
java -jar derby/lib/derbyrun.jar server shutdown
```

If you use another database, you need to consult the documentation to find out how to start and stop your database server, and how to connect to it and issue SQL commands.

### 5.3.4 Registering the Driver Class

Many JDBC JAR files (such as the Apache Derby driver) automatically register the driver class. In that case, you can skip the manual registration step that we describe in this section. A JAR file can automatically register the driver class if it contains a file META-INF/services/java.sql.Driver. You can simply unzip your driver's JAR file to check.

If your driver's JAR file doesn't support automatic registration, you need to find out the name of the JDBC driver classes used by your vendor. Typical driver names are

[Click here to view code image](#)

```
org.apache.derby.jdbc.ClientDriver
org.postgresql.Driver
```

There are two ways to register the driver with the DriverManager. One way is to load the driver class in your Java program. For example,

[Click here to view code image](#)

```
Class.forName("org.postgresql.Driver"); // force loading of driver
class
```

This statement causes the driver class to be loaded, thereby executing a static initializer that registers the driver.

Alternatively, you can set the `jdbc.drivers` property. You can specify the property with a command-line argument, such as

[Click here to view code image](#)

```
java -Djdbc.drivers=org.postgresql.Driver ProgramName
```

Or, your application can set the system property with a call such as

[Click here to view code image](#)

```
System.setProperty("jdbc.drivers", "org.postgresql.Driver");
```

You can also supply multiple drivers; separate them with colons, for example:

[Click here to view code image](#)

```
org.postgresql.Driver:org.apache.derby.jdbc.ClientDriver
```

### 5.3.5 Connecting to the Database

In your Java program, open a database connection like this:

[Click here to view code image](#)

```
String url = "jdbc:postgresql:COREJAVA";
String username = "dbuser";
String password = "secret";
Connection conn = DriverManager.getConnection(url, username,
password);
```

The driver manager iterates through the registered drivers to find a driver that can use the subprotocol specified in the database URL.

The `getConnection` method returns a `Connection` object. In the following sections, you will see how to use the `Connection` object to execute SQL statements.

To connect to the database, you will need a user name and password for your database.



## Note

By default, Derby lets you connect with any user name, and it does not check passwords. A separate set of tables is generated for each user. The default user name is app.

---

The test program in [Listing 5.1](#) puts these steps to work. It loads connection parameters from a file named database.properties and connects to the database. The database.properties file supplied with the sample code contains connection information for the Derby database. If you use a different database, put your database-specific connection information into that file. Here is an example for connecting to a PostgreSQL database:

[Click here to view code image](#)

```
jdbc.drivers=org.postgresql.Driver
jdbc.url=jdbc:postgresql:COREJAVA
jdbc.username=dbuser
jdbc.password=secret
```

After connecting to the database, the test program executes the following SQL statements:

[Click here to view code image](#)

```
CREATE TABLE Greetings (Message CHAR(20))
INSERT INTO Greetings VALUES ('Hello, World!')
SELECT * FROM Greetings
```

The result of the SELECT statement is printed, and you should see an output of

Hello, World!

Then the table is removed by executing the statement

```
DROP TABLE Greetings
```

To run this test, start your database as described previously, and launch the program as

[Click here to view code image](#)

```
java -classpath .:driverJAR test.TestDB
```

(As always, Windows users need to use ; instead of : to separate the path elements.)

---



### Tip

One way to debug JDBC-related problems is to enable JDBC tracing. Call the `DriverManager.setLogWriter` method to send trace messages to a `PrintWriter`. The trace output contains a detailed listing of the JDBC activity. Most JDBC driver implementations provide additional mechanisms for tracing. For example, with Derby, you can add a `traceFile` option to the JDBC URL:

```
jdbc:derby://localhost:1527/COREJAVA;create=true;traceFile=trace.out.
```

---

### **Listing 5.1** test/TestDB.java

[Click here to view code image](#)

```
1 package test;
2
3 import java.nio.file.*;
4 import java.sql.*;
5 import java.io.*;
6 import java.nio.charset.*;
7 import java.util.*;
8
9 /**
10 * This program tests that the database and the JDBC driver are
11 * correctly configured.
12 * @version 1.04 2021-06-17
13 * @author Cay Horstmann
```

```
13 /*
14 public class TestDB
15 {
16 public static void main(String args[]) throws IOException
17 {
18 try
19 {
20 runTest();
21 }
22 catch (SQLException e)
23 {
24 for (Throwable t : e)
25 t.printStackTrace();
26 }
27 }
28
29 /**
30 * Runs a test by creating a table, adding a value, showing
31 * the table contents, and
32 * removing the table.
33 */
34 public static void runTest() throws SQLException,
35 IOException
36 {
37 try (Connection conn = getConnection();
38 Statement stat = conn.createStatement())
39 {
40 stat.executeUpdate("CREATE TABLE Greetings (Message
41 CHAR(20));");
42 stat.executeUpdate("INSERT INTO Greetings
43 VALUES ('Hello, World!');");
44
45 try (ResultSet result = stat.executeQuery("SELECT *
46 FROM Greetings"))
47 {
48 if (result.next())
49 System.out.println(result.getString(1));
50
51 stat.executeUpdate("DROP TABLE Greetings");
52 }
53 }
54 }
55 }
```

```
48 }
49
50 /**
51 * Gets a connection from the properties specified in the
52 * file database.properties.
53 * @return the database connection
54 */
55 public static Connection getConnection() throws
56 SQLException, IOException
57 {
58 var props = new Properties();
59 try (Reader in = Files.newBufferedReader(
60 Path.of("database.properties"),
61 StandardCharsets.UTF_8))
62 {
63 props.load(in);
64 String drivers = props.getProperty("jdbc.drivers");
65 if (drivers != null) System.setProperty("jdbc.drivers",
66 drivers);
67
68 String url = props.getProperty("jdbc.url");
69 String username = props.getProperty("jdbc.username");
70 String password = props.getProperty("jdbc.password");
71
72 return DriverManager.getConnection(url, username,
73 password);
74 }
75 }
```

---

## **java.sql.DriverManager 1.1**

- static Connection getConnection(String url,  
String user, String password)
- establishes a connection to the given database and returns a Connection object.

## 5.4 Working with JDBC Statements

In the following sections, you will see how to use the JDBC Statement to execute SQL statements, obtain results, and deal with errors. Then we show you a simple program for populating a database.

### 5.4.1 Executing SQL Statements

To execute a SQL statement, you first create a Statement object. To create statement objects, use the Connection object that you obtained from the call to `DriverManager.getConnection`.

[Click here to view code image](#)

```
Statement stat = conn.createStatement();
```

Next, place the statement that you want to execute into a string, for example:

[Click here to view code image](#)

```
String command = "UPDATE Books"
+ " SET Price = Price - 5.00"
+ " WHERE Title NOT LIKE '%Introduction%'";
```

Then, call the `executeUpdate` method of the Statement interface:

```
stat.executeUpdate(command);
```

The `executeUpdate` method returns a count of the rows that were affected by the SQL statement, or zero for statements that do not return a row count. For example, the call to `executeUpdate` in the preceding example returns the number of rows where the price was lowered by \$5.00.

The `executeUpdate` method can execute actions such as `INSERT`, `UPDATE`, and `DELETE`, as well as data definition statements such as `CREATE TABLE` and `DROP TABLE`. However, you need to use the `executeQuery` method to execute `SELECT` queries. There is also a catch-all `execute` statement to execute arbitrary SQL statements. It's commonly used only for queries that a user supplies interactively.

When you execute a query, you are interested in the result. The `executeQuery` object returns an object of type `ResultSet` that you can use to walk through the result one row at a time.

[Click here to view code image](#)

```
ResultSet rs = stat.executeQuery("SELECT * FROM Books");
```

The basic loop for analyzing a result set looks like this:

```
while (rs.next())
{
 look at a row of the result set
}
```

---



## Caution

The iteration protocol of the `ResultSet` interface is subtly different from that of the `java.util.Iterator` interface. Here, the iterator is initialized to a position *before* the first row. You must call the `next` method once to move the iterator to the first row. Also, there is no `hasNext` method; keep calling `next` until it returns `false`.

---

The order of the rows in a result set is completely arbitrary. Unless you specifically ordered the result with an `ORDER BY` clause, you should not attach any significance to the row order.

When inspecting an individual row, you will want to know the contents of the fields. A large number of accessor methods give you this information.

[Click here to view code image](#)

```
String isbn = rs.getString(1);
double price = rs.getDouble("Price");
```

There are accessors for various *types*, such as `getString` and `getDouble`. Each accessor has two forms, one taking a numeric argument, and the other, a

string argument. When you supply a numeric argument, you refer to the column with that number. For example, `rs.getString(1)` returns the value of the first column in the current row.

---



## Caution

Unlike array indexes, database column numbers start at 1.

---

When you supply a string argument, you refer to the column in the result set with that name. For example, `rs.getDouble("Price")` returns the value of the column with label `Price`. Using the numeric argument is a bit more efficient, but string arguments make the code easier to read and maintain.

Each `get` method makes reasonable type conversions when the type of the method doesn't match the type of the column. For example, the call `rs.getString("Price")` converts the floating-point value of the `Price` column to a string.

### ***java.sql.Connection 1.1***

- `Statement createStatement()`

creates a `Statement` object that can be used to execute SQL queries and updates without parameters.

- `void close()`

immediately closes the current connection and the JDBC resources that it created.

### ***java.sql.Statement 1.1***

- `ResultSet executeQuery(String sqlQuery)`

executes the SQL statement given in the string and returns a `ResultSet` object to view the query result.

- `int executeUpdate(String sqlStatement)`
- `long executeLargeUpdate(String sqlStatement)` **8**

execute the SQL INSERT, UPDATE, or DELETE statement specified by the string. Also execute Data Definition Language (DDL) statements such as CREATE TABLE. Return the number of rows affected, or 0 for a statement without an update count.

- `boolean execute(String sqlStatement)`

executes the SQL statement specified by the string. Multiple result sets and update counts may be produced. Returns `true` if the first result is a result set, `false` otherwise. Call `getResultSet` or `getUpdateCount` to retrieve the first result. See [Section 5.5.4, “Multiple Results,”](#) on p. 329 for details on processing multiple results.

- `ResultSet getResultSet()`

returns the result set of the preceding query statement, or `null` if the preceding statement did not have a result set. Call this method only once per executed statement.

- `int getUpdateCount()`
- `long getLargeUpdateCount()` **8**

return the number of rows affected by the preceding update statement, or `-1` if the preceding statement was a statement without an update count. Call this method only once per executed statement.

- `void close()`  
closes this statement object and its associated result set.
- `boolean isClosed()` **6**  
returns `true` if this statement is closed.
- `void closeOnCompletion()` **7**

causes this statement to be closed once all of its result sets have been closed.

### ***java.sql.ResultSet*** 1.1

- `boolean next()`

makes the current row in the result set move forward by one. Returns `false` after the last row. Note that you must call this method to advance to the first row.

- `Xxx getXxx(int columnNumber)`
- `Xxx getXxx(String columnLabel)`  
*(Xxx is a type such as int, double, String, Date, etc.)*
- `<T> T getObject(int columnIndex, Class<T> type)`  
7
- `<T> T getObject(String columnLabel, Class<T> type)` 7
- `void updateObject(int columnIndex, Object x, SQLType targetSqlType)` 8
- `void updateObject(String columnLabel, Object x, SQLType targetSqlType)` 8

return or update the value of the column with the given column index or label, converted to the specified type. The column label is the label specified in the SQL AS clause or the column name if AS is not used.

- `int findColumn(String columnName)`  
gives the column index associated with a column name.
- `void close()`  
immediately closes the current result set.
- `boolean isClosed()` 6

returns true if this statement is closed.

### 5.4.2 Managing Connections, Statements, and Result Sets

Every Connection object can create one or more Statement objects. You can use the same Statement object for multiple unrelated commands and queries. However, a statement has *at most one* open result set. If you issue multiple queries whose results you analyze concurrently, you need multiple Statement objects.

Be forewarned, though, that there is a limit to the number of statements per connection. Use the `getMaxStatements` method of the DatabaseMetaData interface to find out the number of concurrently open statements that your JDBC driver supports.

In practice, you should probably not fuss with multiple concurrent result sets. If the result sets are related, you should be able to issue a combined query and analyze a single result. It is much more efficient to let the database combine queries than it is for a Java program to iterate through multiple result sets.

Be sure to finish processing of any result set before you issue a new query or update on a Statement object. The result sets of prior queries are automatically closed.

When you are done using a ResultSet, Statement, or Connection, it is a good idea to call the `close` method immediately. These objects use large data structures that draw on the finite resources of the database server.

The `close` method of a Statement object closes any associated result sets. Similarly, the `close` method of the Connection class closes all statements of the connection.

Conversely, you can call the `closeOnCompletion` method on a Statement, and it will close automatically as soon as all its result sets have closed.

If your connections are short-lived, don't worry about closing statements and result sets. To make sure a connection object cannot possibly remain open, use a try-with-resources statement:

[Click here to view code image](#)

```
try (Connection conn = . . .)
{
 Statement stat = conn.createStatement();
 ResultSet result = stat.executeQuery(queryString);
 process query result
}
```

### 5.4.3 Analyzing SQL Exceptions


Each SQLException has a chain of SQLException objects that are retrieved with the `getNextException` method. This exception chain is in addition to the “cause” chain of Throwable objects that every exception has. (See Volume I, [Chapter 7](#) for details about Java exceptions.) One would need two nested loops to fully enumerate all these exceptions. Fortunately, the SQLException class has been enhanced to implement the `Iterable<Throwable>` interface. The `iterator()` method yields an `Iterator<Throwable>` that iterates through both chains: It starts by going through the cause chain of the first SQLException, then moves on to the next SQLException, and so on. You can simply use an enhanced `for` loop:

[Click here to view code image](#)

```
for (Throwable t : sqlException)
{
 do something with t
}
```

You can call `getSQLState` and `getErrorCode` on a SQLException to analyze it further. The first method yields a string that is standardized by either X/Open or SQL:2003. (Call the `getSQLStateType` method of the `DatabaseMetaData` interface to find out which standard is used by your driver.) The error code is vendor-specific.

The SQL exceptions are organized into an inheritance tree (shown in [Figure 5.5](#)). This allows you to catch specific error types in a vendor-independent way.



**Figure 5.5** SQL exception types

In addition, the database driver can report nonfatal conditions as warnings. You can retrieve warnings from connections, statements, and result sets. The SQLWarning class is a subclass of SQLException (even though a SQLWarning is not thrown as an exception). Call getSQLState and getErrorCode to get further information about the warnings. Similar to SQL exceptions, warnings are chained. To retrieve all warnings, use this loop:

[Click here to view code image](#)

```

SQLWarning w = stat.getWarning();
while (w != null)
{
 do something with w
}

```

```
w = w.nextWarning();
}
```

The DataTruncation subclass of SQLWarning is used when data being read from the database are unexpectedly truncated. If data truncation happens in an update statement, a DataTruncation is thrown as an exception.

### **`java.sql.SQLException`** 1.1

- `SQLException getNextException()`  
gets the next SQL exception chained to this one, or `null` at the end of the chain.
- `Iterator<Throwable> iterator()` 6  
gets an iterator that yields the chained SQL exceptions and their causes.
- `String getSQLState()`  
gets the “SQL state”—a standardized error code.
- `int getErrorCode()`  
gets the vendor-specific error code.

### **`java.sql.SQLWarning`** 1.1

- `SQLWarning getNextWarning()`  
returns the next warning chained to this one, or `null` at the end of the chain.

### **`java.sql.Connection`** 1.1

### **`java.sql.Statement`** 1.1

### **`java.sql.ResultSet`** 1.1

- `SQLWarning getWarnings()`  
returns the first of the pending warnings, or `null` if no warnings are pending.

### **`java.sql.DataTruncation`** 1.1

- `boolean getParameter()`  
returns `true` if the data truncation applies to a parameter, `false` if it applies to a column.
- `int getIndex()`  
returns the index of the truncated parameter or column.
- `int getDataSize()`  
returns the number of bytes that should have been transferred, or `-1` if the value is unknown.
- `int getTransferSize()`  
returns the number of bytes that were actually transferred, or `-1` if the value is unknown.

#### **5.4.4 Populating a Database**

We are now ready to write our first real JDBC program. Sure, it would be nice to try some of the fancy queries discussed earlier, but we have a problem: Right now, there are no data in the database. We need to populate the database, and a simple way of doing that is with a set of SQL instructions to create tables and insert data into them. Most database programs can process a set of SQL

instructions from a text file, but there are pesky differences about statement terminators and other syntactical issues.

For that reason, we will use JDBC in a simple program that reads a file with SQL instructions, one instruction per line, and executes them.

Specifically, the program reads data from a text file in a format such as

[Click here to view code image](#)

```
CREATE TABLE Publishers (Publisher_Id CHAR(6), Name CHAR(30), URL
CHAR(80));
INSERT INTO Publishers VALUES ('0201', 'Addison-Wesley', 'www.aw-
bc.com');
INSERT INTO Publishers VALUES ('0471', 'John Wiley & Sons',
'www.wiley.com');
. . .
```

[Listing 5.2](#) contains the code for the program that reads a file with SQL statements and executes them. You don't have to read through the code; simply use the program so you can populate your database and run the examples in the remainder of this chapter.

Make sure that your database server is running, and run the program as follows:

[Click here to view code image](#)

```
java -classpath driverPath:. exec.ExecSQL Books.sql
java -classpath driverPath:. exec.ExecSQL Authors.sql
java -classpath driverPath:. exec.ExecSQL Publishers.sql
java -classpath driverPath:. exec.ExecSQL BooksAuthors.sql
```

Before running the program, check that the file `database.properties` is set up properly for your environment (see [Section 5.3.5, “Connecting to the Database,”](#) on p. 304).



**Note**

Your database may also have a utility to read SQL files directly. For example, with Derby, you can run

[Click here to view code image](#)

```
java -jar derby/lib/derbyrun.jar ij -p ij.properties Books.sql
```

(The `ij.properties` file is described in [Section 5.3.3, “Starting the Database,”](#) on p. 303.)

In the data format for the `ExecSQL` command, we allow an optional semicolon at the end of each line because most database utilities expect this format.

---

The following steps briefly describe the `ExecSQL` program:

1. Connect to the database. The `getConnection` method reads the properties in the file `database.properties` and adds the `jdbc.drivers` property to the system properties. The driver manager uses the `jdbc.drivers` property to load the appropriate database driver. The `getConnection` method uses the `jdbc.url`, `jdbc.username`, and `jdbc.password` properties to open the database connection.
2. Open the file with the SQL statements. If no file name was supplied, prompt the user to enter the statements on the console.
3. Execute each statement with the generic `execute` method. If it returns `true`, the statement had a result set. The four SQL files provided for the book database all end in a `SELECT *` statement so that you can see that the data were successfully inserted.
4. If there was a result set, print out the result. Since this is a generic result set, we need to use metadata to find out how many columns the result has. For more information, see [Section 5.8, “Metadata,”](#) on p. 343.
5. If there is any SQL exception, print the exception and any chained exceptions that may be contained in it.
6. Close the connection to the database.

[Listing 5.2](#) shows the code for the program.

---

**Listing 5.2** exec/ExecSQL.java

---

[Click here to view code image](#)

```
1 package exec;
2
3 import java.io.*;
4 import java.nio.charset.*;
5 import java.nio.file.*;
6 import java.util.*;
7 import java.sql.*;
8
9 /**
10 * Executes all SQL statements in a file. Call this program as

11 * java -classpath driverPath:. ExecSQL commandFile
12 *
13 * @version 1.34 2021-06-17
14 * @author Cay Horstmann
15 */
16 class ExecSQL
17 {
18 public static void main(String args[]) throws IOException
19 {
20 try (Scanner in = args.length == 0 ? new
Scanner(System.in)
21 : new Scanner(Path.of(args[0]),
StandardCharsets.UTF_8))
22 {23 try (Connection conn = getConnection();
24 Statement stat = conn.createStatement())
25 {
26 while (true)
27 {
28 if (args.length == 0) System.out.println("Enter
command or EXIT to exit:");
29
30 if (!in.hasNextLine()) return;
31
32 String line = in.nextLine().strip();
33 if (line.equalsIgnoreCase("EXIT")) return;
34
35 }
36 }
37 }
38 }
39 }
```

```
34 if (line.endsWith(";")) // remove trailing
semicolon
35 line = line.substring(0, line.length() - 1);
36 try
37 {
38 boolean isResult = stat.execute(line);
39 if (isResult)
40 {
41 try (ResultSet rs = stat.getResultSet())
42 {
43 showResultSet(rs);
44 }
45 }
46 else
47 {
48 int updateCount = stat.getUpdateCount();
49 System.out.println(updateCount + " rows
updated");
50 }
51 }
52 catch (SQLException e)
53 {
54 for (Throwable t : e)
55 t.printStackTrace();
56 }
57 }
58 }
59 }
60 catch (SQLException e)
61 {
62 for (Throwable t : e)
63 t.printStackTrace();
64 }
65 }
66
67 /**
68 * Gets a connection from the properties specified in the file
database.properties
69 * @return the database connection
```

```
70 */
71 public static Connection getConnection() throws SQLException,
72 IOException72 {
73 var props = new Properties();
74 try (Reader in = Files.newBufferedReader(
75 Path.of("database.properties"),
76 StandardCharsets.UTF_8))
77 {
78 props.load(in);
79 String drivers = props.getProperty("jdbc.drivers");
80 if (drivers != null) System.setProperty("jdbc.drivers",
81 drivers);
82 String url = props.getProperty("jdbc.url");
83 String username = props.getProperty("jdbc.username");
84 String password = props.getProperty("jdbc.password");
85
86 return DriverManager.getConnection(url, username,
87 password);
88 }
89 /**
90 * Prints a result set.
91 * @param result the result set to be printed
92 */
93 public static void showResultSet(ResultSet result) throws
SQLException
94 {
95 ResultSetMetaData metaData = result.getMetaData();
96 int columnCount = metaData.getColumnCount();
97
98 for (int i = 1; i <= columnCount; i++)
99 {
100 if (i > 1) System.out.print(", ");
101 System.out.print(metaData.getColumnLabel(i));
102 }
103 System.out.println();
104 }
```

```
105 while (result.next())
106 {
107 for (int i = 1; i <= columnCount; i++)
108 {
109 if (i > 1) System.out.print(", ");
110 System.out.print(result.getString(i));
111 }
112 System.out.println();
113 }
114 }
115 }
```

---

## 5.5 Query Execution

In this section, we write a program that executes queries against the COREJAVA database. For this program to work, you must have a COREJAVA database populated with tables as described in the preceding section.

When querying the database, you can select the author and the publisher or leave either of them as Any.

You can also change the data in the database. Select a publisher and type an amount. All prices of that publisher are adjusted by the amount you entered, and the program displays how many rows were changed. After a price change, you might want to run a query to verify the new prices.

### 5.5.1 Prepared Statements

In this program, we use one new feature, *prepared statements*. Consider the SQL query for all books by a particular publisher, regardless of the author:

[Click here to view code image](#)

```
SELECT Books.Price, Books.Title
FROM Books, Publishers
WHERE Books.Publisher_Id = Publishers.Publisher_Id
AND Publishers.Name = the name from the list box
```

Instead of building a separate query statement every time the user launches such a query, we can *prepare* a query with a host variable and use it many times, each time filling in a different string for the variable. That technique improves performance. Whenever the database executes a query, it first computes a strategy of how to do it efficiently. By preparing the query and reusing it, you ensure that the planning step is done only once.

Each host variable in a prepared query is indicated with a ?. If there is more than one variable, you must keep track of the positions of the ? when setting the values. For example, our prepared query becomes

[Click here to view code image](#)

```
String publisherQuery
 = "SELECT Books.Price, Books.Title"
 + " FROM Books, Publishers"
 + " WHERE Books.Publisher_Id = Publishers.Publisher_Id AND
Publishers.Name = ?";
PreparedStatement stat = conn.prepareStatement(publisherQuery);
```

Before executing the prepared statement, you must bind the host variables to actual values with a set method. As with the get methods of the ResultSet interface, there are different set methods for the various types. Here, we want to set a string to a publisher name:

```
stat.setString(1, publisher);
```

The first argument is the position number of the host variable that we want to set. The position 1 denotes the first ?. The second argument is the value that we want to assign to the host variable.

If you reuse a prepared query that you have already executed, all host variables stay bound unless you change them with a set method or call the clearParameters method. That means you only need to call a setXxx method on those host variables that change from one query to the next.

Once all variables have been bound to values, you can execute the prepared statement:

[Click here to view code image](#)

```
ResultSet rs = stat.executeQuery();
```

---



## Tip

Building a query manually, by concatenating strings, is tedious and potentially dangerous. You have to worry about special characters such as quotes—and, if your query involves user input, you have to guard against injection attacks. Therefore, use prepared statements whenever your query involves variables.

---

The price update feature is implemented as an UPDATE statement. Note that we call `executeUpdate`, not `executeQuery`, because the UPDATE statement does not return a result set. The return value of `executeUpdate` is the count of changed rows.

[Click here to view code image](#)

```
int r = stat.executeUpdate();
System.out.println(r + " rows updated");
```

---



## Note

A `PreparedStatement` object becomes invalid after the associated `Connection` object is closed. However, many databases automatically *cache* prepared statements. If the same query is prepared twice, the database simply reuses the query strategy. Therefore, don't worry about the overhead of calling `prepareStatement`.

---

The following list briefly describes the structure of the example program:

- The author and publisher array lists are populated by running two queries that return all author and publisher names in the database.
- The queries involving authors are complex. A book can have multiple authors, so the `BooksAuthors` table stores the correspondence between

authors and books. For example, the book with ISBN 0-201-96426-0 has two authors with codes DATE and DARW. The BooksAuthors table has the rows

```
0-201-96426-0, DATE, 1
0-201-96426-0, DARW, 2
```

to indicate this fact. The third column lists the order of the authors. (We can't just use the position of the rows in the table. There is no fixed row ordering in a relational table.) Thus, the query has to join the Books, BooksAuthors, and Authors tables to compare the author name with the one selected by the user.

[Click here to view code image](#)

```
SELECT Books.Price, Books.Title FROM Books, BooksAuthors,
Authors, Publishers
WHERE Authors.Author_Id = BooksAuthors.Author_Id AND
BooksAuthors.ISBN = Books.ISBN
AND Books.Publisher_Id = Publishers.Publisher_Id AND Authors.Name
= ?
AND Publishers.Name = ?
```

---



### Tip

Some Java programmers avoid complex SQL statements such as this one. A surprisingly common, but very inefficient, workaround is to write lots of Java code that iterates through multiple result sets. But the database is *a lot* better at executing query code than a Java program can be—that's the core competency of a database. A rule of thumb: If you can do it in SQL, don't do it in Java.

---

- The changePrices method executes an UPDATE statement. Note that the WHERE clause of the UPDATE statement needs the publisher *code* and we only know the publisher *name*. This problem is solved with a nested subquery:

[Click here to view code image](#)

```
UPDATE Books
SET Price = Price + ?
WHERE Books.Publisher_Id = (SELECT Publisher_Id FROM Publishers
WHERE Name = ?)
```

[Listing 5.3](#) is the complete program code.

---

### **Listing 5.3** query/QueryTest.java

---

[Click here to view code image](#)

```
1 package query;
2
3 import java.io.*;
4 import java.nio.charset.*;
5 import java.nio.file.*;
6 import java.sql.*;
7 import java.util.*;
8
9 /**
10 * This program demonstrates several complex database queries.
11 * @version 1.32 2021-06-17
12 * @author Cay Horstmann
13 */
14 public class QueryTest
15 {
16 private static final String allQuery = "SELECT Books.Price,
Books.Title FROM Books";
1718 private static final String authorPublisherQuery = """
19 SELECT Books.Price, Books.Title
20 FROM Books, BooksAuthors, Authors, Publishers
21 WHERE Authors.Author_Id = BooksAuthors.Author_Id
22 AND BooksAuthors.ISBN = Books.ISBN
23 AND Books.Publisher_Id = Publishers.Publisher_Id
24 AND Authors.Name = ?
25 AND Publishers.Name = ?
26 """;;
27
28 private static final String authorQuery = """
```

```
29 SELECT Books.Price, Books.Title FROM Books, BooksAuthors,
Authors
30 WHERE Authors.Author_Id = BooksAuthors.Author_Id"
31 AND BooksAuthors.ISBN = Books.ISBN"
32 AND Authors.Name = ?
33 """";
34
35 private static final String publisherQuery = """
36 SELECT Books.Price, Books.Title FROM Books, Publishers
37 WHERE Books.Publisher_Id = Publishers.Publisher_Id
38 AND Publishers.Name = ?
39 """";
40
41 private static final String priceUpdate = """
42 UPDATE Books SET Price = Price + ? "
43 WHERE Books.Publisher_Id =
44 (SELECT Publisher_Id FROM Publishers WHERE Name = ?)
45 """";
46
47 private static Scanner in;
48 private static ArrayList<String> authors = new ArrayList<>();
49 private static ArrayList<String> publishers = new ArrayList<>()
();
50
51 public static void main(String[] args) throws IOException
52 {
53 try (Connection conn = getConnection())
54 {
55 in = new Scanner(System.in);
56 authors.add("Any");
57 publishers.add("Any");
58 try (Statement stat = conn.createStatement())
59 {
60 // Fill the authors array list
61 String query = "SELECT Name FROM Authors";
62 try (ResultSet rs = stat.executeQuery(query))
63 {
64 while (rs.next()) 65
authors.add(rs.getString(1));

```

```
66 }
67
68 // Fill the publishers array list
69 query = "SELECT Name FROM Publishers";
70 try (ResultSet rs = stat.executeQuery(query))
71 {
72 while (rs.next())
73 publishers.add(rs.getString(1));
74 }
75 }
76 boolean done = false;
77 while (!done)
78 {
79 System.out.print("Q) uey C) hange prices E)xit: ");
80 String input = in.nextLine().toUpperCase();
81 if (input.equals("Q"))
82 executeQuery(conn);
83 else if (input.equals("C"))
84 changePrices(conn);
85 else
86 done = true;
87 }
88 }
89 catch (SQLException e)
90 {
91 for (Throwable t : e)
92 System.out.println(t.getMessage());
93 }
94 }
95
96 /**
97 * Executes the selected query.
98 * @param conn the database connection
99 */
100 private static void executeQuery(Connection conn) throws
SQLException
101 {
102 String author = select("Authors:", authors);
103 String publisher = select("Publishers:", publishers);
```

```
104 PreparedStatement stat;
105 if (!author.equals("Any") && !publisher.equals("Any"))
106 {
107 stat = conn.prepareStatement(authorPublisherQuery);
108 stat.setString(1, author);
109 stat.setString(2, publisher);
110 }
111 else if (!author.equals("Any") &&
112 publisher.equals("Any"))
113 {
114 stat = conn.prepareStatement(authorQuery);
115 stat.setString(1, author);
116 }
117 else if (author.equals("Any") &&
118 !publisher.equals("Any"))
119 {
120 stat = conn.prepareStatement(publisherQuery);
121 stat.setString(1, publisher);
122 }
123 else
124 {
125 stat = conn.prepareStatement(allQuery);
126 try (ResultSet rs = stat.executeQuery())
127 {
128 while (rs.next())
129 System.out.println(rs.getString(1) + ", " +
130 rs.getString(2));
131 }
132 }
133 /**
134 * Executes an update statement to change prices.
135 * @param conn the database connection
136 */
137 public static void changePrices(Connection conn) throws
138 SQLException
139 {
140 String publisher = select("Publishers:",
141 publishers.subList(1, publishers.size()));
```

```
138 System.out.print("Change prices by: ");
139 double priceChange = in.nextDouble();
140 PreparedStatement stat =
141 conn.prepareStatement(priceUpdate);
142 stat.setDouble(1, priceChange);
143 stat.setString(2, publisher);
144 int r = stat.executeUpdate();
145 System.out.println(r + " records updated.");
146 }
147 /**
148 * Asks the user to select a string.
149 * @param prompt the prompt to display
150 * @param options the options from which the user can choose
151 * @return the option that the user chose
152 */
153 public static String select(String prompt, List<String>
options)
154 {
155 while (true)
156 {
157 System.out.println(prompt);
158 for (int i = 0; i < options.size(); i++)
159 System.out.printf("%2d) %s%n", i + 1,
options.get(i));
160 int sel = in.nextInt();
161 if (sel > 0 && sel <= options.size())
162 return options.get(sel - 1);
163 }
164 }
165
166 /**
167 * Gets a connection from the properties specified in the
file database.properties.
168 * @return the database connection
169 */
170 public static Connection getConnection() throws SQLException,
IOException
171 {
```

```
172 var props = new Properties();
173 try (Reader in = Files.newBufferedReader(
174 Path.of("database.properties"),
175 StandardCharsets.UTF_8))
176 {
177 props.load(in);
178 }
179 String drivers = props.getProperty("jdbc.drivers");
180 if (drivers != null) System.setProperty("jdbc.drivers",
181 drivers);
182 String url = props.getProperty("jdbc.url");
183 String username = props.getProperty("jdbc.username");
184 String password = props.getProperty("jdbc.password");
185
186 return DriverManager.getConnection(url, username,
187 password);
187 }
188 }
```

---

### ***java.sql.Connection 1.1***

- `PreparedStatement prepareStatement(String sql)`  
returns a `PreparedStatement` object containing the precompiled statement. The string `sql` contains a SQL statement with one or more parameter placeholders denoted by `?` characters.

### ***java.sql.PreparedStatement 1.1***

- `void setXxx(int n, Xxx x)`  
(`Xxx` is a type such as `int`, `double`, `String`, `Date`, etc.)

- sets the value of the nth parameter to x.
- void clearParameters ()  
clears all current parameters in the prepared statement.
- ResultSet executeQuery ()  
executes a prepared SQL query and returns a ResultSet object.
- int executeUpdate ()  
executes the prepared SQL INSERT, UPDATE, or DELETE statement represented by the PreparedStatement object. Returns the number of rows affected, or 0 for DDL statements such as CREATE TABLE.

## 5.5.2 Reading and Writing LOBs

In addition to numbers, strings, and dates, many databases can store *large objects* (LOBs) such as images or other data. In SQL, binary large objects are called BLOBS, and character large objects are called CLOBs.

To read a LOB, execute a SELECT statement and call the getBlob or getClob method on the ResultSet. You will get an object of type Blob or Clob. To get the binary data from a Blob, call the getBytes or getBinaryStream. For example, if you have a table with book cover images, you can retrieve an image like this:

[Click here to view code image](#)

```

PreparedStatement stat = conn.prepareStatement("SELECT Cover FROM
BookCovers WHERE ISBN=?");
. . .
stat.setInt(1, isbn);
try (ResultSet result = stat.executeQuery())
{
 if (result.next())
 {
 Blob coverBlob = result.getBlob(1);
 }
}

```

```
 Image coverImage =
 ImageIO.read(coverBlob.getBinaryStream());
 }
}
```

Similarly, if you retrieve a `Clob` object, you can get character data by calling the `getSubString` or `getCharacterStream` method.

To place a LOB into a database, call `createBlob` or `createClob` on your `Connection` object, get an output stream or writer to the LOB, write the data, and store the object in the database. For example, here is how you store an image:

[Click here to view code image](#)

```
Blob coverBlob = connection.createBlob();
int offset = 0;
OutputStream out = coverBlob.setBinaryStream(offset);
ImageIO.write(coverImage, "PNG", out);
PreparedStatement stat = conn.prepareStatement("INSERT INTO Cover
VALUES (?, ?)");
stat.set(1, isbn);
stat.set(2, coverBlob);
stat.executeUpdate();
```

### ***java.sql.ResultSet* 1.1**

- `Blob getBlob(int columnIndex)` 1.2
- `Blob getBlob(String columnLabel)` 1.2
- `Clob getBlob(int columnIndex)` 1.2
- `Clob getBlob(String columnLabel)` 1.2

get the BLOB or CLOB at the given column.

### ***java.sql.Blob* 1.2**

- `long length()`  
gets the length of this BLOB.
- `byte[] getBytes(long startPosition, long length)`  
gets the data in the given range from this BLOB.
- `InputStream getBinaryStream()`
- `InputStream getBinaryStream(long startPosition, long length)`  
return a stream to read the data from this BLOB or from the given range.
- `OutputStream setBinaryStream(long startPosition)` **1.4**  
returns an output stream for writing into this BLOB, starting at the given position.

#### ***java.sql.Clob 1.4***

- `long length()`  
gets the number of characters of this CLOB.
- `String getSubString(long startPosition, long length)`  
gets the characters in the given range from this CLOB.
- `Reader getCharacterStream()`
- `Reader getCharacterStream(long startPosition, long length)`  
return a reader (not a stream) to read the characters from this CLOB or from the given range.

- `Writer setCharacterStream(long startPosition)` 1.4  
returns a writer (not a stream) for writing into this CLOB, starting at the given position.

### ***java.sql.Connection*** 1.1

- `Blob createBlob()` 6
- `Clob createClob()` 6  
create an empty BLOB or CLOB.

### **5.5.3 SQL Escapes**

The “escape” syntax features are commonly supported by databases but use database-specific syntax variations. It is the job of the JDBC driver to translate the escape syntax to the syntax of a particular database.

Escapes are provided for the following features:

- Date and time literals
- Calling scalar functions
- Calling stored procedures
- Outer joins
- The escape character in `LIKE` clauses

Date and time literals vary widely among databases. To embed a date or time literal, specify the value in the ISO 8601 format ([www.cl.cam.ac.uk/~mgk25/iso-time.html](http://www.cl.cam.ac.uk/~mgk25/iso-time.html)). The driver will then translate it into the native format. Use `d`, `t`, `ts` for `DATE`, `TIME`, or `TIMESTAMP` values:

```
{d '2008-01-24'}
{t '23:59:59'}
{ts '2008-01-24 23:59:59.999'}
```

A *scalar function* is a function that returns a single value. Many functions are widely available in databases, but with varying names. The JDBC specification provides standard names and translates them into the database-specific names. To call a function, embed the standard function name and arguments like this:

```
{fn left(?, 20)}
{fn user()}
```

You can find a complete list of supported function names in the JDBC specification.

An *outer join* of two tables does not require that the rows of each table match according to the join condition. For example, the query

[Click here to view code image](#)

```
SELECT * FROM {oj Books LEFT OUTER JOIN Publishers
ON Books.Publisher_Id = Publisher.Publisher_Id}
```

contains books for which Publisher\_Id has no match in the Publishers table, with NULL values to indicate that no match exists. You would need a RIGHT OUTER JOIN to include publishers without matching books, or a FULL OUTER JOIN to return both. The escape syntax is needed because not all databases use a standard notation for these joins.

Finally, the \_ and % characters have special meanings in a LIKE clause—to match a single character or a sequence of characters. There is no standard way to use them literally. If you want to match all strings containing a \_, use this construct:

```
. . . WHERE ? LIKE %!_% {escape '!'}
```

Here we define ! as the escape character. The combination !\_ denotes a literal underscore.

A *stored procedure* is a procedure that executes in the database, written in a database-specific language. To invoke a stored procedure, use the call escape. You need not supply parentheses if the procedure has no parameters. Use = to capture a return value:

```
{call PROC1(?, ?)}
{call PROC2}
{call ? = PROC3(?)}
```

You need to use the `CallableStatement` interface to execute a stored procedure. Set all input parameters and specify the types of any outputs.

[Click here to view code image](#)

```
CallableStatement stat = conn.prepareCall("{call PROC4(?, ?)}")
stat.setInt(1, id);
stat.registerOutParameter(2, java.sql.Types.VARCHAR);
stat.execute();
String name = stat.getString(2);
```

#### 5.5.4 Multiple Results

It is possible for a query to return multiple results. This can happen when executing a stored procedure, or with databases that also allow submission of multiple `SELECT` statements in a single query. Here is how you retrieve all result sets:

1. Use the `execute` method to execute the SQL statement.
2. Retrieve the first result or update count.
3. Repeatedly call the `getMoreResults` method to move on to the next result set.
4. Finish when there are no more result sets or update counts.

The `execute` and `getMoreResults` methods return `true` if the next item in the chain is a result set. The `getUpdateCount` method returns `-1` if the next item in the chain is not an update count.

The following loop traverses all results:

[Click here to view code image](#)

```
boolean isResult = stat.execute(command);
boolean done = false;
while (!done)
```

```

{
 if (isResult)
 {
 ResultSet result = stat.getResultSet();
 do something with result
 }
 else
 {
 int updateCount = stat.getUpdateCount();
 if (updateCount >= 0)
 do something with updateCount
 else
 done = true;
 }
 if (!done) isResult = stat.getMoreResults();
}

```

### ***java.sql.Statement*** 1.1

- boolean getMoreResults()
- boolean getMoreResults(int current) **6**

get the next result for this statement. The `current` parameter is one of `CLOSE_CURRENT_RESULT` (default), `KEEP_CURRENT_RESULT`, or `CLOSE_ALL_RESULTS`. Return `true` if the next result exists and is a result set.

## 5.5.5 Retrieving Autogenerated Keys

Most databases support some mechanism for autonumbering rows in a database. Unfortunately, the mechanisms differ widely among vendors. These automatic numbers are often used as primary keys. Although JDBC doesn't offer a vendor-independent solution for generating keys, it does provide an efficient way of retrieving them. When you insert a new row into a table and a key is automatically generated, you can retrieve it with the following code:

[Click here to view code image](#)

```
stat.executeUpdate(insertStatement,
Statement.RETURN_GENERATED_KEYS);
ResultSet rs = stat.getGeneratedKeys();
if (rs.next())
{
 int key = rs.getInt(1);
 . . .
}
```

### ***java.sql.Statement* 1.1**

- boolean execute(String statement, int autogenerated) 1.4
- int executeUpdate(String statement, int autogenerated) 1.4

execute the given SQL statement, as previously described. If autogenerated is set to Statement.RETURN\_GENERATED\_KEYS and the statement is an INSERT statement, the first column contains the autogenerated key.

## **5.6 Scrollable and Updatable Result Sets**

As you have seen, the next method of the ResultSet interface iterates over the rows in a result set. That is certainly adequate for a program that needs to analyze the data. However, consider a visual data display that shows a table or query results (such as [Figure 5.4](#) on p. 298). You usually want the user to be able to move both forward and backward in the result set. In a *scrollable* result, you can move forward and backward through a result set and even jump to any position.

Furthermore, once users see the contents of a result set displayed, they may be tempted to edit it. In an *updatable* result set, you can programmatically update

entries so that the database is automatically updated. We discuss these capabilities in the following sections.

### 5.6.1 Scrollable Result Sets

By default, result sets are not scrollable or updatable. To obtain scrollable result sets from your queries, you must obtain a different Statement object with the method

[Click here to view code image](#)

```
Statement stat = conn.createStatement(type, concurrency);
```

For a prepared statement, use the call

[Click here to view code image](#)

```
PreparedStatement stat = conn.prepareStatement(command, type,
concurrency);
```

The possible values of `type` and `concurrency` are listed in [Tables 5.6](#) and [5.7](#). You have the following choices:

**Table 5.6** ResultSet Type Values

Value	Explanation
<code>TYPE_FORWARD_ONLY</code>	The result set is not scrollable (default).
<code>TYPE_SCROLL_INSENSITIVE</code>	The result set is scrollable but not sensitive to database changes.
<code>TYPE_SCROLL_SENSITIVE</code>	The result set is scrollable and sensitive to database changes.

**Table 5.7** ResultSet Concurrency Values

Value	Explanation
<code>CONCUR_READ_ONLY</code>	The result set cannot be used to update the database (default).

Value	Explanation
CONCUR_UPDATABLE BLE	The result set can be used to update the database.

- Do you want the result set to be scrollable? If not, use `ResultSet.TYPE_FORWARD_ONLY`.
- If the result set is scrollable, do you want it to reflect changes in the database that occurred after the query that yielded it? (In our discussion, we assume the `ResultSet.TYPE_SCROLL_INSENSITIVE` setting for scrollable result sets. This assumes that the result set does not “sense” database changes that occurred after execution of the query.)
- Do you want to be able to update the database by editing the result set? (See the next section for details.)

For example, if you simply want to be able to scroll through a result set but don’t want to edit its data, use

[Click here to view code image](#)

```
Statement stat = conn.createStatement(
 ResultSet.TYPE_SCROLL_INSENSITIVE, ResultSet.CONCUR_READ_ONLY);
```

All result sets that are returned by calls

[Click here to view code image](#)

```
ResultSet rs = stat.executeQuery(query);
```

are now scrollable. A scrollable result set has a *cursor* that indicates the current position.



## Note

Not all database drivers support scrollable or updatable result sets. (The `supportsResultSetType` and `supportsResultSetConcurrency` methods of the `DatabaseMetaData` interface will tell you which types and concurrency modes are supported by a particular database using a

particular driver.) Even if a database supports all result set modes, a particular query might not be able to yield a result set with all the properties that you requested. (For example, the result set of a complex query might not be updatable.) In that case, the `executeQuery` method returns a `ResultSet` of lesser capabilities and adds a `SQLWarning` to the connection object. ([Section 5.4.3, “Analyzing SQL Exceptions,”](#) on p. 312 shows how to retrieve the warning.) Alternatively, you can use the `getType` and `getConcurrency` methods of the `ResultSet` interface to find out what mode a result set actually has. If you do not check the result set capabilities and issue an unsupported operation, such as `previous` on a result set that is not scrollable, the operation will throw a `SQLException`.

---

Scrolling is very simple. Use

```
if (rs.previous()) . . .;
```

to scroll backward. The method returns `true` if the cursor is positioned on an actual row, or `false` if it is now positioned before the first row.

You can move the cursor backward or forward by any number of rows with the call

```
rs.relative(n);
```

If  $n$  is positive, the cursor moves forward. If  $n$  is negative, it moves backward. If  $n$  is zero, the call has no effect. If you attempt to move the cursor outside the current set of rows, it is set to point either after the last row or before the first row, depending on the sign of  $n$ . Then, the method returns `false` and the cursor does not move. The method returns `true` if the cursor is positioned on an actual row.

Alternatively, you can set the cursor to a particular row number:

```
rs.absolute(n);
```

To get the current row number, call

```
int currentRow = rs.getRow();
```

The first row in the result set has number 1. If the return value is 0, the cursor is not currently on a row—it is either before the first row or after the last row.

The convenience methods `first`, `last`, `beforeFirst`, and `afterLast` move the cursor to the first, to the last, before the first, or after the last position.

Finally, the methods `isFirst`, `isLast`, `isBeforeFirst`, and `isAfterLast` test whether the cursor is at one of these special positions.

Using a scrollable result set is very simple. The hard work of caching the query data is carried out behind the scenes by the database driver.

## 5.6.2 Updatable Result Sets

If you want to edit the data in the result set and have the changes automatically reflected in the database, create an updatable result set. Updatable result sets don't have to be scrollable, but if you present data to a user for editing, you usually want to allow scrolling as well.

To obtain updatable result sets, create a statement as follows:

[Click here to view code image](#)

```
Statement stat = conn.createStatement(
 ResultSet.TYPE_SCROLL_INSENSITIVE, ResultSet.CONCUR_UPDATABLE);
```

The result sets returned by a call to `executeQuery` are then updatable.

---



### Note

Not all queries return updatable result sets. If your query is a join that involves multiple tables, the result might not be updatable. However, if your query involves only a single table or if it joins multiple tables by their primary keys, you should expect the result set to be updatable. Call the `getConcurrency` method of the `ResultSet` interface to find out for sure.

---

For example, suppose you want to raise the prices of some books, but you don't have a simple criterion for issuing an UPDATE statement. Then, you can iterate through all books and update prices based on arbitrary conditions.

[Click here to view code image](#)

```
String query = "SELECT * FROM Books";
ResultSet rs = stat.executeQuery(query);
while (rs.next())
{
 if (...)
 {
 double increase = ...;
 double price = rs.getDouble("Price");
 rs.updateDouble("Price", price + increase);
 rs.updateRow(); // make sure to call updateRow after
updating fields
 }
}
```

There are updateXxx methods for all data types that correspond to SQL types, such as updateDouble, updateString, and so on; specify the name or the number of the column (as with the getXxx methods), then the new value for the field.

---



### Note

If you use the updateXxx method whose first parameter is the column number, be aware that this is the column number in the *result set*. It could well be different from the column number in the database.

---

The updateXxx method changes only the row values, not the database. When you are done with the field updates in a row, you must call the updateRow method. That method sends all updates in the current row to the database. If you move the cursor to another row without calling updateRow,

this row's updates are discarded from the row set and never communicated to the database. You can also call the `cancelRowUpdates` method to cancel the updates to the current row.

The preceding example shows how to modify an existing row. If you want to add a new row to the database, first use the `moveToInsertRow` method to move the cursor to a special position, called the *insert row*. Then, build up a new row in the insert row position by issuing `updateXxx` instructions. When you are done, call the `insertRow` method to deliver the new row to the database. When you are done inserting, call `moveToCurrentRow` to move the cursor back to the position before the call to `moveToInsertRow`. Here is an example:

[Click here to view code image](#)

```
rs.moveToInsertRow();
rs.updateString("Title", title);
rs.updateString("ISBN", isbn);
rs.updateString("Publisher_Id", pubid);
rs.updateDouble("Price", price);
rs.insertRow();
rs.moveToCurrentRow();
```

Note that you cannot influence *where* the new data is added in the result set or the database.

If you don't specify a column value in the insert row, it is set to a SQL NULL. However, if the column has a NOT NULL constraint, an exception is thrown and the row is not inserted.

Finally, you can delete the row under the cursor:

```
rs.deleteRow();
```

The `deleteRow` method immediately removes the row from both the result set and the database.

The `updateRow`, `insertRow`, and `deleteRow` methods of the `ResultSet` interface give you the same power as executing UPDATE, INSERT, and DELETE SQL statements. However, Java programmers might

find it more natural to manipulate the database contents through result sets than by constructing SQL statements.

---



## Caution

If you are not careful, you can write staggeringly inefficient code with updatable result sets. It is *much* more efficient to execute an UPDATE statement than to make a query and iterate through the result, changing data along the way. Updatable result sets make sense for interactive programs in which a user can make arbitrary changes, but for most programmatic changes, a SQL UPDATE is more appropriate.

---



## Note

JDBC 2 delivered further enhancements to result sets, such as the capability to update a result set with the most recent data if the data have been modified by another concurrent database connection.

JDBC 3 added yet another refinement, specifying the behavior of result sets when a transaction is committed. However, these advanced features are outside the scope of this introductory chapter. We refer you to the *JDBC™ API Tutorial and Reference, Third Edition*, by Maydene Fisher, Jon Ellis, and Jonathan Bruce (Addison-Wesley, 2003) and the JDBC specification for more information.

---

### `java.sql.Connection` 1.1

- Statement `createStatement(int type, int concurrency)` 1.2
- PreparedStatement `prepareStatement(String command, int type, int concurrency)` 1.2

create a statement or prepared statement that yields result sets with the given type and concurrency. The type parameter is of the constants

`TYPE_FORWARD_ONLY`, `TYPE_SCROLL_INSENSITIVE`, or `TYPE_SCROLL_SENSITIVE`, and `concurrency` is one of the constants `CONCUR_READ_ONLY` or `CONCUR_UPDATABLE`, all defined in the `ResultSet` interface.

### **`java.sql.ResultSet` 1.1**

- `int getType()` 1.2  
returns the type of this result set—one of `TYPE_FORWARD_ONLY`, `TYPE_SCROLL_INSENSITIVE`, or `TYPE_SCROLL_SENSITIVE`.
- `int getConcurrency()` 1.2  
returns the concurrency setting of this result set—one of `CONCUR_READ_ONLY` or `CONCUR_UPDATABLE`.
- `boolean previous()` 1.2  
moves the cursor to the preceding row. Returns `true` if the cursor is positioned on a row, or `false` if the cursor is positioned before the first row.
- `int getRow()` 1.2  
gets the number of the current row. Rows are numbered starting with 1.
- `boolean absolute(int r)` 1.2  
moves the cursor to row `r`. Returns `true` if the cursor is positioned on a row.
- `boolean relative(int d)` 1.2  
moves the cursor by `d` rows. If `d` is negative, the cursor is moved backward. Returns `true` if the cursor is positioned on a row.
- `boolean first()` 1.2
- `boolean last()` 1.2

move the cursor to the first or last row. Return true if the cursor is positioned on a row.

- `void beforeFirst() 1.2`
- `void afterLast() 1.2`

move the cursor before the first or after the last row.

- `boolean isFirst() 1.2`
- `boolean isLast() 1.2`

test whether the cursor is at the first or last row.

- `boolean isBeforeFirst() 1.2`
- `boolean isAfterLast() 1.2`

test whether the cursor is before the first or after the last row.

- `void moveToInsertRow() 1.2`

moves the cursor to the insert row. The insert row is a special row for inserting new data with the `updateXxx` and `insertRow` methods.

- `void moveToCurrentRow() 1.2`

moves the cursor back from the insert row to the row that it occupied when the `moveToInsertRow` method was called.

- `void insertRow() 1.2`

inserts the contents of the insert row into the database and the result set.

- `void deleteRow() 1.2`

deletes the current row from the database and the result set.

- `void updateXxx(int column, Xxx data) 1.2`
- `void updateXxx(String columnName, Xxx data) 1.2`

(`Xxx` is a type such as `int`, `double`, `String`, `Date`, etc.)

update a field in the current row of the result set.

- `void updateRow()` 1.2  
sends the current row updates to the database.
- `void cancelRowUpdates()` 1.2  
cancels the current row updates.

### ***java.sql.DatabaseMetaData*** 1.1

- `boolean supportsResultSetType(int type)` 1.2  
returns `true` if the database can support result sets of the given type; `type` is one of the constants `TYPE_FORWARD_ONLY`, `TYPE_SCROLL_INSENSITIVE`, or `TYPE_SCROLL_SENSITIVE` of the `ResultSet` interface.
- `boolean supportsResultSetConcurrency(int type, int concurrency)` 1.2  
returns `true` if the database can support result sets of the given combination of type and concurrency. The `type` parameter is one of the constants `TYPE_FORWARD_ONLY`, `TYPE_SCROLL_INSENSITIVE`, or `TYPE_SCROLL_SENSITIVE`, and `concurrency` is one of the constants `CONCUR_READ_ONLY` or `CONCUR_UPDATABLE`, all defined in the `ResultSet` interface.

## 5.7 Row Sets

Scorable result sets are powerful, but they have a major drawback. You need to keep the database connection open during the entire user interaction. However, a user can walk away from the computer for a long time, leaving the connection occupied. That is not good—database connections are scarce resources. In this situation, use a *row set*. The `RowSet` interface extends the

`ResultSet` interface, but row sets don't have to be tied to a database connection.

Row sets are also suitable if you need to move a query result to a different tier of a complex application, or to another device such as a cell phone. You would never want to move a result set—its data structures can be huge, and it is tethered to the database connection.

### 5.7.1 Constructing Row Sets

The `javax.sql.rowset` package provides the following interfaces that extend the `RowSet` interface:

- A `CachedRowSet` allows disconnected operation. We will discuss cached row sets in the following section.
- A `WebRowSet` is a cached row set that can be saved to an XML file. The XML file can be moved to another tier of a web application where it is opened by another `WebRowSet` object.
- The `FilteredRowSet` and `JoinRowSet` interfaces support lightweight operations on row sets that are equivalent to SQL `SELECT` and `JOIN` operations. These operations are carried out on the data stored in row sets, without having to make a database connection.
- A `JdbcRowSet` is a thin wrapper around a `ResultSet`. It adds useful methods from the `RowSet` interface.

To obtain a cached row set, call:

[Click here to view code image](#)

```
RowSetFactory factory = RowSetProvider.newFactory();
CachedRowSet crs = factory.createCachedRowSet();
```

There are similar methods for obtaining the other row set types.

### 5.7.2 Cached Row Sets

A cached row set contains all data from a result set. Since `CachedRowSet` is a subinterface of the `ResultSet` interface, you can use a cached row set exactly as you would use a result set. Cached row sets confer an important

benefit: You can close the connection and still use the row set. As you will see in our sample program in [Listing 5.4](#), this greatly simplifies the implementation of interactive applications. Each user command simply opens the database connection, issues a query, puts the result in a cached row set, and then closes the database connection.

It is even possible to modify the data in a cached row set. Of course, the modifications are not immediately reflected in the database; you need to make an explicit request to accept the accumulated changes. The CachedRowSet then reconnects to the database and issues SQL statements to write the accumulated changes.

You can populate a CachedRowSet from a result set:

[Click here to view code image](#)

```
ResultSet result = . . .;
RowSetFactory factory = RowSetProvider.newFactory();
CachedRowSet crs = factory.createCachedRowSet();
crs.populate(result);
conn.close(); // now OK to close the database connection
```

Alternatively, you can let the CachedRowSet object establish a connection automatically. Set up the database parameters:

[Click here to view code image](#)

```
crs.setURL("jdbc:derby://localhost:1527/COREJAVA");
crs.setUsername("dbuser");
crs.setPassword("secret");
```

Then set the query statement and any parameters:

[Click here to view code image](#)

```
crs.setCommand("SELECT * FROM Books WHERE Publisher_ID = ?");
crs.setString(1, publisherId);
```

Finally, populate the row set with the query result:

```
crs.execute();
```

This call establishes a database connection, issues the query, populates the row set, and disconnects.

If your query result is very large, you would not want to put it into the row set in its entirety. After all, your users will probably only look at a few rows. In that case, specify a page size:

```
CachedRowSet crs = . . .;
crs.setCommand(command);
crs.setPageSize(20);
. . .
crs.execute();
```

Now you will only get 20 rows. To get the next batch of rows, call

```
crs.nextPage();
```

You can inspect and modify the row set with the same methods you use for result sets. If you modified the row set contents, you must write it back to the database by calling

```
crs.acceptChanges(conn);
```

or

```
crs.acceptChanges();
```

The second call works only if you configured the row set with the information required to connect to a database (such as the URL, user name, and password).

In [Section 5.6.2, “Updatable Result Sets,”](#) on p. 334, you saw that not all result sets are updatable. Similarly, a row set that contains the result of a complex query will not be able to write its changes back to the database. You should be safe if your row set contains data from a single table.



## Caution

If you populated the row set from a result set, the row set does not know the name of the table to update. You need to call `setTableName` to set the table name.

---

Another complexity arises if the data in the database have changed after you populated the row set. This is clearly a sign of trouble that could lead to inconsistent data. The reference implementation checks whether the original row set values (that is, the values before editing) are identical to the current values in the database. If so, they are replaced with the edited values; otherwise, a `SyncProviderException` is thrown and none of the changes are written. Other implementations may use other strategies for synchronization.

#### ***javax.sql.RowSet 1.4***

- `String getURL()`
- `void setURL(String url)`  
get or set the database URL.
- `String getUsername()`
- `void setUsername(String username)`  
get or set the user name for connecting to the database.
- `String getPassword()`
- `void setPassword(String password)`  
get or set the password for connecting to the database.
- `String getCommand()`
- `void setCommand(String command)`  
get or set the command that is executed to populate this row set.
- `void execute()`

populates this row set by issuing the statement set with `setCommand`. For the driver manager to obtain a connection, the URL, user name, and password must be set.

## ***javax.sql.rowset.CachedRowSet 5.0***

- `void execute(Connection conn)`

populates this row set by issuing the statement set with `setCommand`. This method uses the given connection *and closes it*.

- `void populate(ResultSet result)`

populates this cached row set with the data from the given result set.

- `String getTableName()`

- `void setTableName(String tableName)`

get or set the name of the table from which this cached row set was populated.

- `int getPageSize()`

- `void setPageSize(int size)`

get or set the page size.

- `boolean nextPage()`

- `boolean previousPage()`

load the next or previous page of rows. Return `true` if there is a next or previous page.

- `void acceptChanges()`

- `void acceptChanges(Connection conn)`

reconnect to the database and write the changes that are the result of editing the row set. May throw a `SyncProviderException` if the data cannot be written back because the database data have changed.

### **`javax.sql.rowset.RowSetProvider`** 7

- `static RowSetFactory newFactory()`  
creates a row set factory.

### **`javax.sql.rowset.RowSetFactory`** 7

- `CachedRowSet createCachedRowSet()`
  - `FilteredRowSet createFilteredRowSet()`
  - `JdbcRowSet createJdbcRowSet()`
  - `JoinRowSet createJoinRowSet()`
  - `WebRowSet createWebRowSet()`
- create a row set of the specified type.

## 5.8 Metadata

In the preceding sections, you saw how to populate, query, and update database tables. However, JDBC can give you additional information about the *structure* of a database and its tables. For example, you can get a list of the tables in a particular database or the column names and types of a table. This information is not useful when you are implementing a business application with a predefined database. After all, if you design the tables, you know their structure. Structural information is, however, extremely useful for programmers who write tools that work with any database.

In SQL, data that describe the database or one of its parts are called *metadata* (to distinguish them from the actual data stored in the database). You can get three kinds of metadata: about a database, about a result set, and about parameters of prepared statements.

To find out more about the database, request an object of type DatabaseMetaData from the database connection.

[Click here to view code image](#)

```
DatabaseMetaData meta = conn.getMetaData();
```

Now you are ready to get some metadata. For example, the call

[Click here to view code image](#)

```
ResultSet mrs = meta.getTables(null, null, null, new String[] {
 "TABLE" });
```

returns a result set that contains information about all tables in the database. (See the API note at the end of this section for other parameters to this method.)

Each row in the result set contains information about a table in the database. The third column is the name of the table. (Again, see the API note for the other columns.) The following loop gathers all table names:

[Click here to view code image](#)

```
while (mrs.next())
 tableNames.addItem(mrs.getString(3));
```

There is a second important use for database metadata. Databases are complex, and the SQL standard leaves plenty of room for variability. Well over a hundred methods in the DatabaseMetaData interface can inquire about the database, including calls with such exotic names as

[Click here to view code image](#)

```
meta.supportsCatalogsInPrivilegeDefinitions()
```

and

```
meta.nullPlusNonNullIsNull()
```

Clearly, these are geared toward advanced users with special needs—in particular, those who need to write highly portable code that works with

multiple databases.


The DatabaseMetaData interface gives data about the database. A second metadata interface, ResultSetMetaData, reports information about a result set. Whenever you have a result set from a query, you can inquire about the number of columns and each column's name, type, and field width. Here is a typical loop:

[Click here to view code image](#)

```
ResultSet rs = stat.executeQuery("SELECT * FROM " + tableName);
ResultSetMetaData meta = rs.getMetaData();
for (int i = 1; i <= meta.getColumnCount(); i++)
{
 String columnName = meta.getColumnName(i);
 int columnWidth = meta.getColumnDisplaySize(i);
 . . .
}
```

In this section, we will show you how to write such a simple tool. The program in [Listing 5.4](#) uses metadata to let you browse all tables in a database. The program also illustrates the use of a cached row set.

The combo box on top displays all tables in the database. Select one of them, and the center of the frame is filled with the field names of that table and the values of the first row, as shown in [Figure 5.6](#). Click Next and Previous to scroll through the rows in the table. You can also delete a row and edit the row values. Click the Save button to save the changes to the database.



**Figure 5.6** The ViewDB application



## Note

Many databases come with much more sophisticated tools for viewing and editing tables. If your database doesn't, check out DBeaver (<https://dbeaver.io>) or SQuirreL (<http://squirrel-sql.sourceforge.net>). These programs can view the tables in any JDBC database. Our example program is not intended as a replacement for these tools—it just shows you how to implement a tool for working with arbitrary tables.

---

### **Listing 5.4** view/ViewDB.java

[Click here to view code image](#)

```
1 package view;
2
3 import java.awt.*;
4 import java.awt.event.*;
5 import java.io.*;
6 import java.nio.charset.*;
7 import java.nio.file.*;
8 import java.sql.*;
9 import java.util.*;
10
11 import javax.sql.*;
12 import javax.sql.rowset.*;
13 import javax.swing.*;
14
15 /**
16 * This program uses metadata to display arbitrary tables in a
17 * database.
18 * @version 1.35 2021-06-17
19 * @author Cay Horstmann
20 */
21 public class ViewDB
```

```
21 {
22 public static void main(String[] args)
23 {
24 EventQueue.invokeLater(() ->
25 {
26 var frame = new ViewDBFrame();
27 frame.setTitle("ViewDB");
28
29 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
30 frame.setVisible(true);
31 });
32 }
33
34 /**
35 * The frame that holds the data panel and the navigation
36 * buttons.
37
38 class ViewDBFrame extends JFrame
39 {
40 private JButton previousButton;
41 private JButton nextButton;
42 private JButton deleteButton;
43 private JButton saveButton;
44 private JPanel dataPanel;
45 private Component scrollPane;
46 private JComboBox<String> tableNames;
47 private Properties props;
48 private CachedRowSet crs;
49 private Connection conn;
50
51 public ViewDBFrame()
52 {
53 tableNames = new JComboBox<String>();
54
55 try
56 {
57 readDatabaseProperties();
58 conn = getConnection();
```

```
58 DatabaseMetaData meta = conn.getMetaData();
59 try (ResultSet mrs = meta.getTables(null, null, null,
60 new String[] { "TABLE" })) {
61 while (mrs.next())
62 tableNames.addItem(mrs.getString(3));
63 }
64 }
65 catch (SQLException e)
66 {
67 for (Throwable t : e)
68 t.printStackTrace();
69 }
70 catch (IOException e)
71 {
72 ex.printStackTrace();
73 }
74
75 tableNames.addActionListener(
76 event -> showTable((String)
tableNames.getSelectedItem(), conn));
77 add(tableNames, BorderLayout.NORTH);
78 addWindowListener(new WindowAdapter()
79 {
80 public void windowClosing(WindowEvent event)
81 {
82 try
83 {
84 if (conn != null) conn.close();
85 }86 catch (SQLException e)
87 {
88 for (Throwable t : e)
89 t.printStackTrace();
90 }
91 }
92 });
93
94 var buttonPanel = new JPanel();
95 add(buttonPanel, BorderLayout.SOUTH);
```

```
96
97 previousButton = new JButton("Previous");
98 previousButton.addActionListener(event ->
99 showPreviousRow());
100 buttonPanel.add(previousButton);
101
102 nextButton = new JButton("Next");
103 nextButton.addActionListener(event -> showNextRow());
104 buttonPanel.add(nextButton);
105
106 deleteButton = new JButton("Delete");
107 deleteButton.addActionListener(event -> deleteRow());
108 buttonPanel.add(deleteButton);
109
110 saveButton = new JButton("Save");
111 saveButton.addActionListener(event -> saveChanges());
112 if (tableNames getItemCount() > 0)
113 showTable(tableNames getItemAt(0), conn);
114 }
115
116 /**
117 * Prepares the text fields for showing a new table, and
118 * shows the first row.
119 * @param tableName the name of the table to display
120 * @param conn the database connection
121 */
122 public void showTable(String tableName, Connection conn)
123 {
124 try (Statement stat = conn.createStatement();
125 ResultSet result = stat.executeQuery("SELECT * FROM
126 " + tableName))
127 {
128 // get result set
129
130 // copy into cached row set
131 RowSetFactory factory = RowSetProvider.newFactory();
132 crs = factory.createCachedRowSet();
133 crs.setTableName(tableName);
```

```
132 crs.populate(result);
133
134 if (scrollPane != null) remove(scrollPane);135
135 dataPanel = new DataPanel(crs);
136 scrollPane = new JScrollPane(dataPanel);
137 add(scrollPane, BorderLayout.CENTER);
138 pack();
139 showNextRow();
140 }
141 catch (SQLException e)
142 {
143 for (Throwable t : e)
144 t.printStackTrace();
145 }
146 }
147
148 /**
149 * Moves to the previous table row.
150 */
151 public void showPreviousRow()
152 {
153 try
154 {
155 if (crs == null || crs.isFirst()) return;
156 crs.previous();
157 dataPanel.showRow(crs);
158 }
159 catch (SQLException e)
160 {
161 for (Throwable t : e)
162 t.printStackTrace();
163 }
164 }
165
166 /**
167 * Moves to the next table row.
168 */
169 public void showNextRow()
170 {
```

```
171 try
172 {
173 if (crs == null || crs.isLast()) return;
174 crs.next();
175 dataPanel.showRow(crs);
176 }
177 catch (SQLException e)
178 {
179 for (Throwable t : e)
180 t.printStackTrace();
181 }182
183
184 /**
185 * Deletes current table row.
186 */
187 public void deleteRow()
188 {
189 if (crs == null) return;
190 new SwingWorker<Void, Void>()
191 {
192 public Void doInBackground() throws SQLException
193 {
194 crs.deleteRow();
195 crs.acceptChanges(conn);
196 if (crs.isAfterLast())
197 if (!crs.last()) crs = null;
198 return null;
199 }
200 public void done()
201 {
202 dataPanel.showRow(crs);
203 }
204 }.execute();
205 }
206 /**
207 * Saves all changes.
208 */
209 public void saveChanges()
210 {
```

```
211 if (crs == null) return;
212 new SwingWorker<Void, Void>()
213 {
214 public Void doInBackground() throws SQLException
215 {
216 dataPanel.setRow(crs);
217 crs.acceptChanges(conn);
218 return null;
219 }
220 }.execute();
221 }
222
223 private void readDatabaseProperties() throws IOException
224 {
225 props = new Properties();
226 try (Reader in = Files.newBufferedReader(
227 Path.of("database.properties"),
228 StandardCharsets.UTF_8))
229 {
230 props.load(in);
231 String drivers =
232 props.getProperty("jdbc.drivers");
233 if (drivers != null) System.setProperty("jdbc.drivers",
234 drivers);
235 }
236 /**
237 * Gets a connection from the properties specified in the
238 * file database.properties.
239 * @return the database connection
240 */
241 private Connection getConnection() throws SQLException
242 {
243 String url = props.getProperty("jdbc.url");
244 String username = props.getProperty("jdbc.username");
245 String password = props.getProperty("jdbc.password");
246
247 return DriverManager.getConnection(url, username,
248 password);
```

```
246 }
247 }
248
249 /**
250 * This panel displays the contents of a result set.
251 */
252 class DataPanel extends JPanel
253 {
254 private java.util.List<JTextField> fields;
255
256 /**
257 * Constructs the data panel.
258 * @param rs the result set whose contents this panel
259 * displays
260 */
261 public DataPanel(ResultSet rs) throws SQLException
262 {
263 fields = new ArrayList<>();
264 setLayout(new GridBagLayout());
265 var gbc = new GridBagConstraints();
266 gbc.gridwidth = 1;
267 gbc.gridheight = 1;
268
269 ResultSetMetaData rsmd = rs.getMetaData();
270 for (int i = 1; i <= rsmd.getColumnCount(); i++)
271 {
272 gbc.gridx = i - 1;
273
274 String columnName = rsmd.getColumnName(i);
275 gbc.gridx = 0;
276 gbc.anchor = GridBagConstraints.EAST;
277 add(new JLabel(columnName), gbc);
278 int columnWidth = rsmd getColumnDisplaySize(i);
279 var tb = new JTextField(columnWidth);
280 if
281 (!rsmd.getColumnClassName(i).equals("java.lang.String"))
282 tb.setEditable(false);
283
284 fields.add(tb);
285 }
286 }
```

```
284
285 gbc.gridx = 1;
286 gbc.anchor = GridBagConstraints.WEST;
287 add(tb, gbc);
288 }
289 }
290
291 /**
292 * Shows a database row by populating all text fields with
293 the column values.
294 */
295 public void showRow(ResultSet rs)
296 {
297 try
298 {
299 for (int i = 1; i <= fields.size(); i++)
300 {
301 String field = rs == null ? "" : rs.getString(i);
302 JTextField tb = fields.get(i - 1);
303 tb.setText(field);
304 }
305 catch (SQLException e)
306 {
307 for (Throwable t : e)
308 t.printStackTrace();
309 }
310 }
311
312 /**
313 * Updates changed data into the current row of the row set.
314 */
315 public void setRow(RowSet rs) throws SQLException
316 {
317 for (int i = 1; i <= fields.size(); i++)
318 {
319 String field = rs.getString(i);
320 JTextField tb = fields.get(i - 1);
321 if (!field.equals(tb.getText()))
```

```
322 rs.updateString(i, tb.getText());
323 }
324 rs.updateRow();
325 }
326 }
```

---

### ***java.sql.Connection*** 1.1

- `DatabaseMetaData getMetaData()`

returns the metadata for the connection as a `DatabaseMetaData` object.

### ***java.sql.DatabaseMetaData*** 1.1

- `ResultSet getTables(String catalog, String schemaPattern, String tableNamePattern, String types[])`

returns a description of all tables in a catalog that match the schema and table name patterns and the type criteria. (A *schema* describes a group of related tables and access permissions. A *catalog* describes a related group of schemas. These concepts are important for structuring large databases.)

The `catalog` and `schemaPattern` parameters can be "" to retrieve those tables without a catalog or schema, or null to return tables regardless of catalog or schema.

The `types` array contains the names of the table types to include. Typical types are TABLE, VIEW, SYSTEM TABLE, GLOBAL TEMPORARY, LOCAL TEMPORARY, ALIAS, and SYNONYM. If `types` is null, tables of all types are returned.

The result set has five columns, all of which are of type `String`.

<b>Column Name</b>	<b>Explanation</b>
1 TABLE_CAT	Table catalog (may be null)
2 TABLE_SCHEM	Table schema (may be null)
3 TABLE_NAME	Table name
4 TABLE_TYPE	Table type
5 REMARKS	Comment on the table

- `int getJDBCMajorVersion () 1.4`
- `int getJDBCMinorVersion () 1.4`

return the major or minor JDBC version numbers of the driver that established the database connection. For example, a JDBC 4.3 driver has major version number 4 and minor version number 3.

- `int getMaxConnections ()`

returns the maximum number of concurrent connections allowed to this database.

- `int getMaxStatements ()`

returns the maximum number of concurrently open statements allowed per database connection, or 0 if the number is unlimited or unknown.

### ***java.sql.ResultSet 1.1***

- `ResultSetMetaData getMetaData ()`

returns the metadata associated with the current ResultSet columns.

### ***java.sql.ResultSetMetaData 1.1***

- `int getColumnCount ()`

returns the number of columns in the current `ResultSet` object.

- `int getColumnDisplaySize(int column)`

returns the maximum width of the column specified by the index parameter.

- `String getColumnLabel(int column)`

returns the suggested title for the column.

- `String getColumnName(int column)`

returns the column name associated with the column index specified.

## 5.9 Transactions

You can group a set of statements to form a *transaction*. The transaction can be *committed* when all has gone well—or, if an error has occurred in one of them, it can be *rolled back* as if none of the statements had been issued.

The major reason for grouping statements into transactions is *database integrity*. For example, suppose we want to transfer money from one bank account to another. Then, it is important that we simultaneously debit one account and credit another. If the system fails after debiting the first account but before crediting the other account, the debit needs to be undone.

If you group update statements into a transaction, the transaction either succeeds in its entirety and can be *committed*, or it fails somewhere in the middle. In that case, you can carry out a *rollback* and the database automatically undoes the effect of all updates that occurred since the last committed transaction.

### 5.9.1 Programming Transactions with JDBC

By default, a database connection is in *autocommit mode*, and each SQL statement is committed to the database as soon as it is executed. Once a

statement is committed, you cannot roll it back. Turn off this default so you can use transactions:

```
conn.setAutoCommit(false);
```

Create a statement object in the normal way:

[Click here to view code image](#)

```
Statement stat = conn.createStatement();
```

Call `executeUpdate` any number of times:

```
stat.executeUpdate(command1);
stat.executeUpdate(command2);
stat.executeUpdate(command3);
. . .
```

If all statements have been executed without error, call the `commit` method:

```
conn.commit();
```

However, if an error occurred, call

```
conn.rollback();
```

Then, all statements since the last commit are automatically reversed. You typically issue a rollback when your transaction was interrupted by a `SQLException`.

## 5.9.2 Save Points

With some databases and drivers, you can gain finer-grained control over the rollback process by using *save points*. Creating a save point marks a point to which you can later return without having to abandon the entire transaction. For example,

[Click here to view code image](#)

```
Statement stat = conn.createStatement(); // start transaction;
rollback() goes here
stat.executeUpdate(command1);
Savepoint svpt = conn.setSavepoint(); // set savepoint;
rollback(svpt) goes here
stat.executeUpdate(command2);
if (...) conn.rollback(svpt); // undo effect of command2
...
conn.commit();
```

When you no longer need a save point, you should release it:

```
conn.releaseSavepoint(svpt);
```

### 5.9.3 Batch Updates

Suppose a program needs to execute many `INSERT` statements to populate a database table. You can improve the performance of the program by using a *batch update*. In a batch update, a sequence of statements is collected and submitted as a batch.

---



#### Note

Use the `supportsBatchUpdates` method of the `DatabaseMetaData` interface to find out if your database supports this feature.

---

The statements in a batch can be actions such as `INSERT`, `UPDATE`, or `DELETE` as well as data definition statements such as `CREATE TABLE` or `DROP TABLE`. An exception is thrown if you add a `SELECT` statement to a batch. (Conceptually, a `SELECT` statement makes no sense in a batch because it returns a result set without updating the database.)

To execute a batch, first create a `Statement` object in the usual way:

[Click here to view code image](#)

```
Statement stat = conn.createStatement();
```

Now, instead of calling `executeUpdate`, call the `addBatch` method:

[Click here to view code image](#)

```
String command = "CREATE TABLE . . ."
stat.addBatch(command);

while (. . .)
{
 command = "INSERT INTO . . . VALUES (" + . . . + ")";
 stat.addBatch(command);
}
```

Finally, submit the entire batch:

[Click here to view code image](#)

```
int[] counts = stat.executeBatch();
```

The call to `executeBatch` returns an array of the row counts for all submitted statements.

For proper error handling in batch mode, treat the batch execution as a single transaction. If a batch fails in the middle, you want to roll back to the state before the beginning of the batch.

First, turn the autocommit mode off, then collect the batch, execute it, commit it, and finally restore the original autocommit mode:

[Click here to view code image](#)

```
boolean autoCommit = conn.getAutoCommit();
conn.setAutoCommit(false);
Statement stat = conn.createStatement();
. . .
// keep calling stat.addBatch(. . .);
. . .
stat.executeBatch();
conn.commit(); conn.setAutoCommit(autoCommit);
```

## ***java.sql.Connection*** 1.1

- `boolean getAutoCommit()`
- `void setAutoCommit(boolean b)`

get or set the autocommit mode of this connection to b. If autocommit is true, all statements are committed as soon as their execution is completed.

- `void commit()`

commits all statements that were issued since the last commit.

- `void rollback()`

undoes the effect of all statements that were issued since the last commit.

- `Savepoint setSavepoint() 1.4`

- `Savepoint setSavepoint(String name) 1.4`

set an unnamed or named save point.

- `void rollback(Savepoint svpt) 1.4`

rolls back until the given save point.

- `void releaseSavepoint(Savepoint svpt) 1.4`

releases the given save point.

## ***java.sql.Savepoint*** 1.4

- `int getSavepointId()`

gets the ID of this unnamed save point, or throws a SQLException if this is a named save point.

- `String getSavepointName()`

gets the name of this save point, or throws a `SQLException` if this is an unnamed save point.

#### ***java.sql.Statement*** 1.1

- `void addBatch(String command)` 1.2

adds the command to the current batch of commands for this statement.

- `int[] executeBatch()` 1.2

- `long[] executeLargeBatch()` 8

execute all commands in the current batch. Each value in the returned array corresponds to one of the batch statements. If it is non-negative, it is a row count. If it is the value `SUCCESS_NO_INFO`, the statement succeeded, but no row count is available. If it is `EXECUTE_FAILED`, the statement failed.

#### ***java.sql.DatabaseMetaData*** 1.1

- `boolean supportsBatchUpdates()` 1.2

returns `true` if the driver supports batch updates.

### 5.9.4 Advanced SQL Types

[Table 5.8](#) lists the SQL data types supported by JDBC and their equivalents in the Java programming language.

**Table 5.8** SQL Data Types and Their Corresponding Java Types

<b>SQL Data Type</b>	<b>Java Data Type</b>
INTEGER or INT	int
SMALLINT	short
NUMERIC ( $m, n$ ) , DECIMAL ( $m, n$ ) or DEC ( $m, n$ )	java.math.BigDecimal
FLOAT ( $n$ )	double
REAL	float
DOUBLE	double
CHARACTER ( $n$ ) or CHAR ( $n$ )	String
VARCHAR ( $n$ ) , LONG VARCHAR	String
BOOLEAN	boolean
DATE	java.sql.Date
TIME	java.sql.Time
TIMESTAMP	java.sql.Timestamp
BLOB	java.sql.Blob
CLOB	java.sql.Clob
ARRAY	java.sql.Array
ROWID	java.sql.RowId
NCHAR ( $n$ ) , NVARCHAR ( $n$ ) , LONG NVARCHAR	String
NCLOB	java.sql.NClob
SQLXML	java.sql.SQLXML

A SQL ARRAY is a sequence of values. For example, in a Student table, you can have a Scores column that is an ARRAY OF INTEGER. The getArray method returns an object of the interface type java.sql.Array. That interface has methods to fetch the array values.

When you get a LOB or an array from a database, the actual contents are fetched from the database only when you request individual values. This is a useful performance enhancement, as the data can be quite voluminous.

Some databases support ROWID values that describe the location of a row so that it can be retrieved very rapidly. JDBC 4 introduced an interface `java.sql.RowId` and the methods to supply the row ID in queries and retrieve it from results.

A *national character string* (`NCHAR` and its variants) stores strings in a local character encoding and sorts them using a local sorting convention. JDBC 4 provided methods for converting between Java `String` objects and national character strings in queries and results.

Some databases can store user-defined structured types. JDBC 3 provides a mechanism for automatically mapping structured SQL types to Java objects.

Some databases provide native storage for XML data. JDBC 4 introduced a `SQLXML` interface that can mediate between the internal XML representation and the DOM Source/Result interfaces, as well as binary streams. See the API documentation for the `SQLXML` class for details.

We do not discuss these advanced SQL types any further. You can find more information on these topics in the *JDBC API Tutorial and Reference* and the JDBC specification.

## 5.10 Connection Management in Web and Enterprise Applications

The simplistic database connection setup with a `database.properties` file, as described in the preceding sections, is suitable for small test programs but won't scale for larger applications.

When a JDBC application is deployed in a web or enterprise environment, the management of database connections is integrated with the JNDI. The properties of data sources across the enterprise can be stored in a directory. Using a directory allows for centralized management of user names, passwords, database names, and JDBC URLs.

In such an environment, you can use the following code to establish a database connection:

[Click here to view code image](#)

```
var jndiContext = new InitialContext();
var source = (DataSource)
jndiContext.lookup("java:comp/env/jdbc/corejava");
Connection conn = source.getConnection();
```

Note that the `DriverManager` is no longer involved. Instead, the JNDI service locates a *data source*. A data source is an interface that allows for simple JDBC connections as well as more advanced services, such as executing distributed transactions that involve multiple databases. The `DataSource` interface is defined in the `javax.sql` standard extension package.

---



## Note

In a Java EE container, you don't even have to program the JNDI lookup. Simply use the `Resource` annotation on a `DataSource` field, and the data source reference will be set when your application is loaded:

[Click here to view code image](#)

```
@Resource(name="jdbc/corejava")
private DataSource source;
```

---

Of course, the data source needs to be configured somewhere. If you write database programs that execute in a servlet container such as Apache Tomcat or in an application server such as GlassFish, place the database configuration (including the JNDI name, JDBC URL, user name, and password) in a configuration file, or set it in an admin GUI.

Management of user names and logins is just one of the issues that require special attention. Another issue involves the cost of establishing database connections. Our sample database programs used two strategies for obtaining a database connection. The `QueryDB` program in [Listing 5.3](#) established a single database connection at the start of the program and closed it at the end of the program. The `ViewDB` program in [Listing 5.4](#) opened a new connection whenever one was needed.

However, neither of these approaches is satisfactory. Database connections are a finite resource. If a user walks away from an application for some time, the connection should not be left open. Conversely, obtaining a connection for each query and closing it afterward is very costly.

The solution is to *pool* connections. This means that database connections are not physically closed but are kept in a queue and reused. Connection pooling is an important service, and the JDBC specification provides hooks for implementors to supply it. However, the JDK itself does not provide any implementation, and database vendors don't usually include one with their JDBC drivers either. Instead, vendors of web containers and application servers supply connection pool implementations.

Using a connection pool is completely transparent to the programmer. Acquire a connection from a source of pooled connections by obtaining a data source and calling `getConnection`. When you are done using the connection, call `close`. That doesn't close the physical connection but tells the pool that you are done using it. The connection pool typically makes an effort to pool prepared statements as well.

You have now learned about the JDBC fundamentals and know enough to implement simple database applications. However, as we mentioned at the beginning of this chapter, databases are complex and quite a few advanced topics are beyond the scope of this introductory chapter. For an overview of advanced JDBC capabilities, refer to the *JDBC API Tutorial and Reference* or the JDBC specification.

In this chapter, you have learned how to work with relational databases in Java. The next chapter covers the Java 8 date and time library.

---

# Chapter 6. The Date and Time API

---

## In this chapter

- [6.1 The Time Line](#)
- [6.2 Local Dates](#)
- [6.3 Date Adjusters](#)
- [6.4 Local Time](#)
- [6.5 Zoned Time](#)
- [6.6 Formatting and Parsing](#)
- [6.7 Interoperating with Legacy Code](#)

Time flies like an arrow, and we can easily set a starting point and count forward and backward in seconds. So why is it so hard to deal with time? The problem is humans. All would be easy if we could just tell each other: “Meet me at 1523793600, and don’t be late!” But we want time to relate to daylight and the seasons. That’s where things get complicated. Java 1.0 had a `Date` class that was, in hindsight, naïve, and had most of its methods deprecated in Java 1.1 when a `Calendar` class was introduced. Its API wasn’t stellar, its instances were mutable, and it didn’t deal with issues such as leap seconds. The third time is a charm, and the `java.time` API introduced in Java 8 has remedied the flaws of the past and should serve us for quite some time. In this chapter, you will learn what makes time computations so vexing, and how the Date and Time API solves these issues.

## 6.1 The Time Line

Historically, the fundamental time unit—the second—was derived from Earth’s rotation around its axis. There are 24 hours or  $24 \times 60 \times 60 = 86400$  seconds in a full revolution, so it seems just a question of astronomical measurements to precisely define a second. Unfortunately, Earth wobbles slightly, and a more precise definition was needed. In 1967, a new precise definition of a second, matching the historical definition, was derived from an intrinsic property of atoms of caesium-133. Since then, a network of atomic clocks keeps the official time.

Ever so often, the official time keepers synchronize the absolute time with the rotation of Earth. At first, the official seconds were slightly adjusted, but starting in 1972, “leap seconds” were occasionally inserted. (In theory, a second might need to be removed once in a while, but that has not yet happened.) There is talk of changing the system again. Clearly, leap seconds are a pain, and many computer systems instead use “smoothing” where time is artificially slowed down or sped up just before the leap second, keeping 86,400 seconds per day. This works because the local time on a computer isn’t all that precise, and computers are used to synchronizing themselves with an external time service.

The Java Date and Time API specification requires that Java uses a time scale that

- Has 86,400 seconds per day
- Exactly matches the official time at noon each day
- Closely matches it elsewhere, in a precisely defined way

That gives Java the flexibility to adjust to future changes in the official time.

In Java, an `Instant` represents a point on the time line. An origin, called the *epoch*, is arbitrarily set at midnight of January 1, 1970 at the prime meridian that passes through the Greenwich Royal Observatory in London. This is the same convention used in the UNIX/POSIX time. Starting from that origin, time is measured in 86,400 seconds per day, forward and

backward, to nanosecond precision. The `Instant` values go back as far as a billion years (`Instant.MIN`). That's not quite enough to express the age of the universe (around 13.5 billion years) but it should be enough for all practical purposes. After all, a billion years ago, the earth was covered in ice and populated by microscopic ancestors of today's plants and animals. The largest value, `Instant.MAX`, is December 31 of the year 1,000,000,000.

The static method call `Instant.now()` gives the current instant. You can compare two instants with the `equals` and `compareTo` methods in the usual way, so you can use instants as timestamps.

To find out the difference between two instants, use the static method `Duration.between`. For example, here is how you can measure the running time of an algorithm:

[Click here to view code image](#)

```
Instant start = Instant.now();
runAlgorithm();
Instant end = Instant.now();
Duration timeElapsed = Duration.between(start, end);
long millis = timeElapsed.toMillis();
```

A `Duration` is the amount of time between two instants. You can get the length of a `Duration` in conventional units by calling `toNanos`, `toMillis`, `toSeconds`, `toMinutes`, `toHours`, or `toDays`.

---



### Note

In Java 8, you had to call `getSeconds` instead of `toSeconds`.

---

If you need nanosecond precision, be aware of overflow. A `long` value can hold almost 300 years of nanoseconds. If your durations are shorter than that, simply convert them to nanoseconds. You can use longer durations—a `Duration` object stores the number of seconds in a `long`, and the number

of nanoseconds in an additional int. The Duration API has a number of methods, shown at the end of this section, for carrying out arithmetic.

For example, if you want to check whether an algorithm is at least ten times faster than another, you can compute

[Click here to view code image](#)

```
Duration timeElapsed2 = Duration.between(start2, end2);
boolean overTenTimesFaster
=
timeElapsed.multipliedBy(10).minus(timeElapsed2).isNegative();
```

This is just to show the syntax. Since the algorithms aren't going to run for hundreds of years, you can simply use

[Click here to view code image](#)

```
boolean overTenTimesFaster = timeElapsed.toNanos() * 10 <
timeElapsed2.toNanos();
```

---



## Note

The Instant and Duration classes are immutable, and all methods, such as multipliedBy or minus, return a new instance.

---

In the example program in [Listing 6.1](#), you can see how to use the Instant and Duration classes for timing two algorithms.

---

### **Listing 6.1** timeline/TimeLine.java

---

[Click here to view code image](#)

```
1 package timeline;
2
3 /**
4 */
```

```
4 * @version 1.01 2021-09-06
5 * @author Cay Horstmann
6 */
7
8 import java.time.*;
9 import java.util.*;
10 import java.util.stream.*;
11
12 public class Timeline
13 {
14 public static void main(String[] args)
15 {
16 Instant start = Instant.now();
17 runAlgorithm();
18 Instant end = Instant.now();
19 Duration timeElapsed = Duration.between(start, end);
20 long millis = timeElapsed.toMillis();
21 System.out.printf("%d milliseconds\n", millis);
22
23 Instant start2 = Instant.now();
24 runAlgorithm2();
25 Instant end2 = Instant.now();
26 Duration timeElapsed2 = Duration.between(start2, end2);
27 System.out.printf("%d milliseconds\n",
28 timeElapsed2.toMillis());
28 boolean overTenTimesFaster =
29 timeElapsed.multipliedBy(10)
30 .minus(timeElapsed2).isNegative();
30 System.out.printf("The first algorithm is %smore than
ten times faster",
31 overTenTimesFaster ? "" : "not ");
32 }
33
34 public static void runAlgorithm()
35 {
36 int size = 10;
37 ArrayList<Integer> list = new Random().ints().map(i ->
i % 100).limit(size)
```

```

38
 .boxed().collect(Collectors.toCollection(ArrayList::new));
39 Collections.sort(list);
40 System.out.println(list);
41 }
42
43 public static void runAlgorithm2()
44 {
45 int size = 10;
46 List<Integer> list = new Random().ints().map(i -> i %
100).limit(size)
47
 .boxed().collect(Collectors.toCollection(ArrayList::new));
48 while (!IntStream.range(1, list.size())
49 .allMatch(i -> list.get(i -
1).compareTo(list.get(i)) <= 0))
50 Collections.shuffle(list);
51 System.out.println(list);
52 }
53 }
```

---

## **java.time.Instant**

- `static Instant now()`  
gets the current instant from the best available system clock.
- `Instant plus(TemporalAmount amountToAdd)`
- `Instant minus(TemporalAmount amountToSubtract)`  
yield an instant that is the given amount away from this `Instant`.  
The classes `Duration` and `Period` (see [Section 6.2, “Local Dates,”](#) on p. 366) implement the `TemporalAmount` interface.
- `Instant (plus|minus)(Nanos|Millis|Seconds)(long number)`

yields an Instant that is the given number of nanoseconds, milliseconds, or seconds away from this Instant.

## java.time.Duration 8

- static Duration of(Nanos|Millis|Seconds|Minutes|Hours|Days)(long number)

yields a duration of the given number of time units.

- static Duration between(Temporal startInclusive, Temporal endExclusive)

yields a duration between the given points in time. The Temporal interface is implemented by the Instant class as well as LocalDate/LocalDateTime/LocalTime (see [Section 6.4, “Local Time,” on p. 373](#)) and ZonedDateTime (see [Section 6.5, “Zoned Time,” on p. 375](#)).

- long toNanos()
- long toMillis()
- long toSeconds() 9
- long toMinutes()
- long toHours()
- long toDays()

get the number of the time units in the method name for this Duration.

- int to(Nanos|Millis|Seconds|Minutes|Hours)Part() 9
- long toDaysPart() 9

The part of the given time unit in this Duration. For example, in a duration of 100 seconds, the minutes part is 1 and the seconds part

is 40.

- Duration plus(TemporalAmount amountToAdd)
- Duration minus(TemporalAmount amountToSubtract)

yield a duration that is the given amount away from this Duration. The classes Duration and Period (see [Section 6.2, “Local Dates,”](#) on p. 366) implement the TemporalAmount interface.

- Duration multipliedBy(long multiplicand)
- Duration dividedBy(long divisor)
- Duration negated()

yield a duration that is obtained by multiplying or dividing this Duration by the given amount, or by  $-1$ .

- boolean isZero()
- boolean isNegative()

return true if this Duration is zero or negative.

- Duration (plus|minus) (Nanos|Millis|Seconds|Minutes|Hours|Days)(long number)

yields a Duration obtained by adding or subtracting the given number of time units.

## 6.2 Local Dates

Now let us turn from absolute time to human time. There are two kinds of human time in the Java API, *local date/time* and *zoned time*. Local date/time has a date and/or time of day, but no associated time zone information. An example of a local date is June 14, 1903 (the day on which

Alonzo Church, inventor of the lambda calculus, was born). Since that date has neither a time of day nor time zone information, it does not correspond to a precise instant of time. In contrast, July 16, 1969, 09:32:00 EDT (the launch of Apollo 11) is a zoned date/time, representing a precise instant on the time line.

There are many calculations where time zones are not required, and in some cases they can even be a hindrance. Suppose you schedule a meeting every week at 10:00. If you add 7 days (that is,  $7 \times 24 \times 60 \times 60$  seconds) to the last zoned time, and you happen to cross the daylight savings time boundary, the meeting will be an hour too early or too late!

For that reason, the API designers recommend that you do not use zoned time unless you really want to represent absolute time instances. Birthdays, holidays, schedule times, and so on are usually best represented as local dates or times.

A `LocalDate` is a date with a year, month, and day of the month. To construct one, you can use the `now` or `of` static methods:

[Click here to view code image](#)

```
LocalDate today = LocalDate.now(); // Today's date
LocalDate alonzosBirthday = LocalDate.of(1903, 6, 14);
alonzosBirthday = LocalDate.of(1903, Month.JUNE, 14);
// Uses the Month enumeration
```

Unlike the irregular conventions in UNIX and `java.util.Date`, where months are zero-based and years are counted from 1900, here you supply the usual numbers for the month of year. Alternatively, you can use the `Month` enumeration.

The API notes at the end of this section show the most useful methods for working with `LocalDate` objects.

For example, *Programmer’s Day* is the 256th day of the year. Here is how you can easily compute it:

[Click here to view code image](#)

```
LocalDate programmersDay = LocalDate.of(2014, 1,
1).plusDays(255);
// September 13, but in a leap year it would be September 12
```

Recall that the difference between two time instants is a Duration. The equivalent for local dates is a Period, which expresses a number of elapsed years, months, or days. You can call `birthday.plus(Period.ofYears(1))` to get the birthday next year. Of course, you can also just call `birthday.plusYears(1)`. But `birthday.plus(Period.ofDays(365))` won't produce the correct result in a leap year.

The `until` method yields the difference between two local dates. For example,

[Click here to view code image](#)

```
independenceDay.until(christmas)
```

yields a period of 5 months and 21 days. That is actually not terribly useful because the number of days per month varies. To find the number of days, use

[Click here to view code image](#)

```
independenceDay.until(christmas, ChronoUnit.DAYS) // 174 days
```

---



## Caution

Some methods in the `LocalDate` API could potentially create nonexistent dates. For example, adding one month to January 31 should not yield February 31. Instead of throwing an exception, these methods return the last valid day of the month. For example,

[Click here to view code image](#)

```
LocalDate.of(2016, 1, 31).plusMonths(1)
```

and

[Click here to view code image](#)

```
LocalDate.of(2016, 3, 31).minusMonths(1)
```

yield February 29, 2016.

---

The `getDayOfWeek` yields the weekday, as a value of the `DayOfWeek` enumeration. `DayOfWeek.MONDAY` has the numerical value 1, and `DayOfWeek.SUNDAY` has the value 7. For example,

[Click here to view code image](#)

```
LocalDate.of(1900, 1, 1).getDayOfWeek().getValue()
```

yields 1. The `DayOfWeek` enumeration has convenience methods `plus` and `minus` to compute weekdays modulo 7. For example, `DayOfWeek.SATURDAY.plus(3)` yields `DayOfWeek.TUESDAY`.

---



## Note

The weekend days actually come at the end of the week. This is different from `java.util.Calendar` where Sunday has value 1 and Saturday value 7.

---

Java 9 adds two useful methods `datesUntil` that yield streams of `LocalDate` objects.

[Click here to view code image](#)

```
LocalDate start = LocalDate.of(2000, 1, 1);
LocalDate endExclusive = LocalDate.now();
Stream<LocalDate> allDays = start.datesUntil(endExclusive);
Stream<LocalDate> firstDaysInMonth =
 start.datesUntil(endExclusive, Period.ofMonths(1));
```

In addition to `LocalDate`, there are also classes `MonthDay`, `YearMonth`, and `Year` to describe partial dates. For example, December 25 (with the year unspecified) can be represented as a `MonthDay`.

The example program in Listing 6.2 shows how to work with the `LocalDate` class.

---

**Listing 6.2** localdates/LocalDates.java

---

[Click here to view code image](#)

```
1 package localdates;
2
3 /**
4 * @version 1.01 2021-09-06
5 * @author Cay Horstmann
6 */
7 import java.time.*;
8 import java.time.temporal.*;
9 import java.util.stream.*;
10
11 public class LocalDates
12 {
13 public static void main(String[] args)
14 {
15 LocalDate today = LocalDate.now(); // Today's date
16 System.out.println("today: " + today);
17
18 LocalDate alonzosBirthday = LocalDate.of(1903, 6, 14);
19 alonzosBirthday = LocalDate.of(1903, Month.JUNE, 14);
20 // Uses the Month enumeration
21 System.out.println("alonzosBirthday: " +
22 alonzosBirthday);
23
24 LocalDate programmersDay = LocalDate.of(2018, 1,
25).plusDays(255);
26 // September 13, but in a leap year it would be
27 September 12
```

```
25 System.out.println("programmersDay: " +
programmersDay);
26
27 LocalDate independenceDay = LocalDate.of(2018,
Month.JULY, 4);
28 LocalDate christmas = LocalDate.of(2018,
Month.DECEMBER, 25);
29
30 System.out.println("Until christmas: " +
independenceDay.until(christmas));
31 System.out.println("Until christmas: " +
32 + independenceDay.until(christmas,
ChronoUnit.DAYS));
33
34 System.out.println(LocalDate.of(2016, 1,
31).plusMonths(1));
35 System.out.println(LocalDate.of(2016, 3,
31).minusMonths(1));
36
37 DayOfWeek startOfLastMillennium = LocalDate.of(1900, 1,
1).getDayOfWeek();
38 System.out.println("startOfLastMillennium: " +
startOfLastMillennium);
39 System.out.println(startOfLastMillennium.getValue());
40 System.out.println(DayOfWeek.SATURDAY.plus(3));
41
42 LocalDate start = LocalDate.of(2000, 1, 1);
43 LocalDate endExclusive = LocalDate.now();
44 Stream<LocalDate> firstDaysInMonth =
start.datesUntil(endExclusive, Period.ofMonths(1));
45 System.out.println("firstDaysInMonth: " +
46 + firstDaysInMonth.toList());
47 }
48 }
```

---

**java.time.LocalDate 8**

- static LocalDate now()  
gets the current LocalDate.
- static LocalDate of(int year, int month, int dayOfMonth)
- static LocalDate of(int year, Month month, int dayOfMonth)

yield a local date with the given year, month (as integer between 1 and 12 or a value of the Month enumeration), and day of the month (between 1 and 31).

- LocalDate (plus|minus)(Days|Weeks|Months|Years)  
(long number)

yields a LocalDate obtained by adding or subtracting the given number of time units.

- LocalDate plus(TemporalAmount amountToAdd)
- LocalDate minus(TemporalAmount amountToSubtract)

yields a LocalDate that is the given amount away from this LocalDate. The classes Duration and Period implement the TemporalAmount interface.

- LocalDate withDayOfMonth(int dayOfMonth)
- LocalDate withDayOfYear(int dayOfYear)
- LocalDate withMonth(int month)
- LocalDate withYear(int year)

return a new LocalDate with the day of month, day of year, month, or year changed to the given value.

- int getDayOfMonth()  
gets the day of the month (between 1 and 31).

- `int getDayOfYear()`  
gets the day of the year (between 1 and 366).
- `DayOfWeek getDayOfWeek()`  
gets the day of the week, returning a value of the `DayOfWeek` enumeration.
- `Month getMonth()`
- `int getMonthValue()`  
get the month as a value of the `Month` enumeration, or as a number between 1 and 12.
- `int getYear()`  
gets the year, between `-999,999,999` and `999,999,999`.
- `Period until(ChronoLocalDate endDateExclusive)`  
gets the period until the given end date. The `ChronoLocalDate` interface is implemented by `LocalDate` and date classes for non-Gregorian calendars.
- `boolean isBefore(ChronoLocalDate other)`
- `boolean isAfter(ChronoLocalDate other)`  
return `true` if this date is before or after the given date.
- `boolean isLeapYear()`  
returns `true` if the year is a leap year—that is, if it is divisible by 4 but not by 100, or divisible by 400. The algorithm is applied for all past years, even though that is historically inaccurate. (Leap years were invented in the year `-46`, and the rules involving divisibility by 100 and 400 were introduced in the Gregorian calendar reform of 1582. The reform took over 300 years to become universal.)

- Stream<LocalDate> datesUntil (LocalDate endExclusive) 9
- Stream<LocalDate> datesUntil (LocalDate endExclusive, Period step) 9

yield a stream of dates from this LocalDate until the end, with step size 1 or the given period.

## **java.time.Period 8**

- static Period of(int years, int months, int days)
- Period of(Days|Weeks|Months|Years)(int number)

yield a Period with the given number of time units.

- int get(Days|Months|Years)()

gets the days, months, or years of this Period.

- Period (plus|minus)(Days|Months|Years)(long number)

yields a Period obtained by adding or subtracting the given number of time units.

- Period plus(TemporalAmount amountToAdd)
- Period minus(TemporalAmount amountToSubtract)

yield an instant that is the given amount away from this Instant. The classes Duration and Period implement the TemporalAmount interface.

- Period with(Days|Months|Years)(int number)

returns a new `Period` with the days, months, or years changed to the given number.

## 6.3 Date Adjusters

For scheduling applications, you often need to compute dates such as “the first Tuesday of every month.” The `TemporalAdjusters` class provides a number of static methods for common adjustments. You pass the result of an adjustment method to the `with` method. For example, the first Tuesday of a month can be computed like this:

[Click here to view code image](#)

```
LocalDate firstTuesday = LocalDate.of(year, month, 1).with(
 TemporalAdjusters.nextOrSame(DayOfWeek.TUESDAY));
```

As always, the `with` method returns a new `LocalDate` object without modifying the original. The API notes at the end of this section show the available adjusters.

You can also make your own adjuster by implementing the `TemporalAdjuster` interface. Here is an adjuster for computing the next weekday:

[Click here to view code image](#)

```
TemporalAdjuster NEXT_WORKDAY = w ->
{
 var result = (LocalDate) w;
 do
 {
 result = result.plusDays(1);
 }
 while (result.getDayOfWeek().getValue() >= 6);
 return result;
};
LocalDate backToWork = today.with(NEXT_WORKDAY);
```

Note that the parameter of the lambda expression has type Temporal, and it must be cast to LocalDate. You can avoid this cast with the ofDateAdjuster method that expects a lambda of type UnaryOperator<LocalDate>.

[Click here to view code image](#)

```
TemporalAdjuster NEXT_WORKDAY =
TemporalAdjusters.ofDateAdjuster(w ->
{
 LocalDate result = w; // No cast
 do
 {
 result = result.plusDays(1);
 }
 while (result.getDayOfWeek().getValue() >= 6);
 return result;
});
```

### **java.time.LocalDate 9**

- LocalDate with(TemporalAdjuster adjuster)  
returns the result of adjusting this date by the given adjuster.

### **java.time.temporal.TemporalAdjusters 9**

- static TemporalAdjuster next(DayOfWeek dayOfWeek)
- static TemporalAdjuster nextOrSame(DayOfWeek dayOfWeek)
- static TemporalAdjuster previous(DayOfWeek dayOfWeek)

- static `TemporalAdjuster previousOrSame(DayOfWeek dayOfWeek)`  
return an adjuster that adjusts a date to the given day of the week.
- static `TemporalAdjuster dayOfWeekInMonth(int n, DayOfWeek dayOfWeek)`
- static `TemporalAdjuster lastInMonth(DayOfWeek dayOfWeek)`  
return an adjuster that adjusts a date to the nth or last given weekday on the month.
- static `TemporalAdjuster firstDayOfMonth()`
- static `TemporalAdjuster firstDayOfNextMonth()`
- static `TemporalAdjuster firstDayOfYear()`
- static `TemporalAdjuster firstDayOfNextYear()`
- static `TemporalAdjuster lastDayOfMonth()`
- static `TemporalAdjuster lastDayOfYear()`  
return an adjuster that adjusts a date to the given day of the month or year.

## 6.4 Local Time

A `LocalTime` represents a time of day, such as 15:30:00. You can create an instance with the `now` or `of` methods:

[Click here to view code image](#)

```
LocalTime rightNow = LocalTime.now();
LocalTime bedtime = LocalTime.of(22, 30); // or
LocalTime.of(22, 30, 0)
```

The API notes show common operations with local times. The plus and minus operations wrap around a 24-hour day. For example,

[Click here to view code image](#)

```
LocalTime wakeup = bedtime.plusHours(8); // wakeup is 6:30:00
```

---



## Note

`LocalTime` doesn't concern itself with AM/PM. That silliness is left to a formatter—see [Section 6.6, “Formatting and Parsing,”](#) on p. [379](#).

---

There is a `LocalDateTime` class representing a date and time. That class is suitable for storing points in time in a fixed time zone—for example, for a schedule of classes or events. However, if you need to make calculations that span the daylight savings time, or if you need to deal with users in different time zones, you should use the `ZonedDateTime` class that we discuss next.

### `java.time.LocalTime` 8

- `static LocalTime now()`  
gets the current `LocalTime`.
- `static LocalTime of(int hour, int minute)`
- `static LocalTime of(int hour, int minute, int second)`
- `static LocalTime of(int hour, int minute, int second, int nanoOfSecond)`

yield a local time with the given hour (between 0 and 23), minute, second (between 0 and 59), and nanosecond (between 0 and 999,999,999).

- LocalTime (plus|minus) (Hours|Minutes|Seconds|Nanos)(long number)  
yields a LocalTime obtained by adding or subtracting the given number of time units.
- LocalTime plus (TemporalAmount amountToAdd)
- LocalTime minus (TemporalAmount amountToSubtract)  
yield a LocalTime that is the given amount away from this LocalTime.
- LocalTime with(Hour|Minute|Second|Nano)(int value)  
returns a new LocalTime with the hour, minute, second, or nanosecond changed to the given value.
- int getHour()  
gets the hour (between 0 and 23).
- int getMinute()
- int getSecond()  
get the minute or second (between 0 and 59).
- int getNano()  
gets the nanoseconds (between 0 and 999,999,999).
- int toSecondOfDay()
- long toNanoOfDay()  
yield the seconds or nanoseconds since midnight.
- boolean isBefore(LocalTime other)
- boolean isAfter(LocalTime other)

return true if this date is before or after the given date.

## 6.5 Zoned Time

Time zones, perhaps because they are an entirely human creation, are even messier than the complications caused by the earth's irregular rotation. In a rational world, we'd all follow the clock in Greenwich, and some of us would eat our lunch at 02:00, others at 22:00. Our stomachs would figure it out. This is actually done in China, which spans four conventional time zones. Elsewhere, we have time zones with irregular and shifting boundaries and, to make matters worse, the daylight savings time.

As capricious as the time zones may appear to the enlightened, they are a fact of life. When you implement a calendar application, it needs to work for people who fly from one country to another. When you have a conference call at 10:00 in New York, but happen to be in Berlin, you expect to be alerted at the correct local time.

The Internet Assigned Numbers Authority (IANA) keeps a database of all known time zones around the world ([www.iana.org/time-zones](http://www.iana.org/time-zones)), which is updated several times per year. The bulk of the updates deals with the changing rules for daylight savings time. Java uses the IANA database.

Each time zone has an ID, such as America/New\_York or Europe/Berlin. To find out all available time zones, call ZoneId.getAvailableZoneIds. At the time of this writing, there are almost 600 IDs.

Given a time zone ID, the static method ZoneId.of(id) yields a ZoneId object. You can use that object to turn a LocalDateTime object into a ZonedDateTime object by calling local.atZone(zoneId), or you can construct a ZonedDateTime by calling the static method ZonedDateTime.of(year, month, day, hour, minute, second, nano, zoneId). For example,

[Click here to view code image](#)

```
ZonedDateTime apollo11launch = ZonedDateTime.of(1969, 7, 16,
9, 32, 0, 0,
ZoneId.of("America/New_York"));
// 1969-07-16T09:32-04:00[America/New_York]
```

This is a specific instant in time. Call `apollo11launch.toInstant` to get the Instant. Conversely, if you have an instant in time, call `instant.atZone(ZoneId.of("UTC"))` to get the ZonedDateTime at the Greenwich Royal Observatory, or use another ZoneId to get it elsewhere on the planet.

---



## Note

UTC stands for “Coordinated Universal Time,” and the acronym is a compromise between the aforementioned English and the French “Temps Universel Coordiné,” having the distinction of being incorrect in either language. UTC is the time at the Greenwich Royal Observatory, without daylight savings time.

---

Many of the methods of ZonedDateTime are the same as those of LocalDateTime (see the API notes at the end of this section). Most are straightforward, but daylight savings time introduces some complications.

When daylight savings time starts, clocks advance by an hour. What happens when you construct a time that falls into the skipped hour? For example, in 2013, Central Europe switched to daylight savings time on March 31 at 2:00. If you try to construct nonexistent time March 31 2:30, you actually get 3:30.

[Click here to view code image](#)

```
ZonedDateTime skipped = ZonedDateTime.of(
LocalDate.of(2013, 3, 31),
LocalTime.of(2, 30),
ZoneId.of("Europe/Berlin"));
// Constructs March 31 3:30
```

Conversely, when daylight time ends, clocks are set back by an hour, and there are two instants with the same local time! When you construct a time within that span, you get the earlier of the two.

[Click here to view code image](#)

```
ZonedDateTime ambiguous = ZonedDateTime.of(
 LocalDate.of(2013, 10, 27), // End of daylight savings time
 LocalTime.of(2, 30),
 ZoneId.of("Europe/Berlin"));
// 2013-10-27T02:30+02:00[Europe/Berlin]

ZonedDateTime anHourLater = ambiguous.plusHours(1);
// 2013-10-27T02:30+01:00[Europe/Berlin]
```

An hour later, the time has the same hours and minutes, but the zone offset has changed.

You also need to pay attention when adjusting a date across daylight savings time boundaries. For example, if you set a meeting for next week, don't add a duration of seven days:

[Click here to view code image](#)

```
ZonedDateTime nextMeeting = meeting.plus(Duration.ofDays(7));
// Caution! Won't work with daylight savings time
```

Instead, use the `Period` class.

[Click here to view code image](#)

```
ZonedDateTime nextMeeting = meeting.plus(Period.ofDays(7)); //
OK
```



## Caution

There is also an `OffsetDateTime` class that represents times with an offset from UTC, but without time zone rules. That class is intended for specialized applications that specifically require the

absence of those rules, such as certain network protocols. For human time, use `ZonedDateTime`.

---

The example program in [Listing 6.3](#) demonstrates the `ZonedDateTime` class.

---

### **Listing 6.3** zonedtimes/ZonedDateTime.java

---

[Click here to view code image](#)

```
1 package zonedtimes;
2
3 /**
4 * @version 1.0 2016-05-10
5 * @author Cay Horstmann
6 */
7
8 import java.time.*;
9
10 public class ZonedDateTime
11 {
12 public static void main(String[] args)
13 {
14 ZonedDateTime apollo11launch = ZonedDateTime.of(1969,
15, 16, 9, 32, 0, 0,
16 ZoneId.of("America/New_York")); // 1969-07-16T09:32-
17 04:00[America/New_York]
18 System.out.println("apollo11launch: " +
19 apollo11launch);
20
21 Instant instant = apollo11launch.toInstant();
22 System.out.println("instant: " + instant);
23
24 ZonedDateTime zonedDateTime =
25 instant.atZone(ZoneId.of("UTC"));
26 System.out.println("zonedDateTime: " + zonedDateTime);
27 }
28 }
```

```

24 ZonedDateTime skipped =
ZonedDateTime.of(LocalDate.of(2013, 3, 31),
25 LocalTime.of(2, 30), ZoneId.of("Europe/Berlin")); //
Constructs March 31 3:30
26 System.out.println("skipped: " + skipped);
27
28 ZonedDateTime ambiguous = ZonedDateTime.of(
29 LocalDate.of(2013, 10, 27), // End of daylight
savings time
30 LocalTime.of(2, 30), ZoneId.of("Europe/Berlin"));
31 // 2013-10-27T02:30+02:00[Europe/Berlin]
32 ZonedDateTime anHourLater = ambiguous.plusHours(1);
33 // 2013-10-27T02:30+01:00[Europe/Berlin]
34 System.out.println("ambiguous: " + ambiguous);
35 System.out.println("anHourLater: " + anHourLater);
36
37 ZonedDateTime meeting =
ZonedDateTime.of(LocalDate.of(2013, 10, 31),
38 LocalTime.of(14, 30),
ZoneId.of("America/Los_Angeles"));
39 System.out.println("meeting: " + meeting);
40 ZonedDateTime nextMeeting =
meeting.plus(Duration.ofDays(7));
41 // Caution! Won't work with daylight savings time
42 System.out.println("nextMeeting: " + nextMeeting);
43 nextMeeting = meeting.plus(Period.ofDays(7)); // OK
44 System.out.println("nextMeeting: " + nextMeeting);
45 }
46 }
```

---

## **java.time.ZonedDateTime 8**

- static ZonedDateTime now()

gets the current ZonedDateTime.

- static ZonedDateTime of(int year, int month, int dayOfMonth, int hour, int minute, int second, int nanoOfSecond, ZoneId zone)
- static ZonedDateTime of(LocalDate date, LocalTime time, ZoneId zone)
- static ZonedDateTime of(LocalDateTime localDateTime, ZoneId zone)
- static ZonedDateTime ofInstant(Instant instant, ZoneId zone)

**yield a ZonedDateTime with the given parameters and time zone.**

- ZonedDateTime (plus|minus) (Days|Weeks|Months|Years|Hours|Minutes|Seconds|Nanos)(long number)

**yields a ZonedDateTime obtained by adding or subtracting the given number of time units.**

- ZonedDateTime plus(TemporalAmount amountToAdd)
- ZonedDateTime minus(TemporalAmount amountToSubtract)

**yield a ZonedDateTime that is the given amount away from this ZonedDateTime.**

- ZonedDateTime with(DayOfMonth|DayOfYear|Month|Year|Hour|Minute|Second|Nano)(int value)

**returns a new ZonedDateTime with the given temporal unit replaced by the given value.**

- ZonedDateTime withZoneSameInstant(ZoneId zone)
- ZonedDateTime withZoneSameLocal(ZoneId zone)

return a new `ZonedDateTime` in the given time zone, either representing the same instant or the same local time.

- `int getDayOfMonth()`  
gets the day of the month (between 1 and 31).
- `int getDayOfYear()`  
gets the day of the year (between 1 and 366).
- `DayOfWeek getDayOfWeek()`  
gets the day of the week, returning a value of the `DayOfWeek` enumeration.
- `Month getMonth()`
- `int getMonthValue()`  
get the month as a value of the `Month` enumeration, or as a number between 1 and 12.
- `int getYear()`  
gets the year, between `-999,999,999` and `999,999,999`.
- `int getHour()`  
gets the hour (between 0 and 23).
- `int getMinute()`
- `int getSecond()`  
get the minute or second (between 0 and 59).
- `int getNano()`  
gets the nanoseconds (between 0 and `999,999,999`).
- `public ZoneOffset getOffset()`

gets the offset from UTC. Offsets can vary from  $-12:00$  to  $+14:00$ . Some time zones have fractional offsets. Offsets change with daylight savings time.

- `LocalDate toLocalDate()`
  - `LocalTime toLocalTime()`
  - `LocalDateTime toLocalDateTime()`
  - `Instant toInstant()`
- yield the local date, time, or date/time, or the corresponding instant.
- `boolean isBefore(ChronoZonedDateTime other)`
  - `boolean isAfter(ChronoZonedDateTime other)`
- return `true` if this zoned date/time is before or after the given zoned date/time.

## 6.6 Formatting and Parsing

The `DateTimeFormatter` class provides three kinds of formatters to print a date/time value:

- Predefined standard formatters (see [Table 6.1](#))

**Table 6.1** Predefined Formatters

Formatter	Description	Example
<code>BASIC_ISO_DATE</code>	Year, month, day, zone offset without separators	19690716-0500

<b>Formatter</b>	<b>Description</b>	<b>Example</b>
ISO_LOCAL_D ATE,		1969-07-16,
ISO_LOCAL_T IME,	Separators -, :, T	09:32:00, 1969- 07-16T09:32:00
ISO_LOCAL_D ATE_TIME		
ISO_OFFSET_DATE, ISO_OFFSET_TIME, ISO_OFFSET_DATE_TIME	Like ISO_LOCAL_XXX, but with zone offset	1969-07- 05:00, 09:32:00- 05:00, 1969-07- 16T09:32:00- 05:00
ISO_ZONED_D ATE_TIME_ID	With zone offset and zone ID	1969-07- 16T09:32:00- 05:00 [America/Ne w_York]
ISO_INSTANT	In UTC, denoted by the Z zone ID	1969-07- 16T14:32:00Z
ISO_DATE, ISO_TIME, ISO_DATE_TIME	Like ISO_OFFSET_DATE, ISO_OFFSET_TIME, and ISO_ZONED_DATE_TIME, but the zone information is optional	1969-07-16- 05:00, 09:32:00- 05:00, 1969-07- 16T09:32:00- 05:00 [America/Ne w_York]
ISO_ORDINAL_DATE	The year and day of year, for LocalDate	1969-197
ISO_WEEK_DATE	The year, week, and day of week, for LocalDate	1969-W29-3

Formatter	Description	Example
RFC_1123_DA TE_TIME	The standard for email timestamps, codified in RFC 822 and updated to four digits for the year in RFC 1123	Wed, 16 Jul 1969 09:32:00 -0500

- Locale-specific formatters
- Formatters with custom patterns

To use one of the standard formatters, simply call its `format` method:

[Click here to view code image](#)

```
String formatted =
DateTimeFormatter.ISO_OFFSET_DATE_TIME.format(apollo11Launch);
// 1969-07-16T09:32:00-04:00"
```

The standard formatters are mostly intended for machine-readable timestamps. To present dates and times to human readers, use a locale-specific formatter. There are four styles, `SHORT`, `MEDIUM`, `LONG`, and `FULL`, for both date and time—see [Table 6.2](#).

**Table 6.2** Locale-Specific Formatting Styles

Style	Date	Time
SHORT	7/16/69	9:32 AM
MEDIUM	Jul 16, 1969	9:32:00 AM
LONG	July 16, 1969	9:32:00 AM EDT
FULL	Wednesday, July 16, 1969	9:32:00 AM EDT

The static methods `ofLocalizedDate`, `ofLocalizedTime`, and `ofLocalizedDateTime` create such a formatter. For example:

[Click here to view code image](#)

```
DateTimeFormatter formatter =
DateTimeFormatter.ofLocalizedDateTime(FormatStyle.LONG);
String formatted = formatter.format(apollo11launch);
// July 16, 1969 9:32:00 AM EDT
```

These methods use the default locale. To change to a different locale, simply use the `withLocale` method.

[Click here to view code image](#)

```
formatted =
formatter.withLocale(Locale.FRENCH).format(apollo11launch);
// 16 juillet 1969 09:32:00 EDT
```

The `DayOfWeek` and `Month` enumerations have methods `getDisplayName` for giving the names of weekdays and months in different locales and formats.

[Click here to view code image](#)

```
for (DayOfWeek w : DayOfWeek.values())
 System.out.print(w.getDisplayName(TextStyle.SHORT,
 Locale.ENGLISH) + " ");
// Prints Mon Tue Wed Thu Fri Sat Sun
```

See [Chapter 7](#) for more information about locales.



## Note

The `java.time.format.DateTimeFormatter` class is intended as a replacement for `java.util.DateFormat`. If you need an instance of the latter for backward compatibility, call `formatter.toFormat()`.

---

Finally, you can roll your own date format by specifying a pattern. For example,

[Click here to view code image](#)

```
formatter = DateTimeFormatter.ofPattern("E yyyy-MM-dd HH:mm");
```

formats a date in the form `Wed 1969-07-16 09:32`. Each letter denotes a different time field, and the number of times the letter is repeated selects a particular format, according to rules that are arcane and seem to have organically grown over time. [Table 6.3](#) shows the most useful pattern elements.

**Table 6.3** Commonly Used Formatting Symbols for Date/Time Formats

ChronoField or Purpose	Examples
ERA	G: AD, GGGG: Anno Domini, GGGGG: A
YEAR_OF_ERA	yy: 69, yyyy: 1969
MONTH_OF_YEAR	M: 7, MM: 07, MMM: Jul, MMMM: July, MMMMM: J
DAY_OF_MONTH	d: 6, dd: 06
DAY_OF_WEEK	e: 3, E: Wed, EEEE: Wednesday, EEEEE: W
HOUR_OF_DAY	H: 9, HH: 09
CLOCK_HOUR_OF_AM_PM	K: 9, KK: 09
AMPM_OF_DAY	a: AM
Period of day (since Java 16)	B: in the evening, at night, midnight
MINUTE_OF_HOUR	mm: 02
SECOND_OF_MINUTE	ss: 00
NANO_OF_SECOND	nnnnnn: 000000

ChronoField or Purpose	Examples
Time zone ID	VV: America/New_York
Time zone name	z: EDT, zzzz: Eastern Daylight Time, v: ET, vvvv: Eastern Time
Zone offset	x: -04, xx: -0400, xxx: -04:00, XXX: same, but use Z for zero
Localized zone offset	O: GMT-4, OOOO: GMT-04:00
Modified Julian Day	g: 58243

To parse a date/time value from a string, use one of the static parse methods. For example,

[Click here to view code image](#)

```
LocalDate churchsBirthday = LocalDate.parse("1903-06-14");
ZonedDateTime apollo11Launch =
 ZonedDateTime.parse("1969-07-16 03:32:00-0400",
 DateTimeFormatter.ofPattern("yyyy-MM-dd HH:mm:ssxx"));
```

The first call uses the standard ISO\_LOCAL\_DATE formatter, the second one a custom formatter.

The program in [Listing 6.4](#) shows how to format and parse dates and times.

---

#### **Listing 6.4** `formatting/Formatting.java`

---

[Click here to view code image](#)

```
1 package formatting;
2
3 /**
4 * @version 1.0 2016-05-10
5 * @author Cay Horstmann
6 */
```

```
7
8 import java.time.*;
9 import java.time.format.*;
10 import java.util.*;
11
12 public class Formatting
13 {
14 public static void main(String[] args)
15 {
16 ZonedDateTime apollo11lauch = ZonedDateTime.of(1969,
17, 16, 9, 32, 0, 0,
18 ZoneId.of("America/New_York"));
19
20 String formatted =
21 DateTimeFormatter.ISO_OFFSET_DATE_TIME.format(apollo11lauch);
22 // 1969-07-16T09:32:00-04:00
23 System.out.println(formatted);
24
25 DateTimeFormatter formatter =
26 DateTimeFormatter.ofLocalizedDateTime(FormatStyle.LONG);
27 formatted = formatter.format(apollo11lauch);
28 // July 16, 1969 9:32:00 AM EDT
29 System.out.println(formatted);
30
31 formatted =
32 formatter.withLocale(Locale.FRENCH).format(apollo11lauch);
33 // 16 juillet 1969 09:32:00 EDT
34 System.out.println(formatted);
35
36 formatter = DateTimeFormatter.ofPattern("E yyyy-MM-dd
HH:mm");
37 formatted = formatter.format(apollo11lauch);
38 System.out.println(formatted);
39
40 LocalDate churchsBirthday = LocalDate.parse("1903-06-
41");
42 System.out.println("churchsBirthday: " +
43 churchsBirthday);
44 apollo11lauch = ZonedDateTime.parse("1969-07-16
```

```
03:32:00-0400",
38 DateTimeFormatter.ofPattern("yyyy-MM-dd
HH:mm:ssxx"));
39 System.out.println("apollo11launch: " +
apollo11launch);
40
41 for (DayOfWeek w : DayOfWeek.values())
42 System.out.print(w.getDisplayName(TextStyle.SHORT,
Locale.ENGLISH) + " ");
43 }
44 }
```

---

## **java.time.format.DateTimeFormatter 8**

- `String format(TemporalAccessor temporal)`  
formats the given value. The classes Instant, LocalDate, LocalTime, LocalDateTime, and ZonedDateTime, as well as many others, implement the TemporalAccessor interface.
- `static DateTimeFormatter ofLocalizedDate(FormatStyle dateStyle)`
- `static DateTimeFormatter ofLocalizedTime(FormatStyle timeStyle)`
- `static DateTimeFormatter ofLocalDateTime(FormatStyle dateTextStyle)`
- `static DateTimeFormatter ofLocalDateTime(FormatStyle dateStyle, FormatStyle timeStyle)`  
yield a formatter for the given styles. The FormatStyle enumeration has values SHORT, MEDIUM, LONG, and FULL.
- `DateTimeFormatter withLocale(Locale locale)`

yields a formatter equal to this formatter, using the given locale.

- static DateTimeFormatter ofPattern(String pattern)
- static DateTimeFormatter ofPattern(String pattern, Locale locale)

yield a formatter using the given pattern and locale. See [Table 6.3](#) for the pattern syntax.

### **java.time.LocalDate 8**

- static LocalDate parse(CharSequence text)
- static LocalDate parse(CharSequence text, DateTimeFormatter formatter)

yield a LocalDate using the default formatter, or the given formatter.

### **java.time.ZonedDateTime 8**

- static ZonedDateTime parse(CharSequence text)
- static ZonedDateTime parse(CharSequence text, DateTimeFormatter formatter)

yield a ZonedDateTime using the default formatter, or the given formatter.

## **6.7 Interoperating with Legacy Code**

As a new creation, the Java Date and Time API will have to interoperate with existing classes—in particular, the ubiquitous `java.util.Date`, `java.util.GregorianCalendar`, and `java.sql.Date/Time/Timestamp`.

The `Instant` class is a close analog to `java.util.Date`. In Java 8, that class has two added methods: the `toInstant` method that converts a `Date` to an `Instant`, and the static `from` method that converts in the other direction.

Similarly, `ZonedDateTime` is a close analog to `java.util.GregorianCalendar`, and that class has gained conversion methods in Java 8. The `toZonedDateTime` method converts a `GregorianCalendar` to a `ZonedDateTime`, and the static `from` method does the opposite conversion.

Another set of conversions is available for the date and time classes in the `java.sql` package. You can also pass a `DateTimeFormatter` to legacy code that uses `java.text.Format`. [Table 6.4](#) summarizes these conversions.

**Table 6.4** Conversions between `java.time` Classes and Legacy Classes

Classes	To Legacy Class	From Legacy Class
<code>Instant</code> ↔ <code>java.util.Date</code>	<code>Date.from(instant)</code>	<code>date.toInstant()</code>
<code>ZonedDateTime</code> ↔ <code>java.util.GregorianCalendar</code>	<code>GregorianCalendar.from(zonedDateTime)</code>	<code>cal.toZonedDateTime()</code>
<code>Instant</code> ↔ <code>java.sql.Timestamp</code>	<code>Timestamp.from.instant())</code>	<code>timestamp.toInstant()</code>
<code>LocalDateTime</code> ↔ <code>java.sql.Timestamp</code>	<code>Timestamp.valueOf(localDateTime)</code>	<code>timestamp.toLocalDateTime()</code>

<b>Classes</b>	<b>To Legacy Class</b>	<b>From Legacy Class</b>
LocalDate ↔ java.sql.Date	Date.valueOf(loc alDate)	date.toLoca lDate()
LocalTime ↔ java.sql.Time	Time.valueOf(loc alTime)	time.toLoca lTime()
DateTimeFormatter → java.text.DateFormat at() at	formatter.toForm	None
java.util.TimeZone ↔ ZoneId	TimeZone.getTime Zone(id)	ZoneId()
java.nio.file.attribute.FileTime ↔ Instant	FileTime.from(in stant)	fileTime.to Instant()

You now know how to use the Java 8 date and time library to work with date and time values around the world. The next chapter takes the discussion of programming for an international audience further. You will see how to format program messages, numbers, and currencies in the way that makes sense for your customers, wherever they may be.

---

# Chapter 7. Internationalization

---

## In this chapter

- [7.1 Locales](#)
- [7.2 Number Formats](#)
- [7.3 Date and Time](#)
- [7.4 Collation and Normalization](#)
- [7.5 Message Formatting](#)
- [7.6 Text Input and Output](#)
- [7.7 Resource Bundles](#)
- [7.8 A Complete Example](#)

There's a big world out there; we hope that lots of its inhabitants will be interested in your software. The Internet, after all, effortlessly spans the barriers between countries. On the other hand, when you pay no attention to an international audience, *you* are putting up a barrier.

The Java programming language was the first language designed from the ground up to support internationalization. From the beginning, it had the one essential feature needed for effective internationalization: It used Unicode for all strings. Unicode support makes it easy to write Java programs that manipulate strings in most of the world's languages.

Many programmers believe that all they need to do to internationalize their application is to support Unicode and to translate the messages in the user interface. However, as this chapter demonstrates, there is a lot more to

internationalizing programs than just Unicode support. Dates, times, currencies, even numbers are formatted differently in different parts of the world. You need an easy way to configure menu and button names, message strings, and keyboard shortcuts for different languages.

In this chapter, you will see how to write internationalized Java programs and how to localize dates, times, numbers, text, and GUIs. I will show you the tools that Java offers for writing internationalized programs. The chapter concludes with a complete example—a retirement calculator with a user interface in English, German, and Chinese.

## 7.1 Locales

When you look at an application that is adapted to an international market, the most obvious difference you notice is the language. This observation is actually a bit too limiting for true internationalization, since countries can share a common language, but you might still need to do some work to make computer users of both countries happy. As Oscar Wilde famously said: “We have really everything in common with America nowadays, except, of course, language.”

### 7.1.1 Why Locales?

When you provide international versions of a program, all program messages need to be translated to the local language. However, simply translating the user interface text is not sufficient. There are many more subtle differences—for example, numbers are formatted quite differently in English and in German. The number

123,456.78

should be displayed as

123.456,78

for a German user—that is, the roles of the decimal point and the decimal comma separator are reversed. There are similar variations in the display of

dates. In the United States, dates are (somewhat irrationally) displayed as month/day/year. Germany uses the more sensible order of day/month/year, whereas in China, the usage is year/month/day. Thus, the date

3/22/61

should be presented as

22.03.1961

to a German user. Of course, if the month names are written out explicitly, the difference in languages becomes apparent. The English

March 22, 1961

should be presented as

22. März 1961

in German, or

1961年3月22日

in Chinese.

A *locale* captures local preferences such as these. Whenever you present numbers, dates, currency values, and other items whose formatting varies by language or location, you need to use locale-aware APIs.

### 7.1.2 Specifying Locales

A locale is made up of up to five components:

1. A language, specified by two or three lowercase letters, such as en (English), de (German), or zh (Chinese). [Table 7.1](#) shows common codes.

**Table 7.1** Common ISO 639-1 Language Codes

---

<b>Language</b>	<b>Code</b>	<b>Language</b>	<b>Code</b>
Chinese	zh	Italian	it
Danish	da	Japanese	ja
Dutch	nl	Korean	ko
English	en	Norwegian	no
French	fr	Portuguese	pt
Finnish	fi	Spanish	es
German	de	Swedish	sv
Greek	el	Turkish	tr

2. Optionally, a script, specified by four letters with an initial uppercase, such as Latn (Latin), Cyrl (Cyrillic), or Hant (traditional Chinese characters). This can be useful because some languages, such as Serbian, are written in Latin or Cyrillic, and some Chinese readers prefer the traditional over the simplified characters.
3. Optionally, a country or region, specified by two uppercase letters or three digits, such as US (United States) or CH (Switzerland). [Table 7.2](#) shows common codes.

**Table 7.2** Common ISO 3166-1 Country Codes

<b>Country</b>	<b>Code</b>	<b>Country</b>	<b>Code</b>
Austria	AT	Japan	JP
Belgium	BE	Korea	KR
Canada	CA	The Netherlands	NL
China	CN	Norway	NO
Denmark	DK	Portugal	PT
Finland	FI	Spain	ES
Germany	DE	Sweden	SE
Great Britain	GB	Switzerland	CH
Greece	GR	Taiwan	TW

<b>Country</b>	<b>Code</b>	<b>Country</b>	<b>Code</b>
Ireland	IE	Turkey	TR
Italy	IT	United States	US

4. Optionally, a variant, specifying miscellaneous features such as dialects or spelling rules. Variants are rarely used nowadays. There used to be a “Nynorsk” variant of Norwegian, but it is now expressed with a different language code, nn. What used to be variants for the Japanese imperial calendar and Thai numerals are now expressed as extensions (see the next item).
5. Optionally, an extension. Extensions describe local preferences for calendars (such as the Japanese calendar), numbers (Thai instead of Western digits), and so on. The Unicode standard specifies some of these extensions. Extensions start with u- and a two-letter code specifying whether the extension deals with the calendar (ca), numbers (nu), and so on. For example, the extension u-nu-thai denotes the use of Thai numerals. Other extensions are entirely arbitrary and start with x-, such as x-java.

Rules for locales are formulated in the “Best Current Practices” memo BCP 47 of the Internet Engineering Task Force (<https://tools.ietf.org/search/bcp47>). You can find a more accessible summary at [www.w3.org/International/articles/language-tags](http://www.w3.org/International/articles/language-tags).

The codes for languages and countries seem a bit random because some of them are derived from local languages. German in German is Deutsch, Chinese in Chinese is zhongwen: hence de and zh. And Switzerland is CH, deriving from the Latin term *Confoederatio Helvetica* for the Swiss confederation.

Locales are described by tags—hyphenated strings of locale elements such as en-US.

In Germany, you would use a locale de-DE. Switzerland has four official languages (German, French, Italian, and Rhaeto-Romance). A German speaker in Switzerland would want to use a locale de-CH. This locale uses

the rules for the German language, but currency values are expressed in Swiss francs, not euros.

If you only specify the language, say, de, then the locale cannot be used for country-specific issues such as currencies.

You can construct a Locale object from a tag string like this:

[Click here to view code image](#)

```
Locale usEnglish = Locale.forLanguageTag("en-US");
```

The toLanguageTag method yields the language tag for a given locale. For example, Locale.US.toLanguageTag() is the string "en-US".

For your convenience, there are predefined locale objects for various countries:

```
Locale.CANADA
Locale.CANADA_FRENCH
Locale.CHINA
Locale.FRANCE
Locale.GERMANY
Locale.ITALY
Locale.JAPAN
Locale.KOREA
Locale.PRC
Locale.TAIWAN
Locale.UK
Locale.US
```

A number of predefined locales specify just a language without a location:

```
Locale.CHINESE
Locale.ENGLISH
Locale.FRENCH
Locale.GERMAN
Locale.ITALIAN
Locale.JAPANESE
```

```
Locale.KOREAN
Locale.SIMPLIFIED_CHINESE
Locale.TRADITIONAL_CHINESE
```

Finally, the static `getAvailableLocales` method returns an array of all locales known to the virtual machine.

---



### Note

You can get all language codes as

`Locale.getISOLanguages()` and all country codes as  
`Locale.getISOCountries()`.

---

### 7.1.3 The Default Locale

The static `getDefault` method of the `Locale` class initially gets the default locale as stored by the local operating system. You can change the default Java locale by calling the `setDefault` method with a different locale.

Some operating systems allow the user to specify different locales for displayed messages and for formatting. For example, a French speaker living in the United States can have French menus but currency values in dollar.

To obtain these preferences, call

[Click here to view code image](#)

```
Locale displayLocale =
Locale.getDefault(Locale.Category.DISPLAY);
Locale formatLocale = Locale.getDefault(Locale.Category.FORMAT);
```

---



### Note

In UNIX, you can specify separate locales for numbers, currencies, and dates, by setting the `LC_NUMERIC`, `LC_MONETARY`, and `LC_TIME` environment variables. Java does not pay attention to these settings.

---

---



### Tip

If you want to test a locale that just has language and country settings, you can supply them on the command line when you launch your program. For example, here we set the default locale to `de-CH`:

[Click here to view code image](#)

```
java -Duser.language=de -Duser.region=CH MyProgram
```

---

#### 7.1.4 Display Names

Once you have a locale, what can you do with it? Initially, not much, as it turns out. The only useful methods in the `Locale` class are those for identifying the language and country codes. The most important one is `getDisplayName`. It returns a string describing the locale. This string does not contain the cryptic two-letter codes, but is in a form that can be presented to a user, such as

German (Switzerland)

Actually, there is a problem here. The display name is issued in the default locale. That might not be appropriate. If your user already selected German as the preferred language, you probably want to present the string in German. You can do just that by giving the German locale as a parameter. The code

[Click here to view code image](#)

```
var loc = new Locale("de", "CH");
System.out.println(loc.getDisplayName(Locale.GERMAN));
```

prints

```
Deutsch (Schweiz)
```

This example shows why you need `Locale` objects. You feed them to locale-aware methods that produce text that is presented to users in different locations. You will see many examples of this in the following sections.

---



## Caution

Even such mundane operations as turning a string into lowercase or uppercase can be locale-specific. For example, in the Turkish locale, the lowercase of the letter I is a dotless i. Programs that tried to normalize strings by storing them in lowercase have mysteriously failed for Turkish customers where I and the dotted i don't have the same lowercase version. It is a good idea to always use the variants of `toUpperCase` and `toLowerCase` that take a `Locale` argument. For example, try out:

[Click here to view code image](#)

```
String cmd = "QUIT".toLowerCase(Locale.forLanguageTag("tr"));
// "quit" with a dotless i
```

Of course, in Turkey, where `Locale.getDefault()` yields just that locale, `"QUIT".toLowerCase()` is not the same as `"quit"`.

If you want to normalize English language strings to lowercase, you should pass an English locale to the `toLowerCase` method.

---



## Note

You can explicitly set the locale for input and output operations.

- When reading numbers from a `Scanner`, you can set its locale with the `useLocale` method.

- The `String.format` and `PrintWriter.printf` methods optionally take a `Locale` argument.
- 

## `java.util.Locale` 1.1

- `Locale(String language)`
- `Locale(String language, String country)`
- `Locale(String language, String country, String variant)`

construct a locale with the given language, country, and variant. Don't use variants in new code—use the IETF BCP 47 language tags instead.

- `static Locale forLanguageTag(String languageTag)`  
constructs a locale corresponding to the given language tag.
- `static Locale getDefault()`  
returns the default locale.
- `static voidsetDefault(Locale loc)`  
sets the default locale.
- `String getDisplayName()`  
returns a name describing the locale, expressed in the current locale.
- `String getDisplayName(Locale loc)`  
returns a name describing the locale, expressed in the given locale.
- `String getLanguage()`  
returns the language code—a lowercase two-letter ISO 639 code.

- `String getDisplayLanguage()`  
returns the name of the language, expressed in the current locale.
- `String getDisplayLanguage(Locale loc)`  
returns the name of the language, expressed in the given locale.
- `String getCountry()`  
returns the country code as an uppercase two-letter ISO 3166 code.
- `static String[] getISOCountries()`
- `static Set<String> getISOCountries(Locale.IsoCountryCode type) 9`  
get all two-letter country codes, or all country codes with 2, 3, or 4 letters. The `type` is one of the enumeration constants `PART1_ALPHA2`, `PART1_ALPHA3`, and `PART3`.
- `String getDisplayCountry()`  
returns the name of the country, expressed in the current locale.
- `String getDisplayCountry(Locale loc)`  
returns the name of the country, expressed in the given locale.
- `String toLanguageTag() 7`  
returns the IETF BCP 47 language tag for this locale—for example, "`de-CH`".
- `String toString()`  
returns a description of the locale, with the language and country separated by underscores (e.g., "`de_CH`"). Use this method only for debugging.

## 7.2 Number Formats

I already mentioned how number and currency formatting is highly locale-dependent. The Java library supplies a collection of formatter objects that can format and parse numeric values in the `java.text` package.

### 7.2.1 Formatting Numeric Values

Go through the following steps to format a number for a particular locale:

1. Get the locale object, as described in the preceding section.
2. Use a “factory method” to obtain a formatter object.
3. Use the formatter object for formatting and parsing.

The factory methods are static methods of the `NumberFormat` class that take a `Locale` argument. There are three factory methods: `getNumberInstance`, `getCurrencyInstance`, and `getPercentInstance`. These methods return objects that can format and parse numbers, currency amounts, and percentages, respectively. For example, here is how you can format a currency value in German:

[Click here to view code image](#)

```
Locale loc = Locale.GERMAN;
NumberFormat formatter = NumberFormat.getCurrencyInstance(loc);
double amt = 123456.78;
String result = formatter.format(amt);
```

The result is

123.456,78 €

Note that the currency symbol is € and that it is placed at the end of the string. Also, note the reversal of decimal points and decimal commas.

Java 12 adds a “compact” format with two styles: short (123K) and long (123 thousand). Here is how to obtain the short style:

[Click here to view code image](#)

```
formatter = NumberFormat.getCompactNumberInstance(loc,
NumberFormat.Style.SHORT);
```

Conversely, to read in a number that was entered or stored with the conventions of a certain locale, use the parse method. For example, the following code parses the value that the user typed into a text field. The parse method can deal with decimal points and commas, as well as digits in other languages.

[Click here to view code image](#)

```
TextField inputField;
. . .
NumberFormat fmt = NumberFormat.getNumberInstance();
// get the number formatter for default locale
Number input = fmt.parse(inputField.getText().strip());
double x = input.doubleValue();
```

The return type of parse is the abstract type Number. The returned object is either a Double or a Long wrapper object, depending on whether the parsed number was a floating-point number. If you don't care about the distinction, you can simply use the doubleValue method of the Number class to retrieve the wrapped number.

---



### Caution

Objects of type Number are not automatically unboxed—you cannot simply assign a Number object to a primitive type. Instead, use the doubleValue or intValue method.

---

If the text for the number is not in the correct form, the method throws a ParseException. For example, leading whitespace in the string is *not* allowed. (Call trim to remove it.) However, any characters that follow the number in the string are simply ignored, so no exception is thrown.

Note that the classes returned by the `getXXXInstance` factory methods are not actually of type `NumberFormat`. The `NumberFormat` type is an abstract class, and the actual formatters belong to one of its subclasses. The factory methods merely know how to locate the object that belongs to a particular locale.

You can get a list of the currently supported locales with the static `getAvailableLocales` method. That method returns an array of the locales for which number formatter objects can be obtained.

---



### Note

You can use a `Scanner` to read localized integers and floating-point numbers. Call the `useLocale` method to set the locale.

---

The book companion code contains a GUI program that lets you experiment with number formatters (see [Figure 7.1](#)). The combo box at the top of the figure contains all locales with number formatters. You can choose between number, currency, and percentage formatters. Each time you make another choice, the number in the text field is reformatted. If you go through a few locales, you can get a good impression of the many ways that a number or currency value can be formatted. You can also type a different number and click the Parse button to call the `parse` method, which tries to parse what you entered. If your input is successfully parsed, it is passed to `format` and the result is displayed. If parsing fails, a “Parse error” message is displayed in the text field.



**Figure 7.1** The `NumberFormatTest` program

[Listing 7.1](#) shows a text version of the number format explorer that is a bit easier to follow.

---

**Listing 7.1** numberFormat/NumberFormatTest2.java

---

[Click here to view code image](#)

```
1 package numberFormat;
2
3 import java.text.*;
4 import java.util.*;
5 import util.*;
6
7 /**
8 * This program demonstrates formatting numbers under various
9 * locales.
10 * @version 2.0 2021-09-22
11 * @author Cay Horstmann
12 */
13 public class NumberFormatTest2
14 {
15 public static void main(String[] args)
16 {
17 Scanner in = new Scanner(System.in);
18 var locales = (Locale[])
NumberFormat.getAvailableLocales().clone();
19 Arrays.sort(locales,
Comparator.comparing(Locale::getDisplayName));
20 Locale loc = Choices.choose(in, locales,
Locale::getDisplayName);
21 var formatters = new LinkedHashMap<NumberFormat, String>
();
22 formatters.put(NumberFormat.getNumberInstance(loc),
"Number");
23 formatters.put(NumberFormat.getCompactNumberInstance(
24 loc, NumberFormat.Style.SHORT), "Compact Short");
25 formatters.put(NumberFormat.getCompactNumberInstance(
26 loc, NumberFormat.Style.LONG), "Compact Long");
27 formatters.put(NumberFormat.getPercentInstance(loc),
"Percent");
```

```
28 formatters.put(NumberFormat.getCurrencyInstance(loc),
29 "Currency");
30
31 NumberFormat formatter = Choices.choose(in, formatters);
32
33 String operation = Choices.choose(in, "Format", "Parse");
34 if (operation.equals("Format"))
35 {
36 System.out.print("Enter a floating-point number to
37 format: ");
38
39 double number = in.nextDouble();
40 System.out.println(formatter.format(number));
41
42 }
43 else
44 {
45 System.out.print("Enter a floating-point number to
46 parse: ");
47
48 String text = in.next();
49 try
50 {
51 System.out.println(formatter.parse(text));
52 }
53 catch (ParseException e)
54 {
55 System.out.println("ParseException " +
56 e.getMessage());
57 }
58 }
59 }
60 }
```

---

## java.text.NumberFormat 1.1

- static Locale[] getAvailableLocales()  
returns an array of Locale objects for which NumberFormat  
formatters are available.

- static NumberFormat getNumberInstance()
- static NumberFormat getNumberInstance(Locale inLocale)
- static NumberFormat getCurrencyInstance()
- static NumberFormat getCurrencyInstance(Locale inLocale)
- static NumberFormat getPercentInstance()
- static NumberFormat getPercentInstance(Locale inLocale)

return a formatter for numbers, currency amounts, or percentage values for the current locale or for the given locale.

- static NumberFormat  
getCompactNumberInstance() 12
- static NumberFormat  
getCompactNumberInstance(Locale locale,  
NumberFormat.Style formatStyle) 12

return a compact number formatter in the current locale and SHORT style, or in the given locale and style (either SHORT or LONG).

- String format(double number)
- String format(long number)

return the string resulting from formatting the given floating-point number or integer.

- Number parse(String source)

parses the given string and returns the number value, as a Double if the input string describes a floating-point number or as a Long otherwise. The beginning of the string must contain a number; no leading whitespace is allowed. The number can be followed by other characters, which are ignored. Throws ParseException if parsing was not successful.

- `void setParseIntegerOnly(boolean value)`
- `boolean isParseIntegerOnly()`

set or get a flag to indicate whether this formatter should parse only integer values.

- `void setGroupingUsed(boolean newValue)`
- `boolean isGroupingUsed()`

set or get a flag to indicate whether this formatter emits and recognizes decimal separators (such as 100,000).

- `void setMinimumIntegerDigits(int newValue)`
- `int getMinimumIntegerDigits()`
- `void setMaximumIntegerDigits(int newValue)`
- `int getMaximumIntegerDigits()`
- `void setMinimumFractionDigits(int newValue)`
- `int getMinimumFractionDigits()`
- `void setMaximumFractionDigits(int newValue)`
- `int getMaximumFractionDigits()`

set or get the maximum or minimum number of digits allowed in the integer or fractional part of a number.

### 7.2.2 The DecimalFormat Class

In most locales, the `NumberFormat` factory methods that you saw in the preceding section return an instance of the `DecimalFormat` class. This class describes the formatting variations that occur around the world. You can modify individual settings, or create an entirely new formatter. A pattern syntax makes this a bit more convenient.

The pattern describes the number of required and optional digits, and the prefixes and suffixes for positive and negative numbers. There are also a

couple more esoteric settings—see [Table 7.3](#).

**Table 7.3** DecimalFormat Properties

Property Name	Description	Pattern
groupingSize	The number of integer digits grouped together (usually 3 or 4)	The number of digits between the last , and the end of the integer part, such as #, ## for a grouping size of 3
maximumFractionDigits	The minimum and maximum number of digits of the fractional part	Use required (0) and optional (#) digits in the fractional part: .00##
minimumIntegerDigits	The minimum number of digits of the integer part	Use required (0) digits in the integer part: 000
maximumIntegerDigits	The maximum number of integer digits	With exponential notation, the number of # digits in the integer part, such as ###, ##0.00E0. Otherwise, cannot be set in pattern.
—	the minimum number of digits in the exponential part	Use 0 digits in the E part: #.00E00
multiplier	The multiplier for percent, per thousand	Use % for 100, ‰ (U+2030) for 1000

Property Name	Description	Pattern
positivePrefix/Suffix, negativePrefix/Suffix	The prefix and suffix for positive or negative numbers	Surround the positive or negative part of the pattern with the literal prefix or suffix, e.g. +#0.00; (#) uses a + prefix and no suffix for positive numbers and encloses negative numbers in parentheses.
decimalsSeparator, AlwaysShowsOwn	true if the separator is shown for a zero fractional part	Cannot be set in pattern

Consider this example:

[Click here to view code image](#)

```
var formatter = new DecimalFormat("0.00;(#)") ;
```

The semicolon separates the positive and the optional negative part. From the positive part, we see that there must be at least one digit in the integer part and at least two digits in the fractional part. This holds for all numbers, regardless of sign. Negative numbers use the accounting format—a prefix ( and a suffix ).

The prefix or suffix may contain a ☰ currency sign (U+00A4) to denote where the currency symbol should go.

If you need to insert a special character into the prefix or suffix, precede it with a single quote. For example, a prefix ' # is a literal hash sign, and o ''clock has one quotation mark.

The actual symbols for the digits, separators, and miscellaneous other number parts are taken from a `DecimalFormatSymbols` object that you can also customize. [Table 7.4](#) lists its properties.

**Table 7.4** `DecimalFormatSymbol` Properties

Property	Type	Description
currencySymbol	String	A string such as "\$" or "EUR" to use where the prefix or suffix has a currency sign
decimalSeparator, monetaryDecimalSep arator	Character	The decimal separator to use with numbers or currency values
exponentSeparator	String	The string before the exponent part, usually "E"
groupingSeparator, monetaryGroupingSe parator (since Java 15)	Character	The group separator to use with numbers or currency values
infinity, NaN	String	The strings for formatting Double.POSITIVE_INFINITY, Double.NEGATIVE_INFINITY, and Double.NaN
internationalCurre ncySymbol	String	The ISO 4217 currency symbol—see <a href="#">Section 7.2.3</a>

Property	Type	Description
minusSign	c h a r	The minus sign that is used when there is no negative pattern
percent, perMill	c h a r	The characters used for percent or per mille
zeroDigit	c h a r	The character for the digit zero. The other digits are the subsequent nine Unicode characters

Suppose, for example, that you want to show numbers in the US style, with , as group separator and . as decimal separator, no matter what the locale is. Customize the `DecimalFormatSymbols` and the formatter:

[Click here to view code image](#)

```
DecimalFormatSymbols symbols = new DecimalFormatSymbols(loc);
symbols.setGroupingSeparator(',');
symbols.setDecimalSeparator('.');
DecimalFormat formatter = (DecimalFormat)
NumberFormat.getNumberInstance(loc);
formatter.setDecimalFormatSymbols(symbols);
```

### 7.2.3 Currencies

To format a currency value, you can use the `NumberFormat.getCurrencyInstance` method. However, that method is not very flexible—it returns a formatter for a single currency. Suppose you prepare an invoice for an American customer in which some amounts are in dollars and others are in euros. You can't just use two formatters:

[Click here to view code image](#)

```
NumberFormat dollarFormatter =
NumberFormat.getCurrencyInstance(Locale.US);
NumberFormat euroFormatter =
NumberFormat.getCurrencyInstance(Locale.GERMANY);
```

Your invoice would look very strange, with some values shown as \$100,000 and others as 100.000 €. (Note that the euro value uses a decimal point, not a comma.)

Instead, use the `Currency` class to control the currency used by the formatters. You can get a `Currency` object by passing a currency identifier to the static `Currency.getInstance` method. Then call the `setCurrency` method for each formatter. Here is how you would set up the euro formatter for your American customer:

[Click here to view code image](#)

```
NumberFormat euroFormatter =
NumberFormat.getCurrencyInstance(Locale.US);
euroFormatter.setCurrency(Currency.getInstance("EUR"));
```

The currency identifiers are defined by ISO 4217 (see <https://www.iso.org/iso-4217-currency-codes.html>). Table 7.5 provides a partial list.

**Table 7.5** Currency Identifiers

Currency Value	Identifier	Numeric Code
U.S. Dollar	USD	840
Euro	EUR	978
British Pound	GBP	826
Japanese Yen	JPY	392
Chinese Renminbi (Yuan)	CNY	156
Indian Rupee	INR	356
Russian Ruble	RUB	643

## **java.util.Currency** 1.4

- static Currency getInstance(String currencyCode)
- static Currency getInstance(Locale locale)

return the Currency instance for the given ISO 4217 currency code or the country of the given locale.
- String toString()
- String getCurrencyCode()
- String getNumericCode() 7
- String getNumericCodeAsString() 9

get the ISO 4217 alphabetic or numeric currency code of this currency.
- String getSymbol()
- String getSymbol(Locale locale)

get the formatting symbol of this currency for the default locale or the given locale. For example, the symbol for USD can be "\$" or "US\$", depending on the locale.
- int getDefaultFractionDigits()

gets the default number of fraction digits of this currency.
- static Set<Currency> getAvailableCurrencies() 7

gets all available currencies.

## **7.3 Date and Time**

When you are formatting date and time, you should be concerned with four locale-dependent issues:

- The names of months and weekdays should be presented in the local language.
- There will be local preferences for the order of year, month, and day.
- The Gregorian calendar might not be the local preference for expressing dates.
- The time zone of the location must be taken into account.

The `DateTimeFormatter` class from the `java.time` package handles these issues. Pick one of the formatting styles shown in [Tables 7.6](#). Then, get a formatter:

**Table 7.6** Date and Time Formatting Styles

Style	Date	Time
SHO RT	7/16/69	9:32 AM
MED IUM	Jul 16, 1969	9:32:00 AM
LON G	July 16, 1969	9:32:00 AM EDT in en-US, 9:32:00 MSZ in de-DE (only for ZonedDateTime)
FUL L	Wednesday, July 16, 1969	9:32:00 AM EDT in en-US, 9:32 Uhr MSZ in de-DE (only for ZonedDateTime)

[Click here to view code image](#)

```
FormatStyle style = . . .; // One of FormatStyle.SHORT,
FormatStyle.MEDIUM, . . .
DateTimeFormatter dateFormatter =
DateTimeFormatter.ofLocalizedDate(style);
DateTimeFormatter timeFormatter =
DateTimeFormatter.ofLocalizedTime(style);
```

```
DateTimeFormatter dateTimeFormatter =
 DateTimeFormatter.ofLocalizedDateTime(style);
 // or DateTimeFormatter.ofLocalizedDateTime(style1, style2)
```

These formatters use the current locale. To use a different locale, use the `withLocale` method:

[Click here to view code image](#)

```
DateTimeFormatter dateFormatter =
 DateTimeFormatter.ofLocalizedDate(style).withLocale(locale);
```

Now you can format a `LocalDate`, `LocalDateTime`, `LocalTime`, or `ZonedDateTime`:

[Click here to view code image](#)

```
ZonedDateTime appointment = . . .;
String formatted = formatter.format(appointment);
```

---



## Note

Here we use the `DateTimeFormatter` class from the `java.time` package. There is also a legacy `java.text.SimpleDateFormat` class from Java 1.1 that works with `Date` and `Calendar` objects.

---

You can use one of the static `parse` methods of `LocalDate`, `LocalDateTime`, `LocalTime`, or `ZonedDateTime` to parse a date or time in a string:

[Click here to view code image](#)

```
LocalTime time = LocalTime.parse("9:32 AM", formatter);
```

These methods are not suitable for parsing human input, at least not without preprocessing. For example, the short time formatter for the United States

will parse "9 : 32 AM" but not "9 : 32AM" or "9 : 32 am".

---



## Caution

Date formatters parse nonexistent dates, such as November 31, and adjust them to the last date in the given month.

---

Sometimes, you need to display just the names of weekdays and months, for example, in a calendar application. Call the `getDisplayName` method of the `DayOfWeek` and `Month` enumerations.

[Click here to view code image](#)

```
for (Month m : Month.values())
 System.out.println(m.getDisplayName(textStyle, locale) + "
");
```

Tables 7.7 shows the text styles. The STANDALONE versions are for display outside a formatted date. For example, in Finnish, January is “tammikuuta” inside a date, but “tammikuu” standalone.

**Table 7.7** Values of the `java.time.format.TextStyle` Enumeration

Style	Example
FULL / FULL_STANDALONE	January
SHORT / SHORT_STANDALONE	Jan
NARROW / NARROW_STANDALONE	J

---



## Note

The first day of the week can be Saturday, Sunday, or Monday, depending on the locale. You can obtain it like this:


[Click here to view code image](#)

```
DayOfWeek first = WeekFields.of(locale).getFirstDayOfWeek();
```

---

[Listing 7.2](#) shows the `DateFormat` class in action. You can select a locale and see how the date and time are formatted in different places around the world.

[Figure 7.2](#) shows a GUI version of the program, which is included in the book companion code. You may need to install Chinese fonts to see the Chinese characters displayed.



**Figure 7.2** The `DateFormatTest` program

---

[Listing 7.2](#) `dateFormat/DateTimeFormatTest2.java`

---

[Click here to view code image](#)

```
1 package dateFormat;
2
3 import java.text.*;
4 import java.time.*;
5 import java.time.format.*;
6 import java.util.*;
7 import util.*;
8
9 /**
10 * This program demonstrates formatting dates under various
locales.
11 * @version 2.0 2021-09-23
12 * @author Cay Horstmann
13 */
14 public class DateTimeFormatTest2
```

```
15 {
16 public static void main(String[] args)
17 {
18 Scanner in = new Scanner(System.in);
19 var locales = (Locale[])
NumberFormat.getAvailableLocales().clone();
20 Arrays.sort(locales,
21 Comparator.comparing(Locale::getDisplayName));
22 Locale loc = Choices.choose(in, locales,
23 Locale::getDisplayName);
24 FormatStyle style = Choices.choose(in, FormatStyle.class,
25 "Short", "Medium", "Long", "Full");
26 String type = Choices.choose(in, "Date", "Time", "Date
and Time");
27
28 if (type.equals("Date"))
29 {
30 DateTimeFormatter formatter =
DateTimeFormatter.ofLocalizedDate(
31 style).withLocale(loc);
32 System.out.println(formatter.format(LocalDate.now()));
33 System.out.print("Enter another date: ");
34 String input = in.nextLine();
35 LocalDate date = LocalDate.parse(input, formatter);
36 System.out.println(formatter.format(date));
37 }
38 else if (type.equals("Time"))
39 {
40 DateTimeFormatter formatter =
DateTimeFormatter.ofLocalizedTime(
41 style).withLocale(loc);
42 System.out.println(formatter.format(LocalTime.now()));
43 System.out.print("Enter another time: ");
44 String input = in.nextLine();
45 LocalTime time = LocalTime.parse(input, formatter);
46 System.out.println(formatter.format(time));
47 }
48 }
49 }
```

```
47 {
48 DateTimeFormatter formatter =
49 DateTimeFormatter.ofLocalizedDateTime(
50 style).withLocale(loc);
51
52 System.out.println(formatter.format(ZonedDateTime.now()));
53
54 System.out.print("Enter another date and time: ");
55 String input = in.nextLine();
56 ZonedDateTime dateTime = ZonedDateTime.parse(input,
57 formatter);
58
59 System.out.println(formatter.format(dateTime));
60 }
61 }
```

java.time.format.DateTimeFormatter 8

- static DateTimeFormatter ofLocalizedDate(FormatStyle dateStyle)
  - static DateTimeFormatter ofLocalizedTime(FormatStyle dateStyle)
  - static DateTimeFormatter ofLocalizedDateTime(FormatStyle dateTimeStyle)
  - static DateTimeFormatter ofLocalizedDateTime(FormatStyle dateStyle, FormatStyle timeStyle)  
return DateTimeFormatter instances that format dates, times, or dates and times with the specified styles.
  - DateTimeFormatter withLocale(Locale locale)  
returns a copy of this formatter with the given locale.
  - String format(TemporalAccessor temporal)  
returns the string resulting from formatting the given date/time.

```
java.time.LocalDate 8
java.time.LocalTime 8
java.time.LocalDateTime 8
java.time.ZonedDateTime 8
```

- static `Xxx parse(CharSequence text, DateTimeFormatter formatter)`

parses the given string and returns the `LocalDate`, `LocalTime`, `LocalDateTime`, or `ZonedDateTime` described in it. Throws a `DateTimeParseException` if parsing was not successful.

## 7.4 Collation and Normalization

Most programmers know how to compare strings with the `compareTo` method of the `String` class. Unfortunately, when interacting with human users, this method is not very useful. The `compareTo` method uses the values of the UTF-16 encoding of the string, which leads to absurd results, even in English. For example, the following five strings are ordered according to the `compareTo` method:

America  
Zulu  
able  
zebra  
Ångström

For dictionary ordering, you would want to consider upper case and lower case to be equivalent. To an English speaker, the sample list of words would be ordered as

```
able
America
Ångström
zebra
Zulu
```

However, that order would not be acceptable to a Swedish user. In Swedish, the letter Å is different from the letter A, and it is collated *after* the letter Z! That is, a Swedish user would want the words to be sorted as

```
able
America
zebra
Zulu
Ångström
```

To obtain a locale-sensitive comparator, call the static `Collator.getInstance` method:

[Click here to view code image](#)

```
Collator coll = Collator.getInstance(locale);
words.sort(coll); // Collator implements Comparator<Object>
```

Since the `Collator` class implements the `Comparator` interface, you can pass a `Collator` object to the `List.sort(Comparator)` method to sort a list of strings.

There are a couple of advanced settings for collators. You can set a collator's *strength* to adjust how selective it should be. Character differences are classified as *primary*, *secondary*, or *tertiary*. For example, in English, the difference between "A" and "Z" is considered primary, the difference between "A" and "Å" is secondary, and between "A" and "a" is tertiary.

By setting the strength of the collator to `Collator.PRIMARY`, you tell it to pay attention only to primary differences. By setting the strength to `Collator.SECONDARY`, you instruct the collator to take secondary differences into account. That is, two strings will be more likely to be

considered different when the strength is set to “secondary” or “tertiary,” as shown in [Table 7.8](#).

**Table 7.8** Collations with Different Strengths (English Locale)

Primary	Secondary	Tertiary
Angstrom = Ångström	Angstrom ≠ Ångström	Angstrom ≠ Ångström
Able = able	Able = able	Able ≠ able

When the strength has been set to `Collator.IDENTICAL`, no differences are allowed. This setting is mainly useful in conjunction with a rather technical collator setting, the *decomposition mode*, which we take up next.

Occasionally, a character or sequence of characters can be described in more than one way in Unicode. For example, an “Å” can be Unicode character U+00C5, or it can be expressed as a plain "A" (U+0065) followed by a "°" (“combining ring above”; U+030A). Perhaps more surprisingly, the letter sequence “ffi” can be described with a single character “Latin small ligature ffi” with code U+FB03. (One could argue that this is a presentation issue that should not have resulted in different Unicode characters, but we don’t make the rules.)

The Unicode standard defines four *normalization forms* (D, KD, C, and KC) for strings. See

[www.unicode.org/unicode/reports/tr15/tr15-23.html](http://www.unicode.org/unicode/reports/tr15/tr15-23.html) for the details. In the normalization form C, accented characters are always composed. For example, a sequence of "A" and a combining ring above "°" is combined into a single character "Å". In form D, accented characters are always decomposed into their base letters and combining accents: "Å" is turned into "A" followed by "°". Forms KC and KD also decompose characters such as ligatures or the trademark symbol.

You can choose the degree of normalization that you want a collator to use. The value `Collator.NO_DECOMPOSITION` does not normalize strings at all. This option is faster, but it might not be appropriate for texts that express characters in multiple forms. The default, `Collator.CANONICAL_DECOMPOSITION`, uses the normalization

form D. This is useful for texts that contain accents but not ligatures. Finally, “full decomposition” uses normalization form KD. See [Table 7.9](#) for examples.

**Table 7.9** Differences between Decomposition Modes

No Decomposition	Canonical Decomposition	Full Decomposition
$\text{Å} \neq \text{A}^\circ$	$\text{Å} = \text{A}^\circ$	$\text{Å} = \text{A}^\circ$
$\text{™} \neq \text{TM}$	$\text{™} \neq \text{TM}$	$\text{™} = \text{TM}$

It is wasteful to have the collator decompose a string many times. If one string is compared against other strings many times, you can save the decomposition in a *collation* key object. The `getCollationKey` method returns a `CollationKey` object that you can use for further, faster comparisons. Here is an example:

[Click here to view code image](#)

```
String a = . . .;
CollationKey aKey = coll.getCollationKey(a);
if(aKey.compareTo(coll.getCollationKey(b)) == 0) // fast
comparison
. . .
```

Finally, you might want to convert strings into their normalized forms even if you don’t do collation—for example, to store strings in a database or communicate with another program. The `java.text.Normalizer` class carries out the normalization process. For example,

[Click here to view code image](#)

```
String name = "Ångström";
String normalized = Normalizer.normalize(name,
Normalizer.Form.NFD);
// uses normalization form D
```

The normalized string contains ten characters. The “Å” and “ö” are replaced by “A°” and “o” sequences.

However, that is not usually the best form for storage and transmission. Normalization form C first applies decomposition and then combines the accents back in a standardized order. According to the W3C, this is the recommended mode for transferring data over the Internet.

The program in Listing 7.3 lets you experiment with collation order. The book companion code also has a GUI version. Type a word into the text field and click the Add button to add it to the list of words. Each time you add another word, or change the locale, strength, or decomposition mode, the list of words is sorted again. An = sign indicates words that are considered identical (see Figure 7.3).



**Figure 7.3** The CollationTest program

The locale names are displayed in sorted order, using the collator of the default locale. If you run this program with the US English locale, note that

“Norwegian (Norway,Nynorsk)” comes before “Norwegian (Norway)”, even though the Unicode value of the comma character is greater than the Unicode value of the closing parenthesis.

---

**Listing 7.3** collation/CollationTest2.java

---

[Click here to view code image](#)

```
1 package collation;
2
3 import java.text.*;
4 import java.util.*;
5 import util.*;
6
7 /**
8 * This program demonstrates collating strings under various
9 * locales.
10 * @version 2.0 2021-09-23
11 * @author Cay Horstmann
12 */
13 public class CollationTest2
14 {
15 public static void main(String[] args)
16 {
17 Scanner in = new Scanner(System.in);
18 var locales = (Locale[])
19 NumberFormat.getAvailableLocales().clone();
20 Arrays.sort(locales,
21 Comparator.comparing(Locale::getDisplayName));
22 Locale loc = Choices.choose(in, locales,
23 Locale::getDisplayName);
24
25 Collator coll = Collator.getInstance(loc);
26 int strength = Choices.choose(in, Collator.class,
27 "Primary", "Secondary", "Tertiary", "Identical");
28 int decomposition = Choices.choose(in, Collator.class,
29 "Canonical Decomposition", "Full Decomposition",
30 "No Decomposition");
```

```
26
27 List<String> strings = new ArrayList<>();
28 strings.add("America");
29 strings.add("able");
30 strings.add("Zulu");
31 strings.add("zebra");
32 strings.add("\u00C5ngstr\u00F6m");
33 strings.add("A\u030angstro\u0308m");
34 strings.add("Angstrom");
35 strings.add("Able");
36 strings.add("office");
37 strings.add("o\uFB03ce");
38 strings.add("Java\u2122");
39 strings.add("JavaTM");
40
41 coll.setStrength(strength);
42 coll.setDecomposition(decomposition);
43
44 strings.sort(coll);
45
46 for (int i = 0; i < strings.size(); i++)
47 {
48 String s = strings.get(i);
49 if (i > 0 && coll.compare(s, strings.get(i - 1)) == 0)
50 System.out.print("= ");
51 System.out.println(s);
52 }
53 }
54 }
```

---

## java.text.Collator 1.1

- static Locale[] getAvailableLocales()  
returns an array of Locale objects for which Collator objects are available.

- `static Collator getInstance()`
- `static Collator getInstance(Locale l)`

return a collator for the default locale or the given locale.
- `int compare(String a, String b)`

returns a negative value if a comes before b, 0 if they are considered identical, and a positive value otherwise.
- `boolean equals(String a, String b)`

returns true if a and b are considered identical, false otherwise.
- `void setStrength(int strength)`
- `int getStrength()`

set or get the strength of the collator. Stronger collators tell more words apart. Strength values are Collator.PRIMARY, Collator.SECONDARY, and Collator.TERTIARY.
- `void setDecomposition(int decomp)`
- `int getDecompositon()`

set or get the decomposition mode of the collator. The more a collator decomposes a string, the more strict it will be in deciding whether two strings should be considered identical. Decomposition values are Collator.NO\_DECOMPOSITION, Collator.CANONICAL\_DECOMPOSITION, and Collator.FULL\_DECOMPOSITION.
- `CollationKey getCollationKey(String a)`

returns a collation key that contains a decomposition of the characters in a form that can be quickly compared against another collation key.

- `int compareTo(CollationKey b)`  
returns a negative value if this key comes before `b`, 0 if they are considered identical, and a positive value otherwise.

## **java.text.Normalizer 6**

- `static String normalize(CharSequence str, Normalizer.Form form)`  
returns the normalized form of `str`. The `form` value is one of NFD, NFKD, NFC, or NFKC.

## **7.5 Message Formatting**

The Java library has a `MessageFormat` class that formats text with variable parts. It is similar to formatting with the `printf` method, but it supports locales and formats for numbers and dates. We will examine that mechanism in the following sections.

### **7.5.1 Formatting Numbers and Dates**

Here is a typical message format string:

[Click here to view code image](#)

```
"On {2}, a {0} destroyed {1} houses and caused {3} of damage."
```

The numbers in braces are placeholders for actual names and values. The static method `MessageFormat.format` lets you substitute values for the variables. It is a “varargs” method, so you can simply supply the parameters as follows:

[Click here to view code image](#)

```
String msg
= MessageFormat.format("On {2}, a {0} destroyed {1} houses
and caused {3} of damage.",
"hurricane", 99, new GregorianCalendar(1999, 0,
1).getTime(), 10.0E8);
```

In this example, the placeholder {0} is replaced with "hurricane", {1} is replaced with 99, and so on.

The result of our example is the string

[Click here to view code image](#)

```
On 1/1/99 12:00 AM, a hurricane destroyed 99 houses and caused
100,000,000 of damage.
```

That is a start, but it is not perfect. We don't want to display the time "12:00 AM," and we want the damage amount printed as a currency value. The way we do this is by supplying an optional format for some of the placeholders:

[Click here to view code image](#)

```
"On {2,date,long}, a {0} destroyed {1} houses and caused
{3,number,currency} of damage."
```

This example code prints:

[Click here to view code image](#)

```
On January 1, 1999, a hurricane destroyed 99 houses and caused
$100,000,000 of damage.
```

In general, the placeholder index can be followed by a *type* and a *style*. Separate the index, type, and style by commas. The type can be any of

- number
- time
- date
- choice

If the type is number, then the style can be

integer  
currency  
percent

or it can be a `DecimalFormat` pattern such as `$,##0`—see [Section 7.2.2, “The DecimalFormat Class,”](#) on p. 399 for the possible formats.

If the type is either `time` or `date`, then the style can be

short  
medium  
long  
full

or a date format pattern such as `yyyy-MM-dd`. (See the documentation of the `SimpleDateFormat` class for the possible formats.)

---



## Caution

The static `MessageFormat.format` method uses the current locale to format the values. To format with an arbitrary locale, you have to work a bit harder because there is no “varargs” method that you can use. You need to place the values to be formatted into an `Object[]` array, like this:

[Click here to view code image](#)

```
var mf = new MessageFormat(pattern, loc);
String msg = mf.format(new Object[] { values });
```

---

### **java.text.MessageFormat 1.1**

- `MessageFormat(String pattern)`

- `MessageFormat(String pattern, Locale loc)`  
construct a message format object with the specified pattern and locale.
- `void applyPattern(String pattern)`  
sets the pattern of a message format object to the specified pattern.
- `void setLocale(Locale loc)`
- `Locale getLocale()`  
set or get the locale to be used for the placeholders in the message. The locale is *only* used for subsequent patterns that you set by calling the `applyPattern` method.
- `static String format(String pattern, Object... args)`  
formats the pattern string by using `args[i]` as input for placeholder `{i}`.
- `StringBuffer format(Object args, StringBuffer result, FieldPosition pos)`  
formats the pattern of this `MessageFormat`. The `args` parameter must be an array of objects. The formatted string is appended to `result`, and `result` is returned. If `pos` equals new `FieldPosition(MessageFormat.Field.ARGUMENT)`, its `beginIndex` and `endIndex` properties are set to the location of the text that replaces the `{1}` placeholder. Supply `null` if you are not interested in position information.

## **java.text.Format 1.1**

- `String format(Object obj)`

formats the given object, according to the rules of this formatter. This method calls `format(obj, new StringBuffer(), new FieldPosition(1)).toString()`.

## 7.5.2 Choice Formats

Let's look closer at the pattern of the preceding section:

[Click here to view code image](#)

```
"On {2}, a {0} destroyed {1} houses and caused {3} of damage."
```

If we replace the disaster placeholder `{0}` with "earthquake", the sentence is not grammatically correct in English:

[Click here to view code image](#)

```
On January 1, 1999, a earthquake destroyed . . .
```

What we really want to do is integrate the article "a" into the placeholder:

[Click here to view code image](#)

```
"On {2}, {0} destroyed {1} houses and caused {3} of damage."
```

The `{0}` would then be replaced with "a hurricane" or "an earthquake". That is especially appropriate if this message needs to be translated into a language where the gender of a word affects the article. For example, in German, the pattern would be

[Click here to view code image](#)

```
"{0} zerstörte am {2} {1} Häuser und richtete einen Schaden von
{3} an."
```

The placeholder would then be replaced with the grammatically correct combination of article and noun, such as "Ein Wirbelsturm" or "Eine Naturkatastrophe".

Now let us turn to the `{1}` parameter. If the disaster wasn't all that catastrophic, `{1}` might be replaced with the number 1, and the message would read:

[Click here to view code image](#)

```
On January 1, 1999, a mudslide destroyed 1 houses and . . .
```

Ideally, we would like the message to vary according to the placeholder value, so it would read

```
no houses
one house
2 houses
. . .
```

depending on the placeholder value. The `choice` formatting option was designed for this purpose.

A choice format is a sequence of pairs, each containing

- A *lower limit*
- A *format string*

The lower limit and format string are separated by a `#` character, and the pairs are separated by `|` characters.

For example,

[Click here to view code image](#)

```
{1,choice,0#no houses|1#one house|2#{1} houses}
```

Table 7.10 shows the effect of this format string for various values of `{1}`.

**Table 7.10** String Formatted by Choice Format

<code>{1}</code>	<b>Result</b>	<code>{1}</code>	<b>Result</b>
0	"no houses"	3	"3 houses"

<b>{1}</b>	<b>Result</b>	<b>{1}</b>	<b>Result</b>
1	"one house"	-1	"no houses"

Why do we use {1} twice in the format string? When the message format applies the choice format to the {1} placeholder and the value is 2, the choice format returns "{1} houses". That string is then formatted again by the message format, and the answer is spliced into the result.

---



## Note

This example shows that the designer of the choice format was a bit muddleheaded. If you have three format strings, you need two limits to separate them. In general, you need *one fewer limit* than you have format strings. As you saw in [Table 7.10](#), the `MessageFormat` class ignores the first limit.

The syntax would have been a lot clearer if the designer of this class realized that the limits belong *between* the choices, such as

[Click here to view code image](#)

```
no houses|1|one house|2|{1} houses // not the actual format
```

---

You can use the < symbol to denote that a choice should be selected if the lower bound is strictly less than the value.

You can also use the  $\leq$  symbol (expressed as the Unicode character code \u2264) as a synonym for #. If you like, you can even specify a lower bound of  $-\infty$  as -\u221E for the first value.

For example,

[Click here to view code image](#)

```
-\u221E<no houses|0<one house|2\leq{1} houses
```

or, using Unicode escapes,

[Click here to view code image](#)

```
-\u221E<no houses|0<one house|2\u2264{1} houses
```

Let's finish our natural disaster scenario. If we put the choice string inside the original message string, we get the following format instruction:

[Click here to view code image](#)

```
String pattern = "On {2,date,long}, {0} destroyed {1,choice,0#no
houses|1#one house|2#{1}
houses}" + "and caused {3,number,currency} of damage.;"
```

Or, in German,

[Click here to view code image](#)

```
String pattern
= "{0} zerstörte am {2,date,long} {1,choice,0#kein Haus|1#ein
Haus|2#{1} Häuser}"
+ "und richtete einen Schaden von {3,number,currency}
an.;"
```

Note that the ordering of the words is different in German, but the array of objects you pass to the `format` method is the *same*. The order of the placeholders in the format string takes care of the changes in the word ordering.

## 7.6 Text Input and Output

As you know, the Java programming language itself is fully Unicode-based. However, Windows and Mac OS X still support legacy character encodings such as Windows-1252 or Mac Roman in Western European countries, or Big5 in Taiwan. Therefore, communicating with your users through text is not as simple as it should be. The following sections discuss the complications that you may encounter.

### 7.6.1 Text Files

Nowadays, it is best to use UTF-8 for saving and loading text files. But you may need to work with legacy files. If you know the expected character encoding, you can specify it when writing or reading text files:

[Click here to view code image](#)

```
var out = new PrintWriter(filename, "Windows-1252");
```

For a guess of the best encoding to use, get the “platform encoding” by calling

[Click here to view code image](#)

```
Charset platformEncoding = Charset.defaultCharset();
```

## 7.6.2 Line Endings

This isn't an issue of locales but of platforms. On Windows, text files are expected to use `\r\n` at the end of each line, where UNIX-based systems only require a `\n` character. Nowadays, most Windows programs can deal with just a `\n`. The notable exception is Notepad. If it is important to you that users can double-click on a text file that your application produces and view it in Notepad, make sure that the text file has proper line endings.

Any line written with the `println` method will be properly terminated. The only problem is if you print strings that contain `\n` characters. They are not automatically modified to the platform line ending.

Instead of using `\n` in strings, you can use `printf` and the `%n` format specifier to produce platform-dependent line endings. For example,

```
out.printf("Hello%nWorld%n");
```

produces

```
Hello\r\nWorld\r\n
```

on Windows and

```
Hello\nWorld\n
```

everywhere else.

### 7.6.3 The Console

If you write programs that communicate with the user through `System.in/System.out` or `System.console()`, you have to face the possibility that the console may use a character encoding that is different from the platform encoding reported by `Charset.defaultCharset()`. This is particularly noticeable when working with the `cmd` shell on Windows. In the US version of Windows 10, the command shell still uses the archaic `IBM437` encoding that originated with IBM personal computers in 1982. There is no official API for revealing that information. The `Charset.defaultCharset()` method will return the `Windows-1252` character set, which is quite different. For example, the euro symbol `€` is present in `Windows-1252` but not in `IBM437`. When you call

```
System.out.println("100 €");
```

the console will display

```
100 ?
```

You can advise your users to switch the character encoding of the console. In Windows, that is achieved with the `chcp` command. For example,

```
chcp 1252
```

changes the console to the `Windows-1252` code page.

Ideally, of course, your users should switch the console to UTF-8. In Windows, the command is

```
chcp 65001
```

Unfortunately, that is not enough to make Java use UTF-8 in the console. It is also necessary to set the platform encoding with the unofficial `file.encoding` system property:

[Click here to view code image](#)

```
java -Dfile.encoding=UTF-8 MyProg
```

#### 7.6.4 Log Files

When log messages from the `java.util.logging` library are sent to the console, they are written in the console encoding. You saw how to control that in the preceding section. However, log messages in a file use a `FileHandler` which, by default, uses the platform encoding.

To change the encoding to UTF-8, you need to change the log manager settings. In the logging configuration file, set

[Click here to view code image](#)

```
java.util.logging.FileHandler.encoding=UTF-8
```

#### 7.6.5 The UTF-8 Byte Order Mark

As already mentioned, it is a good idea to use UTF-8 for text files when you can. However, if your application has to read UTF-8 text files created by other programs, you run into another potential problem. It is perfectly legal to add a “byte order mark” character U+FEFF as the first character of a file. In the UTF-16 encoding, where each code unit is a two-byte quantity, the byte order mark tells a reader whether the file uses “big-endian” or “little-endian” byte ordering. UTF-8 is a single-byte encoding, so there is no need to specify a byte ordering. But if a file starts with bytes 0xEF 0xBB 0xBF (the UTF-8 encoding of U+FEFF), that is a strong indication that it uses UTF-8. For that reason, the Unicode standard encourages this practice. Any reader is supposed to discard an initial byte order mark.

There is just one fly in the ointment. The Oracle Java implementation stubbornly refuses to follow the Unicode standard, citing potential compatibility issues. That means that you, the programmer, must do what the

platform won't do. When you read a text file and encounter a U+FEFF at the beginning, ignore it.

---



### Caution

Unfortunately, the JDK implementors do not follow this advice. When you pass the `javac` compiler a valid UTF-8 source file that starts with a byte order mark, compilation fails with an error message “illegal character: \65279”.

---

### 7.6.6 Character Encoding of Source Files

You, the programmer, will need to communicate with the Java compiler—and you do that with tools on your local system. For example, you can use the Chinese version of Notepad to write your Java source code files. The resulting source code files are *not portable* because they use the local character encoding (GB or Big5, depending on which Chinese operating system you use). Only the compiled class files are portable—they will automatically use the “modified UTF-8” encoding for identifiers and strings. That means that when a program is compiling and running, three character encodings are involved:

- Source files: platform encoding
- Class files: modified UTF-8
- Virtual machine: UTF-16

(See [Chapter 1](#) for a definition of the modified UTF-8 and UTF-16 formats.)

---



### Tip

You can specify the character encoding of your source files with the `-encoding` flag, for example:

[Click here to view code image](#)

```
javac -encoding UTF-8 Myfile.java
```

---

## 7.7 Resource Bundles

When localizing an application, you'll probably have a dauntingly large number of message strings, button labels, and so on, that all need to be translated. To make this task feasible, you'll want to define the message strings in an external location, usually called a *resource*. The person carrying out the translation can then simply edit the resource files without having to touch the source code of the program.

In Java, you can use property files to specify string resources, and you can implement classes for resources of other types.

---



### Note

Java technology resources are not the same as Windows or Macintosh resources. A Macintosh or Windows executable program stores resources, such as menus, dialog boxes, icons, and messages, in a section separate from the program code. A resource editor can inspect and update these resources without affecting the program code.

---



### Note

Volume I, [Chapter 5](#) describes a concept of JAR file resources, whereby data files, sounds, and images can be placed in a JAR file. The `getResource` method of the class `Class` finds the file, opens it, and returns a URL to the resource. By placing your files into the JAR file, you leave the job of finding the files to the class loader—which already knows how to locate items in a JAR file. However, that mechanism has no locale support.

---

### 7.7.1 Locating Resource Bundles

When localizing an application, you produce a set of *resource bundles*. Each bundle is a property file or a class that describes locale-specific items (such as messages, labels, and so on). For each bundle, you have to provide versions for all locales that you want to support.

You need to use a specific naming convention for these bundles. For example, resources specific to Germany go into a file `baseName_de_DE`, whereas those shared by all German-speaking countries go into `baseName_de`. In general, use

`baseName_language_country`

for all country-specific resources, and

`baseName_language`

for all language-specific resources. Finally, as a fallback, you can put defaults into a file without any suffix.

To load a bundle, use the command

[Click here to view code image](#)

```
 ResourceBundle currentResources =
 ResourceBundle.getBundle(baseName, currentLocale);
```

The `getBundle` method attempts to load the bundle that matches the current locale by language and country. If it is not successful, the country and the language are dropped in turn. Then the same search is applied to the default locale, and, finally, the default bundle file is consulted. If even that attempt fails, the method throws a `MissingResourceException`.

That is, the `getBundle` method tries to load the following bundles:

[Click here to view code image](#)

```
baseName_currentLocaleLanguage_currentLocaleCountry
baseName_currentLocaleLanguage
baseName_defaultLocaleLanguage_defaultLocaleCountry
baseName_defaultLocaleLanguage basename
```

Once the `getBundle` method has located a bundle (say, `baseName_de_DE`), it will still keep looking for `baseName_de` and `baseName`. If these bundles exist, they become the *parents* of the `baseName_de_DE` bundle in a *resource hierarchy*. Later, when looking up a resource, the parents are searched if a lookup was not successful in the current bundle. That is, if a particular resource was not found in `baseName_de_DE`, then the `baseName_de` and `baseName` will be queried as well.

This is clearly a very useful service—and one that would be tedious to program by hand. The resource bundle mechanism of the Java programming language automatically locates the items that are the best match for a given locale. It is easy to add more and more localizations to an existing program—all you have to do is create additional resource bundles.

---



### Note

We simplified the discussion of resource bundle lookup. If a locale has a script or variant, the lookup is quite a bit more complex. See the documentation of the method

`ResourceBundle.Control.getCandidateLocales` for the gory details.

---

---



### Tip

You need not place all resources for your application into a single bundle. You could have one bundle for button labels, one for error messages, and so on.

---

## 7.7.2 Property Files

Internationalizing strings is quite straightforward. You place all your strings into a property file such as `MyProgramStrings.properties`. This is simply a text file with one key/value pair per line. A typical file would look like this:

```
computeButton=Rechnen
colorName=black
defaultPaperSize=210×297
```

Then you name your property files as described in the preceding section, for example:

[Click here to view code image](#)

```
MyProgramStrings.properties
MyProgramStrings_en.properties
MyProgramStrings_de_DE.properties
```

You can load the bundle simply as

[Click here to view code image](#)

```
ResourceBundle bundle =
 ResourceBundle.getBundle("MyProgramStrings", locale);
```

To look up a specific string, call

[Click here to view code image](#)

```
String computeButtonLabel = bundle.getString("computeButton");
```



### Caution

Before Java 9, files for storing properties had to be ASCII files. If you are using an old Java version and need to place a Unicode character into

a property file, encode it using the \uxxxx encoding. For example, to specify "colorName=Grün", use

```
colorName=Gr\u00FCn
```

You can use the native2ascii tool to generate these encodings.

---

### 7.7.3 Bundle Classes

To provide resources that are not strings, define classes that extend the ResourceBundle class. Use the standard naming convention to name your classes, for example

[Click here to view code image](#)

```
MyProgramResources.java
MyProgramResources_en.java
MyProgramResources_de_DE.java
```

Load the class with the same getBundle method that you use to load a property file:

[Click here to view code image](#)

```
ResourceBundle bundle =
ResourceBundle.getBundle("MyProgramResources", locale);
```

---



#### Caution

When searching for bundles, a bundle in a class is given preference over a property file when the two bundles have the same base names.

---

Each resource bundle class implements a lookup table. You need to provide a key string for each setting you want to localize, and use that key string to retrieve the setting. For example,

[Click here to view code image](#)

```
var backgroundColor = (Color)
bundle.getObject("backgroundColor");
double[] paperSize = (double[])
bundle.getObject("defaultPaperSize");
```

The simplest way to implement resource bundle classes is to extend the `ListResourceBundle` class. The `ListResourceBundle` lets you place all your resources into an object array and then does the lookup for you. Follow this code outline:

[Click here to view code image](#)

```
public class baseName_language_country extends
ListResourceBundle
{
 private static final Object[][] contents =
 {
 { key1, value2 },
 { key2, value2 },
 . . .
 }
 public Object[][] getContents() { return contents; }
}
```

For example,

[Click here to view code image](#)

```
public class ProgramResources_de extends ListResourceBundle
{
 private static final Object[][] contents =
 {
 { "backgroundColor", Color.black },
 { "defaultPaperSize", new double[] { 210, 297 } }
 }
 public Object[][] getContents() { return contents; }
}
public class ProgramResources_en_US extends ListResourceBundle
```

```
{
 private static final Object[][] contents =
 {
 { "backgroundColor", Color.blue },
 { "defaultPaperSize", new double[] { 216, 279 } }
 }
 public Object[][] getContents() { return contents; }
}
```

---



## Note

The paper sizes are given in millimeters. Everyone on the planet, with the exception of the United States and Canada, uses ISO 216 paper sizes. For more information, see  
[www.cl.cam.ac.uk/~mgk25/iso-paper.html](http://www.cl.cam.ac.uk/~mgk25/iso-paper.html).

---

Alternatively, your resource bundle classes can extend the ResourceBundle class. Then you need to implement two methods, to enumerate all keys and to look up the value for a given key:

[Click here to view code image](#)

```
Enumeration<String> getKeys()
Object handleGetObject(String key)
```

The getObject method of the ResourceBundle class calls the handleGetObject method that you supply.

### **java.util.ResourceBundle 1.1**

- static      ResourceBundle      `getBundle(String  
baseName, Locale loc)`
- static      ResourceBundle      `getBundle(String  
baseName)`

load the resource bundle class with the given name, for the given locale or the default locale, and its parent classes. If the resource bundle classes are located in a package, the base name must contain the full package name, such as "intl.ProgramResources". The resource bundle classes must be public so that the `getBundle` method can access them.

- `Object getObject(String name)`  
looks up an object from the resource bundle or its parents.
- `String getString(String name)`  
looks up an object from the resource bundle or its parents and casts it as a string.
- `String[] getStringArray(String name)`  
looks up an object from the resource bundle or its parents and casts it as a string array.
- `Enumeration<String> getKeys()`  
returns an enumeration object to enumerate the keys of this resource bundle. It enumerates the keys in the parent bundles as well.
- `Object handleGetObject(String key)`  
should be overridden to look up the resource value associated with the given key if you define your own resource lookup mechanism.

## 7.8 A Complete Example

In this section, we apply the material of this chapter to localize a retirement calculator. The program calculates whether or not you are saving enough money for your retirement. You enter your age, how much money you save every month, and so on (see [Figure 7.4](#)).



**Figure 7.4** The retirement calculator in English


The text area and the graph show the balance of the retirement account for every year. If the numbers turn negative toward the later part of your life and the bars in the graph appear below the  $x$  axis, you need to do something—for example, save more money, postpone your retirement, die earlier, or be younger.

The retirement calculator works in three locales (English, German, and Chinese). Here are some of the highlights of the internationalization:


- ▶ The labels, buttons, and messages are translated into German and Chinese. You can find them in the classes `RetireResources_de` and `RetireResources_zh`. English is used as the fallback—see the `RetireResources` file.
- ▶ Whenever the locale changes, we reset the labels and reformat the contents of the text fields.
- ▶ The text fields handle numbers, currency amounts, and percentages in the local format.

- The computation field uses a `MessageFormat`. The format string is stored in the resource bundle of each language.
- Just to show that it can be done, we use different colors for the bar graph, depending on the language chosen by the user.

[Listings 7.4](#) through [7.7](#) show the code. [Listings 7.8](#) through [7.10](#) are the property files for the localized strings. [Figures 7.5](#) and [7.6](#) show the outputs in German and Chinese, respectively. To see Chinese characters, be sure you have Chinese fonts installed and configured with your Java runtime. Otherwise, Chinese characters will show up as “missing character” icons.



**Figure 7.5** The retirement calculator in German



**Figure 7.6** The retirement calculator in Chinese

---

**Listing 7.4** retire/Retire.java

---

[Click here to view code image](#)

```

1 package retire;
2
3 import java.awt.*;
4 import java.awt.geom.*;
5 import java.text.*;
6 import java.util.*;
7
8 import javax.swing.*;
9
10 /**
11 * This program shows a retirement calculator. The UI is
12 * displayed in English, German, and
13 * Chinese.
14 * @version 1.25 2018-05-01

```

```
14 * @author Cay Horstmann
15 */
16 public class Retire
17 {
18 public static void main(String[] args)
19 {
20 EventQueue.invokeLater(() ->
21 {
22 var frame = new RetireFrame();
23
24 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
25 frame.setVisible(true);
26 });
27 }
28
29 class RetireFrame extends JFrame
30 {
31 private JTextField savingsField = new JTextField(10);
32 private JTextField contribField = new JTextField(10);
33 private JTextField incomeField = new JTextField(10);
34 private JTextField currentAgeField = new JTextField(4);
35 private JTextField retireAgeField = new JTextField(4);
36 private JTextField deathAgeField = new JTextField(4);
37 private JTextField inflationPercentField = new
JTextField(6);
38 private JTextField investPercentField = new JTextField(6);
39 private JTextArea retireText = new JTextArea(10, 25);
40 private RetireComponent retireCanvas = new
RetireComponent();
41 private JButton computeButton = new JButton();
42 private JLabel languageLabel = new JLabel();
43 private JLabel savingsLabel = new JLabel();
44 private JLabel contribLabel = new JLabel();
45 private JLabel incomeLabel = new JLabel();
46 private JLabel currentAgeLabel = new JLabel();
47 private JLabel retireAgeLabel = new JLabel();
48 private JLabel deathAgeLabel = new JLabel();
```

```
49 private JLabel inflationPercentLabel = new JLabel();
50 private JLabel investPercentLabel = new JLabel();
51 private RetireInfo info = new RetireInfo();
52 private Locale[] locales = { Locale.US, Locale.CHINA,
53 Locale.GERMANY };
54 private Locale currentLocale;
55 private JComboBox<Locale> localeCombo = new
56 LocaleCombo(locales);
57 private ResourceBundle res;
58 private ResourceBundle resStrings;
59 private NumberFormat currencyFmt;
60 private NumberFormat numberFmt;
61 private NumberFormat percentFmt;
62
63 public RetireFrame()
64 {
65 setLayout(new GridBagLayout());
66 add(languageLabel, new GBC(0, 0).setAnchor(GBC.EAST));
67 add(savingsLabel, new GBC(0, 1).setAnchor(GBC.EAST));
68 add(contribLabel, new GBC(2, 1).setAnchor(GBC.EAST));
69 add(incomeLabel, new GBC(4, 1).setAnchor(GBC.EAST));
70 add(currentAgeLabel, new GBC(0, 2).setAnchor(GBC.EAST));
71 add(retireAgeLabel, new GBC(2, 2).setAnchor(GBC.EAST));
72 add(deathAgeLabel, new GBC(4, 2).setAnchor(GBC.EAST));
73 add(inflationPercentLabel, new GBC(0,
74 3).setAnchor(GBC.EAST));
74 add(investPercentLabel, new GBC(2,
75 3).setAnchor(GBC.EAST));
75 add(localeCombo, new GBC(1, 0, 3, 1));
76 add(savingsField, new GBC(1, 1).setWeight(100,
77 0).setFill(GBC.HORIZONTAL));
78 add(contribField, new GBC(3, 1).setWeight(100,
79 0).setFill(GBC.HORIZONTAL));
80 add(incomeField, new GBC(5, 1).setWeight(100,
81 0).setFill(GBC.HORIZONTAL));
82 add(currentAgeField, new GBC(1, 2).setWeight(100,
83 0).setFill(GBC.HORIZONTAL));
84 add(retireAgeField, new GBC(3, 2).setWeight(100,
```

```
0).setFill(GBC.HORIZONTAL));
79 add(deathAgeField, new GBC(5, 2).setWeight(100,
0).setFill(GBC.HORIZONTAL));
80 add(inflationPercentField, new GBC(1,
3).setWeight(100, 0).setFill(GBC.HORIZONTAL));
81 add(investPercentField, new GBC(3, 3).setWeight(100,
0).setFill(GBC.HORIZONTAL));
82 add(retireCanvas, new GBC(0, 4, 4, 1).setWeight(100,
100).setFill(GBC.BOTH));
83 add(new JScrollPane(retireText),
84 new GBC(4, 4, 2, 1).setWeight(0,
100).setFill(GBC.BOTH));
85
86 computeButton.setName("computeButton");
87 computeButton.addActionListener(event ->
88 {
89 getInfo();
90 updateData();
91 updateGraph();
92 });
93 add(computeButton, new GBC(5, 3));
94
95 retireText.setEditable(false);
96 retireText.setFont(new Font("Monospaced", Font.PLAIN,
10));
97
98 info.setSavings(0);
99 info.setContrib(9000);
100 info.setIncome(60000);
101 info.setCurrentAge(35);
102 info.setRetireAge(65);
103 info.setDeathAge(85);
104 info.setInvestPercent(0.1);
105 info.setInflationPercent(0.05);
106
107 int localeIndex = 0; // US locale is default
selection
108 for (int i = 0; i < locales.length; i++)
```

```
109 // if current locale one of the choices, select it
110 if (getLocale().equals(locales[i])) localeIndex =
111 i;
112 setCurrentLocale(locales[localeIndex]);
113
114 localeCombo.addActionListener(event ->
115 {
116 setCurrentLocale((Locale)
117 localeCombo.getSelectedItem());
118 validate();
119 });
120
121 /**
122 * Sets the current locale.
123 * @param locale the desired locale
124 */
125 public void setCurrentLocale(Locale locale)
126 {
127 currentLocale = locale;
128 localeCombo.setLocale(currentLocale);
129 localeCombo.setSelectedItem(currentLocale);
130
131 res =
132 ResourceBundle.getBundle("retire.RetireResources", currentLocale);
133 resStrings =
134 ResourceBundle.getBundle("retire.RetireStrings", currentLocale);
135 currencyFmt =
136 NumberFormat.getCurrencyInstance(currentLocale);
137 numberFmt =
138 NumberFormat.getNumberInstance(currentLocale);
139 percentFmt =
140 NumberFormat.getPercentInstance(currentLocale);
141
142 updateDisplay();
143 updateInfo();
144 updateData();
```

```
140 updateGraph();
141 }
142
143 /**
144 * Updates all labels in the display.
145 */
146 public void updateDisplay()
147 {
148
149 languageLabel.setText(resStrings.getString("language"));
150 savingsLabel.setText(resStrings.getString("savings"));
151 contribLabel.setText(resStrings.getString("contrib"));
152 incomeLabel.setText(resStrings.getString("income"));
153
154 currentAgeLabel.setText(resStrings.getString("currentAge"));
155
156 retireAgeLabel.setText(resStrings.getString("retireAge"));
157
158 deathAgeLabel.setText(resStrings.getString("deathAge"));
159
160 inflationPercentLabel.setText(resStrings.getString("inflationPerce
161 nt"));
162
163 investPercentLabel.setText(resStrings.getString("investPercent"));
164
165 computeButton.setText(resStrings.getString("computeButton"));
166
167 }
168
169 /**
170 * Updates the information in the text fields.
171 */
172
173 public void updateInfo()
174 {
175
176 savingsField.setText(currencyFmt.format(info.getSavings()));
177
178 contribField.setText(currencyFmt.format(info.getContrib()));
179
180 }
181
182 /**
183 * Updates the graph with the new data.
184 */
185
186 public void updateGraph()
187 {
188
189 // Get the current values from the text fields
190 double savings = Double.parseDouble(savingsField.getText());
191 double contrib = Double.parseDouble(contribField.getText());
192
193 // Create a new Info object with the updated values
194 Info info = new Info(savings, contrib);
195
196 // Call the calculate() method on the info object
197 info.calculate();
198
199 // Set the new values in the text fields
200 savingsField.setText(currencyFmt.format(info.getSavings()));
201 contribField.setText(currencyFmt.format(info.getContrib()));
202
203 }
204
205 /**
206 * Handles the button click event.
207 */
208
209 public void actionPerformed(ActionEvent e)
210 {
211
212 // Get the button that was clicked
213 JButton button = (JButton) e.getSource();
214
215 // If the button is the "Compute" button, call the updateInfo() method
216 if (button == computeButton)
217 updateInfo();
218
219 // If the button is the "Update" button, call the updateDisplay() method
220 if (button == updateButton)
221 updateDisplay();
222
223 }
224
225 /**
226 * Sets up the GUI components.
227 */
228
229 public void init()
230 {
231
232 // Create the main window
233 frame = new JFrame("Financial Planner");
234
235 // Create the title bar
236 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
237
238 // Create the content pane
239 contentPane = frame.getContentPane();
240
241 // Create the labels
242 languageLabel = new JLabel("Language:");
243 savingsLabel = new JLabel("Savings:");
244 contribLabel = new JLabel("Contributions:");
245 incomeLabel = new JLabel("Income:");
246
247 // Create the text fields
248 savingsField = new JTextField("0.00");
249 contribField = new JTextField("0.00");
250
251 // Create the buttons
252 computeButton = new JButton("Compute");
253 updateButton = new JButton("Update");
254
255 // Create the inflation and investment percent labels
256 inflationPercentLabel = new JLabel("Inflation Percent:");
257 investPercentLabel = new JLabel("Investment Percent:");
258
259 // Create the retirement age labels
260 currentAgeLabel = new JLabel("Current Age:");
261 retireAgeLabel = new JLabel("Retirement Age:");
262 deathAgeLabel = new JLabel("Death Age:");
263
264 // Create the inflation and investment percent labels
265 inflationPercentLabel = new JLabel("Inflation Percent:");
266 investPercentLabel = new JLabel("Investment Percent:");
267
268 // Create the graph
269 graphPanel = new GraphPanel();
270
271 // Add the components to the content pane
272 contentPane.add(languageLabel, "Language");
273 contentPane.add(savingsLabel, "Savings");
274 contentPane.add(contribLabel, "Contributions");
275 contentPane.add(incomeLabel, "Income");
276
277 contentPane.add(savingsField, "Savings");
278 contentPane.add(contribField, "Contributions");
279
280 contentPane.add(computeButton, "Compute");
281 contentPane.add(updateButton, "Update");
282
283 contentPane.add(inflationPercentLabel, "Inflation Percent");
284 contentPane.add(investPercentLabel, "Investment Percent");
285
286 contentPane.add(currentAgeLabel, "Current Age");
287 contentPane.add(retireAgeLabel, "Retirement Age");
288 contentPane.add(deathAgeLabel, "Death Age");
289
290 contentPane.add(graphPanel, "Graph");
291
292 // Set the title of the window
293 frame.setTitle("Financial Planner");
294
295 // Set the size of the window
296 frame.setSize(400, 300);
297
298 // Set the location of the window
299 frame.setLocationRelativeTo(null);
300
301 // Show the window
302 frame.setVisible(true);
303
304 }
305
306 /**
307 * Formats the double value as a currency string.
308 */
309
310 public String formatCurrency(double value)
311 {
312
313 // Create a new DecimalFormat object
314 DecimalFormat currencyFmt = new DecimalFormat("###,###.##");
315
316 // Format the value as a currency string
317 String formattedValue = currencyFmt.format(value);
318
319 return formattedValue;
320
321 }
322
323 /**
324 * Updates the graph with the new data.
325 */
326
327 public void updateGraph()
328 {
329
330 // Get the current values from the text fields
331 double savings = Double.parseDouble(savingsField.getText());
332 double contrib = Double.parseDouble(contribField.getText());
333
334 // Create a new Info object with the updated values
335 Info info = new Info(savings, contrib);
336
337 // Call the calculate() method on the info object
338 info.calculate();
339
340 // Set the new values in the text fields
341 savingsField.setText(currencyFmt.format(info.getSavings()));
342 contribField.setText(currencyFmt.format(info.getContrib()));
343
344 }
345
346 /**
347 * Handles the button click event.
348 */
349
350 public void actionPerformed(ActionEvent e)
351 {
352
353 // Get the button that was clicked
354 JButton button = (JButton) e.getSource();
355
356 // If the button is the "Compute" button, call the updateInfo() method
357 if (button == computeButton)
358 updateInfo();
359
360 // If the button is the "Update" button, call the updateDisplay() method
361 if (button == updateButton)
362 updateDisplay();
363
364 }
365
366 /**
367 * Sets up the GUI components.
368 */
369
370 public void init()
371 {
372
373 // Create the main window
374 frame = new JFrame("Financial Planner");
375
376 // Create the title bar
377 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
378
379 // Create the content pane
380 contentPane = frame.getContentPane();
381
382 // Create the labels
383 languageLabel = new JLabel("Language:");
384 savingsLabel = new JLabel("Savings:");
385 contribLabel = new JLabel("Contributions:");
386 incomeLabel = new JLabel("Income:");
387
388 // Create the text fields
389 savingsField = new JTextField("0.00");
390 contribField = new JTextField("0.00");
391
392 // Create the buttons
393 computeButton = new JButton("Compute");
394 updateButton = new JButton("Update");
395
396 // Create the inflation and investment percent labels
397 inflationPercentLabel = new JLabel("Inflation Percent:");
398 investPercentLabel = new JLabel("Investment Percent:");
399
400 // Create the retirement age labels
401 currentAgeLabel = new JLabel("Current Age:");
402 retireAgeLabel = new JLabel("Retirement Age:");
403 deathAgeLabel = new JLabel("Death Age:");
404
405 // Create the inflation and investment percent labels
406 inflationPercentLabel = new JLabel("Inflation Percent:");
407 investPercentLabel = new JLabel("Investment Percent:");
408
409 // Create the graph
410 graphPanel = new GraphPanel();
411
412 // Add the components to the content pane
413 contentPane.add(languageLabel, "Language");
414 contentPane.add(savingsLabel, "Savings");
415 contentPane.add(contribLabel, "Contributions");
416 contentPane.add(incomeLabel, "Income");
417
418 contentPane.add(savingsField, "Savings");
419 contentPane.add(contribField, "Contributions");
420
421 contentPane.add(computeButton, "Compute");
422 contentPane.add(updateButton, "Update");
423
424 contentPane.add(inflationPercentLabel, "Inflation Percent");
425 contentPane.add(investPercentLabel, "Investment Percent");
426
427 contentPane.add(currentAgeLabel, "Current Age");
428 contentPane.add(retireAgeLabel, "Retirement Age");
429 contentPane.add(deathAgeLabel, "Death Age");
430
431 contentPane.add(graphPanel, "Graph");
432
433 // Set the title of the window
434 frame.setTitle("Financial Planner");
435
436 // Set the size of the window
437 frame.setSize(400, 300);
438
439 // Set the location of the window
440 frame.setLocationRelativeTo(null);
441
442 // Show the window
443 frame.setVisible(true);
444
445 }
446
447 /**
448 * Formats the double value as a currency string.
449 */
450
451 public String formatCurrency(double value)
452 {
453
454 // Create a new DecimalFormat object
455 DecimalFormat currencyFmt = new DecimalFormat("###,###.##");
456
457 // Format the value as a currency string
458 String formattedValue = currencyFmt.format(value);
459
460 return formattedValue;
461
462 }
463
464 /**
465 * Updates the graph with the new data.
466 */
467
468 public void updateGraph()
469 {
470
471 // Get the current values from the text fields
472 double savings = Double.parseDouble(savingsField.getText());
473 double contrib = Double.parseDouble(contribField.getText());
474
475 // Create a new Info object with the updated values
476 Info info = new Info(savings, contrib);
477
478 // Call the calculate() method on the info object
479 info.calculate();
480
481 // Set the new values in the text fields
482 savingsField.setText(currencyFmt.format(info.getSavings()));
483 contribField.setText(currencyFmt.format(info.getContrib()));
484
485 }
486
487 /**
488 * Handles the button click event.
489 */
490
491 public void actionPerformed(ActionEvent e)
492 {
493
494 // Get the button that was clicked
495 JButton button = (JButton) e.getSource();
496
497 // If the button is the "Compute" button, call the updateInfo() method
498 if (button == computeButton)
499 updateInfo();
500
501 // If the button is the "Update" button, call the updateDisplay() method
502 if (button == updateButton)
503 updateDisplay();
504
505 }
506
507 /**
508 * Sets up the GUI components.
509 */
510
511 public void init()
512 {
513
514 // Create the main window
515 frame = new JFrame("Financial Planner");
516
517 // Create the title bar
518 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
519
520 // Create the content pane
521 contentPane = frame.getContentPane();
522
523 // Create the labels
524 languageLabel = new JLabel("Language:");
525 savingsLabel = new JLabel("Savings:");
526 contribLabel = new JLabel("Contributions:");
527 incomeLabel = new JLabel("Income:");
528
529 // Create the text fields
530 savingsField = new JTextField("0.00");
531 contribField = new JTextField("0.00");
532
533 // Create the buttons
534 computeButton = new JButton("Compute");
535 updateButton = new JButton("Update");
536
537 // Create the inflation and investment percent labels
538 inflationPercentLabel = new JLabel("Inflation Percent:");
539 investPercentLabel = new JLabel("Investment Percent:");
540
541 // Create the retirement age labels
542 currentAgeLabel = new JLabel("Current Age:");
543 retireAgeLabel = new JLabel("Retirement Age:");
544 deathAgeLabel = new JLabel("Death Age:");
545
546 // Create the inflation and investment percent labels
547 inflationPercentLabel = new JLabel("Inflation Percent:");
548 investPercentLabel = new JLabel("Investment Percent:");
549
550 // Create the graph
551 graphPanel = new GraphPanel();
552
553 // Add the components to the content pane
554 contentPane.add(languageLabel, "Language");
555 contentPane.add(savingsLabel, "Savings");
556 contentPane.add(contribLabel, "Contributions");
557 contentPane.add(incomeLabel, "Income");
558
559 contentPane.add(savingsField, "Savings");
560 contentPane.add(contribField, "Contributions");
561
562 contentPane.add(computeButton, "Compute");
563 contentPane.add(updateButton, "Update");
564
565 contentPane.add(inflationPercentLabel, "Inflation Percent");
566 contentPane.add(investPercentLabel, "Investment Percent");
567
568 contentPane.add(currentAgeLabel, "Current Age");
569 contentPane.add(retireAgeLabel, "Retirement Age");
570 contentPane.add(deathAgeLabel, "Death Age");
571
572 contentPane.add(graphPanel, "Graph");
573
574 // Set the title of the window
575 frame.setTitle("Financial Planner");
576
577 // Set the size of the window
578 frame.setSize(400, 300);
579
580 // Set the location of the window
581 frame.setLocationRelativeTo(null);
582
583 // Show the window
584 frame.setVisible(true);
585
586 }
587
588 /**
589 * Formats the double value as a currency string.
590 */
591
592 public String formatCurrency(double value)
593 {
594
595 // Create a new DecimalFormat object
596 DecimalFormat currencyFmt = new DecimalFormat("###,###.##");
597
598 // Format the value as a currency string
599 String formattedValue = currencyFmt.format(value);
600
601 return formattedValue;
602
603 }
604
605 /**
606 * Updates the graph with the new data.
607 */
608
609 public void updateGraph()
610 {
611
612 // Get the current values from the text fields
613 double savings = Double.parseDouble(savingsField.getText());
614 double contrib = Double.parseDouble(contribField.getText());
615
616 // Create a new Info object with the updated values
617 Info info = new Info(savings, contrib);
618
619 // Call the calculate() method on the info object
620 info.calculate();
621
622 // Set the new values in the text fields
623 savingsField.setText(currencyFmt.format(info.getSavings()));
624 contribField.setText(currencyFmt.format(info.getContrib()));
625
626 }
627
628 /**
629 * Handles the button click event.
630 */
631
632 public void actionPerformed(ActionEvent e)
633 {
634
635 // Get the button that was clicked
636 JButton button = (JButton) e.getSource();
637
638 // If the button is the "Compute" button, call the updateInfo() method
639 if (button == computeButton)
640 updateInfo();
641
642 // If the button is the "Update" button, call the updateDisplay() method
643 if (button == updateButton)
644 updateDisplay();
645
646 }
647
648 /**
649 * Sets up the GUI components.
650 */
651
652 public void init()
653 {
654
655 // Create the main window
656 frame = new JFrame("Financial Planner");
657
658 // Create the title bar
659 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
660
661 // Create the content pane
662 contentPane = frame.getContentPane();
663
664 // Create the labels
665 languageLabel = new JLabel("Language:");
666 savingsLabel = new JLabel("Savings:");
667 contribLabel = new JLabel("Contributions:");
668 incomeLabel = new JLabel("Income:");
669
670 // Create the text fields
671 savingsField = new JTextField("0.00");
672 contribField = new JTextField("0.00");
673
674 // Create the buttons
675 computeButton = new JButton("Compute");
676 updateButton = new JButton("Update");
677
678 // Create the inflation and investment percent labels
679 inflationPercentLabel = new JLabel("Inflation Percent:");
680 investPercentLabel = new JLabel("Investment Percent:");
681
682 // Create the retirement age labels
683 currentAgeLabel = new JLabel("Current Age:");
684 retireAgeLabel = new JLabel("Retirement Age:");
685 deathAgeLabel = new JLabel("Death Age:");
686
687 // Create the inflation and investment percent labels
688 inflationPercentLabel = new JLabel("Inflation Percent:");
689 investPercentLabel = new JLabel("Investment Percent:");
690
691 // Create the graph
692 graphPanel = new GraphPanel();
693
694 // Add the components to the content pane
695 contentPane.add(languageLabel, "Language");
696 contentPane.add(savingsLabel, "Savings");
697 contentPane.add(contribLabel, "Contributions");
698 contentPane.add(incomeLabel, "Income");
699
700 contentPane.add(savingsField, "Savings");
701 contentPane.add(contribField, "Contributions");
702
703 contentPane.add(computeButton, "Compute");
704 contentPane.add(updateButton, "Update");
705
706 contentPane.add(inflationPercentLabel, "Inflation Percent");
707 contentPane.add(investPercentLabel, "Investment Percent");
708
709 contentPane.add(currentAgeLabel, "Current Age");
710 contentPane.add(retireAgeLabel, "Retirement Age");
711 contentPane.add(deathAgeLabel, "Death Age");
712
713 contentPane.add(graphPanel, "Graph");
714
715 // Set the title of the window
716 frame.setTitle("Financial Planner");
717
718 // Set the size of the window
719 frame.setSize(400, 300);
720
721 // Set the location of the window
722 frame.setLocationRelativeTo(null);
723
724 // Show the window
725 frame.setVisible(true);
726
727 }
728
729 /**
730 * Formats the double value as a currency string.
731 */
732
733 public String formatCurrency(double value)
734 {
735
736 // Create a new DecimalFormat object
737 DecimalFormat currencyFmt = new DecimalFormat("###,###.##");
738
739 // Format the value as a currency string
740 String formattedValue = currencyFmt.format(value);
741
742 return formattedValue;
743
744 }
745
746 /**
747 * Updates the graph with the new data.
748 */
749
750 public void updateGraph()
751 {
752
753 // Get the current values from the text fields
754 double savings = Double.parseDouble(savingsField.getText());
755 double contrib = Double.parseDouble(contribField.getText());
756
757 // Create a new Info object with the updated values
758 Info info = new Info(savings, contrib);
759
760 // Call the calculate() method on the info object
761 info.calculate();
762
763 // Set the new values in the text fields
764 savingsField.setText(currencyFmt.format(info.getSavings()));
765 contribField.setText(currencyFmt.format(info.getContrib()));
766
767 }
768
769 /**
770 * Handles the button click event.
771 */
772
773 public void actionPerformed(ActionEvent e)
774 {
775
776 // Get the button that was clicked
777 JButton button = (JButton) e.getSource();
778
779 // If the button is the "Compute" button, call the updateInfo() method
780 if (button == computeButton)
781 updateInfo();
782
783 // If the button is the "Update" button, call the updateDisplay() method
784 if (button == updateButton)
785 updateDisplay();
786
787 }
788
789 /**
790 * Sets up the GUI components.
791 */
792
793 public void init()
794 {
795
796 // Create the main window
797 frame = new JFrame("Financial Planner");
798
799 // Create the title bar
800 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
801
802 // Create the content pane
803 contentPane = frame.getContentPane();
804
805 // Create the labels
806 languageLabel = new JLabel("Language:");
807 savingsLabel = new JLabel("Savings:");
808 contribLabel = new JLabel("Contributions:");
809 incomeLabel = new JLabel("Income:");
810
811 // Create the text fields
812 savingsField = new JTextField("0.00");
813 contribField = new JTextField("0.00");
814
815 // Create the buttons
816 computeButton = new JButton("Compute");
817 updateButton = new JButton("Update");
818
819 // Create the inflation and investment percent labels
820 inflationPercentLabel = new JLabel("Inflation Percent:");
821 investPercentLabel = new JLabel("Investment Percent:");
822
823 // Create the retirement age labels
824 currentAgeLabel = new JLabel("Current Age:");
825 retireAgeLabel = new JLabel("Retirement Age:");
826 deathAgeLabel = new JLabel("Death Age:");
827
828 // Create the inflation and investment percent labels
829 inflationPercentLabel = new JLabel("Inflation Percent:");
830 investPercentLabel = new JLabel("Investment Percent:");
831
832 // Create the graph
833 graphPanel = new GraphPanel();
834
835 // Add the components to the content pane
836 contentPane.add(languageLabel, "Language");
837 contentPane.add(savingsLabel, "Savings");
838 contentPane.add(contribLabel, "Contributions");
839 contentPane.add(incomeLabel, "Income");
840
841 contentPane.add(savingsField, "Savings");
842 contentPane.add(contribField, "Contributions");
843
844 contentPane.add(computeButton, "Compute");
845 contentPane.add(updateButton, "Update");
846
847 contentPane.add(inflationPercentLabel, "Inflation Percent");
848 contentPane.add(investPercentLabel, "Investment Percent");
849
850 contentPane.add(currentAgeLabel, "Current Age");
851 contentPane.add(retireAgeLabel, "Retirement Age");
852 contentPane.add(deathAgeLabel, "Death Age");
853
854 contentPane.add(graphPanel, "Graph");
855
856 // Set the title of the window
857 frame.setTitle("Financial Planner");
858
859 // Set the size of the window
860 frame.setSize(400, 300);
861
862 // Set the location of the window
863 frame.setLocationRelativeTo(null);
864
865 // Show the window
866 frame.setVisible(true);
867
868 }
869
870 /**
871 * Formats the double value as a currency string.
872 */
873
874 public String formatCurrency(double value)
875 {
876
877 // Create a new DecimalFormat object
878 DecimalFormat currencyFmt = new DecimalFormat("###,###.##");
879
880 // Format the value as a currency string
881 String formattedValue = currencyFmt.format(value);
882
883 return formattedValue;
884
885 }
886
887 /**
888 * Updates the graph with the new data.
889 */
890
891 public void updateGraph()
892 {
893
894 // Get the current values from the text fields
895 double savings = Double.parseDouble(savingsField.getText());
896 double contrib = Double.parseDouble(contribField.getText());
897
898 // Create a new Info object with the updated values
899 Info info = new Info(savings, contrib);
900
901 // Call the calculate() method on the info object
902 info.calculate();
903
904 // Set the new values in the text fields
905 savingsField.setText(currencyFmt.format(info.getSavings()));
906 contribField.setText(currencyFmt.format(info.getContrib()));
907
908 }
909
910 /**
911 * Handles the button click event.
912 */
913
914 public void actionPerformed(ActionEvent e)
915 {
916
917 // Get the button that was clicked
918 JButton button = (JButton) e.getSource();
919
920 // If the button is the "Compute" button, call the updateInfo() method
921 if (button == computeButton)
922 updateInfo();
923
924 // If the button is the "Update" button, call the updateDisplay() method
925 if (button == updateButton)
926 updateDisplay();
927
928 }
929
930 /**
931 * Sets up the GUI components.
932 */
933
934 public void init()
935 {
936
937 // Create the main window
938 frame = new JFrame("Financial Planner");
939
940 // Create the title bar
941 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
942
943 // Create the content pane
944 contentPane = frame.getContentPane();
945
946 // Create the labels
947 languageLabel = new JLabel("Language:");
948 savingsLabel = new JLabel("Savings:");
949 contribLabel = new JLabel("Contributions:");
950 incomeLabel = new JLabel("Income:");
951
952 // Create the text fields
953 savingsField = new JTextField("0.00");
954 contribField = new JTextField("0.00");
955
956 // Create the buttons
957 computeButton = new JButton("Compute");
958 updateButton = new JButton("Update");
959
960 // Create the inflation and investment percent labels
961 inflationPercentLabel = new JLabel("Inflation Percent:");
962 investPercentLabel = new JLabel("Investment Percent:");
963
964 // Create the retirement age labels
965 currentAgeLabel = new JLabel("Current Age:");
966 retireAgeLabel = new JLabel("Retirement Age:");
967 deathAgeLabel = new JLabel("Death Age:");
968
969 // Create the inflation and investment percent labels
970 inflationPercentLabel = new JLabel("Inflation Percent:");
971 investPercentLabel = new JLabel("Investment Percent:");
972
973 // Create the graph
974 graphPanel = new GraphPanel();
975
976 // Add the components to the content pane
977 contentPane.add(languageLabel, "Language");
978 contentPane.add(savingsLabel, "Savings");
979 contentPane.add(contribLabel, "Contributions");
980 contentPane.add(incomeLabel, "Income");
981
982 contentPane.add(savingsField, "Savings");
983 contentPane.add(contribField, "Contributions");
984
985 contentPane.add(computeButton, "Compute");
986 contentPane.add(updateButton, "Update");
987
988 contentPane.add(inflationPercentLabel, "Inflation Percent");
989 contentPane.add(investPercentLabel, "Investment Percent");
990
991 contentPane.add(currentAgeLabel, "Current Age");
992 contentPane.add(retireAgeLabel, "Retirement Age");
993 contentPane.add(deathAgeLabel, "Death Age");
994
995 contentPane.add(graphPanel, "Graph");
996
997 // Set the title of the window
998 frame.setTitle("Financial Planner");
999
1000 // Set the size of the window
1001 frame.setSize(400, 300);
1002
1003 // Set the location of the window
1004 frame.setLocationRelativeTo(null);
1005
1006 // Show the window
1007 frame.setVisible(true);
1008
1009 }
1010
1011 /**
1012 * Formats the double value as a currency string.
1013 */
1014
1015 public String formatCurrency(double value)
1016 {
1017
1018 // Create a new DecimalFormat object
1019 DecimalFormat currencyFmt = new DecimalFormat("###,###.##");
1020
1021 // Format the value as a currency string
1022 String formattedValue = currencyFmt.format(value);
1023
1024 return formattedValue;
1025
1026 }
1027
1028 /**
1029 * Updates the graph with the new data.
1030 */
1031
1032 public void updateGraph()
1033 {
1034
1035 // Get the current values from the text fields
1036 double savings = Double.parseDouble(savingsField.getText());
1037 double contrib = Double.parseDouble(contribField.getText());
1038
1039 // Create a new Info object with the updated values
1040 Info info = new Info(savings, contrib);
1041
1042 // Call the calculate() method on the info object
1043 info.calculate();
1044
1045 // Set the new values in the text fields
1046 savingsField.setText(currencyFmt.format(info.getSavings()));
1047 contribField.setText(currencyFmt.format(info.getContrib()));
1048
1049 }
1050
1051 /**
1052 * Handles the button click event.
1053 */
1054
1055 public void actionPerformed(ActionEvent e)
1056 {
1057
1058 // Get the button that was clicked
1059 JButton button = (JButton) e.getSource();
1060
1061 // If the button is the "Compute" button, call the updateInfo() method
1062 if (button == computeButton)
1063 updateInfo();
1064
1065 // If the button is the "Update" button, call the updateDisplay() method
1066 if (button == updateButton)
1067 updateDisplay();
1068
1069 }
1070
1071 /**
1072 * Sets up the GUI components.
1073 */
1074
1075 public void init()
1076 {
1077
1078 // Create the main window
1079 frame = new JFrame("Financial Planner");
1080
1081 // Create the title bar
1082 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
1083
1084 // Create the content pane
1085 contentPane = frame.getContentPane();
1086
1087 // Create the labels
1088 languageLabel = new JLabel("Language:");
1089 savingsLabel = new JLabel("Savings:");
1090 contribLabel = new JLabel("Contributions:");
1091 incomeLabel = new JLabel("Income:");
1092
1093 // Create the text fields
1094 savingsField = new JTextField("0.00");
1095 contribField = new JTextField("0.00");
1096
1097 // Create the buttons
1098 computeButton = new JButton("Compute");
1099 updateButton = new JButton("Update");
1100
1101 // Create the inflation and investment percent labels
1102 inflationPercentLabel = new JLabel("Inflation Percent:");
1103 investPercentLabel = new JLabel("Investment Percent:");
1104
1105 // Create the retirement age labels
1106 currentAgeLabel = new JLabel("Current Age:");
1107 retireAgeLabel = new JLabel("Retirement Age:");
1108 deathAgeLabel = new JLabel("Death Age:");
1109
1110 // Create the inflation and investment percent labels
1111 inflationPercentLabel = new JLabel("Inflation Percent:");
1112 investPercentLabel = new JLabel("Investment Percent:");
1113
1114 // Create the graph
1115 graphPanel = new GraphPanel();
1116
1117 // Add the components to the content pane
1118 contentPane.add(languageLabel, "Language");
1119 contentPane.add(savingsLabel, "Savings");
1120 contentPane.add(contribLabel, "Contributions");
1121 contentPane.add(incomeLabel, "Income");
1122
1123 contentPane.add(savingsField, "Savings");
1124 contentPane.add(contribField, "Contributions");
1125
1126 contentPane.add(computeButton, "Compute");
1127 contentPane.add(updateButton, "Update");
1128
1129 contentPane.add(inflationPercentLabel, "Inflation Percent");
1130 contentPane.add(investPercentLabel, "Investment Percent");
1131
1132 contentPane.add(currentAgeLabel, "Current Age");
1133 contentPane.add(retireAgeLabel, "Retirement Age");
1134 contentPane.add(deathAgeLabel, "Death Age");
1135
1136 contentPane.add(graphPanel, "Graph");
1137
1138 // Set the title of the window
1139 frame.setTitle("Financial Planner");
1140
1141 // Set the size of the window
1142 frame.setSize(400, 300);
1143
1144 // Set the location of the window
1145 frame.setLocationRelativeTo(null);
1146
1147 // Show the window
1148 frame.setVisible(true);
1149
1150 }
1151
1152 /**
1153 * Formats the double value as a currency string.
1154 */
1155
1156 public String formatCurrency(double value)
1157 {
1158
1159 // Create a new DecimalFormat object
1160 DecimalFormat currencyFmt = new DecimalFormat("###,###.##");
1161
1162 // Format the value as a currency string
1163 String formattedValue = currencyFmt.format(value);
1164
1165 return formattedValue;
1166
1167 }
1168
1169 /**
1170 * Updates the graph with the new data.
1171 */
1172
1173 public void updateGraph()
1174 {
1175
1176 // Get the current values from the text fields
1177 double savings = Double.parseDouble(savingsField.getText());
1178 double contrib = Double.parseDouble(contribField.getText());
1179
1180 // Create a new Info object with the updated values
1181 Info info = new Info(savings, contrib);
1182
1183 // Call the calculate() method on the info object
1184 info.calculate();
1185
1186 // Set the new values in the text fields
1187 savingsField.setText(currencyFmt.format(info.getSavings()));
1188 contribField.setText(currencyFmt.format(info.getContrib()));
1189
1190 }
1191
1192 /**
1193 * Handles the button click event.
1194 */
1195
1196 public void actionPerformed(ActionEvent e)
1197 {
1198
1199 // Get the button that was clicked
1200 JButton button = (JButton) e.getSource();
1201
1202 // If the button is the "Compute" button, call the updateInfo() method
1203 if (button == computeButton)
1204 updateInfo();
1205
1206 // If the button is the "Update" button, call the updateDisplay() method
1207 if (button == updateButton)
1208 updateDisplay();
1209
1210 }
1211
1212 /**
1213 * Sets up the GUI components.
1214 */
1215
1216 public void init()
1217 {
1218
1219 // Create the main window
1220 frame = new JFrame("Financial Planner");
1221
1222 // Create the title bar
1223 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
1224
1225 // Create the content pane
1226 contentPane = frame.getContentPane();
1227
1228 // Create the labels
1229 languageLabel = new JLabel("Language:");
1230 savingsLabel = new JLabel("Savings:");
1231 contribLabel = new JLabel("Contributions:");
1232 incomeLabel = new JLabel("Income:");
1233
1234 // Create the text fields
1235 savingsField = new JTextField("0.00");
1236 contribField = new JTextField("0.00");
1237
1238 // Create the buttons
1239 computeButton = new JButton("Compute");
1240 updateButton = new JButton("Update");
1241
1242 // Create the inflation and investment percent labels
1243 inflationPercentLabel = new JLabel("Inflation Percent:");
1244 investPercentLabel = new JLabel("Investment Percent:");
1245
1246 // Create the retirement age labels
1247 currentAgeLabel = new JLabel("Current Age:");
1248 retireAgeLabel = new JLabel("Retirement Age:");
1249 deathAgeLabel = new JLabel("Death Age:");
1250
1251 // Create the inflation and investment percent labels
1252 inflationPercentLabel = new JLabel("Inflation Percent:");
1253 investPercentLabel = new JLabel("Investment Percent:");
1254
1255 // Create the graph
1256 graphPanel = new GraphPanel();
1257
1258 // Add the components to the content pane
1259 contentPane.add(languageLabel, "Language");
1260 contentPane.add(savingsLabel, "Savings");
1261 contentPane.add(contribLabel, "Contributions");
1262 contentPane.add(incomeLabel, "Income");
1263
1264 contentPane.add(savingsField, "Savings");
1265 contentPane.add(contribField, "Contributions");
1266
1267 contentPane.add(computeButton, "Compute");
1268 contentPane.add(updateButton, "Update");
1269
1270 contentPane.add(inflationPercentLabel, "Inflation Percent");
1271 contentPane.add(investPercentLabel, "Investment Percent");
1272
1273 contentPane.add(currentAgeLabel, "Current Age");
1274 contentPane.add(retireAgeLabel, "Retirement Age");
1275 contentPane.add(deathAgeLabel, "Death Age");
1276
1277 contentPane.add(graphPanel, "Graph");
1278
1279 // Set the title of the window
1280 frame.setTitle("Financial Planner");
1281
1282 // Set the size of the window
1283 frame.setSize(400, 300);
1284
1285 // Set the location of the window
1286 frame.setLocationRelativeTo(null);
1287
1288 // Show the window
1289 frame.setVisible(true);
1290
1291 }
1292
1293 /**
1294 * Formats the double value as a currency string.
1295 */
1296
1297 public String formatCurrency(double value)
1298 {
1299
1300 // Create a new DecimalFormat object
1301 DecimalFormat currencyFmt = new DecimalFormat("###,###.##");
1302
1303 // Format the value as a currency string
1304 String formattedValue = currencyFmt.format(value);
1305
1306 return formattedValue;
1307
1308 }
1309
1310 /**
1311 * Updates the graph with the new data.
1312 */
1313
1314 public void updateGraph()
1315 {
1316
1317 // Get the current values from the text fields
1318 double savings = Double.parseDouble(savingsField.getText());
1319 double contrib = Double.parseDouble(contribField.getText());
1320
1321 // Create a new Info object with the updated values
1322 Info info = new Info(savings, contrib);
1323
1324 // Call the calculate() method on the info object
1325 info.calculate();
1326
1327 // Set the new values in the text fields
1328 savingsField.setText(currencyFmt.format(info.getSavings()));
1329 contribField.setText(currencyFmt.format(info.getContrib()));
1330
1331 }
1332
1333 /**
1334 * Handles the button click event.
1335 */
1336
1337 public void actionPerformed(ActionEvent e)
1338 {
1339
1
```

```
incomeField.setText(currencyFmt.format(info.getIncome()));
168
currentAgeField.setText(numberFmt.format(info.getCurrentAge()));
169
retireAgeField.setText(numberFmt.format(info.getRetireAge()));
170
deathAgeField.setText(numberFmt.format(info.getDeathAge()));
171
investPercentField.setText(percentFmt.format(info.getInvestPercent()
()));
172
inflationPercentField.setText(percentFmt.format(info.getInflationP
ercent()));
173 }
174
175 /**
176 * Updates the data displayed in the text area.
177 */
178 public void updateData()
179 {
180 retireText.setText("");
181 var retireMsg = new MessageFormat("");
182 retireMsg.setLocale(currentLocale);
183
184 retireMsg.applyPattern(resStrings.getString("retire"));
185 for (int i = info.getCurrentAge(); i <=
info.getDeathAge(); i++)
186 {
187 Object[] args = { i, info.getBalance(i) };
188 retireText.append(retireMsg.format(args) + "\n");
189 }
190 }
191
192 /**
193 * Updates the graph.
194 */
195 public void updateGraph()
```

```
196 {
197 retireCanvas.setColorPre((Color)
res.getObject("colorPre"));
198 retireCanvas.setColorGain((Color)
res.getObject("colorGain"));
199 retireCanvas.setColorLoss((Color)
res.getObject("colorLoss"));
200 retireCanvas.setInfo(info);
201 repaint();
202 }
203
204 /**
205 * Reads the user input from the text fields.
206 */
207 public void getInfo()
208 {
209 try
210 {
211
info.setSavings(currencyFmt.parse(savingsField.getText()).doubleValue());
212
info.setContrib(currencyFmt.parse(contribField.getText()).doubleValue());
213
info.setIncome(currencyFmt.parse(incomeField.getText()).doubleValue());
214
info.setCurrentAge(numberFmt.parse(currentAgeField.getText()).intValue());
215
info.setRetireAge(numberFmt.parse(retireAgeField.getText()).intValue());
216
info.setDeathAge(numberFmt.parse(deathAgeField.getText()).intValue());
217
info.setInvestPercent(percentFmt.parse(investPercentField.getText())
```

```
)).doubleValue());
218 info.setInflationPercent(
219
220 percentFmt.parse(inflationPercentField.getText()).doubleValue());
221 }
222 catch (ParseException e)
223 {
224 e.printStackTrace();
225 }
226 }
227
228 /**
229 * The information required to compute retirement income
data.
230 */
231 class RetireInfo
232 {
233 private double savings;
234 private double contrib;
235 private double income;
236 private int currentAge;
237 private int retireAge;
238 private int deathAge;
239 private double inflationPercent;
240 private double investPercent;
241 private int age;
242 private double balance;
243
244 /**
245 * Gets the available balance for a given year.
246 * @param year the year for which to compute the balance
247 * @return the amount of money available (or required) in
that year
248 */
249 public double getBalance(int year)
250 {
251 if (year < currentAge) return 0;
```

```
252 else if (year == currentAge)
253 {
254 age = year;
255 balance = savings;
256 return balance;
257 }
258 else if (year == age) return balance;
259 if (year != age + 1) getBalance(year - 1);
260 age = year;
261 if (age < retireAge) balance += contrib;
262 else balance -= income;
263 balance = balance * (1 + (investPercent -
inflationPercent));
264 return balance;
265 }
266
267 /**
268 * Gets the amount of prior savings.
269 * @return the savings amount
270 */
271 public double getSavings()
272 {
273 return savings;
274 }
275
276 /**
277 * Sets the amount of prior savings.
278 * @param newValue the savings amount
279 */
280 public void setSavings(double newValue)
281 {
282 savings = newValue;
283 }
284
285 /**
286 * Gets the annual contribution to the retirement account.
287 * @return the contribution amount
288 */
```

```
289 public double getContrib()
290 {
291 return contrib;
292 }
293
294 /**
295 * Sets the annual contribution to the retirement account.
296 * @param newValue the contribution amount
297 */
298 public void setContrib(double newValue)
299 {
300 contrib = newValue;
301 }
302
303 /**
304 * Gets the annual income.
305 * @return the income amount
306 */
307 public double getIncome()
308 {
309 return income;
310 }
311
312 /**
313 * Sets the annual income.
314 * @param newValue the income amount
315 */
316 public void setIncome(double newValue)
317 {
318 income = newValue;
319 }
320
321 /**
322 * Gets the current age.
323 * @return the age
324 */
325 public int getCurrentAge()
326 {
```

```
327 return currentAge;
328 }
329
330 /**
331 * Sets the current age.
332 * @param newValue the age
333 */
334 public void setCurrentAge(int newValue)
335 {
336 currentAge = newValue;
337 }
338
339 /**
340 * Gets the desired retirement age.
341 * @return the age
342 */
343 public int getRetireAge()
344 {
345 return retireAge;
346 }
347
348 /**
349 * Sets the desired retirement age.
350 * @param newValue the age
351 */
352 public void setRetireAge(int newValue)
353 {
354 retireAge = newValue;
355 }
356
357 /**
358 * Gets the expected age of death.
359 * @return the age
360 */
361 public int getDeathAge()
362 {
363 return deathAge;
364 }
```

```
365
366 /**
367 * Sets the expected age of death.
368 * @param newValue the age
369 */
370 public void setDeathAge(int newValue)
371 {
372 deathAge = newValue;
373 }
374
375 /**
376 * Gets the estimated percentage of inflation.
377 * @return the percentage
378 */
379 public double getInflationPercent()
380 {
381 return inflationPercent;
382 }
383
384 /**
385 * Sets the estimated percentage of inflation.
386 * @param newValue the percentage
387 */
388 public void setInflationPercent(double newValue)
389 {
390 inflationPercent = newValue;
391 }
392
393 /**
394 * Gets the estimated yield of the investment.
395 * @return the percentage
396 */
397 public double getInvestPercent()
398 {
399 return investPercent;
400 }
401
402 /**
```

```
403 * Sets the estimated yield of the investment.
404 * @param newValue the percentage
405 */
406 public void setInvestPercent(double newValue)
407 {
408 investPercent = newValue;
409 }
410 }
411
412 /**
413 * This component draws a graph of the investment result.
414 */
415 class RetireComponent extends JComponent
416 {
417 private static final int PANEL_WIDTH = 400;
418 private static final int PANEL_HEIGHT = 200;
419 private static final Dimension PREFERRED_SIZE = new
Dimension(800, 600);
420 private RetireInfo info = null;
421 private Color colorPre;
422 private Color colorGain;
423 private Color colorLoss;
424
425 public RetireComponent()
426 {
427 setSize(PANEL_WIDTH, PANEL_HEIGHT);
428 }
429
430 /**
431 * Sets the retirement information to be plotted.
432 * @param newInfo the new retirement info.
433 */
434 public void setInfo(RetireInfo newInfo)
435 {
436 info = newInfo;
437 repaint();
438 }
439
```

```
440 public void paintComponent(Graphics g)
441 {
442 var g2 = (Graphics2D) g;
443 if (info == null) return;
444
445 double minValue = 0;
446 double maxValue = 0;
447 int i;
448 for (i = info.getCurrentAge(); i <= info.getDeathAge();
i++)
449 {
450 double v = info.getBalance(i);
451 if (minValue > v) minValue = v;
452 if (maxValue < v) maxValue = v;
453 }
454 if (maxValue == minValue) return;
455
456 int barWidth = getWidth() / (info.getDeathAge() -
info.getCurrentAge() + 1);
457 double scale = getHeight() / (maxValue - minValue);
458
459 for (i = info.getCurrentAge(); i <= info.getDeathAge();
i++)
460 {
461 int x1 = (i - info.getCurrentAge()) * barWidth + 1;
462 int y1;
463 double v = info.getBalance(i);
464 int height;
465 int yOrigin = (int) (maxValue * scale);
466
467 if (v >= 0)
468 {
469 y1 = (int) ((maxValue - v) * scale);
470 height = yOrigin - y1;
471 }
472 else
473 {
474 y1 = yOrigin;
```

```
475 height = (int) (-v * scale);
476 }
477
478 if (i < info.getRetireAge()) g2.setPaint(colorPre);
479 else if (v >= 0) g2.setPaint(colorGain);
480 else g2.setPaint(colorLoss);
481 var bar = new Rectangle2D.Double(x1, y1, barWidth -
2, height);
482 g2.fill(bar);
483 g2.setPaint(Color.black);
484 g2.draw(bar);
485 }
486 }
487
488 /**
489 * Sets the color to be used before retirement.
490 * @param color the desired color
491 */
492 public void setColorPre(Color color)
493 {
494 colorPre = color;
495 repaint();
496 }
497
498 /**
499 * Sets the color to be used after retirement while the
500 * account balance is positive.
501 * @param color the desired color
502 */
503 public void setColorGain(Color color)
504 {
505 colorGain = color;
506 repaint();
507 }
508
509 /**
510 * Sets the color to be used after retirement when the
511 * account balance is negative.
```

```
510 * @param color the desired color
511 */
512 public void setColorLoss(Color color)
513 {
514 colorLoss = color;
515 repaint();
516 }
517
518 public Dimension getPreferredSize() { return
519 PREFERRED_SIZE; }
```

---

### **Listing 7.5** retire/RetireResources.java

[Click here to view code image](#)

```
1 package retire;
2
3 import java.awt.*;
4
5 /**
6 * These are the English non-string resources for the
7 * retirement calculator.
8 * @version 1.21 2001-08-27
9 * @author Cay Horstmann
10 */
11
12 public class RetireResources extends
13 java.util.ListResourceBundle
14 {
15 private static final Object[][][] contents =
16 {
17 // BEGIN LOCALIZE
18 { "colorPre", Color.blue }, { "colorGain", Color.white },
19 { "colorLoss", Color.red }
20 // END LOCALIZE
21 };
22
23 public Object[][][] getContents()
```

```
20 {
21 return contents;
22 }
23 }
```

---

### **Listing 7.6** retire/RetireResources\_de.java

[Click here to view code image](#)

```
1 package retire;
2
3 import java.awt.*;
4
5 /**
6 * These are the German non-string resources for the
7 * retirement calculator.
8 * @version 1.21 2001-08-27
9 * @author Cay Horstmann
10 */
11 public class RetireResources_de extends
12 java.util.ListResourceBundle
13 {
14 private static final Object[][] contents =
15 {
16 // BEGIN LOCALIZE
17 { "colorPre", Color.yellow }, { "colorGain", Color.black
18 }, { "colorLoss", Color.red }
19 // END LOCALIZE
20 };
21
22 public Object[][] getContents()
23 {
24 return contents;
25 }
26 }
```

---

### **Listing 7.7** retire/RetireResources\_zh.java

[Click here to view code image](#)

```
1 package retire;
2
3 import java.awt.*;
4
5 /**
6 * These are the Chinese non-string resources for the
7 * retirement calculator.
8 * @version 1.21 2001-08-27
9 * @author Cay Horstmann
10 */
11 public class RetireResources_zh extends
12 java.util.ListResourceBundle
13 {
14 private static final Object[][] contents =
15 {
16 // BEGIN LOCALIZE
17 { "colorPre", Color.red }, { "colorGain", Color.blue }, {
18 "colorLoss", Color.yellow }
19 // END LOCALIZE
20 };
21
22 public Object[][] getContents()
23 {
24 return contents;
25 }
26 }
```

---

---

### **Listing 7.8** retire/RetireStrings.properties

---

[Click here to view code image](#)

```
1 language=Language
2 computeButton=Compute
3 savings=Prior Savings
4 contrib=Annual Contribution
5 income=Retirement Income
```

```
6 currentAge=Current Age
7 retireAge=Retirement Age
8 deathAge=Life Expectancy
9 inflationPercent=Inflation
10 investPercent=Investment Return
11 retire=Age: {0,number} Balance: {1,number,currency}
```

---

### **Listing 7.9** retire/RetireStrings\_de.properties

[Click here to view code image](#)

```
1 language=Sprache
2 computeButton=Rechnen
3 savings=Vorherige Erspарнisse
4 contrib=Jährliche Einzahlung
5 income=Einkommen nach Ruhestand
6 currentAge=Jetziges Alter
7 retireAge=Ruhestandsalter
8 deathAge=Lebenserwartung
9 inflationPercent=Inflation
10 investPercent=Investitionsgewinn
11 retire=Alter: {0,number} Guthaben: {1,number,currency}
```

---

### **Listing 7.10** retire/RetireStrings\_zh.properties

```
1 language=语言
2 computeButton=计算
3 savings=既存
4 contrib=每年存金
5 income=退休收入
6 currentAge=现龄
7 retireAge=退休年龄
8 deathAge=预期寿命
9 inflationPercent=通货膨胀
10 investPercent=投资报酬
11 retire=年龄: {0,number} 总结: {1,number,currency}
```

---

You have seen how to use the internationalization features of the Java language. You can now use resource bundles to provide translations into multiple languages, and use formatters and collators for locale-specific text processing.

In the next chapter, we will delve into scripting, compiling, and annotation processing.

---

# Chapter 8. Scripting, Compiling, and Annotation Processing

---

## In this chapter

- [8.1 Scripting for the Java Platform](#)
- [8.2 The Compiler API](#)
- [8.3 Using Annotations](#)
- [8.4 Annotation Syntax](#)
- [8.5 Standard Annotations](#)
- [8.6 Source-Level Annotation Processing](#)
- [8.7 Bytecode Engineering](#)

This chapter introduces three techniques for processing code. The scripting API lets you invoke code in a scripting language such as JavaScript or Groovy. You can use the compiler API when you want to compile Java code inside your application. Annotation processors operate on Java source or class files that contain annotations. As you will see, there are many applications for annotation processing, ranging from simple diagnostics to “bytecode engineering”—the insertion of bytecodes into class files or even running programs.

## 8.1 Scripting for the Java Platform

A scripting language is a language that avoids the usual edit/compile/link/run cycle by interpreting the program text at runtime. Scripting languages have a number of advantages:

- Rapid turnaround, encouraging experimentation
- Changing the behavior of a running program
- Enabling customization by program users

On the other hand, most scripting languages lack features that are beneficial for programming complex applications, such as strong typing, encapsulation, and modularity.

It is therefore tempting to combine the advantages of scripting and traditional languages. The scripting API lets you do just that for the Java platform. It enables you to invoke scripts written in JavaScript, Groovy, Ruby, and even exotic languages such as Scheme and Haskell, from a Java program. For example, the Renjin project ([www.renjin.org](http://www.renjin.org)) provides a Java implementation of the R programming language, which is commonly used for statistical programming, together with an “engine” of the scripting API.

In the following sections, I'll show you how to select an engine for a particular language, how to execute scripts, and how to make use of advanced features that some scripting engines offer.

### 8.1.1 Getting a Scripting Engine

A scripting engine is a library that can execute scripts in a particular language. When the virtual machine starts, it discovers the available scripting engines. To enumerate them, construct a `ScriptEngineManager` and invoke the `getEngineFactories` method. You can ask each engine factory for the supported engine names, MIME types, and file extensions. [Table 8.1](#) shows typical values.

**Table 8.1** Properties of Scripting Engine Factories

---

<b>Eng ine</b>	<b>Names</b>	<b>MIME types</b>	<b>Ext ensi ons</b>
Rhi	no (Java aScr ipt)	rhino, Rhino, application/javascript, JavaScript, application/ecmascript, javascript text/javascript, text/ecmascript	js
Gro ovy	groovy	None	gro ovy
Renj in	Renjin	text/x-R	R, r, S, s

Usually, you know which engine you need, and you can simply request it by name, MIME type, or extension. For example:

[Click here to view code image](#)

```
var manager = new ScriptEngineManager();
ScriptEngine engine = manager.getEngineByName("javascript");
```

You need to provide the JAR files that implement the script engine on the classpath. (The Oracle JDK used to contain a JavaScript engine, but it has been removed in Java 15.)

## javax.script.ScriptEngineManager 6

- `List<ScriptEngineFactory> getEngineFactories()`  
gets a list of all discovered engine factories.
- `ScriptEngine getEngineByName(String name)`

- ScriptEngine getEngineByExtension (String extension)
- ScriptEngine getEngineByMimeType (String mimeType)

get the script engine with the given name, script file extension, or MIME type.

### ***javax.script.ScriptEngineFactory*** 6

- List<String> getNames ()
- List<String> getExtensions ()
- List<String> getMimeTypes ()

get the names, script file extensions, and MIME types under which this factory is known.

## **8.1.2 Script Evaluation and Bindings**

Once you have an engine, you can call a script simply by invoking

[Click here to view code image](#)

```
Object result = engine.eval(scriptString);
```

If the script is stored in a file, open a Reader and call

[Click here to view code image](#)

```
Object result = engine.eval(reader);
```

You can invoke multiple scripts on the same engine. If one script defines variables, functions, or classes, most scripting engines retain the definitions for later use. For example,

[Click here to view code image](#)

```
engine.eval("n = 1728");
Object result = engine.eval("n + 1");
```

will return 1729.

---



## Note

To find out whether it is safe to concurrently execute scripts in multiple threads, call

[Click here to view code image](#)

```
Object param = factory.getParameter("THREADING");
```

The returned value is one of the following:

- null: Concurrent execution is not safe.
  - "MULTITHREADED": Concurrent execution is safe. Effects from one thread might be visible from another thread.
  - "THREAD-ISOLATED": In addition to "MULTITHREADED", different variable bindings are maintained for each thread.
  - "STATELESS": In addition to "THREAD-ISOLATED", scripts do not alter variable bindings.
- 

You will often want to add variable bindings to the engine. A binding consists of a name and an associated Java object. For example, consider these statements:

[Click here to view code image](#)

```
engine.put("k", 1728);
Object result = engine.eval("k + 1");
```

The script code reads the definition of k from the bindings in the “engine scope.” This is particularly important because most scripting languages can

access Java objects, often with a syntax that is simpler than the Java syntax. For example,

[Click here to view code image](#)

```
engine.put("b", new JButton());
engine.eval("b.text = 'Ok'");
```

Conversely, you can retrieve variables that were bound by scripting statements:

[Click here to view code image](#)

```
engine.eval("n = 1728");
Object result = engine.get("n");
```

In addition to the engine scope, there is also a global scope. Any bindings that you add to the `ScriptEngineManager` are visible to all engines.

Instead of adding bindings to the engine or global scope, you can collect them in an object of type `Bindings` and pass it to the `eval` method:

[Click here to view code image](#)

```
Bindings scope = engine.createBindings();
scope.put("b", new JButton());
engine.eval(scriptString, scope);
```

This is useful if a set of bindings should not persist for future calls to the `eval` method.



## Note

You might want to have scopes other than the engine and global scopes. For example, a web container might need request and session scopes. However, then you are on your own. You will need to write a class that implements the `ScriptContext` interface, managing a collection of scopes. Each scope is identified by an integer number,

and scopes with lower numbers should be searched first. (The standard library provides a `SimpleScriptContext` class, but it only holds global and engine scopes.)

---

### ***javax.script.ScriptEngine*** 6

- `Object eval(String script)`
- `Object eval(Reader reader)`
- `Object eval(String script, Bindings bindings)`
- `Object eval(Reader reader, Bindings bindings)`

evaluate the script given by the string or reader, subject to the given bindings.

- `Object get(String key)`
- `void put(String key, Object value)`  
get or put a binding in the engine scope.
- `Bindings createBindings()`  
creates an empty `Bindings` object suitable for this engine.

### ***javax.script.ScriptEngineManager*** 6

- `Object get(String key)`
- `void put(String key, Object value)`  
get or put a binding in the global scope.

### ***javax.script.Bindings*** 6

- `Object get(String key)`
- `void put(String key, Object value)`

get or put a binding into the scope represented by this Bindings object.

### 8.1.3 Redirecting Input and Output

You can redirect the standard input and output of a script by calling the `setReader` and `setWriter` methods of the script context. For example,

[Click here to view code image](#)

```
var writer = new StringWriter();
engine.getContext().setWriter(new PrintWriter(writer, true));
```

Any output written with the JavaScript `print` or `println` functions is sent to `writer`.

The `setReader` and `setWriter` methods only affect the scripting engine's standard input and output sources. For example, if you execute the JavaScript code

[Click here to view code image](#)

```
println("Hello");
java.lang.System.out.println("World");
```

only the first output is redirected.

The Rhino engine does not have the notion of a standard input source. Calling `setReader` has no effect.

#### ***javax.script.ScriptEngine*** 6

- `ScriptContext getContext()`

gets the default script context for this engine.

### ***javax.script.ScriptContext*** 6

- Reader getReader()
- void setReader(Reader reader)
- Writer getWriter()
- void setWriter(Writer writer)
- Writer getErrorWriter()
- void setErrorWriter(Writer writer)

get or set the reader for input or writer for normal or error output.

#### **8.1.4 Calling Scripting Functions and Methods**

With many script engines, you can invoke a function in the scripting language without having to evaluate the actual script code. This is useful if you allow users to implement a service in a scripting language of their choice.

The script engines that offer this functionality implement the `Invocable` interface. In particular, the Rhino engine implements `Invocable`.

To call a function, call the `invokeFunction` method with the function name, followed by the function parameters:

[Click here to view code image](#)

```
// Define greet function in JavaScript
engine.eval("function greet(how, whom) { return how + ', ' +
whom + '!' }");

// Call the function with arguments "Hello", "World"
result = ((Invocable) engine).invokeFunction("greet", "Hello",
"World");
```

If the scripting language is object-oriented, call `invokeMethod`:

[Click here to view code image](#)

```
// Define Greeter class in JavaScript
engine.eval("function Greeter(how) { this.how = how }");
engine.eval("Greeter.prototype.welcome =
 + " function(whom) { return this.how + ', ' + whom + '!'"
}");

// Construct an instance
Object yo = engine.eval("new Greeter('Yo')");

// Call the welcome method on the instance
result = ((Invocable) engine).invokeMethod(yo, "welcome",
"World");
```

---



## Note

Rhino does not support the modern JavaScript class syntax. For more information on how to define classes in JavaScript the old-fashioned way, see *JavaScript—The Good Parts* by Douglas Crockford (O'Reilly, 2008).

---



## Note

If the script engine does not implement the `Invocable` interface, you might still be able to call a method in a language-independent way. The `getMethodCallSyntax` method of the `ScriptEngineFactory` interface produces a string that you can pass to the `eval` method. For this, however, all method parameters must be bound to names, whereas `invokeMethod` can be called with arbitrary values.

---

You can go a step further and ask the scripting engine to implement a Java interface. Then you can call scripting functions and methods with the Java method call syntax.

The details depend on the scripting engine, but typically you need to supply a function for each method of the interface. For example, consider a Java interface

```
public interface Greeter
{
 String welcome(String whom);
}
```

If you define a global function with the same name in Rhino, you can call it through this interface:

[Click here to view code image](#)

```
// Define welcome function in JavaScript
engine.eval("function welcome(whom) { return 'Hello, ' + whom +
'!' }");
// Get a Java object and call a Java method
Greeter g = ((Invocable) engine).getInterface(Greeter.class);
result = g.welcome("World");
```

In an object-oriented scripting language, you can access a script class through a matching Java interface. For example, here is how to call an object of the JavaScript Greeter class with Java syntax:

[Click here to view code image](#)

```
Greeter g = ((Invocable) engine).getInterface(yo,
Greeter.class);
result = g.welcome("World");
```

In summary, the `Invocable` interface is useful if you want to call scripting code from Java without worrying about the scripting language syntax.

## ***javax.script.Invocable*** 6

- `Object invokeFunction(String name, Object... parameters)`
- `Object invokeMethod(Object implicitParameter, String name, Object... explicitParameters)`

invoke the function or method with the given name, passing the given parameters.

- `<T> T getInterface(Class<T> iface)`

returns an implementation of the given interface, implementing the methods with functions in the scripting engine.

- `<T> T getInterface(Object implicitParameter, Class<T> iface)`

returns an implementation of the given interface, implementing the methods with the methods of the given object.

### **8.1.5 Compiling a Script**

Some scripting engines can compile scripting code into an intermediate form for efficient execution. Those engines implement the `Compilable` interface. The following example shows how to compile and evaluate code contained in a script file:

[Click here to view code image](#)

```
var reader = new FileReader("myscript.js");
CompiledScript script = null;
if (engine implements Compilable)
 script = ((Compilable) engine).compile(reader);
```

Once the script is compiled, you can execute it. The following code executes the compiled script if compilation was successful, or the original script if the engine didn't support compilation:

```
if (script != null)
 script.eval();
else
 engine.eval(reader);
```

Of course, it only makes sense to compile a script if you need to execute it repeatedly.

#### ***javax.script.Compilable*** 6

- `CompiledScript compile(String script)`
- `CompiledScript compile(Reader reader)`

compile the script given by a string or reader.

#### ***javax.script.CompiledScript*** 6

- `Object eval()`
- `Object eval(Bindings bindings)`

evaluate this script.

### **8.1.6 An Example: Scripting GUI Events**

To illustrate the scripting API, we will write a sample program that allows users to specify event handlers in a scripting language of their choice.

Have a look at the program in [Listing 8.1](#) that adds scripting to an arbitrary frame class. By default it reads the `ButtonFrame` class in [Listing 8.2](#), which is similar to the event handling demo in Volume I, with two differences:

- Each component has its `name` property set.
- There are no event handlers.

The event handlers are defined in a property file. Each property definition has the form

[Click here to view code image](#)

*componentName.eventName = scriptCode*

For example, if you choose to use JavaScript, supply the event handlers in a file `js.properties`, like this:

[Click here to view code image](#)

```
yellowButton.action=panel.background = java.awt.Color.YELLOW
blueButton.action=panel.background = java.awt.Color.BLUE
redButton.action=panel.background = java.awt.Color.RED
```

The companion code also has files for Groovy and R.

The program starts by loading an engine for the language specified on the command line. If no language is specified, we use JavaScript.

We then process a script `init.language` if it is present. This is useful for languages such as R which need some initializations that we do not want to include in every event handler script.

Next, we recursively traverse all child components and add the bindings (`name, object`) into a map of components. Then we add the bindings to the engine.

Next, we read the file `language.properties`. For each property, we synthesize an event handler proxy that causes the script code to be executed. The details are a bit technical. You might want to read the section

on proxies in Volume I, [Chapter 6](#), if you want to follow the implementation in detail. The essential part, however, is that each event handler calls

```
engine.eval(scriptCode);
```

Let us look at the `yellowButton` in more detail. When the line

[Click here to view code image](#)

```
yellowButton.action=panel.background = java.awt.Color.YELLOW
```

is processed, we find the `JButton` component with the name "`yellowButton`". We then attach an `ActionListener` with an `actionPerformed` method that executes the script

[Click here to view code image](#)

```
panel.background = java.awt.Color.YELLOW
```

if the scripting is done with Rhino.

The engine contains a binding that binds the name "`panel`" to the `JPanel` object. When the event occurs, the `setBackground` method of the panel is executed, and the color changes.

If you use Java 15 or beyond, the classpath must contain a JavaScript engine such as Rhino (<https://github.com/mozilla/rhino>). Start the program like this:

[Click here to view code image](#)

```
java -classpath .:rhino-version.jar:rhino-engine-version.jar
ScriptTest
```

For the Groovy handlers, use

[Click here to view code image](#)

```
java -classpath .:groovy/lib/* ScriptTest groovy
```

Here, *groovy* is the directory into which you installed Groovy.

For the Renjin implementation of R, include the JAR files for Renjin Studio and the Renjin script engine on the classpath. Both are available at [www.renjin.org/downloads.html](http://www.renjin.org/downloads.html).

This application demonstrates how to use scripting for Java GUI programming. One could go a step further and describe the GUI with an XML file, as you have seen in [Chapter 3](#). Then our program would become an interpreter for GUIs that have their visual presentation defined in XML and behavior defined in a scripting language. Note the similarity to a dynamic HTML page or a dynamic server-side scripting environment.

---

**Listing 8.1** `script/ScriptTest.java`

---

[Click here to view code image](#)

```
1 package script;
2
3 import java.awt.*;
4 import java.beans.*;
5 import java.io.*;
6 import java.lang.reflect.*;
7 import java.nio.charset.*;
8 import java.util.*;
9 import javax.script.*;
10 import javax.swing.*;
11
12 /**
13 * @version 1.04 2021-06-17
14 * @author Cay Horstmann
15 */
16 public class ScriptTest
17 {
18 public static void main(String[] args)
19 {
20 EventQueue.invokeLater(() ->
21 {
```

```
22 try
23 {
24 var manager = new ScriptEngineManager();
25 String language;
26 if (args.length == 0)
27 {
28 System.out.println("Available factories:
");
29 for (ScriptEngineFactory factory :
manager.getEngineFactories())
30
System.out.println(factory.getEngineName());
31
32 language = "nashorn";
33 }
34 else language = args[0];
35
36 final ScriptEngine engine =
manager.getEngineByName(language);
37 if (engine == null)
38 {
39 System.err.println("No engine for " +
language);
40 System.exit(1);
41 }
42
43 final String frameClassName
44 = args.length < 2 ? "buttons1.ButtonFrame"
: args[1];
45
46 var frame
47 = (JFrame)
Class.forName(frameClassName).getConstructor().newInstance();
48 InputStream in =
frame.getClass().getResourceAsStream("init." + language);
49 if (in != null) engine.eval(
50 new InputStreamReader(in,
StandardCharsets.UTF_8));
```

```
51 var components = new HashMap<String,
Component>();
52 getComponentBindings(frame, components);
53 components.forEach((name, c) ->
engine.put(name, c));
54
55 var events = new Properties();
56 in =
frame.getClass().getResourceAsStream(language + ".properties");
57 events.load(
58 new InputStreamReader(in,
StandardCharsets.UTF_8));
59
60 for (Object e : events.keySet())
61 {
62 String[] s = ((String) e).split("\\.");
63 addListener(s[0], s[1], (String)
events.get(e), engine, components);
64 }
65 frame.setTitle("ScriptTest");
66
frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
67 frame.setVisible(true);
68 }
69 catch (ReflectiveOperationException | IOException
70 | ScriptException | IntrospectionException
e)
71 {
72 e.printStackTrace();
73 }
74);
75 }
76
77 /**
78 * Gathers all named components in a container.
79 * @param c the component
80 * @param namedComponents a map into which to enter the
component names and components
```

```
81 */
82 private static void getComponentBindings(Component c,
83 Map<String, Component> namedComponents)
84 {
85 String name = c.getName();
86 if (name != null) { namedComponents.put(name, c); }
87 if (c instanceof Container container)
88 {
89 for (Component child : container.getComponents())
90 getComponentBindings(child, namedComponents);
91 }
92 }
93
94 /**
95 * Adds a listener to an object whose listener method
96 * executes a script.
97 * @param beanName the name of the bean to which the
98 * listener should be added
99 * @param eventName the name of the listener type, such as
100 * "action" or "change"
101 * @param scriptCode the script code to be executed
102 * @param engine the engine that executes the code
103 * @param bindings the bindings for the execution
104 * @throws IntrospectionException
105 */
106 private static void addListener(String beanName, String
107 eventName, final String scriptCode,
108 ScriptEngine engine, Map<String, Component>
109 components)
110 throws ReflectiveOperationException,
111 IntrospectionException
112 {
113 Object bean = components.get(beanName);
114 EventSetDescriptor descriptor =
115 getEventSetDescriptor(bean, eventName);
116 if (descriptor == null) return;
117 descriptor.getAddListenerMethod().invoke(bean,
118 Proxy.newProxyInstance(null, new Class[] {
```

```
descriptor.getListenerType() },
112 (proxy, method, args) ->
113 {
114 engine.eval(scriptCode);
115 return null;
116 }));
117 }
118
119 private static EventSetDescriptor
getEventSetDescriptor(Object bean, String eventName)
120 throws IntrospectionException
121 {
122 for (EventSetDescriptor descriptor :
Introspector.getBeanInfo(bean.getClass())
123 .getEventSetDescriptors())
124 if (descriptor.getName().equals(eventName)) return
descriptor;
125 return null;
126 }
127 }
```

---

---

### **Listing 8.2** buttons1/ButtonFrame.java

---

[Click here to view code image](#)

```
1 package buttons1;
2
3 import javax.swing.*;
4
5 /**
6 * A frame with a button panel.
7 * @version 1.00 2007-11-02
8 * @author Cay Horstmann
9 */
10 public class ButtonFrame extends JFrame
11 {
12 private static final int DEFAULT_WIDTH = 300;
13 private static final int DEFAULT_HEIGHT = 200;
```

```
14
15 private JPanel panel;
16 private JButton yellowButton;
17 private JButton blueButton;
18 private JButton redButton;
19
20 public ButtonFrame()
21 {
22 setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
23
24 panel = new JPanel();
25 panel.setName("panel");
26 add(panel);
27
28 yellowButton = new JButton("Yellow");
29 yellowButton.setName("yellowButton");
30 blueButton = new JButton("Blue");
31 blueButton.setName("blueButton");
32 redButton = new JButton("Red");
33 redButton.setName("redButton");
34
35 panel.add(yellowButton);
36 panel.add(blueButton);
37 panel.add(redButton);
38 }
39 }
```

---

## 8.2 The Compiler API

There are quite a few tools that need to compile Java code. Obviously, development environments and programs that teach Java programming are among them, as well as testing and build automation tools. Another example is the processing of JavaServer Pages—web pages with embedded Java statements.

### 8.2.1 Invoking the Compiler

It is very easy to invoke the compiler. Here is a sample call:

[Click here to view code image](#)

```
JavaCompiler compiler = ToolProvider.getSystemJavaCompiler();
OutputStream outStream = . . .;
OutputStream errStream = . . .;
int result = compiler.run(null, outStream, errStream,
 "-sourcepath", "src", "Test.java");
```

A result value of 0 indicates successful compilation.

The compiler sends its output and error messages to the provided streams. You can set these parameters to null, in which case `System.out` and `System.err` are used. The first parameter of the `run` method is an input stream. As the compiler takes no console input, you can always leave it as null. (The `run` method is inherited from a generic `Tool` interface, which allows for tools that read input.)

The remaining parameters of the `run` method are the arguments that you would pass to `javac` if you invoked it on the command line. These can be options or file names.

### 8.2.2 Launching a Compilation Task

You can have more control over the compilation process with a `CompilationTask` object. This can be useful if you want to supply source from string, capture class files in memory, or process the error and warning messages.

To obtain a `CompilationTask`, start with a `compiler` object as in the preceding section. Then call

[Click here to view code image](#)

```
JavaCompiler.CompilationTask task = compiler.getTask(
 errorWriter, // Uses System.err if null
 fileManager, // Uses the standard file manager if null
 diagnostics, // Uses System.err if null
```

```
options, // null if no options
classes, // For annotation processing; null if none
sources);
```

The last three arguments are `Iterable` instances. For example, a sequence of options might be specified as

[Click here to view code image](#)

```
Iterable<String> options = List.of("-d", "bin");
```

The `sources` parameter is an `Iterable` of `JavaFileObject` instances. If you want to compile disk files, get a `StandardJavaFileManager` and call its `getJavaFileObjects` method:

[Click here to view code image](#)

```
StandardJavaFileManager fileManager =
compiler.getStandardFileManager(null, null, null);
Iterable<JavaFileObject> sources
=
fileManager.getJavaFileObjectsFromStrings(List.of("File1.java",
"File2.java"));
JavaCompiler.CompilationTask task = compiler.getTask(
null, null, null, options, null, sources);
```

---



## Note

The `classes` parameter is only used for annotation processing. In that case, you also need to call `task.processors(annotationProcessors)` with a list of `Processor` objects. See [Section 8.6, “Source-Level Annotation Processing,”](#) on p. 488 for an example of annotation processing.

---

The `getTask` method returns the task object but does not yet start the compilation process. The `CompilationTask` class extends `Callable<Boolean>`. You can pass it to an `ExecutorService` for concurrent execution, or you can just make a synchronous call:

```
Boolean success = task.call();
```

### 8.2.3 Capturing Diagnostics

To listen to error messages, install a `DiagnosticListener`. The listener receives a `Diagnostic` object whenever the compiler reports a warning or error message. The `DiagnosticCollector` class implements this interface. It simply collects all diagnostics so that you can iterate through them after the compilation is complete.

[Click here to view code image](#)

```
DiagnosticCollector<JavaFileObject> collector = new
DiagnosticCollector<>();
compiler.getTask(null, fileManager, collector, null, null,
sources).call();
for (Diagnostic<? extends JavaFileObject> d :
collector.getDiagnostics())
{
 System.out.println(d);
}
```

A `Diagnostic` object contains information about the problem location (including file name, line number, and column number) as well as a human-readable description.

You can also install a `DiagnosticListener` to the standard file manager, in case you want to trap messages about missing files:

[Click here to view code image](#)

```
StandardJavaFileManager fileManager
= compiler.getStandardFileManager(diagnostics, null, null);
```

## 8.2.4 Reading Source Files from Memory

If you generate source code on the fly, you can have it compiled from memory, without having to save files to disk. Use this class to hold the code:

[Click here to view code image](#)

```
public class StringSource extends SimpleJavaFileObject
{
 private String code;
 StringSource(String name, String code)
 {
 super(URI.create("string:/// " + name.replace('.', '/') +
".java"), Kind.SOURCE);
 this.code = code;
 }

 public CharSequence getCharContent(boolean
ignoreEncodingErrors)
 {
 return code;
 }
}
```

Then generate the code for your classes and give the compiler a list of `StringSource` objects:

[Click here to view code image](#)

```
List<StringSource> sources = List.of(
 new StringSource(className1, class1CodeString), . . .);
task = compiler.getTask(null, fileManager, diagnostics, null,
null, sources);
```

## 8.2.5 Writing Byte Codes to Memory

If you compile classes on the fly, there is no need to save the class files to disk. You can save them to memory and load them right away.

First, here is a class for holding the bytes:

[Click here to view code image](#)

```
public class ByteArrayClass extends SimpleJavaFileObject
{
 private ByteArrayOutputStream out;

 ByteArrayClass(String name)
 {
 super(URI.create("bytes://" + name.replace('.', '/') +
".class"), Kind.CLASS);
 }

 public byte[] getCode()
 {
 return out.toByteArray();
 }

 public OutputStream openOutputStream() throws IOException
 {
 out = new ByteArrayOutputStream();
 return out;
 }
}
```

Next, you need to configure the file manager to use these classes for output:

[Click here to view code image](#)

```
List<ByteArrayClass> classes = new ArrayList<>();
StandardJavaFileManager stdFileManager

= compiler.getStandardFileManager(null, null, null);
JavaFileManager fileManager
= new ForwardingJavaFileManager<JavaFileManager>
```

```

(stdFileManager)
{
 public JavaFileObject getJavaFileForOutput(Location
location,
 String className, Kind kind, FileObject sibling)
throws IOException
{
 if (kind == Kind.CLASS)
 {
 ByteArrayClass outfile = new
ByteArrayClass(className);
 classes.add(outfile);
 return outfile;
 }
 else
 return super.getJavaFileForOutput(location,
className, kind, sibling);
}
};

```

To load the classes, you need a class loader (see [Chapter 10](#)):

[Click here to view code image](#)

```

public class ByteArrayClassLoader extends ClassLoader
{
 private Iterable<ByteArrayClass> classes;

 public ByteArrayClassLoader(Iterable<ByteArrayClass>
classes)
 {
 this.classes = classes;
 }

 public Class<?> findClass(String name) throws
ClassNotFoundException
 {
 for (ByteArrayClass cl : classes)
 {

```

```

 if (cl.getName().equals="/" + name.replace('.', '/') +
".class"))
 {
 byte[] bytes = cl.getCode();
 return defineClass(name, bytes, 0, bytes.length);
 }
}
throw new ClassNotFoundException(name);
}
}

```

After compilation has finished, call the `Class.forName` method with that class loader:

[Click here to view code image](#)

```

ByteArrayClassLoader loader = new
ByteArrayClassLoader(classes);
Class<?> cl = Class.forName(className, true, loader);

```

## 8.2.6 An Example: Dynamic Java Code Generation

In the JSP technology for dynamic web pages, you can mix HTML with snippets of Java code, for example:

[Click here to view code image](#)

```

<p>The current date and time is <%= new java.util.Date() %>
.</p>

```

The JSP engine dynamically compiles the Java code into a servlet. In our sample application, we use a simpler example and generate dynamic Swing code instead. The idea is that you use a GUI builder to lay out the components in a frame and specify the behavior of the components in an external file. [Listing 8.4](#) shows a very simple example of a frame class, and [Listing 8.5](#) shows the code for the button actions. Note that the constructor of the frame class calls an abstract method `addEventHandlers`. Our code generator will produce a subclass that implements the

`addEventHandlers` method, adding an action listener for each line in the `action.properties` file. (I leave it as the proverbial exercise to the reader to extend the code generation to other event types.)

We place the subclass into a package with the name `x`, which we hope is not used anywhere else in the program. The generated code has the form

[Click here to view code image](#)

```
package x;
public class Frame extends SuperclassName
{
 protected void addEventHandlers()
 {
 componentName1.addActionListener(event ->
 {
 code for event handler1
 });
 // repeat for the other event handlers . . .
 }
}
```

The `buildSource` method in the program of [Listing 8.3](#) builds up this code and places it into a `StringSource` object. That object is passed to the Java compiler.

As described in the preceding section, we use a `ForwardingJavaFileManager` that constructs a `ByteArrayClass` object for every compiled class. These objects capture the class files generated when the `x.Frame` class is compiled. The method adds each file object to a list before returning it so that we can locate the bytecodes later.

After compilation, we use the class loader from the preceding section to load the classes stored in this list. Then, we construct and display the application's frame class.

[Click here to view code image](#)

```
var loader = new ByteArrayClassLoader(classFileObjects);
var frame = (JFrame)
loader.loadClass("x.Frame").getConstructor().newInstance();
frame.setVisible(true);
```

When you click the buttons, the background color changes in the usual way. To see that the actions are dynamically compiled, change one of the lines in `action.properties`, for example, like this:

[Click here to view code image](#)

```
yellowButton=panel.setBackground(java.awt.Color.YELLOW);
yellowButton.setEnabled(false);
```

Run the program again. Now the Yellow button is disabled after you click it. Also, have a look at the code directories. You will not find any source or class files for the classes in the `x` package. This example demonstrates how you can use dynamic compilation with in-memory source and class files.

---

### **Listing 8.3** compiler/CompilerTest.java

---

[Click here to view code image](#)

```
1 package compiler;
2
3 import java.awt.*;
4 import java.io.*;
5 import java.nio.charset.*;
6 import java.nio.file.*;
7 import java.util.*;
8 import java.util.List;
9
10 import javax.swing.*;
11 import javax.tools.*;
12 import javax.tools.JavaFileObject.*;
13
14 /**
15 * @version 1.10 2018-05-01
```

```
16 * @author Cay Horstmann
17 */
18 public class CompilerTest
19 {
20 public static void main(final String[] args)
21 throws IOException, ReflectiveOperationException
22 {
23 JavaCompiler compiler =
24 ToolProvider.getSystemJavaCompiler();
25
26 var classFileObjects = new ArrayList<ByteArrayClass>
27 ();
28
29 var diagnostics = new
30 DiagnosticCollector<JavaFileObject>();
31
32 JavaFileManager fileManager =
33 compiler.getStandardFileManager(diagnostics, null, null);
34 fileManager = new
35 ForwardingJavaFileManager<JavaFileManager>(fileManager)
36 {
37 public JavaFileObject getJavaFileForOutput(Location
38 location,
39 String className, Kind kind, FileObject sibling)
40 throws IOException
41 {
42 if (kind == Kind.CLASS)
43 {
44 var fileObject = new ByteArrayClass(className);
45 classFileObjects.add(fileObject);
46 return fileObject;
47 }
48 else return super.getJavaFileForOutput(location,
49 className, kind, sibling);
50 }
51 };
52
53 };
54
55 }
```

```
46 String frameClassName = args.length == 0 ?
"buttons2.ButtonFrame" : args[0];
47 //compiler.run(null, null, null, frameClassName.replace(".",
"/") + ".java");
48
49 StandardJavaFileManager fileManager2 =
compiler.getStandardFileManager(null, null, null);
50 var sources = new ArrayList<JavaFileObject>();
51 for (JavaFileObject o :
fileManager2.getJavaFileObjectsFromStrings(
52 List.of(frameClassName.replace(".", "/") + ".java")))
53 sources.add(o);
54
55 JavaFileObject source = buildSource(frameClassName);
56 JavaCompiler.CompilationTask task = compiler.getTask(null,
fileManager, diagnostics,
57 null, null, List.of(source));
58 Boolean result = task.call();
59
60 for (Diagnostic<? extends JavaFileObject> d :
diagnostics.getDiagnostics())
61 System.out.println(d.getKind() + ": " +
d.getMessage(null));
62 fileManager.close();
63 if (!result)
64 {
65 System.out.println("Compilation failed.");
66 System.exit(1);
67 }
68
69 var loader = new ByteArrayClassLoader(classFileObjects);
70 var frame = (JFrame)
loader.loadClass("x.Frame").getConstructor().newInstance();
71
72 EventQueue.invokeLater(() ->
73 {
74 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
75 frame.setTitle("CompilerTest");
```

```
76 frame.setVisible(true);
77 });
78 }
79
80 /*
81 * Builds the source for the subclass that implements the
82 * addEventHandlers method.
83 * @return a file object containing the source in a string
84 * builder
85 */
86 static JavaFileObject buildSource(String superClass)
87 throws IOException, ClassNotFoundException
88 {
89 var builder = new StringBuilder();
90 builder.append("package x;\n\n");
91 builder.append("public class Frame extends " +
92 superClass + " {\n");
93 builder.append("protected void addEventHandlers() {\n");
94 var props = new Properties();
95 props.load(Files.newBufferedReader(
96 Path.of(superClass.replace(".", "/"))
97 .getParent()
98 .resolve("action.properties"),
99 StandardCharsets.UTF_8));
100 for (Map.Entry<Object, Object> e : props.entrySet())
101 {
102 var beanName = (String) e.getKey();
103 var eventCode = (String) e.getValue();
104 builder.append(beanName + ".addActionListener(event ->
105 {\n");
106 builder.append(eventCode);
107 builder.append("\n})\n");
108 }
109 builder.append("}\n");
110 return new StringSource("x.Frame", builder.toString());
111 }
```

---

---

**Listing 8.4** buttons2/ButtonFrame.java

---

[Click here to view code image](#)

```
1 package buttons2;
2 import javax.swing.*;
3
4 /**
5 * A frame with a button panel.
6 * @version 1.00 2007-11-02
7 * @author Cay Horstmann
8 */
9 public abstract class ButtonFrame extends JFrame
10 {
11 public static final int DEFAULT_WIDTH = 300;
12 public static final int DEFAULT_HEIGHT = 200;
13
14 protected JPanel panel;
15 protected JButton yellowButton;
16 protected JButton blueButton;
17 protected JButton redButton;
18
19 protected abstract void addEventHandlers();
20
21 public ButtonFrame()
22 {
23 setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
24
25 panel = new JPanel();
26 add(panel);
27
28 yellowButton = new JButton("Yellow");
29 blueButton = new JButton("Blue");
30 redButton = new JButton("Red");
31
32 panel.add(yellowButton);
33 panel.add(blueButton);
34 panel.add(redButton);
```

```
35
36 addEventHandlers();
37 }
38 }
```

---

### **Listing 8.5** buttons2/action.properties

[Click here to view code image](#)

```
1 yellowButton=panel.setBackground(java.awt.Color.YELLOW);
2 blueButton=panel.setBackground(java.awt.Color.BLUE);
```

---

#### ***javax.tools.Tool*** 6

- `int run(InputStream in, OutputStream out, OutputStream err, String... arguments)`

runs the tool with the given input, output, and error streams and the given arguments. Returns 0 for success, a nonzero value for failure.

#### ***javax.tools.JavaCompiler*** 6

- `StandardJavaFileManager getStandardFileManager(DiagnosticListener<? super JavaFileObject> diagnosticListener, Locale locale, Charset charset)`

gets the standard file manager for this compiler. You can supply null for default error reporting, locale, and character set.

- `JavaCompiler.CompilationTask getTask(Writer out, JavaFileManager fileManager, DiagnosticListener<? super JavaFileObject>`

```
diagnosticListener, Iterable<String> options,
Iterable<String>
classesForAnnotationProcessing, Iterable<?
extends JavaFileObject> sourceFiles)
```

gets a compilation task that, when called, will compile the given source files. See the discussion in the preceding section for details.

## ***javax.tools.StandardJavaFileManager*** 6

- Iterable<? extends JavaFileObject>  
getJavaFileObjectsFromStrings(Iterable<String> fileNames)
- Iterable<? extends JavaFileObject>  
getJavaFileObjectsFromPaths(Collection<?  
extends Path> paths) 13
- Iterable<? extends JavaFileObject>  
getJavaFileObjectsFromFile(Iterable<?  
extends File> files)

translate a sequence of file names or files into a sequence of JavaFileObject instances.

## ***javax.tools.JavaCompiler.CompilationTask*** 6

- Boolean call()  
performs the compilation task.

## ***javax.tools.DiagnosticCollector<S>*** 6

- `DiagnosticCollector()`  
constructs an empty collector.
- `List<Diagnostic<? extends S>> getDiagnostics()`  
gets the collected diagnostics.

## ***javax.tools.Diagnostic<S>*** 6

- `S getSource()`  
gets the source object associated with this diagnostic.
- `Diagnostic.Kind getKind()`  
gets the type of this diagnostic—one of `ERROR`, `WARNING`, `MANDATORY_WARNING`, `NOTE`, or `OTHER`.
- `String getMessage(Locale locale)`  
gets the message describing the issue raised in this diagnostic. Pass `null` for the default locale.
- `long getLineNumber()`
- `long getColumnNumber()`  
get the position of the issue raised in this diagnostic.

## ***javax.tools.SimpleJavaFileObject*** 6

- CharSequence `getCharContent(boolean ignoreEncodingErrors)`

Override this method for a file object that represents a source file and produces the source code.

- OutputStream `openOutputStream()`

Override this method for a file object that represents a class file and produces a stream to which the bytecodes can be written.

### **`javax.tools.ForwardingJavaFileManager<M extends JavaFileManager>`**

- `protected ForwardingJavaFileManager(M fileManager)`

constructs a JavaFileManager that delegates all calls to the given file manager.

- `FileObject getFileForOutput(JavaFileManager.Location location, String className, JavaFileObject.Kind kind, FileObject sibling)`

Intercept this call if you want to substitute a file object for writing class files; kind is one of SOURCE, CLASS, HTML, or OTHER.

## **8.3 Using Annotations**

Annotations are tags that you insert into your source code so that some tool can process them. The tools can operate on the source level, or they can process class files into which the compiler has placed annotations.

Annotations do not change the way in which your programs are compiled. The Java compiler generates the same virtual machine instructions with or without the annotations.

To benefit from annotations, you need to select a *processing tool*. Use annotations that your processing tool understands, then apply the processing tool to your code.

There is a wide range of uses for annotations, and that generality can be confusing at first. Here are some uses for annotations:

- Automatic generation of auxiliary files, such as deployment descriptors or bean information classes
- Automatic generation of code for testing, logging, transaction semantics, and so on

### 8.3.1 An Introduction into Annotations

I'll start our discussion of annotations with the basic concepts and put them to use in a concrete example, in which I will mark methods as event listeners for AWT components and show you an annotation processor that analyzes the annotations and hooks up the listeners. I'll then discuss the syntax rules in detail and finish the chapter with two advanced examples of annotation processing. One of them processes source-level annotations, the other uses the Apache Bytecode Engineering Library to process class files, injecting additional bytecodes into annotated methods.

Here is an example of a simple annotation:

[Click here to view code image](#)

```
public class MyClass
{
 ...
 @Test public void checkRandomInsertions()
}
```

The annotation `@Test` annotates the `checkRandomInsertions` method.

In Java, an annotation is used like a *modifier* and is placed before the annotated item *without a semicolon*. (A modifier is a keyword such as `public` or `static`.) The name of each annotation is preceded by an `@` symbol, similar to Javadoc comments. However, Javadoc comments occur inside the `/** . . . */` delimiters, whereas annotations are part of the code.

By itself, the `@Test` annotation does not do anything. It needs a tool to be useful. For example, the JUnit testing tool (available at <http://junit.org>) calls all methods that are labeled `@Test` when testing a class. Another tool might remove all test methods from a class file so they are not shipped with the program after it has been tested.

Annotations can be defined to have *elements*, such as

```
@Test(timeout="10000")
```

These elements can be processed by the tools that read the annotations. Other forms of elements are possible; we'll discuss them later in this chapter.

Besides methods, you can annotate classes, fields, and local variables—an annotation can be anywhere you could put a modifier such as `public` or `static`. In addition, as you will see in [Section 8.4, “Annotation Syntax,”](#) on p. [475](#), you can annotate packages, parameter variables, type parameters, and type uses.

Each annotation must be defined by an *annotation interface*. The methods of the interface correspond to the elements of the annotation. For example, the JUnit Test annotation is defined by the following interface:

[Click here to view code image](#)

```
@Target(ElementType.METHOD)
@Retention(RetentionPolicy.RUNTIME)
public @interface Test
{
 long timeout() default 0L;
```

```
 }
```

The `@interface` declaration creates an actual Java interface. Tools that process annotations receive objects that implement the annotation interface. A tool would call the `timeout` method to retrieve the `timeout` element of a particular `Test` annotation.

The `Target` and `Retention` annotations are *meta-annotations*. They annotate the `Test` annotation, marking it as an annotation that can be applied to methods only and is retained when the class file is loaded into the virtual machine. We'll discuss these in detail in Section 8.5.2, “[Meta-Annotations](#),” on p. 484.

You have now seen the basic concepts of program metadata and annotations. In the next section, we'll walk through a concrete example of annotation processing.



### Note

For a compelling use of annotations, check out `JCommander` (<http://jcommander.org>) and `picocli` (<http://picocli.info>). These libraries use annotations for the processing of command-line parameters.

---

### 8.3.2 An Example: Annotating Event Handlers

One of the more boring tasks in user interface programming is the wiring of listeners to event sources. Many listeners are of the form

[Click here to view code image](#)

```
myButton.addActionListener(() -> doSomething());
```

In this section, we'll design an annotation to reverse the wiring. The annotation, defined in Listing 8.8, is used as follows:

[Click here to view code image](#)

```
@ActionListenerFor(source="myButton") void doSomething() { . . .
. }
```

The programmer no longer has to make calls to `addActionListener`. Instead, each method is tagged with an annotation. [Listing 8.7](#) shows the `ButtonFrame` class from Volume I, [Chapter 10](#), reimplemented with these annotations.

We also need to define an annotation interface. The code is in [Listing 8.8](#).

Of course, the annotations don't do anything by themselves. They sit in the source file. The compiler places them in the class file, and the virtual machine loads them. We now need a mechanism to analyze them and install action listeners. That is the job of the `ActionListenerInstaller` class. The `ButtonFrame` constructor calls

[Click here to view code image](#)

```
ActionListenerInstaller.processAnnotations(this);
```

The static `processAnnotations` method enumerates all methods of the object it received. For each method, it gets the `ActionListenerFor` annotation object and processes it.

[Click here to view code image](#)

```
Class<?> cl = obj.getClass();
for (Method m : cl.getDeclaredMethods())
{
 ActionListenerFor a =
 m.getAnnotation(ActionListenerFor.class);
 if (a != null) . . .
}
```

Here, we use the `getAnnotation` method defined in the `AnnotatedElement` interface. The classes `Method`, `Constructor`, `Field`, `Class`, and `Package` implement this interface.

The name of the source field is stored in the annotation object. We retrieve it by calling the `source` method, and then look up the matching field.


[Click here to view code image](#)

```
String fieldName = a.source();
Field f = cl.getDeclaredField(fieldName);
```

This shows a limitation of our annotation. The source element must be the name of a field. It cannot be a local variable.

The remainder of the code is rather technical. For each annotated method, we construct a proxy object, implementing the `ActionListener` interface, with an `actionPerformed` method that calls the annotated method. (For more information about proxies, see Volume I, [Chapter 6](#).) The details are not important. The key observation is that the functionality of the annotations was established by the `processAnnotations` method.

[Figure 8.1](#) shows how annotations are handled in this example.



**Figure 8.1** Processing annotations at runtime

In this example, the annotations were processed at runtime. It is also possible to process them at the source level: A source code generator would

then produce the code for adding the listeners. Alternatively, the annotations can be processed at the bytecode level: A bytecode editor could inject the calls to `addActionListener` into the frame constructor. This sounds complex, but libraries are available to make this task relatively straightforward. You can see an example in [Section 8.7, “Bytecode Engineering,”](#) on p. 493.

Our example was not intended as a serious tool for user interface programmers. A utility method for adding a listener could be just as convenient for the programmer as the annotation. (In fact, the `java.beans.EventHandler` class tries to do just that. You could make the class truly useful by supplying a method that adds the event handler instead of just constructing it.)

However, this example shows the mechanics of annotating a program and of analyzing the annotations. Having seen a concrete example, you are now more prepared (I hope) for the following sections that describe the annotation syntax in complete detail.

---

### **Listing 8.6**

`runtimeAnnotations/ActionListenerInstaller.java`

---

[Click here to view code image](#)

```
1 package runtimeAnnotations;
2
3 import java.awt.event.*;
4 import java.lang.reflect.*;
5
6 /**
7 * @version 1.00 2004-08-17
8 * @author Cay Horstmann
9 */
10 public class ActionListenerInstaller
11 {
12 /**
13 * Processes all ActionListenerFor annotations in the given
object.
```

```
14 * @param obj an object whose methods may have
15 * ActionListenerFor annotations
16 */
17 public static void processAnnotations(Object obj)
18 {
19 try
20 {
21 Class<?> cl = obj.getClass();
22 for (Method m : cl.getDeclaredMethods())
23 {
24 ActionListenerFor a =
25 m.getAnnotation(ActionListenerFor.class);
26 if (a != null)
27 {
28 Field f = cl.getDeclaredField(a.source());
29 f.setAccessible(true);
30 addListener(f.get(obj), obj, m);
31 }
32 }
33 catch (ReflectiveOperationException e)
34 {
35 e.printStackTrace();
36 }
37 }
38 /**
39 * Adds an action listener that calls a given method.
40 * @param source the event source to which an action
41 * listener is added
42 * @param param the implicit parameter of the method that
43 * the listener calls
44 * @param m the method that the listener calls
45 */
46 public static void addListener(Object source, final Object
param, final Method m)
47 throws ReflectiveOperationException
48 {
```

```

47 var handler = new InvocationHandler()
48 {
49 public Object invoke(Object proxy, Method mm,
50 Object[] args) throws Throwable
51 {
52 return m.invoke(param);
53 }
54 };
55 Object listener = Proxy.newProxyInstance(null,
56 new Class[] { java.awt.event.ActionListener.class },
57 handler);
58 Method adder =
59 source.getClass().getMethod("addActionListener",
60 ActionListener.class);
61 adder.invoke(source, listener);
62 }

```

---

### **Listing 8.7** buttons3/ButtonFrame.java

[Click here to view code image](#)

```

1 package buttons3;
2
3 import java.awt.*;
4 import javax.swing.*;
5 import runtimeAnnotations.*;
6
7 /**
8 * A frame with a button panel.
9 * @version 1.00 2004-08-17
10 * @author Cay Horstmann
11 */
12 public class ButtonFrame extends JFrame
13 {
14 private static final int DEFAULT_WIDTH = 300;
15 private static final int DEFAULT_HEIGHT = 200;

```

```
16
17 private JPanel panel;
18 private JButton yellowButton;
19 private JButton blueButton;
20 private JButton redButton;
21
22 public ButtonFrame()
23 {
24 setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
25
26 panel = new JPanel();
27 add(panel);
28
29 yellowButton = new JButton("Yellow");
30 blueButton = new JButton("Blue");
31 redButton = new JButton("Red");
32
33 panel.add(yellowButton);
34 panel.add(blueButton);
35 panel.add(redButton);
36
37 ActionListenerInstaller.processAnnotations(this);
38 }
39
40 @ActionListenerFor(source = "yellowButton")
41 public void yellowBackground()
42 {
43 panel.setBackground(Color.YELLOW);
44 }
45
46 @ActionListenerFor(source = "blueButton")
47 public void blueBackground()
48 {
49 panel.setBackground(Color.BLUE);
50 }
51
52 @ActionListenerFor(source = "redButton")
53 public void redBackground()
```

```
54 {
55 panel.setBackground(Color.RED);
56 }
57 }
```

---

---

### **Listing 8.8**

`runtimeAnnotations/ActionListenerFor.java`

---

[Click here to view code image](#)

```
1 package runtimeAnnotations;
2
3 import java.lang.annotation.*;
4
5 /**
6 * @version 1.00 2004-08-17
7 * @author Cay Horstmann
8 */
9 @Target(ElementType.METHOD)
10 @Retention(RetentionPolicy.RUNTIME)
11 public @interface ActionListenerFor
12 {
13 String source();
14 }
```

---

### ***java.lang.reflect.AnnotatedElement 5.0***

- `boolean isAnnotationPresent(Class<? extends Annotation> annotationType)`  
returns true if this item has an annotation of the given type.
- `<T extends Annotation> T getAnnotation(Class<T> annotationType)`

T

gets the annotation of the given type, or `null` if this item has no such annotation.

- ```
<T extends Annotation> T[] getAnnotationsByType(Class<T> annotationType)
```

gets all annotations of a repeatable annotation type (see [Section 8.5.2, “Meta-Annotations,”](#) on p. 484), or an array of length 0.

- `Annotation[] getAnnotations()`

gets all annotations present for this item, including inherited annotations. If no annotations are present, an array of length 0 is returned.

- `Annotation[] getDeclaredAnnotations()`

gets all annotations declared for this item, excluding inherited annotations. If no annotations are present, an array of length 0 is returned.

8.4 Annotation Syntax

In the following sections, we cover everything you need to know about the annotation syntax.

8.4.1 Annotation Interfaces

An annotation is defined by an annotation interface:

[Click here to view code image](#)

```
modifiers @interface AnnotationName
{
    elementDeclaration1
```

```
elementDeclaration2
...
}
```

Each element declaration has the form

```
type elementName() ;
```

or

[Click here to view code image](#)

```
type elementName() default value;
```

For example, the following annotation has two elements, `assignedTo` and `severity`:

[Click here to view code image](#)

```
public @interface BugReport
{
    String assignedTo() default "[none]";
    int severity();
}
```

All annotation interfaces implicitly extend the `java.lang.annotation.Annotation` interface. That interface is a regular interface, *not* an annotation interface. See the API notes at the end of this section for the methods provided by this interface. You cannot extend an annotation interface—in other words, all annotation interfaces directly extend `java.lang.annotation.Annotation`. You never supply classes that implement annotation interfaces.

The methods of an annotation interface have no parameters and no `throws` clauses. They cannot be `default` or `static` methods, and they cannot have type parameters.

The type of an annotation element is one of the following:

- A primitive type (int, short, long, byte, char, double, float, or boolean)
- String
- Class (with an optional type parameter such as Class<? extends MyClass>)
- An enum type
- An annotation type
- An array of the preceding types (an array of arrays is not a legal element type)

Here are examples of valid element declarations:

[Click here to view code image](#)

```
public @interface BugReport
{
    enum Status { UNCONFIRMED, CONFIRMED, FIXED, NOTABUG };
    boolean showStopper() default false;
    String assignedTo() default "[none]";
    Class<?> testCase() default Void.class;
    Status status() default Status.UNCONFIRMED;
    Reference ref() default @Reference(); // an annotation type
    String[] reportedBy();
}
```

***java.lang.annotation.Annotation* 5.0**

- Class<? extends Annotation> annotationType()

returns the Class object that represents the annotation interface of this annotation object. Note that calling getClass on an annotation object would return the actual class, not the interface.
- boolean equals(Object other)

returns true if other is an object that implements the same annotation interface as this annotation object and if all elements of this object and other are equal.

- int hashCode()

returns a hash code, compatible with the equals method, derived from the name of the annotation interface and the element values.

- String toString()

returns a string representation that contains the annotation interface name and the element values, for example @BugReport(assignedTo=[none], severity=0).

8.4.2 Annotations

Each annotation has the format

[Click here to view code image](#)

```
@AnnotationName(elementName1=value1, elementName2=value2, . . .  
.)
```

For example,

[Click here to view code image](#)

```
@BugReport(assignedTo="Harry", severity=10)
```

The order of the elements does not matter. The annotation

[Click here to view code image](#)

```
@BugReport(severity=10, assignedTo="Harry")
```

is identical to the preceding one.

The default value of the declaration is used if an element value is not specified. For example, consider the annotation

```
@BugReport(severity=10)
```

The value of the `assignedTo` element is the string "`[none]`".



Caution

Defaults are not stored with the annotation; instead, they are dynamically computed. For example, if you change the default for the `assignedTo` element to "`[]`" and recompile the `BugReport` interface, the annotation `@BugReport(severity=10)` will use the new default, even in class files that have not been recompiled after the default changed.

Two special shortcuts can simplify annotations.

If no elements are specified, either because the annotation doesn't have any or because all of them use the default value, you don't need to use parentheses. For example,

```
@BugReport
```

is the same as

[Click here to view code image](#)

```
@BugReport(assignedTo="[none]", severity=0)
```

Such an annotation is called a *marker annotation*.

The other shortcut is the *single-value annotation*. If an element has the special name `value` and no other element is specified, you can omit the

element name and the = symbol. For example, had we defined the `ActionListenerFor` annotation interface of the preceding section as

[Click here to view code image](#)

```
public @interface ActionListenerFor
{
    String value();
}
```

then the annotations could be written as

[Click here to view code image](#)

```
@ActionListenerFor("yellowButton")
```

instead of

[Click here to view code image](#)

```
@ActionListenerFor(value="yellowButton")
```

An item can have multiple annotations:

[Click here to view code image](#)

```
@Test
@BugReport(showStopper=true, reportedBy="Joe")
public void checkRandomInsertions()
```

If the author of an annotation declared it to be repeatable, you can repeat the same annotation multiple times:

[Click here to view code image](#)

```
@BugReport(showStopper=true, reportedBy="Joe")
@BugReport(reportedBy={"Harry", "Carl"})
public void checkRandomInsertions()
```



Note

Since annotations are evaluated by the compiler, all element values must be compile-time constants. For example,

[Click here to view code image](#)

```
@BugReport(showStopper=true, assignedTo="Harry",
testCase=MyTestCase.class,
status=BugReport.Status.CONFIRMED, . . .)
```



Caution

An annotation element can never be set to null. Not even a default of null is permissible. This can be rather inconvenient in practice. You will need to find other defaults, such as "" or Void.class.

If an element value is an array, enclose its values in braces:

[Click here to view code image](#)

```
@BugReport(. . ., reportedBy={"Harry", "Carl"})
```

You can omit the braces if the element has a single value:

[Click here to view code image](#)

```
@BugReport(. . ., reportedBy="Joe") // OK, same as {"Joe"}
```

Since an annotation element can be another annotation, you can build arbitrarily complex annotations. For example,

[Click here to view code image](#)

```
@BugReport(ref=@Reference(id="3352627"), . . .)
```



Note

It is an error to introduce circular dependencies in annotations. For example, BugReport has an element of the annotation type Reference, therefore Reference cannot have an element of type BugReport.

8.4.3 Annotating Declarations

There are many places where annotations can occur. They fall into two categories: *declarations* and *type uses*. Declaration annotations can appear at the declarations of

- Packages
- Classes (including enum)
- Interfaces (including annotation interfaces)
- Methods
- Constructors
- Instance fields (including enum constants)
- Local variables
- Parameter variables
- Type parameters

For classes and interfaces, put the annotations before the `class` or `interface` keyword:

[Click here to view code image](#)

```
@Entity public class User { . . . }
```

For variables, put them before the type:

[Click here to view code image](#)

```
@SuppressWarnings("unchecked") List<User> users = . . .;
public User getUser(@Param("id") String userId)
```

A type parameter in a generic class or method can be annotated like this:

[Click here to view code image](#)

```
public class Cache<@Immutable V> { . . . }
```

A package is annotated in a file `package-info.java` that contains only the package statement preceded by annotations.

[Click here to view code image](#)

```
/***
 * Package-level Javadoc
 */
@GPL(version="3")
package com.horstmann.corejava;
import org.gnu.GPL;
```



Note

Annotations for local variables can only be processed at the source level. Class files do not describe local variables. Therefore, all local variable annotations are discarded when a class is compiled. Similarly, annotations for packages are not retained beyond the source level.

8.4.4 Annotating Type Uses

A declaration annotation provides some information about the item being declared. For example, in the declaration

[Click here to view code image](#)

```
public User getUser(@NonNull String userId)
```

it is asserted that the `userId` parameter is not null.



Note

The `@NotNull` annotation is a part of the Checker Framework (<https://checkerframework.org>). With that framework, you can include assertions in your program—for example, that a parameter is non-null or that a `String` contains a regular expression. A static analysis tool then checks whether the assertions are valid in a given body of source code.

Now, suppose we have a parameter of type `List<String>`, and we want to express that all of the strings are non-null. That is where type use annotations come in. Place the annotation before the type argument: `List<@NotNull String>`.

Type use annotations can appear in the following places:

- With generic type arguments: `List<@NotNull String>`, `Comparator.<@NotNull String> reverseOrder()`.
- In any position of an array: `@NotNull String[][] words` (`words[i][j]` is not null), `String @NotNull [][] words` (`words` is not null), `String[] @NotNull [] words` (`words[i]` is not null).
- With superclasses and implemented interfaces: `class Warning extends @Localized Message`.
- With constructor invocations: `new @Localized String(...)`.
- With casts and instanceof checks: `(@Localized String) text, if (text instanceof @Localized String)`. (The annotations are only for use by external tools. They have no effect on the behavior of a cast or an instanceof check.)
- With exception specifications: `public String read() throws @Localized IOException`.

- With wildcards and type bounds: `List<@Localized ? extends Message>, List<? extends @Localized Message>`.
- With method and constructor references: `@Localized Message::getText`.

There are a few type positions that cannot be annotated:

[Click here to view code image](#)

```
@NonNull String.class // ERROR: Cannot annotate class literal
import java.lang.@NonNull String; // ERROR: Cannot annotate
import
```

You can place annotations before or after other modifiers such as `private` and `static`. It is customary (but not required) to put type use annotations after other modifiers, and declaration annotations before other modifiers. For example,

[Click here to view code image](#)

```
private @NonNull String text; // Annotates the type use
@Id private String userId; // Annotates the variable
```

When annotating a record component, the annotation also applies to the generated field, getter method, and constructor parameter.



Note

An annotation author needs to specify where a particular annotation can appear. If an annotation is permissible both for a variable and a type use, and it is used in a variable declaration, then both the variable and the type use are annotated. For example, consider

[Click here to view code image](#)

```
public User getUser(@NonNull String userId)
```

If `@NonNull` can apply both to parameters and to type uses, the `userId` parameter is annotated, and the parameter type is `@NonNull`

String.

8.4.5 Annotating `this`

Suppose you want to annotate parameters that are not being mutated by a method.

[Click here to view code image](#)

```
public class Point
{
    public boolean equals(@ReadOnly Object other) { . . . }
}
```

Then a tool that processes this annotation would, upon seeing a call

```
p.equals(q)
```

reason that `q` has not been changed.

But what about `p`?

When the method is called, the `this` variable is bound to `p`. But `this` is never declared, so you cannot annotate it.

Actually, you can declare it, with a rarely used syntax variant, just so that you can add an annotation:

[Click here to view code image](#)

```
public class Point
{
    public boolean equals(@ReadOnly Point this, @ReadOnly Object
other) { . . . }
}
```

The first parameter is called the *receiver parameter*. It must be named `this`. Its type is the class that is being constructed.



Note

You can provide a receiver parameter only for methods, not for constructors. Conceptually, the `this` reference in a constructor is not an object of the given type until the constructor has completed. Instead, an annotation placed on the constructor describes a property of the constructed object.

A different hidden parameter is passed to the constructor of an inner class, namely the reference to the enclosing class object. You can make that parameter explicit as well:

[Click here to view code image](#)

```
public class Sequence
{
    private int from;
    private int to;

    class Iterator implements java.util.Iterator<Integer>
    {
        private int current;
        public Iterator(@ReadOnly Sequence Sequence.this)
        {
            this.current = Sequence.this.from;
        }
        . . .
    }
    . . .
}
```

The parameter must be named just like when you refer to it, `EnclosingClass.this`, and its type is the enclosing class.

8.5 Standard Annotations

A number of annotation interfaces are defined in the `java.lang`, `java.lang.annotation`, and `javax.annotation` packages. Four of them are meta-annotations that describe the behavior of annotation interfaces. The others are regular annotations that you can use to annotate items in your source code. [Table 8.2](#) shows these annotations. We'll discuss them in detail in the following two sections.

Table 8.2 The Standard Annotations

| Annotation Interface | Applicable To | Purpose |
|----------------------|----------------------------------|--|
| Deprecated | All | Marks item as deprecated. |
| SuppressWarnings | All but packages and annotations | Suppresses warnings of the given type. |
| SafeVarargs | Methods and constructors | Asserts that the varargs parameter is safe to use. |
| Override | Methods | Checks that this method overrides a superclass method. |
| Serializable | Methods | Checks that this method is a correct serialization method. |
| FunctionalInterface | Interfaces | Marks an interface as functional (with a single abstract method). |
| Generated | All | Marks an item as source code that has been generated by a tool. |
| Target | Annotations | Specifies the items to which this annotation can be applied. |
| Retention | Annotations | Specifies how long this annotation is retained. |
| Documented | Annotations | Specifies that this annotation should be included in the documentation of annotated items. |

| Annotation Interface | Applicable To | Purpose |
|------------------------|---------------|--|
| Inherited Annotations | Annotations | Specifies that this annotation, when applied to a class, is automatically inherited by its subclasses. |
| Repeatable Annotations | Annotations | Specifies that this annotation can be applied multiple times to the same item. |

8.5.1 Annotations for Compilation

The `@Deprecated` annotation can be attached to any items whose use is no longer encouraged. The compiler will warn when you use a deprecated item. This annotation has the same role as the `@deprecated` Javadoc tag. However, the annotation persists until runtime.



Note

The `jdeprscan` utility that is part of the JDK can scan a set of JAR files for deprecated elements.

The `@SuppressWarnings` annotation tells the compiler to suppress warnings of a particular type, for example:

[Click here to view code image](#)

```
@SuppressWarnings("unchecked")
```

The `@Override` annotation applies only to methods. The compiler checks that a method with this annotation really overrides a method from the superclass. For example, if you declare

[Click here to view code image](#)

```
public MyClass
{
```

```

@Override public boolean equals(MyClass other);
. . .
}

```

then the compiler will report an error. After all, the `equals` method does *not* override the `equals` method of the `Object` class because that method has a parameter of type `Object`, not `MyClass`.

The `@Generated` annotation is intended for use by code generator tools. Any generated source code can be annotated to differentiate it from programmer-created code. For example, a code editor can hide the generated code, or a code generator can remove older versions of generated code. Each annotation must contain a unique identifier for the code generator. A date string (in ISO 8601 format) and a comment string are optional. For example,

[Click here to view code image](#)

```

@Generated("com.horstmann.beanproperty", "2008-01-
04T12:08:56.235-0700");

```

8.5.2 Meta-Annotations

The `@Target` meta-annotation is applied to an annotation, restricting the items to which the annotation applies. For example,

[Click here to view code image](#)

```

@Target({ElementType.TYPE, ElementType.METHOD})
public @interface BugReport

```

Table 8.3 shows all possible values. They belong to the enumerated type `ElementType`. You can specify any number of element types, enclosed in braces.

Table 8.3 Element Types for the `@Target` Annotation

| Element Type | Annotation Applies To |
|--------------|-----------------------|
|--------------|-----------------------|

| Element Type | Annotation Applies To |
|---------------------|--|
| ANNOTATION_TYPE | Annotation type declarations |
| PACKAGE | Packages |
| TYPE | Classes (including enum) and interfaces (including annotation types) |
| METHOD | Methods |
| CONSTRUCTOR | Constructors |
| FIELD | Fields (including enum constants) |
| PARAMETER | Method or constructor parameters |
| LOCAL_VARIABLE | Local variables |
| TYPE_PARAMETER | Type parameters |
| TYPE_USE | Uses of a type |

An annotation without an @Target restriction can be applied to any item. The compiler checks that you apply an annotation only to a permitted item. For example, if you apply @BugReport to a field, a compile-time error results.

The @Retention meta-annotation specifies how long an annotation is retained. You can specify at most one of the values in [Table 8.4](#). The default is RetentionPolicy.CLASS.

Table 8.4 Retention Policies for the @Retention Annotation

| Retent
on
Policy | Description |
|---------------------------------|--|
| SOURCE | Annotations are not included in class files. |

| Retention Policy | Description |
|-------------------------|---|
| CLASS | Annotations are included in class files, but the virtual machine need not load them. |
| RUNTIME | Annotations are included in class files and loaded by the virtual machine. They are available through the reflection API. |

In Listing 8.8 on p. 474, the `@ActionListenerFor` annotation was declared with `RetentionPolicy.RUNTIME` because we used reflection to process annotations. In the following two sections, you will see examples of processing annotations at the source and class file levels.

The `@Documented` meta-annotation gives a hint to documentation tools such as Javadoc. Documented annotations should be treated just like other modifiers, such as `protected` or `static`, for documentation purposes. The use of other annotations is not included in the documentation. For example, suppose we declare `@ActionListenerFor` as a documented annotation:

[Click here to view code image](#)

```

@Documented
@Target(ElementType.METHOD)
@Retention(RetentionPolicy.RUNTIME)
public @interface ActionListenerFor

```

Now the documentation of each annotated method contains the annotation, as shown in Figure 8.2.




Figure 8.2 Documented annotations

If an annotation is transient (such as @BugReport), you should probably not document its use.



Note

It is legal to apply an annotation to itself. For example, the @Documented annotation is itself annotated as @Documented. Therefore, the Javadoc documentation for annotations shows whether they are documented.

The @Inherited meta-annotation applies only to annotations for classes. When a class has an inherited annotation, then all of its subclasses

automatically have the same annotation. This makes it easy to create annotations that work as marker interfaces, such as `Serializable`.

In fact, an annotation `@Serializable` would be more appropriate than the `Serializable` marker interface with no methods. A class is serializable because there is runtime support for reading and writing its fields, not because of any principles of object-oriented design. An annotation describes this fact better than does interface inheritance. Of course, the `Serializable` interface was created in JDK 1.1, long before annotations existed.

Suppose you define an inherited annotation `@Persistent` to indicate that objects of a class can be saved in a database. Then the subclasses of persistent classes are automatically annotated as persistent.

[Click here to view code image](#)

```
@Inherited @interface Persistent { }
@Persistent class Employee { . . . }
class Manager extends Employee { . . . } // also @Persistent
```

When the persistence mechanism searches for objects to store in the database, it will detect both `Employee` and `Manager` objects.

As of Java 8, it is legal to apply the same annotation type multiple times to an item. For backward compatibility, the implementor of a repeatable annotation needs to provide a *container annotation* that holds the repeated annotations in an array.

Here is how to define the `@TestCase` annotation and its container:

```
@Repeatable(TestCases.class)
@interface TestCase
{
    String params();
    String expected();
}

@interface TestCases
```

```
{  
    TestCase[] value();  
}
```

Whenever the user supplies two or more @TestCase annotations, they are automatically wrapped into a @TestCases annotation.



Caution

You have to be careful when processing repeatable annotations. If you call `getAnnotation` to look up a repeatable annotation, and the annotation was actually repeated, then you get `null`. That is because the repeated annotations were wrapped into the container annotation.

In that case, you should call `getAnnotationsByType`. That call “looks through” the container and gives you an array of the repeated annotations. If there was just one annotation, you get it in an array of length 1. With this method, you don’t have to worry about the container annotation.

8.6 Source-Level Annotation Processing

In the preceding section, you saw how to analyze annotations in a running program. Another use for annotation is the automatic processing of source files to produce more source code, configuration files, scripts, or whatever else one might want to generate.

8.6.1 Annotation Processors

Annotation processing is integrated into the Java compiler. During compilation, you can *invoke annotation processors* by running

[Click here to view code image](#)

```
javac -processor ProcessorClassName1,ProcessorClassName2,. . .
sourceFiles
```

The compiler locates the annotations of the source files. Each annotation processor is executed in turn and given the annotations in which it expressed an interest. If an annotation processor creates a new source file, the process is repeated. Once a processing round yields no further source files, all source files are compiled.



Note

An annotation processor can only generate new source files. It cannot modify an existing source file.

An annotation processor implements the `Processor` interface, generally by extending the `AbstractProcessor` class. You need to specify which annotations your processor supports. In our case:

[Click here to view code image](#)

```
@SupportedAnnotationTypes("com.horstmann.annotations.ToString")
@SupportedSourceVersion(SourceVersion.RELEASE_8)
public class ToStringAnnotationProcessor extends
AbstractProcessor
{
    public boolean process(Set<? extends TypeElement>
annotations,
                           RoundEnvironment currentRound)
    {
        . . .
    }
}
```

A processor can claim specific annotation types, wildcards such as `"com.horstmann.*"` (all annotations in the `com.horstmann` package or any subpackage), or even `"*"` (all annotations).

The process method is called once for each round, with the set of all annotations that were found in any files during this round, and a RoundEnvironment reference that contains information about the current processing round.

8.6.2 The Language Model API

Use the *language model* API for analyzing source-level annotations. Unlike the reflection API, which presents the virtual machine representation of classes and methods, the language model API lets you analyze a Java program according to the rules of the Java language.

The compiler produces a tree whose nodes are instances of classes that implement the javax.lang.model.element.Element interface and its subinterfaces: TypeElement, VariableElement, ExecutableElement, and so on. These are the compile-time analogs to the Class, Field/Parameter, Method/Constructor reflection classes.

I do not want to cover the API in detail, but here are the highlights that you need to know for processing annotations:

- The RoundEnvironment gives you a set of all elements annotated with a particular annotation. Call the method

[Click here to view code image](#)

```
Set<? extends Element> getElementsAnnotatedWith(Class<? extends Annotation> a)
```

- The source-level equivalent of the AnnotateElement interface is AnnotatedConstruct. Use the methods

[Click here to view code image](#)

```
A getAnnotation(Class<A> annotationType)
A[] getAnnotationsByType(Class<A> annotationType)
```

to get the annotation or repeated annotations for a given annotation class.

- A TypeElement represents a class or interface. The getEnclosedElements method yields a list of its fields and methods.
- Calling getSimpleName on an Element or getQualifiedName on a TypeElement yields a Name object that can be converted to a string with `toString`.

8.6.3 Using Annotations to Generate Source Code

As an example, we will use annotations to reduce the tedium of implementing `toString` methods. We can't put these methods into the original classes—annotation processors can only produce new classes, not modify existing ones.

Therefore, we'll add all methods into a utility class `ToStrings`:

[Click here to view code image](#)

```
public class ToStrings
{
    public static String toString(Point obj)
    {
        Generated code
    }

    public static String toString(Rectangle obj)
    {
        Generated code
    }

    . . .

    public static String toString(Object obj)
    {
        return Objects.toString(obj);
    }
}
```

We don't want to use reflection, so we annotate accessor methods, not fields:

[Click here to view code image](#)

```
@ToString  
public class Rectangle  
{  
    . . .  
    @ToString(includeName=false) public Point getTopLeft() {  
        return topLeft; }  
    @ToString public int getWidth() { return width; }  
    @ToString public int getHeight() { return height; }  
}
```

The annotation processor should then generate the following source code:

[Click here to view code image](#)

```
public static String toString(Rectangle obj)  
{  
    var result = new StringBuilder();  
    result.append("Rectangle");  
    result.append("[");  
    result.append(toString(obj.getTopLeft()));  
    result.append(",");  
    result.append("width=");  
    result.append(toString(obj.getWidth()));  
    result.append(",");  
    result.append("height=");  
    result.append(toString(obj.getHeight()));  
    result.append("]");  
    return result.toString();  
}
```

The “boilerplate” code is in gray. Here is an outline of the method that produces the `toString` method for a class with a given `TypeElement`:

[Click here to view code image](#)

```
private void writeToStringMethod(PrintWriter out, TypeElement  
        te)  
{
```

```

String className = te.getQualifiedName().toString();
Print method header and declaration of string builder
ToString ann = te.getAnnotation(ToString.class);
if (ann.includeName())
    Print code to add class name
for (Element c : te.getEnclosedElements())
{
    ann = c.getAnnotation(ToString.class);
    if (ann != null)
    {
        if (ann.includeName()) Print code to add field name
        Print code to append toString(obj.methodName())
    }
}
Print code to return string
}

```

And here is an outline of the `process` method of the annotation processor. It creates a source file for the helper class and writes the class header and one method for each annotated class.

[Click here to view code image](#)

```

public boolean process(Set<? extends TypeElement> annotations,
                      RoundEnvironment currentRound)
{
    if (annotations.size() == 0) return true;
    try
    {
        JavaFileObject sourceFile =
processingEnv.getFiler().createSourceFile(
            "com.horstmann.annotations.ToStrings");
        try (var out = new PrintWriter(sourceFile.openWriter()))
        {
            Print code for package and class
            for (Element e :
currentRound.getElementsAnnotatedWith(ToString.class))
                if (e instanceof TypeElement te)

```

```

        writeToStringMethod(out, te);
        Print code for toString(Object)
    }
    catch (IOException e)
    {
        processingEnv.getMessager().printMessage(
            Kind.ERROR, ex.getMessage());
    }
}
return true;
}

```

For the tedious details, check the book's companion code.

Note that the process method is called in subsequent rounds with an empty list of annotations. It then returns immediately so it doesn't create the source file twice.

First, compile the annotation processor, and then compile and run the test program as follows:

[Click here to view code image](#)

```

javac sourceAnnotations/ToStringAnnotationProcessor.java
javac -processor sourceAnnotations.ToStringAnnotationProcessor
rect/*.java
java rect.SourceLevelAnnotationDemo

```



Tip

To see the rounds, run the `javac` command with the `-XprintRounds` flag:

[Click here to view code image](#)

Round 1:

```

input files: {rect.Point, rect.Rectangle,
rect.SourceLevelAnnotationDemo}

```

```
annotations: [sourceAnnotations.ToString]
last round: false
Round 2:
    input files: {sourceAnnotations.ToStrings}
    annotations: []
    last round: false
Round 3:
    input files: {}
    annotations: []
    last round: true
```

This example demonstrates how tools can harvest source file annotations to produce other files. The generated files don't have to be source files. Annotation processors may choose to generate XML descriptors, property files, shell scripts, HTML documentation, and so on.



Note

Some people have suggested using annotations to remove an even bigger drudgery. Wouldn't it be nice if trivial getters and setters were generated automatically? For example, the annotation

[Click here to view code image](#)

```
@Property private String title;
```

could produce the methods

[Click here to view code image](#)

```
public String getTitle() { return title; }
public void setTitle(String title) { this = title; }
```

However, those methods need to be added to the *same class*. This requires editing a source file, not just generating another file, and is beyond the capabilities of annotation processors. It would be possible to build another tool for this purpose, but such a tool would go beyond

the mission of annotations. An annotation is intended as a description *about* a code item, not a directive for adding or changing code.

8.7 Bytecode Engineering

You have seen how annotations can be processed at runtime or at the source code level. There is a third possibility: processing at the bytecode level. Unless annotations are removed at the source level, they are present in the class files. The class file format is documented (see <http://docs.oracle.com/javase/specs/jvms/se10/html>) . The format is rather complex, and it would be challenging to process class files without special libraries. One such library is the ASM library, available at <https://asm.ow2.org>. Download `asm-9.2.jar` and `asm-commons-9.2.jar` and place them in a directory of your choice, called `asm` in the instructions.

8.7.1 Modifying Class Files

In this section, we use ASM to add logging messages to annotated methods. If a method is annotated with

```
@LogEntry(logger=loggerName)
```

then we add the bytecodes for the following statement at the beginning of the method:

[Click here to view code image](#)

```
Logger.getLogger(loggerName).entering(className, methodName);
```

For example, if you annotate the `hashCode` method of the `Item` class as

[Click here to view code image](#)

```
@LogEntry(logger="global") public int hashCode()
```

then a message similar to the following is printed whenever the method is called:

[Click here to view code image](#)

```
May 17, 2016 10:57:59 AM Item hashCode
FINER: ENTRY
```

To achieve this, we do the following:

1. Load the bytecodes in the class file.
2. Locate all methods.
3. For each method, check whether it has a `LogEntry` annotation.
4. If it does, add the bytecodes for the following instructions at the beginning of the method:

[Click here to view code image](#)

```
ldc loggerName
invokestatic
    java/util/logging/Logger.getLogger:
(Ljava/lang/String;)Ljava/util/logging/Logger;
ldc className
ldc methodName
invokevirtual
    java/util/logging/Logger.entering:
(Ljava/lang/String;Ljava/lang/String;)V
```

Inserting these bytecodes sounds tricky, but ASM makes it fairly straightforward. We don't describe the process of analyzing and inserting bytecodes in detail. The important point is that the program in [Listing 8.9](#) edits a class file and inserts a logging call at the beginning of the methods annotated with the `LogEntry` annotation.

For example, here is how you add the logging instructions to `Item.java` in [Listing 8.10](#), where `asm` is the directory into which you installed the ASM library:

[Click here to view code image](#)

```
javac set/Item.java  
javac -classpath .:asm/* bytecodeAnnotations/EntryLogger.java  
java -classpath .:asm/* bytecodeAnnotations.EntryLogger  
set.Item
```

Try running

```
javap -c set.Item
```

before and after modifying the Item class file. You can see the inserted instructions at the beginning of the hashCode, equals, and compareTo methods.

[Click here to view code image](#)

```
public int hashCode();  
Code:  
0: ldc #85; // String global  
2: invokestatic #80;  
   // Method  
   // java/util/logging/Logger.getLogger:  
(Ljava/lang/String;)Ljava/util/logging/Logger;  
5: ldc #86; //String Item  
7: ldc #88; //String hashCode  
9: invokevirtual #84;  
   // Method java/util/logging/Logger.entering:  
(Ljava/lang/String;Ljava/lang/String;)V  
12: bipush 13  
14: aload_0  
15: getfield #2; // Field  
description:Ljava/lang/String;  
18: invokevirtual #15; // Method  
java/lang/String.hashCode:()I  
21: imul  
22: bipush 17  
24: aload_0  
25: getfield #3; // Field partNumber:I  
28: imul
```

```
29:    iadd  
30:    ireturn
```

The SetTest program in [Listing 8.11](#) inserts Item objects into a hash set. When you run it with the modified class file, you will see the logging messages.

[Click here to view code image](#)

```
May 17, 2016 10:57:59 AM Item hashCode  
FINER: ENTRY  
May 17, 2016 10:57:59 AM Item hashCode  
FINER: ENTRY  
May 17, 2016 10:57:59 AM Item hashCode  
FINER: ENTRY  
May 17, 2016 10:57:59 AM Item equals  
FINER: ENTRY  
[[description=Toaster, partNumber=1729],  
[description=Microwave, partNumber=4104]]
```

Note the call to equals when we insert the same item twice.

This example shows the power of bytecode engineering. Annotations are used to add directives to a program, and a bytecode editing tool picks up the directives and modifies the virtual machine instructions.

Listing 8.9 bytecodeAnnotations/EntryLogger.java

[Click here to view code image](#)

```
1 package bytecodeAnnotations;  
2  
3 import java.io.*;  
4 import java.nio.file.*;  
5  
6 import org.objectweb.asm.*;  
7 import org.objectweb.asm.commons.*;  
8  
9 /**
```

```
10 * Adds "entering" logs to all methods of a class that have
11 the LogEntry annotation.
12 * @version 1.21 2018-05-01
13 * @author Cay Horstmann
14 */
15 public class EntryLogger extends ClassVisitor
16 {
17     private String className;
18     /**
19      * Constructs an EntryLogger that inserts logging into
20      * annotated methods of a given class.
21     */
22     public EntryLogger(ClassWriter writer, String className)
23     {
24         super(Opcodes.ASM5, writer);
25         this.className = className;
26     }
27     public MethodVisitor visitMethod(int access, String
methodName, String desc,
28                                     String signature, String[] exceptions)
29     {
30         MethodVisitor mv = cv.visitMethod(access, methodName,
desc, signature, exceptions);
31         return new AdviceAdapter(Opcodes.ASM5, mv, access,
methodName, desc)
32     {
33         private String loggerName;
34
35         public AnnotationVisitor visitAnnotation(String desc,
boolean visible)
36         {
37             return new AnnotationVisitor(Opcodes.ASM5)
38             {
39                 public void visit(String name, Object value)
40                 {
41                     if
```

```
(desc.equals("LbytecodeAnnotations/LogEntry;"))
42                         && name.equals("logger"))
43                     loggerName = value.toString();
44                 }
45             };
46         }
47     }
48     public void onMethodEnter()
49     {
50         if (loggerName != null)
51         {
52             visitLdcInsn(loggerName);
53             visitMethodInsn(INVOKESTATIC,
"java/util/logging/Logger", "getLogger",
54                         "
(Ljava/lang/String;)Ljava/util/logging/Logger;, false);
55             visitLdcInsn(className);
56             visitLdcInsn(methodName);
57             visitMethodInsn(INVOKEVIRTUAL,
"java/util/logging/Logger", "entering",
58                         "(Ljava/lang/String;Ljava/lang/String;)V",
false);
59             loggerName = null;
60         }
61     }
62 }
63 }
64
65 /**
66 * Adds entry logging code to the given class.
67 * @param args the name of the class file to patch
68 */
69 public static void main(String[] args) throws IOException
70 {
71     if (args.length == 0)
72     {
73         System.out.println("USAGE: java
bytecodeAnnotations.EntryLogger classfile");
```

```
74         System.exit(1);
75     }
76     Path path = Path.of(args[0]);
77     var reader = new ClassReader(Files.newInputStream(path));
78     var writer = new ClassWriter(
79         ClassWriter.COMPUTE_MAXS |
    ClassWriter.COMPUTE_FRAMES);
80     var entryLogger = new EntryLogger(writer,
81         path.toString().replace(".class", "").replaceAll(
82             "[/\\\\\\\\]", "."));
83     reader.accept(entryLogger, ClassReader.EXPAND_FRAMES);
84     Files.write(Path.of(args[0]), writer.toByteArray());
85 }
```

Listing 8.10 set/Item.java

[Click here to view code image](#)

```
1 package set;
2
3 import java.util.*;
4 import bytecodeAnnotations.*;
5
6 /**
7  * An item with a description and a part number.
8  * @version 1.01 2012-01-26
9  * @author Cay Horstmann
10 */
11 public class Item
12 {
13     private String description;
14     private int partNumber;
15
16     /**
17      * Constructs an item.
18      * @param aDescription the item's description
19      * @param aPartNumber the item's part number
```

```
20     */
21     public Item(String aDescription, int aPartNumber)
22     {
23         description = aDescription;
24         partNumber = aPartNumber;
25     }
26
27     /**
28      * Gets the description of this item.
29      * @return the description
30      */
31     public String getDescription()
32     {
33         return description;
34     }
35
36     public String toString()
37     {
38         return "[description=" + description + ", partNumber=" +
partNumber + "]";
39     }
40
41     @LogEntry(logger = "com.horstmann")
42     public boolean equals(Object otherObject)
43     {
44         if (this == otherObject) return true;
45         if (otherObject == null) return false;
46         if (getClass() != otherObject.getClass()) return false;
47         var other = (Item) otherObject;
48         return Objects.equals(description, other.description) &&
partNumber == other.partNumber;
49     }
50
51     @LogEntry(logger = "com.horstmann")
52     public int hashCode()
53     {
54         return Objects.hash(description, partNumber);
```

```
55      }
56 }
```

Listing 8.11 set/SetTest.java

[Click here to view code image](#)

```
1 package set;
2
3 import java.util.*;
4 import java.util.logging.*;
5
6 /**
7 * @version 1.03 2018-05-01
8 * @author Cay Horstmann
9 */
10 public class SetTest
11 {
12     public static void main(String[] args)
13     {
14
15         Logger.getLogger("com.horstmann").setLevel(Level.FINEST);
16         var handler = new ConsoleHandler();
17         handler.setLevel(Level.FINEST);
18         Logger.getLogger("com.horstmann").addHandler(handler);
19
20         var parts = new HashSet<Item>();
21         parts.add(new Item("Toaster", 1279));
22         parts.add(new Item("Microwave", 4104));
23         parts.add(new Item("Toaster", 1279));
24         System.out.println(parts);
25     }
26 }
```

8.7.2 Modifying Bytecodes at Load Time

In the last section, you saw a tool that edits class files. However, it can be cumbersome to add yet another tool into the build process. An attractive alternative is to defer the bytecode engineering until *load time*, when the class loader loads the class.

The *instrumentation API* has a hook for installing a bytecode transformer. The transformer must be installed before the `main` method of the program is called. You can meet this requirement by defining an *agent*, a library that is loaded to monitor a program in some way. The agent code can carry out initializations in a `premain` method.

Here are the steps required to build an agent:

1. Implement a class with a method

[Click here to view code image](#)

```
public static void premain(String arg, Instrumentation  
instr)
```

This method is called when the agent is loaded. The agent can get a single command-line argument, which is passed in the `arg` parameter. The `instr` parameter can be used to install various hooks.

2. Make a manifest file `EntryLoggingAgent.mf` that sets the `Premain-Class` attribute, for example:

[Click here to view code image](#)

```
Premain-Class: bytecodeAnnotations.EntryLoggingAgent
```

3. Package the agent code and the manifest into a JAR file:

[Click here to view code image](#)

```
javac -classpath .:asm/*  
bytecodeAnnotations/EntryLoggingAgent.java  
jar cvfm EntryLoggingAgent.jar  
bytecodeAnnotations/EntryLoggingAgent.mf \  
bytecodeAnnotations/Entry*.class
```

To launch a Java program together with the agent, use the following command-line options:

[Click here to view code image](#)

```
java -javaagent:AgentJARFile=agentArgument . . .
```

For example, to run the `SetTest` program with the entry logging agent, call

[Click here to view code image](#)

```
javac set/SetTest.java  
java -javaagent:EntryLoggingAgent.jar=set.Item -classpath  
.:/asm/* set.SetTest
```

The `Item` argument is the name of the class that the agent should modify.

[Listing 8.12](#) shows the agent code. The agent installs a class file transformer. The transformer first checks whether the class name matches the agent argument. If so, it uses the `EntryLogger` class from the preceding section to modify the bytecodes. However, the modified bytecodes are not saved to a file. Instead, the transformer returns them for loading into the virtual machine (see [Figure 8.3](#)). In other words, this technique carries out “just in time” modification of the bytecodes.




Figure 8.3 Modifying classes at load time

Listing 8.12

bytecodeAnnotations/EntryLoggingAgent.java

[Click here to view code image](#)

```
1 package bytecodeAnnotations;
2
3 import java.lang.instrument.*;
4
5 import org.objectweb.asm.*;
6
7 /**
8 * @version 1.11 2018-05-01
9 * @author Cay Horstmann
10 */
11 public class EntryLoggingAgent
12 {
13     public static void premain(final String arg,
Instrumentation instr)
14     {
15         instr.addTransformer(new ClassFileTransformer()
16         {
17             public byte[] transform(ClassLoader loader, String
className, Class<?> cl,
18                         ProtectionDomain pd, byte[] data) throws
IllegalClassFormatException
19             {
20                 if (!className.replace("/", ".").equals(arg))
return null;
21                 var reader = new ClassReader(data);
22                 var writer = new ClassWriter(
23                     ClassWriter.COMPUTE_MAXS |
ClassWriter.COMPUTE_FRAMES);
24                 var el = new EntryLogger(writer, className);
25                 reader.accept(el, ClassReader.EXPAND_FRAMES);
26                 return writer.toByteArray();

```

```
27         }
28     } );
29 }
30 }
```

In this chapter, you have learned how to

- Add annotations to Java programs
- Design your own annotation interfaces
- Implement tools that make use of the annotations

You have seen three technologies for processing code: scripting, compiling Java programs, and processing annotations. The first two were quite straightforward. On the other hand, building annotation tools is undeniably complex and not something that most developers will need to tackle. This chapter gave you the background for understanding the inner workings of the annotation tools you will encounter, and perhaps piqued your interest in developing your own tools.

The following chapter discusses the Java Platform Module System, the key feature of Java 9 that is important for moving the Java platform forward.

Chapter 9. The Java Platform Module System

In this chapter

- [9.1 The Module Concept](#)
- [9.2 Naming Modules](#)
- [9.3 The Modular “Hello, World!” Program](#)
- [9.4 Requiring Modules](#)
- [9.5 Exporting Packages](#)
- [9.6 Modular JARs](#)
- [9.7 Modules and Reflective Access](#)
- [9.8 Automatic Modules](#)
- [9.9 The Unnamed Module](#)
- [9.10 Command-Line Flags for Migration](#)
- [9.11 Transitive and Static Requirements](#)
- [9.12 Qualified Exporting and Opening](#)
- [9.13 Service Loading](#)
- [9.14 Tools for Working with Modules](#)

An important characteristic of object-oriented programming is encapsulation. A class declaration consists of a public interface and a

private implementation. A class can evolve by changing the implementation without affecting its users. A module system provides the same benefits for programming in the large. A module can make classes and packages selectively available so that its evolution can be controlled.

Several existing Java module systems rely on class loaders to isolate classes. However, Java 9 introduced a new system, called the Java Platform Module System, that is supported by the Java compiler and virtual machine. It was designed to modularize the large code base of the Java platform. You can, if you choose, use this system to modularize your own applications.

Whether or not you use Java platform modules in your own applications, you may be impacted by the modularized Java platform. This chapter shows you how to declare and use Java platform modules. You will also learn how to migrate your applications to work with the modularized Java platform and third-party modules.

9.1 The Module Concept

In object-oriented programming, the fundamental building block is the class. Classes provide encapsulation. Private features can only be accessed by code that has explicit permission—namely, the methods of the class. This makes it possible to reason about access. If a private variable has changed, you can produce a set of all possible culprits. If you need to modify the private representation, you know which methods are affected.

In Java, packages provide the next larger organizational grouping. A package is a collection of classes. Packages also provide a level of encapsulation. Any feature with package access (neither public nor private) is accessible only from methods in the same package.

However, in large systems, this level of access control is not enough. Any public feature (that is, a feature that is accessible outside a package) is accessible everywhere. Suppose you want to modify or drop a rarely used feature. Once it is public, there is no way to reason about the impact of that change.

This is the situation that the Java platform designers faced. Over twenty years, the JDK grew by leaps and bounds, but clearly some features are now essentially obsolete. Everyone's favorite example is CORBA. When was the last time you used it? Yet, the `org.omg.corba` package was shipped with every JDK until Java 10. As of Java 11, those few who still need it must add the required JAR files to their projects.

What about `java.awt`? It shouldn't be required in a server-side application, right? Except that the class `java.awt.DataFlavor` is used in the implementation of SOAP, an XML-based web services protocol.

The Java platform designers, faced with a giant hairball of code, decided that they needed a structuring mechanism that provides more control. They looked at existing module systems (such as OSGi) and found them unsuitable for their problem. Instead, they designed a new system, called the *Java Platform Module System*, that is now a part of the Java language and virtual machine. That system has been used successfully to modularize the Java API, and you can, if you so choose, use it with your own applications.

A Java platform module consists of

- A collection of packages
- Optionally, resource files and other files such as native libraries
- A list of the accessible packages in the module
- A list of all modules on which this module depends

The Java platform enforces encapsulation and dependencies, both at compile time and in the virtual machine.

Why should you consider using the Java Platform Module System for your own programs instead of following the traditional approach of using JAR files on the class path? There are two advantages.

1. Strong encapsulation: You can control which of your packages are accessible, and you don't have to worry about maintaining code that you didn't intend for public consumption.

2. Reliable configuration: You avoid common class path problems such as duplicate or missing classes.

There are some issues that the Java Platform Module System does not address, such as versioning of modules. There is no support for specifying which version of a module is required, or for using multiple versions of a module in the same program. These can be desirable features, but you must use mechanisms other than the Java Platform Module System if you need them.

9.2 Naming Modules

A module is a collection of packages. The package names in the module need not be related. For example, the module `java.sql` contains packages `java.sql`, `javax.sql`, and `javax.transaction.xa`. Also, as you can see from this example, it is perfectly acceptable for the module name to be the same as a package name.

Just like a path name, a module name is made up of letters, digits, underscores, and periods. Also, just as with path names, there is no hierarchical relationship between modules. If you had a module `com.horstmann` and another module `com.horstmann.corejava`, they would be unrelated, as far as the module system is concerned.

When creating a module for use by others, it is important to ensure that its name is globally unique. It is expected that most module names will follow the “reverse domain name” convention, just like package names.

The easiest approach is to name a module after the top-level package that the module provides. For example, the SLF4J logging façade has a module `org.slf4j` with packages `org.slf4j`, `org.slf4j.spi`, `org.slf4j.event`, and `org.slf4j.helpers`.

This convention prevents package name conflicts in modules. Any given package can only be placed in one module. If your module names are unique and your package names start with the module name, then your package names will also be unique.

You can use shorter module names for modules that are not meant to be used by other programmers, such as a module containing an application program. Just to show that it can be done, I will do the same in this chapter. Modules with what could plausibly be library code will have names such as com.horstmann.util, and modules containing programs (with a class that has a main method) will have catchy names such as v2ch09.hellomod.



Note

Module names are only used in module declarations. In the source files for your Java classes, you never refer to module names; instead, use package names the way they have always been used.

9.3 The Modular “Hello, World!” Program

Let us put the traditional “Hello, World!” program into a module. First, we need to put the class into a package—the “unnamed package” cannot be contained in a module. Here it is:

[Click here to view code image](#)

```
package com.horstmann.hello;

public class HelloWorld
{
    public static void main(String[] args)
    {
        System.out.println("Hello, Modular World!");
    }
}
```

So far, nothing has changed. To make a module v2ch09.hellomod containing this package, you need to add a module declaration. You place it in a file named module-info.java, located in the base directory (that

is, the same directory that contains the `com` directory). By convention, the name of the base directory is the same as the module name.

```
v2ch09.hellomod/
└ module-info.java
  com/
    └ horstmann/
      └ hello/
        └ HelloWorld.java
```

The `module-info.java` file contains the module declaration:

```
module v2ch09.hellomod
{}
```

This module declaration is empty because the module has nothing to offer to anyone, nor does it need anything.

Now, compile as usual:

[Click here to view code image](#)

```
javac v2ch09.hellomod/module-info.java
v2ch09.hellomod/com/horstmann/hello/HelloWorld.java
```

The `module-info.java` file doesn't look like a Java source file, and of course there can't be a class with the name `module-info`, since class names cannot contain hyphens. The `module` keyword, as well as keywords `requires`, `exports`, and so on, that you will see in the following sections, are “restricted keywords” that have a special meaning only in module declarations. The file is compiled into a class file `module-info.class` that contains the module definition in binary form.

To run this program as a modular application, you specify the *module path*, which is similar to the class path but contains modules. You also specify the main class in the format `modulename/classname`:

[Click here to view code image](#)

```
java --module-path v2ch09.hellomod --module  
v2ch09.hellomod/com.horstmann.hello.HelloWorld
```

Instead of `--module-path` and `--module`, you can use the single-letter options `-p` and `-m`:

[Click here to view code image](#)

```
java -p v2ch09.hellomod -m  
v2ch09.hellomod/com.horstmann.hello.HelloWorld
```

Either way, the "Hello, Modular World!" greeting will appear, demonstrating that you have successfully modularized your first application.



Note

When you compile this module, you get a warning:

[Click here to view code image](#)

```
warning: [module] module name component v2ch09 should avoid  
terminal digits
```

This warning is intended to discourage programmers from adding version numbers to module names. You can ignore the warning, or suppress it with an annotation:

```
@SuppressWarnings("module")  
module v2ch09.hellomod  
{  
}
```

In this one respect, the `module` declaration is just like a class declaration: You can annotate it. (The annotation type must have target `ElementType.MODULE`.)

9.4 Requiring Modules

Let us make a new module `v2ch09.requiremod` in which a program uses a `JOptionPane` to show the “Hello, Modular World!” message:

[Click here to view code image](#)

```
package com.horstmann.hello;

import javax.swing.JOptionPane;

public class HelloWorld
{
    public static void main(String[] args)
    {
        JOptionPane.showMessageDialog(null, "Hello, Modular
World!");
    }
}
```

Now compilation fails with this message:

[Click here to view code image](#)

```
error: package javax.swing is not visible
  (package javax.swing is declared in module java.desktop,
  but module v2ch09.requiremod does not read it)
```

The JDK has been modularized, and the `javax.swing` package is now contained in the `java.desktop` module. Our module needs to declare that it relies on that module:

```
module v2ch09.requiremod
{
    requires java.desktop;
}
```

It is a design goal of the module system that modules are explicit about their requirements, so the virtual machine can ensure that all requirements are fulfilled before starting a program.

In the preceding section, the need for explicit requirements did not arise because we only used the `java.lang` and `java.io` packages. These packages are included in the `java.base` module which is required by default.

Note that our `v2ch09.requiremod` module lists only its own module requirements. It requires the `java.desktop` module so that it can use the `javax.swing` package. The `java.desktop` module itself declares that it requires three other modules, namely `java.datatransfer`, `java.prefs`, and `java.xml`.

[Figure 9.1](#) shows the *module graph* whose nodes are modules. The edges of the graph—the arrows joining nodes—are either declared requirements or the implied requirement on `java.base` when none is declared.




Figure 9.1 The module graph of the Swing “Hello, Modular World” application

You cannot have cycles in the module graph—that is, a module cannot directly or indirectly require itself.

A module does not automatically pass on access rights to other modules. In our example, the `java.desktop` module declares that it requires `java.prefs`, and the `java.prefs` module declares that it requires `java.xml`. That does not give `java.desktop` the right to use packages from the `java.xml` module. It needs to explicitly declare that requirement. In mathematical terms, the `requires` relationship is not “transitive.” Generally, this behavior is desirable because it makes requirements explicit, but as you will see in [Section 9.11, “Transitive and Static Requirements,”](#) on p. 523, you can relax it in some cases.



Note

The error message at the beginning of this section stated that our `v2ch09.requiremod` module did not “read” the `java.desktop` module. In the parlance of the Java Platform Module System, module *M* *reads* module *N* in the following cases:

1. *M* requires *N*.
 2. *M* requires a module that transitively requires *N* (see [Section 9.11, “Transitive and Static Requirements,”](#) on p. 523).
 3. *N* is *M* or `java.base`.
-

9.5 Exporting Packages

In the preceding section, you saw that a module must require another module if it wants to use its packages. However, that does not automatically make all packages in the required module available. A module states which

of its packages are accessible, using the `exports` keyword. For example, here is a part of the module declaration for the `java.xml` module:

[Click here to view code image](#)

```
module java.xml
{
    exports javax.xml;
    exports javax.xml.catalog;
    exports javax.xml.datatype;
    exports javax.xml.namespace;
    exports javax.xml.parsers;
    ...
}
```

This module makes many packages available, but hides others (such as `jdk.xml.internal`) by not exporting them.

When a package is exported, its `public` and `protected` classes and interfaces, and their `public` and `protected` members, are accessible outside the module. (As always, `protected` types and members are accessible only in subclasses.)

However, a package that is not exported is not accessible outside its own module. This is quite different from Java before modules. In the past, you were able to use public classes from any package, even if it was not part of the public API. For example, it was commonly recommended to use classes such as `sun.misc.BASE64Encoder` or `com.sun.rowset.CachedRowSetImpl` when the public API did not provide the appropriate functionality.

Nowadays, you can no longer access unexported packages from the Java platform API since all of them are contained inside modules. As a result, some programs will no longer run with Java 9. Of course, nobody ever committed to keeping non-public APIs available, so this should not come as a shock.

Let us put `exports` to use in a simple situation. We will prepare a module `com.horstmann.greet` that exports a package, also called

com.horstmann.greet, following the convention that a module that provides code for others should be named after the top-level package inside it. There is also a package com.horstmann.greet.internal that we don't export.

A public Greeter interface is in the first package.

[Click here to view code image](#)

```
package com.horstmann.greet;

public interface Greeter
{
    static Greeter newInstance()
    {
        return new com.horstmann.greet.internal.GreeterImpl();
    }

    String greet(String subject);
}
```

The second package has a class that implements the interface. The class is public since it is accessed in the first package.

[Click here to view code image](#)

```
package com.horstmann.greet.internal;

import com.horstmann.greet.Greeter;

public class GreeterImpl implements Greeter
{
    public String greet(String subject)
    {
        return "Hello, " + subject + "!";
    }
}
```

The `com.horstmann.greet` module contains both packages but only exports the first:

```
module com.horstmann.greet
{
    exports com.horstmann.greet;
}
```

The second package is inaccessible outside the module.

We put our application into a second module, which will require the first module:

```
module v2ch09.exportedpkg
{
    requires com.horstmann.greet;
}
```



Note

The `exports` statement is followed by a package name, whereas `requires` is followed by a module name.

Our application now uses a Greeter to obtain a greeting:

[Click here to view code image](#)

```
package com.horstmann.hello;

import com.horstmann.greet.Greeter;

public class HelloWorld
{
    public static void main(String[] args)
    {
        Greeter greeter = Greeter.newInstance();
```

```
        System.out.println(greeter.greet("Modular World"));
    }
}
```

Here is the source file structure for these two modules:

```
com.horstmann.greet
├ module-info.java
└ com
  └ horstmann
    └ greet
      ├ Greeter.java
      └ internal
        └ GreeterImpl.java
v2ch09.exportedpkg
├ module-info.java
└ com
  └ horstmann
    └ hello
      └ HelloWorld.java
```

To build this application, first compile the `com.horstmann.greet` module:

[Click here to view code image](#)

```
javac com.horstmann.greet/module-info.java \
       com.horstmann.greet/com/horstmann/greet/Greeter.java \
       com.horstmann.greet/com/horstmann/greet/internal/GreeterImpl.ja
va
```

Then compile the application module with the first module on the module path:

[Click here to view code image](#)

```
javac -p com.horstmann.greet v2ch09.exportedpkg/module-
info.java \
```

v2ch09.exportedpkg/com/horstmann/hello/HelloWorld.java

Finally, run the program with both modules on the module path:

[Click here to view code image](#)

```
java -p v2ch09.exportedpkg:com.horstmann.greet \
      -m v2ch09.exportedpkg/com.horstmann.hello.HelloWorld
```



Tip

To build this application with Eclipse, make a separate project for each module. In the v2ch09.exportedpkg project, edit the project properties. In the Projects tab, add the com.horstmann.greet module to the module path—see [Figure 9.2](#).




Figure 9.2 Adding a dependent module to an Eclipse project

You have now seen the `requires` and `exports` statements that form the backbone of the Java Platform Module System. As you can see, the module system is conceptually simple. Modules specify what modules they need, and which packages they offer to other modules. [Section 9.12, “Qualified Exporting and Opening,”](#) on p. 525 shows a minor variation of the `exports` statement.



Caution

A module does not provide a scope. You cannot have two packages with the same name in different modules. This is true even for hidden packages (that is, packages that are not exported.)

9.6 Modular JARs

So far, we have simply compiled modules into the directory tree of the source code. Clearly, that is not satisfactory for deployment. Instead, a module can be deployed by placing all its classes in a JAR file, with a `module-info.class` in the root. Such a JAR file is called a *modular JAR*.

To create a modular JAR file, use the `jar` tool in the usual way. If you have multiple packages, it is best to compile with the `-d` option which places class files into a separate directory. The directory is created if it doesn't already exist. Then use the `-C` option of the `jar` command to change to that directory when collecting files.

[Click here to view code image](#)

```
javac -d modules/com.horstmann.greet $(find com.horstmann.greet  
-name *.java)  
jar -c -v -f com.horstmann.greet.jar -C  
modules/com.horstmann.greet .
```

If you use a build tool such as Maven, Ant, or Gradle, just keep building your JAR file as you always do. As long as `module-info.class` is included, you get a modular JAR.

Then, include the modular JAR in the module path, and the module will be loaded.



Caution

In the past, classes of a package were sometimes distributed over multiple JAR files. (Such a package is called a “split package”.) This was probably never a good idea, and it is not possible with modules.

As with regular JAR files, you can specify a main class in a modular JAR:

[Click here to view code image](#)

```
javac -p com.horstmann.greet.jar \
      -d modules/v2ch09.exportedpkg $(find v2ch09.exportedpkg - \
      name *.java)
jar -c -v -f v2ch09.exportedpkg.jar -e
com.horstmann.hello.HelloWorld \
      -C modules/v2ch09.exportedpkg .
```

When you launch the program, you specify the module containing the main class:

[Click here to view code image](#)

```
java -p com.horstmann.greet.jar:v2ch09.exportedpkg.jar -m
v2ch09.exportedpkg
```

When creating a JAR file, you can optionally specify a version number. Use the `--module-version` parameter, and also add @ and the version number to the JAR file name:

[Click here to view code image](#)

```
jar -c -v -f com.horstmann.greet@1.0.jar --module-version 1.0 -
      C com.horstmann.greet .
```

As already discussed, the version number is not used by the Java Platform Module System for resolving modules, but it can be queried by other tools and frameworks.



Note

You can find out the version number through the reflection API. In our example:

[Click here to view code image](#)

```
Optional<String> version =
Greeter.class.getModule().getDescriptor().rawVersion();
```

yields an `Optional` containing the version string "1.0".



Note

The module equivalent to a class loader is a *layer*. The Java Platform Module System loads the JDK modules and application modules into the *boot layer*. A program can load other modules, using the layer API (which is not covered in this book). Such a program may choose to take module versions into account. It is expected that developers of programs such as Java EE application servers will make use of the layer API to provide support for modules.



Tip

If you want to load a module into JShell, include the JAR on the module path and use the `--add-modules` option:

[Click here to view code image](#)

```
jshell --module-path com.horstmann.greet@1.0.jar --add-modules  
com.horstmann.greet
```

9.7 Modules and Reflective Access

In the preceding sections, you saw that the module system enforces encapsulation. A module can only access explicitly exported packages from another module. In the past, it was always possible to overcome pesky access restrictions by using reflection. As you have seen in [Chapter 5](#) of Volume I, reflection can access private members of any class.

However, in the modular world, that is no longer true. If a class is inside a module, reflective access to non-public members will fail. Specifically,

recall how we accessed private fields:

[Click here to view code image](#)

```
Field f = obj.getClass().getDeclaredField("salary");
f.setAccessible(true);
double value = f.getDouble(obj);
f.setDouble(obj, value * 1.1);
```

The call `f.setAccessible(true)` succeeds unless a security manager disallows private field access. However, it is not common to run Java applications with security managers, and there are many libraries that use reflective access. Typical examples are object-relational mappers, such as JPA, that automatically persist objects in databases and libraries that convert between objects and XML or JSON, such as JAXB and JSON-B.

If you use such a library, and you also want to use modules, you have to be careful. To demonstrate this issue, let us place the `ObjectAnalyzer` class from [Chapter 5](#) of Volume I into a module `com.horstmann.util`. That class has a `toString` method that prints the fields of an object, using reflection.

A separate `v2ch09.openpkg` module contains a simple `Country` class:

[Click here to view code image](#)

```
package com.horstmann.places;

public class Country
{
    private String name;
    private double area;

    public Country(String name, double area)
    {
        this.name = name;
        this.area = area;
    }
}
```

```
// . . .
}
```

A short program demonstrates how to analyze a Country object:

[Click here to view code image](#)

```
package com.horstmann.places;

import com.horstmann.util.*;

public class Demo
{
    public static void main(String[] args) throws
ReflectiveOperationException
    {
        var belgium = new Country("Belgium", 30510);
        var analyzer = new ObjectAnalyzer();
        System.out.println(analyzer.toString(belgium));
    }
}
```

Now compile both modules and the Demo program:

[Click here to view code image](#)

```
javac com.horstmann.util/module-info.java \
com.horstmann.util/com/horstmann/util/ObjectAnalyzer.java
javac -p com.horstmann.util v2ch09.openpkg/module-info.java \
v2ch09.openpkg/com/horstmann/places/*.java
java -p v2ch09.openpkg:com.horstmann.util -m
v2ch09.openpkg/com.horstmann.places.Demo
```

The program will fail with an exception:

[Click here to view code image](#)

```
Exception in thread "main"
java.lang.reflect.InaccessibleObjectException:
    Unable to make field private java.lang.String
```

```
com.horstmann.places.Country.name  
accessible: module v2ch09.openpkg does not "opens  
com.horstmann.places" to module  
com.horstmann.util
```

Of course, in pristine theory, it is wrong to violate encapsulation and poke around in the private members of an object. But mechanisms such as object-relational mapping or XML/JSON binding are so common that the module system must accommodate them.

Using the `opens` keyword, a module can *open* a package, which enables reflective access to all instances of classes in the given package. Here is what our module has to do:

```
module v2ch09.openpkg  
{  
    requires com.horstmann.util;  
    opens com.horstmann.places;  
}
```

With this change, the ObjectAnalyzer will work correctly.

A module can be declared as open, such as

[Click here to view code image](#)

```
open module v2ch09.openpkg  
{  
    requires com.horstmann.util;  
}
```

An open module grants runtime access to all of its packages, as if all packages had been declared with `exports` and `opens`. However, only explicitly exported packages are accessible at compile time. Open modules combine the compile-time safety of the module system with the classic permissive runtime behavior.

Recall from [Chapter 5](#) of Volume I that JAR files can contain, in addition to class files and a manifest, *file resources* which can be loaded with the

method `Class.getResourceAsStream`, and now also with `Module.getResourceAsStream`. If a resource is stored in a directory that matches a package in a module, then the package must be opened to the caller. Resources in other directories, as well as the class files and manifest, can be read by anyone.



Note

For a more realistic example, we can convert the `Country` object to XML or JSON, using the JSON-B specification. To use the Yasson implementation of JSON-B, download the JAR files `jakarta.json-api-2.0.1.jar`, `jakarta.json.bind-api-2.0.0.jar`, `jakarta.json-2.0.1-module.jar`, and `yasson-2.0.3.jar` from the Maven Central Repository. Place the JAR files on the module path and run the `com.horstmann.places.Demo` program in the `v2ch09.openpkg2` module. When the `com.horstmann.places` package is opened, conversion to JSON succeeds.



Note

It is possible that future libraries will use *variable handles* instead of reflection for reading and writing fields. A `VarHandle` is similar to a `Field`. You can use it to read or write a specific field of any instance of a specific class. However, to obtain a `VarHandle`, the library code needs a `Lookup` object:

[Click here to view code image](#)

```
public Object getFieldValue(Object obj, String fieldName,  
    Lookup lookup)  
    throws NoSuchFieldException, IllegalAccessException  
{  
    Class<?> cl = obj.getClass();
```

```

        Field field = cl.getDeclaredField(fieldName);
        VarHandle handle = MethodHandles.privateLookupIn(cl, lookup)
            .unreflectVarHandle(field);
        return handle.get(obj);
    }
}

```

This works provided the `Lookup` object is generated in the module that has the permission to access the field. Some method in the module simply calls `MethodHandles.lookup()`, which yields an object encapsulating the access rights of the caller. In this way, one module can give permission for accessing private members to another module. The practical issue is how those permissions can be given with a minimum of hassle.

9.8 Automatic Modules

You now know to put the Java Platform Module System to use. If you start with a brand-new project in which you write all the code yourself, you can design modules, declare module dependencies, and package your application into modular JAR files.

However, that is an extremely uncommon scenario. Almost all projects rely on third-party libraries. Of course, you can wait until the providers of all libraries have turned them into modules, and then modularize your own code.

But what if you don't want to wait? The Java Platform Module System provides two mechanisms for crossing the chasm that separates today's premodular world and fully modular applications: automatic modules and the unnamed module.

For migration purposes, you can turn any JAR file into a module simply by placing it onto a directory in the module path instead of the class path. A JAR without a `module-info.class` on the module path is called an *automatic module*. An automatic module has the following properties:

1. The module implicitly has a `requires` clause for all other modules.
2. All of its packages are exported and opened.
3. If there is an entry with key `Automatic-Module-Name` in the JAR file manifest `META-INF/MANIFEST.MF`, its value becomes the module name.
4. Otherwise the module name is obtained from the JAR file name, dropping any trailing version number and replacing sequences of non-alphanumeric characters with a dot.

The first two rules imply that the packages in the automatic module act as if they were on the class path. The reason for using the module path is for the benefit of other modules, allowing them to express dependencies on this module.

Suppose, for example, that you are implementing a module that processes CSV files and uses the Apache Commons CSV library. You would like to express in your `module-info.java` file that your module depends on Apache Commons CSV.

If you add `commons-csv-1.9.0.jar` onto the module path, then your modules can reference the module. Its name is `commons.csv` since the trailing version number `-1.9.0` is removed and the non-alphanumeric character `-` is replaced by a dot.

This name might be an acceptable module name because Commons CSV is well known and it is unlikely that someone else will try to use the same name for a different module. But it would be better if the maintainers of this JAR file could quickly agree to reserve a reverse DNS name, preferably the top-level package name `org.apache.commons.csv`, as the module name. They just need to add a line

[Click here to view code image](#)

```
Automatic-Module-Name: org.apache.commons.csv
```

to the `META-INF/MANIFEST.MF` file inside the JAR. Eventually, hopefully, they will turn the JAR file into a true module by adding

`module-info.java` with the reserved module name—and every other module that refers to the CSV module with that name will just continue to work.



Note

The migration plan to modules is a great social experiment, and nobody knows whether it will end well. Before you put third-party JARs on the module path, check whether they are modular, and if not, whether their manifest has a module name. If not, you can still turn the JAR into an automatic module, but be prepared to update the module name later.

As this book is being written, version 1.9.0 of the Commons CSV JAR file does not have a module descriptor or an automatic module name. Nevertheless, it will work fine on the module path. You can download the library from <https://commons.apache.org/proper/commons-csv>. Place the `commons-csv-1.9.0.jar` file into the directory of the `v2ch9.automod` module. That module contains a simple program that reads a CSV file with country data:

[Click here to view code image](#)

```
package com.horstmann.places;

import java.io.*;
import org.apache.commons.csv.*;

public class CSVDemo
{
    public static void main(String[] args) throws IOException
    {
        var in = new FileReader("countries.csv");
        Iterable<CSVRecord> records =
            CSVFormat.EXCEL.withDelimiter(';')
                .withHeader().parse(in);
```

```

        for (CSVRecord record : records)
        {
            String name = record.get("Name");
            double area = Double.parseDouble(record.get("Area"));
            System.out.println(name + " has area " + area);
        }
    }
}

```

Since we will use commons-csv-1.9.0.jar as an automatic module, we need to require it:

```

@SuppressWarnings("module")
module v2ch09.automod
{
    requires commons.csv;
}

```

Here are the commands for compiling and running the program:

[Click here to view code image](#)

```

javac -p v2ch09.automod:commons-csv-1.9.0.jar \
    v2ch09.automod/com/horstmann/places/CSVDemo.java \
    v2ch09.automod/module-info.java
java -p v2ch09.automod:commons-csv-1.9.0.jar \
    -m v2ch09.automod/com.horstmann.places.CSVDemo

```

9.9 The Unnamed Module

Any class that is not on the module path is part of an *unnamed module*. Technically, there may be more than one unnamed module, but all of them together act as if they are a single module which is called *the unnamed module*. As with automatic modules, the unnamed module can access all other modules, and all of its packages are exported and opened.

However, *no explicit module* can access the unnamed module. (An explicit module is a module that is neither automatic nor unnamed—that is, a module with a `module-info.class` on the module path.) In other words, explicit modules are always free from the “class path hell.”

Consider, for example, the program of the preceding section. Suppose you put `commons-csv-1.9.0.jar` onto the class path instead of the module path:

[Click here to view code image](#)

```
java --module-path v2ch09.automod \
      --class-path commons-csv-1.9.0.jar \
      -m v2ch09.automod/com.horstmann.places.CSVDemo
```

Now the program won't start:

[Click here to view code image](#)

```
Error occurred during initialization of boot layer
java.lang.module.FindException: Module commons.csv not found,
required by v2ch09.automod
```

Therefore, migration to the Java Platform Module System is necessarily a bottom-up process:

1. The Java platform itself is modularized.
 2. Next, libraries are modularized, either by using automatic modules or by turning them into explicit modules.
 3. Once all libraries used by your application are modularized, you can turn the code of your application into a module.
-



Note

Automatic modules *can* read the unnamed module, so their dependencies can go onto the class path.

9.10 Command-Line Flags for Migration

Even if your programs do not use modules, you cannot escape the modular world when using Java 9 and beyond. Your application code may reside on the class path in an unnamed module, so that all packages are exported and opened. Still, the code interacts with the Java platform, which is modularized.

As of Java 11, compile-time encapsulation is strictly enforced. However, before Java 16, runtime access was permitted. The default behavior was to display a warning on the console for the first instance of each offense. As of Java 16, reflective access at runtime is also enforced. In order to give you time to prepare for that change, the `java` launcher in Java 9 through 16 had an `--illegal-access` flag with four possible settings:

1. `--illegal-access=permit` is the Java 9 default behavior, printing a message for the first instance of illegal access.
2. `--illegal-access=warn` prints a message for each illegal access.
3. `--illegal-access=debug` prints a message and stack trace for each illegal access.
4. `--illegal-access=deny` is the Java 16 default behavior, denying all illegal access.

The `--illegal-access` flag is no longer usable in Java 17.

The `--add-exports` and `--add-opens` flags allow you to tweak legacy applications. Consider an application that uses an internal API which is no longer accessible, such as `com.sun.rowset.CachedRowSetImpl`. The best remedy is to change the implementation. (As of Java 7, you can get a cached row set from a `RowSetProvider`.) But suppose you don't have access to the source code.

In that case, start the application with the `--add-exports` flag. Specify the module and the package that you want to export, and the module to which you want to export the package, which in our case is the unnamed module.

[Click here to view code image](#)

```
java --add-exports java.sql.rowset/com.sun.rowset=ALL_UNNAMED \
-jar MyApp.jar
```

Now, suppose your application uses reflection to access private fields or methods. Reflection inside the unnamed module is OK, but it is no longer possible to reflectively access non-public members of the Java platform classes. For example, some libraries that dynamically generate Java classes call the protected `ClassLoader.defineClass` method through reflection. If an application uses such a library, add the flag

[Click here to view code image](#)

```
--add-opens java.base/java.lang=ALL-UNNAMED
```

When adding all those command-line options to get a legacy app to work, you may well end up with the command line from hell. To better manage multiple options, you can put them in one or more files specified with an @ prefix. For example,

[Click here to view code image](#)

```
java @options1 @options2 -jar MyProg.java
```

where the files `options1` and `options2` contain options for the `java` command.

There are a few syntax rules for the options files:

- Separate options with spaces, tabs, or newlines.
- Use double quotes around arguments that include spaces, such as "Program Files".
- A line ending in a \ is merged with the next line.
- Backslashes must be escaped, such as C:\\Users\\\\Fred.
- Comment lines start with #.

9.11 Transitive and Static Requirements

In Section 9.4, “[Requiring Modules](#),” on p. 508, you have seen the basic form of the `requires` statement. In this section, you will see two variants that are occasionally useful.

In some situation, it can be tedious for a user of a given module to declare all required modules. Consider, for example, the `java.desktop` module. It requires three modules: `java.prefs`, `java.datatransfer` and `java.xml`. The `java.prefs` module is only used internally. However, classes from `java.datatransfer` and `java.xml` appear in the public API, in methods such as

[Click here to view code image](#)

```
java.awt.datatransfer.Clipboard  
java.awt.Toolkit.getSystemClipboard()  
java.beans.XMLDecoder(org.xml.sax.InputSource is)
```

That is not something that a user of the `java.desktop` module should have to think about. For that reason, the `java.desktop` module declares the requirement with the `transitive` modifier:

[Click here to view code image](#)

```
module java.desktop  
{  
    requires java.prefs;  
    requires transitive java.datatransfer;  
    requires transitive java.xml;  
    . . .  
}
```

Any module that declares a requirement on `java.desktop` now automatically requires these two modules.



Note

Some programmers recommend that you should always use `requires transitive` when a package from another module is used in the public API. But that is not a requirement of the Java language. Consider, for example, the `java.sql` module:

[Click here to view code image](#)

```
module java.sql
{
    requires transitive java.logging;
    ...
}
```

There is a single use of a package from the `java.logging` module in the entire `java.sql` API, namely the `java.sql.Driver.parentLogger` method that returns a `java.util.logging.Logger`. It would have been perfectly acceptable to not declare this module requirement as transitive. Then, those modules—and only those—who actually use that method would need to declare that they require `java.logging`.

One compelling use of the `requires transitive` statement is an *aggregator* module—a module with no packages and only transitive requirements. One such module is the `java.se` module, declared like this:

[Click here to view code image](#)

```
module java.se
{
    requires transitive java.compiler;
    requires transitive java.datatransfer;
    requires transitive java.desktop;
    ...
    requires transitive java.sql;
    requires transitive java.sql.rowset;
    requires transitive java.xml;
    requires transitive java.xml.crypto;
}
```

A programmer who isn't interested in fine-grained module dependencies can simply require `java.se` and get all modules of the Java SE platform.

Finally, there is an uncommon `requires static` variant that declares that a module must be present at compile time but is optional at runtime. There are two use cases:

1. To access an annotation that is processed at compile time and declared in a different module.
2. To use a class in a different module if it is available, and otherwise do something else, such as:

[Click here to view code image](#)

```
try
{
    new oracle.jdbc.driver.OracleDriver();
    . . .
}
catch (NoClassDefFoundError er)
{
    Do something else
}
```

9.12 Qualified Exporting and Opening

In this section, you will see a variant of the `exports` and `opens` statement that narrows their scope to a specified set of modules. For example, the `java.base` module contains a statement

```
exports sun.net to
    java.net.http,
    jdk.naming.dns;
```

Such a statement is called a *qualified export*. The listed modules can access the exported package, but other modules cannot.

Excessive use of qualified exports can indicate a poor modular structure. Nevertheless, they can arise when modularizing an existing code base. Here, the `sun.net` package is placed inside the `java.base` module because that is where it is mostly needed. However, a couple of other modules also use that package. The Java platform designers didn't want to make `java.base` even bigger, and they didn't want to make the internal `sun.net` package generally available. In a greenfield project, one can instead design a more modular API.

Similarly, you can restrict the `opens` statement to specific modules. For example, in [Section 9.7, “Modules and Reflective Access,”](#) on p. 515 we could have used a qualified `opens` statement, like this:

[Click here to view code image](#)

```
module v2ch09.openpkg
{
    requires com.horstmann.util;
    opens com.horstmann.places to com.horstmann.util;
}
```

Now the `com.horstmann.places` package is only opened to the `com.horstmann.util` module.

9.13 Service Loading

The `ServiceLoader` class (see [Chapter 6](#) of Volume I) provides a lightweight mechanism for matching up service interfaces with implementations. The Java Platform Module System makes this mechanism easier to use.

Here is a quick reminder of service loading. A service has an interface and one or more possible implementations. Here is a simple example of an interface:

[Click here to view code image](#)

```
public interface GreeterService
{
    String greet(String subject);
    Locale getLocale();
}
```

One or more modules provide implementations, such as

[Click here to view code image](#)

```
public class FrenchGreeter implements GreeterService
{
    public String greet(String subject) { return "Bonjour " +
subject; }
    public Locale getLocale() { return Locale.FRENCH; }
}
```

The service consumer must pick an implementation among all offered implementations, based on whatever criteria it deems appropriate.

[Click here to view code image](#)

```
ServiceLoader<GreeterService> greeterLoader =
ServiceLoader.load(GreeterService.class);
GreeterService chosenGreeter;
for (GreeterService greeter : greeterLoader)
{
    if (. . .)
    {
        chosenGreeter = greeter;
    }
}
```

In the past, implementations were offered by placing text files into the META-INF/services directory of the JAR file containing the implementation classes. The module system provides a better approach. Instead of text files, you can add statements to the module descriptors.

A module providing an implementation of a service adds a `provides` statement that lists the service interface (which may be defined in any module) and the implementing class (which must be a part of this module). Here is an example from the `jdk.security.auth` module:

[Click here to view code image](#)

```
module jdk.security.auth
{
    ...
    provides javax.security.auth.spi.LoginModule with
        com.sun.security.auth.module.Krb5LoginModule,
        com.sun.security.auth.module.UnixLoginModule,
        com.sun.security.auth.module.JndiLoginModule,
        com.sun.security.auth.module.KeyStoreLoginModule,
        com.sun.security.auth.module.LdapLoginModule,
        com.sun.security.auth.module.NTLoginModule;
}
```

This is the equivalent of the `META-INF/services` file.

A consuming module contains a `uses` statement.

[Click here to view code image](#)

```
module java.base
{
    ...
    uses javax.security.auth.spi.LoginModule;
}
```

When code in a consuming module calls `ServiceLoader.load(ServiceInterface.class)`, the matching provider classes will be loaded, even though they may not be in accessible packages.

In our code example, we provide implementations for a German and French greeter in the package `com.horstmann.greetsvc.internal`. The service module exports the `com.horstmann.greetsvc` package, but

not the package with the implementations. The provides statement declares the service and its implementing classes in the unexported package:

[Click here to view code image](#)

```
module com.horstmann.greetsvc
{
    exports com.horstmann.greetsvc;

    provides com.horstmann.greetsvc.GreeterService with
        com.horstmann.greetsvc.internal.FrenchGreeter,
        com.horstmann.greetsvc.internal.GermanGreeterFactory;
}
```

The v2ch09.usesservice module consumes the service. Using the ServiceLoader facility, we iterate over the provided services and pick the one matching the desired language:

[Click here to view code image](#)

```
package com.horstmann.hello;

import java.util.*;
import com.horstmann.greetsvc.*;

public class HelloWorld
{
    public static void main(String[] args)
    {
        ServiceLoader<GreeterService> greeterLoader
            = ServiceLoader.load(GreeterService.class);
        String desiredLanguage = args.length > 0 ? args[0] :
        "de";
        GreeterService chosenGreeter = null;
        for (GreeterService greeter : greeterLoader)
        {
            if
(greeter.getLocale().getLanguage().equals(desiredLanguage))
```

```

        chosenGreeter = greeter;
    }
    if (chosenGreeter == null)
        System.out.println("No suitable greeter.");
    else
        System.out.println(chosenGreeter.greet("Modular
World"));
    }
}

```

The module declaration requires the service module and declares that the GreeterService is being used.

[Click here to view code image](#)

```

module v2ch09.usesservice
{
    requires com.horstmann.greetsvc;
    uses com.horstmann.greetsvc.GreeterService;
}

```

As a result of the provides and uses declarations, the module that consumes the service is allowed access to the private implementation classes.

To build and run the program, first compile the service:

[Click here to view code image](#)

```

javac com.horstmann.greetsvc/module-info.java \
com.horstmann.greetsvc/com/horstmann/greetsvc/GreeterService.ja
va \
com.horstmann.greetsvc/com/horstmann/greetsvc/internal/*.java

```

Then compile and run the consuming module:

[Click here to view code image](#)

```
javac -p com.horstmann.greetsvc \
    v2ch09.useservice/com/horstmann/hello/HelloWorld.java \
    v2ch09.useservice/module-info.java
java -p com.horstmann.greetsvc:v2ch09.useservice \
    -m v2ch09.useservice/com.horstmann.hello.HelloWorld
```

9.14 Tools for Working with Modules

The `jdeps` tool analyzes the dependencies of a given set of JAR files. Suppose, for example, that you want to modularize JUnit 4. Run

[Click here to view code image](#)


```
jdeps -s junit-4.12.jar hamcrest-core-1.3.jar
```

The `-s` flag generates a summary output:

[Click here to view code image](#)

```
hamcrest-core-1.3.jar -> java.base
junit-4.12.jar -> hamcrest-core-1.3.jar
junit-4.12.jar -> java.base
junit-4.12.jar -> java.management
```

That tells you the module graph:



If you omit the `-s` flag, you get the module summary followed by a mapping from packages to required packages and modules. If you add the `-v` flag, the listing maps classes to required packages and modules.

The `--generate-module-info` option produces `module-info` files for each analyzed module:

[Click here to view code image](#)

```
jdeps --generate-module-info /tmp/junit junit-4.12.jar  
hamcrest-core-1.3.jar
```




Note

There is also an option to generate graphical output in the “dot” language for describing graphs. Assuming you have the dot tool installed, run these commands:

[Click here to view code image](#)

```
jdeps -s -dotoutput /tmp/junit junit-4.12.jar hamcrest-core-  
1.3.jar  
dot -Tpng /tmp/junit/summary.dot > /tmp/junit/summary.png
```

You get this `summary.png` image:



Use the `jlink` tool to produce an application that executes without a separate Java runtime. The resulting image is much smaller than the entire JDK. You specify the modules that you want to have included and an output directory.

[Click here to view code image](#)

```
jlink --module-path  
com.horstmann.greet.jar:v2ch09.exportedpkg.jar:$JAVA_HOME/jmods  
\  
--add-modules v2ch09.exportedpkg --output /tmp/hello
```

The output directory has a subdirectory `bin` with a `java` executable. If you run

[Click here to view code image](#)

```
bin/java -m v2ch09.exportedpkg
```

the `main` method of the module's main class is invoked.

The point of `jlink` is that it bundles up the minimal set of modules required to run the application. You can list them all:

```
bin/java --list-modules
```

In this example, the output is

```
v2ch09.exportedpkg  
com.horstmann.greet  
java.base@9
```

All modules are included in a *runtime image* file `lib/modules`. On my computer, that file is 23MB, whereas the runtime image of all JDK modules takes up 121MB. The entire application takes up 45MB, a fraction of the size of the JDK.

This can be the basis of a useful tool for packaging applications. You would still need to produce file sets for multiple platforms and launch scripts for

the application.



Note

You can inspect the runtime image with the `jimage` command. However, the format is internal to the JVM, and runtime images are not meant to be generated or used by other tools.

Finally, the `jmod` tool builds and inspects the module files that are included with the JDK. When you look into the `jmods` directory inside the JDK, you will find a file with extension `jmod` for each module. There is no longer a `rt.jar` file.

Like JAR files, these files contain class files. In addition, they can hold native code libraries, commands, header files, configuration files, and legal notices. The JMOD files use the ZIP format. You can inspect their contents with any ZIP tool.

Unlike JAR files, JMOD files are only useful for linking—that is, for producing runtime images. There is no need for you to produce JMOD files unless you also want to bundle binary files such as native code libraries with your modules.

This brings us to the end of the chapter on the Java Platform Module System. The following chapter covers another important topic: security. Security has always been a core feature of the Java platform. As the world in which we live and compute gets more dangerous, a thorough understanding of Java security will be of increasing importance for many developers.

Chapter 10. Security

In this chapter

- [10.1 Class Loaders](#)
- [10.2 User Authentication](#)
- [10.3 Digital Signatures](#)
- [10.4 Encryption](#)

When Java technology first appeared on the scene, the excitement was not about a well-crafted programming language but about the possibility of safely executing applets delivered over the Internet. Obviously, serving executable applets is only practical when the recipients can be sure the code won't wreak havoc on their machines. Security therefore was and is a major concern of both the designers and the users of Java technology. This means that unlike other languages and systems, where security was implemented as an afterthought or as a reaction to break-ins, security mechanisms are an integral part of Java technology.

The security architecture was composed of three parts:

1. Language and virtual machine design features (bounds checking on arrays, no unchecked type conversions, no pointer arithmetic, and so on).
2. A *security manager* that controls what the code can do (file access, network access, and so on).

3. Code signing, whereby code authors can use standard cryptographic algorithms to authenticate Java code. Then, the users of the code can determine exactly who created the code and ensure that the code has not been altered after it was signed.

The first part has been a resounding success. C++ programs are routinely vulnerable to attacks such as buffer overruns, but Java provides strong protection. Unfortunately, the other two parts have not fared as well. The security manager was complex and had a large attack surface. It is being deprecated as of Java 17. The code signing architecture was effectively abandoned with the demise of applets and Java Web Start—two mechanisms for the secure delivery of client-side applications.

In previous editions of this book, the security manager and code signing were the highlights of this chapter, but obviously the need for such coverage has gone away. We will first discuss *class loaders* that check class files for integrity when they are loaded into the virtual machine. I will demonstrate how that mechanism can detect tampering with class files. Then, you'll learn about an authentication framework and cryptographic algorithms which are useful for many security-related operations.

10.1 Class Loaders

A Java compiler converts source instructions into code for the Java virtual machine. The virtual machine code is stored in a class file with a `.class` extension. Each class file contains the definition and implementation code for one class or interface. In the following section, you will see how the virtual machine loads these class files.

10.1.1 The Class-Loading Process

The virtual machine loads only those class files that are needed for the execution of a program. For example, suppose program execution starts with `MyProgram.class`. Here are the steps that the virtual machine carries out:

1. The virtual machine has a mechanism for loading class files—for example, by reading the files from disk or by requesting them from the Web; it uses this mechanism to load the contents of the `MyProgram` class file.
2. If the `MyProgram` class has fields or superclasses of another class type, their class files are loaded as well. (The process of loading all the classes that a given class depends on is called *resolving* the class.)
3. The virtual machine then executes the `main` method in `MyProgram` (which is static, so no instance of a class needs to be created).
4. If the `main` method or a method that `main` calls requires additional classes, these are loaded next.

The class loading mechanism doesn't just use a single class loader, however. Every Java program has at least three class loaders:

- The bootstrap class loader
- The platform class loader
- The system class loader (sometimes called the application class loader)

The bootstrap class loader loads the platform classes contained in the modules

```
java.base  
java.datatransfer  
java.desktop  
java.instrument  
java.logging  
java.management  
java.management.rmi  
java.naming  
java.prefs  
java.rmi  
java.security.sasl  
java.xml
```

as well as a number of JDK-internal modules.

There is no `ClassLoader` object corresponding to the bootstrap class loader. For example,

[Click here to view code image](#)

```
StringBuilder.class.getClassLoader()
```

returns null.

Prior to Java 9, the Java platform classes were located in a file `rt.jar`. Nowadays, the Java platform is modular, and each platform module is contained in a JMOD file (see [Chapter 9](#)). The platform class loader loads all classes of the Java platform that are not loaded by the bootstrap class loader.

The system class loader loads application classes from the module path and class path.



Note

Prior to Java 9, an “extension class loader” loaded “standard extensions” from the `jre/lib/ext` directory, and an “endorsed standards override” mechanism provided a way of overriding certain platform classes (including the CORBA and XML implementations) with newer versions. Both of these mechanisms have been removed.

10.1.2 The Class Loader Hierarchy

Class loaders have a *parent/child* relationship. Every class loader except for the bootstrap one has a parent class loader. A class loader will give its parent a chance to load any given class and will only load it if the parent has failed. For example, when the system class loader is asked to load a system class (say, `java.lang.StringBuilder`), it first asks the platform class loader. That class loader first asks the bootstrap class loader.

The bootstrap class loader finds and loads the class, so neither of the other class loaders searches any further.

Some programs have a plugin architecture in which certain parts of the code are packaged as optional plugins. If the plugins are packaged as JAR files, you can simply load the plugin classes with an instance of URLClassLoader.

[Click here to view code image](#)

```
var url = new URL("file:///path/to/plugin.jar");
var pluginLoader = new URLClassLoader(new URL[] { url });
Class<?> cl = pluginLoader.loadClass("mypackage.MyClass");
```

Since no parent was specified in the URLClassLoader constructor, the parent of the pluginLoader is the system class loader. [Figure 10.1](#) shows the hierarchy.




Figure 10.1 The class loader hierarchy



Caution

Prior to Java 9, the system class loader was an instance of `URLClassLoader`. Some programmers used a cast to access the `getURLs` method, or added JAR files to the class path by calling the protected `addURLs` method through reflection. This is no longer possible.

Most of the time, you don't have to worry about the class loader hierarchy. Generally, classes are loaded because they are required by other classes, and that process is transparent to you.

Occasionally, however, you need to intervene and specify a class loader. Consider this example:

- Your application code contains a helper method that calls `Class.forName(classNameString)`.
- That method is called from a plugin class.
- The `classNameString` specifies a class that is contained in the plugin JAR.

The author of the plugin wants the class to be loaded. However, the helper method's class was loaded by the system class loader, and that is the class loader used by `Class.forName`. The classes in the plugin JAR are not visible. This phenomenon is called *classloader inversion*.

To overcome this problem, the helper method needs to use the correct class loader. It can require the class loader as a parameter. Alternatively, it can require that the correct class loader is set as the *context class loader* of the current thread. This strategy is used by many frameworks (such as JAXP and JNDI).

Each thread has a reference to a class loader, called the context class loader. The main thread's context class loader is the system class loader. When a new thread is created, its context class loader is set to the creating thread's context class loader. Thus, if you don't do anything, all threads will have their context class loaders set to the system class loader.

However, you can set any class loader by calling

[Click here to view code image](#)

```
Thread t = Thread.currentThread();
t.setContextClassLoader(loader);
```

The helper method can then retrieve the context class loader:

[Click here to view code image](#)

```
Thread t = Thread.currentThread();
ClassLoader loader = t.getContextClassLoader();
Class<?> cl = loader.loadClass(className);
```



Tip

If you write a method that loads a class by name, it is a good idea to offer the caller the choice between passing an explicit class loader and using the context class loader. Don't simply use the class loader of the method's class.

10.1.3 Using Class Loaders as Namespaces

Every Java programmer knows that package names are used to eliminate name conflicts. There are two classes called `Date` in the standard library, but of course their real names are `java.util.Date` and `java.sql.Date`. The simple name is only a programmer convenience and requires the inclusion of appropriate `import` statements. In a running program, all class names contain their package names.




Figure 10.2 Two class loaders load different classes with the same name.

It might surprise you, however, that you can have two classes in the same virtual machine that have the same class *and package* name. A class is

determined by its full name *and* the class loader. This technique is useful for loading code from multiple sources. For example, an application server uses separate class loaders for each application. This allows the virtual machine to separate classes from different applications, no matter what they are named. [Figure 10.2](#) shows an example. Suppose an application server loads two different applications, and each has a class called `Util`. Since each class is loaded by a separate class loader, these classes are entirely distinct and do not conflict with each other.

10.1.4 Writing Your Own Class Loader

You can write your own class loader for specialized purposes. That lets you carry out custom checks before you pass the bytecodes to the virtual machine. For example, your class loader may refuse to load a class that has not been marked as “paid for.”

To write your own class loader, simply extend the `ClassLoader` class and override the method

[Click here to view code image](#)

```
findClass(String className)
```

The `loadClass` method of the `ClassLoader` superclass takes care of the delegation to the parent and calls `findClass` only if the class hasn’t already been loaded and if the parent class loader was unable to load the class.

Your implementation of this method must do the following:

1. Load the bytecodes for the class from the local file system or some other source.
2. Call the `defineClass` method of the `ClassLoader` superclass to present the bytecodes to the virtual machine.

In the program of [Listing 10.1](#), we implement a class loader that loads encrypted class files. The program asks the user for the name of the first class to load (that is, the class containing `main`) and the decryption key. It

then uses a special class loader to load the specified class and calls the main method. The class loader decrypts the specified class and all nonsystem classes that are referenced by it. Finally, the program calls the main method of the loaded class (see [Figure 10.3](#)).




Figure 10.3 The ClassLoaderTest program

For simplicity, we ignore the 2,000 years of progress in the field of cryptography and use the venerable Caesar cipher for encrypting the class files.



Note

David Kahn's wonderful book *The Codebreakers* (Macmillan, 1967, p. 84) refers to Suetonius as a historical source for the Caesar cipher. Caesar shifted the 24 letters of the Roman alphabet by 3 letters, which at the time baffled his adversaries.

When this chapter was first written, the U.S. government restricted the export of strong encryption methods. Therefore, I used Caesar's method for my example because it was clearly legal for export.

Our version of the Caesar cipher has as a key a number between 1 and 255. To decrypt, simply add that key to every byte and reduce modulo 256. The `Caesar.java` program of Listing 10.2 carries out the encryption.

To not confuse the regular class loader, we use a different extension, `.caesar`, for the encrypted class files.

To decrypt, the class loader simply subtracts the key from every byte. In the companion code for this book, you will find four class files, encrypted with a key value of 3—the traditional choice. To run the encrypted program, you'll need the custom class loader defined in our `ClassLoaderTest` program.

Encrypting class files has a number of practical uses (provided, of course, that you use something stronger than the Caesar cipher). Without the decryption key, the class files are useless. They can neither be executed by a standard virtual machine nor readily disassembled.

This means that you can use a custom class loader to authenticate the user of the class or to ensure that a program has been paid for before it will be allowed to run. Of course, encryption is only one application of a custom class loader. You can use other types of class loaders to solve other problems—for example, storing class files in a database.

Listing 10.1 `classLoader/ClassLoaderTest.java`

[Click here to view code image](#)

```
1 package classLoader;
2
3 import java.io.*;
4 import java.lang.reflect.*;
5 import java.nio.file.*;
6 import java.awt.*;
7 import java.awt.event.*;
8 import javax.swing.*;
9
10 /**
11 * This program demonstrates a custom class loader that
```

```
decrypts class files.

12  * @version 1.25 2018-05-01
13  * @author Cay Horstmann
14  */
15 public class ClassLoaderTest
16 {
17     public static void main(String[] args)
18     {
19         EventQueue.invokeLater(() ->
20             {
21                 var frame = new ClassLoaderFrame();
22                 frame.setTitle("ClassLoaderTest");
23
frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
24                 frame.setVisible(true);
25             });
26     }
27 }
28
29 /**
30  * This frame contains two text fields for the name of the
31  * class to load and the
32  * decryption key.
33  */
34 class ClassLoaderFrame extends JFrame
35 {
36     private JTextField keyField = new JTextField("3", 4);
37     private JTextField nameField = new
JTextField("Calculator", 30);
38     private static final int DEFAULT_WIDTH = 300;
39     private static final int DEFAULT_HEIGHT = 200;
40
41     public ClassLoaderFrame()
42     {
43         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
44         setLayout(new GridBagLayout());
45         add(new JLabel("Class"), new GBC(0,
0).setAnchor(GBC.EAST));
46     }
47 }
```

```
45         add(nameField, new GBC(1, 0).setWeight(100,
0).setAnchor(GBC.WEST));
46         add(new JLabel("Key"), new GBC(0,
1).setAnchor(GBC.EAST));
47         add(keyField, new GBC(1, 1).setWeight(100,
0).setAnchor(GBC.WEST));
48         var loadButton = new JButton("Load");
49         add(loadButton, new GBC(0, 2, 2, 1));
50         loadButton.addActionListener(
51             event -> runClass(nameField.getText(),
keyField.getText()));
52         pack();
53     }
54
55 /**
56 * Runs the main method of a given class.
57 * @param name the class name
58 * @param key the decryption key for the class files
59 */
60 public void runClass(String name, String key)
61 {
62     try
63     {
64         var loader = new
CryptoClassLoader(Integer.parseInt(key));
65         Class<?> c = loader.loadClass(name);
66         Method m = c.getMethod("main", String[].class);
67         m.invoke(null, (Object) new String[] {} );
68     }
69     catch (Throwable t)
70     {
71         JOptionPane.showMessageDialog(this, t);
72     }
73 }
74 }
75
76 /**
77 * This class loader loads encrypted class files.
```

```
78     */
79     class CryptoClassLoader extends ClassLoader
80     {
81         private int key;
82
83         /**
84          * Constructs a crypto class loader.
85          * @param k the decryption key
86          */
87         public CryptoClassLoader(int k)
88         {
89             key = k;
90         }
91
92         protected Class<?> findClass(String name) throws
93             ClassNotFoundException
94         {
95             try
96             {
97                 byte[] classBytes = null;
98                 classBytes = loadClassBytes(name);
99                 Class<?> cl = defineClass(name, classBytes, 0,
100                     classBytes.length);
101                 if (cl == null) throw new
102                     ClassNotFoundException(name);
103                 return cl;
104             }
105             catch (IOException e)
106             {
107                 throw new ClassNotFoundException(name);
108             }
109             /**
110              * Loads and decrypt the class file bytes.
111              * @param name the class name
112              * @return an array with the class file bytes
113              */
114         }
```

```
113     private byte[] loadClassBytes(String name) throws
114         IOException
115     {
116         String cname = name.replace('.', '/') + ".caesar";
117         byte[] bytes = Files.readAllBytes(Path.of(cname));
118         for (int i = 0; i < bytes.length; i++)
119             bytes[i] = (byte) (bytes[i] - key);
120     }
121 }
```

Listing 10.2 classLoader/Caesar.java

[Click here to view code image](#)

```
1 package classLoader;
2
3 import java.io.*;
4
5 /**
6  * Encrypts a file using the Caesar cipher.
7  * @version 1.02 2018-05-01
8  * @author Cay Horstmann
9 */
10 public class Caesar
11 {
12     public static void main(String[] args) throws Exception
13     {
14         if (args.length != 3)
15         {
16             System.out.println("USAGE: java classLoader.Caesar in
out key");
17             return;
18         }
19
20         try (var in = new FileInputStream(args[0]);
21              var out = new FileOutputStream(args[1]))
22         {
```

```
23     int key = Integer.parseInt(args[2]);
24     int ch;
25     while ((ch = in.read()) != -1)
26     {
27         byte c = (byte) (ch + key);
28         out.write(c);
29     }
30 }
31 }
32 }
```

java.lang.Class 1.0

- `ClassLoader getClassLoader()`
gets the class loader that loaded this class.

java.lang.ClassLoader 1.0

- `ClassLoader getParent()` 1.2
returns the parent class loader, or `null` if the parent class loader is the bootstrap class loader.
- `static ClassLoader getSystemClassLoader()` 1.2
gets the system class loader—that is, the class loader that was used to load the first application class.
- `protected Class findClass(String name)` 1.2
should be overridden by a class loader to find the bytecodes for a class and present them to the virtual machine by calling the `defineClass` method. In the name of the class, use `.` as package name separator, and don't use a `.class` suffix.

- `Class defineClass(String name, byte[] byteCodeData, int offset, int length)`
adds a new class to the virtual machine whose bytecodes are provided in the given data range.

java.net.URLClassLoader 1.2

- `URLClassLoader(URL[] urls)`
- `URLClassLoader(URL[] urls, ClassLoader parent)`

construct a class loader that loads classes from the given URLs. If the URL ends in a /, it is assumed to be a directory, otherwise it is assumed to be a JAR file.

java.lang.Thread 1.0

- `ClassLoader getContextClassLoader() 1.2`
gets the class loader that the creator of this thread has designated as the most reasonable class loader to use when executing this thread.
- `void setContextClassLoader(ClassLoader loader) 1.2`
sets a class loader for code in this thread to retrieve for loading classes. If no context class loader is set explicitly when a thread is started, the parent's context class loader is used.

10.1.5 Bytecode Verification

When a class loader presents the bytecodes of a newly loaded Java platform class to the virtual machine, these bytecodes are first inspected by a *verifier*. The verifier checks that the instructions cannot perform actions that are obviously damaging. All classes except for system classes are verified.

Here are some of the checks that the verifier carries out:

- Variables are initialized before they are used.
- Method calls match the types of object references.
- Rules for accessing private data and methods are not violated.
- Local variable accesses fall within the runtime stack.
- The runtime stack does not overflow.

If any of these checks fails, the class is considered corrupted and will not be loaded.



Note

If you are familiar with Gödel's theorem, you might wonder how the verifier can prove that a class file is free from type mismatches, uninitialized variables, and stack overflows. Gödel's theorem states that it is impossible to design algorithms that process a program and decide whether it has a particular property (such as being free from stack overflows). Is this a conflict between the public relations department at Oracle and the laws of logic? No—in fact, the verifier is *not* a decision algorithm in the sense of Gödel. If the verifier accepts a program, it is indeed safe. However, the verifier might reject virtual machine instructions even though they would actually be safe. (You might have run into this issue when you were forced to initialize a variable with a dummy value because the verifier couldn't see that it was going to be properly initialized.)

This strict verification is an important security consideration. Accidental errors, such as uninitialized variables, can easily wreak havoc if they are not

caught. More importantly, in the wide open world of the Internet, you must be protected against malicious programmers who create evil effects on purpose. For example, by modifying values on the runtime stack or by writing to the private instance fields of system objects, a program can break through the security system of a browser.

You might wonder, however, why a special verifier is needed to check all these features. After all, the compiler would never allow you to generate a class file in which an uninitialized variable is used or in which a private instance field is accessed from another class. Indeed, a class file generated by a compiler for the Java programming language always passes verification. However, the bytecode format used in the class files is well documented, and it is an easy matter for someone with experience in assembly programming and a hex editor to manually produce a class file containing valid but unsafe instructions for the Java virtual machine. The verifier is always guarding against maliciously altered class files—not just checking the class files produced by a compiler.

Here's an example of how to construct such an altered class file. We start with the program `VerifierTest.java` of [Listing 10.3](#). This is a simple program that calls a method and displays the method's result. The `fun` method itself just computes $1 + 2$.

```
static int fun()
{
    int m;
    int n;
    m = 1;
    n = 2;
    int r = m + n;
    return r;
}
```

As an experiment, try to compile the following modification of this program:

```
static int fun()
{
```

```

int m = 1;
int n;
m = 1;
m = 2;
int r = m + n;
return r;
}

```

Here, n is not initialized, so it could have any random value. Of course, the compiler detects that problem and refuses to compile the program. To create a bad class file, we have to work a little harder. First, run the javap program to find out how the compiler translates the fun method. The command

[Click here to view code image](#)

```
javap -c verifier.VerifierTest
```

shows the bytecodes in the class file in mnemonic form.

```

Method int fun()
  0  iconst_1
  1  istore_0
  2  iconst_2
  3  istore_1
  4  iload_0
  5  iload_1
  6  iadd
  7  istore_2
  8  iload_2
  9  ireturn

```

Use a hex editor to change instruction 3 from `istore_1` to `istore_0`. That is, local variable 0 (which is m) is initialized twice, and local variable 1 (which is n) is not initialized at all. We need to know the hexadecimal values for these instructions; these values are readily available from the Java Virtual Machine specification

(<https://docs.oracle.com/javase/specs/jvms/se11/html/index.html>).

```
0  iconst_1  04
1  istore_0  3B
2  iconst_2  05
3  istore_1  3C
4  iload_0   1A
5  iload_1   1B
6  iadd      60
7  istore_2  3D
8  iload_2   1C
9  ireturn   AC
```

You can use any hex editor to carry out the modification. In [Figure 10.4](#), you see the class file `VerifierTest.class` loaded into the Gnome hex editor, with the bytecodes of the `fun` method highlighted.




Figure 10.4 Modifying bytecodes with a hex editor

Change 3C to 3B and save the class file. Then try running the VerifierTest program. You get an error message:

[Click here to view code image](#)

```
Exception in thread "main" java.lang.VerifyError: (class:
VerifierTest, method:fun signature:
()I) Accessing value from uninitialized register 1
```

That is good—the virtual machine detected our modification.

Now run the program with the `-noverify` (or `-Xverify:none`) option:

[Click here to view code image](#)

```
java -noverify verifier.VerifierTest
```

The `fun` method returns a seemingly random value. This is actually 2 plus the value that happened to be stored in the variable `n`, which was never initialized.

Here is a typical printout:

```
1 + 2 == 15102330
```

Listing 10.3 verifier/VerifierTest.java

[Click here to view code image](#)

```
1 package verifier;
2
3 import java.awt.*;
4
5 /**
6  * This application demonstrates the bytecode verifier of the
7  * virtual machine. If you use a
8  * hex editor to modify the class file, then the virtual
9  * machine should detect the tampering.
10 */
11 public class VerifierTest
12 {
13     public static void main(String[] args)
14     {
15         System.out.println("1 + 2 == " + fun());
16     }
17
18     /**
19      * A function that computes 1 + 2.
20      * @return 3, if the code has not been corrupted
21 }
```

```
21     */
22     public static int fun()
23     {
24         int m;
25         int n;
26         m = 1;
27         n = 2;
28         // use hex editor to change to "m = 2" in class file
29         int r = m + n;
30         return r;
31     }
32 }
```

10.2 User Authentication

The Java API provides a framework, called the Java Authentication and Authorization Service (JAAS), that provides access to platform-provided and custom authentication mechanisms. We'll discuss the JAAS framework in the following sections.

10.2.1 The JAAS Framework

As you can tell from its name, the JAAS framework has two components. The “authentication” part is concerned with ascertaining the identity of a program user. The “authorization” part is tied to the deprecated security manager, and we will not discuss it.

JAAS is a “pluggable” API that isolates Java applications from the particular technology used to implement authentication. It supports, among others, UNIX logins, Windows logins, Kerberos authentication, and certificate-based authentication.

Here is the basic outline of the login code:

[Click here to view code image](#)

```

try
{
    System.setSecurityManager(new SecurityManager());
    var context = new LoginContext("Login1"); // defined in JAAS
configuration file
    context.login();
    // get the authenticated Subject
    Subject subject = context.getSubject();
    . . .
    context.logout();
}
catch (LoginException e) // thrown if login was not successful
{
    exception.printStackTrace();
}

```

Now the `subject` denotes the individual who has been authenticated.

The string parameter "Login1" in the `LoginContext` constructor refers to an entry with the same name in the JAAS configuration file. Here is a sample configuration file:

[Click here to view code image](#)

```

Login1
{
    com.sun.security.auth.module.UnixLoginModule required;
    com.whizzbang.auth.module.RetinaScanModule sufficient;
};

Login2
{
    . . .
};

```

Of course, the JDK contains no biometric login modules. The following modules are supplied in the `com.sun.security.auth.module` package:

```
UnixLoginModule  
NTLoginModule  
Krb5LoginModule  
JndiLoginModule  
KeyStoreLoginModule
```

A login policy consists of a sequence of login modules, each labeled required, sufficient, requisite, or optional. The meaning of these keywords is given by the following algorithm:

1. The modules are executed in turn, until a sufficient module succeeds, a requisite module fails, or the end of the module list is reached.
2. Authentication is successful if all required and requisite modules succeed, or if none of them were executed, if at least one sufficient or optional module succeeds.

A login authenticates a *subject*, which can have multiple *principals*. A principal describes some property of the subject, such as the user name, group ID, or role. The com.sun.security.auth.UnixPrincipal describes the UNIX login name, and the UnixNumericGroupPrincipal can test for membership in a UNIX group.

The program in [Listings 10.4](#) displays the principals of the currently logged-in user. Run the program as

[Click here to view code image](#)

```
java -Djava.security.auth.login.config=auth/jaas.config  
auth.AuthTest
```

[Listing 10.5](#) shows the login configuration.

On Windows, change UnixPrincipal to NTUserPrincipal in AuthTest.policy and UnixLoginModule to NTLoginModule in jaas.config.

Listing 10.4 auth/AuthTest.java

[Click here to view code image](#)

```
1 package auth;
2
3 import java.security.*;
4 import javax.security.auth.*;
5 import javax.security.auth.login.*;
6
7 /**
8  * This program obtains information about a user's Unix login
9  * @version 1.03 2021-11-29
10 * @author Cay Horstmann
11 */
12 public class AuthTest
13 {
14     public static void main(final String[] args)
15     {
16         try
17         {
18             var context = new LoginContext("Login1");
19             context.login();
20             System.out.println("Authentication successful.");
21             Subject subject = context.getSubject();
22             for (Principal p : subject.getPrincipals())
23             {
24                 System.out.println(p.getClass().getName() + ": " +
25 p.getName());
26             }
27         }
28         catch (LoginException e)
29         {
30             System.out.println("Authentication failed.");
31             e.printStackTrace();
32         }
33     }
34 }
```

```
33      }
34 }
```

Listing 10.5 auth/jaas.config

[Click here to view code image](#)

```
1 Login1
2 {
3     com.sun.security.auth.module.UnixLoginModule required;
4 };
```

javax.security.auth.login.LoginContext 1.4

- `LoginContext(String name)`
constructs a login context. The name corresponds to the login descriptor in the JAAS configuration file.
- `void login()`
establishes a login or throws `LoginException` if the login failed. Invokes the `login` method on the managers in the JAAS configuration file.
- `void logout()`
logs out the subject. Invokes the `logout` method on the managers in the JAAS configuration file.
- `Subject getSubject()`
returns the authenticated subject.

javax.security.auth.Subject 1.4

- `Set<Principal> getPrincipals()`
gets the principals of this subject.

java.security.Principal 1.1

- `String getName()`
returns the identifying name of this principal.

10.2.2 JAAS Login Modules

In this section, we'll look at a JAAS example that shows you

- How to implement your own login module
- How to implement *role-based* authentication

Supplying your own login module is useful if you store login information in a database.

One job of the login module is to populate the principal set of the subject that is being authenticated. If a login module supports roles, it adds `Principal` objects that describe roles. The Java library does not provide a class for this purpose, so I wrote my own (see [Listing 10.6](#)). The class simply stores a description/value pair, such as `role=admin`. Its `getName` method returns that pair.

The login module looks up users, passwords, and roles in a text file that contains lines like this:

```
harry|secret|admin  
carl|guessme|HR
```

Of course, in a realistic login module, you would store this information in a database or directory.

You can find the code for the SimpleLoginModule in [Listing 10.7](#). The checkLogin method checks whether the user name and password match a record in the password file. If so, we add two SimplePrincipal objects to the subject's principal set:

[Click here to view code image](#)

```
Set<Principal> principals = subject.getPrincipals();
principals.add(new SimplePrincipal("username", username));
principals.add(new SimplePrincipal("role", role));
```

The remainder of SimpleLoginModule is straightforward plumbing. The initialize method receives

- The Subject that is being authenticated
- A handler to retrieve login information
- A sharedState map that can be used for communication between login modules
- An options map that contains the name/value pairs that are set in the login configuration

For example, we configure our module as follows:

[Click here to view code image](#)

```
SimpleLoginModule required pwfile="jaas/password.txt";
```

The login module retrieves the pwfile settings from the options map.

The login module does not gather the user name and password; that is the job of a separate handler. This separation allows you to use the same login module without worrying whether the login information comes from a GUI dialog box, a console prompt, or a configuration file.

The handler is specified when you construct the LoginContext, for example:

[Click here to view code image](#)

```
var context = new LoginContext("Login1",
    new com.sun.security.auth.callback.DialogCallbackHandler());
```

The DialogCallbackHandler pops up a simple GUI dialog box to retrieve the user name and password. The com.sun.security.auth.callback.TextCallbackHandler class gets the information from the console.

However, in my application, I have my own GUI for collecting the user name and password (see [Figure 10.5](#)). I created a simple handler that merely stores and returns that information (see [Listing 10.8](#)).



Figure 10.5 A custom login module

The handler has a single method, handle, that processes an array of Callback objects. A number of predefined classes, such as NameCallback and PasswordCallback, implement the Callback interface. You could also add your own class, such as RetinaScanCallback. The handler code is a bit unsightly because it needs to analyze the types of the callback objects:

[Click here to view code image](#)

```
public void handle(Callback[] callbacks)
{
    for (Callback callback : callbacks)
    {
        if (callback instanceof NameCallback) . . .
        else if (callback instanceof PasswordCallback) . . .
        else . . .
```

```
    }  
}
```

The login module prepares an array of the callbacks that it needs for authentication:

[Click here to view code image](#)

```
var nameCall = new NameCallback("username: ");  
var passCall = new PasswordCallback("password: ", false);  
callbackHandler.handle(new Callback[] { nameCall, passCall });
```

Then it retrieves the information from the callbacks.

The program in [Listing 10.9](#) displays a form for entering the login information. When the login is successful, the principals are shown. Run the program as

[Click here to view code image](#)

```
java -Djava.security.auth.login.config=jaas/jaas.config  
jaas.JAASTest
```



Note

It is possible to support a more complex two-phase protocol, whereby a login is *committed* if all modules in the login configuration were successful. For more information, see the login module developer's guide at <http://docs.oracle.com/javase/8/docs/technologies/guides/security/jaas/JAASLMDevGuide.html>.

Listing 10.6 jaas/SimplePrincipal.java

[Click here to view code image](#)

```
1 package jaas;
2
3 import java.security.*;
4 import java.util.*;
5
6 /**
7  * A principal with a named value (such as "role=HR" or
8  * "username=harry").
9  */
10 public class SimplePrincipal implements Principal
11 {
12     private String descr;
13     private String value;
14
15     /**
16      * Constructs a SimplePrincipal to hold a description and a
17      * value.
18      *
19      * @param descr the description
20      * @param value the associated value
21      */
22     public SimplePrincipal(String descr, String value)
23     {
24         this.descr = descr;
25         this.value = value;
26     }
27
28     public SimplePrincipal(String descrAndValue)
29     {
30         String[] dv = descrAndValue.split("=");
31         this.descr = dv[0];
32         this.value = dv[1];
33     }
34
35     /**
36      * @return the description and value of this simple
37      * principal.
38      */
39     public String getName()
```

```
36     {
37         return descr + "=" + value;
38     }
39
40     public boolean equals(Object otherObject)
41     {
42         if (this == otherObject) return true;
43         if (otherObject == null) return false;
44         if (getClass() != otherObject.getClass()) return false;
45         var other = (SimplePrincipal) otherObject;
46         return Objects.equals(getName(), other.getName());
47     }
48
49     public int hashCode()
50     {
51         return Objects.hashCode(getName());
52     }
53 }
```

Listing 10.7 jaas/SimpleLoginModule.java

[Click here to view code image](#)

```
1  package jaas;
2
3  import java.io.*;
4  import java.nio.charset.*;
5  import java.nio.file.*;
6  import java.security.*;
7  import java.util.*;
8  import javax.security.auth.*;
9  import javax.security.auth.callback.*;
10 import javax.security.auth.login.*;
11 import javax.security.auth.spi.*;
12
13 /**
14  * This login module authenticates users by reading
 usernames, passwords, and roles from
```

```
15 * a text file.
16 */
17 public class SimpleLoginModule implements LoginModule
18 {
19     private Subject subject;
20     private CallbackHandler callbackHandler;
21     private Map<String, ?> options;
22
23     public void initialize(Subject subject, CallbackHandler
callbackHandler,
24                         Map<String, ?> sharedState, Map<String, ?> options)
25     {
26         this.subject = subject;
27         this.callbackHandler = callbackHandler;
28         this.options = options;
29     }
30
31     public boolean login() throws LoginException
32     {
33         if (callbackHandler == null) throw new
LoginException("no handler");
34
35         var nameCall = new NameCallback("username: ");
36         var passCall = new PasswordCallback("password: ",
false);
37         try
38         {
39             callbackHandler.handle(new Callback[] { nameCall,
passCall });
40         }
41         catch (UnsupportedCallbackException e)
42         {
43             var e2 = new LoginException("Unsupported callback");
44             e2.initCause(e);
45             throw e2;
46         }
47         catch (IOException e)
48         {
```

```
49         var e2 = new LoginException("I/O exception in
callback");
50         e2.initCause(e);
51         throw e2;
52     }
53
54     try
55     {
56         return checkLogin(nameCall.getName(),
passCall.getPassword());
57     }
58     catch (IOException e)
59     {
60         var e2 = new LoginException();
61         e2.initCause(e);
62         throw e2;
63     }
64 }
65
66 /**
67 * Checks whether the authentication information is valid.
If it is, the subject acquires
68 * principals for the user name and role.
69 * @param username the user name
70 * @param password a character array containing the
password
71 * @return true if the authentication information is valid
72 */
73 private boolean checkLogin(String username, char[]
password)
74         throws LoginException, IOException
75     {
76         try (var in = new Scanner(
77                 Path.of("") + options.get("pwfile")),
StandardCharsets.UTF_8))
78     {
79         while (in.hasNextLine())
80         {
```

```
81         String[] inputs = in.nextLine().split("\\\\|");
82         if (inputs[0].equals(username)
83             && Arrays.equals(inputs[1].toCharArray(),
84             password))
85     {
86         String role = inputs[2];
87         Set<Principal> principals =
88             subject.getPrincipals();
89         principals.add(new SimplePrincipal("username",
90             username));
91         principals.add(new SimplePrincipal("role",
92             role));
93     }
94 }
95
96     public boolean logout()
97     {
98         return true;
99     }
100
101    public boolean abort()
102    {
103        return true;
104    }
105
106    public boolean commit()
107    {
108        return true;
109    }
110 }
```

Listing 10.8 jaas/SimpleCallbackHandler.java

[Click here to view code image](#)

```
1 package jaas;
2
3 import javax.security.auth.callback.*;
4
5 /**
6  * This simple callback handler presents the given user name
7  * and password.
8 */
9 public class SimpleCallbackHandler implements CallbackHandler
10 {
11     private String username;
12
13     /**
14      * Constructs the callback handler.
15      * @param username the user name
16      * @param password a character array containing the
17      * password
18
19     */
20     public SimpleCallbackHandler(String username, char[]
21     password)
22     {
23
24         this.username = username;
25         this.password = password;
26     }
27
28     public void handle(Callback[] callbacks)
29     {
30         for (Callback callback : callbacks)
31         {
32             if (callback instanceof NameCallback c)
33             {
34                 c.setName(username);
35             }
36             else if (callback instanceof PasswordCallback c)
37             {
38                 c.setPassword(password);
39             }
40         }
41     }
42 }
```

```
34             c.setPassword(password);
35         }
36     }
37 }
38 }
```

Listing 10.9 jaas/JAASTest.java

[Click here to view code image](#)

```
1 package jaas;
2
3 import java.awt.*;
4 import javax.swing.*;
5
6 /**
7  * This program authenticates a user via a custom login
8  * @version 1.04 2021-05-30
9  * @author Cay Horstmann
10 */
11 public class JAASTest
12 {
13     public static void main(final String[] args)
14     {
15         EventQueue.invokeLater(() ->
16         {
17             var frame = new JAASFrame();
18
19             frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
20             frame.setTitle("JAASTest");
21             frame.setVisible(true);
22         });
23     }
}
```

Listing 10.10 jaas/jaas.config

[Click here to view code image](#)

```
1 Login1
2 {
3     jaas.SimpleLoginModule required pwfile="jaas/password.txt"
debug=true;
4 };
```

javax.security.auth.callback.CallbackHandler 1.4

- void handle(Callback[] callbacks)

handles the given callbacks, interacting with the user if desired, and stores the security information in the callback objects.

javax.security.auth.callback.NameCallback 1.4

- NameCallback(String prompt)
- NameCallback(String prompt, String defaultName)

construct a NameCallback with the given prompt and default name.

- String getName()
- void setName(String name)

get or set the name gathered by this callback.

- String getPrompt()
- gets the prompt to use when querying this name.
- String getDefaultName()

gets the default name to use when querying this name.

`javax.security.auth.callback.PasswordCallback` 1.4

- `PasswordEncoder(String prompt, boolean echoOn)`
constructs a `PasswordCallback` with the given prompt and echo flag.
- `char[] getPassword()`
- `void setPassword(char[] password)`
get or set the password gathered by this callback.
- `String getPrompt()`
gets the prompt to use when querying this password.
- `boolean isEchoOn()`
gets the echo flag to use when querying this password.

`javax.security.auth.spi.LoginModule` 1.4

- `void initialize(Subject subject, CallbackHandler handler, Map<String, ?> sharedState, Map<String, ?> options)`
initializes this `LoginModule` for authenticating the given subject. During login processing, uses the given handler to gather login information. Use the `sharedState` map for communicating with other login modules. The `options` map

contains the name/value pairs specified in the login configuration for this module instance.

- `boolean login()`

carries out the authentication process and populates the subject's principals. Returns `true` if the login was successful.

- `boolean commit()`

is called after all login modules were successful, for login scenarios that require a two-phase commit. Returns `true` if the operation was successful.

- `boolean abort()`

is called if the failure of another login module caused the login process to abort. Returns `true` if the operation was successful.

- `boolean logout()`

logs out this subject. Returns `true` if the operation was successful.

10.3 Digital Signatures

As already mentioned, applets were what started the Java craze. In practice, people discovered that although they could write animated applets (like the famous "nervous text"), applets could not do a whole lot of useful stuff in the JDK 1.0 security model. For example, since applets under JDK 1.0 were so closely supervised, they couldn't do much good on a corporate intranet, even though relatively little risk attaches to executing an applet from your company's secure intranet. It quickly became clear to Sun that for applets to become truly useful, users need to be able to assign *different* levels of security, depending on where the applet originated. If an applet comes from a trusted supplier and has not been tampered with, the user of that applet can decide whether to give the applet more privileges.

To give more trust to an applet, we need to know two things:

- Where did the applet come from?
- Was the code corrupted in transit?

In the past 50 years, mathematicians and computer scientists have developed sophisticated algorithms for ensuring the integrity of data and for creating electronic signatures. The `java.security` package contains implementations of many of these algorithms. Fortunately, you don't need to understand the underlying mathematics to use the algorithms in the `java.security` package. In the next sections, I'll show you how message digests can detect changes in data files and how digital signatures can prove the identity of the signer.

10.3.1 Message Digests

A message digest is a digital fingerprint of a block of data. For example, the so-called SHA-1 (Secure Hash Algorithm #1) condenses any data block, no matter how long, into a sequence of 160 bits (20 bytes). As with real fingerprints, one hopes that no two different messages have the same SHA-1 fingerprint. Of course, that cannot be true—there are only 2^{160} SHA-1 fingerprints, so there must be some messages with the same fingerprint. But 2^{160} is so large that the probability of a collision is negligible. How negligible? According to James Walsh in *True Odds: How Risks Affect Your Everyday Life* (Merritt Publishing, 1996), the chance that you will die from being struck by lightning is about one in 30,000. Now, think of nine other people—for example, your nine least favorite managers or professors. The chance that you and *all of them* will die from lightning strikes is higher than that of a forged message having the same SHA-1 fingerprint as the original. (Of course, more than ten people, none of whom you are likely to know, *will* die from lightning strikes. However, we are talking about the far slimmer chance that *your particular choice* of people will be wiped out.)

A message digest has two essential properties:

- If one bit or several bits of the data are changed, the message digest also changes.

- A forger who is in possession of a given message cannot construct a fake message that has the same message digest as the original.

The second property is, again, a matter of probabilities. Consider the following message by the billionaire father:

“Upon my death, my property shall be divided equally among my children; however, my son George shall receive nothing.”

That message (with a final newline) has an SHA-1 fingerprint of

[Click here to view code image](#)

```
12 5F 09 03 E7 31 30 19 2E A6 E7 E4 90 43 84 B4 38 99 8F 67
```

The distrustful father has deposited the message with one attorney and the fingerprint with another. Now, suppose George bribes the lawyer holding the message. He wants to change the message so that Bill gets nothing. Of course, that changes the fingerprint to a completely different bit pattern:

[Click here to view code image](#)

```
7D F6 AB 08 EB 40 EC CD AB 74 ED E9 86 F9 ED 99 D1 45 B1 57
```

Can George find some other wording that matches the fingerprint? If he had been the proud owner of a billion computers from the time the Earth was formed, each computing a million messages a second, he would not yet have found a message he could substitute.

A number of algorithms have been designed to compute such message digests. Among them are SHA-1, the secure hash algorithm developed by the National Institute of Standards and Technology, and MD5, an algorithm invented by Ronald Rivest of MIT. Both algorithms scramble the bits of a message in ingenious ways. For details about these algorithms, see, for example, *Cryptography and Network Security, Seventh Edition*, by William Stallings (Prentice Hall, 2017). However, subtle regularities have been discovered in both algorithms, and NIST recommends to switch to stronger alternatives. Java supports the SHA-2 and SHA-3 sets of algorithms.

The `MessageDigest` class is a *factory* for creating objects that encapsulate the fingerprinting algorithms. It has a static method, called `getInstance`, that returns an object of a class that extends the `MessageDigest` class. This means the `MessageDigest` class serves double duty:

- As a factory class
- As the superclass for all message digest algorithms

For example, here is how you obtain an object that can compute SHA fingerprints:

[Click here to view code image](#)

```
MessageDigest alg = MessageDigest.getInstance("SHA-1");
```

After you have obtained a `MessageDigest` object, feed it all the bytes in the message by repeatedly calling the `update` method. For example, the following code passes all bytes in a file to the `alg` object just created to do the fingerprinting:

[Click here to view code image](#)

```
InputStream in = . . .;
int ch;
while ((ch = in.read()) != -1)
    alg.update((byte) ch);
```

Alternatively, if you have the bytes in an array, you can update the entire array at once:

```
byte[] bytes = . . .;
alg.update(bytes);
```

When you are done, call the `digest` method. This method pads the input as required by the fingerprinting algorithm, does the computation, and returns the digest as an array of bytes.

```
byte[] hash = alg.digest();
```

The program in [Listing 10.11](#) computes a message digest. You can specify the file and algorithm on the command line:

[Click here to view code image](#)

```
java hash.Digest hash/input.txt SHA-1
```

If you do not supply command-line arguments, you will be prompted for the file and algorithm name.

Listing 10.11 hash/Digest.java

[Click here to view code image](#)

```
1 package hash;
2
3 import java.io.*;
4 import java.nio.file.*;
5 import java.security.*;
6 import java.util.*;
7
8 /**
9  * This program computes the message digest of a file.
10 * @version 1.21 2018-04-10
11 * @author Cay Horstmann
12 */
13 public class Digest
14 {
15     /**
16      * @param args args[0] is the filename, args[1] is
17      * optionally the algorithm
18      * (SHA-1, SHA-256, or MD5)
19      */
20     public static void main(String[] args) throws IOException,
21     GeneralSecurityException
22     {
23         var in = new Scanner(System.in);
24         String filename;
```

```
23     if (args.length >= 1)
24         filename = args[0];
25     else
26     {
27         System.out.print("File name: ");
28         filename = in.nextLine();
29     }
30     String aliname;
31     if (args.length >= 2)
32         aliname = args[1];
33     else
34     {
35         System.out.println("Select one of the following
algorithms: ");
36         for (Provider p : Security.getProviders())
37             for (Provider.Service s : p.getServices())
38                 if (s.getType().equals("MessageDigest"))
39                     System.out.println(s.getAlgorithm());
40         System.out.print("Algorithm: ");
41         aliname = in.nextLine();
42     }
43     MessageDigest alg = MessageDigest.getInstance(aliname);
44     byte[] input = Files.readAllBytes(Path.of(filename));
45     byte[] hash = alg.digest(input);
46     for (int i = 0; i < hash.length; i++)
47         System.out.printf("%02X ", hash[i] & 0xFF);
48     System.out.println();
49 }
50 }
```

java.security.MessageDigest 1.1

- static MessageDigest getInstance(String algorithmName)

returns a `MessageDigest` object that implements the specified algorithm. Throws `NoSuchAlgorithmException` if the algorithm is not provided.

- `void update(byte input)`
- `void update(byte[] input)`
- `void update(byte[] input, int offset, int len)`

update the digest, using the specified bytes.

- `byte[] digest()`

completes the hash computation, returns the computed digest, and resets the algorithm object.

- `void reset()`

resets the digest.

10.3.2 Message Signing

In the last section, you saw how to compute a message digest—a fingerprint for the original message. If the message is altered, the fingerprint of the altered message will not match the fingerprint of the original. If the message and its fingerprint are delivered separately, the recipient can check whether the message has been tampered with. However, if both the message and the fingerprint were intercepted, it is an easy matter to modify the message and then recompute the fingerprint. After all, the message digest algorithms are publicly known, and they don't require secret keys. In that case, the recipient of the forged message and the recomputed fingerprint would never know that the message has been altered. Digital signatures solve this problem.

To help you understand how digital signatures work, let's look at a few concepts from the field called *public key cryptography*. Public key cryptography is based on the notion of a *public key* and *private key*. The

idea is that you tell everyone in the world your public key. However, only you hold the private key, and it is important that you safeguard it and don't release it to anyone else. The keys are matched by mathematical relationships, though the exact nature of these relationships is not important to us. (If you are interested, look it up in *The Handbook of Applied Cryptography* at www.cacr.math.uwaterloo.ca/hac.)

The keys are quite long and complex. For example, here is a matching pair of public and private Digital Signature Algorithm (DSA) keys.

Public key:

[Click here to view code image](#)

p:

```
fca682ce8e12caba26efccf7110e526db078b05edecbcd1eb4a208f3ae1617a  
e01f35b91a47e6df63413c5e12  
ed0899bcd132acd50d99151bdc43ee737592e17
```

q: 962eddcc369cba8ebb260ee6b6a126d9346e38c5

g:

```
678471b27a9cf44ee91a49c5147db1a9aaf244f05a434d6486931d2d14271b9  
e35030b71fd73da179069b32e2  
935630e1c2062354d0da20a6c416e50be794ca4
```

y:

```
c0b6e67b4ac098eb1a32c5f8c4c1f0e7e6fb9d832532e27d0bdab9ca2d2a812  
3ce5a8018b8161a760480fadd0  
40b927281ddb22cb9bc4df596d7de4d1b977d50
```

Private key:

[Click here to view code image](#)

p:

```
fca682ce8e12caba26efccf7110e526db078b05edecbcd1eb4a208f3ae1617a  
e01f35b91a47e6df63413c5e12  
ed0899bcd132acd50d99151bdc43ee737592e17
```

q: 962eddcc369cba8ebb260ee6b6a126d9346e38c5

g:

678471b27a9cf44ee91a49c5147db1a9aaf244f05a434d6486931d2d14271b9
e35030b71fd73da179069b32e2
935630e1c2062354d0da20a6c416e50be794ca4

x: 146c09f881656cc6c51f27ea6c3a91b85ed1d70a

It is believed to be practically impossible to compute one key from the other. That is, even though everyone knows your public key, they can't, in your lifetime, compute your private key, no matter how many computing resources they have available.

It may be difficult to believe that the private key can't be computed from the public key—but nobody has found an algorithm to do this for the encryption algorithms in common use today. If the keys are sufficiently long, brute force—simply trying all possible keys—would require more computers than can be built from all the atoms in the solar system, crunching away for thousands of years. Of course it is possible that someone could come up with algorithms for computing keys that are much more clever than brute force. For example, the RSA algorithm (the encryption algorithm invented by Rivest, Shamir, and Adleman) depends on the difficulty of factoring large numbers. For the last 20 years, many of the best mathematicians have tried to come up with good factoring algorithms, but so far with no success. For that reason, most cryptographers believe that keys with a “modulus” of 2,000 bits or more are currently completely safe from any attack. DSA is believed to be similarly secure.

[Figure 10.6](#) illustrates how the process works in practice.




Figure 10.6 Public key signature exchange with DSA

Suppose Alice wants to send Bob a message, and Bob wants to know this message came from Alice and not an impostor. Alice writes the message and *signs* the message digest with her private key. Bob gets a copy of her public key. Bob then applies the public key to *verify* the signature. If the verification passes, Bob can be assured of two facts:

- The original message has not been altered.
- The message was signed by Alice, the holder of the private key that matches the public key that Bob used for verification.

You can see why the security of private keys is so important. If someone steals Alice's private key, or if a government can require her to turn it over, then she is in trouble. The thief or a government agent can now impersonate her by sending messages, such as money transfer instructions, that others will believe came from Alice.

10.3.3 Verifying a Signature

The JDK comes with the `keytool` program, which is a command-line tool to generate and manage a set of certificates. We expect that ultimately the functionality of this tool will be embedded in other, more user-friendly programs. But right now, we'll use `keytool` to show how Alice can sign a document and send it to Bob, and how Bob can verify that the document really was signed by Alice and not an impostor.

The `keytool` program manages *keystores*—databases of certificates and private/public key pairs. Each entry in the keystore has an *alias*. Here is how Alice creates a keystore, `alice.certs`, and generates a key pair with alias `alice`:

[Click here to view code image](#)

```
keytool -genkeypair -keystore alice.certs -alias alice
```

When creating or opening a keystore, you are prompted for a keystore password. For this example, just use `secret`. If you were to use the `keytool`-generated keystore for any serious purpose, you would need to choose a good password and safeguard this file.

When generating a key, you are prompted for the following information:

[Click here to view code image](#)

```
Enter keystore password: secret
Reenter new password: secret
What is your first and last name?
[Unknown]: Alice Lee
What is the name of your organizational unit?
[Unknown]: Engineering
```

What is the name of your organization?

[Unknown] : **ACME Software**

What is the name of your City or Locality?

[Unknown] : **San Francisco**

What is the name of your State or Province?

[Unknown] : **CA**

What is the two-letter country code for this unit?

[Unknown] : **US**

Is <CN=Alice Lee, OU=Engineering, O=ACME Software, L=San Francisco, ST=CA, C=US> correct?

[no] : **yes**

The keytool uses names in the X.500 format, whose components are Common Name (CN), Organizational Unit (OU), Organization (O), Location (L), State (ST), and Country (C), to identify key owners and certificate issuers.

Finally, specify a key password, or press Enter to use the keystore password as the key password.

Suppose Alice wants to give her public key to Bob. She needs to export a certificate file:

[Click here to view code image](#)

```
keytool -exportcert -keystore alice.certs -alias alice -file  
alice.cer
```

Now Alice can send the certificate to Bob. When Bob receives the certificate, he can print it:

[Click here to view code image](#)

```
keytool -printcert -file alice.cer
```

The printout looks like this:

[Click here to view code image](#)

Owner: CN=Alice Lee, OU=Engineering, O=ACME Software, L=San Francisco, ST=CA, C=US
Issuer: CN=Alice Lee, OU=Engineering, O=ACME Software, L=San Francisco, ST=CA, C=US
Serial number: 470835ce
Valid from: Sat Oct 06 18:26:38 PDT 2007 until: Fri Jan 04 17:26:38 PST 2008
Certificate fingerprints:
MD5: BC:18:15:27:85:69:48:B1:5A:C3:0B:1C:C6:11:B7:81
SHA1:
31:0A:A0:B8:C2:8B:3B:B6:85:7C:EF:C0:57:E5:94:95:61:47:6D:34
Signature algorithm name: SHA1withDSA
Version: 3

If Bob wants to check that he got the right certificate, he can call Alice and verify the certificate fingerprint over the phone.



Note

Some certificate issuers publish certificate fingerprints on their web sites. For example, to check the DigiCert certificate in the keystore `jre/lib/security/cacerts` directory, use the `-list` option:

[Click here to view code image](#)

```
keytool -list -v -keystore jre/lib/security/cacerts
```

The password for this keystore is `changeit`. One of the certificates in this keystore is

[Click here to view code image](#)

Owner: CN=DigiCert Assured ID Root G3, OU=www.digicert.com, O=DigiCert Inc, C=US
Issuer: CN=DigiCert Assured ID Root G3, OU=www.digicert.com, O=DigiCert Inc, C=US

```
Serial number: ba15afa1ddfa0b54944afcd24a06cec
Valid from: Thu Aug 01 14:00:00 CEST 2013 until: Fri Jan 15
13:00:00 CET 2038
Certificate fingerprints:
    SHA1:
F5:17:A2:4F:9A:48:C6:C9:F8:A2:00:26:9F:DC:0F:48:2C:AB:30:89
    SHA256:
7E:37:CB:8B:4C:47:09:0C:AB:36:55:1B:A6:F4:5D:B8:40:68:0F:BA:
                           16:6A:95:2D:B1:00:71:7F:43:05:3F:C2
```

You can check that your certificate is valid by visiting the web site
www.digicert.com/digicert-root-certificates.htm.

Once Bob trusts the certificate, he can import it into his keystore.

[Click here to view code image](#)

```
keytool -importcert -keystore bob.certs -alias alice -file
alice.cer
```



Caution

Never import into a keystore a certificate that you don't fully trust. Once a certificate is added to the keystore, any program that uses the keystore assumes that the certificate can be used to verify signatures.

Now Alice can start sending signed documents to Bob. The jarsigner tool signs and verifies JAR files. Alice simply adds the document to be signed into a JAR file.

[Click here to view code image](#)

```
jar cvf document.jar document.txt
```

She then uses the `jarsigner` tool to add the signature to the file. She needs to specify the keystore, the JAR file, and the alias of the key to use.

[Click here to view code image](#)

```
jarsigner -keystore alice.certs document.jar alice
```

When Bob receives the file, he uses the `-verify` option of the `jarsigner` program.

[Click here to view code image](#)

```
jarsigner -verify -keystore bob.certs document.jar
```

Bob does not need to specify the key alias. The `jarsigner` program finds the X.500 name of the key owner in the digital signature and looks for a matching certificate in the keystore.

If the JAR file is not corrupted and the signature matches, the `jarsigner` program prints

```
jar verified.
```

Otherwise, the program displays an error message.

10.3.4 The Authentication Problem

Suppose you get a message from your friend Alice, signed with her private key, using the method I just showed you. You might already have her public key, or you can easily get it by asking her for a copy or by getting it from her web page. Then, you can verify that the message was in fact authored by Alice and has not been tampered with. Now, suppose you get a message from a stranger who claims to represent a famous software company, urging you to run a program attached to the message. The stranger even sends you a copy of his public key so you can verify that he authored the message. You check that the signature is valid. This proves that the message was signed with the matching private key and has not been corrupted.

Be careful: *You still have no idea who wrote the message.* Anyone can generate a pair of public and private keys, sign the message with the private key, and send the signed message and the public key to you. The problem of determining the identity of the sender is called the *authentication problem*.

The usual way to solve the authentication problem is simple. Suppose the stranger and you have a common acquaintance you both trust. Suppose the stranger meets your acquaintance in person and hands over a disk with the public key. Your acquaintance later meets you, assures you that he met the stranger and that the stranger indeed works for the famous software company, and then gives you the disk (see [Figure 10.7](#)). That way, your acquaintance vouches for the authenticity of the stranger.




Figure 10.7 Authentication through a trusted intermediary

In fact, your acquaintance does not actually need to meet you. Instead, he can use his private key to sign the stranger's public key file (see [Figure 10.8](#)).




Figure 10.8 Authentication through a trusted intermediary's signature

When you get the public key file, you verify the signature of your friend, and because you trust him, you are confident that he did check the stranger's credentials before applying his signature.

However, you might not have a common acquaintance. Some trust models assume that there is always a “chain of trust”—a chain of mutual acquaintances—so that you trust every member of that chain. In practice, of course, that isn’t always true. You might trust your friend, Alice, and you know that Alice trusts Bob, but you don’t know Bob and aren’t sure that you trust him. Other trust models assume that there is a benevolent big brother—a company in which we all trust. Companies with confidence-inspiring names such as DigiCert, GlobalSign, and Entrust provide verification services.

You will often encounter digital signatures signed by one or more entities who will vouch for the authenticity, and you will need to evaluate to what degree you trust the authenticators. You might place a great deal of trust in a particular certificate authority, perhaps because you saw their logo on many web pages or because you heard that they require multiple people with black attaché cases to come together into a secure chamber whenever new master keys are to be minted.

However, you should have realistic expectations about what is actually being authenticated. You can get a “class 1” ID simply by filling out a web form and paying a small fee. The key is mailed to the e-mail address included in the certificate. Thus, you can be reasonably assured that the e-mail address is genuine, but the requestor could have filled in *any* name and organization. There are more stringent classes of IDs. For example, with a “class 3” ID, the certificate authority will require an individual requestor to appear before a notary public, and it will check the financial rating of a corporate requestor. Other authenticators will have different procedures. Thus, when you receive an authenticated message, it is important that you understand what, in fact, is being authenticated.

10.3.5 Certificate Signing

In [Section 10.3.3, “Verifying a Signature,”](#) on p. 569 you saw how Alice used a self-signed certificate to distribute a public key to Bob. However, Bob needed to ensure that the certificate was valid by verifying the fingerprint with Alice.

Suppose Alice wants to send her colleague Cindy a signed message, but Cindy doesn't want to bother with verifying lots of signature fingerprints. Now suppose there is an entity that Cindy trusts to verify signatures. In this example, Cindy trusts the Information Resources Department at ACME Software.

That department operates a *certificate authority* (CA). Everyone at ACME has the CA's public key in their keystore, installed by a system administrator who carefully checked the key fingerprint. The CA signs the keys of ACME employees. When they install each other's keys, the keystore will trust them implicitly because they are signed by a trusted key.

Here is how you can simulate this process. Create a keystore `acmesoft.certs`. Generate a key pair and export the public key:

[Click here to view code image](#)

```
keytool -genkeypair -keystore acmesoft.certs -alias acmeroot  
keytool -exportcert -keystore acmesoft.certs -alias acmeroot -  
file acmeroot.cer
```

The public key is exported into a “self-signed” certificate. Then, add it to every employee's keystore:

[Click here to view code image](#)

```
keytool -importcert -keystore cindy.certs -alias acmeroot -file  
acmeroot.cer
```

For Alice to send messages to Cindy and to everyone else at ACME Software, she needs to bring her certificate to the Information Resources Department and have it signed. Unfortunately, this functionality is missing in the `keytool` program. In the book's companion code, I supply a `CertificateSigner` class to fill the gap. An authorized staff member at ACME Software would verify Alice's identity and generate a signed certificate as follows:

[Click here to view code image](#)

```
java CertificateSigner -keystore acmesoft.certs -alias acmeroot  
\\  
-infile alice.cer -outfile alice_signedby_acmeroot.cer
```

The certificate signer program must have access to the ACME Software keystore, and the staff member must know the keystore password. Clearly, this is a sensitive operation.

Alice gives the file `alice_signedby_acmeroot.cer` to Cindy and to anyone else in ACME Software. Alternatively, ACME Software can simply store the file in a company directory. Remember, this file contains Alice's public key and an assertion by ACME Software that this key really belongs to Alice.

Now Cindy imports the signed certificate into her keystore:

[Click here to view code image](#)

```
keytool -importcert -keystore cindy.certs -alias alice -file  
alice_signedby_acmeroot.cer
```

The keystore verifies that the key was signed by a trusted root key that is already present in the keystore. Cindy is *not* asked to verify the certificate fingerprint.

Once Cindy has added the root certificate and the certificates of the people who regularly send her documents, she never has to worry about the keystore again.

10.3.6 Certificate Requests

In the preceding section, we simulated a CA with a keystore and the `CertificateSigner` tool. However, most CAs run more sophisticated software to manage certificates, and they use slightly different formats for certificates. This section shows the added steps required to interact with those software packages.

We will use the OpenSSL software package as an example. The software is preinstalled on many Linux systems and Mac OS X, and a Cygwin port for

Windows is also available. You can download the software at www.openssl.org.

To create a CA, run the CA script. The exact location depends on your operating system. On Ubuntu, run

[Click here to view code image](#)

```
/usr/lib/ssl/misc/CA.pl -newca
```

This script creates a subdirectory called `demoCA` in the current directory. The directory contains a root key pair and storage for certificates and certificate revocation lists.

You will want to import the public key into the Java keystores of all employees, but it is in the Privacy Enhanced Mail (PEM) format, not the DER format that the keystore accepts easily. Copy the file `demoCA/cacert.pem` to a file `acmeroot.pem` and open that file in a text editor. Remove everything before the line

```
-----BEGIN CERTIFICATE-----
```

and after the line

```
-----END CERTIFICATE-----
```

Now you can import `acmeroot.pem` into each keystore in the usual way:

[Click here to view code image](#)

```
keytool -importcert -keystore cindy.certs -alias acmeroot -file  
acmeroot.pem
```

It seems quite incredible that the keytool cannot carry out this editing operation itself.

To sign Alice's public key, start by generating a *certificate request* that contains the certificate in the PEM format:

[Click here to view code image](#)

```
keytool -certreq -keystore alice.store -alias alice -file  
alice.pem
```

To sign the certificate, run

[Click here to view code image](#)

```
openssl ca -in alice.pem -out alice_signedby_acmeroot.pem
```

As before, cut out everything outside the BEGIN CERTIFICATE/END CERTIFICATE markers from alice_signedby_acmeroot.pem. Then import it into the keystore:

[Click here to view code image](#)

```
keytool -importcert -keystore cindy.certs -alias alice -file  
alice_signedby_acmeroot.pem
```

You can use the same steps to have a certificate signed with a key that is issued by a certificate authority.

10.3.7 Code Signing

A common use of authentication technology is signing executable programs. If you download a program, you are naturally concerned about the damage it can do. For example, the program could have been infected by a virus. If you know where the code comes from *and* that it has not been tampered with since it left its origin, your comfort level will be a lot higher than without this knowledge.

In this section, I'll show you how to sign JAR files, and how you can configure Java to verify the signature. This capability was designed for applets and Java Web Start applications. These are no longer commonly used technologies, but you may still need to support them in legacy products.

When Java was first released, applets ran in the “sandbox,” with limited permissions, as soon as they were loaded. If users wanted to use applets that can access the local file system, make network connections, and so on, they

had to explicitly agree. To ensure that the applet code was not tampered with in transit, it had to be digitally signed.

Here is a specific example. Suppose that while surfing the Internet, you encounter a web site that offers to run an applet from an unfamiliar vendor, provided you grant it the permission to do so (see [Figure 10.9](#)). Such a program is signed with a *software developer* certificate issued by a certificate authority that the Java runtime trusts. The pop-up dialog box identifies the software developer and the certificate issuer. Now you need to decide whether to authorize the program.




Figure 10.9 Launching a signed applet

What facts do you have at your disposal that might influence your decision? Here is what you know:

- Thawte sold a certificate to the software developer.
- The program really was signed with that certificate, and it hasn't been modified in transit.
- That certificate really was signed by Thawte—it was verified by the public key in the local `cacerts` file.

Of course, none of this tells you whether the code is safe to run. Can you trust a vendor if all you know is the vendor's name and the fact that Thawte sold them a software developer certificate? This approach never made much sense.

For intranet deployment, certificates are more plausible. Administrators can install policy files and certificates on local machines so that no user interaction is required for launching trusted code. However, with the deprecation of the security manager, this approach is no longer viable.

10.4 Encryption

So far, we have discussed one important cryptographic technique implemented in the Java security API—namely, authentication through digital signatures. A second important aspect of security is *encryption*. Even when authenticated, the information itself is plainly visible. The digital signature merely verifies that the information has not been changed. In contrast, when information is encrypted, it is not visible. It can only be decrypted with a matching key.

Authentication is sufficient for code signing—there is no need to hide the code. However, encryption is necessary when applications transfer confidential information, such as credit card numbers and other personal data.

In the past, patents and export controls prevented many companies from offering strong encryption. Fortunately, export controls are now much less

stringent, and the patents for important algorithms have expired. Nowadays, Java provides excellent encryption support as a part of the standard library.

10.4.1 Symmetric Ciphers

The Java cryptographic extensions contain a class `Cipher` that is the superclass of all encryption algorithms. To get a cipher object, call the `getInstance` method:

[Click here to view code image](#)

```
Cipher cipher = Cipher.getInstance(algorithmName);
```

or

[Click here to view code image](#)

```
Cipher cipher = Cipher.getInstance(algorithmName,  
providerName);
```

The JDK comes with ciphers by the provider named "SunJCE". It is the default provider used if you don't specify another provider name. You might want another provider if you need specialized algorithms that Oracle does not support.

The algorithm name is a string such as "AES" or "DES/CBC/PKCS5Padding".

The Data Encryption Standard (DES) is a venerable block cipher with a key length of 56 bits. Nowadays, the DES algorithm is considered obsolete because it can be cracked with brute force. A far better alternative is its successor, the Advanced Encryption Standard (AES). See <https://nvlpubs.nist.gov/nistpubs/FIPS/NIST.FIPS.197.pdf> for a detailed description of the AES algorithm. I use AES in this example.

Once you have a cipher object, initialize it by setting the mode and the key:

```
int mode = . . .;
Key key = . . .;
cipher.init(mode, key);
```

The mode is one of

```
Cipher.ENCRYPT_MODE
Cipher.DECRYPT_MODE
Cipher.WRAP_MODE
Cipher.UNWRAP_MODE
```

The wrap and unwrap modes encrypt one key with another—see the next section for an example.

Now you can repeatedly call the `update` method to encrypt blocks of data:

[Click here to view code image](#)

```
int blockSize = cipher.getBlockSize();
var inBytes = new byte[blockSize];
. . . // read inBytes
int outputSize= cipher.getOutputSize(blockSize);
var outBytes = new byte[outputSize];
int outLength = cipher.update(inBytes, 0, outputSize,
outBytes);
. . . // write outBytes
```

When you are done, you must call the `doFinal` method once. If a final block of input data is available (with fewer than `blockSize` bytes), call

[Click here to view code image](#)

```
outBytes = cipher.doFinal(inBytes, 0, inLength);
```

If all input data have been encrypted, instead call

[Click here to view code image](#)

```
outBytes = cipher.doFinal();
```

The call to `doFinal` is necessary to carry out *padding* of the final block. Consider the DES cipher. It has a block size of eight bytes. Suppose the last block of the input data has fewer than eight bytes. Of course, we can fill the remaining bytes with 0, to obtain one final block of eight bytes, and encrypt it. But when the blocks are decrypted, the result will have several trailing 0 bytes appended to it, and therefore will be slightly different from the original input file. To avoid this problem, we need a *padding scheme*. A commonly used padding scheme is the one described in the Public Key Cryptography Standard (PKCS) #5 by RSA Security, Inc. (<https://tools.ietf.org/html/rfc2898>).

In this scheme, the last block is not padded with a pad value of zero, but with a pad value that equals the number of pad bytes. In other words, if L is the last (incomplete) block, it is padded as follows:

[Click here to view code image](#)

```
L 01                                if length(L) = 7  
L 02 02                            if length(L) = 6  
L 03 03 03                        if length(L) = 5  
.  
.  
.  
L 07 07 07 07 07 07 07          if length(L) = 1
```

Finally, if the length of the input is actually divisible by 8, then one block

```
08 08 08 08 08 08 08 08
```

is appended to the input and encrypted. After decryption, the very last byte of the plaintext is a count of the padding characters to discard.

10.4.2 Key Generation

To encrypt, you need to generate a key. Each cipher has a different format for keys, and you need to make sure that the key generation is random. Follow these steps:

1. Get a `KeyGenerator` for your algorithm.

2. Initialize the generator with a source for randomness. If the block length of the cipher is variable, also specify the desired block length.
3. Call the `generateKey` method.

For example, here is how you generate an AES key:

[Click here to view code image](#)

```
KeyGenerator keygen = KeyGenerator.getInstance("AES");
var random = new SecureRandom(); // see below
keygen.init(random);
Key key = keygen.generateKey();
```

Alternatively, you can produce a key from a fixed set of raw data (perhaps derived from a password or the timing of keystrokes). Construct a `SecretKeySpec` (which implements the `SecretKey` interface) like this:

[Click here to view code image](#)

```
byte[] keyData = . . .; // 16 bytes for AES
var key = new SecretKeySpec(keyData, "AES");
```

When generating keys, make sure you use *truly random* numbers. For example, the regular random number generator in the `Random` class, seeded by the current date and time, is not random enough. Suppose the computer clock is accurate to 1/10 of a second. Then there are at most 864,000 seeds per day. If an attacker knows the day a key was issued (which can often be deduced from a message date or certificate expiration date), it is an easy matter to generate all possible seeds for that day.

The `SecureRandom` class generates random numbers that are far more secure than those produced by the `Random` class. You still need to provide a seed to start the number sequence at a random spot. The best method for doing this is to obtain random input from a hardware device such as a white-noise generator. Another reasonable source for random input is to ask the user to type away aimlessly on the keyboard, with each keystroke contributing only one or two bits to the random seed. Once you gather such random bits in an array of bytes, pass it to the `setSeed` method:

[Click here to view code image](#)

```
var random = new SecureRandom();
var b = new byte[20];
// fill with truly random bits
random.setSeed(b);
```

If you don't seed the random number generator, it will compute its own 20-byte seed by launching threads, putting them to sleep, and measuring the exact time when they are awakened.



Note

This algorithm is *not* known to be safe. In the past, algorithms that relied on the timing of some components of the computer, such as hard disk access time, were shown not to be completely random.

The sample program at the end of this section puts the AES cipher to work (see [Listing 10.12](#)). The `crypt` utility method in [Listing 10.13](#) will be reused in other examples. To use the program, you first need to generate a secret key. Run

[Click here to view code image](#)

```
java aes.AESTest -genkey secret.key
```

The secret key is saved in the file `secret.key`.

Now you can encrypt with the command

[Click here to view code image](#)

```
java aes.AESTest -encrypt plaintextFile encryptedFile
secret.key
```

Decrypt with the command

[Click here to view code image](#)

```
java aes.AESTest -decrypt encryptedFile decryptedFile  
secret.key
```

The program is straightforward. The `-genkey` option produces a new secret key and serializes it in the given file. That operation takes a long time because the initialization of the secure random generator is time-consuming. The `-encrypt` and `-decrypt` options both call into the same `crypt` method that calls the `update` and `doFinal` methods of the cipher. Note how the `update` method is called so long as the input blocks have the full length, and the `doFinal` method is either called with a partial input block (which is then padded) or with no additional data (to generate one pad block).

Listing 10.12 aes/AESTest.java

[Click here to view code image](#)

```
1 package aes;  
2  
3 import java.io.*;  
4 import java.security.*;  
5 import javax.crypto.*;  
6  
7 /**  
8  * This program tests the AES cipher. Usage:<br>  
9  * java aes.AESTest -genkey keyfile<br>  
10 * java aes.AESTest -encrypt plaintext encrypted keyfile<br>  
11 * java aes.AESTest -decrypt encrypted decrypted keyfile<br>  
12 * @author Cay Horstmann  
13 * @version 1.02 2018-05-01  
14 */  
15 public class AESTest  
16 {  
17     public static void main(String[] args)  
18         throws IOException, GeneralSecurityException,  
ClassNotFoundException  
19     {
```

```

20         if (args[0].equals("-genkey"))
21     {
22         KeyGenerator keygen =
23             KeyGenerator.getInstance("AES");
24         var random = new SecureRandom();
25         keygen.init(random);
26         SecretKey key = keygen.generateKey();
27         try (var out = new ObjectOutputStream(new
28             FileOutputStream(args[1])))
29         {
30             out.writeObject(key);
31         }
32     }
33     else
34     {
35         int mode;
36         if (args[0].equals("-encrypt")) mode =
37             Cipher.ENCRYPT_MODE;
38         else mode = Cipher.DECRYPT_MODE;
39
40         try (var keyIn = new ObjectInputStream(new
41             FileInputStream(args[3]));
42             var in = new FileInputStream(args[1]));
43             var out = new FileOutputStream(args[2]))
44         {
45             var key = (Key) keyIn.readObject();
46             Cipher cipher = Cipher.getInstance("AES");
47             cipher.init(mode, key);
48             Util.crypt(in, out, cipher);
49         }
50     }
51 }

```

Listing 10.13 aes/Util.java

[Click here to view code image](#)

```
1 package aes;
2
3 import java.io.*;
4 import java.security.*;
5 import javax.crypto.*;
6
7 public class Util
8 {
9     /**
10      * Uses a cipher to transform the bytes in an input stream
11     * and sends the transformed bytes
12     * to an output stream.
13     * @param in the input stream
14     * @param out the output stream
15     * @param cipher the cipher that transforms the bytes
16     */
17     public static void crypt(InputStream in, OutputStream out,
18     Cipher cipher)
19         throws IOException, GeneralSecurityException
20     {
21         int blockSize = cipher.getBlockSize();
22         int outputSize = cipher.getOutputSize(blockSize);
23         var inBytes = new byte[blockSize];
24         var outBytes = new byte[outputSize];
25
26         int inLength = 0;
27         boolean done = false;
28         while (!done)
29         {
30             inLength = in.read(inBytes);
31             if (inLength == blockSize)
32             {
33                 int outLength = cipher.update(inBytes, 0,
34                 blockSize, outBytes);
35                 out.write(outBytes, 0, outLength);
36             }
37             else done = true;
38         }
39     }
40 }
```

```
36         if (inLength > 0) outBytes = cipher.doFinal(inBytes, 0,  
inLength);  
37         else outBytes = cipher.doFinal();  
38         out.write(outBytes);  
39     }  
40 }
```

javax.crypto.Cipher 1.4

- static Cipher getInstance(String algorithmName)
- static Cipher getInstance(String algorithmName, String providerName)

return a Cipher object that implements the specified algorithm. Throw a NoSuchAlgorithmException if the algorithm is not provided.

- int getBlockSize()

returns the size (in bytes) of a cipher block, or 0 if the cipher is not a block cipher.

- int getOutputSize(int inputLength)

returns the size of an output buffer that is needed if the next input has the given number of bytes. This method takes into account any buffered bytes in the cipher object.

- void init(int mode, Key key)

initializes the cipher algorithm object. The mode is one of ENCRYPT_MODE, DECRYPT_MODE, WRAP_MODE, or UNWRAP_MODE.

- byte[] update(byte[] in)

- `byte[] update(byte[] in, int offset, int length)`
- `int update(byte[] in, int offset, int length, byte[] out)`

transform one block of input data. The first two methods return the output. The third method returns the number of bytes placed into `out`.

- `byte[] doFinal()`
- `byte[] doFinal(byte[] in)`
- `byte[] doFinal(byte[] in, int offset, int length)`
- `int doFinal(byte[] in, int offset, int length, byte[] out)`

transform the last block of input data and flush the buffer of this algorithm object. The first three methods return the output. The fourth method returns the number of bytes placed into `out`.

javax.crypto.KeyGenerator 1.4

- `static KeyGenerator getInstance(String algorithmName)`

returns a `KeyGenerator` object that implements the specified algorithm. Throws a `NoSuchAlgorithmException` if the algorithm is not provided.

- `void init(SecureRandom random)`
- `void init(int keySize, SecureRandom random)`

initialize the key generator.

- `SecretKey generateKey()`

generates a new key.

javax.crypto.spec.SecretKeySpec 1.4

- `SecretKeySpec(byte[] key, String algorithmName)`

constructs a key specification.

10.4.3 Cipher Streams

The JCE library provides a convenient set of stream classes that automatically encrypt or decrypt stream data. For example, here is how you can encrypt data to a file:

[Click here to view code image](#)

```
Cipher cipher = . . .;
cipher.init(Cipher.ENCRYPT_MODE, key);
var out = new CipherOutputStream(new
FileOutputStream(outputFileName), cipher);

var bytes = new byte[BLOCKSIZE];
int inLength = getData(bytes); // get data from data source
while (inLength != -1)
{
    out.write(bytes, 0, inLength);
    inLength = getData(bytes); // get more data from data source
}
out.flush();
```

Similarly, you can use a `CipherInputStream` to read and decrypt data from a file:

[Click here to view code image](#)

```
Cipher cipher = . . .;
cipher.init(Cipher.DECRYPT_MODE, key);
var in = new CipherInputStream(new
FileInputStream(inputFileName), cipher);
var bytes = new byte[BLOCKSIZE];
int inLength = in.read(bytes);
while (inLength != -1)
{
    putData(bytes, inLength); // put data to destination
    inLength = in.read(bytes);
}
```

The cipher stream classes transparently handle the calls to update and doFinal, which is clearly a convenience.

javax.crypto.CipherInputStream 1.4

- `CipherInputStream(InputStream in, Cipher cipher)`
constructs an input stream that reads data from in and decrypts or encrypts them by using the given cipher.
- `int read()`
- `int read(byte[] b, int off, int len)`
read data from the input stream, which is automatically decrypted or encrypted.

javax.crypto.CipherOutputStream 1.4

- `CipherOutputStream(OutputStream out, Cipher cipher)`
 constructs an output stream that writes data to `out` and encrypts or decrypts them using the given cipher.
- `void write(int ch)`
- `void write(byte[] b, int off, int len)`
 write data to the output stream, which is automatically encrypted or decrypted.
- `void flush()`
 flushes the cipher buffer and carries out padding if necessary.

10.4.4 Public Key Ciphers

The AES cipher that you have seen in the preceding section is a *symmetric* cipher. The same key is used for both encryption and decryption. The Achilles heel of symmetric ciphers is key distribution. If Alice sends Bob an encrypted message, Bob needs the same key that Alice used. If Alice changes the key, she needs to send Bob both the message and, through a secure channel, the new key. But perhaps she has no secure channel to Bob—which is why she encrypts her messages to him in the first place.

Public key cryptography solves that problem. In a public key cipher, Bob has a key pair consisting of a public key and a matching private key. Bob can publish the public key anywhere, but he must closely guard the private key. Alice simply uses the public key to encrypt her messages to Bob.

Actually, it's not quite that simple. All known public key algorithms are *much* slower than symmetric key algorithms such as DES or AES. It would not be practical to use a public key algorithm to encrypt large amounts of information. However, that problem can easily be overcome by combining a public key cipher with a fast symmetric cipher, like this:

1. Alice generates a random symmetric encryption key. She uses it to encrypt her plaintext.
2. Alice encrypts the symmetric key with Bob's public key.
3. Alice sends Bob both the encrypted symmetric key and the encrypted plaintext.
4. Bob uses his private key to decrypt the symmetric key.
5. Bob uses the decrypted symmetric key to decrypt the message.

Nobody but Bob can decrypt the symmetric key because only Bob has the private key for decryption. Thus, the expensive public key encryption is only applied to a small amount of key data.

The most commonly used public key algorithm is the RSA algorithm invented by Rivest, Shamir, and Adleman. Until October 2000, the algorithm was protected by a patent assigned to RSA Security, Inc. Licenses were not cheap—typically a 3% royalty, with a minimum payment of \$50,000 per year. Now the algorithm is in the public domain.

To use the RSA algorithm, you need a public/private key pair. Use a `KeyPairGenerator` like this:

[Click here to view code image](#)

```
KeyPairGenerator pairgen = KeyPairGenerator.getInstance("RSA");
var random = new SecureRandom();
pairgen.initialize(KEYSIZE, random);
KeyPair keyPair = pairgen.generateKeyPair();

Key publicKey = keyPair.getPublic();
Key privateKey = keyPair.getPrivate();
```

The program in [Listing 10.14](#) has three options. The `-genkey` option produces a key pair. The `-encrypt` option generates an AES key and wraps it with the public key.

[Click here to view code image](#)

```
Key key = . . .; // an AES key
Key publicKey = . . .; // a public RSA key
Cipher cipher = Cipher.getInstance("RSA");
cipher.init(Cipher.WRAP_MODE, publicKey);
byte[] wrappedKey = cipher.wrap(key);
```

It then produces a file that contains

- The length of the wrapped key
- The wrapped key bytes
- The plaintext encrypted with the AES key

The `-decrypt` option decrypts such a file. To try the program, first generate the RSA keys:

[Click here to view code image](#)

```
java rsa.RSATest -genkey public.key private.key
```

Then encrypt a file:

[Click here to view code image](#)

```
java rsa.RSATest -encrypt plaintextFile encryptedFile
public.key
```

Finally, decrypt it and verify that the decrypted file matches the plaintext:

[Click here to view code image](#)

```
java rsa.RSATest -decrypt encryptedFile decryptedFile
private.key
```

Listing 10.14 rsa/RSATest.java

[Click here to view code image](#)

```
1 package rsa;
2
```

```
3 import java.io.*;
4 import java.security.*;
5 import javax.crypto.*;
6
7 /**
8  * This program tests the RSA cipher. Usage:<br>
9  * java rsa.RSATest -genkey public private<br>
10 * java rsa.RSATest -encrypt plaintext encrypted public<br>
11 * java rsa.RSATest -decrypt encrypted decrypted private<br>
12 * @author Cay Horstmann
13 * @version 1.02 2018-05-01
14 */
15 public class RSATest
16 {
17     private static final int KEYSIZE = 512;
18
19     public static void main(String[] args)
20         throws IOException, GeneralSecurityException,
21     ClassNotFoundException
22     {
23         if (args[0].equals("-genkey"))
24         {
25             KeyPairGenerator pairgen =
26             KeyPairGenerator.getInstance("RSA");
27             var random = new SecureRandom();
28             pairgen.initialize(KEYSIZE, random);
29             KeyPair keyPair = pairgen.generateKeyPair();
30             try (var out = new ObjectOutputStream(new
31             FileOutputStream(args[1])))
32             {
33                 out.writeObject(keyPair.getPublic());
34             }
35             try (var out = new ObjectOutputStream(new
36             FileOutputStream(args[2])))
37             {
38                 out.writeObject(keyPair.getPrivate());
39             }
40         }
41     }
42 }
```

```
37         else if (args[0].equals("-encrypt"))
38     {
39         KeyGenerator keygen =
40             KeyGenerator.getInstance("AES");
41         var random = new SecureRandom();
42         keygen.init(random);
43         SecretKey key = keygen.generateKey();
44
45         // wrap with RSA public key
46         try (var keyIn = new ObjectInputStream(new
FileInputStream(args[3])));
47             var out = new DataOutputStream(new
FileOutputStream(args[2]));
48             var in = new FileInputStream(args[1]) )
49         {
50             var publicKey = (Key) keyIn.readObject();
51             Cipher cipher = Cipher.getInstance("RSA");
52             cipher.init(Cipher.WRAP_MODE, publicKey);
53             byte[] wrappedKey = cipher.wrap(key);
54             out.writeInt(wrappedKey.length);
55             out.write(wrappedKey);
56
57             cipher = Cipher.getInstance("AES");
58             cipher.init(Cipher.ENCRYPT_MODE, key);
59             Util.crypt(in, out, cipher);
60         }
61     else
62     {
63         try (var in = new DataInputStream(new
FileInputStream(args[1]));
64             var keyIn = new ObjectInputStream(new
FileInputStream(args[3]));
65             var out = new FileOutputStream(args[2])) )
66         {
67             int length = in.readInt();
68             var wrappedKey = new byte[length];
69             in.read(wrappedKey, 0, length);
```

```
70
71         // unwrap with RSA private key
72         var privateKey = (Key) keyIn.readObject();
73
74         Cipher cipher = Cipher.getInstance("RSA");
75         cipher.init(Cipher.UNWRAP_MODE, privateKey);
76         Key key = cipher.unwrap(wrappedKey, "AES",
77             Cipher.SECRET_KEY);
78
79         cipher = Cipher.getInstance("AES");
80         cipher.init(Cipher.DECRYPT_MODE, key);
81
82         Util.crypt(in, out, cipher);
83     }
84 }
85 }
```

In this chapter, you had a glimpse at class loaders, and you saw the services for authentication and encryption that the Java library provides. Along the way, you perhaps shed a tear that the classic Java security architecture, based on a security manager and code signing, is now a distant memory.

In the next chapter, we will delve into advanced Swing and graphics programming.

Chapter 11. Advanced Swing and Graphics

In this chapter

- [11.1 Tables](#)
- [11.2 Trees](#)
- [11.3 Advanced AWT](#)
- [11.4 Raster Images](#)
- [11.5 Printing](#)

In this chapter, we continue our discussion of the Swing user interface toolkit and AWT graphics from Volume I. We focus on techniques that are applicable to both client-side user interfaces and server-side generation of graphics and images. Swing has sophisticated components for rendering tables and trees. With the 2D graphics API, you can produce vector art of arbitrary complexity. The ImageIO API lets you manipulate raster images. Finally, you can use the printing API to generate printouts and PostScript files.

11.1 Tables

The `JTable` component displays a two-dimensional grid of objects. Tables are common in user interfaces, and the Swing team has put a lot of effort into the table control. Tables are inherently complex, but—perhaps more


successfully than other Swing classes—the `JTable` component hides much of that complexity. You can produce fully functional tables with rich behavior by writing a few lines of code. You can also write more code and customize the display and behavior for your specific applications.

In the following sections, I'll explain how to make simple tables, how the user interacts with them, and how to make some of the most common adjustments. As with the other complex Swing controls, it is impossible to cover all aspects in complete detail. For more information, look in *Graphic Java™, Third Edition*, by David M. Geary (Prentice Hall, 1999), or *Core Swing* by Kim Topley (Prentice Hall, 1999).

11.1.1 A Simple Table

A `JTable` does not store its own data but obtains them from a *table model*. The `JTable` class has a constructor that wraps a two-dimensional array of objects into a default model. That is the strategy that we use in our first example; later in this chapter, we will turn to table models.

Figure 11.1 shows a typical table, describing the properties of the planets of the solar system. (A planet is *gaseous* if it consists mostly of hydrogen and helium. You should take the “Color” entries with a grain of salt—that column was added because it will be useful in later code examples.)



The screenshot shows a Java application window titled "TableTest". The window contains a `JTable` displaying data about the planets of the solar system. The table has five columns: "Planet", "Radius", "Moons", "Gaseous", and "Color". The data rows are as follows:

| Planet | Radius | Moons | Gaseous | Color |
|---------|---------|-------|---------|---------------|
| Mercury | 2440.0 | 0 | false | java.awt.C... |
| Venus | 6052.0 | 0 | false | java.awt.C... |
| Earth | 6378.0 | 1 | false | java.awt.C... |
| Mars | 3397.0 | 2 | false | java.awt.C... |
| Jupiter | 71492.0 | 16 | true | java.awt.C... |
| Saturn | 60268.0 | 18 | true | java.awt.C... |
| Uranus | 25559.0 | 17 | true | java.awt.C... |
| Neptune | 24766.0 | 8 | true | java.awt.C... |

At the bottom of the window, there is a "Print" button.

Figure 11.1 A simple table

As you can see from the code in [Listing 11.1](#), the data of the table is stored as a two-dimensional array of `Object` values:

[Click here to view code image](#)

```
Object[][] cells =  
{  
    { "Mercury", 2440.0, 0, false, Color.YELLOW },  
    { "Venus", 6052.0, 0, false, Color.YELLOW },  
    . . .  
}
```



Note

Here, we take advantage of autoboxing. The entries in the second, third, and fourth columns are automatically converted into objects of type `Double`, `Integer`, and `Boolean`.

The table simply invokes the `toString` method on each object to display it. That's why the colors show up as `java.awt.Color[r=. . . , g=. . . , b=. . .]`.

Supply the column names in a separate array of strings:

[Click here to view code image](#)

```
String[] columnNames = { "Planet", "Radius", "Moons",  
    "Gaseous", "Color" };
```

Then, construct a table from the cell and column name arrays:

[Click here to view code image](#)

```
var table = new JTable(cells, columnNames);
```

You can add scroll bars in the usual way—by wrapping the table in a `JScrollPane`:

[Click here to view code image](#)

```
var pane = new JScrollPane(table);
```

When you scroll the table, the table header doesn't scroll out of view.

Next, click on one of the column headers and drag it to the left or right. See how the entire column becomes detached (see [Figure 11.2](#)). You can drop it in a different location. This rearranges the columns *in the view only*. The data model is not affected.

| Planet | Radius | Moons | Gaseous | Color |
|---------|---------|-------|---------|---------------|
| Mercury | 2440.0 | 0 | false | java.awt.C... |
| Venus | 6052.0 | 0 | false | java.awt.C... |
| Earth | 6378.0 | 1 | false | java.awt.C... |
| Mars | 3397.0 | 2 | false | java.awt.C... |
| Jupiter | 71492.0 | 16 | true | java.awt.C... |
| Saturn | 60268.0 | 18 | true | java.awt.C... |
| Uranus | 25559.0 | 17 | true | java.awt.C... |
| Neptune | 24766.0 | 8 | true | java.awt.C... |

Figure 11.2 Moving a column

To *resize* columns, simply place the cursor between two columns until the cursor shape changes to an arrow. Then, drag the column boundary to the desired place (see [Figure 11.3](#)).

| Planet | Radius | Moons | Gas↔ | Color |
|---------|---------|-------|-------|----------------------|
| Mercury | 2440.0 | 0 | false | java.awt.Color[r=... |
| Venus | 6052.0 | 0 | false | java.awt.Color[r=... |
| Earth | 6378.0 | 1 | false | java.awt.Color[r=... |
| Mars | 3397.0 | 2 | false | java.awt.Color[r=... |
| Jupiter | 71492.0 | 16 | true | java.awt.Color[r=... |
| Saturn | 60268.0 | 18 | true | java.awt.Color[r=... |
| Uranus | 25559.0 | 17 | true | java.awt.Color[r=... |
| Neptune | 24766.0 | 8 | true | java.awt.Color[r=... |

Figure 11.3 Resizing columns

Users can select rows by clicking anywhere in a row. The selected rows are highlighted; you will see later how to get selection events. Users can also edit the table entries by clicking on a cell and typing into it. However, in this code example, the edits do not change the underlying data. In your programs, you should either make cells uneditable or handle cell editing events and update your model. We will discuss those topics later in this section.

Finally, click on a column header. The rows are automatically sorted. Click again, and the sort order is reversed. This behavior is activated by the call

[Click here to view code image](#)

```
table.setAutoCreateRowSorter(true);
```

You can print a table with the call

```
table.print();
```



Caution

If you don't wrap a table into a scroll pane, you need to explicitly add the header:

[Click here to view code image](#)

```
add(table.getTableHeader(), BorderLayout.NORTH);
```

Listing 11.1 table/TableTest.java

[Click here to view code image](#)

```
1 package table;
2
3 import java.awt.*;
4 import java.awt.print.*;
```

```
5
6 import javax.swing.*;
7
8 /**
9  * This program demonstrates how to show a simple table.
10 * @version 1.14 2018-05-01
11 * @author Cay Horstmann
12 */
13 public class TableTest
14 {
15     public static void main(String[] args)
16     {
17         EventQueue.invokeLater(() ->
18         {
19             var frame = new PlanetTableFrame();
20             frame.setTitle("TableTest");
21
22             frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
23             frame.setVisible(true);
24         });
25     }
26
27 /**
28  * This frame contains a table of planet data.
29 */
30 class PlanetTableFrame extends JFrame
31 {
32     private String[] columnNames = { "Planet", "Radius",
33                                     "Moons", "Gaseous", "Color" };
34     private Object[][] cells =
35     {
36         { "Mercury", 2440.0, 0, false, Color.YELLOW },
37         { "Venus", 6052.0, 0, false, Color.YELLOW },
38         { "Earth", 6378.0, 1, false, Color.BLUE },
39         { "Mars", 3397.0, 2, false, Color.RED },
40         { "Jupiter", 71492.0, 16, true, Color.ORANGE },
41         { "Saturn", 60268.0, 18, true, Color.ORANGE },
```

```

41         { "Uranus", 25559.0, 17, true, Color.BLUE },
42         { "Neptune", 24766.0, 8, true, Color.BLUE },
43         { "Pluto", 1137.0, 1, false, Color.BLACK }
44     };
45
46     public PlanetTableFrame()
47     {
48         var table = new JTable(cells, columnNames);
49         table.setAutoCreateRowSorter(true);
50         add(new JScrollPane(table), BorderLayout.CENTER);
51         var printButton = new JButton("Print");
52         printButton.addActionListener(event ->
53         {
54             try { table.print(); }
55             catch (SecurityException | PrinterException e) {
56                 e.printStackTrace();
57             }
58         });
59         var buttonPanel = new JPanel();
60         buttonPanel.add(printButton);
61         add(buttonPanel, BorderLayout.SOUTH);
62         pack();
63     }
64 }
```

javax.swing.JTable 1.2

- **JTable(Object[][] entries, Object[] columnNames)**
constructs a table with a default table model.
- **void print() 5.0**
displays a print dialog box and prints the table.
- **boolean getAutoCreateRowSorter() 6**

- void setAutoCreateRowSorter(boolean newValue) **6**

get or set the `autoCreateRowSorter` property. The default is false. When set, a default row sorter is automatically set whenever the model changes.

- boolean getFillsViewportHeight() **6**
- void setFillsViewportHeight(boolean newValue) **6**

get or set the `fillsViewportHeight` property. The default is false. When set, the table always fills the enclosing viewport.

11.1.2 Table Models

In the preceding example, the table data were stored in a two-dimensional array. However, you should generally not use that strategy in your own code. Instead of dumping data into an array to display it as a table, consider implementing your own table model.

Table models are particularly simple to implement because you can take advantage of the `AbstractTableModel` class that implements most of the required methods. You only need to supply three methods:

[Click here to view code image](#)

```
public int getRowCount();
public int getColumnCount();
public Object getValueAt(int row, int column);
```

There are many ways of implementing the `getValueAt` method. For example, if you want to display the contents of a `RowSet` that contains the result of a database query, simply provide this method:


[Click here to view code image](#)

```

public Object getValueAt(int r, int c)
{
    try
    {
        rowSet.absolute(r + 1);
        return rowSet.getObject(c + 1);
    }
    catch (SQLException e)
    {
        e.printStackTrace();
        return null;
    }
}

```

Our sample program is even simpler. We construct a table that shows some computed values—namely, the growth of an investment under different interest rate scenarios (see [Figure 11.4](#)).



The screenshot shows a Java Swing application window titled "InvestmentTable". The window contains a table with 16 rows and 6 columns. The columns represent interest rates: 5%, 6%, 7%, 8%, 9%, and 10%. The first row contains the initial investment amounts for each rate. Subsequent rows show the growth of the investment over time, with the last column showing the final value after 20 years.

| | 5% | 6% | 7% | 8% | 9% | 10% |
|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| 100000.00 | 100000.00 | 100000.00 | 100000.00 | 100000.00 | 100000.00 | 100000.00 |
| 105000.00 | 106000.00 | 107000.00 | 108000.00 | 109000.00 | 110000.00 | 110000.00 |
| 110250.00 | 112360.00 | 114490.00 | 116640.00 | 118810.00 | 121000.00 | 121000.00 |
| 115762.50 | 119101.60 | 122504.30 | 125971.20 | 129502.90 | 133100.00 | 133100.00 |
| 121550.63 | 126247.70 | 131079.60 | 136048.90 | 141158.16 | 146410.00 | 146410.00 |
| 127628.16 | 133822.56 | 140255.17 | 146932.81 | 153862.40 | 161051.00 | 161051.00 |
| 134009.56 | 141851.91 | 150073.04 | 158687.43 | 167710.01 | 177156.10 | 177156.10 |
| 140710.04 | 150363.03 | 160578.15 | 171382.43 | 182803.91 | 194871.71 | 194871.71 |
| 147745.54 | 159384.81 | 171818.62 | 185093.02 | 199256.26 | 214358.88 | 214358.88 |
| 155132.82 | 168947.90 | 183845.92 | 199900.46 | 217189.33 | 235794.77 | 235794.77 |
| 162889.46 | 179084.77 | 196715.14 | 215892.50 | 236736.37 | 259374.25 | 259374.25 |
| 171033.94 | 189829.86 | 210485.20 | 233163.90 | 258042.64 | 285311.67 | 285311.67 |
| 179585.63 | 201219.65 | 225219.16 | 251817.01 | 281266.48 | 313842.84 | 313842.84 |
| 188564.91 | 213292.83 | 240984.50 | 271962.37 | 306580.46 | 345227.12 | 345227.12 |
| 197993.16 | 226090.40 | 257853.42 | 293719.36 | 334172.70 | 379749.83 | 379749.83 |
| 207892.82 | 239655.82 | 275903.15 | 317216.91 | 364248.25 | 417724.82 | 417724.82 |

Figure 11.4 Growth of an investment

The `getValueAt` method computes the appropriate value and formats it:

[Click here to view code image](#)

```
public Object getValueAt(int r, int c)
{
    double rate = (c + minRate) / 100.0;
    int nperiods = r;
    double futureBalance = INITIAL_BALANCE * Math.pow(1 + rate,
nperiods);
    return "%,.2f".formatted(futureBalance);
}
```

The `getRowCount` and `getColumnCount` methods simply return the number of rows and columns:

[Click here to view code image](#)

```
public int getRowCount() { return years; }
public int getColumnCount() { return maxRate - minRate + 1; }
```

If you don't supply column names, the `getColumnName` method of the `AbstractTableModel` names the columns A, B, C, and so on. To change the default column names, override the `getColumnName` method. In this example, we simply label each column with the interest rate.

[Click here to view code image](#)

```
public String getColumnName(int c) { return (c + minRate) +
"%"; }
```

You can find the complete source code in [Listing 11.2](#).

Listing 11.2 `tableModel/InvestmentTable.java`

[Click here to view code image](#)

```
1 package tableModel;
2
3 import java.awt.*;
4
5 import javax.swing.*;
```

```
6 import javax.swing.table.*;
7
8 /**
9  * This program shows how to build a table from a table
model.
10 * @version 1.05 2021-09-09
11 * @author Cay Horstmann
12 */
13 public class InvestmentTable
14 {
15     public static void main(String[] args)
16     {
17         EventQueue.invokeLater(() ->
18         {
19             var frame = new InvestmentTableFrame();
20             frame.setTitle("InvestmentTable");
21
22             frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
23             frame.setVisible(true);
24         });
25     }
26
27 /**
28  * This frame contains the investment table.
29 */
30 class InvestmentTableFrame extends JFrame
31 {
32     public InvestmentTableFrame()
33     {
34         var model = new InvestmentTableModel(30, 5, 10);
35         var table = new JTable(model);
36         add(new JScrollPane(table));
37         pack();
38     }
39 }
40
```

[Click here to view code image](#)

```
41  /**
42   * This table model computes the cell entries each time they
43   * are requested. The table contents
44   * shows the growth of an investment for a number of years
45   * under different interest rates.
46  */
47 class InvestmentTableModel extends AbstractTableModel
48 {
49     private static double INITIAL_BALANCE = 100000.0;
50
51     private int years;
52     private int minRate;
53     private int maxRate;
54
55     /**
56      * Constructs an investment table model.
57      * @param y the number of years
58      * @param r1 the lowest interest rate to tabulate
59      * @param r2 the highest interest rate to tabulate
60     */
61     public InvestmentTableModel(int y, int r1, int r2)
62     {
63         years = y;
64         minRate = r1;
65         maxRate = r2;
66     }
67
68     public int getRowCount()
69     {
70         return years;
71     }
72
73     public int getColumnCount()
74     {
75         return maxRate - minRate + 1;
76     }
```

```
75
76     public Object getValueAt(int r, int c)
77     {
78         double rate = (c + minRate) / 100.0;
79         int nperiods = r;
80         double futureBalance = INITIAL_BALANCE * Math.pow(1 +
81             rate, nperiods);
82         return "%,.2f".formatted(futureBalance);
83     }
84
85     public String getColumnName(int c)
86     {
87         return (c + minRate) + "%";
88     }

```

javax.swing.table.TableModel 1.2

- `int getRowCount()`
get the number of rows and columns in the table model.
- `Object getValueAt(int row, int column)`
gets the value at the given row and column.
- `void setValueAt(Object newValue, int row, int column)`
sets a new value at the given row and column.
- `boolean isCellEditable(int row, int column)`
returns `true` if the cell at the given row and column is editable.
- `String getColumnName(int column)`

gets the column title.

11.1.3 Working with Rows and Columns

In this subsection, you will see how to manipulate the rows and columns in a table. As you read through this material, keep in mind that a Swing table is quite asymmetric—the operations that you can carry out on rows and columns are different. The table component was optimized to display rows of information with the same structure, such as the result of a database query, not an arbitrary two-dimensional grid of objects. You will see this asymmetry throughout this subsection.

11.1.3.1 Column Classes

In the next example, we again display our planet data, but this time we want to give the table more information about the column types. This is achieved by defining the method

[Click here to view code image](#)

```
Class<?> getColumnClass(int columnIndex)
```

of the table model to return the class that describes the column type.

The `JTable` class uses this information to pick an appropriate renderer for the class. [Table 11.1](#) shows the default rendering actions.

Table 11.1 Default Rendering Actions

| Type | Rendered As |
|---------|-------------|
| Boolean | Checkbox |
| Icon | Image |
| Object | String |

You can see the checkboxes and images in [Figure 11.5](#). (Thanks to Jim Evins for providing the planet images!)

The screenshot shows a Java Swing application window titled "TableRowColumnTest". The window has a menu bar with "Selection" and "Edit" options. A context menu is open on the first row, with "Rows" checked, "Columns" unchecked, and "Cells" unchecked. The table has five columns: "Name", "Diameter", "Moons", "Gaseous", and "Color". The last column, "Image", contains small images of the planets. The data rows are:

| | | | | | |
|---------|--------|----|-------------------------------------|---------------------------------|--|
| Mercury | 3,052 | 0 | <input type="checkbox"/> | java.awt.Color[r=255,g=255,b=0] | |
| Earth | 6,378 | 1 | <input type="checkbox"/> | java.awt.Color[r=0,g=0,b=255] | |
| Mars | 3,397 | 2 | <input type="checkbox"/> | java.awt.Color[r=255,g=0,b=0] | |
| Jupiter | 71,492 | 16 | <input checked="" type="checkbox"/> | java.awt.Color[r=255,g=200,b=0] | |
| Saturn | 60,268 | 18 | <input checked="" type="checkbox"/> | java.awt.Color[r=255,g=200,b=0] | |

Figure 11.5 A table with planet data

To render other types, you can install a custom renderer—see [Section 11.1.4, “Cell Rendering and Editing,”](#) on p. 617.

11.1.3.2 Accessing Table Columns

The `JTable` class stores information about table columns in objects of type `TableColumn`. A `TableColumnModel` object manages the columns. ([Figure 11.6](#) shows the relationships among the most important

table classes.) If you don't want to insert or remove columns dynamically, you won't use the column model much. The most common use for the column model is simply to get a `TableColumn` object:




Figure 11.6 Relationship between table classes

[Click here to view code image](#)

```
int columnIndex = . . .;
TableColumn column =
table.getColumnModel().getColumn(columnIndex);
```

11.1.3.3 Resizing Columns

The `TableColumn` class gives you control over the resizing behavior of columns. You can set the preferred, minimum, and maximum width with the methods

[Click here to view code image](#)

```
void setPreferredWidth(int width)  
void setMinWidth(int width)  
void setMaxWidth(int width)
```

This information is used by the table component to lay out the columns.

Use the method

[Click here to view code image](#)

```
void setResizable(boolean resizable)
```

to control whether the user is allowed to resize the column.

You can programmatically resize a column with the method

```
void setWidth(int width)
```

When a column is resized, the default is to leave the total size of the table unchanged. Of course, the width increase or decrease of the resized column must then be distributed over other columns. The default behavior is to change the size of all columns to the right of the resized column. That's a good default because it allows a user to adjust all columns to a desired width, moving from left to right.

You can set another behavior from [Table 11.2](#) by using the method

Table 11.2 Resize Modes

| Mode | Behavior |
|------|----------|
| | |

| Mode | Behavior |
|--|--|
| AUTO_RESIZE
_OFF | Don't resize other columns; change the table width. |
| AUTO_RESIZE
_NEXT_COLUMN | Resize the next column only. |
| N | |
| AUTO_RESIZE
_SUBSEQUENT
_COLUMNS | Resize all subsequent columns equally; this is the default behavior. |
| AUTO_RESIZE
_LAST_COLUMN | Resize the last column only. |
| N | |
| AUTO_RESIZE
_ALL_COLUMN
S | Resize all columns in the table; this is not a good choice because it prevents the user from adjusting multiple columns to a desired size. |

[Click here to view code image](#)

```
void setAutoResizeMode(int mode)
```

of the `JTable` class.

11.1.3.4 Resizing Rows

Row heights are managed directly by the `JTable` class. If your cells are taller than the default, you may want to set the row height:

[Click here to view code image](#)

```
table.setRowHeight(height);
```

By default, all rows of the table have the same height. You can set the heights of individual rows with the call

[Click here to view code image](#)

```
table.setRowHeight(row, height);
```

The actual row height equals the row height set with these methods, reduced by the row margin. The default row margin is 1 pixel, but you can change it with the call

```
table.setRowMargin(margin);
```

11.1.3.5 Selecting Rows, Columns, and Cells

Depending on the selection mode, the user can select rows, columns, or individual cells in the table. By default, row selection is enabled. Clicking inside a cell selects the entire row (see [Figure 11.5](#) on p. [601](#)). Call

[Click here to view code image](#)

```
table.setRowSelectionAllowed(false);
```

to disable row selection.

When row selection is enabled, you can control whether the user is allowed to select a single row, a contiguous set of rows, or any set of rows. You need to retrieve the *selection model* and use its `setSelectionMode` method:

[Click here to view code image](#)

```
table.getSelectionModel().setSelectionMode(mode);
```

Here, `mode` is one of the three values:

[Click here to view code image](#)

```
ListSelectionModel.SINGLE_SELECTION  
ListSelectionModel.SINGLE_INTERVAL_SELECTION  
ListSelectionModel.MULTIPLE_INTERVAL_SELECTION
```

Column selection is disabled by default. You can turn it on with the call

[Click here to view code image](#)

```
table.setColumnSelectionAllowed(true);
```

Enabling both row and column selection is equivalent to enabling cell selection. The user then selects ranges of cells (see [Figure 11.7](#)). You can also enable that setting with the call

| Planet | Radius | Moons | Gaseous | Color | Image |
|---------|--------|-------|-------------------------------------|---------------------------------|-------|
| Mars | 3,397 | 2 | <input type="checkbox"/> | java.awt.Color[r=255,g=0,b=0] | |
| Jupiter | 71,492 | 16 | <input checked="" type="checkbox"/> | java.awt.Color[r=255,g=200,b=0] | |
| Saturn | 60,268 | 18 | <input checked="" type="checkbox"/> | java.awt.Color[r=255,g=200,b=0] | |
| Uranus | 25,559 | 17 | <input checked="" type="checkbox"/> | java.awt.Color[r=0,g=0,b=255] | |
| | | | | | |

Figure 11.7 Selecting a range of cells

[Click here to view code image](#)

```
table.setCellSelectionEnabled(true);
```

Run the program in [Listing 11.3](#) to watch cell selection in action. Enable row, column, or cell selection in the Selection menu and watch how the selection behavior changes.

You can find out which rows and columns are selected by calling the `getSelectedRows` and `getSelectedColumns` methods. Both return an `int[]` array of the indexes of the selected items. Note that the index values are those of the table view, not the underlying table model. Try selecting rows and columns, then drag columns to different places and sort the rows by clicking on column headers. Use the Print Selection menu item to see which rows and columns are reported as selected.

If you need to translate the table index values to table model index values, use the `JTable` methods `convertRowIndexToModel` and `convertColumnIndexToModel`.

11.1.3.6 Sorting Rows

As you have seen in our first table example, it is easy to add row sorting to a `JTable` simply by calling the `setAutoCreateRowSorter` method. However, to have finer-grained control over the sorting behavior, install a `TableRowSorter<M>` object into a `JTable` and customize it. The type parameter `M` denotes the table model; it needs to be a subtype of the `TableModel` interface.

[Click here to view code image](#)

```
var sorter = new TableRowSorter<TableModel>(model);
table.setRowSorter(sorter);
```

Some columns should not be sortable, such as the image column in our planet data. Turn sorting off by calling

[Click here to view code image](#)

```
sorter.setSortable(IMAGE_COLUMN, false);
```

You can install a custom comparator for each column. In our example, we will sort the colors in the Color column by preferring blue and green over

red. When you click on the Color column, you will see that the blue planets go to the bottom of the table. This is achieved with the following call:

[Click here to view code image](#)

```
sorter.setComparator(COLOR_COLUMN, new Comparator<Color>()
{
    public int compare(Color c1, Color c2)
    {
        int d = c1.getBlue() - c2.getBlue();
        if (d != 0) return d;
        d = c1.getGreen() - c2.getGreen();
        if (d != 0) return d;
        return c1.getRed() - c2.getRed();
    }
});
```

If you do not specify a comparator for a column, the sort order is determined as follows:

1. If the column class is `String`, use the default collator returned by `Collator.getInstance()`. It sorts strings in a way that is appropriate for the current locale. (See [Chapter 7](#) for more information about locales and collators.)
2. If the column class implements `Comparable`, use its `compareTo` method.
3. If a `TableStringConverter` has been set for the sorter, sort the strings returned by the converter's `toString` method with the default collator. If you want to use this approach, define a converter as follows:

[Click here to view code image](#)

```
sorter.setStringConverter(new TableStringConverter()
{
    public String toString(TableModel model, int row, int
column)
    {
        Object value = model.getValueAt(row, column);
        convert value to a string and return it
    }
});
```

```
    }  
});
```

4. Otherwise, call the `toString` method on the cell values and sort them with the default collator.

11.1.3.7 Filtering Rows

In addition to sorting rows, the `TableRowSorter` can also selectively hide rows—a process called *filtering*. To activate filtering, set a `RowFilter`. For example, to include all rows that contain at least one moon, call

[Click here to view code image](#)

```
sorter.setRowFilter(RowFilter.numberFilter(ComparisonType.NOT_E  
QUAL, 0, MOONS_COLUMN));
```

Here, we use a predefined number filter. To construct a number filter, supply

- The comparison type (one of `EQUAL`, `NOT_EQUAL`, `AFTER`, or `BEFORE`).
- An object of a subclass of `Number` (such as an `Integer` or `Double`). Only objects that have the same class as the given `Number` object are considered.
- Zero or more column index values. If no index values are supplied, all columns are searched.

The static `RowFilter.dateFilter` method constructs a date filter in the same way; you need to supply a `Date` object instead of the `Number` object.

Finally, the static `RowFilter.regexFilter` method constructs a filter that looks for strings matching a regular expression. For example,

[Click here to view code image](#)

```
sorter.setRowFilter(RowFilter.regexFilter(".*[^s]$",
PLANET_COLUMN));
```

only displays those planets whose name doesn't end with an "s". (See [Chapter 2](#) for more information on regular expressions.)

You can also combine filters with the `andFilter`, `orFilter`, and `notFilter` methods. To filter for planets not ending in an "s" with at least one moon, you can use this filter combination:

[Click here to view code image](#)

```
sorter.setRowFilter(RowFilter.andFilter(List.of(
    RowFilter.regexFilter(".*[^s]$",
    PLANET_COLUMN),
    RowFilter.numberFilter(ComparisonType.NOT_EQUAL,
    0,
    MOONS_COLUMN))));
```

To implement your own filter, provide a subclass of `RowFilter` and implement an `include` method to indicate which rows should be displayed. This is easy to do, but the glorious generality of the `RowFilter` class makes it a bit scary.

The `RowFilter<M, I>` class has two type parameters—the types for the model and for the row identifier. When dealing with tables, the model is always a subtype of `TableModel` and the identifier type is `Integer`. (At some point in the future, other components might also support row filtering. For example, to filter rows in a `JTree`, one might use a `RowFilter<TreeModel, TreePath>`.)

A row filter must implement the method

[Click here to view code image](#)

```
public boolean include(RowFilter.Entry<? extends M, ? extends
I> entry)
```

The `RowFilter.Entry` class supplies methods to obtain the model, the row identifier, and the value at a given index. Therefore, you can filter both by row identifier and by the contents of the row.

For example, this filter displays every other row:

[Click here to view code image](#)

```
var filter = new RowFilter<TableModel, Integer>()
{
    public boolean include(Entry<? extends TableModel, ?
extends Integer> entry)
    {
        return entry.getIdentifier() % 2 == 0;
    }
};
```

If you wanted to include only those planets with an even number of moons, you would instead test for

[Click here to view code image](#)

```
((Integer) entry.getValue(MOONS_COLUMN)) % 2 == 0
```

In our sample program, we allow the user to hide arbitrary rows. We store the hidden row indexes in a set. The row filter shows all rows whose indexes are not in that set.

The filtering mechanism wasn't designed for filters with criteria changing over time. In our sample program, we keep calling

```
sorter.setRowFilter(filter);
```

whenever the set of hidden rows changes. Setting a filter causes it to be applied immediately.

11.1.3.8 Hiding and Displaying Columns

As you saw in the preceding section, you can filter table rows by either their contents or their row identifier. Hiding table columns uses a completely different mechanism.

The `removeColumn` method of the `JTable` class removes a column from the table view. The column data are not actually removed from the model—they are just hidden from view. The `removeColumn` method takes a `TableColumn` argument. If you have the column number (for example, from a call to `getSelectedColumns`), you need to ask the table model for the actual table column object:

[Click here to view code image](#)

```
TableColumnModel columnModel = table.getColumnModel();  
TableColumn column = columnModel.getColumn(i);  
table.removeColumn(column);
```

If you remember the column, you can later add it back in:

[Click here to view code image](#)

```
table.addColumn(column);
```

This method adds the column to the end. If you want it to appear elsewhere, call the `moveColumn` method.

You can also add a new column that corresponds to a column index in the table model, by adding a new `TableColumn` object:

[Click here to view code image](#)

```
table.addColumn(new TableColumn(modelColumnIndex));
```

You can have multiple table columns that view the same column of the model.

The program in [Listing 11.3](#) demonstrates selection and filtering of rows and columns.

Listing 11.3 `tableRowColumn/PlanetTableFrame.java`

[Click here to view code image](#)

```
1 package TableRowColumn;
2
3 import java.awt.*;
4 import java.util.*;
5
6 import javax.swing.*;
7 import javax.swing.table.*;
8
9 /**
10  * This frame contains a table of planet data.
11 */
12 public class PlanetTableFrame extends JFrame
13 {
14     private static final int DEFAULT_WIDTH = 600;
15     private static final int DEFAULT_HEIGHT = 500;
16
17     public static final int COLOR_COLUMN = 4;
18     public static final int IMAGE_COLUMN = 5;
19
20     private JTable table;
21     private HashSet<Integer> removedRowIndices;
22     private ArrayList<TableColumn> removedColumns;
23     private JCheckBoxMenuItem rowsItem;
24     private JCheckBoxMenuItem columnsItem;
25     private JCheckBoxMenuItem cellsItem;
26
27     private String[] columnNames = { "Planet", "Radius",
28                                     "Moons", "Gaseous", "Color", "Image" };
29
30     private Object[][] cells =
31     {
32         { "Mercury", 2440.0, 0, false, Color.YELLOW,
33           new ImageIcon(getClass().getResource("Mercury.gif")) },
34         { "Venus", 6052.0, 0, false, Color.YELLOW,
35           new ImageIcon(getClass().getResource("Venus.gif")) },
36         { "Earth", 6378.0, 1, false, Color.BLUE,
```

```
36             new ImageIcon(getClass().getResource("Earth.gif")))
37     },
38     { "Mars", 3397.0, 2, false, Color.RED,
39       new ImageIcon(getClass().getResource("Mars.gif"))
40     },
41     { "Jupiter", 71492.0, 16, true, Color.ORANGE,
42       new
43       ImageIcon(getClass().getResource("Jupiter.gif")) },
44     { "Saturn", 60268.0, 18, true, Color.ORANGE,
45       new
46       ImageIcon(getClass().getResource("Saturn.gif")) },
47     { "Uranus", 25559.0, 17, true, Color.BLUE,
48       new
49       ImageIcon(getClass().getResource("Uranus.gif")) },
50     { "Neptune", 24766.0, 8, true, Color.BLUE,
51       new
52       ImageIcon(getClass().getResource("Neptune.gif")) },
53     { "Pluto", 1137.0, 1, false, Color.BLACK,
54       new ImageIcon(getClass().getResource("Pluto.gif"))
55   }
56   };
57
58   public PlanetTableFrame()
59   {
60     setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
61
62     var model = new DefaultTableModel(cells, columnNames)
63     {
64       public Class<?> getColumnClass(int c)
65       {
66         return cells[0][c].getClass();
67       }
68     };
69
70     table = new JTable(model);
71
72     table.setRowHeight(100);
73
74   }
75 }
```

```
table.getColumnModel().getColumn(COLOR_COLUMN).setMinWidth(250);
67
table.getColumnModel().getColumn(IMAGE_COLUMN).setMinWidth(100);
68
69     var sorter = new TableRowSorter<TableModel>(model);
70     table.setRowSorter(sorter);
71     sorter.setComparator(COLOR_COLUMN,
72         Comparator.comparing(Color::getBlue)
73             .thenComparing(Color::getGreen).thenComparing(Color::getRed));
74     sorter.setSortable(IMAGE_COLUMN, false);
75     add(new JScrollPane(table), BorderLayout.CENTER);
76
77     removedRowIndices = new HashSet<>();
78     removedColumns = new ArrayList<>();
79
80     var filter = new RowFilter<TableModel, Integer>()
81     {
82         public boolean include(Entry<? extends
83             TableModel, ? extends Integer> entry)
84         {
85             return
86                 !removedRowIndices.contains(entry.getIdentifier());
87         }
88     };
89
90     // create menu
91
92     var menuBar = new JMenuBar();
93     setJMenuBar(menuBar);
94
95     var selectionMenu = new JMenu("Selection");
96     menuBar.add(selectionMenu);
97
98     rowsItem = new JCheckBoxMenuItem("Rows");
99     columnsItem = new JCheckBoxMenuItem("Columns");
100    cellsItem = new JCheckBoxMenuItem("Cells");
```

```
99         rowsItem.setSelected(table.getRowSelectionAllowed());
100
101     columnsItem.setSelected(table.getColumnSelectionAllowed());
102
103     cellsItem.setSelected(table.getCellSelectionEnabled());
104
104     rowsItem.addActionListener(event ->
105     {
106         table.clearSelection();
107
108         table.setRowSelectionAllowed(rowsItem.isSelected());
109         updateCheckboxMenuItems();
110     });
110
111     selectionMenu.add(rowsItem);
112
112     columnsItem.addActionListener(event ->
113     {
114         table.clearSelection();
115
116         table.setColumnSelectionAllowed(columnsItem.isSelected());
117         updateCheckboxMenuItems();
118     });
117
118     selectionMenu.add(columnsItem);
119
119     cellsItem.addActionListener(event ->
120     {
121         table.clearSelection();
122
122     table.setCellSelectionEnabled(cellsItem.isSelected());
123         updateCheckboxMenuItems();
124     });
125
125     selectionMenu.add(cellsItem);
126
126
127     var tableMenu = new JMenu("Edit");
128     menuBar.add(tableMenu);
129
130     var hideColumnsItem = new JMenuItem("Hide Columns");
131     hideColumnsItem.addActionListener(event ->
```

```
132     {
133         int[] selected = table.getSelectedColumns();
134         TableColumnModel columnModel =
135             table.getColumnModel();
136         // remove columns from view, starting at the
137         // last
138         // index so that column numbers aren't affected
139         for (int i = selected.length - 1; i >= 0; i--) {
140             {
141                 TableColumn column =
142                     columnModel.getColumn(selected[i]);
143                     table.removeColumn(column);
144
145                     // store removed columns for "show columns"
146                     command
147                     removedColumns.add(column);
148             }
149         }
150         tableMenu.add(hideColumnsItem);
151
152         var showColumnsItem = new JMenuItem("Show Columns");
153         showColumnsItem.addActionListener(event ->
154             {
155                 // restore all removed columns
156                 for (TableColumn tc : removedColumns)
157                     table.addColumn(tc);
158                 removedColumns.clear();
159             });
160         tableMenu.add(showColumnsItem);
161
162         var hideRowsItem = new JMenuItem("Hide Rows");
163         hideRowsItem.addActionListener(event ->
164             {
165                 int[] selected = table.getSelectedRows();
166                 for (int i : selected)
```

```
166     removedRowIndices.add(table.convertRowIndexToModel(i));
167         sorter.setRowFilter(filter);
168     });
169     tableMenu.add(hideRowsItem);
170
171     var showRowsItem = new JMenuItem("Show Rows");
172     showRowsItem.addActionListener(event ->
173     {
174         removedRowIndices.clear();
175         sorter.setRowFilter(filter);
176     });
177     tableMenu.add(showRowsItem);
178
179     var printSelectionItem = new JMenuItem("Print
Selection");
180     printSelectionItem.addActionListener(event ->
181     {
182         int[] selected = table.getSelectedRows();
183         System.out.println("Selected rows: " +
Arrays.toString(selected));
184         selected = table.getSelectedColumns();
185         System.out.println("Selected columns: " +
Arrays.toString(selected));
186     });
187     tableMenu.add(printSelectionItem);
188 }
189
190     private void updateCheckboxMenuItems()
191     {
192         rowsItem.setSelected(table.getRowSelectionAllowed());
193
columnsItem.setSelected(table.getColumnSelectionAllowed());
194
cellsItem.setSelected(table.getCellSelectionEnabled());
195     }
196 }
```

javax.swing.table.TableModel 1.2

- `Class getColumnClass(int columnIndex)`
gets the class for the values in this column. This information is used for sorting and rendering.

javax.swing.JTable 1.2

- `TableColumnModel getColumnModel()`
gets the column model that describes the arrangement of the table columns.
- `void setAutoResizeMode(int mode)`
sets the mode for automatic resizing of table columns.

Pa m One of AUTO_RESIZE_OFF,
ra m AUTO_RESIZE_NEXT_COLUMN,
me o AUTO_RESIZE_SUBSEQUENT_COLUMNS,
ter d AUTO_RESIZE_LAST_COLUMN, and
s: e AUTO_RESIZE_ALL_COLUMNS

- `int getRowMargin()`
- `void setRowMargin(int margin)`
get or set the amount of empty space between cells in adjacent rows.
- `int getRowHeight()`
- `void setRowHeight(int height)`
get or set the default height of all rows of the table.

- `int getRowHeight(int row)`
- `void setRowHeight(int row, int height)`

get or set the height of the given row of the table.
- `ListSelectionModel getSelectionModel()`

returns the list selection model. You need that model to choose between row, column, and cell selection.
- `boolean getRowSelectionAllowed()`
- `void setRowSelectionAllowed(boolean b)`

get or set the `rowSelectionAllowed` property. If true, rows are selected when the user clicks on cells.
- `boolean getColumnSelectionAllowed()`
- `void setColumnSelectionAllowed(boolean b)`

get or set the `columnSelectionAllowed` property. If true, columns are selected when the user clicks on cells.
- `boolean getCellSelectionEnabled()`

returns true if both `rowSelectionAllowed` and `columnSelectionAllowed` are true.
- `void setCellSelectionEnabled(boolean b)`

sets both `rowSelectionAllowed` and `columnSelectionAllowed` to b.
- `void addColumn(TableColumn column)`

adds a column as the last column of the table view.
- `void moveColumn(int from, int to)`

moves the column whose table index is `from` so that its index becomes `to`. Only the view is affected.

- `void removeColumn(TableColumn column)`
removes the given column from the view.
- `int convertRowIndexToModel(int index) 6`
- `int convertColumnIndexToModel(int index)`
return the model index of the row or column with the given index.
This value is different from `index` when rows are sorted or
filtered, or when columns are moved or removed.
- `void setRowSorter(RowSorter<? extends TableModel> sorter)`
sets the row sorter.

javax.swing.table.TableColumnModel 1.2

- `TableColumn getColumn(int index)`
gets the table column object that describes the column with the
given view index.

javax.swing.table.TableColumn 1.2

- `TableColumn(int modelColumnIndex)`
constructs a table column for viewing the model column with the
given index.
- `void setPreferredWidth(int width)`
- `void setMinWidth(int width)`
- `void setMaxWidth(int width)`

set the preferred, minimum, and maximum width of this table column to width.

- `void setWidth(int width)`
sets the actual width of this column to width.
- `void setResizable(boolean b)`
If b is true, this column is resizable.

***javax.swing.ListSelectionModel* 1.2**

- `void setSelectionMode(int mode)`

Para ^m One of SINGLE_SELECTION,
mete ^o SINGLE_INTERVAL_SELECTION, and
rs: ^d MULTIPLE_INTERVAL_SELECTION
^e

***javax.swing.DefaultRowSorter<M, I>* 6**

- `void setComparator(int column, Comparator<?> comparator)`
sets the comparator to be used with the given column.
- `void setSortable(int column, boolean enabled)`
enables or disables sorting for the given column.
- `void setRowFilter(RowFilter<? super M, ? super I> filter)`

sets the row filter.

javax.swing.table.TableRowSorter<M extends TableModel> 6

- void setStringConverter(TableStringConverter stringConverter)

sets the string converter used for sorting and filtering.

javax.swing.table.TableStringConverter 6

- abstract String toString(TableModel model, int row, int column)
- converts the model value at the given location to a string; you can override this method.

javax.swing.RowFilter<M, I> 6

- boolean include(RowFilter.Entry<? extends M, ? extends I> entry)
- specifies the rows that are retained; you can override this method.
- static <M, I> RowFilter<M, I> numberFilter(RowFilter.ComparisonType type, Number number, int... indices)
 - static <M, I> RowFilter<M, I> dateFilter(RowFilter.ComparisonType type,

```
Date date, int... indices)
```

return a filter that includes rows containing values that match the given comparison to the given number or date. The comparison type is one of EQUAL, NOT_EQUAL, AFTER, or BEFORE. If any column model indexes are given, only those columns are searched; otherwise, all columns are searched. For the number filter, the class of the cell value must match the class of number.

- static <M, I> RowFilter<M, I>
regexFilter(String regex, int... indices)

returns a filter that includes rows that have a string value matching the given regular expression. If any column model indexes are given, only those columns are searched; otherwise, all columns are searched. Note that the string returned by the getStringValue method of RowFilter.Entry is matched.

- static <M, I> RowFilter<M, I>
andFilter(Iterable<? extends RowFilter<?
super M, ? super I>> filters)
- static <M, I> RowFilter<M, I>
orFilter(Iterable<? extends RowFilter<?
super M, ? super I>> filters)

return a filter that includes the entries included by all filters, or at least one of the filters.

- static <M, I> RowFilter<M, I>
notFilter(RowFilter<M, I> filter)

returns a filter that includes the entries not included by the given filter.

- `I getIdentifier()`
returns the identifier of this row entry.
- `M getModel()`
returns the model of this row entry.
- `Object getValue(int index)`
returns the value stored at the given index of this row.
- `int getValueCount()`
returns the number of values stored in this row.
- `String getStringValue(int index)`
returns the value stored at the given index of this row, converted to a string. The `TableRowSorter` produces entries whose `getStringValue` calls the sorter's string converter.

11.1.4 Cell Rendering and Editing

As you saw in [Section 11.1.3.2, “Accessing Table Columns,”](#) on p. 601, the column type determines how the cells are rendered. There are default renderers for the types `Boolean` and `Icon` that render a checkbox or icon. For all other types, you need to install a custom renderer.

11.1.4.1 Rendering Cells

Table cell renderers are similar to the list cell renderers that you saw earlier. They implement the `TableCellRenderer` interface that has a single method:

[Click here to view code image](#)

```
Component getTableCellRendererComponent(JTable table, Object
value,
```

```
boolean isSelected, boolean hasFocus, int row, int
column)
```

That method is called when the table needs to draw a cell. You return a component whose `paint` method is then invoked to fill the cell area.

The table in [Figure 11.8](#) contains cells of type `Color`. The renderer simply returns a panel with a background color that is the color object stored in the cell. The color is passed as the `value` parameter.

| Planet | Radius | Gaseous | Color | Image |
|---------|--------|---------|-------|-------|
| Mars | 3,397 | 2 | ■ | |
| Jupiter | 71,492 | 16 | ■ | |
| Saturn | 60,268 | 18 | ■ | |

Figure 11.8 A table with cell renderers

[Click here to view code image](#)

```
class ColorTableCellRenderer extends JPanel implements
TableCellRenderer
{
    public Component getTableCellRendererComponent(JTable table,
```

```

Object value,
        boolean isSelected, boolean hasFocus, int row, int
column)
{
    setBackground((Color) value);
    if (hasFocus)

setBorder(UIManager.getBorder("Table.focusCellHighlightBorder"))
);

    else
        setBorder(null);
    return this;
}
}

```

As you can see, the renderer draws a border when the cell has focus. (We ask the UIManager for the correct border. To find the lookup key, we peeked into the source code of the DefaultTableCellRenderer class.)



Tip

If your renderer simply draws a text string or an icon, you can extend the DefaultTableCellRenderer class. It takes care of rendering the focus and selection status for you.

You need to tell the table to use this renderer with all objects of type Color. The `setDefaultRenderer` method of the `JTable` class lets you establish this association. Supply a `Class` object and the renderer:

[Click here to view code image](#)

```

table.setDefaultRenderer(Color.class, new
ColorTableCellRenderer());

```

That renderer is now used for all objects of the given type in this table.

If you want to select a renderer based on some other criterion, you need to subclass the `JTable` class and override the `getCellRenderer` method.

11.1.4.2 Rendering the Header

To display an icon in the header, set the header value:

[Click here to view code image](#)

```
moonColumn.setHeaderValue(new ImageIcon("Moons.gif"));
```

However, the table header isn't smart enough to choose an appropriate renderer for the header value. You have to install the renderer manually. For example, to show an image icon in a column header, call

[Click here to view code image](#)

```
moonColumn.setHeaderRenderer(table.getDefaultRenderer(ImageIcon.class));
```

11.1.4.3 Editing Cells

To enable cell editing, the table model must indicate which cells are editable by defining the `isCellEditable` method. Most commonly, you will want to make certain columns editable. In the example program, we allow editing in four columns.

[Click here to view code image](#)

```
public boolean isCellEditable(int r, int c)
{
    return c == PLANET_COLUMN || c == MOONS_COLUMN || c ==
GASEOUS_COLUMN
    || c == COLOR_COLUMN;
}
```



Note

The `AbstractTableModel` defines the `isCellEditable` method to always return `false`. The `DefaultTableModel` overrides the method to always return `true`.

If you run the program ([Listings 11.4 to 11.7](#)), note that you can click the checkboxes in the Gaseous column and turn the check marks on and off. If you click a cell in the Moons column, a combo box appears (see [Figure 11.9](#)). You will shortly see how to install such a combo box as a cell editor.

| Planet | Radius | Gaseous | Color | Image |
|---------|--------|--------------------------------------|-------|-------|
| Mercury | 2,440 | 0 | | |
| Venus | 6,052 | 0
1
2
3
4
5
6
7 | | |
| Earth | 6,378 | 1 | | |

Figure 11.9 A cell editor

Finally, click a cell in the first column. The cell gains focus. You can start typing, and the cell contents change.

What you just saw in action are the three variations of the `DefaultCellEditor` class. A `DefaultCellEditor` can be constructed with a `JTextField`, a `JCheckBox`, or a `JComboBox`. The `JTable` class automatically installs a checkbox editor for Boolean cells and a text field editor for all editable cells that don't supply their own renderer. The text fields let the user edit the strings that result from applying `toString` to the return value of the `getValueAt` method of the table model.

When the edit is complete, the edited value is retrieved by calling the `getCellEditorValue` method of your editor. That method should return a value of the correct type (that is, the type returned by the `getColumnType` method of the model).

To get a combo box editor, set a cell editor manually—the `JTable` component has no idea what values might be appropriate for a particular type. For the Moons column, we wanted to enable the user to pick any value between 0 and 20. Here is the code for initializing the combo box:

[Click here to view code image](#)

```
var moonCombo = new JComboBox();
for (int i = 0; i <= 20; i++)
    moonCombo.addItem(i);
```

To construct a `DefaultCellEditor`, supply the combo box in the constructor:

[Click here to view code image](#)

```
var moonEditor = new DefaultCellEditor(moonCombo);
```

Next, we need to install the editor. Unlike the color cell renderer, this editor does not depend on the object *type*—we don't necessarily want to use it for all objects of type `Integer`. Instead, we need to install it into a particular column:

[Click here to view code image](#)

```
moonColumn.setCellEditor(moonEditor);
```

11.1.4.4 Custom Editors

Run the example program again and click a color. A *color chooser* pops up and lets you pick a new color for the planet. Select a color and click OK. The cell color is updated (see Figure 11.10).




Figure 11.10 Editing the cell color with a color chooser

The color cell editor is not a standard table cell editor but a custom implementation. To create a custom cell editor, implement the `TableCellEditor` interface. That interface is a bit tedious, and an `AbstractCellEditor` class is provided to take care of the event handling details.

The `getTableCellEditorComponent` method of the `TableCellEditor` interface requests a component to render the cell. It is exactly the same as the `getTableCellRendererComponent` method of the `TableCellRenderer` interface, except that there is no `focus` parameter. When the cell is being edited, it is presumed to have focus. The editor component temporarily *replaces* the renderer when the editing is in progress. In our example, we return a blank panel that is not colored. This is an indication to the user that the cell is currently being edited.

Next, you want to have your editor pop up when the user clicks on the cell.

The `JTable` class calls your editor with an event (such as a mouse click) to find out if that event is acceptable to initiate the editing process. The `AbstractCellEditor` class defines the method to accept all events.

[Click here to view code image](#)

```
public boolean isCellEditable(EventObject anEvent)
{
    return true;
}
```

However, if you override this method to return `false`, the table would not go through the trouble of inserting the editor component.

Once the editor component is installed, the `shouldSelectCell` method is called, presumably with the same event. You should initiate editing in this method—for example, by popping up an external edit dialog box.

[Click here to view code image](#)

```
public boolean shouldSelectCell(EventObject anEvent)
{
    colorDialog.setVisible(true);
    return true;
}
```

If the user cancels the edit, the table calls the `cancelCellEditing` method. If the user has clicked on another table cell, the table calls the `stopCellEditing` method. In both cases, you should hide the dialog box. When your `stopCellEditing` method is called, the table would like to use the partially edited value. You should return `true` if the current value is valid. In the color chooser, any value is valid. But if you edit other data, you can ensure that only valid data are retrieved from the editor.

Also, you should call the superclass methods that take care of event firing—otherwise, the editing won't be properly canceled.

[Click here to view code image](#)

```
public void cancelCellEditing()
{
    colorDialog.setVisible(false);
    super.cancelCellEditing();
}
```

Finally, you need a method that yields the value that the user supplied in the editing process:

[Click here to view code image](#)

```
public Object getCellEditorValue()
{
    return colorChooser.getColor();
}
```

To summarize, your custom editor should do the following:

1. Extend the `AbstractCellEditor` class and implement the `TableCellEditor` interface.

2. Define the `getTableCellEditorComponent` method to supply a component. This can either be a dummy component (if you pop up a dialog box) or a component for in-place editing such as a combo box or text field.
3. Define the `shouldSelectCell`, `stopCellEditing`, and `cancelCellEditing` methods to handle the start, completion, and cancellation of the editing process. The `stopCellEditing` and `cancelCellEditing` methods should call the superclass methods to ensure that listeners are notified.
4. Define the `getCellEditorValue` method to return the value that is the result of the editing process.

Finally, indicate when the user is finished editing by calling the `stopCellEditing` and `cancelCellEditing` methods. When constructing the color dialog box, we install the `accept` and `cancel` callbacks that fire these events.

[Click here to view code image](#)

```
colorDialog = JColorChooser.createDialog(null, "Planet Color",
false, colorChooser,
EventHandler.create(ActionListener.class, this,
"stopCellEditing"),
EventHandler.create(ActionListener.class, this,
"cancelCellEditing"));
```

This completes the implementation of the custom editor.

You now know how to make a cell editable and how to install an editor. There is one remaining issue—how to update the model with the value that the user edited. When editing is complete, the `JTable` class calls the following method of the table model:

[Click here to view code image](#)

```
void setValueAt(Object value, int r, int c)
```

You need to override the method to store the new value. The `value` parameter is the object that was returned by the cell editor. If you implemented the cell editor, you know the type of the object you return from the `getCellEditorValue` method. In the case of the `DefaultCellEditor`, there are three possibilities for that value. It is a `Boolean` if the cell editor is a checkbox, a string if it is a text field, and, if the value comes from a combo box, it is the object that the user selected.

If the `value` object does not have the appropriate type, you need to convert it. That happens most commonly when a number is edited in a text field. In our example, we populated the combo box with `Integer` objects so that no conversion is necessary.

Listing 11.4

`tableCellRender/TableCellRenderFrame.java`

[Click here to view code image](#)

```
1 package tableCellRender;
2
3 import java.awt.*;
4 import javax.swing.*;
5 import javax.swing.table.*;
6
7 /**
8 * This frame contains a table of planet data.
9 */
10 public class TableCellRenderFrame extends JFrame
11 {
12     private static final int DEFAULT_WIDTH = 600;
13     private static final int DEFAULT_HEIGHT = 400;
14
15     public TableCellRenderFrame()
16     {
17         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
18
19         var model = new PlanetTableModel();
20         var table = new JTable(model);
```

```

21         table.setRowSelectionAllowed(false);
22
23         // set up renderers and editors
24
25         table.setDefaultRenderer(Color.class, new
ColorTableCellRenderer());
26         table.setDefaultEditor(Color.class, new
ColorTableCellEditor());
27
28         var moonCombo = new JComboBox<Integer>();
29         for (int i = 0; i <= 20; i++)
30             moonCombo.addItem(i);
31
32         TableColumnModel columnModel = table.getColumnModel();
33         TableColumn moonColumn =
columnModel.getColumn(PlanetTableModel.MOONS_COLUMN);
34         moonColumn.setCellEditor(new
DefaultCellEditor(moonCombo));
35
moonColumn.setHeaderRenderer(table.getDefaultRenderer(ImageIcon.c
lass));
36         moonColumn.setHeaderValue(new
ImageIcon(getClass().getResource("Moons.gif")));
37
38         // show table
39
40         table.setRowHeight(100);
41         add(new JScrollPane(table), BorderLayout.CENTER);
42     }
43 }
```

Listing 11.5 tableCellRender/PlanetTableModel.java

[Click here to view code image](#)

```

1 package tableCellRender;
2
3 import java.awt.*;
```

```
4 import javax.swing.*;
5 import javax.swing.table.*;
6
7 /**
8  * The planet table model specifies the values, rendering and
9  * editing properties for the
10 */
11 public class PlanetTableModel extends AbstractTableModel
12 {
13     public static final int PLANET_COLUMN = 0;
14     public static final int MOONS_COLUMN = 2;
15     public static final int GASEOUS_COLUMN = 3;
16     public static final int COLOR_COLUMN = 4;
17
18     private Object[][] cells =
19     {
20         { "Mercury", 2440.0, 0, false, Color.YELLOW,
21             new
ImageIcon(getClass().getResource("Mercury.gif")) },
22         { "Venus", 6052.0, 0, false, Color.YELLOW,
23             new
ImageIcon(getClass().getResource("Venus.gif")) },
24         { "Earth", 6378.0, 1, false, Color.BLUE,
25             new
ImageIcon(getClass().getResource("Earth.gif")) },
26         { "Mars", 3397.0, 2, false, Color.RED,
27             new ImageIcon(getClass().getResource("Mars.gif"))
},
28         { "Jupiter", 71492.0, 16, true, Color.ORANGE,
29             new
ImageIcon(getClass().getResource("Jupiter.gif")) },
30         { "Saturn", 60268.0, 18, true, Color.ORANGE,
31             new
ImageIcon(getClass().getResource("Saturn.gif")) },
32         { "Uranus", 25559.0, 17, true, Color.BLUE,
33             new
ImageIcon(getClass().getResource("Uranus.gif")) },
```

```
34             { "Neptune", 24766.0, 8, true, Color.BLUE,
35                 new
36                     ImageIcon(getClass().getResource("Neptune.gif")) },
37                 { "Pluto", 1137.0, 1, false, Color.BLACK,
38                     new
39                         ImageIcon(getClass().getResource("Pluto.gif")) }
40             } ;
41
42
43     private String[] columnNames = { "Planet", "Radius",
44                                     "Moons", "Gaseous",
45                                     "Color", "Image" };
46
47
48     public String getColumnName(int c)
49     {
50         return columnNames[c];
51     }
52
53     public Class<?> getColumnClass(int c)
54     {
55         return cells[0][c].getClass();
56     }
57
58     public int getColumnCount()
59     {
60         return cells[0].length;
61     }
62
63     public int getRowCount()
64     {
65         return cells.length;
66     }
67
68     public Object getValueAt(int r, int c)
69     {
70         return cells[r][c];
71     }
72
73     public void setValueAt(Object obj, int r, int c)
```

```
69      {
70          cells[r][c] = obj;
71      }
72
73      public boolean isCellEditable(int r, int c)
74      {
75          return c == PLANET_COLUMN || c == MOONS_COLUMN || c
76          == GASEOUS_COLUMN
77          || c == COLOR_COLUMN;
78      }
```

Listing 11.6

tableCellRender/ColorTableCellRenderer.java

[Click here to view code image](#)

```
1 package tableCellRender;
2
3 import java.awt.*;
4 import javax.swing.*;
5 import javax.swing.table.*;
6
7 /**
8  * This renderer renders a color value as a panel with the
9  * given color.
10 */
11 public class ColorTableCellRenderer extends JPanel implements
12 TableCellRenderer
13 {
14     public Component getTableCellRendererComponent(JTable
15         table, Object value,
16         boolean isSelected, boolean hasFocus, int row, int
17         column)
18     {
19         setBackground((Color) value);
20         if (hasFocus)
21             setBorder(UIManager.getBorder("Table.focusCellHighlightBorder"));
22     }
23 }
```

```
17         else setBorder(null);
18
19     }
20 }
```

Listing 11.7

tableCellRender/ColorTableCellEditor.java

[Click here to view code image](#)

```
1 package tableCellRender;
2
3 import java.awt.*;
4 import java.awt.event.*;
5 import java.beans.*;
6 import java.util.*;
7 import javax.swing.*;
8 import javax.swing.table.*;
9
10 /**
11  * This editor pops up a color dialog to edit a cell value.
12 */
13 public class ColorTableCellEditor extends AbstractCellEditor
14 implements TableCellEditor
15 {
16     private JColorChooser colorChooser;
17     private JDialog colorDialog;
18     private JPanel panel;
19
20     public ColorTableCellEditor()
21     {
22         panel = new JPanel();
23         // prepare color dialog
24
25         colorChooser = new JColorChooser();
26         colorDialog = JColorChooser.createDialog(null, "Planet
Color", false, colorChooser,
27                                         EventHandler.create(ActionListener.class, this,
```

```
    "stopCellEditing"),
27             EventHandler.create(ActionListener.class, this,
28             "cancelCellEditing"));
29
30     public Component getTableCellEditorComponent(JTable
31         table, Object value,
32         boolean isSelected, int row, int column)
33     {
34         // this is where we get the current Color value. We
35         // store it in the dialog in case the
36         // user starts editing
37         colorChooser.setColor((Color) value);
38         return panel;
39     }
40
41     public boolean shouldSelectCell(EventObject anEvent)
42     {
43         // start editing
44         colorDialog.setVisible(true);
45
46         // tell caller it is ok to select this cell
47         return true;
48     }
49
50     public void cancelCellEditing()
51     {
52         // editing is canceled--hide dialog
53         colorDialog.setVisible(false);
54         super.cancelCellEditing();
55     }
56
57     public boolean stopCellEditing()
58     {
59         // editing is complete--hide dialog
60         colorDialog.setVisible(false);
61         super.stopCellEditing();
62     }
63 }
```

```
61         // tell caller it is ok to use color value
62         return true;
63     }
64
65     public Object getCellEditorValue()
66     {
67         return colorChooser.getColor();
68     }
69 }
```

javax.swing.JTable 1.2

- TableCellRenderer getDefaultRenderer(Class<?> type)
gets the default renderer for the given type.
- TableCellEditor getDefaultEditor(Class<?> type)
gets the default editor for the given type.

javax.swing.table.TableCellRenderer 1.2

- Component
getTableCellRendererComponent(JTable table,
Object value, boolean selected, boolean
hasFocus, int row, int column)

returns a component whose paint method is invoked to render a
table cell.

Parameter `table`
`s:`

The table containing the cell to be
rendered

| | |
|----------------|--|
| value | The cell to be rendered |
| selected | true if the cell is currently selected |
| hasFocus | true if the cell currently has focus |
| row,
column | The row and column of the cell |

javax.swing.table.TableColumn 1.2

- `void setCellEditor(TableCellEditor editor)`
set the cell editor or renderer for all cells in this column.
- `void setHeaderRenderer(TableCellRenderer renderer)`
sets the cell renderer for the header cell in this column.
- `void setHeaderValue(Object value)`
sets the value to be displayed for the header in this column.

javax.swing.DefaultCellEditor 1.2

- `DefaultCellEditor(JComboBox comboBox)`
constructs a cell editor that presents the combo box for selecting cell values.

javax.swing.table.TableCellEditor 1.2

- Component getTableCellEditorComponent (JTable table, Object value, boolean selected, int row, int column)

returns a component whose paint method renders a table cell.

| | | |
|--------------------|-------------|--|
| <i>Parameters:</i> | table | The table containing the cell to be rendered |
| | value | The cell to be rendered |
| | selected | true if the cell is currently selected |
| | row, column | The row and column of the cell |

javax.swing.CellEditor 1.2

- boolean isCellEditable(EventObject event)

returns true if the event is suitable for initiating the editing process for this cell.

- boolean shouldSelectCell(EventObject anEvent)

starts the editing process. Returns true if the edited cell should be *selected*. Normally, you want to return true, but you can return false if you don't want the editing process to change the cell selection.

- void cancelCellEditing()

cancels the editing process. You can abandon partial edits.

- `boolean stopCellEditing()`
stops the editing process, with the intent of using the result.
Returns true if the edited value is in a proper state for retrieval.
- `Object getCellEditorValue()`
returns the edited result.
- `void addCellEditorListener(CellEditorListener l)`
- `void removeCellEditorListener(CellEditorListener l)`
add or remove the obligatory cell editor listener.

11.2 Trees

Every computer user who has worked with a hierarchical file system has seen tree displays. Of course, directories and files are only one of the many examples of tree-like organizations. Many tree structures arise in everyday life, such as the hierarchy of countries, states, and cities shown in [Figure 11.11](#).




Figure 11.11 A hierarchy of countries, states, and cities

As programmers, we often need to display tree structures. Fortunately, the Swing library has a `JTree` class for this purpose. The `JTree` class (together with its helper classes) takes care of laying out the tree and processing user requests for expanding and collapsing nodes. In this section, you will learn how to put the `JTree` class to use.

As with the other complex Swing components, we must focus on the common and useful cases and cannot cover every nuance. If you want to achieve something unusual, we recommend that you consult *Graphic Java™, Third Edition*, by David M. Geary or *Core Swing* by Kim Topley.

Before going any further, let's settle on some terminology (see [Figure 11.12](#)). A *tree* is composed of *nodes*. Every node is either a *leaf* or it has *child nodes*. Every node, with the exception of the root node, has exactly one *parent*. A tree has exactly one root node. Sometimes you have a

collection of trees, each with its own root node. Such a collection is called a *forest*.




Figure 11.12 Tree terminology

11.2.1 Simple Trees

In our first example program, we will simply display a tree with a few nodes (see [Figure 11.14](#) on p. 634). As with many other Swing components, you need to provide a model of the data, and the component displays it for you. To construct a `JTree`, supply the tree model in the constructor:

```
TreeModel model = . . .;  
var tree = new JTree(model);
```



Note

There are also constructors that construct trees out of a collection of elements:

[Click here to view code image](#)

```
JTree(Object[] nodes)  
JTree(Vector<?> nodes)  
JTree(Hashtable<?, ?> nodes) // the values become the nodes
```

These constructors are not very useful. They merely build a forest of trees, each with a single node. The third constructor seems particularly useless because the nodes appear in the seemingly random order determined by the hash codes of the keys.

How do you obtain a tree model? You can construct your own model by creating a class that implements the `TreeModel` interface. You will see later in this chapter how to do that. For now, we will stick with the `DefaultTreeModel` that the Swing library supplies.

To construct a default tree model, you must supply a root node.

[Click here to view code image](#)

```
TreeNode root = . . .;  
var model = new DefaultTreeModel(root);
```

`TreeNode` is another interface. Populate the default tree model with objects of any class that implements the interface. For now, we will use the concrete node class that Swing supplies—namely, `DefaultMutableTreeNode`. This class implements the `MutableTreeNode` interface, a subinterface of `TreeNode` (see [Figure 11.13](#)).




Figure 11.13 Tree classes

A default mutable tree node holds an object—the *user object*. The tree renders the user objects for all nodes. Unless you specify a renderer, the tree displays the string that is the result of the `toString` method.

In our first example, we use strings as user objects. In practice, you would usually populate a tree with more expressive user objects. For example, when displaying a directory tree, it makes sense to use `File` objects for the nodes.

You can specify the user object in the constructor, or you can set it later with the `setUserObject` method.

[Click here to view code image](#)

```
var node = new DefaultMutableTreeNode("Texas");
. . .
node.setUserObject("California");
```

Next, you need to establish the parent/child relationships between the nodes. Start with the root node and use the add method to add the children:

[Click here to view code image](#)

```
var root = new DefaultMutableTreeNode("World");
var country = new DefaultMutableTreeNode("USA");
root.add(country);
var state = new DefaultMutableTreeNode("California");
country.add(state);
```

Figure 11.14 illustrates how the tree will look.



Figure 11.14 A simple tree

Link up all nodes in this fashion. Then, construct a DefaultTreeModel with the root node. Finally, construct a JTree with the tree model.

[Click here to view code image](#)

```
var treeModel = new DefaultTreeModel(root);
var tree = new JTree(treeModel);
```

Or, as a shortcut, you can simply pass the root node to the `JTree` constructor. Then the tree automatically constructs a default tree model:

```
var tree = new JTree(root);
```

[Listing 11.8](#) contains the complete code.

Listing 11.8 tree/SimpleTreeFrame.java

[Click here to view code image](#)

```
1 package tree;
2
3 import javax.swing.*;
4 import javax.swing.tree.*;
5
6 /**
7  * This frame contains a simple tree that displays a manually
8  * constructed tree model.
9 */
10 public class SimpleTreeFrame extends JFrame
11 {
12     private static final int DEFAULT_WIDTH = 300;
13     private static final int DEFAULT_HEIGHT = 200;
14
15     public SimpleTreeFrame()
16     {
17         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
18
19         var root = new DefaultMutableTreeNode("World");
20         var country = new DefaultMutableTreeNode("USA");
21         root.add(country);
22         var state = new DefaultMutableTreeNode("California");
23         country.add(state);
24         var city = new DefaultMutableTreeNode("San Jose");
25         state.add(city);
26     }
}
```

```

27     city = new DefaultMutableTreeNode("Cupertino");
28     state.add(city);
29     state = new DefaultMutableTreeNode("Michigan");
30     country.add(state);
31     city = new DefaultMutableTreeNode("Ann Arbor");
32     state.add(city);
33     country = new DefaultMutableTreeNode("Germany");
34     root.add(country);
35     state = new DefaultMutableTreeNode("Schleswig-
Holstein");
36     country.add(state);
37     city = new DefaultMutableTreeNode("Kiel");
38     state.add(city);
39
40     // construct tree and put it in a scroll pane
41
42     var tree = new JTree(root);
43     add(new JScrollPane(tree));
44 }
45 }
```

When you run the program, the tree first looks as in [Figure 11.15](#). Only the root node and its children are visible. Click on the circle icons (the *handles*) to open up the subtrees. The line sticking out from the handle icon points to the right when the subtree is collapsed and down when the subtree is expanded (see [Figure 11.16](#)). We don't know what the designers of the Metal look-and-feel had in mind, but we think of the icon as a door handle. You push down on the handle to open the subtree.



Figure 11.15 The initial tree display




Figure 11.16 Collapsed and expanded subtrees



Note

Of course, the display of the tree depends on the selected look-and-feel. We just described the Metal look-and-feel. In the Windows look-and-feel, the handles have the more familiar look—a “–” or “+” in a box (see [Figure 11.17](#)).



Figure 11.17 A tree with the Windows look-and-feel

You can use the following magic incantation to turn off the lines joining parents and children (see [Figure 11.18](#)):



Figure 11.18 A tree with no connecting lines

[Click here to view code image](#)

```
tree.putClientProperty("JTree.lineStyle", "None");
```

Conversely, to make sure that the lines are shown, use

[Click here to view code image](#)

```
tree.putClientProperty("JTree.lineStyle", "Angled");
```

Another line style, "Horizontal", is shown in [Figure 11.19](#). The tree is displayed with horizontal lines separating only the children of the root. I'm not quite sure what it is good for.



Figure 11.19 A tree with the horizontal line style

By default, there is no handle for collapsing the root of the tree. If you like, you can add one with the call

[Click here to view code image](#)

```
tree.setShowsRootHandles(true);
```

[Figure 11.20](#) shows the result. Now you can collapse the entire tree into the root node.



Figure 11.20 A tree with a root handle

Conversely, you can hide the root altogether. You will thus display a *forest*—a set of trees, each with its own root. You still must join all trees in the forest to a common root; then, hide the root with the instruction

```
tree.setRootVisible(false);
```

Look at [Figure 11.21](#). There appear to be two roots, labeled “USA” and “Germany.” The actual root that joins the two is made invisible.



Figure 11.21 A forest

Let’s turn from the root to the leaves of the tree. Note that the leaves have an icon different from the other nodes (see [Figure 11.22](#)).




Figure 11.22 Leaf and folder icons

When the tree is displayed, each node is drawn with an icon. There are actually three kinds of icons: a leaf icon, an opened nonleaf icon, and a closed nonleaf icon. For simplicity, we refer to the last two as folder icons.

The node renderer needs to know which icon to use for each node. By default, the decision process works like this: If the `isLeaf` method of a node returns `true`, then the leaf icon is used; otherwise, a folder icon is used.

The `isLeaf` method of the `DefaultMutableTreeNode` class returns `true` if the node has no children. Thus, nodes with children get folder icons, and nodes without children get leaf icons.

Sometimes, that behavior is not appropriate. Suppose we added a node “Montana” to our sample tree, but we’re at a loss as to what cities to add. We would not want the state node to get a leaf icon because, conceptually, only the cities are leaves.

The `JTree` class has no idea which nodes should be leaves. It asks the tree model. If a childless node isn’t automatically a conceptual leaf, you can ask the tree model to use a different criterion for leafiness—namely, to query the “allows children” node property.

For those nodes that should not have children, call

[Click here to view code image](#)

```
node.setAllowsChildren(false);
```

Then, tell the tree model to ask the value of the “allows children” property to determine whether a node should be displayed with a leaf icon. Use the `setAsksAllowsChildren` method of the `DefaultTreeModel` class to set this behavior:

[Click here to view code image](#)

```
model.setAsksAllowsChildren(true);
```

With this decision criterion, nodes that allow children get folder icons, and nodes that don’t allow children get leaf icons.

Alternatively, if you construct the tree from the root node, supply the setting for the “asks allows children” property in the constructor.

[Click here to view code image](#)

```
var tree = new JTree(root, true); // nodes that don't allow  
children get leaf icons
```

javax.swing.JTree 1.2

- `JTree(TreeModel model)`
constructs a tree from a tree model.
- `JTree(TreeNode root)`
- `JTree(TreeNode root, boolean asksAllowChildren)`
construct a tree with a default tree model that displays the root and its children.

Para root The root node

meter

s:

asksAllo true to use the “allows children” node
wsChildr property for determining whether a node is
en a leaf

- void setShowsRootHandles(boolean b)

If b is true, the root node has a handle for collapsing or expanding its children.

- void setRootVisible(boolean b)

If b is true, then the root node is displayed. Otherwise, it is hidden.

javax.swing.tree.TreeNode 1.2

- boolean isLeaf()

returns true if this node is conceptually a leaf.

- boolean getAllowsChildren()

returns true if this node can have child nodes.

javax.swing.tree.MutableTreeNode 1.2

- void setUserObject(Object userObject)

sets the “user object” that the tree node uses for rendering.

javax.swing.tree.TreeModel 1.2

- `boolean isLeaf(Object node)`
returns true if node should be displayed as a leaf node.

javax.swing.tree.DefaultTreeModel 1.2

- `void setAsksAllowsChildren(boolean b)`
If b is true, nodes are displayed as leaves when their `getAllowsChildren` method returns false. Otherwise, they are displayed as leaves when their `isLeaf` method returns true.

javax.swing.tree.DefaultMutableTreeNode 1.2

- `DefaultMutableTreeNode(Object userObject)`
constructs a mutable tree node with the given user object.
- `void add(MutableTreeNode child)`
adds a node as the last child of this node.
- `void setAllowsChildren(boolean b)`
If b is true, children can be added to this node.

javax.swing.JComponent 1.2

- `void putClientProperty(Object key, Object value)`

adds a key/value pair to a small table that each component manages. This is an “escape hatch” mechanism that some Swing components use for storing properties specific to a look-and-feel.

11.2.1.1 Editing Trees and Tree Paths

In the next example program, you will see how to edit a tree. [Figure 11.23](#) shows the user interface. If you click the Add Sibling or Add Child button, the program adds a new node (with title New) to the tree. If you click the Delete button, the program deletes the currently selected node.



Figure 11.23 Editing a tree

To implement this behavior, you need to find out which tree node is currently selected. The `JTree` class has a surprising way of identifying nodes in a tree. It does not deal with tree nodes but with *paths of objects*, called *tree paths*. A tree path starts at the root and consists of a sequence of child nodes (see [Figure 11.24](#)).



Figure 11.24 A tree path

You might wonder why the `JTree` class needs the whole path. Couldn't it just get a `TreeNode` and keep calling the `getParent` method? In fact, the `JTree` class knows nothing about the `TreeNode` interface. That interface is never used by the `TreeModel` interface; it is only used by the `DefaultTreeModel` implementation. You can have other tree models in which the nodes do not implement the `TreeNode` interface at all. If you use a tree model that manages other types of objects, those objects might not have `getParent` and `getChild` methods. They would of course need to have some other connection to each other. It is the job of the tree model to link nodes together. The `JTree` class itself has no clue about the nature of their linkage. For that reason, the `JTree` class always needs to work with complete paths.

The `TreePath` class manages a sequence of `Object` (not `TreeNode`!) references. A number of `JTree` methods return `TreePath` objects. When you have a tree path, you usually just need to know the terminal node, which you can get with the `getLastPathComponent` method. For example, to find out the currently selected node in a tree, use the `getSelectionPath` method of the `JTree` class. You will get a `TreePath` object back, from which you can retrieve the actual node.

[Click here to view code image](#)

```
TreePath selectionPath = tree.getSelectionPath();
var selectedNode = (DefaultMutableTreeNode)
```

```
selectionPath.getLastPathComponent();
```

Actually, since this particular query is so common, there is a convenience method that gives the selected node immediately:

[Click here to view code image](#)

```
var selectedNode = (DefaultMutableTreeNode)
tree.getLastSelectedPathComponent();
```

This method is not called `getSelectedNode` because the tree does not know that it contains nodes—its tree model deals only with paths of objects.



Note

Tree paths are one of the two ways in which the `JTree` class describes nodes. Quite a few `JTree` methods take or return an integer index—the *row position*. A row position is simply the row number (starting with 0) of the node in the tree display. Only visible nodes have row numbers, and the row number of a node changes if other nodes before it are expanded, collapsed, or modified. For that reason, you should avoid row positions. All `JTree` methods that use row positions have equivalents that use tree paths instead.

Once you have the selected node, you can edit it. However, do not simply add children to a tree node:

[Click here to view code image](#)

```
selectedNode.add(newNode); // No!
```

If you change the structure of the nodes, you change the model but the associated view is not notified. You could send out a notification yourself, but if you use the `insertNodeInto` method of the `DefaultTreeModel` class, the model class takes care of that. For

example, the following call appends a new node as the last child of the selected node and notifies the tree view:

[Click here to view code image](#)

```
model.insertNodeInto(newNode, selectedNode,  
selectedNode.getChildCount());
```

The analogous call `removeNodeFromParent` removes a node and notifies the view:

[Click here to view code image](#)

```
model.removeNodeFromParent(selectedNode);
```

If you keep the node structure in place but change the user object, you should call the following method:

[Click here to view code image](#)

```
model.nodeChanged(changedNode);
```

The automatic notification is a major advantage of using the `DefaultTreeModel`. If you supply your own tree model, you have to implement automatic notification by hand. (See *Core Swing* by Kim Topley for details.)



Caution

The `DefaultTreeModel` class has a `reload` method that reloads the entire model. However, don't call `reload` simply to update the tree after making a few changes. When the tree is regenerated, all nodes beyond the root's children are collapsed again. It will be quite disconcerting to your users if they have to keep expanding the tree after every change.

When the view is notified of a change in the node structure, it updates the display but does not automatically expand a node to show newly added children. In particular, if a user in our sample program adds a new child node to a node for which children are currently collapsed, the new node is silently added to the collapsed subtree. This gives the user no feedback that the command was actually carried out. In such a case, you should make a special effort to expand all parent nodes so that the newly added node becomes visible. Use the `makeVisible` method of the `JTree` class for this purpose. The `makeVisible` method expects a tree path leading to the node that should become visible.

Thus, you need to construct a tree path from the root to the newly inserted node. To get a tree path, first call the `getPathToRoot` method of the `DefaultTreeModel` class. It returns a `TreeNode []` array of all nodes from a node to the root node. Pass that array to a `TreePath` constructor.

For example, here is how you make the new node visible:

[Click here to view code image](#)

```
TreeNode[] nodes = model.getPathToRoot(newNode);  
var path = new TreePath(nodes);  
tree.makeVisible(path);
```



Note

It is curious that the `DefaultTreeModel` class feigns almost complete ignorance of the `TreePath` class, even though its job is to communicate with a `JTree`. The `JTree` class uses tree paths a lot, and it never uses arrays of node objects.

Now, suppose your tree is contained inside a scroll pane. After the tree node expansion, the new node might still not be visible because it falls outside the viewport. To overcome that problem, call

[Click here to view code image](#)

```
tree.scrollPathToVisible(path);
```

instead of calling `makeVisible`. This call expands all nodes along the path and tells the ambient scroll pane to scroll the node at the end of the path into view (see [Figure 11.25](#)).



Figure 11.25 The scroll pane scrolls to display a new node.

By default, tree nodes cannot be edited. However, if you call

```
tree.setEditable(true);
```

the user can edit a node simply by double-clicking, editing the string, and pressing the Enter key. Double-clicking invokes the *default cell editor*, which is implemented by the `DefaultCellEditor` class (see [Figure 11.26](#)). It is possible to install other cell editors, using the same process that you have seen in our discussion of table cell editors.



Figure 11.26 The default cell editor

[Listing 11.9](#) shows the complete source code of the tree editing program. Run the program, add a few nodes, and edit them by double-clicking. Observe how collapsed nodes expand to show added children and how the scroll pane keeps added nodes in the viewport.

Listing 11.9 treeEdit/TreeEditFrame.java

[Click here to view code image](#)

```
1 package treeEdit;
2
3 import java.awt.*;
4 import javax.swing.*;
5 import javax.swing.tree.*;
6
7 /**
8  * A frame with a tree and buttons to edit the tree.
9  */
10 public class TreeEditFrame extends JFrame
11 {
12     private static final int DEFAULT_WIDTH = 400;
13     private static final int DEFAULT_HEIGHT = 200;
14
15     private DefaultTreeModel model;
16     private JTree tree;
```

```
17
18     public TreeEditFrame()
19     {
20         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
21
22         // construct tree
23
24         TreeNode root = makeSampleTree();
25         model = new DefaultTreeModel(root);
26         tree = new JTree(model);
27         tree.setEditable(true);
28
29         // add scroll pane with tree
30
31         var scrollPane = new JScrollPane(tree);
32         add(scrollPane, BorderLayout.CENTER);
33
34         makeButtons();
35     }
36
37     public TreeNode makeSampleTree()
38     {
39         var root = new DefaultMutableTreeNode("World");
40         var country = new DefaultMutableTreeNode("USA");
41         root.add(country);
42         var state = new DefaultMutableTreeNode("California");
43         country.add(state);
44         var city = new DefaultMutableTreeNode("San Jose");
45         state.add(city);
46         city = new DefaultMutableTreeNode("San Diego");
47         state.add(city);
48         state = new DefaultMutableTreeNode("Michigan");
49         country.add(state);
50         city = new DefaultMutableTreeNode("Ann Arbor");
51         state.add(city);
52         country = new DefaultMutableTreeNode("Germany");
53         root.add(country);
54         state = new DefaultMutableTreeNode("Schleswig-
```

```
Holstein");
55     country.add(state);
56     city = new DefaultMutableTreeNode("Kiel");
57     state.add(city);
58     return root;
59 }
60
61 /**
62  * Makes the buttons to add a sibling, add a child, and
63  delete a node.
64  */
65 public void makeButtons()
66 {
67     var panel = new JPanel();
68     var addSiblingButton = new JButton("Add Sibling");
69     addSiblingButton.addActionListener(event ->
70     {
71         var selectedNode = (DefaultMutableTreeNode)
72             tree.getLastSelectedPathComponent();
73
74         if (selectedNode == null) return;
75
76         var parent = (DefaultMutableTreeNode)
77             selectedNode.getParent();
78
79         if (parent == null) return;
80
81         var newNode = new DefaultMutableTreeNode("New");
82
83         int selectedIndex =
84             parent.getIndex(selectedNode);
85         model.insertNodeInto(newNode, parent,
86             selectedIndex + 1);
87
88         // now display new node
89
90         TreeNode[] nodes = model.getPathToRoot(newNode);
91         var path = new TreePath(nodes);
```

```
87             tree.scrollPathToVisible(path);
88         });
89         panel.add(addSiblingButton);
90
91         var addChildButton = new JButton("Add Child");
92         addChildButton.addActionListener(event ->
93         {
94             var selectedNode = (DefaultMutableTreeNode)
95             tree.getLastSelectedPathComponent();
96
97             if (selectedNode == null) return;
98
99             var newNode = new DefaultMutableTreeNode("New");
100            model.insertNodeInto(newNode, selectedNode,
101                selectedNode.getChildCount());
102
103            // now display new node
104            TreeNode[] nodes =
105            model.getPathToRoot(newNode);
106            var path = new TreePath(nodes);
107            tree.scrollPathToVisible(path);
108        });
109        panel.add(addChildButton);
110
111        var deleteButton = new JButton("Delete");
112        deleteButton.addActionListener(event ->
113        {
114            var selectedNode = (DefaultMutableTreeNode)
115            tree.getLastSelectedPathComponent();
116
117            if (selectedNode != null &&
118                selectedNode.getParent() != null) model
119                    .removeNodeFromParent(selectedNode);
120        });
121        panel.add(deleteButton);
122    add(panel, BorderLayout.SOUTH);
```

```
119      }
120  }
```

javax.swing.JTree 1.2

- `TreePath getSelectionPath()`
gets the path to the currently selected node, or the path to the first selected node if multiple nodes are selected. Returns `null` if no node is selected.
- `Object getLastSelectedPathComponent()`
gets the node object that represents the currently selected node, or the first node if multiple nodes are selected. Returns `null` if no node is selected.
- `void makeVisible(TreePath path)`
expands all nodes along the path.
- `void scrollPathToVisible(TreePath path)`
expands all nodes along the path and, if the tree is contained in a scroll pane, scrolls to ensure that the last node on the path is visible.

javax.swing.tree.TreePath 1.2

- `Object getLastPathComponent()`
gets the last object on this path—that is, the node object that the path represents.

javax.swing.tree.TreeNode 1.2

- `TreeNode getParent()`
returns the parent node of this node.
- `TreeNode getChildAt(int index)`
looks up the child node at the given index. The index must be between 0 and `getChildCount() - 1`.
- `int getChildCount()`
returns the number of children of this node.
- `Enumeration children()`
returns an enumeration object that iterates through all children of this node.

javax.swing.tree.DefaultTreeModel 1.2

- `void insertNodeInto(MutableTreeNode newChild, MutableTreeNode parent, int index)`
inserts newChild as a new child node of parent at the given index and notifies the tree model listeners.
- `void removeNodeFromParent(MutableTreeNode node)`
removes node from this model and notifies the tree model listeners.
- `void nodeChanged(TreeNode node)`

notifies the tree model listeners that node has changed.

- `void nodesChanged(TreeNode parent, int[] changedChildIndexes)`

notifies the tree model listeners that all child nodes of parent with the given indexes have changed.

- `void reload()`

reloads all nodes into the model. This is a drastic operation that you should use only if the nodes have changed completely because of some outside influence.

11.2.2 Node Enumeration

Sometimes you need to find a node in a tree by starting at the root and visiting all children until you have found a match. The `DefaultMutableTreeNode` class has several convenience methods for iterating through nodes.

The `breadthFirstEnumeration` and `depthFirstEnumeration` methods return enumeration objects whose `nextElement` method visits all children of the current node, using either a breadth-first or depth-first traversal. [Figure 11.27](#) shows the traversals for a sample tree—the node labels indicate the order in which the nodes are traversed.




Figure 11.27 Tree traversal orders

Breadth-first enumeration is the easiest to visualize. The tree is traversed in layers. The root is visited first, followed by all of its children, then the grandchildren, and so on.

To visualize depth-first enumeration, imagine a rat trapped in a tree-shaped maze. It rushes along the first path until it comes to a leaf. Then, it backtracks and turns around to the next path, and so on.

Computer scientists also call this *postorder traversal* because the search process visits the children before visiting the parents. The `postOrderEnumeration` method is a synonym for `depthFirstEnumeration`. For completeness, there is also a `preOrderEnumeration`, a depth-first search that enumerates parents before the children.

Here is the typical usage pattern:

[Click here to view code image](#)

```
Enumeration breadthFirst = node.breadthFirstEnumeration();
while (breadthFirst.hasMoreElements())
    do something with breadthFirst.nextElement();
```

Finally, a related method, `pathFromAncestorEnumeration`, finds a path from an ancestor to a given node and enumerates the nodes along that path. That's no big deal—it just keeps calling `getParent` until the ancestor is found and then presents the path in reverse order.

In our next example program, we put node enumeration to work. The program displays inheritance trees of classes. Type the name of a class into the text field on the bottom of the frame. The class and all of its superclasses are added to the tree (see [Figure 11.28](#)).




Figure 11.28 An inheritance tree

In this example, we take advantage of the fact that the user objects of the tree nodes can be objects of any type. Since our nodes describe classes, we store `Class` objects in the nodes.

We don't want to add the same class object twice, so we need to check whether a class already exists in the tree. The following method finds the node with a given user object if it exists in the tree:

[Click here to view code image](#)

```
public DefaultMutableTreeNode findUserObject(Object obj)
{
    ...
```

```

Enumeration e = root.breadthFirstEnumeration();
while (e.hasMoreElements())
{
    DefaultMutableTreeNode node = (DefaultMutableTreeNode)
e.nextElement();
    if (node.getUserObject().equals(obj))
        return node;
}
return null;
}

```

11.2.3 Rendering Nodes

In your applications, you will often need to change the way a tree component draws the nodes. The most common change is, of course, to choose different icons for nodes and leaves. Other changes might involve changing the font of the node labels or drawing images at the nodes. All these changes are possible by installing a new *tree cell renderer* into the tree. By default, the JTree class uses DefaultTreeCellRenderer objects to draw each node. The DefaultTreeCellRenderer class extends the JLabel class. The label contains the node icon and the node label.



Note

The cell renderer does not draw the “handles” for expanding and collapsing subtrees. The handles are part of the look-and-feel, and it is recommended that you do not change them.

You can customize the display in three ways.

- You can change the icons, font, and background color used by a DefaultTreeCellRenderer. These settings are used for all nodes in the tree.

- You can install a renderer that extends the `DefaultTreeCellRenderer` class and vary the icons, fonts, and background color for each node.
- You can install a renderer that implements the `TreeCellRenderer` interface to draw a custom image for each node.

Let us look at these possibilities one by one. The easiest customization is to construct a `DefaultTreeCellRenderer` object, change the icons, and install it into the tree:

[Click here to view code image](#)

```
var renderer = new DefaultTreeCellRenderer();
renderer.setLeafIcon(new ImageIcon("blue-ball.gif")); // used
for leaf nodes
renderer.setClosedIcon(new ImageIcon("red-ball.gif")); // used
for collapsed nodes
renderer.setOpenIcon(new ImageIcon("yellow-ball.gif")); // used
for expanded nodes
tree.setCellRenderer(renderer);
```

You can see the effect in [Figure 11.28](#). We just use the “ball” icons as placeholders—presumably your user interface designer would supply you with appropriate icons to use for your applications.

We don’t recommend that you change the font or background color for an entire tree—that is really the job of the look-and-feel.

However, it can be useful to change the font of some nodes in a tree to highlight them. If you look carefully at [Figure 11.28](#), you will notice that the *abstract* classes are set in italics.

To change the appearance of individual nodes, install a tree cell renderer. Tree cell renderers are very similar to the list cell renderers we discussed earlier in this chapter. The `TreeCellRenderer` interface has a single method:

[Click here to view code image](#)

```
Component getTreeCellRendererComponent(JTree tree, Object
value, boolean selected,
    boolean expanded, boolean leaf, int row, boolean
hasFocus)
```

The `getTreeCellRendererComponent` method of the `DefaultTreeCellRenderer` class returns this—in other words, a label. (The `DefaultTreeCellRenderer` class extends the `JLabel` class.) To customize the component, extend the `DefaultTreeCellRenderer` class. Override the `getTreeCellRendererComponent` method as follows: Call the superclass method so it can prepare the label data, customize the label properties, and finally return this.

[Click here to view code image](#)

```
class MyTreeCellRenderer extends DefaultTreeCellRenderer
{
    public Component getTreeCellRendererComponent(JTree tree,
Object value, boolean selected,
        boolean expanded, boolean leaf, int row, boolean
hasFocus)
    {
        Component comp = super.getTreeCellRendererComponent(tree,
value, selected,
            expanded, leaf, row, hasFocus);
        DefaultMutableTreeNode node = (DefaultMutableTreeNode)
value;
        look at node.getUserObject();
        Font font = appropriate font;
        comp.setFont(font);
        return comp;
    }
}
```



Caution

The `value` parameter of the `getTreeCellRendererComponent` method is the *node* object, *not* the user object! Recall that the user object is a feature of the `DefaultMutableTreeNode`, and that a `JTree` can contain nodes of an arbitrary type. If your tree uses `DefaultMutableTreeNode` nodes, you must retrieve the user object in a second step, as we did in the preceding code sample.



Caution

The `DefaultTreeCellRenderer` uses the *same* label object for all nodes, only changing the label text for each node. If you change the font for a particular node, you must set it back to its default value when the method is called again. Otherwise, all subsequent nodes will be drawn in the changed font! Look at the code in [Listing 11.10](#) to see how to restore the font to the default.

The `ClassNameTreeCellRenderer` in [Listing 11.10](#) sets the class name in either the normal or italic font, depending on the `ABSTRACT` modifier of the `Class` object. We don't want to set a particular font because we don't want to change whatever font the look-and-feel normally uses for labels. For that reason, we use the font from the label and *derive* an italic font from it. Recall that only a single shared `JLabel` object is returned by all calls. We need to hang on to the original font and restore it in the next call to the `getTreeCellRendererComponent` method.

Also, note how we change the node icons in the `ClassTreeFrame` constructor.

`javax.swing.tree.DefaultMutableTreeNode` 1.2

- `Enumeration breadthFirstEnumeration()`
- `Enumeration depthFirstEnumeration()`

- Enumeration preOrderEnumeration()
- Enumeration postOrderEnumeration()

return enumeration objects for visiting all nodes of the tree model in a particular order. In breadth-first traversal, children that are closer to the root are visited before those that are farther away. In depth-first traversal, all children of a node are completely enumerated before its siblings are visited. The postOrderEnumeration method is a synonym for depthFirstEnumeration. The preorder traversal is identical to the postorder traversal except that parents are enumerated before their children.

javax.swing.tree.TreeCellRenderer 1.2

- Component getTreeCellRendererComponent (JTree tree, Object value, boolean selected, boolean expanded, boolean leaf, int row, boolean hasFocus)

returns a component whose paint method is invoked to render a tree cell.

| | | |
|--------------------|----------|--|
| <i>Parameters:</i> | tree | The tree containing the node to be rendered |
| | value | The node to be rendered |
| | selected | true if the node is currently selected |
| | expanded | true if the children of the node are visible |
| | leaf | true if the node needs to be displayed as a leaf |
| | row | The display row containing the node |

hasFoc true if the node currently has input
us focus

javax.swing.tree.DefaultTreeCellRenderer 1.2

- void setLeafIcon(Icon icon)
- void setOpenIcon(Icon icon)
- void setClosedIcon(Icon icon)

set the icon to show for a leaf node, an expanded node, and a collapsed node.

11.2.4 Listening to Tree Events

Most commonly, a tree component is paired with some other component. When the user selects tree nodes, some information shows up in another window. See [Figure 11.29](#) for an example. When the user selects a class, the instance and static variables of that class are displayed in the text area to the right.




Figure 11.29 A class browser

To obtain this behavior, you need to install a *tree selection listener*. The listener must implement the `TreeSelectionListener` interface—an interface with a single method:

[Click here to view code image](#)

```
void valueChanged(TreeSelectionEvent event)
```

That method is called whenever the user selects or deselects tree nodes.

Add the listener to the tree in the normal way:

[Click here to view code image](#)

```
tree.addTreeSelectionListener(listener);
```

You can specify whether the user is allowed to select a single node, a contiguous range of nodes, or an arbitrary, potentially discontiguous, set of nodes. The `JTree` class uses a `TreeSelectionModel` to manage node selection. You need to retrieve the model to set the selection state to one of `SINGLE_TREE_SELECTION`, `CONTIGUOUS_TREE_SELECTION`, or `DISCONTIGUOUS_TREE_SELECTION`. (Discontiguous selection mode

is the default.) For example, in our class browser, we want to allow selection of only a single class:

[Click here to view code image](#)

```
int mode = TreeSelectionModel.SINGLE_TREE_SELECTION;
tree.getSelectionModel().setSelectionMode(mode);
```

Apart from setting the selection mode, you need not worry about the tree selection model.



Note

How the user selects multiple items depends on the look-and-feel. In the Metal look-and-feel, hold down the Ctrl key while clicking an item to add it to the selection, or to remove it if it is currently selected. Hold down the Shift key while clicking an item to select a *range* of items, extending from the previously selected item to the new item.

To find out the current selection, query the tree with the `getSelectionPaths` method:

[Click here to view code image](#)

```
TreePath[] selectedPaths = tree.getSelectionPaths();
```

If you restricted the user to single-item selection, you can use the convenience method `getSelectionPath` which returns the first selected path or `null` if no path was selected.



Caution

The `TreeSelectionEvent` class has a `getPaths` method that returns an array of `TreePath` objects, but that array

describes *selection changes*, not the current selection.

[Listing 11.10](#) shows the frame class for the class tree program. The program displays inheritance hierarchies and customizes the display to show abstract classes in italics. (See [Listing 11.11](#) for the cell renderer.) You can type the name of any class into the text field at the bottom of the frame. Press the Enter key or click the Add button to add the class and its superclasses to the tree. You must enter the full package name, such as `java.util.ArrayList`.

This program is a bit tricky because it uses reflection to construct the class tree. This work is done inside the `addClass` method. (The details are not that important. We use the class tree in this example because inheritance yields a nice supply of trees without laborious coding. When you display trees in your applications, you will have your own source of hierarchical data.) The method uses the breadth-first search algorithm to find whether the current class is already in the tree by calling the `findUserObject` method that we implemented in the preceding section. If the class is not already in the tree, we add the superclasses to the tree, then make the new class node a child and make that node visible.

When you select a tree node, the text area to the right is filled with the fields of the selected class. In the frame constructor, we restrict the user to single-item selection and add a tree selection listener. When the `valueChanged` method is called, we ignore its event parameter and simply ask the tree for the current selection path. As always, we need to get the last node of the path and look up its user object. We then call the `getFieldDescription` method which uses reflection to assemble a string with all fields of the selected class.

Listing 11.10 `treeRender/ClassTreeFrame.java`

[Click here to view code image](#)

```
1 package treeRender;
2
3 import java.awt.*;
```

```
4 import java.awt.event.*;
5 import java.lang.reflect.*;
6 import java.util.*;
7
8 import javax.swing.*;
9 import javax.swing.tree.*;
10
11 /**
12  * This frame displays the class tree, a text field, and an
13 "Add" button to add more classes
14  * into the tree.
15 */
16 public class ClassTreeFrame extends JFrame
17 {
18     private static final int DEFAULT_WIDTH = 400;
19     private static final int DEFAULT_HEIGHT = 300;
20
21     private DefaultMutableTreeNode root;
22     private DefaultTreeModel model;
23     private JTree tree;
24     private JTextField textField;
25     private JTextArea textArea;
26
27     public ClassTreeFrame()
28     {
29         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
30
31         // the root of the class tree is Object
32         root = new
33             DefaultMutableTreeNode(java.lang.Object.class);
34         model = new DefaultTreeModel(root);
35         tree = new JTree(model);
36
37         // add this class to populate the tree with some data
38         addClass(getClass());
39
40         // set up node icons
41         var renderer = new ClassNameTreeCellRenderer();
```

```
40         renderer.setClosedIcon(new
41             ImageIcon(getClass().getResource("red-ball.gif")));
42         renderer.setOpenIcon(new
43             ImageIcon(getClass().getResource("yellow-ball.gif")));
44         renderer.setLeafIcon(new
45             ImageIcon(getClass().getResource("blue-ball.gif")));
46         tree.setCellRenderer(renderer);
47
48         // set up selection mode
49         tree.addTreeSelectionListener(event ->
50             {
51                 // the user selected a different node--update
52                 // description
53                 TreePath path = tree.getSelectionPath();
54                 if (path == null) return;
55                 var selectedNode = (DefaultMutableTreeNode)
56                     path.getLastPathComponent();
57                 Class<?> c = (Class<?>)
58                     selectedNode.getUserObject();
59                 String description = getFieldDescription(c);
60                 textArea.setText(description);
61             });
62         int mode = TreeSelectionModel.SINGLE_TREE_SELECTION;
63         tree.getSelectionModel().setSelectionMode(mode);
64
65         // this text area holds the class description
66         textArea = new JTextArea();
67
68         // add tree and text area
69         var panel = new JPanel();
70         panel.setLayout(new GridLayout(1, 2));
71         panel.add(new JScrollPane(tree));
72         panel.add(new JScrollPane(textArea));
73
74         add(panel, BorderLayout.CENTER);
75
76         addTextField();
77     }
```

```
72
73     /**
74      * Add the text field and "Add" button to add a new class.
75      */
76     public void addTextField()
77     {
78         var panel = new JPanel();
79
80         ActionListener addListener = event ->
81         {
82             // add the class whose name is in the text field
83             try
84             {
85                 String text = textField.getText();
86                 addClass(Class.forName(text)); // clear text
87                 textField.setText("");
88             }
89             catch (ClassNotFoundException e)
90             {
91                 JOptionPane.showMessageDialog(null, "Class not
92                 found");
93             }
94         };
95         // new class names are typed into this text field
96         textField = new JTextField(20);
97         textField.addActionListener(addListener);
98         panel.add(textField);
99
100        var addButton = new JButton("Add");
101        addButton.addActionListener(addListener);
102        panel.add(addButton);
103
104        add(panel, BorderLayout.SOUTH);
105    }
106
107    /**

```

```
108     * Finds an object in the tree.
109     * @param obj the object to find
110     * @return the node containing the object or null if the
111     * object is not present in the tree
112     */
113     public DefaultMutableTreeNode findUserObject(Object obj)
114     {
115         // find the node containing a user object
116         var e = (Enumeration<TreeNode>)
117         root.breadthFirstEnumeration();
118         while (e.hasMoreElements())
119         {
120             var node = (DefaultMutableTreeNode)
121             e.nextElement();
122             if (node.getUserObject().equals(obj)) return node;
123         }
124         return null;
125     }
126     /**
127      * Adds a new class and any parent classes that aren't
128      * yet part of the tree.
129      * @param c the class to add
130      * @return the newly added node
131      */
132     public DefaultMutableTreeNode addClass(Class<?> c)
133     {
134         // add a new class to the tree
135         // skip non-class types
136         if (c.isInterface() || c.isPrimitive()) return null;
137         // if the class is already in the tree, return its
138         // node
139         DefaultMutableTreeNode node = findUserObject(c);
140         if (node != null) return node;
141
142         // class isn't present--first add class parent
```

```
recursively
141
142     Class<?> s = c.getSuperclass();
143
144     DefaultMutableTreeNode parent;
145     if (s == null) parent = root;
146     else parent = addClass(s);
147
148     // add the class as a child to the parent
149     var newNode = new DefaultMutableTreeNode(c);
150     model.insertNodeInto(newNode, parent,
151                         parent getChildCount());
152
153     // make node visible
154     var path = new TreePath(model.getPathToRoot(newNode));
155     tree.makeVisible(path);
156
157     return newNode;
158 }
159 /**
160  * Returns a description of the fields of a class.
161  * @param c the class to be described
162  * @return a string containing all field types and names
163 */
164 public static String getFieldDescription(Class<?> c)
165 {
166     // use reflection to find types and names of fields
167     var r = new StringBuilder();
168     Field[] fields = c.getDeclaredFields();
169     for (int i = 0; i < fields.length; i++)
170     {
171         Field f = fields[i];
172         if ((f.getModifiers() & Modifier.STATIC) != 0)
173             r.append("static ");
174         r.append(f.getType().getName());
175         r.append(" ");
176         r.append(f.getName());
```

```
176         r.append("\n");
177     }
178     return r.toString();
179 }
180 }
```

Listing 11.11

treeRender/ClassNameTreeCellRenderer.java

[Click here to view code image](#)

```
1 package treeRender;
2
3 import java.awt.*;
4 import java.lang.reflect.*;
5 import javax.swing.*;
6 import javax.swing.tree.*;
7
8 /**
9  * This class renders a class name either in plain or italic.
10 * Abstract classes are italic.
11 */
12 public class ClassNameTreeCellRenderer extends
13 DefaultTreeCellRenderer
14 {
15     private Font plainFont = null;
16     private Font italicFont = null;
17
18     public Component getTreeCellRendererComponent(JTree tree,
19 Object value, boolean selected,
20             boolean expanded, boolean leaf, int row, boolean
21 hasFocus)
22     {
23         super.getTreeCellRendererComponent(tree, value,
24 selected, expanded, leaf,
25             row, hasFocus);
26         // get the user object
27         var node = (DefaultMutableTreeNode) value;
```

```
23         Class<?> c = (Class<?>) node.getUserObject();
24
25         // the first time, derive italic font from plain font
26         if (plainFont == null)
27         {
28             plainFont = getFont();
29             // the tree cell renderer is sometimes called with
a label that has a null font
30             if (plainFont != null) italicFont =
plainFont.deriveFont(Font.ITALIC);
31         }
32
33         // set font to italic if the class is abstract, plain
otherwise
34         if ((c.getModifiers() & Modifier.ABSTRACT) == 0)
setFont(plainFont);
35         else setFont(italicFont);
36         return this;
37     }
38 }
```

javax.swing.JTree 1.2

- TreePath getSelectionPath()
- TreePath[] getSelectionPaths()

return the first selected path, or an array of paths to all selected nodes. If no paths are selected, both methods return null.

javax.swing.event.TreeSelectionListener 1.2

- void valueChanged(TreeSelectionEvent event)

is called whenever nodes are selected or deselected.

javax.swing.event.TreeSelectionEvent 1.2

- TreePath getPath()
- TreePath[] getPaths()

get the first path or all paths that have *changed* in this selection event. If you want to know the current selection, not the selection change, call JTree.getSelectionPaths instead.

11.2.5 Custom Tree Models

In the final example, we implement a program that inspects the contents of an object, just like a debugger does (see [Figure 11.30](#)).



Figure 11.30 An object inspection tree

Before going further, compile and run the example program. Each node corresponds to an instance field. If the field is an object, expand it to see *its* instance fields. The program inspects the contents of the frame window. If you poke around a few of the instance fields, you should be able to find some familiar classes. You'll also gain some respect for how complex the Swing user interface components are under the hood.

What's remarkable about the program is that the tree does not use the `DefaultTreeModel`. If you already have data that are hierarchically organized, you might not want to build a duplicate tree and worry about keeping both trees synchronized. That is the situation in our case—the inspected objects are already linked to each other through the object references, so there is no need to replicate the linking structure.

The `TreeModel` interface has only a handful of methods. The first group of methods enables the `JTree` to find the tree nodes by first getting the root, then the children. The `JTree` class calls these methods only when the user actually expands a node.

[Click here to view code image](#)

```
Object getRoot()  
int getChildCount(Object parent)  
Object getChild(Object parent, int index)
```

This example shows why the `TreeModel` interface, like the `JTree` class itself, does not need an explicit notion of nodes. The root and its children can be any objects. The `TreeModel` is responsible for telling the `JTree` how they are connected.

The next method of the `TreeModel` interface is the reverse of `getChild`:

[Click here to view code image](#)

```
int getIndexOfChild(Object parent, Object child)
```

Actually, this method can be implemented in terms of the first three—see the code in [Listing 11.12](#).

The tree model tells the JTree which nodes should be displayed as leaves:

[Click here to view code image](#)

```
boolean isLeaf(Object node)
```

If your code changes the tree model, the tree needs to be notified so it can redraw itself. The tree adds itself as a TreeModelListener to the model. Thus, the model must support the usual listener management methods:

[Click here to view code image](#)

```
void addTreeModelListener(TreeModelListener l)  
void removeTreeModelListener(TreeModelListener l)
```

You can see the implementations for these methods in [Listing 11.13](#).

When the model modifies the tree contents, it calls one of the four methods of the TreeModelListener interface:

[Click here to view code image](#)

```
void treeNodesChanged(TreeModelEvent e)  
void treeNodesInserted(TreeModelEvent e)  
void treeNodesRemoved(TreeModelEvent e)  
void treeStructureChanged(TreeModelEvent e)
```

The TreeModelEvent object describes the location of the change. The details of assembling a tree model event that describes an insertion or removal event are quite technical. You only need to worry about firing these events if your tree can actually have nodes added and removed. In [Listing 11.12](#), we show how to fire one event by replacing the root with a new object.



Tip

To simplify the code for event firing, use the `javax.swing.EventListenerList` convenience class that collects listeners. The last three methods of Listing 11.13 show how to use the class.

Finally, if the user edits a tree node, your model is called with the change:

[Click here to view code image](#)

```
void valueForPathChanged(TreePath path, Object newValue)
```

If you don't allow editing, this method is never called.

If you don't need to support editing, constructing a tree model is easily done. Implement the three methods:

[Click here to view code image](#)

```
Object getRoot()  
int getChildCount(Object parent)  
Object getChild(Object parent, int index)
```

These methods describe the structure of the tree. Supply routine implementations of the other five methods, as in Listing 11.12. You are then ready to display your tree.

Now let's turn to the implementation of the example program. Our tree will contain objects of type `Variable`.



Note

Had we used the `DefaultTreeModel`, our nodes would have been objects of type `DefaultMutableTreeNode` with *user objects* of type `Variable`.

For example, suppose you inspect the variable

```
Employee joe;
```

That variable has a *type* `Employee.class`, a *name* "joe", and a *value* —the value of the object reference `joe`. In Listing 11.14, we define a class `Variable` that describes a variable in a program:

[Click here to view code image](#)

```
var v = new Variable(Employee.class, "joe", joe);
```

If the type of the variable is a primitive type, you must use an object wrapper for the value.

[Click here to view code image](#)

```
new Variable(double.class, "salary", Double.valueOf(salary));
```

If the type of the variable is a class, the variable has *fields*. Using reflection, we enumerate all fields and collect them in an `ArrayList`. Since the `getFields` method of the `Class` class does not return the fields of the superclass, we need to call `getFields` on all superclasses as well. You can find the code in the `Variable` constructor. The `getFields` method of our `Variable` class returns the array of fields. Finally, the `toString` method of the `Variable` class formats the node label. The label always contains the variable type and name. If the variable is not a class, the label also contains the value.



Note

If the type is an array, we do not display the elements of the array. This would not be difficult to do; I leave it as the proverbial “exercise for the reader.”

Let's move on to the tree model. The first two methods are simple.

[Click here to view code image](#)

```

public Object getRoot()
{
    return root;
}
public int getChildCount(Object parent)
{
    return ((Variable) parent).getFields().size();
}

```

The getChild method returns a new Variable object that describes the field with the given index. The getType and getName methods of the Field class yield the field type and name. By using reflection, you can read the field value as f.get(parentValue). That method can throw an IllegalAccessException. However, we made all fields accessible in the Variable constructor, so this won't happen in practice.

Here is the complete code of the getChild method:

[Click here to view code image](#)

```

public Object getChild(Object parent, int index)
{
    ArrayList fields = ((Variable) parent).getFields();
    var f = (Field) fields.get(index);
    Object parentValue = ((Variable) parent).getValue();
    try
    {
        return new Variable(f.getType(), f.getName(),
f.get(parentValue));
    }
    catch (IllegalAccessException e)
    {
        return null;
    }
}

```

These three methods reveal the structure of the object tree to the JTree component. The remaining methods are routine—see the source code in

Listing 11.13.

There is one remarkable fact about this tree model: It actually describes an *infinite* tree. You can verify this by following one of the WeakReference objects. Click on the variable named referent. It leads you right back to the original object. You get an identical subtree, and you can open its WeakReference object again, ad infinitum. Of course, you cannot *store* an infinite set of nodes; the tree model simply generates the nodes on demand as the user expands the parents. Listing 11.12 shows the frame class of the sample program.

Listing 11.12 treeModel/ObjectInspectorFrame.java

[Click here to view code image](#)

```
1 package treeModel;
2
3 import java.awt.*;
4 import javax.swing.*;
5
6 /**
7  * This frame holds the object tree.
8 */
9 public class ObjectInspectorFrame extends JFrame
10 {
11     private JTree tree;
12     private static final int DEFAULT_WIDTH = 400;
13     private static final int DEFAULT_HEIGHT = 300;
14
15     public ObjectInspectorFrame()
16     {
17         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
18
19         // we inspect this frame object
20
21         var v = new Variable(getClass(), "this", this);
22         var model = new ObjectTreeModel();
23         model.setRoot(v);
```

```
24
25      // construct and show tree
26
27      tree = new JTree(model);
28      add(new JScrollPane(tree), BorderLayout.CENTER);
29  }
30 }
```

Listing 11.13 treeModel/ObjectTreeModel.java

[Click here to view code image](#)

```
1 package treeModel;
2
3 import java.lang.reflect.*;
4 import java.util.*;
5 import javax.swing.event.*;
6 import javax.swing.tree.*;
7
8 /**
9  * This tree model describes the tree structure of a Java
10 * object. Children are the objects
11 * that are stored in instance variables.
12 */
13 public class ObjectTreeModel implements TreeModel
14 {
15     private Variable root;
16     private EventListenerList listenerList = new
17     EventListenerList();
18
19 /**
20  * Constructs an empty tree.
21 */
22 public ObjectTreeModel()
23 {
24     root = null;
25 }
```

```

25     /**
26      * Sets the root to a given variable.
27      * @param v the variable that is being described by this
tree
28     */
29     public void setRoot(Variable v)
30     {
31         Variable oldRoot = v;
32         root = v;
33         fireTreeStructureChanged(oldRoot);
34     }
35
36     public Object getRoot()
37     {
38         return root;
39     }
40
41     public int getChildCount(Object parent)
42     {
43         return ((Variable) parent).getFields().size();
44     }
45
46     public Object getChild(Object parent, int index)

```

[Click here to view code image](#)

```

47     {
48         ArrayList<Field> fields = ((Variable)
parent).getFields();
49         var f = (Field) fields.get(index);
50         Object parentValue = ((Variable) parent).getValue();
51         try
52         {
53             return new Variable(f.getType(), f.getName(),
f.get(parentValue));
54         }
55         catch (IllegalAccessException e)
56         {
57             return null;

```

```
58         }
59     }
60
61     public int getChildIndex(Object parent, Object child)
62     {
63         int n = getChildCount(parent);
64         for (int i = 0; i < n; i++)
65             if (getChild(parent, i).equals(child)) return i;
66         return -1;
67     }
68
69     public boolean isLeaf(Object node)
70     {
71         return getChildCount(node) == 0;
72     }
73
74     public void valueForPathChanged(TreePath path, Object
newValue)
75     {
76     }
77
78     public void addTreeModelListener(TreeModelListener l)
79     {
80         listenerList.add(TreeModelListener.class, l);
81     }
82
83     public void removeTreeModelListener(TreeModelListener l)
84     {
85         listenerList.remove(TreeModelListener.class, l);
86     }
87
88     protected void fireTreeStructureChanged(Object oldRoot)
89     {
90         var event = new TreeModelEvent(this, new Object[] {
oldRoot });
91         for (TreeModelListener l :
listenerList.getListeners(TreeModelListener.class))
92             l.treeStructureChanged(event);
```

```
93      }
94  }
```

Listing 11.14 treeModel/Variable.java

[Click here to view code image](#)

```
1  package treeModel;
2
3  import java.lang.reflect.*;
4  import java.util.*;
5
6  /**
7   * A variable with a type, name, and value.
8   */
9  public class Variable
10 {
11     private Class<?> type;
12     private String name;
13     private Object value;
14     private ArrayList<Field> fields;
15
16     /**
17      * Construct a variable.
18      * @param aType the type
19      * @param aName the name
20      * @param aValue the value
21      */
22     public Variable(Class<?> aType, String aName, Object
23 aValue)
24     {
25         type = aType;
26         name = aName;
27         value = aValue;
28         fields = new ArrayList<>();
29
30         // find all fields if we have a class type except we
31         // don't expand strings and
```

```

30          // null values
31
32          if (!type.isPrimitive() && !type.isArray() &&
33              !type.equals(String.class)
34              && value != null)
35          {
36              // get fields from the class and all
37              // superclasses
38              for (Class<?> c = value.getClass(); c != null;
39                  c = c.getSuperclass())
39              {
40                  Field[] fs = c.getDeclaredFields();
41                  AccessibleObject.setAccessible(fs, true);
42
43                  // get all nonstatic fields
44                  for (Field f : fs)
45                      if ((f.getModifiers() & Modifier.STATIC)
46                      == 0) fields.add(f);
47
48          }
49
50      }
51
52  }

```

[Click here to view code image](#)

```

47
48      /**
49      * Gets the value of this variable.
50      * @return the value
51      */
52      public Object getValue()
53      {
54          return value;
55      }
56
57      /**
58      * Gets all nonstatic fields of this variable.
59      * @return an array list of variables describing the
60      fields
61      */

```

```
61     public ArrayList<Field> getFields()
62     {
63         return fields;
64     }
65
66     public String toString()
67     {
68         String r = type + " " + name;
69         if (type.isPrimitive()) r += "=" + value;
70         else if (type.equals(String.class)) r += "=" + value;
71         else if (value == null) r += "=null";
72         return r;
73     }
74 }
```

javax.swing.tree.TreeModel 1.2

- `Object getRoot()`
returns the root node.
- `int getChildCount(Object parent)`
gets the number of children of the parent node.
- `Object getChild(Object parent, int index)`
gets the child node of the parent node at the given index.
- `int getIndexOfChild(Object parent, Object child)`
gets the index of the child node in the parent node, or -1 if child is not a child of parent in this tree model.
- `boolean isLeaf(Object node)`
returns true if node is conceptually a leaf of the tree.

- void addTreeModelListener(TreeModelListener l)
- void removeTreeModelListener(TreeModelListener l)

add or remove listeners that are notified when the information in the tree model changes.

- void valueForPathChanged(TreePath path, Object newValue)

is called when a cell editor has modified the value of a node.

Parameter s: path The path to the node that has been edited

newValue The replacement value returned by the editor

javax.swing.event.TreeModelListener 1.2

- void treeNodesChanged(TreeModelEvent e)
- void treeNodesInserted(TreeModelEvent e)
- void treeNodesRemoved(TreeModelEvent e)
- void treeStructureChanged(TreeModelEvent e)

are called by the tree model when the tree has been modified.

javax.swing.event.TreeModelEvent 1.2

- TreeModelEvent (Object eventSource, TreePath node)

constructs a tree model event.

| | | |
|------------------|--------------------------|--------------------------------------|
| <i>Parameter</i> | <code>eventSource</code> | The tree model generating this event |
| <code>s:</code> | <code>ce</code> | |

| | | |
|------------------|-------------------|--|
| <i>Parameter</i> | <code>node</code> | The path to the node that is being changed |
|------------------|-------------------|--|

11.3 Advanced AWT

You can use the methods of the `Graphics` class to create simple drawings. Those methods are sufficient for simple applications, but they fall short when you need to create complex shapes or require complete control over the appearance of the graphics. The Java 2D API is a more sophisticated class library that you can use to produce high-quality drawings. In the following sections, I'll give you an overview of that API.

11.3.1 The Rendering Pipeline

The original JDK 1.0 had a very simple mechanism for drawing shapes. You selected color and paint mode, and called methods of the `Graphics` class such as `drawRect` or `fillOval`. The Java 2D API supports many more options.

- You can easily produce a wide variety of *shapes*.
- You have control over the *stroke*—the pen that traces shape boundaries.
- You can *fill* shapes with solid colors, varying hues, and repeating patterns.
- You can use *transformations* to move, scale, rotate, or stretch shapes.
- You can *clip* shapes to restrict them to arbitrary areas.
- You can select *composition rules* to describe how to combine the pixels of a new shape with existing pixels.

To draw a shape, go through the following steps:

1. Obtain an object of the `Graphics2D` class. This class is a subclass of the `Graphics` class. Ever since Java 1.2, methods such as `paint` and `paintComponent` automatically receive an object of the `Graphics2D` class. Simply use a cast, as follows:

[Click here to view code image](#)

```
public void paintComponent(Graphics g)
{
    var g2 = (Graphics2D) g;
    . . .
}
```

2. Use the `setRenderingHints` method to set *rendering hints*—trade-offs between speed and drawing quality.

[Click here to view code image](#)

```
RenderingHints hints = . . .;
g2.setRenderingHints(hints);
```

3. Use the `setStroke` method to set the *stroke*. The stroke draws the outline of the shape. You can select the thickness and choose among solid and dotted lines.

```
Stroke stroke = . . .;
g2.setStroke(stroke);
```

4. Use the `setPaint` method to set the *paint*. The paint fills areas such as the stroke or the interior of a shape. You can create solid color paint, paint with changing hues, or tiled fill patterns.

```
Paint paint = . . .;
g2.setPaint(paint);
```

5. Use the `clip` method to set the *clipping region*.

```
Shape clip = . . .;
g2.clip(clip);
```

6. Use the `transform` method to set a *transformation* from user space to device space. Use transformations if it is easier for you to define your shapes in a custom coordinate system than by using pixel coordinates.

[Click here to view code image](#)

```
AffineTransform transform = . . .;  
g2.transform(transform);
```

7. Use the `setComposite` method to set a *composition rule* that describes how to combine the new pixels with the existing pixels.

```
Composite composite = . . .;  
g2.setComposite(composite);
```

8. Create a shape. The Java 2D API supplies many shape objects and methods to combine shapes.

```
Shape shape = . . .;
```

9. Draw or fill the shape. If you draw the shape, its outline is stroked. If you fill the shape, the interior is painted.

```
g2.draw(shape);  
g2.fill(shape);
```

Of course, in many practical circumstances, you don't need all these steps. There are reasonable defaults for the settings of the 2D graphics context; change the settings only if you want to deviate from the defaults.

In the following sections, you will see how to describe shapes, strokes, paints, transformations, and composition rules.

The various `set` methods simply set the state of the 2D graphics context. They don't cause any drawing. Similarly, when you construct `Shape` objects, no drawing takes place. A shape is only rendered when you call `draw` or `fill`. At that time, the new shape is computed in a *rendering pipeline* (see [Figure 11.31](#)).




Figure 11.31 The rendering pipeline

In the rendering pipeline, the following steps take place to render a shape:

1. The path of the shape is stroked.
2. The shape is transformed.
3. The shape is clipped. If there is no intersection between the shape and the clipping area, the process stops.
4. The remainder of the shape after clipping is filled.
5. The pixels of the filled shape are composed with the existing pixels. (In [Figure 11.31](#), the circle is part of the existing pixels, and the cup shape is superimposed over it.)

In the next section, you will see how to define shapes. Then, we will turn to the 2D graphics context settings.

java.awt.Graphics2D 1.2

- `void draw(Shape s)`

draws the outline of the given shape with the current paint.

- `void fill(Shape s)`

fills the interior of the given shape with the current paint.

11.3.2 Shapes

Here are some of the methods in the `Graphics` class to draw shapes:

```
drawLine  
drawRectangle  
drawRoundRect  
draw3DRect  
drawPolygon  
drawPolyline  
drawOval  
drawArc
```

There are also corresponding `fill` methods. These methods have been in the `Graphics` class ever since JDK 1.0. The Java 2D API uses a completely different, object-oriented approach. Instead of methods, there are classes:

```
Line2D  
Rectangle2D  
RoundRectangle2D  
Ellipse2D  
Arc2D  
QuadCurve2D  
  
CubicCurve2D  
GeneralPath
```

These classes all implement the `Shape` interface, which we will examine in the following sections.

11.3.2.1 The Shape Class Hierarchy

The `Line2D`, `Rectangle2D`, `RoundRectangle2D`, `Ellipse2D`, and `Arc2D` classes correspond to the `drawLine`, `drawRectangle`, `drawRoundRect`, `drawOval`, and `drawArc` methods. (The concept of a “3D rectangle” has died the death it so richly deserved—there is no

analog to the `draw3DRect` method.) The Java 2D API supplies two additional classes, quadratic and cubic curves, that we will discuss in this section. There is no `Polygon2D` class; instead, the `GeneralPath` class describes paths made up from lines, quadratic and cubic curves. You can use a `GeneralPath` to describe a polygon; we'll show you how later in this section.

To draw a shape, first create an object of a class that implements the `Shape` interface and then call the `draw` method of the `Graphics2D` class.

The classes

```
Rectangle2D  
RoundRectangle2D  
Ellipse2D  
Arc2D
```

all inherit from a common superclass `RectangularShape`. Admittedly, ellipses and arcs are not rectangular, but they have a *bounding rectangle* (see [Figure 11.32](#)).




Figure 11.32 The bounding rectangle of an ellipse and an arc

Each of the classes with a name ending in “2D” has two subclasses for specifying coordinates as `float` or `double` quantities. In Volume I, you already encountered `Rectangle2D.Float` and `Rectangle2D.Double`.

The same scheme is used for the other classes, such as `Arc2D.Float` and `Arc2D.Double`.

Internally, all graphics classes use float coordinates because float numbers use less storage space but have sufficient precision for geometric computations. However, the Java programming language makes it a bit more tedious to manipulate float numbers. For that reason, most methods of the graphics classes use double parameters and return values. Only when constructing a 2D object you need to choose between the constructors with float and double coordinates. For example,

[Click here to view code image](#)

```
var floatRect = new Rectangle2D.Float(5F, 10F, 7.5F, 15F);  
var doubleRect = new Rectangle2D.Double(5, 10, 7.5, 15);
```

The Xxx2D.Float and Xxx2D.Double classes are subclasses of the Xxx2D classes. After object construction, essentially no benefit accrues from remembering the subclass, and you can just store the constructed object in a superclass variable as in the code example above.

As you can see from the curious names, the Xxx2D.Float and Xxx2D.Double classes are also inner classes of the Xxx2D classes. That is just a minor syntactical convenience to avoid inflation of outer class names.

Finally, the Point2D class describes a point with an *x* and a *y* coordinate. Points are used to define shapes, but they aren't themselves shapes.

[Figure 11.33](#) shows the relationships between the shape classes. However, the Double and Float subclasses are omitted. Legacy classes from the pre-2D library are marked with a gray fill.




Figure 11.33 Relationships between the shape classes

11.3.2.2 Using the Shape Classes

You already saw how to use the Rectangle2D, Ellipse2D, and Line2D classes in Volume I, [Chapter 10](#). In this section, you will learn

how to work with the remaining 2D shapes.

For the `RoundRectangle2D` shape, specify the top left corner, width, height, and the *x* and *y* dimensions of the corner area that should be rounded (see [Figure 11.34](#)). For example, the call




Figure 11.34 Constructing a `RoundRectangle2D`

[Click here to view code image](#)

```
var r = new RoundRectangle2D.Double(150, 200, 100, 50, 20, 20);
```

produces a rounded rectangle with circles of radius 20 at each of the corners.

To construct an arc, specify the bounding box, the start angle, the angle swept out by the arc (see [Figure 11.35](#)), and the closure type—one of `Arc2D.OPEN`, `Arc2D.PIE`, or `Arc2D.CHORD`.




Figure 11.35 Constructing an elliptical arc

[Click here to view code image](#)

```
var a = new Arc2D(x, y, width, height, startAngle, arcAngle,  
closureType);
```

[Figure 11.36](#) illustrates the arc types.




Figure 11.36 Arc types



Caution

If the arc is elliptical, the computation of the arc angles is not at all straightforward. The API documentation states: “The angles are specified relative to the nonsquare framing rectangle such that 45 degrees always falls on the line from the center of the ellipse to the upper right corner of the framing rectangle. As a result, if the framing rectangle is noticeably longer along one axis than the other, the angles to the start and end of the arc segment will be

skewed farther along the longer axis of the frame.” Unfortunately, the documentation is silent on how to compute this “skew.” Here are the details:

Suppose the center of the arc is the origin and the point (x , y) lies on the arc. You can get a skewed angle with the following formula:

[Click here to view code image](#)

```
skewedAngle = Math.toDegrees(Math.atan2(-y * height, x * width));
```

The result is a value between -180 and 180 . Compute the skewed start and end angles in this way. Then, compute the difference between the two skewed angles. If the start angle or the difference is negative, add 360 to the start angle. Then, supply the start angle and the difference to the arc constructor.

If you run the example program at the end of this section, you can visually check that this calculation yields the correct values for the arc constructor (see [Figure 11.39](#) on p. 682).

The Java 2D API supports *quadratic* and *cubic* curves. In this chapter, we do not get into the mathematics of these curves. You can get a feel for how the curves look by running the program in [Listing 11.15](#). As you can see in [Figures 11.37](#) and [11.38](#), quadratic and cubic curves are specified by two *end points* and one or two *control points*. Moving the control points changes the shape of the curves.




Figure 11.37 A quadratic curve




Figure 11.38 A cubic curve

To construct quadratic and cubic curves, give the coordinates of the end points and the control points. For example,

[Click here to view code image](#)

```
var q = new QuadCurve2D.Double(startX, startY, controlX,  
controlY, endX, endY);  
var c = new CubicCurve2D.Double(startX, startY, control1X,  
control1Y,  
control2X, control2Y, endX, endY);
```

Quadratic curves are not very flexible, and they are not commonly used in practice. Cubic curves (such as the Bézier curves drawn by the `CubicCurve2D` class) are, however, very common. By combining many cubic curves so that the slopes at the connection points match, you can create complex, smooth-looking curved shapes. For more information, refer to *Computer Graphics: Principles and Practice, Third Edition*, by John F. Hughes et al.

You can build arbitrary sequences of line segments, quadratic curves, and cubic curves, and store them in a `GeneralPath` object. Specify the first coordinate of the path with the `moveTo` method, for example:

[Click here to view code image](#)

```
var path = new GeneralPath();
path.moveTo(10, 20);
```

You can then extend the path by calling one of the methods `lineTo`, `quadTo`, or `curveTo`. These methods extend the path by a line, a quadratic curve, or a cubic curve. To call `lineTo`, supply the end point. For the two curve methods, supply the control points, then the end point. For example,

[Click here to view code image](#)

```
path.lineTo(20, 30);
path.curveTo(control1X, control1Y, control2X, control2Y, endX,
endY);
```

Close the path by calling the `closePath` method. It draws a straight line back to the starting point of the path.

To make a polygon, simply call `moveTo` to go to the first corner point, followed by repeated calls to `lineTo` to visit the other corner points. Finally, call `closePath` to close the polygon. The program in [Listing 11.15](#) shows this in more detail.

A general path does not have to be connected. You can call `moveTo` at any time to start a new path segment.

Finally, you can use the `append` method to add arbitrary `Shape` objects to a general path. The outline of the shape is added to the end to the path. The second parameter of the `append` method is `true` if the new shape should be connected to the last point on the path, `false` otherwise. For example, the call

```
Rectangle2D r = . . .;
path.append(r, false);
```

appends the outline of a rectangle to the path without connecting it to the existing path. But

```
path.append(r, true);
```

adds a straight line from the end point of the path to the starting point of the rectangle, and then adds the rectangle outline to the path.

The program in [Listing 11.15](#) lets you create sample paths. [Figures 11.37](#) and [11.38](#) show sample runs of the program. You can pick a shape maker from the combo box. The program contains shape makers for

- Straight lines
- Rectangles, rounded rectangles, and ellipses
- Arcs (showing lines for the bounding rectangle and the start and end angles, in addition to the arc itself)
- Polygons (using a `GeneralPath`)
- Quadratic and cubic curves

Use the mouse to adjust the control points. As you move them, the shape continuously repaints itself.

The program is a bit complex because it handles multiple shapes and supports dragging of the control points.

An abstract superclass `ShapeMaker` encapsulates the commonality of the shape maker classes. Each shape has a fixed number of control points that the user can move around. The `getPointCount` method returns that value. The abstract method

```
Shape makeShape(Point2D[] points)
```

computes the actual shape, given the current positions of the control points. The `toString` method returns the class name so that the `ShapeMaker` objects can simply be dumped into a `JComboBox`.

To enable dragging of the control points, the `ShapePanel` class handles both mouse and mouse motion events. If the mouse is pressed on top of a rectangle, subsequent mouse drags move the rectangle.

The majority of the shape maker classes are simple—their `makeShape` methods just construct and return the requested shapes. However, the `ArcMaker` class needs to compute the distorted start and end angles. Furthermore, to demonstrate that the computation is indeed correct, the returned shape is a `GeneralPath` containing the arc itself, the bounding rectangle, and the lines from the center of the arc to the angle control points (see [Figure 11.39](#)).




Figure 11.39 The ShapeTest program

Listing 11.15 `shape/ShapeTest.java`

[Click here to view code image](#)

```
1 package shape;
2
3 import java.awt.*;
4 import java.awt.event.*;
5 import java.awt.geom.*;
6 import java.util.*;
7 import javax.swing.*;
8
9 /**
10  * This program demonstrates the various 2D shapes.
11  * @version 1.04 2018-05-01
12  * @author Cay Horstmann
13  */
14 public class ShapeTest
15 {
16     public static void main(String[] args)
17     {
18         EventQueue.invokeLater(() ->
19         {
20             var frame = new ShapeTestFrame();
21             frame.setTitle("ShapeTest");
22
23             frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
24             frame.setVisible(true);
25         });
26     }
27
28 /**
29  * This frame contains a combo box to select a shape and a
30  * component to draw it.
31  */
32 class ShapeTestFrame extends JFrame
33 {
34     public ShapeTestFrame()
35     {
36         var comp = new ShapeComponent();
37         add(comp, BorderLayout.CENTER);
```

```
37     var comboBox = new JComboBox<ShapeMaker>();
38     comboBox.addItem(new LineMaker());
39     comboBox.addItem(new RectangleMaker());
40     comboBox.addItem(new RoundRectangleMaker());
41     comboBox.addItem(new EllipseMaker());
42     comboBox.addItem(new ArcMaker());
43     comboBox.addItem(new PolygonMaker());
44     comboBox.addItem(new QuadCurveMaker());
45     comboBox.addItem(new CubicCurveMaker());
46     comboBox.addActionListener(event ->
47     {
48         ShapeMaker shapeMaker =
49             comboBox.getSelectedItem();
50         comp.setShapeMaker(shapeMaker);
51     });
52     add(comboBox, BorderLayout.NORTH);
53     comp.setShapeMaker((ShapeMaker) comboBox.getSelectedItem());
54     pack();
55 }
56
57 /**
58 * This component draws a shape and allows the user to move
59 the points that define it.
60 */
61 class ShapeComponent extends JComponent
62 {
63     private static final Dimension PREFERRED_SIZE = new
64 Dimension(300, 200);
65     private Point2D[] points;
66     private static Random generator = new Random();
67     private static int SIZE = 10;
68     private int current;
69     private ShapeMaker shapeMaker;
70
71     public ShapeComponent()
72     {
73         addMouseListener(new MouseAdapter()
```

```
72      {
73          public void mousePressed(MouseEvent event)
74          {
75              Point p = event.getPoint();
76              for (int i = 0; i < points.length; i++)
77              {
78                  double x = points[i].getX() - SIZE / 2;
79                  double y = points[i].getY() - SIZE / 2;
80                  var r = new Rectangle2D.Double(x, y, SIZE,
SIZE);
81                  if (r.contains(p))
82                  {
83                      current = i;
84                      return;
85                  }
86              }
87          }
88
89          public void mouseReleased(MouseEvent event)
90          {
91              current = -1;
92          }
93      );
94      addMouseMotionListener(new MouseMotionAdapter()
95      {
96          public void mouseDragged(MouseEvent event)
97          {
98              if (current == -1) return;
99              points[current] = event.getPoint();
100             repaint();
101         }
102     );
103     current = -1;
104 }
105
106 /**
107 * Set a shape maker and initialize it with a random
point set.
```

```
108     * @param aShapeMaker a shape maker that defines a shape
109     * from a point set
110     */
111     public void setShapeMaker(ShapeMaker aShapeMaker)
112     {
113         shapeMaker = aShapeMaker;
114         int n = shapeMaker.getPointCount();
115         points = new Point2D[n];
116         for (int i = 0; i < n; i++)
117         {
118             double x = generator.nextDouble() * getWidth();
119             double y = generator.nextDouble() * getHeight();
120             points[i] = new Point2D.Double(x, y);
121         }
122         repaint();
123     }
124     public void paintComponent(Graphics g)
125     {
126         if (points == null) return;
127         var g2 = (Graphics2D) g;
128         for (int i = 0; i < points.length; i++)
129         {
130             double x = points[i].getX() - SIZE / 2;
131             double y = points[i].getY() - SIZE / 2;
132             g2.fill(new Rectangle2D.Double(x, y, SIZE, SIZE));
133         }
134         g2.draw(shapeMaker.makeShape(points));
135     }
136 }
137
138     public Dimension getPreferredSize() { return
139     PREFERRED_SIZE; }
140
141 /**
142     * A shape maker can make a shape from a point set. Concrete
143     * subclasses must return a shape in
```

```
143     * the makeShape method.
144     */
145 abstract class ShapeMaker
146 {
147     private int pointCount;
148
149     /**
150      * Constructs a shape maker.
151      * @param pointCount the number of points needed to
define this shape
152      */
153     public ShapeMaker(int pointCount)
154     {
155         this.pointCount = pointCount;
156     }
157
158     /**
159      * Gets the number of points needed to define this shape.
160      * @return the point count
161      */
162     public int getPointCount()
163     {
164         return pointCount;
165     }
166
167     /**
168      * Makes a shape out of the given point set.
169      * @param p the points that define the shape
170      * @return the shape defined by the points
171      */
172     public abstract Shape makeShape(Point2D[] p);
173
174     public String toString()
175     {
176         return getClass().getName();
177     }
178 }
179
```

```
180  /**
181   * Makes a line that joins two given points.
182   */
183 class LineMaker extends ShapeMaker
184 {
185     public LineMaker()
186     {
187         super(2);
188     }
189
190     public Shape makeShape(Point2D[] p)
191     {
192         return new Line2D.Double(p[0], p[1]);
193     }
194 }
195
196 /**
197  * Makes a rectangle that joins two given corner points.
198 */
199 class RectangleMaker extends ShapeMaker
200 {
201     public RectangleMaker()
202     {
203         super(2);
204     }
205
206     public Shape makeShape(Point2D[] p)
207     {
208         var s = new Rectangle2D.Double();
209         s.setFrameFromDiagonal(p[0], p[1]);
210         return s;
211     }
212 }
213
214 /**
215  * Makes a round rectangle that joins two given corner
points.
216 */
```

```
217 class RoundRectangleMaker extends ShapeMaker
218 {
219     public RoundRectangleMaker()
220     {
221         super(2);
222     }
223
224     public Shape makeShape(Point2D[] p)
225     {
226         var s = new RoundRectangle2D.Double(0, 0, 0, 0, 20,
20);
227         s.setFrameFromDiagonal(p[0], p[1]);
228         return s;
229     }
230 }
231
232 /**
233 * Makes an ellipse contained in a bounding box with two
given corner points.
234 */
235 class EllipseMaker extends ShapeMaker
236 {
237     public EllipseMaker()
238     {
239         super(2);
240     }
241
242     public Shape makeShape(Point2D[] p)
243     {
244         var s = new Ellipse2D.Double();
245         s.setFrameFromDiagonal(p[0], p[1]);
246         return s;
247     }
248 }
249
250 /**
251 * Makes an arc contained in a bounding box with two given
corner points, and with starting
```

```
252     * and ending angles given by lines emanating from the
253     * center of the bounding box and ending
254     * in two given points. To show the correctness of the angle
255     * computation, the returned shape
256     * contains the arc, the bounding box, and the lines.
257     */
258 class ArcMaker extends ShapeMaker
259 {
260     public ArcMaker()
261     {
262         super(4);
263     }
264
265     public Shape makeShape(Point2D[] p)
266     {
267         double centerX = (p[0].getX() + p[1].getX()) / 2;
268         double centerY = (p[0].getY() + p[1].getY()) / 2;
269         double width = Math.abs(p[1].getX() - p[0].getX());
270         double height = Math.abs(p[1].getY() - p[0].getY());
271
272         double skewedStartAngle = Math.toDegrees(Math.atan2(
273             (p[2].getY() - centerY) * width,
274             (p[2].getX() - centerX) * height));
275         double skewedEndAngle = Math.toDegrees(Math.atan2(
276             (p[3].getY() - centerY) * width,
277             (p[3].getX() - centerX) * height));
278         double skewedAngleDifference = skewedEndAngle -
279             skewedStartAngle;
280         if (skewedStartAngle < 0) skewedStartAngle += 360;
281         if (skewedAngleDifference < 0) skewedAngleDifference
282             += 360;
283
284         var s = new Arc2D.Double(0, 0, 0, 0,
285             skewedStartAngle, skewedAngleDifference,
286             Arc2D.OPEN);
287         s.setFrameFromDiagonal(p[0], p[1]);
288
289         var g = new GeneralPath();
```

```
283     g.append(s, false);
284     var r = new Rectangle2D.Double();
285     r.setFrameFromDiagonal(p[0], p[1]);
286     g.append(r, false);
287     var center = new Point2D.Double(centerX, centerY);
288     g.append(new Line2D.Double(center, p[2]), false);
289     g.append(new Line2D.Double(center, p[3]), false);
290     return g;
291 }
292 }
293
294 /**
295 * Makes a polygon defined by six corner points.
296 */
297 class PolygonMaker extends ShapeMaker
298 {
299     public PolygonMaker()
300     {
301         super(6);
302     }
303
304     public Shape makeShape(Point2D[] p)
305     {
306         var s = new GeneralPath();
307         s.moveTo((float) p[0].getX(), (float) p[0].getY());
308         for (int i = 1; i < p.length; i++)
309             s.lineTo((float) p[i].getX(), (float) p[i].getY());
310         s.closePath();
311         return s;
312     }
313 }
314
315 /**
316 * Makes a quad curve defined by two end points and a
control point.
317 */
318 class QuadCurveMaker extends ShapeMaker
319 {
```

```
320     public QuadCurveMaker()
321     {
322         super(3);
323     }
324
325     public Shape makeShape(Point2D[] p)
326     {
327         return new QuadCurve2D.Double(p[0].getX(),
328                                         p[0].getY(), p[1].getX(), p[1].getY(),
329                                         p[2].getX(), p[2].getY());
330     }
331
332 /**
333 * Makes a cubic curve defined by two end points and two
control points.
334 */
335 class CubicCurveMaker extends ShapeMaker
336 {
337     public CubicCurveMaker()
338     {
339         super(4);
340     }
341
342     public Shape makeShape(Point2D[] p)
343     {
344         return new CubicCurve2D.Double(p[0].getX(),
p[0].getY(), p[1].getX(), p[1].getY(),
345                                         p[2].getX(), p[2].getY(), p[3].getX(), p[3].getY());
346     }
347 }
```

java.awt.geom.RoundRectangle2D.Double 1.2

- RoundRectangle2D.Double(double x, double y,
double width, double height, double

```
arcWidth, double arcHeight)
```

constructs a rounded rectangle with the given bounding rectangle and arc dimensions. See [Figure 11.34](#) for an explanation of the `arcWidth` and `arcHeight` parameters.

java.awt.geom.Arc2D.Double 1.2

- `Arc2D.Double(double x, double y, double w, double h, double startAngle, double arcAngle, int type)`

constructs an arc with the given bounding rectangle, start and arc angle, and arc type. The `startAngle` and `arcAngle` are explained on p. [678](#). The type is one of `Arc2D.OPEN`, `Arc2D.PIE`, and `Arc2D.CHORD`.

java.awt.geom.QuadCurve2D.Double 1.2

- `QuadCurve2D.Double(double x1, double y1, double ctrlx, double ctrly, double x2, double y2)`

constructs a quadratic curve from a start point, a control point, and an end point.

java.awt.geom.CubicCurve2D.Double 1.2

- `CubicCurve2D.Double(double x1, double y1, double ctrlx1, double ctrly1, double ctrlx2,`

```
double ctrlx2, double ctrlx2, double ctrly2, double x2, double y2)
```

constructs a cubic curve from a start point, two control points, and an end point.

java.awt.geom.GeneralPath 1.2

- `GeneralPath()`

constructs an empty general path.

java.awt.geom.Path2D.Float 6

- `void moveTo(float x, float y)`

makes (x, y) the *current point*—that is, the starting point of the next segment.

- `void lineTo(float x, float y)`
- `void quadTo(float ctrlx, float ctrlx, float ctrly, float x, float y)`
- `void curveTo(float ctrl1x, float ctrl1y, float ctrl2x, float ctrl2y, float x, float y)`

draw a line, quadratic curve, or cubic curve from the current point to the end point (x, y) , and make that end point the current point.

java.awt.geom.Path2D 6

- `void append(Shape s, boolean connect)`
adds the outline of the given shape to the general path. If `connect` is true, the current point of the general path is connected to the starting point of the added shape by a straight line.
- `void closePath()`
closes the path by drawing a straight line from the current point to the first point in the path.

11.3.3 Areas

In the preceding section, you saw how you can specify complex shapes by constructing general paths composed of lines and curves. By using a sufficient number of lines and curves, you can draw essentially any shape. For example, the shapes of characters in the fonts that you see on the screen and on your printouts are made up of lines and quadratic or cubic curves.

Occasionally, it is easier to describe a shape by composing it from *areas*, such as rectangles, polygons, or ellipses. The Java 2D API supports four *constructive area geometry* operations that combine two areas into a new area.

- `add`: The combined area contains all points that are in the first or the second area.
- `subtract`: The combined area contains all points that are in the first but not the second area.
- `intersect`: The combined area contains all points that are in the first and the second area.
- `exclusiveOr`: The combined area contains all points that are in either the first or the second area, but not in both.

Figure 11.40 shows these operations.




Figure 11.40 Constructive area geometry operations

To construct a complex area, start with a default area object.

```
var a = new Area();
```

Then, combine the area with any shape.

[Click here to view code image](#)

```
a.add(new Rectangle2D.Double(. . .));  
a.subtract(path);  
. . .
```

The `Area` class implements the `Shape` interface. You can stroke the boundary of the area with the `draw` method or paint the interior with the `fill` method of the `Graphics2D` class.

java.awt.geom.Area

- void add(Area other)
- void subtract(Area other)
- void intersect(Area other)
- void exclusiveOr(Area other)

carry out the constructive area geometry operation with this area and the other area and set this area to the result.

11.3.4 Strokes

The `draw` operation of the `Graphics2D` class draws the boundary of a shape by using the currently selected *stroke*. By default, the stroke is a solid line that is 1 pixel wide. You can select a different stroke by calling the `setStroke` method and supplying an object of a class that implements the `Stroke` interface. The Java 2D API defines only one such class, called `BasicStroke`. In this section, we'll look at the capabilities of the `BasicStroke` class.

You can construct strokes of arbitrary thickness. For example, here is how to draw lines that are 10 pixels wide:

[Click here to view code image](#)

```
g2.setStroke(new BasicStroke(10.0F));
g2.draw(new Line2D.Double(. . .));
```

When a stroke is more than a pixel thick, the *end* of the stroke can have different styles. [Figure 11.41](#) shows these so-called end cap styles. You have three choices:




Figure 11.41 End cap styles

- A *butt cap* simply ends the stroke at its end point.
- A *round cap* adds a half-circle to the end of the stroke.
- A *square cap* adds a half-square to the end of the stroke.

When two thick strokes meet, there are three choices for the *join style* (see [Figure 11.42](#)).




Figure 11.42 Join styles

- A *bevel join* joins the strokes with a straight line that is perpendicular to the bisector of the angle between the two strokes.
- A *round join* extends each stroke to have a round cap.
- A *miter join* extends both strokes by adding a “spike.”

If two lines come together in a miter join at a very small angle, a bevel join is used instead, preventing extremely long spikes. The *miter limit* controls this transition. Technically, this is the ratio of the distance of the inner and outer corners of the spike divided by the stroke width. The default miter limit of 10 corresponds to an angle of about 11 degrees.

You can specify these choices in the `BasicStroke` constructor, for example:

[Click here to view code image](#)

```
g2.setStroke(new BasicStroke(10.0F, BasicStroke.CAP_ROUND,  
BasicStroke.JOIN_ROUND));
```

```
g2.setStroke(new BasicStroke(10.0F, BasicStroke.CAP_BUTT,  
BasicStroke.JOIN_MITER,  
15.0F /* miter limit */));
```

Finally, you can create dashed lines by setting a *dash pattern*. In the program in Listing 11.16, you can select a dash pattern that spells out SOS in Morse code. The dash pattern is a `float[]` array that contains the lengths of the “on” and “off” intervals (see Figure 11.43).




Figure 11.43 A dash pattern

You can specify the dash pattern and a *dash phase* when constructing the `BasicStroke`. The dash phase indicates where in the dash pattern each line should start. Normally, you set this value to 0.

[Click here to view code image](#)

```
float[] dashPattern = { 10, 10, 10, 10, 10, 10, 10, 30, 10, 30, . . .  
. . .};  
g2.setStroke(new BasicStroke(10.0F, BasicStroke.CAP_BUTT,  
BasicStroke.JOIN_MITER,  
10.0F /* miter limit */, dashPattern, 0 /* dash phase */));
```



Note

End cap styles are applied to the ends of *each dash* in a dash pattern.

The program in [Listing 11.16](#) lets you specify end cap styles, join styles, and dashed lines (see [Figure 11.44](#)). You can move the ends of the line segments to test the miter limit: Select the miter join, then move the line segment to form a very acute angle. You will see the miter join turn into a bevel join.




Figure 11.44 The `StrokeTest` program

The program is similar to the program in [Listing 11.15](#). The mouse listener remembers your click on the end point of a line segment, and the mouse motion listener monitors the dragging of the end point. A set of radio buttons signal the user choices for the end cap style, join style, and solid or dashed line. The `paintComponent` method of the `StrokePanel` class constructs a `GeneralPath` consisting of the two line segments that join the three points which the user can move with the mouse. It then constructs a `BasicStroke`, according to the selections the user made, and finally draws the path.

Listing 11.16 `stroke/StrokeTest.java`

[Click here to view code image](#)

```
1 package stroke;
2
3 import java.awt.*;
4 import java.awt.event.*;
5 import java.awt.geom.*;
6 import javax.swing.*;
7
8 /**
9  * This program demonstrates different stroke types.
10 * @version 1.05 2018-05-01
11 * @author Cay Horstmann
12 */
13 public class StrokeTest
14 {
15     public static void main(String[] args)
16     {
17         EventQueue.invokeLater(() ->
18         {
19             var frame = new StrokeTestFrame();
20             frame.setTitle("StrokeTest");
21
22             frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
23             frame.setVisible(true);
24         });
25     }
26
27 /**
28  * This frame lets the user choose the cap, join, and line
29  * style, and shows the resulting
30  * stroke.
31
32 }
```

```
33     private StrokeComponent canvas;
34     private JPanel buttonPanel;
35
36     public StrokeTestFrame()
37     {
38         canvas = new StrokeComponent();
39         add(canvas, BorderLayout.CENTER);
40
41         buttonPanel = new JPanel();
42         buttonPanel.setLayout(new GridLayout(3, 3));
43         add(buttonPanel, BorderLayout.NORTH);
44
45         var group1 = new ButtonGroup();
46         makeCapButton("Butt Cap", BasicStroke.CAP_BUTT,
47 group1);
47         makeCapButton("Round Cap", BasicStroke.CAP_ROUND,
48 group1);
48         makeCapButton("Square Cap", BasicStroke.CAP_SQUARE,
49 group1);
50
50         var group2 = new ButtonGroup();
51         makeJoinButton("Miter Join", BasicStroke.JOIN_MITER,
52 group2);
52         makeJoinButton("Bevel Join", BasicStroke.JOIN_BEVEL,
53 group2);
53         makeJoinButton("Round Join", BasicStroke.JOIN_ROUND,
54 group2);
54
55         var group3 = new ButtonGroup();
56         makeDashButton("Solid Line", false, group3);
57         makeDashButton("Dashed Line", true, group3);
58     }
59
60     /**
61      * Makes a radio button to change the cap style.
62      * @param label the button label
63      * @param style the cap style
64      * @param group the radio button group
```

```
65      */
66      private void makeCapButton(String label, final int style,
ButtonGroup group)
67      {
68          // select first button in group
69          boolean selected = group.getButtonCount() == 0;
70          var button = new JRadioButton(label, selected);
71          buttonPanel.add(button);
72          group.add(button);
73          button.addActionListener(event ->
canvas.setCap(style));
74          pack();
75      }
76
77      /**
78      * Makes a radio button to change the join style.
79      * @param label the button label
80      * @param style the join style
81      * @param group the radio button group
82      */
83      private void makeJoinButton(String label, final int style,
ButtonGroup group)
84      {
85          // select first button in group
86          boolean selected = group.getButtonCount() == 0;
87          var button = new JRadioButton(label, selected);
88          buttonPanel.add(button);
89          group.add(button);
90          button.addActionListener(event ->
canvas.setJoin(style));
91      }
92
93      /**
94      * Makes a radio button to set solid or dashed lines.
95      * @param label the button label
96      * @param style false for solid, true for dashed lines
97      * @param group the radio button group
98      */
```

```
99      private void makeDashButton(String label, final boolean
style, ButtonGroup group)
100     {
101         // select first button in group
102         boolean selected = group.getButtonCount() == 0;
103         var button = new JRadioButton(label, selected);
104         buttonPanel.add(button);
105         group.add(button);
106         button.addActionListener(event ->
canvas.setDash(style));
107     }
108 }
109
110 /**
111 * This component draws two joined lines, using different
stroke objects, and allows the user
112 * to drag the three points defining the lines.
113 */
114 class StrokeComponent extends JComponent
115 {
116     private static final Dimension PREFERRED_SIZE = new
Dimension(400, 400);
117     private static int SIZE = 10;
118
119     private Point2D[] points;
120     private int current;
121     private float width;
122     private int cap;
123     private int join;
124     private boolean dash;
125
126     public StrokeComponent()
127     {
128         addMouseListener(new MouseAdapter()
129         {
130             public void mousePressed(MouseEvent event)
131             {
132                 Point p = event.getPoint();
```

```
133         for (int i = 0; i < points.length; i++)
134             {
135                 double x = points[i].getX() - SIZE / 2;
136                 double y = points[i].getY() - SIZE / 2;
137                 var r = new Rectangle2D.Double(x, y, SIZE,
138                     SIZE);
139                 if (r.contains(p))
140                     {
141                         current = i;
142                         return;
143                     }
144             }
145
146     public void mouseReleased(MouseEvent event)
147     {
148         current = -1;
149     }
150 );
151
152     addMouseMotionListener(new MouseMotionAdapter()
153     {
154         public void mouseDragged(MouseEvent event)
155         {
156             if (current == -1) return;
157             points[current] = event.getPoint();
158             repaint();
159         }
160     });
161
162     points = new Point2D[3];
163     points[0] = new Point2D.Double(200, 100);
164     points[1] = new Point2D.Double(100, 200);
165     points[2] = new Point2D.Double(200, 200);
166     current = -1;
167     width = 8.0F;
168 }
169
```

```
170     public void paintComponent(Graphics g)
171     {
172         var g2 = (Graphics2D) g;
173         var path = new GeneralPath();
174         path.moveTo((float) points[0].getX(), (float)
points[0].getY());
175         for (int i = 1; i < points.length; i++)
176             path.lineTo((float) points[i].getX(), (float)
points[i].getY());
177         BasicStroke stroke;
178         if (dash)
179         {
180             float miterLimit = 10.0F;
181             float[] dashPattern = { 10F, 10F, 10F, 10F, 10F,
10F, 30F, 10F, 30F, 10F, 30F, 10F,
182                         10F, 10F, 10F, 10F, 10F, 30F };
183             float dashPhase = 0;
184             stroke = new BasicStroke(width, cap, join,
miterLimit, dashPattern, dashPhase);
185         }
186         else stroke = new BasicStroke(width, cap, join);
187         g2.setStroke(stroke);
188         g2.draw(path);
189     }
190
191     /**
192      * Sets the join style.
193      * @param j the join style
194      */
195     public void setJoin(int j)
196     {
197         join = j;
198         repaint();
199     }
200
201     /**
202      * Sets the cap style.
203      * @param c the cap style
```

```
204     */
205     public void setCap(int c)
206     {
207         cap = c;
208         repaint();
209     }
210
211     /**
212      * Sets solid or dashed lines.
213      * @param d false for solid, true for dashed lines
214      */
215     public void setDash(boolean d)
216     {
217         dash = d;
218         repaint();
219     }
220
221     public Dimension getPreferredSize() { return
PREFERRED_SIZE; }
222 }
```

java.awt.Graphics2D 1.2

- `void setStroke(Stroke s)`

sets the stroke of this graphics context to the given object that implements the `Stroke` interface.

java.awt.BasicStroke 1.2

- `BasicStroke(float width)`
- `BasicStroke(float width, int cap, int join)`

- `BasicStroke(float width, int cap, int join, float miterlimit)`
- `BasicStroke(float width, int cap, int join, float miterlimit, float[] dash, float dashPhase)`

construct a stroke object with the given attributes.

Par

amewid The width of the pen
ters th

:

cap The end cap style—one of `CAP_BUTT`, `CAP_ROUND`,
 and `CAP_SQUARE`

joi The join style—one of `JOIN_BEVEL`,
 `JOIN_MITER`, and `JOIN_ROUND`

mit The ratio between the outer and inner corners of the
 join and the stroke width, below which a miter join is
 rendered as a bevel join
erl
imi
t

das An array of the lengths of the alternating filled and
 blank portions of a dashed stroke

das The “phase” of the dash pattern; a segment of this
 length, preceding the starting point of the stroke, is
 assumed to have the dash pattern already applied.
hPh
ase

11.3.5 Paint

When you fill a shape, its inside is covered with *paint*. Use the `setPaint` method to set the paint style to an object whose class implements the `Paint` interface. The Java 2D API provides three such classes:

- The `Color` class implements the `Paint` interface. To fill shapes with a solid color, simply call `setPaint` with a `Color` object, such as

```
g2.setPaint(Color.red);
```

- The `GradientPaint` class varies colors by interpolating between two given color values (see [Figure 11.45](#)).



Figure 11.45 Gradient paint

- The `TexturePaint` class fills an area with repetitions of an image (see [Figure 11.46](#)).




Figure 11.46 Texture paint

You can construct a `GradientPaint` object by specifying two points and the colors that you want at these two points.

[Click here to view code image](#)

```
g2.setPaint(new GradientPaint(p1, Color.RED, p2,  
Color.YELLOW));
```

Colors are interpolated along the line joining the two points. Colors are constant along lines perpendicular to that joining line. Points beyond an end point of the line are given the color at the end point.

Alternatively, if you call the `GradientPaint` constructor with `true` for the `cyclic` parameter:

[Click here to view code image](#)

```
g2.setPaint(new GradientPaint(p1, Color.RED, p2, Color.YELLOW,  
true));
```

Then, the color variation *cycles* and keeps varying beyond the end points.

To construct a `TexturePaint` object, specify a `BufferedImage` and an *anchor* rectangle.

[Click here to view code image](#)

```
g2.setPaint(new TexturePaint(bufferedImage, anchorRectangle));
```

I will introduce the `BufferedImage` class later in this chapter when images are discussed in detail. The simplest way of obtaining a buffered image is to read an image file:

[Click here to view code image](#)

```
bufferedImage = ImageIO.read(new File("blue-ball.gif"));
```

The anchor rectangle is extended indefinitely in *x* and *y* directions to tile the entire coordinate plane. The image is scaled to fit into the anchor and then replicated into each tile.

java.awt.Graphics2D 1.2

- `void setPaint(Paint s)`

sets the paint of this graphics context to the given object that implements the `Paint` interface.

java.awt.GradientPaint 1.2

- `GradientPaint(float x1, float y1, Color color1, float x2, float y2, Color color2)`
- `GradientPaint(float x1, float y1, Color color1, float x2, float y2, Color color2, boolean cyclic)`
- `GradientPaint(Point2D p1, Color color1, Point2D p2, Color color2)`
- `GradientPaint(Point2D p1, Color color1, Point2D p2, Color color2, boolean cyclic)`

construct a gradient paint object that fills shapes with color such that the start point is colored with `color1`, the end point is colored with `color2`, and the colors in between are linearly interpolated. Colors are constant along lines perpendicular to the line joining the start and the end point. By default, the gradient paint is not cyclic—that is, points beyond the start and end points are colored with the same color as the start and end point. If the gradient paint is *cyclic*, then colors continue to be interpolated, first returning to the starting point color and then repeating indefinitely in both directions.

java.awt.TexturePaint 1.2

- `TexturePaint(BufferedImage texture, Rectangle2D anchor)`

creates a texture paint object. The anchor rectangle defines the tiling of the space to be painted; it is repeated indefinitely in *x* and *y* directions, and the texture image is scaled to fill each tile.

11.3.6 Coordinate Transformations

Suppose you need to draw an object, such as an automobile. You know, from the manufacturer's specifications, the height, wheelbase, and total length. You could, of course, figure out all pixel positions, assuming some number of pixels per meter. However, there is an easier way: You can ask the graphics context to carry out the conversion for you.

[Click here to view code image](#)

```
g2.scale(pixelsPerMeter, pixelsPerMeter);
g2.draw(new Line2D.Double(coordinates in meters)); // converts
to pixels and
// draws
scaled line
```

The `scale` method of the `Graphics2D` class sets the *coordinate transformation* of the graphics context to a scaling transformation. That transformation changes *user coordinates* (user-specified units) to *device coordinates* (pixels). [Figure 11.47](#) shows how the transformation works.




Figure 11.47 User and device coordinates

Coordinate transformations are very useful in practice. They allow you to work with convenient coordinate values. The graphics context takes care of the dirty work of transforming them to pixels.

There are four fundamental transformations.

- Scaling: blowing up, or shrinking, all distances from a fixed point
- Rotation: rotating all points around a fixed center
- Translation: moving all points by a fixed amount
- Shear: leaving one line fixed and “sliding” the lines parallel to it by an amount that is proportional to the distance from the fixed line

[Figure 11.48](#) shows how these four fundamental transformations act on a unit square.




Figure 11.48 The fundamental transformations

The `scale`, `rotate`, `translate`, and `shear` methods of the `Graphics2D` class set the coordinate transformation of the graphics context to one of these fundamental transformations.

You can *compose* the transformations. For example, you might want to rotate shapes *and* double their size; supply both a rotation and a scaling transformation:

```
g2.rotate(angle);  
g2.scale(2, 2);  
g2.draw(. . .);
```

In this case, it does not matter in which order you supply the transformations. However, with most transformations, order does matter. For example, if you want to rotate and shear, then it makes a difference which of the transformations you supply first. You need to figure out what your intention is. The graphics context will apply the transformations in the order opposite to that in which you supplied them—that is, the last transformation you supply is applied first.

You can supply as many transformations as you like. For example, consider the following sequence of transformations:

```
g2.translate(x, y);  
g2.rotate(a);  
g2.translate(-x, -y);
```

The last transformation (which is applied first) moves the point (x, y) to the origin. The second transformation rotates with an angle a around the origin. The final transformation moves the origin back to (x, y) . The overall effect is a rotation with center point (x, y) —see [Figure 11.49](#). Since rotating about a point other than the origin is such a common operation, there is a shortcut:

```
g2.rotate(a, x, y);
```




Figure 11.49 Composing transformations

If you know some matrix theory, you are probably aware that all rotations, translations, scalings, shears, and their compositions can be expressed by transformation matrices of the form:

$$\begin{array}{l} x_{new} \\ y_{new} \\ 1 \end{array} = \begin{array}{rrr} a & c & e \\ b & d & f \\ 0 & 0 & 1 \end{array} \cdot \begin{array}{l} x \\ y \\ 1 \end{array}$$

Such a transformation is called an *affine transformation*. In the Java 2D API, the `AffineTransform` class describes such a transformation. If you know the components of a particular transformation matrix, you can construct it directly as

[Click here to view code image](#)

```
var t = new AffineTransform(a, b, c, d, e, f);
```

Additionally, the factory methods `getRotateInstance`, `getScaleInstance`, `getTranslateInstance`, and `getShearInstance` construct the matrices that represent these transformation types. For example, the call

[Click here to view code image](#)

```
t = AffineTransform.getScaleInstance(2.0F, 0.5F);
```

returns a transformation that corresponds to the matrix

$$\begin{matrix} 2 & 0 & 0 \\ 0 & 0.5 & 0 \\ 0 & 0 & 1 \end{matrix}$$

Finally, the instance methods `setToRotation`, `setToScale`, `setToTranslation`, and `setToShear` set a transformation object to a new type. Here is an example:

[Click here to view code image](#)

```
t.setToRotation(angle); // sets t to a rotation
```

You can set the coordinate transformation of the graphics context to an `AffineTransform` object.

[Click here to view code image](#)

```
g2.setTransform(t); // replaces current transformation
```

However, in practice, you shouldn't call the `setTransform` operation, as it replaces any existing transformation that the graphics context may have. For example, a graphics context for printing in landscape mode already contains a 90-degree rotation transformation. If you call `setTransform`, you obliterate that rotation. Instead, call the `transform` method.

[Click here to view code image](#)

```
g2.transform(t); // composes current transformation with t
```

It composes the existing transformation with the new `AffineTransform` object.

If you just want to apply a transformation temporarily, first get the old transformation, compose it with your new transformation, and finally restore the old transformation when you are done.

[Click here to view code image](#)

```
AffineTransform oldTransform = g2.getTransform(); // save old  
transform  
g2.transform(t); // apply temporary transform  
draw on g2  
g2.setTransform(oldTransform); // restore old transform
```

java.awt.geom.AffineTransform 1.2

- `AffineTransform(double a, double b, double c, double d, double e, double f)`
- `AffineTransform(float a, float b, float c, float d, float e, float f)`

construct the affine transform with matrix

$$\begin{matrix} a & c & e \\ b & d & f \\ 0 & 0 & 1 \end{matrix}$$

- `AffineTransform(double[] m)`
- `AffineTransform(float[] m)`

construct the affine transform with matrix

$$\begin{matrix} m[0] & m[2] & m[4] \\ m[1] & m[3] & m[5] \\ 0 & 0 & 1 \end{matrix}$$

- `static AffineTransform
getRotateInstance(double a)`

creates a rotation around the origin by the angle a (in radians). The transformation matrix is

$$\begin{matrix} \cos(a) & -\sin(a) & 0 \\ \sin(a) & \cos(a) & 0 \\ 0 & 0 & 1 \end{matrix}$$

If a is between 0 and $\pi / 2$, the rotation moves the positive x axis toward the positive y axis.

- `static AffineTransform
getRotateInstance(double a, double x, double y)`

creates a rotation around the point (x, y) by the angle a (in radians).

- `static AffineTransform
getScaleInstance(double sx, double sy)`

creates a scaling transformation that scales the x axis by s_x and the y axis by s_y . The transformation matrix is

| | | |
|----|----|---|
| sx | 0 | 0 |
| 0 | sy | 0 |
| 0 | 0 | 1 |

- static `AffineTransform`
`getShearInstance(double shx, double shy)`

creates a shear transformation that shears the x axis by `shx` and the y axis by `shy`. The transformation matrix is

| | | |
|-----|-----|---|
| 1 | shx | 0 |
| shy | 1 | 0 |
| 0 | 0 | 1 |

- static `AffineTransform`
`getTranslateInstance(double tx, double ty)`

creates a translation that moves the x axis by `tx` and the y axis by `ty`. The transformation matrix is

| | | |
|---|---|----|
| 1 | 0 | tx |
| 0 | 1 | ty |
| 0 | 0 | 1 |

- `void setToRotation(double a)`
- `void setToRotation(double a, double x, double y)`
- `void setToScale(double sx, double sy)`
- `void setToShear(double sx, double sy)`
- `void setToTranslation(double tx, double ty)`

set this affine transformation to a basic transformation with the given parameters. See the `getXxxInstance` methods for an explanation of the basic transformations and their parameters.

java.awt.Graphics2D 1.2

- `void setTransform(AffineTransform t)`
replaces the existing coordinate transformation of this graphics context with `t`.
- `void transform(AffineTransform t)`
composes the existing coordinate transformation of this graphics context with `t`.
- `void rotate(double a)`
- `void rotate(double a, double x, double y)`
- `void scale(double sx, double sy)`
- `void shear(double sx, double sy)`
- `void translate(double tx, double ty)`
compose the existing coordinate transformation of this graphics context with a basic transformation with the given parameters. See the `AffineTransform.getXXXInstance` methods for an explanation of the basic transformations and their parameters.

11.3.7 Clipping

By setting a *clipping shape* in the graphics context, you constrain all drawing operations to the interior of that clipping shape.

[Click here to view code image](#)

```
g2.setClip(clipShape); // but see below  
g2.draw(shape); // draws only the part that falls inside the  
clipping shape
```

However, in practice, you don't want to call the `setClip` operation because it replaces any existing clipping shape that the graphics context might have. For example, as you will see later in this chapter, a graphics context for printing comes with a clip rectangle that ensures that you don't draw on the margins. Instead, call the `clip` method.

[Click here to view code image](#)

```
g2.clip(clipShape); // better
```

The `clip` method intersects the existing clipping shape with the new one that you supply.

If you just want to apply a clipping area temporarily, you should first get the old clip, add your new clip, and finally restore the old clip when you are done:

[Click here to view code image](#)

```
Shape oldClip = g2.getClip(); // save old clip
g2.clip(clipShape); // apply temporary clip
draw on g2
g2.setClip(oldClip); // restore old clip
```

In [Figure 11.50](#), we show off the clipping capability with a rather dramatic drawing of a line pattern clipped by a complex shape—namely, the outline of a set of letters.



Figure 11.50 Using letter shapes to clip a line pattern

To obtain the character outlines, you need a *font render context*. Use the `getFontRenderContext` method of the `Graphics2D` class.

[Click here to view code image](#)

```
FontRenderContext context = g2.getFontRenderContext();
```

Next, using a string, a font, and the font render context, create a `TextLayout` object:

[Click here to view code image](#)

```
var layout = new TextLayout("Hello", font, context);
```

This text layout object describes the layout of a sequence of characters, as rendered by a particular font render context. The layout depends on the font render context—the same characters will look different on a screen and on a printer.

More important for our application, the `getOutline` method returns a `Shape` object that describes the shape of the outline of the characters in the text layout. The outline shape starts at the origin (0, 0), which might not be what you want. In that case, supply an affine transform to the `getOutline` operation to specify where you would like the outline to appear.

[Click here to view code image](#)

```
AffineTransform transform =
AffineTransform.getTranslateInstance(0, 100);
Shape outline = layout.getOutline(transform);
```

Then, append the outline to the clipping shape.

[Click here to view code image](#)

```
var clipShape = new GeneralPath();
clipShape.append(outline, false);
```

Finally, set the clipping shape and draw a set of lines. The lines appear only inside the character boundaries.

[Click here to view code image](#)

```
g2.setClip(clipShape);
var p = new Point2D.Double(0, 0);
for (int i = 0; i < NLINES; i++)
{
    double x = . . .;
    double y = . . .;
    var q = new Point2D.Double(x, y);
    g2.draw(new Line2D.Double(p, q)); // lines are clipped
}
```

java.awt.Graphics 1.0

- void `setClip(Shape s)` 1.2
 - sets the current clipping shape to the shape `s`.
- Shape `getClip()` 1.2
 - returns the current clipping shape.

java.awt.Graphics2D 1.2

- void `clip(Shape s)`
 - intersects the current clipping shape with the shape `s`.
- FontRenderContext `getFontRenderContext()`
 - returns a font render context that is necessary for constructing `TextLayout` objects.

java.awt.font.TextLayout 1.2

- `TextLayout(String s, Font f,
FontRenderContext context)`

constructs a text layout object from a given string and font, using the font render context to obtain font properties for a particular device.

- `float getAdvance()`

returns the width of this text layout.

- `float getAscent()`

- `float getDescent()`

return the height of this text layout above and below the baseline.

- `float getLeading()`

returns the distance between successive lines in the font used by this text layout.

11.3.8 Transparency and Composition

In the standard RGB color model, every color is described by its red, green, and blue components. However, it is also convenient to describe areas of an image that are *transparent* or partially transparent. When you superimpose an image onto an existing drawing, the transparent pixels do not obscure the pixels under them at all, whereas partially transparent pixels are mixed with the pixels under them. [Figure 11.51](#) shows the effect of overlaying a partially transparent rectangle on an image. You can still see the details of the image shine through from under the rectangle.



Figure 11.51 Overlaying a partially transparent rectangle on an image

In the Java 2D API, transparency is described by an *alpha channel*. Each pixel has, in addition to its red, green, and blue color components, an alpha value between 0 (fully transparent) and 1 (fully opaque). For example, the rectangle in [Figure 11.51](#) was filled with a pale yellow color with 50% transparency:

```
new Color(0.7F, 0.7F, 0.0F, 0.5F);
```

Now let us look at what happens if you superimpose two shapes. You need to blend or *compose* the colors and alpha values of the source and destination pixels. Porter and Duff, two researchers in the field of computer graphics, have formulated 12 possible *composition rules* for this blending process. The Java 2D API implements all of these rules. Before going any further, I'd like to point out that only two of these rules have practical significance. If you find the rules arcane or confusing, just use the SRC_OVER rule. It is the default rule for a `Graphics2D` object, and it gives the most intuitive results.

Here is the theory behind the rules. Suppose you have a *source pixel* with alpha value a_S . In the image, there is already a *destination pixel* with alpha value a_D . You want to compose the two. The diagram in [Figure 11.52](#) shows how to design a composition rule.




Figure 11.52 Designing a composition rule

Porter and Duff consider the alpha value as the probability that the pixel color should be used. From the perspective of the source, there is a probability a_S that it wants to use the source color and a probability of $1 - a_S$ that it doesn't care. The same holds for the destination. When composing the colors, let us assume that the probabilities are independent. Then there are four cases, as shown in [Figure 11.52](#). If the source wants to use the source color and the destination doesn't care, then it seems reasonable to let the source have its way. That's why the upper right corner of the diagram is labeled "S". The probability for that event is $a_S \cdot (1 - a_D)$. Similarly, the lower left corner is labeled "D". What should one do if both destination and source would like to select their color? That's where the Porter–Duff rules come in. If we decide that the source is more important, we label the lower right corner with an "S" as well. That rule is called `SRC_OVER`. In that rule, you combine the source colors with a weight of a_S and the destination colors with a weight of $(1 - a_S) \cdot a_D$.

The visual effect is a blending of the source and destination, with preference given to the source. In particular, if a_S is 1, then the destination

color is not taken into account at all. If a_S is 0, then the source pixel is completely transparent and the destination color is unchanged.

The other rules depend on what letters you put in the boxes of the probability diagram. [Table 11.3](#) and [Figure 11.53](#) show all rules that are supported by the Java 2D API. The images in the figure show the results of the rules when a rectangular source region with an alpha of 0.75 is combined with an elliptical destination region with an alpha of 1.0.

Table 11.3 The Porter–Duff Composition Rules

| Rule | Explanation |
|--------------|---|
| CLEAR | Source clears destination. |
| SRC | Source overwrites destination and empty pixels. |
| DST | Source does not affect destination. |
| SRC_OV
ER | Source blends with destination and overwrites empty pixels. |
| DST_OV
ER | Source does not affect destination and overwrites empty pixels. |
| SRC_IN | Source overwrites destination. |
| SRC_OU
T | Source clears destination and overwrites empty pixels. |
| DST_IN | Source alpha modifies destination. |
| DST_OU
T | Source alpha complement modifies destination. |
| SRC_AT
OP | Source blends with destination. |
| DST_AT
OP | Source alpha modifies destination. Source overwrites empty pixels. |
| XOR | Source alpha complement modifies destination. Source overwrites empty pixels. |




Figure 11.53 Porter–Duff composition rules

As you can see, most of the rules aren't very useful. Consider, as an extreme case, the `DST_IN` rule. It doesn't take the source color into account at all, but uses the alpha of the source to affect the destination. The `SRC` rule is potentially useful—it forces the source color to be used, turning off blending with the destination.

Use the `setComposite` method of the `Graphics2D` class to install an object of a class that implements the `Composite` interface. The Java 2D API supplies one such class, `AlphaComposite`, that implements all the Porter–Duff rules in [Figure 11.53](#).

The factory method `getInstance` of the `AlphaComposite` class yields an `AlphaComposite` object. You supply the rule and the alpha value to be used for source pixels. For example, consider the following code:

[Click here to view code image](#)

```
int rule = AlphaComposite.SRC_OVER;
float alpha = 0.5f;
g2.setComposite(AlphaComposite.getInstance(rule, alpha));
g2.setPaint(Color.blue);
g2.fill(rectangle);
```

The rectangle is then painted with blue color and an alpha value of 0.5. Since the composition rule is `SRC_OVER`, it is transparently overlaid on the existing image.

The program in [Listing 11.17](#) lets you explore these composition rules. Pick a rule from the combo box and use the slider to set the alpha value of the `AlphaComposite` object.

Furthermore, the program displays a verbal description of each rule. Note that the descriptions are computed from the composition rule diagrams. For example, a "DS" in the second row stands for "blends with destination."

The program has one important twist. There is no guarantee that the graphics context that corresponds to the screen has an alpha channel. (In fact, it generally does not.) When pixels are deposited to a destination without an alpha channel, the pixel colors are multiplied with the alpha value and the alpha value is discarded. Now, several of the Porter–Duff rules use the alpha values of the destination, which means a destination alpha channel is important. For that reason, we use a buffered image with the ARGB color model to compose the shapes. After the images have been composed, we draw the resulting image to the screen.

[Click here to view code image](#)

```
var image = new BufferedImage(getWidth(), getHeight(),
        BufferedImage.TYPE_INT_ARGB);
```

```
Graphics2D gImage = image.createGraphics();
// now draw to gImage
g2.drawImage(image, null, 0, 0);
```

[Listings 11.17](#) and [11.18](#) show the frame and component class. The Rule class in [Listing 11.19](#) provides a brief explanation for each rule—see [Figure 11.54](#). As you run the program, move the alpha slider from left to right to see the effect on the composed shapes. In particular, note that the only difference between the DST_IN and DST_OUT rules is how the destination (!) color changes when you change the source alpha.




Figure 11.54 The CompositeTest program

Listing 11.17 composite/CompositeTestFrame.java

[Click here to view code image](#)

```
1 package composite;
2
3 import java.awt.*;
4 import javax.swing.*;
5
6 /**
7  * This frame contains a combo box to choose a composition
rule, a slider to change the
8  * source alpha channel, and a component that shows the
composition.
9 */
10 class CompositeTestFrame extends JFrame
11 {
12     private static final int DEFAULT_WIDTH = 400;
13     private static final int DEFAULT_HEIGHT = 400;
14
15     private CompositeComponent canvas;
16     private JComboBox<Rule> ruleCombo;
17     private JSlider alphaSlider;
18     private JTextField explanation;
19
20     public CompositeTestFrame()
21     {
22         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
23
24         canvas = new CompositeComponent();
25         add(canvas, BorderLayout.CENTER);
26
27         ruleCombo = new JComboBox<>(new Rule[]
28         {
29             new Rule("CLEAR", " ", " "),
30             new Rule("SRC", " S", " S"), new Rule("DST", " ",
"DD"),
31             new Rule("SRC_OVER", " S", "DS"), new
Rule("DST_OVER", " S", "DD"),
32             new Rule("SRC_IN", " ", " S"), new Rule("SRC_OUT",
" S", " "),
33             new Rule("DST_IN", " ", " D"), new Rule("DST_OUT",
" ", " D")

```

```

" ", "D "),
34             new Rule("SRC_ATOP", " ", "DS"), new
Rule("DST_ATOP", " S", " D"),
35             new Rule("XOR", " S", "D "),
36         );
37     ruleCombo.addActionListener(event ->
38     {
39         var r = (Rule) ruleCombo.getSelectedItem();
40         canvas.setRule(r.getValue());
41         explanation.setText(r.getExplanation());
42     });
43
44     alphaSlider = new JSlider(0, 100, 75);
45     alphaSlider.addChangeListener(event ->
canvas.setAlpha(alphaSlider.getValue()));
46     var panel = new JPanel();
47     panel.add(ruleCombo);
48     panel.add(new JLabel("Alpha"));
49     panel.add(alphaSlider);
50     add(panel, BorderLayout.NORTH);
51
52     explanation = new JTextField();
53     add(explanation, BorderLayout.SOUTH);
54
55     canvas.setAlpha(alphaSlider.getValue());
56     Rule r =
ruleCombo.getItemAt(ruleCombo.getSelectedIndex());
57     canvas.setRule(r.getValue());
58     explanation.setText(r.getExplanation());
59 }
60 }

```

Listing 11.18 composite/CompositeComponent.java

[Click here to view code image](#)

```
1 package composite;
2
3 import java.awt.*;
4 import java.awt.geom.*;
5 import java.awt.image.*;
6 import javax.swing.*;
7
8 /**
9  * This component draws two shapes, composed with a
10 * composition rule.
11 */
12 class CompositeComponent extends JComponent
13 {
14     private int rule;
15     private Shape shape1;
16     private Shape shape2;
17     private float alpha;
18
19     public CompositeComponent()
20     {
21         shape1 = new Ellipse2D.Double(100, 100, 150, 100);
22         shape2 = new Rectangle2D.Double(150, 150, 150, 100);
23     }
24
25     public void paintComponent(Graphics g)
26     {
27
28         var image = new BufferedImage(getWidth(), getHeight(),
29             BufferedImage.TYPE_INT_ARGB);
29         Graphics2D gImage = image.createGraphics();
30         gImage.setPaint(Color.red);
31         gImage.fill(shape1);
32         AlphaComposite composite =
33             AlphaComposite.getInstance(rule, alpha);
34         gImage.setComposite(composite);
35         gImage.setPaint(Color.blue);
36         gImage.fill(shape2);
```

```
36         g2.drawImage(image, null, 0, 0);
37     }
38
39     /**
40      * Sets the composition rule.
41      * @param r the rule (as an AlphaComposite constant)
42      */
43     public void setRule(int r)
44     {
45         rule = r;
46         repaint();
47     }
48
49     /**
50      * Sets the alpha of the source.
51      * @param a the alpha value between 0 and 100
52      */
53     public void setAlpha(int a)
54     {
55         alpha = (float) a / 100.0F;
56         repaint();
57     }
58 }
```

Listing 11.19 composite/Rule.java

[Click here to view code image](#)

```
1 package composite;
2
3 import java.awt.*;
4
5 /**
6  * This class describes a Porter-Duff rule.
7  */
8 class Rule
9 {
```

```
10     private String name;
11     private String porterDuff1;
12     private String porterDuff2;
13
14     /**
15      * Constructs a Porter-Duff rule.
16      * @param n the rule name
17      * @param pd1 the first row of the Porter-Duff square
18      * @param pd2 the second row of the Porter-Duff square
19      */
20     public Rule(String n, String pd1, String pd2)
21     {
22         name = n;
23         porterDuff1 = pd1;
24         porterDuff2 = pd2;
25     }
26
27     /**
28      * Gets an explanation of the behavior of this rule.
29      * @return the explanation
30      */
31     public String getExplanation()
32     {
33         var r = new StringBuilder("Source ");
34         if (porterDuff2.equals(" ")) r.append("clears");
35         if (porterDuff2.equals(" S")) r.append("overwrites");
36         if (porterDuff2.equals("DS")) r.append("blends with");
37         if (porterDuff2.equals(" D")) r.append("alpha
modifies");
38         if (porterDuff2.equals("D ")) r.append("alpha complement
modifies");
39         if (porterDuff2.equals("DD")) r.append("does not
affect");
40         r.append(" destination");
41         if (porterDuff1.equals(" S")) r.append(" and overwrites
empty pixels");
42         r.append(".");
43         return r.toString();

```

```
44      }
45
46      public String toString()
47      {
48          return name;
49      }
50
51      /**
52      * Gets the value of this rule in the AlphaComposite class.
53      * @return the AlphaComposite constant value, or -1 if
54      there is no matching constant
55      */
56      public int getValue()
57      {
58          try
59          {
60              return (Integer)
61              AlphaComposite.class.getField(name).get(null);
62          }
63          catch (Exception e)
64          {
65              return -1;
66      }
67  }
```

java.awt.Graphics2D 1.2

- void setComposite(Composite s)

sets the composite of this graphics context to the given object that implements the Composite interface.

java.awt.AlphaComposite 1.2

- static AlphaComposite getInstance(int rule)
- static AlphaComposite getInstance(int rule, float sourceAlpha)

construct an alpha composite object. The rule is one of CLEAR, SRC, SRC_OVER, DST_OVER, SRC_IN, SRC_OUT, DST_IN, DST_OUT, DST, DST_ATOP, SRC_ATOP, XOR.

11.4 Raster Images

The Java2D API lets you create drawings that are made up of lines, curves, and areas. It is a “vector” API because you specify the mathematical properties of the shapes. However, for processing images that are made up of pixels, you want to work with a “raster” of color data. The following sections show you how to process raster images in Java.

11.4.1 Readers and Writers for Images

The `javax.imageio` package contains out-of-the-box support for reading and writing several common file formats, as well as a framework that enables third parties to add readers and writers for other formats. The GIF, JPEG, PNG, BMP (Windows bitmap), and WBMP (wireless bitmap) file formats are supported.

The basics of the library are extremely straightforward. To load an image, use the static `read` method of the `ImageIO` class:

[Click here to view code image](#)

```
File f = . . .;
BufferedImage image = ImageIO.read(f);
```

The `ImageIO` class picks an appropriate reader, based on the file type. It may consult the file extension and the “magic number” at the beginning of

the file for that purpose. If no suitable reader can be found or the reader can't decode the file contents, the `read` method returns `null`.

Writing an image to a file is just as simple:

[Click here to view code image](#)

```
File f = . . .;
String format = . . .;
ImageIO.write(image, format, f);
```

Here the format string is a string identifying the image format, such as "JPEG" or "PNG". The `ImageIO` class picks an appropriate writer and saves the file.

11.4.1.1 Obtaining Readers and Writers for Image File Types

For more advanced image reading and writing operations that go beyond the static `read` and `write` methods of the `ImageIO` class, you first need to get the appropriate `ImageReader` and `ImageWriter` objects. The `ImageIO` class enumerates readers and writers that match one of the following:

- An image format (such as "JPEG")
 - A file suffix (such as "jpg")
 - A MIME type (such as "image/jpeg")
-



Note

MIME is the Multipurpose Internet Mail Extensions standard. The MIME standard defines common data formats such as `image/jpeg` and `application/pdf`.

For example, you can obtain a reader that reads JPEG files as follows:

[Click here to view code image](#)

```
ImageReader reader = null;
Iterator<ImageReader> iter =
ImageIO.getImageReadersByFormatName("JPEG");
if (iter.hasNext()) reader = iter.next();
```

The `getImageReadersBySuffix` and `getImageReadersByMIMEType` methods enumerate readers that match a file extension or MIME type.

It is possible that the `ImageIO` class can locate multiple readers that can all read a particular image type. In that case, you have to pick one of them, but it isn't clear how you can decide which one is the best. To find out more information about a reader, obtain its *service provider interface*:

[Click here to view code image](#)

```
ImageReaderSpi spi = reader.getOriginatingProvider();
```

Then you can get the vendor name and version number:

[Click here to view code image](#)

```
String vendor = spi.getVendor();
String version = spi.getVersion();
```

Perhaps that information can help you decide among the choices—or you might just present a list of readers to your program users and let them choose. For now, we assume that the first enumerated reader is adequate.

In the sample program in [Listing 11.20](#), we want to find all file suffixes of all available readers so that we can use them in a file filter. Use the static `ImageIO.getReaderFileSuffixes` method for this purpose:

[Click here to view code image](#)

```
String[] extensions = ImageIO.getReaderFileSuffixes();
chooser.setFileFilter(new FileNameExtensionFilter("Image
files", extensions));
```

For saving files, we have to work harder. We'd like to present the user with a menu of all supported image types. Unfortunately, the `getWriterFormatNames` of the `ImageIO` class returns a rather curious list with redundant names, such as

[Click here to view code image](#)

```
jpg, BMP, bmp, JPG, jpeg, wbmp, png, JPEG, PNG, WBMP, GIF, gif
```

That's not something one would want to present in a menu. What is needed is a list of "preferred" format names. We supply a helper method `getWriterFormats` for this purpose (see [Listing 11.20](#)). We look up the first writer associated with each format name. Then we ask it what its format names are, in the hope that it will list the most popular one first. Indeed, for the JPEG writer, this works fine—it lists "JPEG" before the other options. (The PNG writer, on the other hand, lists "png" in lower case before "PNG". We hope this behavior will be addressed at some point in the future. For now, we force all-lowercase names to upper case.) Once we pick a preferred name, we remove all alternate names from the original set. We keep going until all format names are handled.

11.4.1.2 Reading and Writing Files with Multiple Images

Some files—in particular, animated GIF files—contain multiple images. The `read` method of the `ImageIO` class reads a single image. To read multiple images, turn the input source (for example, an input stream or file) into an `ImageInputStream`.

[Click here to view code image](#)

```
InputStream in = . . .;  
ImageInputStream imageIn = ImageIO.createImageInputStream(in);
```

Then, attach the image input stream to the reader:

```
reader.setInput(imageIn, true);
```

The second parameter indicates that the input is in “seek forward only” mode. Otherwise, random access is used, either by buffering stream input as it is read or by using random file access. Random access is required for certain operations. For example, to find out the number of images in a GIF file, you need to read the entire file. If you then want to fetch an image, the input must be read again.

This consideration is only important if you read from a stream, if the input contains multiple images, and if the image format doesn’t have the information that you request (such as the image count) in the header. If you read from a file, simply use

[Click here to view code image](#)

```
File f = . . .;
ImageInputStream imageIn = ImageIO.createImageInputStream(f);
reader.setInput(imageIn);
```

Once you have a reader, you can read the images in the input by calling

[Click here to view code image](#)

```
BufferedImage image = reader.read(index);
```

where `index` is the image index, starting with 0.

If the input is in the “seek forward only” mode, you keep reading images until the `read` method throws an `IndexOutOfBoundsException`. Otherwise, you can call the `getNumImages` method:

[Click here to view code image](#)

```
int n = reader.getNumImages(true);
```

Here, the parameter indicates that you allow a search of the input to determine the number of images. That method throws an `IllegalStateException` if the input is in the “seek forward only” mode. Alternatively, you can set the “allow search” parameter to `false`. Then the `getNumImages` method returns `-1` if it can’t determine the number of images without a search. In that case, you’ll have to switch to

Plan B and keep reading images until you get an `IndexOutOfBoundsException`.

Some files contain thumbnails—smaller versions of an image for preview purposes. You can get the number of thumbnails of an image with the call

[Click here to view code image](#)

```
int count = reader.getNumThumbnails(index);
```

Then you get a particular index as

[Click here to view code image](#)

```
BufferedImage thumbnail = reader.getThumbnail(index,  
thumbnailIndex);
```

Sometimes you may want to get the image size before actually getting the image—in particular, if the image is huge or comes from a slow network connection. Use the calls

[Click here to view code image](#)

```
int width = reader.getWidth(index);  
int height = reader.getHeight(index);
```

to get the dimensions of an image with a given index.

To write a file with multiple images, you first need an `ImageWriter`. The `ImageIO` class can enumerate the writers capable of writing a particular image format:

[Click here to view code image](#)

```
String format = . . .;  
ImageWriter writer = null;  
Iterator<ImageWriter> iter =  
ImageIO.getImageWritersByFormatName(format);  
if (iter.hasNext()) writer = iter.next();
```

Next, turn an output stream or file into an `ImageOutputStream` and attach it to the writer. For example,

[Click here to view code image](#)

```
File f = . . .;
ImageOutputStream imageOut =
ImageIO.createImageOutputStream(f);
writer.setOutput(imageOut);
```

You must wrap each image into an `IIOImage` object. You can optionally supply a list of thumbnails and image metadata (such as compression algorithms and color information). In this example, we just use `null` for both; see the API documentation for additional information.

[Click here to view code image](#)

```
var iioImage = new IIOImage(images[i], null, null);
```

To write out the *first* image, use the `write` method:

[Click here to view code image](#)

```
writer.write(new IIOImage(images[0], null, null));
```

For subsequent images, use

[Click here to view code image](#)

```
if (writer.canInsertImage(i))
writer.writeInsert(i, iioImage, null);
```

The third parameter can contain an `ImageWriteParam` object to set image writing details such as tiling and compression; use `null` for default values.

Not all file formats can handle multiple images. In that case, the `canInsertImage` method returns `false` for $i > 0$, and only a single image is saved.

The program in Listing 11.20 lets you load and save files in the formats for which the Java library supplies readers and writers. The program displays multiple images (see Figure 11.55), but not thumbnails.




Figure 11.55 An animated GIF image

Listing 11.20 `imageIO/ImageIOFrame.java`

[Click here to view code image](#)

```
1 package imageIO;  
2  
3 import java.awt.image.*;  
4 import java.io.*;  
5 import java.util.*;  
6  
7 import javax.imageio.*;  
8 import javax.imageio.stream.*;  
9 import javax.swing.*;
```

```
10 import javax.swing.filechooser.*;
11
12 /**
13  * This frame displays the loaded images. The menu has items
14  * for loading and saving files.
15 */
16 public class ImageIOFrame extends JFrame
17 {
18     private static final int DEFAULT_WIDTH = 400;
19     private static final int DEFAULT_HEIGHT = 400;
20
21     private static Set<String> writerFormats =
22         getWriterFormats();
23
24     public ImageIOFrame()
25     {
26         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
27
28         var fileMenu = new JMenu("File");
29         var openItem = new JMenuItem("Open");
30         openItem.addActionListener(event -> openFileDialog());
31         fileMenu.add(openItem);
32
33         var saveMenu = new JMenu("Save");
34         fileMenu.add(saveMenu);
35         Iterator<String> iter = writerFormats.iterator();
36         while (iter.hasNext())
37         {
38             final String formatName = iter.next();
39             var formatItem = new JMenuItem(formatName);
40             saveMenu.add(formatItem);
41             formatItem.addActionListener(event ->
42                 saveFile(formatName));
43         }
44         var exitItem = new JMenuItem("Exit");
```

```
45     exitItem.addActionListener(event -> System.exit(0));
46     fileMenu.add(exitItem);
47
48     var menuBar = new JMenuBar();
49     menuBar.add(fileMenu);
50     setJMenuBar(menuBar);
51 }
52
53 /**
54  * Open a file and load the images.
55 */
56 public void openFile()
57 {
58     var chooser = new JFileChooser();
59     chooser.setCurrentDirectory(new File("."));
60     String[] extensions = ImageIO.getReaderFileSuffixes();
61     chooser.setFileFilter(new FileNameExtensionFilter("Image
files", extensions));
62     int r = chooser.showOpenDialog(this);
63     if (r != JFileChooser.APPROVE_OPTION) return;
64     File f = chooser.getSelectedFile();
65     Box box = Box.createVerticalBox();
66     try
67     {
68         String name = f.getName();
69         String suffix = name.substring(name.lastIndexOf('.') +
1);
70         Iterator<ImageReader> iter =
ImageIO.getImageReadersBySuffix(suffix);
71         ImageReader reader = iter.next();
72         ImageInputStream imageIn =
ImageIO.createImageInputStream(f);
73         reader.setInput(imageIn);
74         int count = reader.getNumImages(true);
75         images = new BufferedImage[count];
76         for (int i = 0; i < count; i++)
77         {
78             images[i] = reader.read(i);
```

```
79         box.add(new JLabel(new ImageIcon(images[i]))));
80     }
81   }
82   catch (IOException e)
83   {
84     JOptionPane.showMessageDialog(this, e);
85   }
86   setContentPane(new JScrollPane(box));
87   validate();
88 }
89
90 /**
91 * Save the current image in a file.
92 * @param formatName the file format
93 */
94 public void saveFile(final String formatName)
95 {
96   if (images == null) return;
97   Iterator<ImageWriter> iter =
ImageIO.getImageWritersByFormatName(formatName);
98   ImageWriter writer = iter.next();
99   var chooser = new JFileChooser();
100  chooser.setCurrentDirectory(new File("."));
101  String[] extensions =
writer.getOriginatingProvider().getFileSuffixes();
102  chooser.setFileFilter(new
FileNameExtensionFilter("Image files", extensions));
103
104  int r = chooser.showSaveDialog(this);
105  if (r != JFileChooser.APPROVE_OPTION) return;
106  File f = chooser.getSelectedFile();
107  try
108  {
109    ImageOutputStream imageOut =
ImageIO.createImageOutputStream(f);
110    writer.setOutput(imageOut);
111
112    writer.write(new IIOImage(images[0], null, null));

```

```
113         for (int i = 1; i < images.length; i++)
114         {
115             var iioImage = new IIOImage(images[i], null,
116                                         null);
116             if (writer.canInsertImage(i))
117                 writer.writeInsert(i, iioImage, null);
117         }
118     }
119     catch (IOException e)
120     {
121         JOptionPane.showMessageDialog(this, e);
122     }
123 }
124
125 /**
126 * Gets a set of "preferred" format names of all image
writers. The preferred format name
127 * is the first format name that a writer specifies.
128 * @return the format name set
129 */
130 public static Set<String> getWriterFormats()
131 {
132     var writerFormats = new TreeSet<String>();
133     var formatNames =
List.of(ImageIO.getWriterFormatNames());
134     while (formatNames.size() > 0)
135     {
136         String name = formatNames.iterator().next();
137         Iterator<ImageWriter> iter =
ImageIO.getImageWritersByFormatName(name);
138         ImageWriter writer = iter.next();
139         String[] names =
writer.getOriginatingProvider().getFormatNames();
140         String format = names[0];
141         if (format.equals(format.toLowerCase())) format =
format.toUpperCase();
142         writerFormats.add(format);
143         formatNames.removeAll(List.of(names));

```

```
144         }
145     return writerFormats;
146 }
147 }
```

javax.imageio.ImageIO 1.4

- static BufferedImage read(File input)
• static BufferedImage read(InputStream input)
• static BufferedImage read(URL input)

read an image from input.
- static boolean write(RenderedImage image,
String formatName, File output)
• static boolean write(RenderedImage image,
String formatName, OutputStream output)

write an image in the given format to output. Return false if
no appropriate writer was found.
- static Iterator<ImageReader>
getImageReadersByFormatName(String
formatName)
- static Iterator<ImageReader>
getImageReadersBySuffix(String fileSuffix)
- static Iterator<ImageReader>
getImageReadersByMIMEType(String mimeType)
- static Iterator<ImageWriter>
getImageWritersByFormatName(String
formatName)
- static Iterator<ImageWriter>
getImageWritersBySuffix(String fileSuffix)

- static Iterator<ImageWriter> getImageWritersByMIMEType(String mimeType)
get all readers and writers that are able to handle the given format (e.g., "JPEG"), file suffix (e.g., "jpg"), or MIME type (e.g., "image/jpeg").
- static String[] getReaderFormatNames()
- static String[] getReaderMIMETypes()
- static String[] getWriterFormatNames()
- static String[] getWriterMIMETypes()
- static String[] getReaderFileSuffixes() *6*
- static String[] getWriterFileSuffixes() *6*
get all format names, MIME type names, and file suffixes supported by readers and writers.
- ImageInputStream
createImageInputStream(Object input)
- ImageOutputStream
createImageOutputStream(Object output)
create an image input or image output stream from the given object. The object can be a file, a stream, a RandomAccessFile, or another object for which a service provider exists. Return null if no registered service provider can handle the object.

javax.imageio.ImageReader 1.4

- void setInput(Object input)
- void setInput(Object input, boolean seekForwardOnly)

set the input source of the reader.

*Par
ame* `input` An `ImageInputStream` object or another
ters: object that this reader can accept.

`seekF` `true` if the reader should read forward only. By
`orwar` default, the reader uses random access and, if
`dOnly` necessary, buffers image data.

- `BufferedImage read(int index)`

reads the image with the given image index (starting at 0). Throws an `IndexOutOfBoundsException` if no such image is available.

- `int getNumImages(boolean allowSearch)`

gets the number of images in this reader. If `allowSearch` is `false` and the number of images cannot be determined without reading forward, then `-1` is returned. If `allowSearch` is `true` and the reader is in the “seek forward only” mode, then an `IllegalStateException` is thrown.

- `int getNumThumbnails(int index)`

gets the number of thumbnails of the image with the given index.

- `BufferedImage readThumbnail(int index, int thumbnailIndex)`

gets the thumbnail with index `thumbnailIndex` of the image with the given `index`.

- `int getWidth(int index)`

- `int getHeight(int index)`

get the image width and height. Throw an `IndexOutOfBoundsException` if no such image is available.

- `ImageReaderSpi getOriginatingProvider()`
gets the service provider that constructed this reader.

`javax.imageio.spi.IIOServiceProvider` 1.4

- `String getVendorName()`
- `String getVersion()`

get the vendor name and version of this service provider.

`javax.imageio.spi.ImageReaderWriterSpi` 1.4

- `String[] getFormatNames()`
- `String[] getFileSuffixes()`
- `String[] getMIMETypes()`

get the format names, file suffixes, and MIME types supported by the readers or writers that this service provider creates.

`javax.imageio.ImageWriter` 1.4

- `void setOutput(Object output)`
sets the output target of this writer.

Param out An `ImageOutputStream` object or another
eters: put object that this writer can accept

- `void write(IIOImage image)`
write a single image to the output.
- `void writeInsert(int index, IIOImage image, ImageWriteParam param)`
writes an image into a multi-image file.
- `boolean canInsertImage(int index)`
returns `true` if it is possible to insert an image at the given index.
- `ImageWriterSpi getOriginatingProvider()`
gets the service provider that constructed this writer.

javax.imageio.IIOImage 1.4

- `IIOImage(RenderedImage image, List thumbnails, IIOMetadata metadata)`
constructs an `IIOImage` from an image, optional thumbnails, and optional metadata.

11.4.2 Image Manipulation

Suppose you have an image and you would like to improve its appearance. You then need to access the individual pixels of the image and replace them with other pixels. Or perhaps you want to compute the pixels of an image from scratch—for example, to show the result of physical measurements or

a mathematical computation. The `BufferedImage` class gives you control over the pixels in an image, and the classes that implement the `BufferedImageOp` interface let you transform images.



Note

JDK 1.0 had a completely different, and far more complex, imaging framework that was optimized for *incremental rendering* of images downloaded from the Web, a scan line at a time. However, it was difficult to manipulate those images. We do not discuss that framework in this book.

11.4.2.1 Constructing Raster Images

Most of the images that you manipulate are simply read in from an image file—they were either produced by a device such as a digital camera or scanner, or constructed by a drawing program. In this section, we'll show you a different technique for constructing an image—namely, building it up a pixel at a time.

To create an image, construct a `BufferedImage` object in the usual way.

[Click here to view code image](#)

```
image = new BufferedImage(width, height,  
    BufferedImage.TYPE_INT_ARGB);
```

Now, call the `getRaster` method to obtain an object of type `WritableRaster`. You will use this object to access and modify the pixels of the image.

[Click here to view code image](#)

```
WritableRaster raster = image.getRaster();
```

The `setPixel` method lets you set an individual pixel. The complexity here is that you can't simply set the pixel to a `Color` value. You must

know how the buffered image specifies color values. That depends on the *type* of the image. If your image has a type of `TYPE_INT_ARGB`, then each pixel is described by four values—red, green, blue, and alpha, each between 0 and 255. You have to supply them in an array of four integers:

[Click here to view code image](#)

```
int[] black = { 0, 0, 0, 255 };  
raster.setPixel(i, j, black);
```

In the lingo of the Java 2D API, these values are called the *sample values* of the pixel.



Caution

There are also `setPixel` methods that take array parameters of types `float[]` and `double[]`. However, the values that you need to place into these arrays are *not* normalized color values between 0.0 and 1.0.

[Click here to view code image](#)

```
float[] red = { 1.0F, 0.0F, 0.0F, 1.0F };  
raster.setPixel(i, j, red); // ERROR
```

You need to supply values between 0 and 255, no matter what the type of the array is.

You can supply a batch of pixels with the `setPixels` method. Specify the starting pixel position and the width and height of the rectangle that you want to set. Then, supply an array that contains the sample values for all pixels. For example, if your buffered image has a type of `TYPE_INT_ARGB`, supply the red, green, blue, and alpha values of the first pixel, then the red, green, blue, and alpha values for the second pixel, and so on.

[Click here to view code image](#)

```
var pixels = new int[4 * width * height];
pixels[0] = . . .; // red value for first pixel

pixels[1] = . . .; // green value for first pixel
pixels[2] = . . .; // blue value for first pixel
pixels[3] = . . .; // alpha value for first pixel
. . .
raster.setPixels(x, y, width, height, pixels);
```

Conversely, to read a pixel, use the `getPixel` method. Supply an array of four integers to hold the sample values.

[Click here to view code image](#)

```
var sample = new int[4];
raster.getPixel(x, y, sample);
var color = new Color(sample[0], sample[1], sample[2],
sample[3]);
```

You can read multiple pixels with the `getPixels` method.

[Click here to view code image](#)

```
raster.getPixels(x, y, width, height, samples);
```

If you use an image type other than `TYPE_INT_ARGB` and you know how that type represents pixel values, you can still use the `getPixel`/`setPixel` methods. However, you have to know the encoding of the sample values in the particular image type.

If you need to manipulate an image with an arbitrary, unknown image type, then you have to work a bit harder. Every image type has a *color model* that can translate between sample value arrays and the standard RGB color model.



Note

The RGB color model isn't as standard as you might think. The exact look of a color value depends on the characteristics of the imaging device. Digital cameras, scanners, monitors, and LCD displays all have their own idiosyncrasies. As a result, the same RGB value can look quite different on different devices. The International Color Consortium (www.color.org) recommends that all color data be accompanied by an *ICC profile* that specifies how the colors map to a standard form such as the 1931 CIE XYZ color specification. That specification was designed by the Commission Internationale de l'Eclairage, or CIE (www.cie.co.at), the international organization in charge of providing technical guidance in all matters of illumination and color. The specification is a standard method for representing any color that the human eye can perceive as a triplet of coordinates called X, Y, Z. (See, for example, *Computer Graphics: Principles and Practice, Third Edition*, by John F. Hughes et al., Chapter 28, for more information on the 1931 CIE XYZ specification.)

ICC profiles are complex, however. A simpler proposed standard, called sRGB (<https://www.w3.org/Graphics/Color/sRGB.html>), specifies an exact mapping between RGB values and the 1931 CIE XYZ values that was designed to work well with typical color monitors. The Java 2D API uses that mapping when converting between RGB and other color spaces.

The `getColorModel` method returns the color model:

[Click here to view code image](#)

```
ColorModel model = image.getColorModel();
```

To find the color value of a pixel, call the `getDataElements` method of the `Raster` class. That call returns an `Object` that contains a color-model-specific description of the color value.

[Click here to view code image](#)

```
Object data = raster.getDataElements(x, y, null);
```



Note

The object that is returned by the `getDataElements` method is actually an array of sample values. You don't need to know this to process the object, but it explains why the method is called `getDataElements`.

The color model can translate the object to standard ARGB values. The `getRGB` method returns an `int` value that has the alpha, red, green, and blue values packed in four blocks of eight bits each. You can construct a `Color` value out of that integer with the `Color(int argb, boolean hasAlpha)` constructor:

[Click here to view code image](#)

```
int argb = model.getRGB(data);
var color = new Color(argb, true);
```

To set a pixel to a particular color, reverse these steps. The `getRGB` method of the `Color` class yields an `int` value with the alpha, red, green, and blue values. Supply that value to the `getDataElements` method of the `ColorModel` class. The return value is an `Object` that contains the color-model-specific description of the color value. Pass the object to the `setDataElements` method of the `WritableRaster` class.

[Click here to view code image](#)

```
int argb = color.getRGB();
Object data = model.getDataElements(argb, null);
raster.setDataElements(x, y, data);
```

To illustrate how to use these methods to build an image from individual pixels, we bow to tradition and draw a Mandelbrot set, as shown in [Figure 11.56](#).




Figure 11.56 A Mandelbrot set

The idea of the Mandelbrot set is that each point of the plane is associated with a sequence of numbers. If that sequence stays bounded, you color the point. If it “escapes to infinity,” you leave it transparent.

Here is how you can construct the simplest Mandelbrot set. For each point (a, b) , look at sequences that start with $(x, y) = (0, 0)$ and iterate:

$$x_{\text{new}} = x^2 - y^2 + a$$

$$y_{\text{new}} = 2 \cdot x \cdot y + b$$

It turns out that if x or y ever gets larger than 2, then the sequence escapes to infinity. Only the pixels that correspond to points (a, b) leading to a bounded sequence are colored. (The formulas for the number sequences come ultimately from the mathematics of complex numbers; we'll just take them for granted.)

[Listing 11.21](#) shows the code. This program demonstrates how to use the `ColorModel` class for translating `Color` values into pixel data. That process is independent of the image type. Just for fun, change the color type of the buffered image to `TYPE_BYTE_GRAY`. You don't need to change any other code—the color model of the image automatically takes care of the conversion from colors to sample values.

Listing 11.21 rasterImage/RasterImageFrame.java

[Click here to view code image](#)

```
1 package rasterImage;
2
3 import java.awt.*;
4 import java.awt.image.*;
5 import javax.swing.*;
6
7 /**
8  * This frame shows an image with a Mandelbrot set.
9  */
10 public class RasterImageFrame extends JFrame
11 {
12     private static final double XMIN = -2;
13     private static final double XMAX = 2;
14     private static final double YMIN = -2;
15     private static final double YMAX = 2;
16     private static final int MAX_ITERATIONS = 16;
17     private static final int IMAGE_WIDTH = 400;
18     private static final int IMAGE_HEIGHT = 400;
19
20     public RasterImageFrame()
21     {
22         BufferedImage image = makeMandelbrot(IMAGE_WIDTH,
23                                             IMAGE_HEIGHT);
24         add(new JLabel(new ImageIcon(image)));
25         pack();
26     }
27 }
```

```
26
27     /**
28      * Makes the Mandelbrot image.
29      * @param width the width
30      * @param height the height
31      * @return the image
32     */
33     public BufferedImage makeMandelbrot(int width, int height)
34     {
35         var image = new BufferedImage(width, height,
36             BufferedImage.TYPE_INT_ARGB);
37         WritableRaster raster = image.getRaster();
38         ColorModel model = image.getColorModel();
39         Color fractalColor = Color.RED;
40         int argb = fractalColor.getRGB();
41         Object colorData = model.getDataElements(argb, null);
42
43         for (int i = 0; i < width; i++)
44             for (int j = 0; j < height; j++)
45             {
46                 double a = XMIN + i * (XMAX - XMIN) / width;
47                 double b = YMIN + j * (YMAX - YMIN) / height;
48                 if (!escapesToInfinity(a, b))
49                     raster.setDataElements(i, j, colorData);
50             }
51         return image;
52     }
53
54     private boolean escapesToInfinity(double a, double b)
55     {
56         double x = 0.0;
57         double y = 0.0;
58         int iterations = 0;
59         while (x <= 2 && y <= 2 && iterations < MAX_ITERATIONS)
60         {
61             double xnew = x * x - y * y + a;
62             double ynew = 2 * x * y + b;
```

```
62         x = xnew;
63         y = ynew;
64         iterations++;
65     }
66     return x > 2 || y > 2;
67 }
68 }
```

java.awt.image.BufferedImage 1.2

- `BufferedImage(int width, int height, int imageType)`

constructs a buffered image object.

Par `widt`
`ameh,` The image dimensions
`ters heig`
`:` `ht`

`imag` The image type. The most common types are
`eTyp` `TYPE_INT_RGB`, `TYPE_INT_ARGB`,
`e` `TYPE_BYTE_GRAY`, and
 `TYPE_BYTE_INDEXED`.

- `ColorModel getColorModel()`

returns the color model of this buffered image.

- `WritableRaster getRaster()`

gets the raster for accessing and modifying pixels of this buffered image.

java.awt.image.Raster 1.2

- `Object getDataElements(int x, int y, Object data)`

returns the sample data for a raster point, in an array whose element type and length depend on the color model. If data is not null, it is assumed to be an array that is appropriate for holding sample data, and it is filled. If data is null, a new array is allocated. Its element type and length depend on the color model.

- `int[] getPixel(int x, int y, int[] sampleValues)`
- `float[] getPixel(int x, int y, float[] sampleValues)`
- `double[] getPixel(int x, int y, double[] sampleValues)`
- `int[] getPixels(int x, int y, int width, int height, int[] sampleValues)`
- `float[] getPixels(int x, int y, int width, int height, float[] sampleValues)`
- `double[] getPixels(int x, int y, int width, int height, double[] sampleValues)`

return the sample values for a raster point, or a rectangle of raster points, in an array whose length depends on the color model. If sampleValues is not null, it is assumed to be sufficiently long for holding the sample values, and it is filled. If sampleValues is null, a new array is allocated. These methods are only useful if you know the meaning of the sample values for a color model.

- `void setDataElements(int x, int y, Object data)`

sets the sample data for a raster point. `data` is an array filled with the sample data for a pixel. Its element type and length depend on the color model.

- `void setPixel(int x, int y, int[] sampleValues)`
- `void setPixel(int x, int y, float[] sampleValues)`
- `void setPixel(int x, int y, double[] sampleValues)`
- `void setPixels(int x, int y, int width, int height, int[] sampleValues)`
- `void setPixels(int x, int y, int width, int height, float[] sampleValues)`
- `void setPixels(int x, int y, int width, int height, double[] sampleValues)`

set the sample values for a raster point or a rectangle of raster points. These methods are only useful if you know the encoding of the sample values for a color model.

java.awt.image.ColorModel 1.2

- `int getRGB(Object data)`

returns the ARGB value that corresponds to the sample data passed in the `data` array. Its element type and length depend on the color model.

- `Object getDataElements(int argb, Object data);`

returns the sample data for a color value. If data is not null, it is assumed to be an array that is appropriate for holding sample data, and it is filled. If data is null, a new array is allocated. data is an array filled with the sample data for a pixel. Its element type and length depend on the color model.

java.awt.Color 1.0

- `Color(int argb, boolean hasAlpha) 1.2`
creates a color with the specified combined ARGB value if hasAlpha is true, or the specified RGB value if hasAlpha is false.
- `int getRGB()`
returns the ARGB color value corresponding to this color.

11.4.2.2 Filtering Images

In the preceding section, you saw how to build up an image from scratch. However, often you want to access image data for a different reason: You already have an image and you want to improve it in some way.

Of course, you can use the `getPixel/getDataElements` methods that you saw in the preceding section to read the image data, manipulate them, and write them back. Fortunately, the Java 2D API already supplies a number of *filters* that carry out common image processing operations for you.

The image manipulations all implement the `BufferedImageOp` interface. After you construct the operation, simply call the `filter` method to transform an image into another.

[Click here to view code image](#)

```

BufferedImageOp op = . . .;
BufferedImage filteredImage
    = new BufferedImage(image.getWidth(), image.getHeight(),
image.getType());
op.filter(image, filteredImage);

```

Some operations can transform an image in place (`op.filter(image, image)`), but most can't.

Five classes implement the `BufferedImageOp` interface:

```

AffineTransformOp
RescaleOp
LookupOp
ColorConvertOp
ConvolveOp

```

The `AffineTransformOp` carries out an affine transformation on the pixels. For example, here is how you can rotate an image about its center:

[Click here to view code image](#)

```

AffineTransform transform =
AffineTransform.getRotateInstance(Math.toRadians(angle),
    image.getWidth() / 2, image.getHeight() / 2);
var op = new AffineTransformOp(transform, interpolation);
op.filter(image, filteredImage);

```

The `AffineTransformOp` constructor requires an affine transform and an *interpolation* strategy. Interpolation is necessary to determine the target image pixels if the source pixels are transformed somewhere between target pixels. For example, if you rotate source pixels, they will generally not fall exactly onto target pixels. There are three interpolation strategies: `AffineTransformOp.TYPE_BICUBIC`, `AffineTransformOp.TYPE_BILINEAR`, and `AffineTransformOp.TYPE_NEAREST_NEIGHBOR`. Bicubic interpolation takes a bit longer but looks better than the other two.

The program in Listing 11.22 lets you rotate an image by 5 degrees (see Figure 11.57).




Figure 11.57 A rotated image

The RescaleOp carries out a rescaling operation

$$x_{\text{new}} = a \cdot x + b$$

for each of the color components in the image. (Alpha components are not affected.) The effect of rescaling with $a > 1$ is to brighten the image. Construct the RescaleOp by specifying the scaling parameters and optional rendering hints. In Listing 11.22, we use:

[Click here to view code image](#)

```
float a = 1.1f;
float b = 20.0f;
var op = new RescaleOp(a, b, null);
```

You can also supply separate scaling values for each color component—see the API notes.

The LookupOp operation lets you specify an arbitrary mapping of sample values. Supply a table that specifies how each value should be mapped. In

the example program, we compute the *negative* of all colors, changing the color c to $255 - c$.

The `LookupOp` constructor requires an object of type `LookupTable` and a map of optional hints. The `LookupTable` class is abstract, with two concrete subclasses: `ByteLookupTable` and `ShortLookupTable`. Since RGB color values are bytes, a `ByteLookupTable` should suffice. However, because of the bug described in https://bugs.java.com/bugdatabase/view_bug.do?bug_id=6183251, we will use a `ShortLookupTable` instead. Here is how we construct the `LookupOp` for the example program:

[Click here to view code image](#)

```
var negative = new short[256];
for (int i = 0; i < 256; i++) negative[i] = (short) (255 - i);
var table = new ShortLookupTable(0, negative);
var op = new LookupOp(table, null);
```

The lookup is applied to each color component separately, but not to the alpha component. You can also supply different lookup tables for each color component—see the API notes.



Note

You cannot apply a `LookupOp` to an image with an indexed color model. (In those images, each sample value is an offset into a color palette.)

The `ColorConvertOp` is useful for color space conversions. We do not discuss it here.

The most powerful of the transformations is the `ConvolveOp`, which carries out a mathematical *convolution*. Without getting too deeply into the mathematical details, the basic idea is simple. Consider, for example, the *blur filter* (see [Figure 11.58](#)).




Figure 11.58 Blurring an image

The blurring is achieved by replacing each pixel with the *average* value from the pixel and its eight neighbors. Intuitively, it makes sense why this operation would blur out the picture. Mathematically, the averaging can be expressed as a convolution operation with the following *kernel*:

$$\begin{matrix} 1/9 & 1/9 & 1/9 \\ 1/9 & 1/9 & 1/9 \\ 1/9 & 1/9 & 1/9 \end{matrix}$$

The kernel of a convolution is a matrix that tells what weights should be applied to the neighboring values. The kernel above produces a blurred image. A different kernel carries out *edge detection*, locating the areas of color changes:

$$\begin{matrix} 0 & -1 & 0 \\ -1 & 4 & -1 \\ 0 & -1 & 0 \end{matrix}$$

Edge detection is an important technique for analyzing photographic images (see [Figure 11.59](#)).



Figure 11.59 Edge detection and inversion

To construct a convolution operation, first set up an array of the values for the kernel and construct a `Kernel` object. Then, construct a `ConvolveOp` object from the kernel and use it for filtering.

[Click here to view code image](#)

```
float[] elements =
{
    0.0f, -1.0f, 0.0f,
    -1.0f, 4.f, -1.0f,
    0.0f, -1.0f, 0.0f
};

var kernel = new Kernel(3, 3, elements);
var op = new ConvolveOp(kernel);
op.filter(image, filteredImage);
```

The program in [Listing 11.22](#) allows a user to load in a GIF or JPEG image and carry out the image manipulations that we discussed. Thanks to the power of the operations provided by Java 2D API, the program is very simple.

Listing 11.22

`imageProcessing/ImageProcessingFrame.java`

[Click here to view code image](#)

```
1 package imageProcessing;
2
3 import java.awt.*;
4 import java.awt.geom.*;
5 import java.awt.image.*;
6 import java.io.*;
7
8 import javax.imageio.*;
9 import javax.swing.*;
10 import javax.swing.filechooser.*;
11
12 /**
13  * This frame has a menu to load an image and to specify
14  * various transformations, and a
15  * component to show the resulting image.
16 */
17 public class ImageProcessingFrame extends JFrame
18 {
19     private static final int DEFAULT_WIDTH = 400;
20     private static final int DEFAULT_HEIGHT = 400;
21
22     private BufferedImage image;
23
24     public ImageProcessingFrame()
25     {
26         setTitle("ImageProcessingTest");
27         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
28
29         add(new JComponent()
30         {
31             public void paintComponent(Graphics g)
32             {
33                 if (image != null) g.drawImage(image, 0, 0,
null);
34             }
35         });
36     }
37 }
```

```
34         });
35
36     var fileMenu = new JMenu("File");
37     var openItem = new JMenuItem("Open");
38     openItem.addActionListener(event -> openFileDialog());
39     fileMenu.add(openItem);
40
41     var exitItem = new JMenuItem("Exit");
42     exitItem.addActionListener(event -> System.exit(0));
43     fileMenu.add(exitItem);
44
45     var editMenu = new JMenu("Edit");
46     var blurItem = new JMenuItem("Blur");
47     blurItem.addActionListener(event ->
48     {
49         float weight = 1.0f / 9.0f;
50         float[] elements = new float[9];
51         for (int i = 0; i < 9; i++)
52             elements[i] = weight;
53         convolve(elements);
54     });
55     editMenu.add(blurItem);
56
57     var sharpenItem = new JMenuItem("Sharpen");
58     sharpenItem.addActionListener(event ->
59     {
60         float[] elements = { 0.0f, -1.0f, 0.0f, -1.0f,
61                             5.f, -1.0f, 0.0f, -1.0f, 0.0f };
62         convolve(elements);
63     });
64     editMenu.add(sharpenItem);
65
66     var brightenItem = new JMenuItem("Brighten");
67     brightenItem.addActionListener(event ->
68     {
69         float a = 1.1f;
70         float b = 20.0f;
71         var op = new RescaleOp(a, b, null);
```

```
71         filter(op);
72     });
73     editMenu.add(brightenItem);
74
75     var edgeDetectItem = new JMenuItem("Edge detect");
76     edgeDetectItem.addActionListener(event ->
77     {
78         float[] elements = { 0.0f, -1.0f, 0.0f, -1.0f,
79                             4.f, -1.0f, 0.0f, -1.0f, 0.0f };
80         convolve(elements);
81     });
82     editMenu.add(edgeDetectItem);
83
84     var negativeItem = new JMenuItem("Negative");
85     negativeItem.addActionListener(event ->
86     {
87         short[] negative = new short[256 * 1];
88         for (int i = 0; i < 256; i++)
89             negative[i] = (short) (255 - i);
90         var table = new ShortLookupTable(0, negative);
91         var op = new LookupOp(table, null);
92         filter(op);
93     });
94     editMenu.add(negativeItem);
95
96     var rotateItem = new JMenuItem("Rotate");
97     rotateItem.addActionListener(event ->
98     {
99         if (image == null) return;
100        var transform =
101            AffineTransform.getRotateInstance(Math.toRadians(5),
102                                         image.getWidth() / 2, image.getHeight() /
103                                         2);
104        var op = new AffineTransformOp(transform,
105                                      AffineTransformOp.TYPE_BICUBIC);
106        filter(op);
107    });
108    editMenu.add(rotateItem);
```

```
106
107     var menuBar = new JMenuBar();
108     menuBar.add(fileMenu);
109     menuBar.add(editMenu);
110     setJMenuBar(menuBar);
111 }
112
113 /**
114  * Open a file and load the image.
115 */
116 public void openFile()
117 {
118     var chooser = new JFileChooser(".");
119     chooser.setCurrentDirectory(new
File(getClass().getPackage().getName()));
120     String[] extensions = ImageIO.getReaderFileSuffixes();
121     chooser.setFileFilter(new
FileNameExtensionFilter("Image files", extensions));
122     int r = chooser.showOpenDialog(this);
123     if (r != JFileChooser.APPROVE_OPTION) return;
124
125     try
126     {
127         Image img = ImageIO.read(chooser.getSelectedFile());
128         image = new BufferedImage(img.getWidth(null),
img.getHeight(null),
129                         BufferedImage.TYPE_INT_RGB);
130         image.getGraphics().drawImage(img, 0, 0, null);
131     }
132     catch (IOException e)
133     {
134         JOptionPane.showMessageDialog(this, e);
135     }
136     repaint();
137 }
138
139 /**
140  * Apply a filter and repaint.
```

```
141     * @param op the image operation to apply
142     */
143     private void filter(BufferedImageOp op)
144     {
145         if (image == null) return;
146         image = op.filter(image, null);
147         repaint();
148     }
149
150 /**
151 * Apply a convolution and repaint.
152 * @param elements the convolution kernel (an array of 9
matrix elements)
153 */
154     private void convolve(float[] elements)
155     {
156         var kernel = new Kernel(3, 3, elements);
157         var op = new ConvolveOp(kernel);
158         filter(op);
159     }
160 }
```

java.awt.image.BufferedImageOp 1.2

- `BufferedImage filter(BufferedImage source, BufferedImage dest)`

applies the image operation to the source image and stores the result in the destination image. If dest is null, a new destination image is created. The destination image is returned.

java.awt.image.AffineTransformOp 1.2

- `AffineTransformOp(AffineTransform t, int interpolationType)`

constructs an affine transform operator. The interpolation type is one of `TYPE_BILINEAR`, `TYPE_BICUBIC`, or `TYPE_NEAREST_NEIGHBOR`.

`java.awt.image.RescaleOp` 1.2

- `RescaleOp(float a, float b, RenderingHints hints)`
- `RescaleOp(float[] as, float[] bs, RenderingHints hints)`

construct a rescale operator that carries out the scaling operation $x_{\text{new}} = a \cdot x + b$. When using the first constructor, all color components (but not the alpha component) are scaled with the same coefficients. When using the second constructor, you supply either the values for each color component, in which case the alpha component is unaffected, or the values for both alpha and color components.

`java.awt.image.LookupOp` 1.2

- `LookupOp(LookupTable table, RenderingHints hints)`

constructs a lookup operator for the given lookup table.

`java.awt.image.ByteLookupTable` 1.2

- `ByteLookupTable(int offset, byte[] data)`
- `ByteLookupTable(int offset, byte[][] data)`

construct a lookup table for converting `byte` values. The offset is subtracted from the input before the lookup. The values in the first constructor are applied to all color components but not the alpha component. When using the second constructor, supply either the values for each color component, in which case the alpha component is unaffected, or the values for both alpha and color components.

`java.awt.image.ShortLookupTable 1.2`

- `ShortLookupTable(int offset, short[] data)`
- `ShortLookupTable(int offset, short[][] data)`

construct a lookup table for converting `short` values. The offset is subtracted from the input before the lookup. The values in the first constructor are applied to all color components but not the alpha component. When using the second constructor, supply either the values for each color component, in which case the alpha component is unaffected, or the values for both alpha and color components.

`java.awt.image.ConvolveOp 1.2`

- `ConvolveOp(Kernel kernel)`
- `ConvolveOp(Kernel kernel, int edgeCondition, RenderingHints hints)`

construct a convolution operator. The edge condition specified is one of EDGE_NO_OP and EDGE_ZERO_FILL. Edge values need to be treated specially because they don't have sufficient neighboring values to compute the convolution. The default is EDGE_ZERO_FILL.

java.awt.image.Kernel 1.2

- Kernel(int width, int height, float[] matrixElements)

constructs a kernel for the given matrix.

11.5 Printing

In the following sections, I'll show you how you can easily print a drawing on a single sheet of paper, how you can manage a multipage printout, and how you can save a printout as a PostScript file.

11.5.1 Graphics Printing

In this section, we will tackle what is probably the most common printing situation: printing a 2D graphic. Of course, the graphic can contain text in various fonts or even consist entirely of text.

To generate a printout, you have to take care of these two tasks:

- Supply an object that implements the `Printable` interface
- Start a print job

The `Printable` interface has a single method:

[Click here to view code image](#)

```
int print(Graphics g, PageFormat format, int page)
```

That method is called whenever the print engine needs to have a page formatted for printing. Your code draws the text and the images to be printed onto the graphics context. The page format tells you the paper size and the print margins. The page number tells you which page to render.

To start a print job, use the `PrinterJob` class. First, call the static `getPrinterJob` method to get a print job object. Then set the `Printable` object that you want to print.

[Click here to view code image](#)

```
Printable canvas = . . .;  
PrinterJob job = PrinterJob.getPrinterJob();  
job.setPrintable(canvas);
```



Caution

The class `PrintJob` handles JDK 1.1-style printing. That class is now obsolete. Do not confuse it with the `PrinterJob` class.

Before starting the print job, you should call the `printDialog` method to display a print dialog box (see [Figure 11.60](#)). That dialog box gives the user a chance to select the printer to be used (in case multiple printers are available), the page range that should be printed, and various printer settings.




Figure 11.60 A cross-platform print dialog box

Collect printer settings in an object of a class that implements the `PrintRequestAttributeSet` interface, such as the `HashPrintRequestAttributeSet` class.

[Click here to view code image](#)

```
var attributes = new HashPrintRequestAttributeSet();
```

Add attribute settings and pass the `attributes` object to the `printDialog` method.

The `printDialog` method returns `true` if the user clicked OK and `false` if the user canceled the dialog box. If the user accepted, call the `print` method of the `PrinterJob` class to start the printing process. The `print` method might throw a `PrinterException`. Here is the outline of the printing code:

[Click here to view code image](#)

```
if (job.printDialog(attributes))  
{  
    try  
    {  
        job.print(attributes);  
    }  
    catch (PrinterException e)  
    {  
        . . .  
    }  
}
```



Note

Prior to JDK 1.4, the printing system used the native print and page setup dialog boxes of the host platform. To show a native print dialog box, call the `printDialog` method with no parameters. (There is no way to collect user settings in an attribute set.)

During printing, the `print` method of the `PrinterJob` class makes repeated calls to the `print` method of the `Printable` object associated with the job.

Since the job does not know how many pages you want to print, it simply keeps calling the `print` method. As long as the `print` method returns the value `Printable.PAGE_EXISTS`, the print job keeps producing pages. When the `print` method returns `Printable.NO_SUCH_PAGE`, the print job stops.



Caution

The page numbers that the print job passes to the `print` method start with page 0.

Therefore, the print job doesn't have an accurate page count until after the printout is complete. For that reason, the print dialog box can't display the correct page range—instead, it displays “Pages 1 to 1.” You will see in the next section how to avoid this blemish by supplying a `Book` object to the print job.

During the printing process, the print job repeatedly calls the `print` method of the `Printable` object. The print job is allowed to make multiple calls *for the same page*. You should therefore not count pages inside the `print` method but always rely on the page number parameter. There is a good reason why the print job might call the `print` method repeatedly for the same page. Some printers, in particular dot-matrix and inkjet printers, use *banding*. They print one band at a time, advance the paper, and then print the next band. The print job might use banding even for laser printers that print a full page at a time—it gives the print job a way of managing the size of the spool file.

If the print job needs the `Printable` object to print a band, it sets the clip area of the graphics context to the requested band and calls the `print` method. Its drawing operations are clipped against the band rectangle, and only those drawing elements that show up in the band are rendered. Your `print` method need not be aware of that process, with one caveat: It should *not* interfere with the clip area.



Caution

The `Graphics` object that your `print` method gets is also clipped against the page margins. If you replace the clip area, you can draw outside the margins. Especially in a printer graphics context, the clipping area must be respected. Call `clip`, not `setClip`, to further restrict the clipping area. If you must remove a clip area, make sure to call `getClip` at the beginning of your `print` method and restore that clip area.

The `PageFormat` parameter of the `print` method contains information about the printed page. The methods `getWidth` and `getHeight` return the paper size, measured in *points*. (One point is 1/72 of an inch; an inch equals 25.4 millimeters.) For example, A4 paper is approximately 595×842 points, and US Letter paper is 612×792 points.

Points are a common measurement in the printing trade in the United States. Much to the chagrin of the rest of the world, the printing package uses point units. There are two purposes for that: paper sizes and paper margins are measured in points, and points are the default unit for all print graphics contexts. You can verify that in the example program at the end of this section. The program prints two lines of text that are 72 units apart. Run the example program and measure the distance between the baselines; they are exactly 1 inch or 25.4 millimeters apart.

The `getWidth` and `getHeight` methods of the `PageFormat` class give you the complete paper size. Not all of the paper area is printable. Users typically select margins, and even if they don't, printers need to somehow grip the sheets of paper on which they print and therefore have a small unprintable area around the edges.

The methods `getImageableWidth` and `getImageableHeight` tell you the dimensions of the area that you can actually fill. However, the margins need not be symmetrical, so you must also know the top left corner of the imageable area (see [Figure 11.61](#)), which you obtain by the methods `getImageableX` and `getImageableY`.




Figure 11.61 Page format measurements



Tip

The graphics context that you receive in the `print` method is clipped to exclude the margins, but the origin of the coordinate system is nevertheless the top left corner of the paper. It makes sense to translate the coordinate system to the top left corner of the imageable area. Simply start your `print` method with

[Click here to view code image](#)

```
g.translate(pageFormat.getImageableX(),
pageFormat.getImageableY());
```

If you want your users to choose the settings for the page margins or to switch between portrait and landscape orientation without setting other

printing attributes, call the `pageDialog` method of the `PrinterJob` class:

[Click here to view code image](#)

```
PageFormat format = job.pageDialog(attributes);
```



Note

One of the tabs of the print dialog box contains the page setup dialog (see [Figure 11.62](#)). You might still want to give users an option to set the page format before printing, especially if your program presents a “what you see is what you get” display of the pages to be printed. The `pageDialog` method returns a `PageFormat` object with the user settings.




Figure 11.62 A cross-platform page setup dialog

The program in [Listings 11.23](#) and [11.24](#) shows how to render the same set of shapes on the screen and on the printed page. A subclass of JPanel implements the Printable interface. Both the paintComponent and the print methods call the same method to carry out the actual drawing.

[Click here to view code image](#)

```
class PrintPanel extends JPanel implements Printable
{
    public void paintComponent(Graphics g)
    {
        super.paintComponent(g);
        var g2 = (Graphics2D) g;
        drawPage(g2);
    }

    public int print(Graphics g, PageFormat pf, int page) throws
PrinterException
    {
        if (page >= 1) return Printable.NO_SUCH_PAGE;
        var g2 = (Graphics2D) g;
        g2.translate(pf.getImageableX(), pf.getImageableY());
        drawPage(g2);
        return Printable.PAGE_EXISTS;
    }

    public void drawPage(Graphics2D g2)
    {
        // shared drawing code goes here
        . . .
    }
    . . .
}
```

This example displays and prints the image shown in [Figure 11.50](#)—namely, the outline of the message “Hello, World” used as a clipping area for a pattern of lines.

Click the Print button to start printing, or click the Page setup button to open the page setup dialog box. [Listing 11.23](#) shows the code.



Note

To show a native page setup dialog box, pass a default `PageFormat` object to the `pageDialog` method. The method clones that object, modifies it according to the user selections in the dialog box, and returns the cloned object.

[Click here to view code image](#)

```
PageFormat defaultFormat = printJob.defaultPage();
PageFormat selectedFormat = printJob.pageDialog(defaultFormat);
```

Listing 11.23 print/PrintTestFrame.java

[Click here to view code image](#)

```
1 package print;
2
3 import java.awt.*;
4 import java.awt.print.*;
5
6 import javax.print.attribute.*;
7 import javax.swing.*;
8
9 /**
10  * This frame shows a panel with 2D graphics and buttons to
11  * print the graphics and to set up
12  * the page format.
13 */
14
15 public class PrintTestFrame extends JFrame
16 {
```

```
17
18     public PrintTestFrame()
19     {
20         canvas = new PrintComponent();
21         add(canvas, BorderLayout.CENTER);
22
23         attributes = new HashPrintRequestAttributeSet();
24
25         var buttonPanel = new JPanel();
26         var printButton = new JButton("Print");
27         buttonPanel.add(printButton);
28         printButton.addActionListener(event ->
29             {
30                 try
31                 {
32                     PrinterJob job = PrinterJob.getPrinterJob();
33                     job.setPrintable(canvas);
34                     if (job.printDialog(attributes))
35                     job.print(attributes);
36                 }
37                 catch (PrinterException e)
38                 {
39                     JOptionPane.showMessageDialog(PrintTestFrame.this, e);
40                 });
41
42         var pageSetupButton = new JButton("Page setup");
43         buttonPanel.add(pageSetupButton);
44         pageSetupButton.addActionListener(event ->
45             {
46                 PrinterJob job = PrinterJob.getPrinterJob();
47                 job.pageDialog(attributes);
48             });
49
50         add(buttonPanel, BorderLayout.NORTH);
51         pack();
```

```
52      }
53 }
```

Listing 11.24 print/PrintComponent.java

[Click here to view code image](#)

```
1 package print;
2
3 import java.awt.*;
4 import java.awt.font.*;
5 import java.awt.geom.*;
6 import java.awt.print.*;
7 import javax.swing.*;
8
9 /**
10  * This component generates a 2D graphics image for screen
display and printing.
11 */
12 public class PrintComponent extends JComponent implements
Printable
13 {
14     private static final Dimension PREFERRED_SIZE = new
Dimension(300, 300);
15
16     public void paintComponent(Graphics g)
17     {
18         var g2 = (Graphics2D) g;
19         drawPage(g2);
20     }
21
22     public int print(Graphics g, PageFormat pf, int page)
throws PrinterException
23     {
24         if (page >= 1) return Printable.NO_SUCH_PAGE;
25         var g2 = (Graphics2D) g;
26         g2.translate(pf.getImageableX(), pf.getImageableY());
```

```
27         g2.draw(new Rectangle2D.Double(0, 0,
28             pf.getImageableWidth(), pf.getImageableHeight())));
29
30     drawPage(g2);
31     return Printable.PAGE_EXISTS;
32 }
33 /**
34  * This method draws the page both on the screen and the
35  * printer graphics context.
36  * @param g2 the graphics context
37  */
38 public void drawPage(Graphics2D g2)
39 {
40     FontRenderContext context = g2.getFontRenderContext();
41     var f = new Font("Serif", Font.PLAIN, 72);
42     var clipShape = new GeneralPath();
43
44     var layout = new TextLayout("Hello", f, context);
45     AffineTransform transform =
46     AffineTransform.getTranslateInstance(0, 72);
47     Shape outline = layout.getOutline(transform);
48     clipShape.append(outline, false);
49
50     layout = new TextLayout("World", f, context);
51     transform = AffineTransform.getTranslateInstance(0,
52         144);
53     outline = layout.getOutline(transform);
54     clipShape.append(outline, false);
55
56     g2.draw(clipShape);
57     g2.clip(clipShape);
58
59     final int NLines = 50;
60     var p = new Point2D.Double(0, 0);
61     for (int i = 0; i < NLines; i++)
62     {
63         double x = (2 * getWidth() * i) / NLines;
```

```
61         double y = (2 * getHeight() * (N_LINES - 1 - i)) /  
N_LINES;  
62         var q = new Point2D.Double(x, y);  
63         g2.draw(new Line2D.Double(p, q));  
64     }  
65 }  
66  
67 public Dimension getPreferredSize() { return PREFERRED_SIZE;  
}  
68 }
```

java.awt.print.Printable 1.2

- `int print(Graphics g, PageFormat format, int pageNumber)`

renders a page and returns `PAGE_EXISTS`, or returns `NO_SUCH_PAGE`.

Parameters: `g` The graphics context onto which the page is rendered

`format` The format of the page to draw on

`pageNum` The number of the requested page

java.awt.print.PrinterJob 1.2

- `static PrinterJob getPrinterJob()`
returns a printer job object.
- `PageFormat defaultPage()`

returns the default page format for this printer.

- `boolean printDialog(PrintRequestAttributeSet attributes)`
- `boolean printDialog()`

open a print dialog box to allow a user to select the pages to be printed and to change print settings. The first method displays a cross-platform dialog box, the second a native dialog box. The first method modifies the `attributes` object to reflect the user settings. Both methods return `true` if the user accepts the dialog box.

- `PageFormat pageDialog(PrintRequestAttributeSet attributes)`
- `PageFormat pageDialog(PageFormat defaults)`

display a page setup dialog box. The first method displays a cross-platform dialog box, the second a native dialog box. Both methods return a `PageFormat` object with the format that the user requested in the dialog box. The first method modifies the `attributes` object to reflect the user settings. The second method does not modify the `defaults` object.

- `void setPrintable(Printable p)`
- `void setPrintable(Printable p, PageFormat format)`

set the `Printable` of this print job and an optional page format.

- `void print()`
- `void print(PrintRequestAttributeSet attributes)`

print the current `Printable` by repeatedly calling its `print` method and sending the rendered pages to the printer, until no

more pages are available.

java.awt.print.PageFormat 1.2

- double getWidth()
- double getHeight()

return the width and height of the page.

- double getImageableWidth()
- double getImageableHeight()

return the width and height of the imageable area of the page.

- double getImageableX()
- double getImageableY()

return the position of the top left corner of the imageable area.

- int getOrientation()

returns one of `PORTRAIT`, `LANDSCAPE`, or `REVERSE_LANDSCAPE`. Page orientation is transparent to programmers because the page format and graphics context settings automatically reflect the page orientation.

11.5.2 Multiple-Page Printing

In practice, you usually don't pass a raw `Printable` object to a print job. Instead, you should obtain an object of a class that implements the `Pageable` interface. The Java platform supplies one such class, called `Book`. A book is made up of sections, each of which is a `Printable` object. To make a book, add `Printable` objects and their page counts.

[Click here to view code image](#)

```
var book = new Book();
Printable coverPage = . . .;
Printable bodyPages = . . .;
book.append(coverPage, pageFormat); // append 1 page
book.append(bodyPages, pageFormat, pageCount);
```

Then, use the `setPageable` method to pass the `Book` object to the print job.

```
printJob.setPageable(book);
```

Now the print job knows exactly how many pages to print, so the print dialog box displays an accurate page range and the user can select the entire range or subranges.



Caution

When the print job calls the `print` methods of the `Printable` sections, it passes the current page number of the *book*, and not of each *section*, as the current page number. That is a huge pain—each section must know the page counts of the preceding sections to make sense of the page number parameter.

From your perspective as a programmer, the biggest challenge of using the `Book` class is that you must know how many pages each section will have when you print it. Your `Printable` class needs a *layout algorithm* that computes the layout of the material on the printed pages. Before printing starts, invoke that algorithm to compute the page breaks and the page count. You can retain the layout information so you have it handy during the printing process.

You must guard against the possibility that the user has changed the page format. If that happens, you must recompute the layout, even if the information that you want to print has not changed.

[Listing 11.26](#) shows how to produce a multipage printout. This program prints a message in very large characters on a number of pages (see [Figure 11.63](#)). You can then trim the margins and tape the pages together to form a banner.




Figure 11.63 A banner

The `layoutPages` method of the `Banner` class computes the layout. We first lay out the message string in a 72-point font. We then compute the height of the resulting string and compare it with the imageable height of the page. We derive a scale factor from these two measurements. When printing the string, we magnify it by that scale factor.



Caution

To lay out your information precisely, you usually need access to the printer graphics context. Unfortunately, there is no way to obtain that graphics context before printing actually starts. In our example program, we make do with the screen graphics context and hope that the font metrics of the screen and printer match.

The `getPageCount` method of the `Banner` class first calls the `layout` method. Then it scales up the width of the string and divides it by the imageable width of each page. The quotient, rounded up to the next integer, is the page count.

It sounds like it might be difficult to print the banner because characters can be broken across multiple pages. However, thanks to the power of the Java

2D API, this turns out not to be a problem at all. When a particular page is requested, we simply use the `translate` method of the `Graphics2D` class to shift the top left corner of the string to the left. Then, we set a clip rectangle that equals the current page (see [Figure 11.64](#)). Finally, we scale the graphics context with the scale factor that the `layout` method computed.




Figure 11.64 Printing a page of a banner

This example shows the power of transformations. The drawing code is kept simple, and the transformation does all the work of placing the drawing in the appropriate place. Finally, the clip cuts away the part of the image that falls outside the page. This program shows another compelling use of transformations—to display a print preview.

Listing 11.25 book/BookTestFrame.java

[Click here to view code image](#)

```
1 package book;  
2  
3 import java.awt.*;  
4 import java.awt.print.*;
```

```
5
6 import javax.print.attribute.*;
7 import javax.swing.*;
8
9 /**
10  * This frame has a text field for the banner text and buttons
for printing, page setup, and
11 * print preview.
12 */
13 public class BookTestFrame extends JFrame
14 {
15     private JTextField text;
16     private PageFormat pageFormat;
17     private PrintRequestAttributeSet attributes;
18
19     public BookTestFrame()
20     {
21         text = new JTextField();
22         add(text, BorderLayout.NORTH);
23
24         attributes = new HashPrintRequestAttributeSet();
25
26         var buttonPanel = new JPanel();
27
28         var printButton = new JButton("Print");
29         buttonPanel.add(printButton);
30         printButton.addActionListener(event ->
31             {
32                 try
33                 {
34                     PrinterJob job = PrinterJob.getPrinterJob();
35                     job.setPageable(makeBook());
36                     if (job.printDialog(attributes))
37                     {
38                         job.print(attributes);
39                     }
40                 }
41             catch (PrinterException e)
```

```
42         {
43
44             JOptionPane.showMessageDialog(BookTestFrame.this, e);
45         });
46
47         var pageSetupButton = new JButton("Page setup");
48         buttonPanel.add(pageSetupButton);
49         pageSetupButton.addActionListener(event ->
50         {
51             PrinterJob job = PrinterJob.getPrinterJob();
52             pageFormat = job.pageDialog(attributes);
53         });
54
55         var printPreviewButton = new JButton("Print preview");
56         buttonPanel.add(printPreviewButton);
57         printPreviewButton.addActionListener(event ->
58         {
59             var dialog = new PrintPreviewDialog(makeBook());
60             dialog.setVisible(true);
61         });
62
63         add(buttonPanel, BorderLayout.SOUTH);
64         pack();
65     }
66
67     /**
68      * Makes a book that contains a cover page and the pages
69      * for the banner.
70
71     public Book makeBook()
72     {
73         if (pageFormat == null)
74         {
75             PrinterJob job = PrinterJob.getPrinterJob();
76             pageFormat = job.defaultPage();
77         }
78         var book = new Book();
```

```
78     String message = text.getText();
79     var banner = new Banner(message);
80     int pageCount = banner.getPageCount((Graphics2D)
81         getGraphics(), pageFormat);
82     book.append(new CoverPage(message + " (" + pageCount + "
83     pages)", pageFormat);
84     book.append(banner, pageFormat, pageCount);
85     return book;
86 }
87 }
```

Listing 11.26 book/Banner.java

[Click here to view code image](#)

```
1 package book;
2
3 import java.awt.*;
4 import java.awt.font.*;
5 import java.awt.geom.*;
6 import java.awt.print.*;
7
8 /**
9  * A banner that prints a text string on multiple pages.
10 */
11 public class Banner implements Printable
12 {
13     private String message;
14     private double scale;
15
16     /**
17      * Constructs a banner.
18      * @param m the message string
19      */
20     public Banner(String m)
21     {
22         message = m;
```

```
23     }
24
25     /**
26      * Gets the page count of this section.
27      * @param g2 the graphics context
28      * @param pf the page format
29      * @return the number of pages needed
30      */
31     public int getPageCount(Graphics2D g2, PageFormat pf)
32     {
33         if (message.equals("")) return 0;
34         FontRenderContext context = g2.getFontRenderContext();
35         var f = new Font("Serif", Font.PLAIN, 72);
36         Rectangle2D bounds = f.getStringBounds(message,
context);
37         scale = pf.getImageableHeight() / bounds.getHeight();
38         double width = scale * bounds.getWidth();
39         int pages = (int) Math.ceil(width /
pf.getImageableWidth());
40         return pages;
41     }
42
43     public int print(Graphics g, PageFormat pf, int page)
throws PrinterException
44     {
45         var g2 = (Graphics2D) g;
46         if (page > getPageCount(g2, pf)) return
Printable.NO_SUCH_PAGE;
47         g2.translate(pf.getImageableX(), pf.getImageableY());
48
49         drawPage(g2, pf, page);
50         return Printable.PAGE_EXISTS;
51     }
52
53     public void drawPage(Graphics2D g2, PageFormat pf, int
page)
54     {
55         if (message.equals("")) return;
```

```
56     page--; // account for cover page
57
58     drawCropMarks(g2, pf);
59     g2.clip(new Rectangle2D.Double(0, 0,
pf.getImageableWidth(), pf.getImageableHeight()));
60     g2.translate(-page * pf.getImageableWidth(), 0);
61     g2.scale(scale, scale);
62     FontRenderContext context = g2.getFontRenderContext();
63     var f = new Font("Serif", Font.PLAIN, 72);
64     var layout = new TextLayout(message, f, context);
65     AffineTransform transform =
AffineTransform.getTranslateInstance(0, layout.getAscent());
66     Shape outline = layout.getOutline(transform);
67     g2.draw(outline);
68 }
69
70 /**
71 * Draws 1/2" crop marks in the corners of the page.
72 * @param g2 the graphics context
73 * @param pf the page format
74 */
75 public void drawCropMarks(Graphics2D g2, PageFormat pf)
76 {
77     final double C = 36; // crop mark length = 1/2 inch
78     double w = pf.getImageableWidth();
79     double h = pf.getImageableHeight();
80     g2.draw(new Line2D.Double(0, 0, 0, C));
81     g2.draw(new Line2D.Double(0, 0, C, 0));
82     g2.draw(new Line2D.Double(w, 0, w, C));
83     g2.draw(new Line2D.Double(w, 0, w - C, 0));
84     g2.draw(new Line2D.Double(0, h, 0, h - C));
85     g2.draw(new Line2D.Double(0, h, C, h));
86     g2.draw(new Line2D.Double(w, h, w, h - C));
87     g2.draw(new Line2D.Double(w, h, w - C, h));
88 }
89 }
90
91 /**
```

```
92 * This class prints a cover page with a title.  
93 */  
94 class CoverPage implements Printable  
95 {  
96     private String title;  
97  
98     /**  
99      * Constructs a cover page.  
100     * @param t the title  
101    */  
102    public CoverPage(String t)  
103    {  
104        title = t;  
105    }  
106  
107    public int print(Graphics g, PageFormat pf, int page)  
throws PrinterException  
108    {  
109        if (page >= 1) return Printable.NO_SUCH_PAGE;  
110        var g2 = (Graphics2D) g;  
111        g2.setPaint(Color.black);  
112        g2.translate(pf.getImageableX(), pf.getImageableY());  
113        FontRenderContext context = g2.getFontRenderContext();  
114        Font f = g2.getFont();  
115        var layout = new TextLayout(title, f, context);  
116        float ascent = layout.getAscent();  
117        g2.drawString(title, 0, ascent);  
118        return Printable.PAGE_EXISTS;  
119    }  
120 }
```

Listing 11.27 book/PrintPreviewDialog.java

[Click here to view code image](#)

```
1 package book;  
2
```

```
3 import java.awt.*;
4 import java.awt.print.*;
5
6 import javax.swing.*;
7
8 /**
9  * This class implements a generic print preview dialog.
10 */
11 public class PrintPreviewDialog extends JDialog
12 {
13     private static final int DEFAULT_WIDTH = 300;
14     private static final int DEFAULT_HEIGHT = 300;
15
16     private PrintPreviewCanvas canvas;
17
18     /**
19      * Constructs a print preview dialog.
20      * @param p a Printable
21      * @param pf the page format
22      * @param pages the number of pages in p
23      */
24     public PrintPreviewDialog(Printable p, PageFormat pf, int
pages)
25     {
26         var book = new Book();
27         book.append(p, pf, pages);
28         layoutUI(book);
29     }
30
31     /**
32      * Constructs a print preview dialog.
33      * @param b a Book
34      */
35     public PrintPreviewDialog(Book b)
36     {
37         layoutUI(b);
38     }
39
```

```
40     /**
41      * Lays out the UI of the dialog.
42      * @param book the book to be previewed
43      */
44     public void layoutUI(Book book)
45     {
46         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
47
48         canvas = new PrintPreviewCanvas(book);
49         add(canvas, BorderLayout.CENTER);
50
51         var buttonPanel = new JPanel();
52
53         var nextButton = new JButton("Next");
54         buttonPanel.add(nextButton);
55         nextButton.addActionListener(event ->
56             canvas.flipPage(1));
57
58         var previousButton = new JButton("Previous");
59         buttonPanel.add(previousButton);
60         previousButton.addActionListener(event ->
61             canvas.flipPage(-1));
62
63         var closeButton = new JButton("Close");
64         buttonPanel.add(closeButton);
65         closeButton.addActionListener(event ->
66             setVisible(false));
67     }
```

Listing 11.28 book/PrintPreviewCanvas.java

[Click here to view code image](#)

```
1 package book;
2
3 import java.awt.*;
4 import java.awt.geom.*;
5 import java.awt.print.*;
6 import javax.swing.*;
7
8 /**
9  * The canvas for displaying the print preview.
10 */
11 class PrintPreviewCanvas extends JComponent
12 {
13     private Book book;
14     private int currentPage;
15
16     /**
17      * Constructs a print preview canvas.
18      * @param b the book to be previewed
19      */
20     public PrintPreviewCanvas(Book b)
21     {
22         book = b;
23         currentPage = 0;
24     }
25
26     public void paintComponent(Graphics g)
27     {
28         var g2 = (Graphics2D) g;
29         PageFormat pageFormat = book.getPageFormat(currentPage);
30
31         double xoff; // x offset of page start in window
32         double yoff; // y offset of page start in window
33         double scale; // scale factor to fit page in window
34         double px = pageFormat.getWidth();
35         double py = pageFormat.getHeight();
36         double sx = getWidth() - 1;
37         double sy = getHeight() - 1;
38         if (px / py < sx / sy) // center horizontally
```

```
39      {
40          scale = sy / py;
41          xoff = 0.5 * (sx - scale * px);
42          yoff = 0;
43      }
44  else
45      // center vertically
46  {
47      scale = sx / px;
48      xoff = 0;
49      yoff = 0.5 * (sy - scale * py);
50  }
51 g2.translate((float) xoff, (float) yoff);
52 g2.scale((float) scale, (float) scale);
53
54 // draw page outline (ignoring margins)
55 var page = new Rectangle2D.Double(0, 0, px, py);
56 g2.setPaint(Color.white);
57 g2.fill(page);
58 g2.setPaint(Color.black);
59 g2.draw(page);
60
61 Printable printable = book.getPrintable(currentPage);
62 try
63 {
64     printable.print(g2, pageFormat, currentPage);
65 }
66 catch (PrinterException e)
67 {
68     g2.draw(new Line2D.Double(0, 0, px, py));
69     g2.draw(new Line2D.Double(px, 0, 0, py));
70 }
71 }
72
73 /**
74 * Flip the book by the given number of pages.
75 * @param by the number of pages to flip by. Negative
values flip backwards.
```

```

76     */
77     public void flipPage(int by)
78     {
79         int newPage = currentPage + by;
80         if (0 <= newPage && newPage < book.getNumberOfPages())
81         {
82             currentPage = newPage;
83             repaint();
84         }
85     }
86 }

```

11.5.3 Print Services

So far, you have seen how to print 2D graphics. However, the printing API affords far greater flexibility. The API defines a number of data types and lets you find print services that are able to print them. Among the data types are

- Images in GIF, JPEG, or PNG format
- Documents in text, HTML, PostScript, or PDF format
- Raw printer code data
- Objects of a class that implements `Printable`, `Pageable`, or `RenderableImage`

The data themselves can be stored in a source of bytes or characters such as an input stream, a URL, or an array. A *document flavor* describes the combination of a data source and a data type. The `DocFlavor` class defines a number of inner classes for the various data sources. Each of the inner classes defines constants to specify the flavors. For example, the constant

`DocFlavor.INPUT_STREAM.GIF`

describes a GIF image that is read from an input stream. [Table 11.4](#) lists the combinations.

Table 11.4 Document Flavors for Print Services

| Data Source | Data Type | MIME Type |
|------------------------|------------|--|
| INPUT_ST
REAM | GIF | image/gif |
| URL | JPEG | image/jpeg |
| BYTE_ARR
AY | PNG | image/png |
| | POSTSCRIPT | application/postscript |
| | PDF | application/pdf |
| TEXT_HTML
HOST | | -text/html (using host encoding) |
| TEXT_HTML
US_ASCII | | -text/html; charset=us-ascii |
| TEXT_HTML
UTF_8 | | -text/html; charset=utf-8 |
| TEXT_HTML
UTF_16 | | -text/html; charset=utf-16 |
| TEXT_HTML
UTF_16LE | | text/html; charset=utf-16le
(little-endian) |
| TEXT_HTML
UTF_16BE | | text/html; charset=utf-16be
(big-endian) |
| TEXT_PLAIN
HOST | | text/plain (using host encoding) |
| TEXT_PLAIN
US_ASCII | | text/plain; charset=us-ascii |
| TEXT_PLAIN
UTF_8 | | text/plain; charset=utf-8 |
| TEXT_PLAIN
UTF_16 | | text/plain; charset=utf-16 |

| Data Source | Data Type | MIME Type |
|-------------------|------------|--|
| | TEXT_PLAIN | text/plain; charset=utf-16LE 16le (little-endian) |
| | TEXT_PLAIN | text/plain; charset=utf-16BE 16be (big-endian) |
| PCL | | application/vnd.hp-PCL
(Hewlett Packard Printer Control Language) |
| AUTOSENSE | | application/octet-stream (raw printer data) |
| READER | TEXT_HTML | text/html; charset=utf-16 |
| STRING | TEXT_PLAIN | text/plain; charset=utf-16 |
| CHAR_ARR | | |
| AY | | |
| SERVICE_FORMATTED | PRINTABLE | N/A |
| | PAGEABLE | N/A |
| | RENDERABLE | N/A |
| | _IMAGE | |

Suppose you want to print a GIF image located in a file. First, find out whether there is a *print service* that is capable of handling the task. The static `lookupPrintServices` method of the `PrintServiceLookup` class returns an array of `PrintService` objects that can handle the given document flavor.

[Click here to view code image](#)

```
DocFlavor flavor = DocFlavor.INPUT_STREAM.GIF;
PrintService[] services =
PrintServiceLookup.lookupPrintServices(flavor, null);
```

The second parameter of the `lookupPrintServices` method is `null` to indicate that we don't want to constrain the search by specifying printer

attributes. We'll cover attributes in the next section.

If the lookup yields an array with more than one element, select from the listed print services. You can call the `getName` method of the `PrintService` class to get the printer names and let the user choose.

Next, get a document print job from the service:

[Click here to view code image](#)

```
DocPrintJob job = services[i].createPrintJob();
```

For printing, you need an object that implements the `Doc` interface. The Java library supplies a class `SimpleDoc` for that purpose. The `SimpleDoc` constructor requires the data source object, the document flavor, and an optional attribute set. For example,

[Click here to view code image](#)

```
var in = new FileInputStream(fileName);
var doc = new SimpleDoc(in, flavor, null);
```

Finally, you are ready to print:

```
job.print(doc, null);
```

As before, the `null` parameter can be replaced by an attribute set.

Note that this printing process is quite different from that of the preceding section. There is no user interaction through print dialog boxes. For example, you can implement a server-side printing mechanism in which users submit print jobs through a web form.

javax.print.PrintServiceLookup 1.4

- `PrintService[] lookupPrintServices(DocFlavor flavor, AttributeSet attributes)`

looks up the print services that can handle the given document flavor and attributes.

Param `flavor` The document flavor
eters: `r`

`attri` The required printing attributes, or null if
`butes` attributes should not be considered

`javax.print.PrintService` 1.4

- `DocPrintJob createPrintJob()`

creates a print job for printing an object of a class that implements the `Doc` interface, such as a `SimpleDoc`.

`javax.print.DocPrintJob` 1.4

- `void print(Doc doc, PrintRequestAttributeSet attributes)`

prints the given document with the given attributes.

Param `doc` The `Doc` to be printed
eters:

`attri` The required printing attributes, or null if
`butes` no printing attributes are required

`javax.print.SimpleDoc` 1.4

- `SimpleDoc(Object data, DocFlavor flavor, DocAttributeSet attributes)`
constructs a `SimpleDoc` object that can be printed with a `DocPrintJob`.

Parameters:

| | |
|---------------------|---|
| <code>data</code> | The object with the print data, such as an input stream or a <code>Printable</code> |
| <code>flavor</code> | The document flavor of the print data |
| <code>attrib</code> | Document attributes, or <code>null</code> if attributes |
| <code>utes</code> | are not required |

11.5.4 Stream Print Services

A print service sends print data to a printer. A stream print service generates the same print data but instead sends them to a stream, perhaps for delayed printing or because the print data format can be interpreted by other programs. In particular, if the print data format is PostScript, it may be useful to save the print data to a file because many programs can process PostScript files. The Java platform includes a stream print service that can produce PostScript output from images and 2D graphics. You can use that service on all systems, even if there are no local printers.

Enumerating stream print services is a bit more tedious than locating regular print services. You need both the `DocFlavor` of the object to be printed and the MIME type of the stream output. You then get a `StreamPrintServiceFactory` array of factories.

[Click here to view code image](#)

```
DocFlavor flavor = DocFlavor.SERVICE_FORMATTED.PRINTABLE;
String mimeType = "application/postscript";
StreamPrintServiceFactory[] factories
=
StreamPrintServiceFactory.lookupStreamPrintServiceFactories(fla
vor, mimeType);
```

The StreamPrintServiceFactory class has no methods that would help us distinguish any one factory from another, so we just take factories[0]. We call the getPrintService method with an output stream parameter to get a StreamPrintService object.

[Click here to view code image](#)

```
var out = new FileOutputStream(fileName);
StreamPrintService service = factories[0].getPrintService(out);
```

The StreamPrintService class is a subclass of PrintService. To produce a printout, simply follow the steps of the preceding section.

javax.print.StreamPrintServiceFactory 1.4

- StreamPrintServiceFactory[]
lookupStreamPrintServiceFactories(DocFlavor flavor, String mimeType)

looks up the stream print service factories that can print the given document flavor and produce an output stream of the given MIME type.
- StreamPrintService
getPrintService(OutputStream out)

gets a print service that sends the printing output to the given output stream.

The program in [Listing 11.29](#) demonstrates how to use a stream print service to print Java 2D shapes to a PostScript file. You can replace the sample drawing code with code that generates any Java 2D shapes and have the shapes converted to PostScript. Then you can easily convert the result to PDF or EPS, using an external tool. (Unfortunately, Java does not support printing to PDF directly.)



Note

In this example, we call a `draw` method that draws Java 2D shapes onto a `Graphics2D` object. If you want to draw the surface of a component (for example, a table or tree), use the following code:

[Click here to view code image](#)

```
private static int IMAGE_WIDTH = component.getWidth();
private static int IMAGE_HEIGHT = component.getHeight();
public static void draw(Graphics2D g2) { component.paint(g2); }
```

Listing 11.29 printService/PrintServiceTest.java

[Click here to view code image](#)

```
1 package printService;
2
3 import java.awt.*;
4 import java.awt.font.*;
5 import java.awt.geom.*;
6 import java.awt.print.*;
7 import java.io.*;
8 import javax.print.*;
9 import javax.print.attribute.*;

10
11 /**
12 * This program demonstrates the use of stream print services.
13 * The program prints
14 * Java 2D shapes to a PostScript file. If you don't supply a
15 * file name on the command
16 * line, the output is saved to out.ps.
17 *
18 public class PrintServiceTest
```

```
19 {
20     // Set your image dimensions here
21     private static int IMAGE_WIDTH = 300;
22     private static int IMAGE_HEIGHT = 300;
23
24     public static void draw(Graphics2D g2)
25     {
26         // Your drawing instructions go here
27         FontRenderContext context = g2.getFontRenderContext();
28         var f = new Font("Serif", Font.PLAIN, 72);
29         var clipShape = new GeneralPath();
30
31         var layout = new TextLayout("Hello", f, context);
32         AffineTransform transform =
33             AffineTransform.getTranslateInstance(0, 72);
34         Shape outline = layout.getOutline(transform);
35         clipShape.append(outline, false);
36
37         layout = new TextLayout("World", f, context);
38         transform = AffineTransform.getTranslateInstance(0,
39             144);
39         outline = layout.getOutline(transform);
40         clipShape.append(outline, false);
41
42         g2.draw(clipShape);
43         g2.clip(clipShape);
44
45         final int NLINES = 50;
46         var p = new Point2D.Double(0, 0);
47         for (int i = 0; i < NLINES; i++)
48         {
49             double x = (2 * IMAGE_WIDTH * i) / NLINES;
50             double y = (2 * IMAGE_HEIGHT * (NLINES - 1 - i)) /
51             NLINES;
52             var q = new Point2D.Double(x, y);
53             g2.draw(new Line2D.Double(p, q));
54         }
55     }
56 }
```

```
54
55     public static void main(String[] args) throws IOException,
PrintException
56     {
57         String fileName = args.length > 0 ? args[0] : "out.ps";
58         DocFlavor flavor =
DocFlavor.SERVICE_FORMATTED.PRINTABLE;
59         String mimeType = "application/postscript";
60         StreamPrintServiceFactory[] factories
61         =
StreamPrintServiceFactory.lookupStreamPrintServiceFactories(flavo
r, mimeType);
62         var out = new FileOutputStream(fileName);
63         if (factories.length > 0)
64         {
65             PrintService service =
factories[0].getPrintService(out);
66             var doc = new SimpleDoc(new Printable()
67             {
68                 public int print(Graphics g, PageFormat pf, int
page)
69                 {
70                     if (page >= 1) return
Printable.NO_SUCH_PAGE;
71                     else
72                     {
73                         double sf1 = pf.getImageableWidth() /
(IMAGE_WIDTH + 1);
74                         double sf2 = pf.getImageableHeight() /
(IMAGE_HEIGHT + 1);
75                         double s = Math.min(sf1, sf2);
76                         var g2 = (Graphics2D) g;
77                         g2.translate((pf.getWidth() -
pf.getImageableWidth()) / 2,
78                                     (pf.getHeight() -
pf.getImageableHeight()) / 2);
79                         g2.scale(s, s);
80
```

```

81                     draw(g2);
82                     return Printable.PAGE_EXISTS;
83                 }
84             }
85         }, flavor, null);
86     DocPrintJob job = service.createPrintJob();
87     var attributes = new HashPrintRequestAttributeSet();
88     job.print(doc, attributes);
89 }
90 else
91     System.out.println("No factories for " + mimeType);
92 }
93 }
```

11.5.5 Printing Attributes

The print service API contains a complex set of interfaces and classes to specify various kinds of attributes. There are four important groups of attributes. The first two specify requests to the printer.

- *Print request attributes* request particular features for all `doc` objects in a print job, such as two-sided printing or the paper size.
- *Doc attributes* are request attributes that apply only to a single `doc` object.

The other two attributes contain information about the printer and job status.

- *Print service attributes* give information about the print service, such as the printer make and model or whether the printer is currently accepting jobs.
- *Print job attributes* give information about the status of a particular print job, such as whether the job is already completed.

To describe the various attributes, there is an interface `Attribute` with subinterfaces:

```
PrintRequestAttribute  
DocAttribute  
PrintServiceAttribute  
PrintJobAttribute  
SupportedValuesAttribute
```

Individual attribute classes implement one or more of these interfaces. For example, objects of the `Copies` class describe the number of copies of a printout. That class implements both the `PrintRequestAttribute` and the `PrintJobAttribute` interfaces. Clearly, a print request can contain a request for multiple copies. Conversely, an attribute of the print job might be how many of these copies were actually printed. That number might be lower, perhaps because of printer limitations or because the printer ran out of paper.

The `SupportedValuesAttribute` interface indicates that an attribute value does not reflect actual request or status data but rather the capability of a service. For example, the `CopiesSupported` class implements the `SupportedValuesAttribute` interface. An object of that class might describe that a printer supports 1 through 99 copies of a printout.

[Figure 11.65](#) shows a class diagram of the attribute hierarchy.




Figure 11.65 The attribute hierarchy

In addition to the interfaces and classes for individual attributes, the print service API defines interfaces and classes for attribute sets. A superinterface, `AttributeSet`, has four subinterfaces:

[Click here to view code image](#)

```

PrintRequestAttributeSet
DocAttributeSet
PrintServiceAttributeSet
PrintJobAttributeSet
  
```

Each of these interfaces has an implementing class, yielding the five classes:

[Click here to view code image](#)

```

HashAttributeSet
HashPrintRequestAttributeSet
  
```

```
HashDocAttributeSet  
HashPrintServiceAttributeSet  
HashPrintJobAttributeSet
```

Figure 11.66 shows a class diagram of the attribute set hierarchy.




Figure 11.66 The attribute set hierarchy

For example, you can construct a print request attribute set like this:

[Click here to view code image](#)

```
var attributes = new HashPrintRequestAttributeSet();
```

After constructing the set, you are freed from worrying about the `Hash` prefix.

Why have all these interfaces? They make it possible to check for correct attribute usage. For example, a `DocAttributeSet` accepts only objects that implement the `DocAttribute` interface. Any attempt to add another attribute results in a runtime error.

An attribute set is a specialized kind of map where the keys are of type `Class` and the values belong to a class that implements the `Attribute` interface. For example, if you insert an object

```
new Copies(10)
```

into an attribute set, then its key is the `Class` object `Copies.class`. That key is called the *category* of the attribute. The `Attribute` interface declares a method

```
Class getCategory()
```

that returns the category of an attribute. The `Copies` class defines the method to return the object `Copies.class`, but it isn't a requirement that the category be the same as the class of the attribute.

When an attribute is added to an attribute set, the category is extracted automatically. Just add the attribute value:

[Click here to view code image](#)

```
attributes.add(new Copies(10));
```

If you subsequently add another attribute with the same category, it overwrites the first one.

To retrieve an attribute, you need to use the category as the key, for example:

[Click here to view code image](#)

```
AttributeSet attributes = job.getAttributes();
var copies = (Copies) attribute.get(Copies.class);
```

Finally, attributes are organized by the values they can have. The `Copies` attribute can have any integer value. The `Copies` class extends the `IntegerSyntax` class that takes care of all integer-valued attributes. The `getValue` method returns the integer value of the attribute, for example:

```
int n = copies.getValue();
```

The classes

```
TextSyntax  
DateTimeSyntax  
URISyntax
```

encapsulate a string, a date and time value, or a URI.

Finally, many attributes can take a finite number of values. For example, the `PrintQuality` attribute has three settings: draft, normal, and high. They are represented by three constants:

```
PrintQuality.DRAFT  
PrintQuality.NORMAL  
PrintQuality.HIGH
```

Attribute classes with a finite number of values extend the `EnumSyntax` class, which provides a number of convenience methods to set up these enumerations in a typesafe manner. You need not worry about the mechanism when using such an attribute. Simply add the named values to attribute sets:

[Click here to view code image](#)

```
attributes.add(PrintQuality.HIGH);
```

Here is how you check the value of an attribute:

[Click here to view code image](#)

```
if (attributes.get(PrintQuality.class) == PrintQuality.HIGH)  
    . . .
```

Table 11.5 lists the printing attributes. The second column lists the superclass of the attribute class (for example, IntegerSyntax for the Copies attribute) or the set of enumeration values for the attributes with a finite set of values. The last four columns indicate whether the attribute class implements the DocAttribute (DA), PrintJobAttribute (PJA), PrintRequestAttribute (PRA), and PrintServiceAttribute (PSA) interfaces.

Table 11.5 Printing Attributes

| Attribute | Superclass or Enumeration Constants | D
A | P
J | P
R
S | P
A
A
A |
|-----------------------|-------------------------------------|--------|--------|-------------|------------------|
| Chromaticity | MONOCHROME, COLOR | | | ✓✓✓ | |
| ColorSupported | SUPPORTED, NOT_SUPPORTED | | | | ✓ |
| Compression | COMPRESS, DEFLATE, GZIP, NONE | | | | ✓ |
| Copies | IntegerSyntax | | | ✓✓ | |
| DateTimedAtComp | DateTimeSyntax | | | | ✓ |
| DateTimedAtCreation | DateTimeSyntax | | | | ✓ |
| DateTimedAtProcessing | DateTimeSyntax | | | | ✓ |
| Destination | URI Syntax | | | ✓✓ | |

| Attribute | Superclass or Enumeration Constants | D
P
A | P
J
AAA | P
R
S |
|-------------------------|---|-------------|---------------|-------------|
| DocumentName | TextSyntax | | | ✓ |
| Fidelity | FIDELITY_TRUE, FIDELITY_FALSE | | | ✓✓ |
| Finishing | NONE, STAPLE, EDGE_STITCH, BIND,
SADDLE_STITCH, COVER, ... | | | ✓✓✓ |
| JobHoldUntil | DateTimeSyntax | | | ✓✓ |
| JobImpressions | IntegerSyntax | | | ✓✓ |
| JobImpressionsCompleted | IntegerSyntax | | | ✓ |
| JobKOctets | IntegerSyntax | | | ✓✓ |
| JobKOctetsProcessed | IntegerSyntax | | | ✓ |
| JobMediaSheets | IntegerSyntax | | | ✓✓ |
| JobMediaSheetsCompleted | IntegerSyntax | | | ✓ |
| JobMessageFromOperator | TextSyntax | | | ✓ |

| Attribute | Superclass or Enumeration Constants | D
P
A
P
J
R
S
A
A
A |
|-------------------------|--|--|
| JobName | TextSyntax | ✓✓ |
| JobOriginatingUser Name | TextSyntax | ✓ |
| JobPriority | IntegerSyntax | ✓✓ |
| JobSheets | STANDARD, NONE | ✓✓ |
| JobStatus | ABORTED, CANCELED, COMPLETED,
PENDING, PENDING_HELD, PROCESSING,
PROCESSING_STOPPED | ✓ |
| JobStatusReason | ABORTED_BY_SYSTEM,
DOCUMENT_FORMAT_ERROR, many others | |
| JobStatusReasons | HashSet | |
| MediaName | ISO_A4_WHITE, ISO_A4_TRANSPARENT,
NA_LETTER_WHITE,
NA_LETTER_TRANSPARENT | ✓✓✓ |
| MediaSize | ISO.A0-ISO.A10, ISO.B0-ISO.B10,
ISO.C0-ISO.C10, NA.LETTER, NA.LEGAL,
various other paper and envelope sizes | |
| MediaSizeName | ISO_A0-ISO_A10, ISO_B0-ISO_B10,
ISO_C0-ISO_C10, NA_LETTER, NA_LEGAL,
various other paper and envelope size names | ✓✓✓ |
| MediaTry | TOP, MIDDLE, BOTTOM, SIDE, ENVELOPE,
LARGE_CAPACITY, MAIN, MANUAL | ✓✓✓ |

| Attribute | Superclass or Enumeration Constants | D
A | P
J | P
R | S
A | A
AA |
|------------------|--|--------|--------|--------|--------|---------|
| | SINGLE_DOCUMENT, | | | | | |
| Multipl | SINGLE_DOCUMENT_NEW_SHEET, | | | | | |
| eDocume | SEPARATE_DOCUMENTS_COLLATED_COPIE | | | | | ✓✓ |
| ntHandl | S, | | | | | |
| ing | SEPARATE_DOCUMENTS_UNCOLLATED_COPIES | | | | | |
| NumberO | | | | | | |
| fDocume | IntegerSyntax | | | | ✓ | |
| nts | | | | | | |
| NumberO | | | | | | |
| fInterv | IntegerSyntax | | | | ✓ | |
| eningJo | | | | | | |
| bs | | | | | | |
| NumberU | IntegerSyntax | | | ✓✓✓ | | |
| p | | | | | | |
| Orienta | PORTRAIT, LANDSCAPE, | | | | | |
| tionReq | REVERSE_PORTRAIT, | | | | ✓✓✓ | |
| uested | REVERSE_LANDSCAPE | | | | | |
| OutputD | | | | | | |
| eviceAs | TextSyntax | | | | ✓ | |
| signed | | | | | | |
| PageRan | SetOfInteger | | | ✓✓✓ | | |
| ges | | | | | | |
| PagesPe | IntegerSyntax | | | | ✓ | |
| rMinute | | | | | | |
| PagesPe | | | | | | |
| rMinute | IntegerSyntax | | | | ✓ | |
| Color | | | | | | |

| Attribute | Superclass or Enumeration Constants | D
P
A | P
P
J
R
S
A
A
A |
|------------------|--|-------------|--------------------------------------|
| PDLover | | | |
| rideSup | ATTEMPTED, NOT_ATTEMPTED | | ✓ |
| ported | | | |
| Present | TORIGHT_TOBOTTOM, TORIGHT_TOTOP, | | |
| ationDi | TOBOTTOM_TORIGHT, TOBOTTOM_TOLEFT, | | |
| rection | TOLEFT_TOBOTTOM, TOLEFT_TOTOP, | ✓ | ✓ |
| | TOTOP_TORIGHT, TOTOP_TOLEFT | | |
| Printer | | | |
| Info | TextSyntax | ✓ | |
| Printer | | | |
| IsAccep | | | |
| tingJob | ACCEPTING_JOBS, NOT_ACCEPTING_JOBS | ✓ | |
| S | | | |
| Printer | | | |
| Locatio | TextSyntax | ✓ | |
| n | | | |
| Printer | | | |
| MakeAnd | TextSyntax | ✓ | |
| Model | | | |
| Printer | | | |
| Message | | | |
| FromOpe | TextSyntax | ✓ | |
| rator | | | |
| Printer | | | |
| MoreInf | URISyntax | ✓ | |
| O | | | |
| Printer | | | |
| MoreInf | | | |
| oManufa | URISyntax | ✓ | |
| cturer | | | |

| Attribute | Superclass or Enumeration Constants | D
A | P
J | P
R | S
A | A
AA |
|-----------------------------|--|--------|--------|--------|--------|---------|
| Printer Name | TextSyntax | | | | | ✓ |
| Printer Resolution | ResolutionSyntax | | | ✓ | ✓ | ✓ |
| Printer State | PROCESSING, IDLE, STOPPED, UNKNOWN | | | | | ✓ |
| Printer StateReason | COVER_OPEN, FUSER_OVER_TEMP,
MEDIA_JAM, and many others | | | | | |
| Printer StateReasons | HashMap | | | | | |
| Printer URI | URISyntax | | | | | ✓ |
| PrintQuality | DRAFT, NORMAL, HIGH | | | ✓ | ✓ | ✓ |
| QueuedJobCount | IntegerSyntax | | | | | ✓ |
| ReferenceUriSchemeSupported | FILE, FTP, GOPHER, HTTP, HTTPS, NEWS,
NNTP, WAIS | | | | | |
| RequestingUserName | TextSyntax | | | | | ✓ |
| Severity | ERROR, REPORT, WARNING | | | | | |

| Attribute | Superclass or Enumeration Constants | D
A | P
J | P
R | S
AAA |
|------------------|--|----------------|----------------|----------------|------------------|
| SheetCo
llate | COLLATED, UNCOLLATED | | | ✓✓✓ | |
| Sides | ONE_SIDED, DUPLEX (=
TWO_SIDED_LONG_EDGE), TUMBLE (=
TWO_SIDED_SHORT_EDGE) | | | ✓✓✓ | |



Note

As you can see, there are lots of attributes, many of which are quite specialized. The source for most of the attributes is the Internet Printing Protocol 1.1 (RFC 2911).



Note

An earlier version of the printing API introduced the `JobAttributes` and `PageAttributes` classes, whose purpose was similar to the printing attributes covered in this section. These classes are now obsolete.

`javax.print.attribute.Attribute` 1.4

- Class `getCategory()`
gets the category of this attribute.
- String `getName()`
gets the name of this attribute.

javax.print.attribute.AttributeSet 1.4

- boolean add(Attribute attr)

adds an attribute to this set. If the set has another attribute with the same category, that attribute is replaced by the given attribute. Returns true if the set changed as a result of this operation.

- Attribute get(Class category)

retrieves the attribute with the given category key, or null if no such attribute exists.

- boolean remove(Attribute attr)

- boolean remove(Class category)

remove the given attribute, or the attribute with the given category, from the set. Return true if the set changed as a result of this operation.

- Attribute[] toArray()

returns an array with all attributes in this set.

javax.print.PrintService 1.4

- PrintServiceAttributeSet getAttributes()

gets the attributes of this print service.

javax.print.DocPrintJob 1.4

- `PrintJobAttributeSet getAttributes()`
gets the attributes of this print job.

You have now reached the end of this long chapter covering advanced Swing and AWT features. In the final chapter, we will turn to a different aspect of Java programming: interacting, on the same machine, with “native” code in a different programming language.

Chapter 12. Native Methods

In this chapter

- [12.1 Calling a C Function from a Java Program](#)
- [12.2 Numeric Parameters and Return Values](#)
- [12.3 String Parameters](#)
- [12.4 Accessing Fields](#)
- [12.5 Encoding Signatures](#)
- [12.6 Calling Java Methods](#)
- [12.7 Accessing Array Elements](#)
- [12.8 Handling Errors](#)
- [12.9 Using the Invocation API](#)
- [12.10 A Complete Example: Accessing the Windows Registry](#)
- [12.11 Foreign Functions: A Glimpse into the Future](#)

While a “100% Pure Java” solution is nice in principle, there are situations in which you will want to write (or use) code in another language. Such code is usually called *native* code.

Particularly in the early days of Java, many people assumed that it would be a good idea to use C or C++ to speed up critical parts of a Java application. However, in practice, this was rarely useful. A presentation at the 1996 JavaOne conference showed this clearly. The developers of the cryptography library at Sun Microsystems reported that a pure Java

platform implementation of their cryptographic functions was more than adequate. It was true that the code was not as fast as a C implementation would have been, but it turned out not to matter. The Java platform implementation was far faster than the network I/O. This turned out to be the real bottleneck.

Of course, there are drawbacks to going native. If a part of your application is written in another language, you must supply a separate native library for every platform you want to support. Code written in C or C++ offers no protection against overwriting memory through invalid pointer usage. It is easy to write native methods that corrupt your program or infect the operating system.

Thus, I suggest using native code only when you need to. In particular, there are three reasons why native code might be the right choice:

- Your application requires access to system features or devices that are not accessible through the Java platform.
- You have substantial amounts of tested and debugged code in another language, and you know how to port it to all desired target platforms.
- You have found, through benchmarking, that the Java code is much slower than the equivalent code in another language.

The Java platform has an API for interoperating with native C code called the Java Native Interface (JNI). We'll discuss JNI programming in this chapter.



C++ Note

You can also use C++ instead of C to write native methods. There are a few advantages—type checking is slightly stricter, and accessing the JNI functions is a bit more convenient. However, JNI does not support any mapping between Java and C++ classes.

As you will see, there is a certain amount of tedium involved in providing a binding layer between Java and native code. Java 17 has, as a preview

feature, an API to access “foreign” functions and memory that is quite a bit more convenient than JNI. At the end of this chapter, you will get a glimpse into this API.

12.1 Calling a C Function from a Java Program

Suppose you have a C function that does something you like and, for one reason or another, you don’t want to bother reimplementing it in Java. For the sake of illustration, we’ll start with a simple C function that prints a greeting.

The Java programming language uses the keyword `native` for a native method, and you will obviously need to place a method in a class. The result is shown in [Listing 12.1](#).

The `native` keyword alerts the compiler that the method will be defined externally. Of course, native methods will contain no Java code, and the method header is followed immediately by a terminating semicolon. Therefore, native method declarations look similar to abstract method declarations.

Listing 12.1 helloNative/HelloNative.java

[Click here to view code image](#)

```
1 /**
2  * @version 1.11 2007-10-26
3  * @author Cay Horstmann
4 */
5 class HelloNative
6 {
7     public static native void greeting();
8 }
```



Note

We do not use packages here to keep examples simple.

In this particular example, the native method is also declared as `static`. Native methods can be both static and nonstatic. We'll start with a static method because we do not yet want to deal with parameter passing.

You can actually compile this class, but if you try to use it in a program, the virtual machine will tell you it doesn't know how to find `greeting`—reporting an `UnsatisfiedLinkError`. To implement the native code, write a corresponding C function. You must name that function *exactly* the way the Java virtual machine expects. Here are the rules:

1. Use the full Java method name, such as `HelloNative.greeting`. If the class is in a package, prepend the package name, such as `com.horstmann.HelloNative.greeting`.
 2. Replace every period with an underscore, and append the prefix `Java_`. For example, `Java_HelloNative_greeting` or `Java_com_horstmann_HelloNative_greeting`.
 3. If the class name contains characters that are not ASCII letters or digits—that is, '`_`', '`$`', or Unicode characters with codes greater than `\u007F`—replace them with `_0xxxx`, where `xxxx` is the sequence of four hexadecimal digits of the character's Unicode value.
-



Note

If you *overload* native methods—that is, if you provide multiple native methods with the same name—you must append a double underscore followed by the encoded argument types. (I'll describe the encoding of the argument types later in this chapter.) For example, if you have a native method `greeting` and another native method `greeting(int repeat)`, then the first one is called `Java_HelloNative_greeting__` and the second, `Java_HelloNative_greeting__I`.

Actually, nobody does this by hand; instead, run javac with the -h flag, providing the directory in which the header files should be placed:

```
javac -h . HelloNative.java
```

This command creates a header file `HelloNative.h` in the current directory, as shown in [Listing 12.2](#).

Listing 12.2 `helloNative/HelloNative.h`

[Click here to view code image](#)

```
1 /* DO NOT EDIT THIS FILE - it is machine generated */
2 #include <jni.h>
3 /* Header for class HelloNative */
4
5 #ifndef _Included_HelloNative
6 #define _Included_HelloNative
7 #ifdef __cplusplus
8 extern "C" {
9 #endif
10 /*
11  * Class: HelloNative
12  * Method: greeting
13  * Signature: ()V
14 */
15 JNIEXPORT void JNICALL Java_HelloNative_greeting
16     (JNIEnv *, jclass);
17
18 #ifdef __cplusplus
19 }
20#endif
21#endif
```

As you can see, this file contains the declaration of a function `Java_HelloNative_greeting`. (The macros `JNIEXPORT` and `JNICALL` are defined in the header file `jni.h`. They denote compiler-

dependent specifiers for exported functions that come from a dynamically loaded library.)

Now, simply copy the function prototype from the header file into a source file and give the implementation code for the function, as shown in Listing 12.3.

Listing 12.3 helloNative/HelloNative.c

[Click here to view code image](#)

```
1 /*  
2  * @version 1.10 1997-07-01  
3  * @author Cay Horstmann  
4 */  
5  
6 #include "HelloNative.h"  
7 #include <stdio.h>  
8  
9 JNIEXPORT void JNICALL Java_HelloNative_greeting(JNIEnv* env,  
jclass cl)  
10 {  
11     printf("Hello, Native World!\n");  
12 }
```

In this simple function, ignore the `env` and `cl` arguments. You'll see their use later.



C++ Note

You can use C++ to implement native methods. However, you must then declare the functions that implement the native methods as `extern "C"`. (This stops the C++ compiler from “mangling” the method name.) For example,

[Click here to view code image](#)

```
extern "C"  
  
JNIEXPORT void JNICALL Java_HelloNative_greeting(JNIEnv* env,  
jclass cl)  
{  
    cout << "Hello, Native World!" << endl;  
}
```

Compile the native C code into a dynamically loaded library. The details depend on your compiler.

For example, with the GNU C compiler on Linux, use these commands:

[Click here to view code image](#)

```
gcc -fPIC -I jdk/include -I jdk/include/linux -shared -o  
libHelloNative.so HelloNative.c
```

With the Microsoft compiler under Windows, the command is

[Click here to view code image](#)

```
cl -I jdk\include -I jdk\include\win32 -LD HelloNative.c -  
FHelloNative.dll
```

Here, *jdk* is the directory that contains the JDK.



Tip

If you use the Microsoft compiler from a command shell, first run a batch file such as `vsvars32.bat` or `vcvarsall.bat`. That batch file sets up the path and the environment variables needed by the compiler. You can find it in the directory `c:\Program Files\Microsoft Visual Studio 14.0\Common7\Tools` or a similar monstrosity. Check the Visual Studio documentation for details.

You can also use the freely available Cygwin programming environment from www.cygwin.com. It contains the GNU C compiler and libraries for UNIX-style programming on Windows. With Cygwin, use the command

[Click here to view code image](#)

```
gcc -mno-cygwin -D __int64="long long" -I jdk/include/ -I  
jdk/include/win32 \  
-shared -Wl,--add-stdcall-alias -o HelloNative.dll  
HelloNative.c
```



Note

The Windows version of the header file `jni_md.h` contains the type declaration

```
typedef __int64 jlong;
```

which is specific to the Microsoft compiler. If you use the GNU compiler, you might want to edit that file, for example,

[Click here to view code image](#)

```
#ifdef __GNUC__  
    typedef long long jlong;  
#else  
    typedef __int64 jlong;  
#endif
```

Alternatively, compile with `-D __int64="long long"`, as shown in the sample compiler invocation.

Finally, add a call to the `System.loadLibrary` method in your program. To ensure that the virtual machine will load the library before the first use of the class, use a static initialization block, as in [Listing 12.4](#).

[Figure 12.1](#) gives a summary of the native code processing.




Figure 12.1 Processing native code

Listing 12.4 helloNative/HelloNativeTest.java

[Click here to view code image](#)

```
1 /**
2  * @version 1.11 2007-10-26
3  * @author Cay Horstmann
4  */
5 class HelloNativeTest
6 {
7     public static void main(String[] args)
8     {
9         HelloNative.greeting();
10    }
11
12    static
13    {
14        System.loadLibrary("HelloNative");
15    }
16 }
```

After you compile and run this program, the message “Hello, Native World!” is displayed in a terminal window.



Note

If you run Linux, you must add the current directory to the library path. Either set the `LD_LIBRARY_PATH` environment variable:

[Click here to view code image](#)

```
export LD_LIBRARY_PATH=.:${LD_LIBRARY_PATH}
```

or set the `java.library.path` system property:

[Click here to view code image](#)

```
java -Djava.library.path=. HelloNativeTest
```

Of course, this is not particularly impressive by itself. Keep in mind, however, that this message is generated by the C `printf` command and not by any Java code. We have taken the first step toward bridging the gap between the two languages!

In summary, follow these steps to link a native method to a Java program:

1. Declare a native method in a Java class.
2. Run `javac -h` to get a header file with a C declaration for the method.
3. Implement the native method in C.
4. Place the code in a shared library.
5. Load that library in your Java program.

java.lang.System 1.0

- `void loadLibrary(String libname)`

loads the library with the given name. The library is located in the library search path. The exact method for locating the library depends on the operating system.



Note

Some shared libraries for native code must execute certain initializations. You can place any initialization code into a `JNI_OnLoad` method. Similarly, when the virtual machine (VM) shuts down, it will call the `JNI_OnUnload` method if you provide it. The prototypes are

[Click here to view code image](#)

```
jint JNI_OnLoad(JavaVM* vm, void* reserved);  
void JNI_OnUnload(JavaVM* vm, void* reserved);
```

The `JNI_OnLoad` method needs to return the minimum version of the VM it requires, such as `JNI_VERSION_1_2`.

12.2 Numeric Parameters and Return Values

When passing numbers between C and Java, you should understand which types correspond to each other. For example, although C does have data types called `int` and `long`, their implementation is platform-dependent. On some platforms, an `int` is a 16-bit quantity, on others it is a 32-bit quantity. On the Java platform, of course, an `int` is *always* a 32-bit integer. For that reason, JNI defines types `jint`, `jlong`, and so on.

Table 12.1 shows the correspondence between Java types and C types.

Table 12.1 Java Types and C Types

| Java Programming Language | C Programming Language | Bytes |
|---------------------------|------------------------|-------|
| <code>boolean</code> | <code>jboolean</code> | 1 |
| <code>byte</code> | <code>jbyte</code> | 1 |
| <code>char</code> | <code>jchar</code> | 2 |
| <code>short</code> | <code>jshort</code> | 2 |
| <code>int</code> | <code>jint</code> | 4 |
| <code>long</code> | <code>jlong</code> | 8 |
| <code>float</code> | <code>jfloat</code> | 4 |
| <code>double</code> | <code>jdouble</code> | 8 |

In the header file `jni.h`, these types are declared with `typedef` statements as the equivalent types on the target platform. That header file also defines the constants `JNI_FALSE = 0` and `JNI_TRUE = 1`.

Until Java 5, Java had no direct analog of the C `printf` function. In the following examples, we will pretend you are stuck with an ancient JDK

release and decide to implement the same functionality by calling the C `printf` function in a native method.

[Listing 12.5](#) shows a class called `Printf1` that uses a native method to print a floating-point number with a given field width and precision.

Listing 12.5 `printf1/Printf1.java`

[Click here to view code image](#)

```
1 /**
2  * @version 1.10 1997-07-01
3  * @author Cay Horstmann
4 */
5 class Printf1
6 {
7     public static native int print(int width, int precision,
double x);
8
9     static
10    {
11        System.loadLibrary("Printf1");
12    }
13 }
```

Notice that when the method is implemented in C, all `int` and `double` parameters are changed to `jint` and `jdouble`, as shown in [Listing 12.6](#).

Listing 12.6 `printf1/Printf1.c`

[Click here to view code image](#)

```
1 /**
2  * @version 1.10 1997-07-01
3  * @author Cay Horstmann
4 */
5
6 #include "Printf1.h"
```

```
7 #include <stdio.h>
8
9 JNIEXPORT jint JNICALL Java_Printf1_print(JNIEnv* env, jclass
cl,
10      jint width, jint precision, jdouble x)
11 {
12     char fmt[30];
13     jint ret;
14     sprintf(fmt, "%%.%df", width, precision);
15     ret = printf(fmt, x);
16     fflush(stdout);
17     return ret;
18 }
```

The function simply assembles a format string "%w.pf" in the variable `fmt`, then calls `printf`. It returns the number of characters printed.

[Listing 12.7](#) shows the test program that demonstrates the `Printf1` class.

Listing 12.7 printf1/Printf1Test.java

[Click here to view code image](#)

```
1 /**
2 * @version 1.10 1997-07-01
3 * @author Cay Horstmann
4 */
5 class Printf1Test
6 {
7     public static void main(String[] args)
8     {
9         int count = Printf1.print(8, 4, 3.14);
10        count += Printf1.print(8, 4, count);
11        System.out.println();
12        for (int i = 0; i < count; i++)
13            System.out.print("-");
14        System.out.println();
```

```
15      }
16 }
```

12.3 String Parameters

Next, let's look at how to transfer strings to and from native methods. Strings are quite different in the two languages: In Java, they are sequences of UTF-16 code points, whereas C strings are null-terminated sequences of bytes. JNI has two sets of functions for manipulating strings: One converts Java strings to “modified UTF-8” byte sequences and another converts them to arrays of UTF-16 values—that is, to `jchar` arrays. (The UTF-8, “modified UTF-8,” and UTF-16 formats were discussed in [Chapter 2](#). Recall that the UTF-8 and “modified UTF-8” encodings leave ASCII characters unchanged, but all other Unicode characters are encoded as multibyte sequences.)



Note

The standard UTF-8 encoding and the “modified UTF-8” encoding differ only for “supplementary” characters with codes higher than `0xFFFF`. In the standard UTF-8 encoding, these characters are encoded as 4-byte sequences. In the “modified” encoding, each such character is first encoded as a pair of “surrogates” in the UTF-16 encoding, and then each surrogate is encoded with UTF-8, yielding a total of 6 bytes. This is clumsy, but it is a historical accident—the JVM specification was written when Unicode was still limited to 16 bits.

If your C code already uses Unicode, you'll want to use the second set of conversion functions. On the other hand, if all your strings are restricted to ASCII characters, you can use the “modified UTF-8” conversion functions.

A native method with a `String` parameter actually receives a value of an opaque type called `jstring`. A native method with a return value of type

String must return a value of type `jstring`. JNI functions read and construct these `jstring` objects. For example, the `NewStringUTF` function makes a new `jstring` object out of a `char` array that contains ASCII characters or, more generally, “modified UTF-8”-encoded byte sequences.

JNI functions have a somewhat odd calling convention. Here is a call to the `NewStringUTF` function:

[Click here to view code image](#)

```
JNIEXPORT jstring JNICALL Java_HelloNative_getGreeting(JNIEnv*  
env, jclass cl)  
{  
    jstring jstr;  
    char greeting[] = "Hello, Native World\n";  
    jstr = (*env)->NewStringUTF(env, greeting);  
    return jstr;  
}
```



Note

Unless explicitly mentioned otherwise, all code in this chapter is C code.

All calls to JNI functions use the `env` pointer that is the first argument of every native method. The `env` pointer is a pointer to a table of function pointers (see [Figure 12.2](#)). Therefore, you must prefix every JNI call with `(*env) ->` to actually dereference the function pointer. Furthermore, `env` is the first parameter of every JNI function.




Figure 12.2 The `env` pointer



C++ Note

It is simpler to access JNI functions in C++. The C++ version of the `JNIEnv` class has inline member functions that take care of the function pointer lookup for you. For example, you can call the `NewStringUTF` function as

[Click here to view code image](#)

```
jstr = env->NewStringUTF(greeting);
```

Note that you omit the `JNIEnv` pointer from the parameter list of the call.

The `NewStringUTF` function lets you construct a new `jstring`. To read the contents of an existing `jstring` object, use the `GetStringUTFChars` function. This function returns a `const`

`jbyte*` pointer to the “modified UTF-8” characters that describe the character string. Note that a specific virtual machine is free to choose this character encoding for its internal string representation, so you might get a character pointer into the actual Java string. Since Java strings are meant to be immutable, it is *very* important that you treat the `const` seriously and do not try to write into this character array. On the other hand, if the virtual machine uses UTF-16 or UTF-32 characters for its internal string representation, this function call allocates a new memory block that will be filled with the “modified UTF-8” equivalents.

The virtual machine must know when you are finished using the string so that it can garbage-collect it. (The garbage collector runs in a separate thread, and it can interrupt the execution of native methods.) For that reason, you must call the `ReleaseStringUTFChars` function.

Alternatively, you can supply your own buffer to hold the string characters by calling the `GetStringRegion` or `GetStringUTFRegion` methods.

Finally, the `GetStringUTFLength` function returns the number of characters needed for the “modified UTF-8” encoding of the string.



Note

You can find the JNI API at

<http://docs.oracle.com/javase/7/docs/technologies/guides/jni>.

Accessing Java Strings from C Code

- `jstring NewStringUTF(JNIEnv* env, const char bytes[])`

returns a new Java string object from a zero byte-terminated “modified UTF-8” byte sequence, or `NULL` if the string cannot be

constructed.

- `jsize GetStringUTFLength(JNIEnv* env, jstring string)`

returns the number of bytes required for the “modified UTF-8” encoding (not counting the zero byte terminator).

- `const jbyte* GetStringUTFChars(JNIEnv* env, jstring string, jboolean* isCopy)`

returns a pointer to the “modified UTF-8” encoding of a string, or NULL if the character array cannot be constructed. The pointer is valid until `ReleaseStringUTFChars` is called. `isCopy` points to a `jboolean` filled with `JNI_TRUE` if a copy is made, or with `JNI_FALSE` otherwise.

- `void ReleaseStringUTFChars(JNIEnv* env, jstring string, const jbyte bytes[])`

informs the virtual machine that the native code no longer needs access to the Java string through `bytes` (a pointer returned by `GetStringUTFChars`).

- `void GetStringRegion(JNIEnv *env, jstring string, jsize start, jsize length, jchar *buffer)`

copies a sequence of UTF-16 double bytes from a string to a user-supplied buffer of size at least $2 \times \text{length}$.

- `void GetStringUTFRegion(JNIEnv *env, jstring string, jsize start, jsize length, jbyte *buffer)`

copies a sequence of “modified UTF-8” bytes from a string to a user-supplied buffer. The buffer must be long enough to hold the bytes. In the worst case, $3 \times \text{length}$ bytes are copied.

- `jstring NewString(JNIEnv* env, const jchar chars[], jsize length)`
 returns a new Java string object from a Unicode string, or NULL if the string cannot be constructed.
- `jsize GetStringLength(JNIEnv* env, jstring string)`
 returns the number of characters in the string.
- `const jchar* GetStringChars(JNIEnv* env, jstring string, jboolean* isCopy)`
 returns a pointer to the Unicode encoding of a string, or NULL if the character array cannot be constructed. The pointer is valid until `ReleaseStringChars` is called. `isCopy` is either NULL or points to a `jboolean` filled with `JNI_TRUE` if a copy is made, or with `JNI_FALSE` otherwise.
- `void ReleaseStringChars(JNIEnv* env, jstring string, const jchar chars[])`
 informs the virtual machine that the native code no longer needs access to the Java string through `chars` (a pointer returned by `GetStringChars`).

Let us put these functions to work and write a class that calls the C function `sprintf`. We would like to call the function as shown in [Listing 12.8](#).

Listing 12.8 printf2/Printf2Test.java

[Click here to view code image](#)

```

1 /**
2  * @version 1.10 1997-07-01
3  * @author Cay Horstmann
4 */

```

```
5 class Printf2Test
6 {
7     public static void main(String[] args)
8     {
9         double price = 44.95;
10        double tax = 7.75;
11        double amountDue = price * (1 + tax / 100);
12
13        String s = Printf2.sprint("Amount due = %8.2f",
amountDue);
14        System.out.println(s);
15    }
16 }
```

[Listing 12.9](#) shows the class with the native `sprint` method.

Listing 12.9 printf2/Printf2.java

[Click here to view code image](#)

```
1 /**
2  * @version 1.10 1997-07-01
3  * @author Cay Horstmann
4 */
5 class Printf2
6 {
7     public static native String sprint(String format, double
x);
8
9     static
10    {
11        System.loadLibrary("Printf2");
12    }
13 }
```

Therefore, the C function that formats a floating-point number has the prototype

[Click here to view code image](#)

```
JNIEXPORT jstring JNICALL Java_Printf2_sprint(JNIEnv* env,
jclass cl,
jstring format, jdouble x)
```

[Listing 12.10](#) shows the code for the C implementation. Note the calls to `GetStringUTFChars` to read the format argument, `NewStringUTF` to generate the return value, and `ReleaseStringUTFChars` to inform the virtual machine that access to the string is no longer required.

Listing 12.10 printf2/Printf2.c

[Click here to view code image](#)

```
1 /**
2  *version 1.10 1997-07-01
3  *@author Cay Horstmann
4 */
5
6 #include "Printf2.h"
7 #include <string.h>
8 #include <stdlib.h>
9 #include <float.h>
10
11 /**
12  *@param format a string containing a printf format specifier
13  *(such as "%8.2f"). Substrings "%%" are skipped.
14  *@return a pointer to the format specifier (skipping the
15  '%')
16  or NULL if there wasn't a unique format specifier
17 */
18 char* find_format(const char format[])
19 {
20     char* p;
21     char* q;
22     p = strchr(format, '%');
```

```
23     while (p != NULL && *(p + 1) == '%') /* skip %% */
24         p = strchr(p + 2, '%');
25     if (p == NULL) return NULL;
26     /* now check that % is unique */
27     p++;
28     q = strchr(p, '%');
29     while (q != NULL && *(q + 1) == '%') /* skip %% */
30         q = strchr(q + 2, '%');
31     if (q != NULL) return NULL; /* % not unique */
32     q = p + strspn(p, " -0+#"); /* skip past flags */
33     q += strspn(q, "0123456789"); /* skip past field width */
34     if (*q == '.') { q++; q += strspn(q, "0123456789"); }
35     /* skip past precision */
36     if (strchr("eEffFgG", *q) == NULL) return NULL;
37     /* not a floating-point format */
38     return p;
39 }
40
41 JNIEXPORT jstring JNICALL Java_Printf2_sprint(JNIEnv* env,
jclass cl,
42         jstring format, jdouble x)
43 {
44     const char* cformat;
45     char* fmt;
46     jstring ret;
47
48     cformat = (*env)->GetStringUTFChars(env, format, NULL);
49     fmt = find_format(cformat);
50     if (fmt == NULL)
51         ret = format;
52     else
53     {
54         char* cret;
55         int width = atoi(fmt);
56         if (width == 0) width = DBL_DIG + 10;
57         cret = (char*) malloc(strlen(cformat) + width);
58         sprintf(cret, cformat, x);
59         ret = (*env)->NewStringUTF(env, cret);
```

```
60         free(cret);
61     }
62     (*env)->ReleaseStringUTFChars(env, format, cformat);
63     return ret;
64 }
```

In this function, we chose to keep error handling simple. If the format code to print a floating-point number is not of the form `%w.pc`, where `c` is one of the characters `e`, `E`, `f`, `g`, or `G`, then we simply do not format the number. We'll show you later how to make a native method throw an exception.

12.4 Accessing Fields

All the native methods you saw so far were static methods with number and string parameters. We'll now consider native methods that operate on objects. As an exercise, we will reimplement as native a method of the `Employee` class that was introduced in Volume I, [Chapter 4](#). Again, this is not something you would normally want to do, but it does illustrate how to access fields from a native method when you need to do so.

12.4.1 Accessing Instance Fields

To see how to access instance fields from a native method, we will reimplement the `raiseSalary` method. Here is the code in Java:

[Click here to view code image](#)

```
public void raiseSalary(double byPercent)
{
    salary *= 1 + byPercent / 100;
}
```

Let us rewrite this as a native method. Unlike the previous examples of native methods, this is not a static method. Running `javac -h` gives the following prototype:

[Click here to view code image](#)

```
JNIEXPORT void JNICALL Java_Employee_raiseSalary(JNIEnv *,  
 jobject, jdouble);
```

Note the second argument. It is no longer of type `jclass` but of type `jobject`. In fact, it is an equivalent of the `this` reference. Static methods obtain a reference to the class, whereas nonstatic methods obtain a reference to the implicit `this` argument object.

Now we access the `salary` field of the implicit argument. In the “raw” Java-to-C binding of Java 1.0, this was easy—a programmer could directly access instance fields. However, direct access requires all virtual machines to expose their internal data layout. For that reason, the JNI requires programmers to get and set the values of instance fields by calling special JNI functions.

In our case, we need to use the `GetDoubleField` and `SetDoubleField` functions because the type of `salary` is `double`. There are other functions—`GetIntField/.SetIntField`, `GetObjectField/SetObjectField`, and so on for other field types. The general syntax is:

[Click here to view code image](#)

```
x = (*env)->GetXxxField(env, this_obj, fieldID);  
(*env)->SetXxxField(env, this_obj, fieldID, x);
```

Here, `fieldID` is a value of a special type, `jfieldID`, that identifies a field in a structure, and `Xxx` represents a Java data type (`Object`, `Boolean`, `Byte`, and so on). To obtain the `fieldID`, you must first get a value representing the class, which you can do in one of two ways. The `GetObjectClass` function returns the class of any object. For example:

[Click here to view code image](#)

```
jclass class_Employee = (*env)->GetObjectClass(env, this_obj);
```

The `FindClass` function lets you specify the class name as a string (curiously, with / characters instead of periods as package name

separators).

[Click here to view code image](#)

```
jclass class_String = (*env)->FindClass(env,  
"java/lang/String");
```

Use the `GetFieldID` function to obtain the `fieldID`. You must supply the name of the field and its *signature*, an encoding of its type. For example, here is the code to obtain the field ID of the `salary` field:

[Click here to view code image](#)

```
jfieldID id_salary = (*env)->GetFieldID(env, class_Employee,  
"salary", "D");
```

The string "`D`" denotes the type `double`. You'll learn the complete rules for encoding signatures in the next section.

You might be thinking that accessing an instance field is quite convoluted. The designers of the JNI did not want to expose the instance fields directly, so they had to supply functions for getting and setting field values. To minimize the cost of these functions, computing the field ID from the field name—which is the most expensive step—is factored out into a separate step. That is, if you repeatedly get and set the value of a particular field, you can incur the cost of computing the field identifier only once.

Let us put all the pieces together. The following code reimplements the `raiseSalary` method as a native method:

[Click here to view code image](#)

```
JNIEXPORT void JNICALL Java_Employee_raiseSalary(JNIEnv* env,  
jobject this_obj,  
jdouble byPercent)  
{  
    /* get the class */  
    jclass class_Employee = (*env)->GetObjectClass(env,  
this_obj);
```

```

/* get the field ID */
jfieldID id_salary = (*env)->GetFieldID(env, class_Employee,
"salary", "D");

/* get the field value */
jdouble salary = (*env)->GetDoubleField(env, this_obj,
id_salary);

salary *= 1 + byPercent / 100;

/* set the field value */
(*env)->SetDoubleField(env, this_obj, id_salary, salary);
}

```



Caution

Class references are only valid until the native method returns. You cannot cache the return values of `GetObjectClass` in your code. Do *not* store away a class reference for reuse in a later method call. You must call `GetObjectClass` every time the native method executes. If this is intolerable, you can lock the reference with a call to `NewGlobalRef`:

[Click here to view code image](#)

```

static jclass class_X = 0;
static jfieldID id_a;
. . .
if (class_X == 0)
{
    jclass cx = (*env)->GetObjectClass(env, obj);
    class_X = (*env)->NewGlobalRef(env, cx);
    id_a = (*env)->GetFieldID(env, class_X, "a", ". . .");
}

```

Now you can use the class reference and field IDs in subsequent calls. When you are done using the class, make sure to call

```
(*env) ->DeleteGlobalRef(env, class_X);
```

Listings 12.11 and 12.12 show the Java code for a test program and the Employee class. Listing 12.13 contains the C code for the native raiseSalary method.

Listing 12.11 employee/EmployeeTest.java

[Click here to view code image](#)

```
1 /**
2  * @version 1.11 2018-05-01
3  * @author Cay Horstmann
4 */
5
6 public class EmployeeTest
7 {
8     public static void main(String[] args)
9     {
10         var staff = new Employee[3];
11
12         staff[0] = new Employee("Harry Hacker", 35000);
13         staff[1] = new Employee("Carl Cracker", 75000);
14         staff[2] = new Employee("Tony Tester", 38000);
15
16         for (Employee e : staff)
17             e.raiseSalary(5);
18         for (Employee e : staff)
19             e.print();
20     }
21 }
```

Listing 12.12 employee/Employee.java

[Click here to view code image](#)

```
1 /**
2  * @version 1.10 1999-11-13
3  * @author Cay Horstmann
4 */
5
6 public class Employee
7 {
8     private String name;
9     private double salary;
10
11    public native void raiseSalary(double byPercent);
12
13    public Employee(String n, double s)
14    {
15        name = n;
16        salary = s;
17    }
18
19    public void print()
20    {
21        System.out.println(name + " " + salary);
22    }
23
24    static
25    {
26        System.loadLibrary("Employee");
27    }
28 }
```

Listing 12.13 employee/Employee.c

[Click here to view code image](#)

```
1 /**
2  * @version 1.10 1999-11-13
3  * @author Cay Horstmann
4 */
```

```

5
6 #include "Employee.h"
7
8 #include <stdio.h>
9
10 JNIEXPORT void JNICALL Java_Employee_raiseSalary(
11     JNIEnv* env, jobject this_obj, jdouble byPercent)
12 {
13     /* get the class */
14     jclass class_Employee = (*env)->GetObjectClass(env,
this_obj);
15
16     /* get the field ID */
17     jfieldID id_salary = (*env)->GetFieldID(env,
class_Employee, "salary", "D");
18
19     /* get the field value */
20     jdouble salary = (*env)->GetDoubleField(env, this_obj,
id_salary);
21
22     salary *= 1 + byPercent / 100;
23
24     /* set the field value */
25     (*env)->SetDoubleField(env, this_obj, id_salary, salary);
26 }
27

```

12.4.2 Accessing Static Fields

Accessing static fields is similar to accessing nonstatic fields. Use the `GetStaticFieldID` and `GetStaticXxxField/SetStaticXxxField` functions that work almost identically to their nonstatic counterparts, with two differences:

- Since you have no object, you must use `FindClass` instead of `GetObjectClass` to obtain the class reference.

- You have to supply the class, not the instance object, when accessing the field.

For example, here is how you can get a reference to `System.out`:

[Click here to view code image](#)

```
/* get the class */
jclass class_System = (*env)->FindClass(env,
"java/lang/System");

/* get the field ID */
jfieldID id_out = (*env)->GetStaticFieldID(env, class_System,
"out",
"Ljava/io/PrintStream;");

/* get the field value */
jobject obj_out = (*env)->GetStaticObjectField(env,
class_System, id_out);
```

Accessing Fields

- `jfieldID GetFieldID(JNIEnv *env, jclass cl, const char name[], const char fieldSignature[])`
returns the identifier of a field in a class.
- `Xxx GetXxxField(JNIEnv *env, jobject obj, jfieldID id)`
returns the value of a field. The field type `Xxx` is one of `Object`, `Boolean`, `Byte`, `Char`, `Short`, `Int`, `Long`, `Float`, or `Double`.
- `void SetXxxField(JNIEnv *env, jobject obj, jfieldID id, Xxx value)`

sets a field to a new value. The field type *Xxx* is one of Object, Boolean, Byte, Char, Short, Int, Long, Float, or Double.

- `jfieldID GetStaticFieldID(JNIEnv *env, jclass cl, const char name[], const char fieldSignature[])`

returns the identifier of a static field in a class.

- `Xxx GetStaticXxxField(JNIEnv *env, jclass cl, jfieldID id)`

returns the value of a static field. The field type *Xxx* is one of Object, Boolean, Byte, Char, Short, Int, Long, Float, or Double.

- `void SetStaticXxxField(JNIEnv *env, jclass cl, jfieldID id, Xxx value)`

sets a static field to a new value. The field type *Xxx* is one of Object, Boolean, Byte, Char, Short, Int, Long, Float, or Double.

12.5 Encoding Signatures

To access instance fields and call methods defined in the Java programming language, you need to learn the rules for “mangling” the names of data types and method signatures. (A method signature describes the parameters and return type of the method.) Here is the encoding scheme:

| | |
|---|--------|
| B | byte |
| C | char |
| D | double |
| F | float |

| | |
|-------------|--------------|
| I | int |
| J | long |
| Lclassname; | a class type |
| S | short |
| V | void |
| Z | boolean |

To describe an array type, use a [. For example, an array of strings is

```
[Ljava/lang/String;
```

A float[][] is mangled into

```
[ [F
```

For the complete signature of a method, list the parameter types inside a pair of parentheses and then list the return type. For example, a method receiving two integers and returning an integer is encoded as

```
(II)I
```

The sprint method in [Section 12.3, “String Parameters,”](#) on p. 795 has a mangled signature of

[Click here to view code image](#)

```
(Ljava/lang/String;D)Ljava/lang/String;
```

That is, the method receives a String and a double and returns a String.

Note that the semicolon at the end of the L expression is the terminator of the type expression, not a separator between parameters. For example, the constructor

[Click here to view code image](#)

```
Employee(java.lang.String, double, java.util.Date)
```

has a signature

[Click here to view code image](#)

```
"(Ljava/lang/String;D)V"
```

Note that there is no separator between the D and Ljava/util/Date;. Also note that in this encoding scheme, you must use / instead of . to separate the package and class names. The V at the end denotes a return type of void. Even though you don't specify a return type for constructors in Java, you need to add a V to the virtual machine signature.



Tip

You can use the `javap` command with option `-s` to generate the method signatures from class files. For example, run

```
javap -s -private Employee
```

You will get the following output, displaying the signatures of all fields and methods:

[Click here to view code image](#)

```
Compiled from "Employee.java"
public class Employee extends java.lang.Object{
    private java.lang.String name;
        Signature: Ljava/lang/String;
    private double salary;
        Signature: D
    public Employee(java.lang.String, double);
        Signature: (Ljava/lang/String;D)V
    public native void raiseSalary(double);
        Signature: (D)V
    public void print();
        Signature: ()V
```

```
    static {};
    Signature: ()V
}
```



Note

There is no rationale whatsoever for forcing programmers to use this mangling scheme for signatures. The designers of the native calling mechanism could have just as easily written a function that reads signatures in the Java programming language style, such as `void(int, java.lang.String)`, and encodes them into whatever internal representation they prefer. Then again, using the mangled signatures lets you partake in the mystique of programming close to the virtual machine.

12.6 Calling Java Methods

Of course, Java programming language functions can call C functions—that is what native methods are for. Can we go the other way? Why would we want to do this anyway? It often happens that a native method needs to request a service from an object that was passed to it. I'll first show you how to do it for instance methods, then for static methods.

12.6.1 Instance Methods

As an example of calling a Java method from native code, let's enhance the `Printf` class and add a method that works similarly to the C function `fprintf`. That is, it should be able to print a string on an arbitrary `PrintWriter` object. Here is the definition of the method in Java:

[Click here to view code image](#)

```
class Printf3
{
```

```
    public native static void fprintf(PrintWriter out, String s,
double x);
    . . .
}
```

We'll first assemble the string to be printed into a `String` object `str`, as in the `sprint` method that we already implemented. Then, from the C function that implements the native method, we'll call the `print` method of the `PrintWriter` class.

You can call any Java method from C by using the function call

[Click here to view code image](#)

```
(*env)->CallXxxMethod(env, implicit parameter, methodID,
explicit parameters)
```

Replace `Xxx` with `Void`, `Int`, `Object`, and so on, depending on the return type of the method. Just as you need a `fieldID` to access a field of an object, you need a method ID to call a method. To obtain a method ID, call the JNI function `GetMethodID` and supply the class, the name of the method, and the method signature.

In our example, we want to obtain the ID of the `print` method of the `PrintWriter` class. The `PrintWriter` class has several overloaded methods called `print`. For that reason, you must also supply a string describing the parameters and the return value of the specific function that you want to use. For example, we want to use `void print(java.lang.String)`. As described in the preceding section, we must now "mangle" the signature into the string "`(Ljava/lang/String;)V`".

Here is the complete code to make the method call:

[Click here to view code image](#)

```
/* get the class of the implicit parameter */
class_PrintWriter = (*env)->GetObjectClass(env, out);
```

```

/* get the method ID */
id_print = (*env)->GetMethodID(env, class_PrintWriter, "print",
"(Ljava/lang/String;)V");

/* call the method */
(*env)->CallVoidMethod(env, out, id_print, str);

```

[Listings 12.14](#) and [12.15](#) show the Java code for a test program and the `Printf3` class. [Listing 12.16](#) contains the C code for the native `fprint` method.



Note

The numerical method IDs and field IDs are conceptually similar to `Method` and `Field` objects in the reflection API. You can convert between them with the following functions:

[Click here to view code image](#)

```

jobject ToReflectedMethod(JNIEnv* env, jclass class,
jmethodID methodID);
    // returns Method object
methodID FromReflectedMethod(JNIEnv* env, jobject
method);
jobject ToReflectedField(JNIEnv* env, jclass class,
jfieldID fieldID);
    // returns Field object
fieldID FromReflectedField(JNIEnv* env, jobject field);

```

12.6.2 Static Methods

Calling static methods from native methods is similar to calling instance methods. There are two differences:

- Use the `GetStaticMethodID` and `CallStaticXxxMethod` functions

- Supply a class object, not an implicit parameter object, when invoking the method

As an example of this, let's make the call to the static method

[Click here to view code image](#)

```
System.getProperty("java.class.path")
```

from a native method. The return value of this call is a string that gives the current class path.

First, we have to find the class to use. As we have no object of the class System readily available, we use FindClass rather than GetObjectClass.

[Click here to view code image](#)

```
jclass class_System = (*env)->FindClass(env,
"java/lang/System");
```

Next, we need the ID of the static getProperty method. The encoded signature of that method is

[Click here to view code image](#)

```
"(Ljava/lang/String;)Ljava/lang/String;"
```

because both the parameter and the return value are strings. Hence, we obtain the method ID as follows:

[Click here to view code image](#)

```
jmethodID id_getProperty = (*env)->GetStaticMethodID(env,
class_System, "getProperty",
"(Ljava/lang/String;)Ljava/lang/String;");
```

Finally, we can make the call. Note that the class object is passed to the CallStaticObjectMethod function.

[Click here to view code image](#)

```
jobject obj_ret = (*env)->CallStaticObjectMethod(env,
class_System, id_getProperty,
(*env)->NewStringUTF(env, "java.class.path"));
```

The return value of this method is of type `jobject`. If we want to manipulate it as a string, we must cast it to `jstring`:

[Click here to view code image](#)

```
jstring str_ret = (jstring) obj_ret;
```



C++ Note

In C, the types `jstring` and `jclass`, as well as the array types to be introduced later, are all type-equivalent to `jobject`. The cast of the preceding example is therefore not strictly necessary in C. But in C++, these types are defined as pointers to “dummy classes” that have the correct inheritance hierarchy. For example, assigning a `jstring` to a `jobject` is legal without a cast in C++, but an assignment from a `jobject` to a `jstring` requires a cast.

12.6.3 Constructors

A native method can create a new Java object by invoking its constructor. Invoke the constructor by calling the `NewObject` function.

[Click here to view code image](#)

```
jobject obj_new = (*env)->NewObject(env, class, methodID,
construction parameters);
```

You can obtain the method ID needed for this call from the `GetMethodID` function by specifying the method name as "`<init>`" and the encoded

signature of the constructor (with return type `void`). For example, here is how a native method can create a `FileOutputStream` object:

[Click here to view code image](#)

```
const char[] fileName = ". . .";
jstring str_fileName = (*env)->NewStringUTF(env, fileName);
jclass class_FileOutputStream = (*env)->FindClass(env,
"java/io/FileOutputStream");
jmethodID id_FileOutputStream
= (*env)->GetMethodID(env, class_FileOutputStream, "<init>",
"(Ljava/lang/String;)V");
jobject obj_stream
= (*env)->NewObject(env, class_FileOutputStream,
id_FileOutputStream, str_fileName);
```

Note that the signature of the constructor takes a parameter of type `java.lang.String` and has a return type of `void`.

12.6.4 Alternative Method Invocations

Several variants of the JNI functions can be used to call a Java method from native code. These are not as important as the functions that we already discussed, but they are occasionally useful.

The `CallNonvirtualXxxMethod` functions receive an implicit argument, a method ID, a class object (which must correspond to a superclass of the implicit argument), and explicit arguments. The function calls the version of the method in the specified class, bypassing the normal dynamic dispatch mechanism.

All call functions have versions with suffixes “A” and “V” that receive the explicit parameters in an array or a `va_list` (as defined in the C header `stdarg.h`).

Listing 12.14 printf3/Printf3Test.java

[Click here to view code image](#)

```
1 import java.io.*;
2
3 /**
4  * @version 1.11 2018-05-01
5  * @author Cay Horstmann
6  */
7 class Printf3Test
8 {
9     public static void main(String[] args)
10    {
11        double price = 44.95;
12        double tax = 7.75;
13        double amountDue = price * (1 + tax / 100);
14        var out = new PrintWriter(System.out);
15        Printf3.fprintf(out, "Amount due = %8.2f\n", amountDue);
16        out.flush();
17    }
18 }
```

Listing 12.15 printf3/Printf3.java

[Click here to view code image](#)

```
1 import java.io.*;
2
3 /**
4  * @version 1.10 1997-07-01
5  * @author Cay Horstmann
6  */
7 class Printf3
8 {
9     public static native void fprintf(PrintWriter out, String
format, double x);
10
11     static
12     {
13         System.loadLibrary("Printf3");
```

```
14      }
15 }
```

Listing 12.16 printf3/Printf3.c

[Click here to view code image](#)

```
1 /**
2  * @version 1.10 1997-07-01
3  * @author Cay Horstmann
4 */
5
6 #include "Printf3.h"
7 #include <string.h>
8 #include <stdlib.h>
9 #include <float.h>
10
11 /**
12  * @param format a string containing a printf format specifier
13  * (such as "%8.2f"). Substrings "%%" are skipped.
14  * @return a pointer to the format specifier (skipping the
15  * '%')
16  * or NULL if there wasn't a unique format specifier
17 */
18 char* find_format(const char format[])
19 {
20     char* p;
21     char* q;
22
23     p = strchr(format, '%');
24     while (p != NULL && *(p + 1) == '%') /* skip %% */
25         p = strchr(p + 2, '%');
26     if (p == NULL) return NULL;
27     /* now check that % is unique */
28     p++;
29     q = strchr(p, '%');
30     while (q != NULL && *(q + 1) == '%') /* skip %% */
31         q = strchr(q + 2, '%');
```

```
31     if (q != NULL) return NULL; /* % not unique */
32     q = p + strspn(p, " -0+#"); /* skip past flags */
33     q += strspn(q, "0123456789"); /* skip past field width */
34     if (*q == '.') { q++; q += strspn(q, "0123456789"); }
35         /* skip past precision */
36     if (strchr("eEfFgG", *q) == NULL) return NULL;
37         /* not a floating-point format */
38     return p;
39 }
40
41 JNIEXPORT void JNICALL Java_Printf3_fprint(JNIEnv* env, jclass
cl,
42         jobject out, jstring format, jdouble x)
43 {
44     const char* cformat;
45     char* fmt;
46     jstring str;
47     jclass class_PrintWriter;
48     jmethodID id_print;
49
50     cformat = (*env)->GetStringUTFChars(env, format, NULL);
51     fmt = find_format(cformat);
52     if (fmt == NULL)
53         str = format;
54     else
55     {
56         char* cstr;
57         int width = atoi(fmt);
58         if (width == 0) width = DBL_DIG + 10;
59         cstr = (char*) malloc(strlen(cformat) + width);
60         sprintf(cstr, cformat, x);
61         str = (*env)->NewStringUTF(env, cstr);
62         free(cstr);
63     }
64     (*env)->ReleaseStringUTFChars(env, format, cformat);
65
66     /* now call out.print(str) */
67 }
```

```

68     /* get the class */
69     class_PrintWriter = (*env)->GetObjectClass(env, out);
70
71     /* get the method ID */
72     id_print = (*env)->GetMethodID(env, class_PrintWriter,
73                                     "print", "(Ljava/lang/String;)V");
74
75     /* call the method */
76     (*env)->CallVoidMethod(env, out, id_print, str);
76 }

```

Executing Java Methods

- jmethodID GetMethodID(JNIEnv *env, jclass cl, const char name[], const char methodSignature[])
- returns the identifier of a method in a class.
- Xxx CallXxxMethod(JNIEnv *env, jobject obj, jmethodID id, args)
 - Xxx CallXxxMethodA(JNIEnv *env, jobject obj, jmethodID id, jvalue args[])
 - Xxx CallXxxMethodV(JNIEnv *env, jobject obj, jmethodID id, va_list args)

call a method. The return type *Xxx* is one of Object, Boolean, Byte, Char, Short, Int, Long, Float, or Double. The first function has a variable number of arguments—simply append the method parameters after the method ID. The second function receives the method arguments in an array of *jvalue*, where *jvalue* is a union defined as

```

typedef union jvalue
{

```

```
jboolean z;
jbyte b;
jchar c;
jshort s;
jint i;
jlong j;
jfloat f;
jdouble d;
jobject l;
} jvalue;
```

The third function receives the method parameters in a `va_list`, as defined in the C header `stdarg.h`.

- `Xxx CallNonvirtualXxxMethod(JNIEnv *env, jobject obj, jclass cl, jmethodID id, args)`
- `Xxx CallNonvirtualXxxMethodA(JNIEnv *env, jobject obj, jclass cl, jmethodID id, jvalue args[])`
- `Xxx CallNonvirtualXxxMethodV(JNIEnv *env, jobject obj, jclass cl, jmethodID id, va_list args)`

call a method, bypassing dynamic dispatch. The return type `Xxx` is one of `Object`, `Boolean`, `Byte`, `Char`, `Short`, `Int`, `Long`, `Float`, or `Double`. The first function has a variable number of arguments—simply append the method parameters after the method ID. The second function receives the method arguments in an array of `jvalue`. The third function receives the method parameters in a `va_list`, as defined in the C header `stdarg.h`.

- `jmethodID GetStaticMethodID(JNIEnv *env, jclass cl, const char name[], const char methodSignature[])`

returns the identifier of a static method in a class.

- `Xxx CallStaticXxxMethod(JNIEnv *env, jclass cl, jmethodID id, args)`
- `Xxx CallStaticXxxMethodA(JNIEnv *env, jclass cl, jmethodID id, jvalue args[])`
- `Xxx CallStaticXxxMethodV(JNIEnv *env, jclass cl, jmethodID id, va_list args)`

call a static method. The return type `Xxx` is one of `Object`, `Boolean`, `Byte`, `Char`, `Short`, `Int`, `Long`, `Float`, or `Double`. The first function has a variable number of arguments—simply append the method parameters after the method ID. The second function receives the method arguments in an array of `jvalue`. The third function receives the method parameters in a `va_list`, as defined in the C header `stdarg.h`.

- `jobject NewObject(JNIEnv *env, jclass cl, jmethodID id, args)`
- `jobject NewObjectA(JNIEnv *env, jclass cl, jmethodID id, jvalue args[])`
- `jobject NewObjectV(JNIEnv *env, jclass cl, jmethodID id, va_list args)`

call a constructor. The method ID is obtained from `GetMethodID` with a method name of "`<init>`" and a return type of `void`. The first function has a variable number of arguments—simply append the method parameters after the method ID. The second function receives the method arguments in an array of `jvalue`. The third function receives the method parameters in a `va_list`, as defined in the C header `stdarg.h`.

12.7 Accessing Array Elements

All array types of the Java programming language have corresponding C types, as shown in [Table 12.2](#).

Table 12.2 Correspondence between Java Array Types and C Types

| Java Type | C Type |
|-----------|---------------|
| boolean[] | jbooleanArray |
| byte[] | jbyteArray |
| char[] | jcharArray |
| int[] | jintArray |
| short[] | jshortArray |
| long[] | jlongArray |
| float[] | jfloatArray |
| double[] | jdoubleArray |
| Object[] | jobjectArray |



C++ Note

In C, all these array types are actually type synonyms of `jobject`. In C++, however, they are arranged in the inheritance hierarchy shown in [Figure 12.3](#). The type `jarray` denotes a generic array.




Figure 12.3 Inheritance hierarchy of array types

The `GetArrayLength` function returns the length of an array.

[Click here to view code image](#)

```
jarray array = . . .;
jsize length = (*env)->GetArrayLength(env, array);
```

How you access elements in an array depends on whether the array stores objects or values of a primitive type (`bool`, `char`, or a numeric type). To access elements in an object array, use the `GetObjectArrayElement` and `SetObjectArrayElement` methods.

[Click here to view code image](#)

```
jobjectArray array = . . .;
int i, j;
jobject x = (*env)->GetObjectArrayElement(env, array, i);
(*env)->SetObjectArrayElement(env, array, j, x);
```

Although simple, this approach is also clearly inefficient; you want to be able to access array elements directly, especially when doing vector and matrix computations.

The `GetXxxArrayElements` function returns a C pointer to the starting element of an array. As with ordinary strings, you must remember to call the corresponding `ReleaseXxxArrayElements` function to tell the virtual machine when you no longer need that pointer. Here, the type `Xxx` must be a primitive type—that is, not `Object`. You can then read and write the array elements directly. However, since the pointer *might point to a copy*, any changes that you make are guaranteed to be reflected in the original array only after you call the corresponding `ReleaseXxxArrayElements` function!



Note

You can find out if an array is a copy by passing a pointer to a `jboolean` variable as the third parameter to a `GetXxxArrayElements` method. The variable is filled with `JNI_TRUE` if the array is a copy. If you aren't interested in that information, just pass a `NULL` pointer.

Here is an example that multiplies all elements in an array of double values by a constant. We obtain a C pointer `a` into the Java array and then access individual elements as `a[i]`.

[Click here to view code image](#)

```
jdoubleArray array_a = . . .;
double scaleFactor = . . .;
double* a = (*env)->GetDoubleArrayElements(env, array_a, NULL);
for (i = 0; i < (*env)->GetArrayLength(env, array_a); i++)
    a[i] = a[i] * scaleFactor;
(*env)->ReleaseDoubleArrayElements(env, array_a, a, 0);
```

Whether the virtual machine actually copies the array depends on how it allocates arrays and does its garbage collection. Some “copying” garbage collectors routinely move objects around and update object references. That strategy is not compatible with “pinning” an array to a particular location, because the collector cannot update the pointer values in native code.



Note

In the Oracle JVM implementation, boolean arrays are represented as packed arrays of 32-bit words. The `GetBooleanArrayElements` method copies them into unpacked arrays of `jboolean` values.

To access just a few elements of a large array, use the `GetXxxArrayRegion` and `SetXxxArrayRegion` methods that copy a range of elements from the Java array into a C array and back.

You can create new Java arrays in native methods with the `NewXxxArray` function. To create a new array of objects, specify the length, the type of the array elements, and an initial element for all entries (typically, `NULL`). Here is an example:

[Click here to view code image](#)

```
jclass class_Employee = (*env)->FindClass(env, "Employee");  
jobjectArray array_e = (*env)->NewObjectArray(env, 100,  
class_Employee, NULL);
```

Arrays of primitive types are simpler: Just supply the length of the array.

[Click here to view code image](#)

```
jdoubleArray array_d = (*env)->NewDoubleArray(env, 100);
```

The array is then filled with zeroes.



Note

The following methods are used for working with "direct buffers":

[Click here to view code image](#)

```
jobject NewDirectByteBuffer(JNIEnv* env, void* address,  
jlong capacity)  
void* GetDirectBufferAddress(JNIEnv* env, jobject buf)  
jlong GetDirectBufferCapacity(JNIEnv* env, jobject buf)
```

Direct buffers are used in the `java.nio` package to support more efficient input/output operations and to minimize the copying of data between native and Java arrays.

Manipulating Java Arrays

- `jsize GetArrayLength(JNIEnv *env, jarray array)`

returns the number of elements in the array.

- `jobject GetObjectArrayElement(JNIEnv *env, jobjectArray array, jsize index)`

returns the value of an array element.

- `void SetObjectArrayElement(JNIEnv *env, jobjectArray array, jsize index, jobject value)`

sets an array element to a new value.

- `Xxx* GetXxxArrayElements(JNIEnv *env, jarray array, jboolean* isCopy)`

yields a C pointer to the elements of a Java array. The field type `Xxx` is one of Boolean, Byte, Char, Short, Int, Long, Float, or Double. The pointer must be passed to `ReleaseXxxArrayElements` when it is no longer needed. `isCopy` is either `NULL` or points to a `jboolean` that is filled with `JNI_TRUE` if a copy is made, with `JNI_FALSE` otherwise.

- `void ReleaseXxxArrayElements(JNIEnv *env, jarray array, Xxx elems[], jint mode)`

notifies the virtual machine that a pointer obtained by `GetXxxArrayElements` is no longer needed. `mode` is one of 0 (free the `elems` buffer after updating the array elements), `JNI_COMMIT` (do not free the `elems` buffer after updating the array elements), or `JNI_ABORT` (free the `elems` buffer without updating the array elements).

- `void GetXxxArrayRegion(JNIEnv *env, jarray array, jint start, jint length, Xxx elems[])`

copies elements from a Java array to a C array. The field type `Xxx` is one of Boolean, Byte, Char, Short, Int, Long, Float, or Double.

- `void SetXxxArrayRegion(JNIEnv *env, jarray array, jint start, jint length, Xxx elems[])`

copies elements from a C array to a Java array. The field type *Xxx* is one of Boolean, Byte, Char, Short, Int, Long, Float, or Double.

12.8 Handling Errors

Native methods are a significant security risk to Java programs. The C runtime system has no protection against array bounds errors, indirection through bad pointers, and so on. It is particularly important that programmers of native methods handle all error conditions to preserve the integrity of the Java platform. In particular, when your native method diagnoses a problem it cannot handle, it should report this problem to the Java virtual machine.

Normally, you would throw an exception in this situation. However, C has no exceptions. Instead, you must call the Throw or ThrowNew function to create a new exception object. When the native method exits, the Java virtual machine throws that exception.

To use the Throw function, call NewObject to create an object of a subtype of Throwable. For example, here we allocate an EOFException object and throw it:

[Click here to view code image](#)

```
jclass class_EOFException = (*env)->FindClass(env,  
"java/io/EOFException");  
jmethodID id_EOFException = (*env)->GetMethodID(env,  
class_EOFException, "<init>", "()V");  
/* ID of no-argument constructor */  
jthrowable obj_exc = (*env)->NewObject(env, class_EOFException,  
id_EOFException);  
(*env)->Throw(env, obj_exc);
```

It is usually more convenient to call ThrowNew, which constructs an exception object, given a class and a “modified UTF-8” byte sequence.

[Click here to view code image](#)

```
(*env)->ThrowNew(env, (*env)->FindClass(env,  
"java/io/EOFException"),  
"Unexpected end of file");
```

Both Throw and ThrowNew merely *post* the exception; they do not interrupt the control flow of the native method. Only when the method returns does the Java virtual machine throw the exception. Therefore, every call to Throw and ThrowNew should be immediately followed by a return statement.



C++ Note

If you implement native methods in C++, you cannot throw a Java exception object in your C++ code. In a C++ binding, it would be possible to implement a translation between exceptions in C++ and Java; however, this is not currently done. Use Throw or ThrowNew to throw a Java exception in a native C++ method, and make sure your native methods throw no C++ exceptions.

Normally, native code need not be concerned with catching Java exceptions. However, when a native method calls a Java method, that method might throw an exception. Moreover, a number of the JNI functions throw exceptions as well. For example, SetObjectArrayElement throws an ArrayIndexOutOfBoundsException if the index is out of bounds, and an ArrayStoreException if the class of the stored object is not a subclass of the element class of the array. In situations like these, a native method should call the ExceptionOccurred method to determine whether an exception has been thrown. The call

[Click here to view code image](#)

```
jthrowable obj_exc = (*env)->ExceptionOccurred(env);
```

returns `NULL` if no exception is pending, or a reference to the current exception object. If you just want to check whether an exception has been thrown, without obtaining a reference to the exception object, use

[Click here to view code image](#)

```
jboolean occurred = (*env)->ExceptionCheck(env);
```

Normally, a native method should simply return when an exception has occurred so that the virtual machine can propagate it to the Java code. However, a native method *may* analyze the exception object to determine if it can handle the exception. If it can, then the function

```
(*env)->ExceptionClear(env);
```

must be called to turn off the exception.

In our next example, we implement the `fprint` native method with all the paranoia appropriate for a native method. Here are the exceptions that we throw:

- A `NullPointerException` if the format string is `NULL`
- An `IllegalArgumentException` if the format string doesn't contain a `%` specifier that is appropriate for printing a `double`
- An `OutOfMemoryError` if the call to `malloc` fails

Finally, to demonstrate how to check for an exception when calling a Java method from a native method, we send the string to the stream, a character at a time, and call `ExceptionOccurred` after each call. [Listing 12.17](#) shows the code for the native method, and [Listing 12.18](#) shows the definition of the class containing the native method. Notice that the native method does not immediately terminate when an exception occurs in the call to `PrintWriter.print`—it first frees the `cstr` buffer. When the native method returns, the virtual machine again raises the exception. The test program in [Listing 12.19](#) demonstrates how the native method throws an exception when the formatting string is not valid.

Listing 12.17 printf4/Printf4.c

[Click here to view code image](#)

```
1  /**
2   * @version 1.10 1997-07-01
3   * @author Cay Horstmann
4  */
5
6 #include "Printf4.h"
7 #include <string.h>
8 #include <stdlib.h>
9 #include <float.h>
10
11 /**
12  * @param format a string containing a printf format
13  * specifier
14  * (such as "%8.2f"). Substrings "%%" are skipped.
15  * @return a pointer to the format specifier (skipping the
16  * '%')
17  * or NULL if there wasn't a unique format specifier
18 */
19 char* find_format(const char format[])
20 {
21     char* p;
22     char* q;
23
24     p = strchr(format, '%');
25     while (p != NULL && *(p + 1) == '%') /* skip %% */
26         p = strchr(p + 2, '%');
27     if (p == NULL) return NULL;
28     /* now check that % is unique */
29     p++;
30     q = strchr(p, '%');
31     while (q != NULL && *(q + 1) == '%') /* skip %% */
32         q = strchr(q + 2, '%');
33     if (q != NULL) return NULL; /* % not unique */
34     q = p + strspn(p, " -0+#"); /* skip past flags */
35     q += strspn(q, "0123456789"); /* skip past field width */
36     if (*q == '.') { q++; q += strspn(q, "0123456789"); }
```

```
35     /* skip past precision */
36     if (strchr("eEfFgG", *q) == NULL) return NULL;
37     /* not a floating-point format */
38     return p;
39 }
40
41 JNIEXPORT void JNICALL Java_Printf4_fprint(JNIEnv* env,
jclass cl,
42         jobject out, jstring format, jdouble x)
43 {
44     const char* cformat;
45     char* fmt;
46     jclass class_PrintWriter;
47     jmethodID id_print;
48     char* cstr;
49     int width;
50     int i;
51
52     if (format == NULL)
53     {
54         (*env)->ThrowNew(env,
55             (*env)->FindClass(env,
56                 "java/lang/NullPointerException"),
57                 "Printf4.fprint: format is null");
58         return;
59     }
60
61     cformat = (*env)->GetStringUTFChars(env, format, NULL);
62     fmt = find_format(cformat);
63
64     if (fmt == NULL)
65     {
66         (*env)->ThrowNew(env,
67             (*env)->FindClass(env,
68                 "java/lang/IllegalArgumentException"),
69                 "Printf4.fprint: format is invalid");
70         return;
71     }
```

```

72
73     width = atoi(fmt);
74     if (width == 0) width = DBL_DIG + 10;
75     cstr = (char*)malloc(strlen(cformat) + width);
76
77     if (cstr == NULL)
78     {
79         (*env)->ThrowNew(env,
80                         (*env)->FindClass(env,
"java/lang/OutOfMemoryError"),
81                         "Printf4.fprintf: malloc failed");
82     }
83
84     sprintf(cstr, cformat, x);
85
86
87     (*env)->ReleaseStringUTFChars(env, format, cformat);
88
89     /* now call ps.print(str) */
90
91     /* get the class */
92     class_PrintWriter = (*env)->GetObjectClass(env, out);
93
94     /* get the method ID */
95     id_print = (*env)->GetMethodID(env, class_PrintWriter,
"print", "(C)V");
96
97     /* call the method */
98     for (i = 0; cstr[i] != 0 && !(*env)-
>ExceptionOccurred(env); i++)
99     {
100         (*env)->CallVoidMethod(env, out, id_print, cstr[i]);
101     }
102 }
```

Listing 12.18 printf4/Printf4.java

[Click here to view code image](#)

```
1 import java.io.*;
2
3 /**
4  * @version 1.10 1997-07-01
5  * @author Cay Horstmann
6  */
7 class Printf4
8 {
9     public static native void fprintf(PrintWriter ps, String
format, double x);
10
11    static
12    {
13        System.loadLibrary("Printf4");
14    }
15 }
```

Listing 12.19 printf4/Printf4Test.java

[Click here to view code image](#)

```
1 import java.io.*;
2
3 /**
4  * @version 1.11 2018-05-01
5  * @author Cay Horstmann
6  */
7 class Printf4Test
8 {
9     public static void main(String[] args)
10    {
11        double price = 44.95;
12        double tax = 7.75;
13        double amountDue = price * (1 + tax / 100);
14        var out = new PrintWriter(System.out);
15        /* This call will throw an exception--note the %% */
```

```
16     printf4.fprint(out, "Amount due = %%8.2f\n", amountDue);
17     out.flush();
18 }
19 }
```

Handling Java Exceptions

- `jint Throw(JNIEnv *env, jthrowable obj)`
prepares an exception to be thrown upon exiting from the native code. Returns 0 on success, a negative value on failure.
- `jint ThrowNew(JNIEnv *env, jclass cl, const char msg[])`
prepares an exception of type `cl` to be thrown upon exiting from the native code. Returns 0 on success, a negative value on failure. `msg` is a “modified UTF-8” byte sequence denoting the `String` construction argument of the exception object.
- `jthrowable ExceptionOccurred(JNIEnv *env)`
returns the exception object if an exception is pending, or `NULL` otherwise.
- `jboolean ExceptionCheck(JNIEnv *env)`
returns `true` if an exception is pending.
- `void ExceptionClear(JNIEnv *env)`
clears any pending exceptions.

12.9 Using the Invocation API

Up to now, we have considered programs in the Java programming language that made a few C calls, presumably because C was faster or allowed access to functionality inaccessible from the Java platform. Suppose you are in the opposite situation. You have a C or C++ program and would like to make calls to Java code. The *invocation API* enables you to embed the Java virtual machine into a C or C++ program. Here is the minimal code that you need to initialize a virtual machine:

[Click here to view code image](#)

```
JavaVMOption options[1];
JavaVMInitArgs vm_args;
JavaVM *jvm;
JNIEnv *env;

options[0].optionString = "-Djava.class.path=.";

memset(&vm_args, 0, sizeof(vm_args));
vm_args.version = JNI_VERSION_1_2;
vm_args.nOptions = 1;
vm_args.options = options;

JNI_CreateJavaVM(&jvm, (void**) &env, &vm_args);
```

The call to `JNI_CreateJavaVM` creates the virtual machine and fills in a pointer `jvm` to the virtual machine and a pointer `env` to the execution environment.

You can supply any number of options to the virtual machine. Simply increase the size of the `options` array and the value of `vm_args.nOptions`. For example,

[Click here to view code image](#)

```
options[i].optionString = "-Djava.compiler=NONE";
```

deactivates the just-in-time compiler.



Tip

When you run into trouble and your program crashes, refuses to initialize the JVM, or can't load your classes, turn on the JNI debugging mode. Set an option to

[Click here to view code image](#)

```
options[i].optionString = "-verbose:jni";
```

You will see a flurry of messages that indicate the progress in initializing the JVM. If you don't see your classes loaded, check both your path and class path settings.

Once you have set up the virtual machine, you can call Java methods as described in the preceding sections. Simply use the `env` pointer in the usual way.

You'll need the `jvm` pointer only to call other functions in the invocation API. Currently, there are only four such functions. The most important one is the function to terminate the virtual machine:

```
(*jvm)->DestroyJavaVM(jvm);
```

Unfortunately, under Windows, it has become difficult to dynamically link to the `JNI_CreateJavaVM` function in the `jre/bin/client/jvm.dll` library, due to the changed linking rules in Vista and Oracle's reliance on an older C runtime library. Our sample program overcomes this problem by loading the library manually. This is the same approach used by the `java` program—see the file `launcher/java_md.c` in the `src.jar` file that is a part of the JDK.

The C program in [Listing 12.20](#) sets up a virtual machine and calls the `main` method of the `Welcome` class, which was discussed in Volume I, [Chapter 2](#). (Make sure to compile the `Welcome.java` file before starting the invocation test program.)

Listing 12.20 invocation/InvocationTest.c

[Click here to view code image](#)

```
1  /**
2   * @version 1.20 2007-10-26
3   * @author Cay Horstmann
4  */
5
6 #include <jni.h>
7 #include <stdlib.h>
8
9 #ifdef _WINDOWS
10
11 #include <windows.h>
12 static HINSTANCE loadJVMLibrary(void);
13 typedef jint (JNICALL *CreateJavaVM_t)(JavaVM **, void **,
JavaVMInitArgs *);
14
15 #endif
16
17 int main()
18 {
19     JavaVMOption options[2];
20     JavaVMInitArgs vm_args;
21     JavaVM *jvm;
22     JNIEnv *env;
23     long status;
24
25     jclass class_Welcome;
26     jclass class_String;
27     jobjectArray args;
28     jmethodID id_main;
29
30 #ifdef _WINDOWS
31     HINSTANCE hjvmlib;
32     CreateJavaVM_t createJavaVM;
33 #endif
```

```
34
35     options[0].optionString = "-Djava.class.path=.";
36
37     memset(&vm_args, 0, sizeof(vm_args));
38     vm_args.version = JNI_VERSION_1_2;
39     vm_args.nOptions = 1;
40     vm_args.options = options;
41
42 #ifdef _WINDOWS
43     hJvmLib = loadJVMLibrary();
44     createJavaVM = (CreateJavaVM_t) GetProcAddress(hJvmLib,
45 "JNI_CreateJavaVM");
46 #else
47     status = JNI_CreateJavaVM(&jvm, (void **) &env, &vm_args);
48 #endif
49
50     if (status == JNI_ERR)
51     {
52         fprintf(stderr, "Error creating VM\n");
53         return 1;
54     }
55
56     class_Welcome = (*env)->FindClass(env, "Welcome");
57     id_main = (*env)->GetStaticMethodID(env, class_Welcome,
58 "main", "([Ljava/lang/String;)V");
59
60     class_String = (*env)->FindClass(env, "java/lang/String");
61     args = (*env)->NewObjectArray(env, 0, class_String, NULL);
62     (*env)->CallStaticVoidMethod(env, class_Welcome, id_main,
63 args);
64
65     (*jvm)->DestroyJavaVM(jvm);
66 }
67
68 #ifdef _WINDOWS
```

```
69
70 static int GetStringFromRegistry(HKEY key, const char *name,
char *buf, jint bufsize)
71 {
72     DWORD type, size;
73
74     return RegQueryValueEx(key, name, 0, &type, 0, &size) == 0
75         && type == REG_SZ
76         && size < (unsigned int) bufsize
77         && RegQueryValueEx(key, name, 0, 0, buf, &size) == 0;
78 }
79
80 static void GetPublicJREHome(char *buf, jint bufsize)
81 {
82     HKEY key, subkey;
83     char version[MAX_PATH];
84
85     /* Find the current version of the JRE */
86     char *JRE_KEY = "Software\\JavaSoft\\Java Runtime
Environment";
87     if (RegOpenKeyEx(HKEY_LOCAL_MACHINE, JRE_KEY, 0, KEY_READ,
&key) != 0)
88     {
89         fprintf(stderr, "Error opening registry key '%s'\n",
JRE_KEY);
90         exit(1);
91     }
92
93     if (!GetStringFromRegistry(key, "CurrentVersion", version,
sizeof(version)))
94     {
95         fprintf(stderr, "Failed reading value of registry
key:\n\t%s\\CurrentVersion\n",
96             JRE_KEY);
97         RegCloseKey(key);
98         exit(1);
99     }
100
```

```
101     /* Find directory where the current version is installed.  
 */  
102     if (RegOpenKeyEx(key, version, 0, KEY_READ, &subkey) != 0)  
103     {  
104         fprintf(stderr, "Error opening registry key  
'%s\\%s'\\n", JRE_KEY, version);  
105         RegCloseKey(key);  
106         exit(1);  
107     }  
108  
109     if (!GetStringFromRegistry(subkey, "JavaHome", buf,  
bufsize))  
110     {  
111         fprintf(stderr, "Failed reading value of registry  
key:\\n\t%s\\%s\\JavaHome\\n",  
112             JRE_KEY, version);  
113         RegCloseKey(key);  
114         RegCloseKey(subkey);  
115         exit(1);  
116     }  
117  
118     RegCloseKey(key);  
119     RegCloseKey(subkey);  
120 }  
121  
122 static HINSTANCE loadJVMLibrary(void)  
123 {  
124     HINSTANCE h1, h2;  
125     char msวดll[MAX_PATH];  
126     char javadll[MAX_PATH];  
127     GetPublicJREHome(msวดll, MAX_PATH);  
128     strcpy(javadll, msวดll);  
129     strncat(msวดll, "\\\bin\\\\msvcr71.dll", MAX_PATH -  
strlen(msวดll));  
130     msวดll[MAX_PATH - 1] = '\0';  
131     strncat(javadll, "\\\bin\\\\client\\\\jvm.dll", MAX_PATH -  
strlen(javadll));  
132     javadll[MAX_PATH - 1] = '\0';
```

```
133
134     h1 = LoadLibrary(msvcdll);
135     if (h1 == NULL)
136     {
137         fprintf(stderr, "Can't load library msvcr71.dll\n");
138         exit(1);
139     }
140
141     h2 = LoadLibrary(javadll);
142     if (h2 == NULL)
143     {
144         fprintf(stderr, "Can't load library jvm.dll\n");
145         exit(1);
146     }
147     return h2;
148 }
149
150 #endif
```

To compile this program under Linux, use

[Click here to view code image](#)

```
gcc -I jdk/include -I jdk/include/linux -o InvocationTest \
      -L jdk/jre/lib/i386/client -ljvm InvocationTest.c
```

When compiling in Windows with the Microsoft compiler, use the command line

[Click here to view code image](#)

```
cl -D_WINDOWS -I jdk\include -I jdk\include\win32
InvocationTest.c \
      jdk\lib\jvm.lib advapi32.lib
```

You will need to make sure that the INCLUDE and LIB environment variables include the paths to the Windows API header and library files.

Using Cygwin, compile with

[Click here to view code image](#)

```
gcc -D_WINDOWS -mno-cygwin -I jdk\include -I jdk\include\win32  
-D__int64="long long" \  
-I c:\cygwin\usr\include\w32api -o InvocationTest
```

Before you run the program under Linux/UNIX, make sure that the LD_LIBRARY_PATH contains the directories for the shared libraries. For example, if you use the bash shell on Linux, issue the following command:

[Click here to view code image](#)

```
export LD_LIBRARY_PATH=jdk/jre/lib/i386/client:$LD_LIBRARY_PATH
```

Invocation API Functions

- `jint JNI_CreateJavaVM(JavaVM** p_jvm, void** p_env, JavaVMInitArgs* vm_args)`

initializes the Java virtual machine. The function returns 0 if successful, JNI_ERR on failure. The `p_jvm` parameter is filled with a pointer to the invocation API function table, and `p_env` is filled with a pointer to the JNI function table.

- `jint DestroyJavaVM(JavaVM* jvm)`

destroys the virtual machine. Returns 0 on success, a negative number on failure. This function must be called through a virtual machine pointer, that is, `(*jvm) ->DestroyJavaVM(jvm)`.

12.10 A Complete Example: Accessing the Windows Registry

In this section, I describe a full, working example that covers everything we discussed in this chapter: using native methods with strings, arrays, objects, constructor calls, and error handling. I'll show you how to put a Java platform wrapper around a subset of the ordinary C-based APIs used to work with the Windows registry. Of course, the Windows registry being a Windows-specific feature, such a program is inherently nonportable. For that reason, the standard Java library has no support for the registry, and it makes sense to use native methods to gain access to it.

12.10.1 Overview of the Windows Registry

The Windows registry is a data depository that holds configuration information for the Windows operating system and application programs. It provides a single point for administration and backup of system and application preferences. On the downside, the registry is also a single point of failure—if you mess up the registry, your computer could malfunction or even fail to boot!

We don't suggest that you use the registry to store configuration parameters for your Java programs. The Java preferences API is a better solution (see Volume I, [Chapter 10](#) for more information). We'll simply use the registry to demonstrate how to wrap a nontrivial native API into a Java class.

The principal tool for inspecting the registry is the *registry editor*. Because of the potential for error by naive but enthusiastic users, there is no icon for launching the registry editor. Instead, start a DOS shell (or open the Start → Run dialog box) and type `regedit`. [Figure 12.4](#) shows the registry editor in action.




Figure 12.4 The registry editor

The left side shows the keys, which are arranged in a tree structure. Note that each key starts with one of the HKEY nodes like

HKEY_CLASSES_ROOT
HKEY_CURRENT_USER
HKEY_LOCAL_MACHINE
... . . .

The right side shows the name/value pairs associated with a particular key. For example, if you installed Java 17, the key

[Click here to view code image](#)

```
HKEY_LOCAL_MACHINE\Software\JavaSoft\Java Runtime Environment
```

contains a name/value pair such as

```
CurrentVersion="17.0_10"
```

In this case, the value is a string. The values can also be integers or arrays of bytes.

12.10.2 A Java Platform Interface for Accessing the Registry

We create a simple interface to access the registry from Java code, and then implement this interface with native code. The interface allows only a few registry operations; to keep the code size down, I omitted some important operations such as adding, deleting, and enumerating keys. (It should be easy to add the remaining registry API functions.)

Even with the limited subset that we supply, you can

- Enumerate all names stored in a key
- Read the value stored with a name
- Set the value stored with a name

Here is the Java class that encapsulates a registry key:

[Click here to view code image](#)

```
public class Win32RegKey
{
    public Win32RegKey(int theRoot, String thePath) { . . . }
    public Enumeration names() { . . . }
    public native Object getValue(String name);
    public native void setValue(String name, Object value);

    public static final int HKEY_CLASSES_ROOT = 0x80000000;
    public static final int HKEY_CURRENT_USER = 0x80000001;
    public static final int HKEY_LOCAL_MACHINE = 0x80000002;
```

```
    . . .
}
```

The names method returns an enumeration that holds all the names stored with the key. You can get at them with the familiar hasMoreElements/nextElement methods. The getValue method returns an object that is either a string, an Integer object, or a byte array. The value parameter of the setValue method must also be of one of these three types.

12.10.3 Implementation of Registry Access Functions as Native Methods

We need to implement three actions:

- Get the value of a name
- Set the value of a name
- Iterate through the names of a key

In this chapter, you have seen essentially all the tools that are required, such as the conversion between Java strings and arrays and those of C. You also saw how to raise a Java exception in case something goes wrong.

Two issues make these native methods more complex than the preceding examples. The getValue and setValue methods deal with the type Object, which can be one of String, Integer, or byte[]. The enumeration object stores the state between successive calls to hasMoreElements and nextElement.

Let us first look at the getValue method. The method (shown in Listing 12.22) goes through the following steps:

1. Opens the registry key. To read their values, the registry API requires that keys be open.
2. Queries the type and size of the value associated with the name.
3. Reads the data into a buffer.

4. Calls `NewStringUTF` to create a new string with the value data if the type is `REG_SZ` (a string).
5. Invokes the `Integer` constructor if the type is `REG_DWORD` (a 32-bit integer).
6. Calls `NewByteArray` to create a new byte array, then `SetByteArrayRegion` to copy the value data into the byte array, if the type is `REG_BINARY`.
7. If the type is none of these or if an error occurred when an API function was called, throws an exception and releases all resources that had been acquired up to that point.
8. Closes the key and returns the object (`String`, `Integer`, or `byte[]`) that had been created.

As you can see, this example illustrates quite nicely how to generate Java objects of different types.

In this native method, coping with the generic return type is not difficult. The `jstring`, `jobject`, or `jarray` reference is simply returned as a `jobject`. However, the `setValue` method receives a reference to an `Object` and must determine the `Object`'s exact type to save the `Object` as a string, integer, or byte array. We can make this determination by querying the class of the value object, finding the class references for `java.lang.String`, `java.lang.Integer`, and `byte[]`, and comparing them with the `IsAssignableFrom` function.

If `class1` and `class2` are two class references, then the call

[Click here to view code image](#)

```
(*env)->IsAssignableFrom(env, class1, class2)
```

returns `JNI_TRUE` when `class1` and `class2` are the same class or when `class1` is a subclass of `class2`. In either case, references to objects of `class1` can be cast to `class2`. For example, when

[Click here to view code image](#)

```
(*env)->IsAssignableFrom(env, (*env)->GetObjectClass(env,
value),
(*env)->FindClass(env, "[B"))
```

is true, we know that `value` is a byte array.

Here is an overview of the steps in the `setValue` method:

1. Open the registry key for writing.
2. Find the type of the value to write.
3. Call `GetStringUTFChars` to get a pointer to the characters if the type is `String`.
4. Call the `intValue` method to get the integer stored in the wrapper object if the type is `Integer`.
5. Call `GetByteArrayElements` to get a pointer to the bytes if the type is `byte[]`.
6. Pass the data and length to the registry.
7. Close the key.
8. Release the pointer to the data if the type is `String` or `byte[]`.

Finally, let us turn to the native methods that enumerate keys. These are methods of the `Win32RegKeyNameEnumeration` class (see [Listing 12.21](#)). When the enumeration process starts, we must open the key. For the duration of the enumeration, we must retain the key handle—that is, the key handle must be stored with the enumeration object. The key handle is of type `DWORD` (a 32-bit quantity), so it can be stored in a Java integer. We store it in the `hkey` field of the enumeration class. When the enumeration starts, the field is initialized with `SetIntField`. Subsequent calls read the value with `GetIntField`.

In this example, we store three other data items with the enumeration object. When the enumeration first starts, we can query the registry for the count of name/value pairs and the length of the longest name, which we need so we can allocate C character arrays to hold the names. These values are stored in the `count` and `maxsize` fields of the enumeration object. Finally, the `index` field, initialized with `-1` to indicate the start of the

enumeration, is set to 0 once the other instance fields are initialized, and is incremented after every enumeration step.

Let's walk through the native methods that support the enumeration. The `hasMoreElements` method is simple:

1. Retrieve the `index` and `count` fields.
2. If the `index` is -1, call the `startNameEnumeration` function which opens the key, queries the count and maximum length, and initializes the `hkey`, `count`, `maxsize`, and `index` fields.
3. Return `JNI_TRUE` if `index` is less than `count`, and `JNI_FALSE` otherwise.

The `nextElement` method needs to work a little harder:

1. Retrieve the `index` and `count` fields.
2. If the `index` is -1, call the `startNameEnumeration` function, which opens the key, queries the count and maximum length, and initializes the `hkey`, `count`, `maxsize`, and `index` fields.
3. If `index` equals `count`, throw a `NoSuchElementException`.
4. Read the next name from the registry.
5. Increment `index`.
6. If `index` equals `count`, close the key.

Before compiling, remember to run `javac -h` on both `Win32RegKey` and `Win32RegKeyNameEnumeration`. The complete command line for the Microsoft compiler is

[Click here to view code image](#)

```
cl -I jdk\include -I jdk\include\win32 -LD Win32RegKey.c  
advapi32.lib -FeWin32RegKey.dll
```

With Cygwin, use

[Click here to view code image](#)

```
gcc -mno-cygwin -D __int64="long long" -I jdk\include -I  
jdk\include\win32 \  
-I c:\cygwin\usr\include\w32api -shared -Wl,--addstdcall-  
alias -o Win32RegKey.dll  
Win32RegKey.c
```

As the registry API is specific to Windows, this program will not work on other operating systems.

[Listing 12.23](#) shows a program to test our new registry functions. We add three name/value pairs, a string, an integer, and a byte array to the key

[Click here to view code image](#)

```
HKEY_CURRENT_USER\Software\JavaSoft\Java Runtime Environment
```

We then enumerate all names of that key and retrieve their values. The program will print

```
Default user=Harry Hacker  
Lucky number=13  
Small primes=2 3 5 7 11 13
```

Although adding these name/value pairs to that key probably does no harm, you might want to use the registry editor to remove them after running this program.

Listing 12.21 win32reg/Win32RegKey.java

[Click here to view code image](#)

```
1 import java.util.*;  
2  
3 /**  
4  * A Win32RegKey object can be used to get and set values of a  
5  * registry key in the Windows  
6  * registry.  
7  * @version 1.00 1997-07-01
```

```
7 * @author Cay Horstmann
8 */
9 public class Win32RegKey
10 {
11     public static final int HKEY_CLASSES_ROOT = 0x80000000;
12     public static final int HKEY_CURRENT_USER = 0x80000001;
13     public static final int HKEY_LOCAL_MACHINE = 0x80000002;
14     public static final int HKEY_USERS = 0x80000003;
15     public static final int HKEY_CURRENT_CONFIG = 0x80000005;
16     public static final int HKEY_DYN_DATA = 0x80000006;
17
18     private int root;
19     private String path;
20
21     /**
22      * Gets the value of a registry entry.
23      * @param name the entry name
24      * @return the associated value
25      */
26     public native Object getValue(String name);
27
28     /**
29      * Sets the value of a registry entry.
30      * @param name the entry name
31      * @param value the new value
32      */
33     public native void setValue(String name, Object value);
34
35     /**
36      * Construct a registry key object.
37      * @param theRoot one of HKEY_CLASSES_ROOT,
HKEY_CURRENT_USER, HKEY_LOCAL_MACHINE,
38      * HKEY_USERS, HKEY_CURRENT_CONFIG, HKEY_DYN_DATA
39      * @param thePath the registry key path
40      */
41     public Win32RegKey(int theRoot, String thePath)
42     {
43         root = theRoot;
```

```
44         path = thePath;
45     }
46
47     /**
48      * Enumerates all names of registry entries under the path
49      * that this object describes.
50      * @return an enumeration listing all entry names
51     */
52     public Enumeration<String> names()
53     {
54         return new Win32RegKeyNameEnumeration(root, path);
55     }
56
57     static
58     {
59         System.loadLibrary("Win32RegKey");
60     }
61
62 class Win32RegKeyNameEnumeration implements
63 Enumeration<String>
64 {
65     public native String nextElement();
66     public native boolean hasMoreElements();
67     private int root;
68     private String path;
69     private int index = -1;
70     private int hkey = 0;
71     private int maxsize;
72     private int count;
73
74     Win32RegKeyNameEnumeration(int theRoot, String thePath)
75     {
76         root = theRoot;
77         path = thePath;
78     }
79 }
```

```
80 class Win32RegKeyException extends RuntimeException
81 {
82     public Win32RegKeyException()
83     {
84     }
85
86     public Win32RegKeyException(String why)
87     {
88         super(why);
89     }
90 }
```

Listing 12.22 win32reg/Win32RegKey.c

[Click here to view code image](#)

```
1 /**
2  * @version 1.00 1997-07-01
3  * @author Cay Horstmann
4 */
5
6 #include "Win32RegKey.h"
7 #include "Win32RegKeyNameEnumeration.h"
8 #include <string.h>
9 #include <stdlib.h>
10 #include <windows.h>
11
12 JNIEXPORT jobject JNICALL Java_Win32RegKey_getValue(
13     JNIEnv* env, jobject this_obj, jobject name)
14 {
15     const char* cname;
16     jstring path;
17     const char* cpath;
18     HKEY hkey;
19     DWORD type;
20     DWORD size;
21     jclass this_class;
22     jfieldID id_root;
```

```
23     jfieldID id_path;
24     HKEY root;
25     jobject ret;
26     char* cret;
27
28     /* get the class */
29     this_class = (*env)->GetObjectClass(env, this_obj);
30
31     /* get the field IDs */
32     id_root = (*env)->GetFieldID(env, this_class, "root",
33 "I");
33     id_path = (*env)->GetFieldID(env, this_class, "path",
34 "Ljava/lang/String;");
34
35     /* get the fields */
36     root = (HKEY) (*env)->GetIntField(env, this_obj, id_root);
37     path = (jstring) (*env)->GetObjectField(env, this_obj,
38 id_path);
38     cpath = (*env)->GetStringUTFChars(env, path, NULL);
39
40     /* open the registry key */
41     if (RegOpenKeyEx(root, cpath, 0, KEY_READ, &hkey) !=
42 ERROR_SUCCESS)
42     {
43         (*env)->ThrowNew(env, (*env)->FindClass(env,
44 "Win32RegKeyException"),
44         "Open key failed");
45         (*env)->ReleaseStringUTFChars(env, path, cpath);
46         return NULL;
47     }
48
49     (*env)->ReleaseStringUTFChars(env, path, cpath);
50     cname = (*env)->GetStringUTFChars(env, name, NULL);
51
52     /* find the type and size of the value */
53     if (RegQueryValueEx(hkey, cname, NULL, &type, NULL, &size)
53 != ERROR_SUCCESS)
54     {
```

```
55      (*env)->ThrowNew(env, (*env)->FindClass(env,
56      "Win32RegKeyException"),
57      "Query value key failed");
58      RegCloseKey(hkey);
59      (*env)->ReleaseStringUTFChars(env, name, cname);
60      return NULL;
61  }
62  /* get memory to hold the value */
63  cret = (char*)malloc(size);
64
65  /* read the value */
66  if (RegQueryValueEx(hkey, cname, NULL, &type, cret, &size)
!= ERROR_SUCCESS)
67  {
68      (*env)->ThrowNew(env, (*env)->FindClass(env,
69      "Win32RegKeyException"),
70      "Query value key failed");
71      free(cret);
72      RegCloseKey(hkey);
73      (*env)->ReleaseStringUTFChars(env, name, cname);
74      return NULL;
75
76  /* depending on the type, store the value in a string,
77  integer, or byte array */
78  if (type == REG_SZ)
79  {
80      ret = (*env)->NewStringUTF(env, cret);
81  }
82  else if (type == REG_DWORD)
83  {
84      jclass class_Integer = (*env)->FindClass(env,
"java/lang/Integer");
85      /* get the method ID of the constructor */
86      jmethodID id_Integer = (*env)->GetMethodID(env,
class_Integer, "<init>", "(I)V");
87      int value = *(int*) cret;
```

```
88     /* invoke the constructor */
89     ret = (*env)->NewObject(env, class_Integer, id_Integer,
90     value);
91
92     }
93     else if (type == REG_BINARY)
94     {
95         ret = (*env)->NewByteArray(env, size);
96         (*env)->SetByteArrayRegion(env, (jarray) ret, 0, size,
97         cret);
98     }
99     else
100    {
101        (*env)->ThrowNew(env, (*env)->FindClass(env,
102        "Win32RegKeyException"),
103        "Unsupported value type");
104
105        ret = NULL;
106
107    }
108
109
110 JNIEXPORT void JNICALL Java_Win32RegKey_setValue(JNIEnv* env,
111 jobject this_obj,
112 jstring name, jobject value)
113 {
114     const char* cname;
115     jstring path;
116     const char* cpath;
117     HKEY hkey;
118     DWORD type;
119     DWORD size;
120     jclass this_class;
121     jclass class_value;
122     jclass class_Integer;
```



```
154     /* determine the type of the value object */
155     if ((*env)->IsAssignableFrom(env, class_value, (*env)-
156 >FindClass(env, "java/lang/String")))
157     {
158         /* it is a string--get a pointer to the characters */
159         cvalue = (*env)->GetStringUTFChars(env, (jstring)
160 value, NULL);
161         type = REG_SZ;
162         size = (*env)->GetStringLength(env, (jstring) value) +
163         1;
164     }
165     else if ((*env)->IsAssignableFrom(env, class_value,
166 class_Integer))
167     {
168         /* it is an integer--call intValue to get the value */
169         jmethodID id_intValue = (*env)->GetMethodID(env,
170 class_Integer, "intValue", "()I");
171         ivalue = (*env)->CallIntMethod(env, value,
172 id_intValue);
173         type = REG_DWORD;
174         cvalue = (char*)&ivalue;
175         size = 4;
176     }
177     else if ((*env)->IsAssignableFrom(env, class_value,
178 (*env)->FindClass(env, "[B")))
179     {
180         /* it is a byte array--get a pointer to the bytes */
181         type = REG_BINARY;
182         cvalue = (char*) (*env)->GetByteArrayElements(env,
183 (jarray) value, NULL);
184         size = (*env)->GetArrayLength(env, (jarray) value);
185     }
186     else
187     {
188         /* we don't know how to handle this type */
189         (*env)->ThrowNew(env, (*env)->FindClass(env,
190 "Win32RegKeyException"),
191                     "Unsupported value type");
192 }
```

```
183     RegCloseKey(hkey);
184     (*env)->ReleaseStringUTFChars(env, name, cname);
185     return;
186 }
187
188 /* set the value */
189 if (RegSetValueEx(hkey, cname, 0, type, cvalue, size) != ERROR_SUCCESS)
190 {
191     (*env)->ThrowNew(env, (*env)->FindClass(env,
192                                         "Win32RegKeyException"),
193                         "Set value failed");
194 }
195
196 RegCloseKey(hkey);
197 (*env)->ReleaseStringUTFChars(env, name, cname);
198
199 /* if the value was a string or byte array, release the
pointer */
200 if (type == REG_SZ)
201 {
202     (*env)->ReleaseStringUTFChars(env, (jstring) value,
cvalue);
203 }
204 else if (type == REG_BINARY)
205 {
206     (*env)->ReleaseByteArrayElements(env, (jarray) value,
(jbyte*) cvalue, 0);
207 }
208
209 /* helper function to start enumeration of names */
210 static int startNameEnumeration(JNIEnv* env, jobject
this_obj, jclass this_class)
211 {
212     jfieldID id_index;
213     jfieldID id_count;
214     jfieldID id_root;
```

```
215     jfieldID id_path;
216     jfieldID id_hkey;
217     jfieldID id_maxsize;
218
219     HKEY root;
220     jstring path;
221     const char* cpath;
222     HKEY hkey;
223     DWORD maxsize = 0;
224     DWORD count = 0;
225
226     /* get the field IDs */
227     id_root = (*env)->GetFieldID(env, this_class, "root",
228                                     "I");
228     id_path = (*env)->GetFieldID(env, this_class, "path",
229                                    "Ljava/lang/String;");
229     id_hkey = (*env)->GetFieldID(env, this_class, "hkey",
230                                     "I");
230     id_maxsize = (*env)->GetFieldID(env, this_class,
231                                      "maxsize", "I");
231     id_index = (*env)->GetFieldID(env, this_class, "index",
232                                     "I");
232     id_count = (*env)->GetFieldID(env, this_class, "count",
233                                     "I");
233
234     /* get the field values */
235     root = (HKEY) (*env)->GetIntField(env, this_obj, id_root);
236     path = (jstring) (*env)->GetObjectField(env, this_obj,
237                                              id_path);
237     cpath = (*env)->GetStringUTFChars(env, path, NULL);
238
239     /* open the registry key */
240     if (RegOpenKeyEx(root, cpath, 0, KEY_READ, &hkey) !=
241         ERROR_SUCCESS)
241     {
242         (*env)->ThrowNew(env, (*env)->FindClass(env,
243                                         "Win32RegKeyException"),
243                         "Open key failed");
```

```
244     (*env)->ReleaseStringUTFChars(env, path, cpath);
245     return -1;
246 }
247 (*env)->ReleaseStringUTFChars(env, path, cpath);
248
249 /* query count and max length of names */
250 if (RegQueryInfoKey(hkey, NULL, NULL, NULL, NULL, NULL,
251     &count, &maxsize,
252     NULL, NULL, NULL) != ERROR_SUCCESS)
253 {
254     (*env)->ThrowNew(env, (*env)->FindClass(env,
255         "Win32RegKeyException"),
256         "Query info key failed");
257     RegCloseKey(hkey);
258     return -1;
259 }
260 /* set the field values */
261 (*env)->SetIntField(env, this_obj, id_hkey, (DWORD) hkey);
262 (*env)->SetIntField(env, this_obj, id_maxsize, maxsize +
263 1);
264 (*env)->SetIntField(env, this_obj, id_index, 0);
265 (*env)->SetIntField(env, this_obj, id_count, count);
266 return count;
267 }
268
269 JNIEXPORT jboolean JNICALL
Java_Win32RegKeyNameEnumeration_hasMoreElements(JNIEnv* env,
270         jobject this_obj)
271 {
272     jclass this_class;
273     jfieldID id_index;
274     jfieldID id_count;
275     int index;
276     int count;
277     /* get the class */
278     this_class = (*env)->GetObjectClass(env, this_obj);
279 }
```

```
278     /* get the field IDs */
279     id_index = (*env)->GetFieldID(env, this_class, "index",
280                                     "I");
280     id_count = (*env)->GetFieldID(env, this_class, "count",
281                                     "I");
281
282     index = (*env)->GetIntField(env, this_obj, id_index);
283     if (index == -1) /* first time */
284     {
285         count = startNameEnumeration(env, this_obj,
286                                     this_class);
286         index = 0;
287     }
288     else
289         count = (*env)->GetIntField(env, this_obj, id_count);
290     return index < count;
291 }
292
293 JNIEXPORT jobject JNICALL
Java_Win32RegKeyNameEnumeration.nextElement(JNIEnv* env,
294                                         jobject this_obj)
295 {
296     jclass this_class;
297     jfieldID id_index;
298     jfieldID id_hkey;
299     jfieldID id_count;
300     jfieldID id_maxsize;
301
302     HKEY hkey;
303     int index;
304     int count;
305     DWORD maxsize;
306
307     char* cret;
308     jstring ret;
309
310     /* get the class */
311     this_class = (*env)->GetObjectClass(env, this_obj);
```

```
312
313     /* get the field IDs */
314     id_index = (*env)->GetFieldID(env, this_class, "index",
315     "I");
315     id_count = (*env)->GetFieldID(env, this_class, "count",
316     "I");
316     id_hkey = (*env)->GetFieldID(env, this_class, "hkey",
317     "I");
317     id_maxsize = (*env)->GetFieldID(env, this_class,
318     "maxsize", "I");
318
319     index = (*env)->GetIntField(env, this_obj, id_index);
320     if (index == -1) /* first time */
321     {
322         count = startNameEnumeration(env, this_obj,
323         this_class);
323         index = 0;
324     }
325     else
326         count = (*env)->GetIntField(env, this_obj, id_count);
327
328     if (index >= count) /* already at end */
329     {
330         (*env)->ThrowNew(env, (*env)->FindClass(env,
331             "java/util/NoSuchElementException"),
331             "past end of enumeration");
332         return NULL;
333     }
334
335     maxsize = (*env)->GetIntField(env, this_obj, id_maxsize);
336     hkey = (HKEY)(*env)->GetIntField(env, this_obj, id_hkey);
337     cret = (char*)malloc(maxsize);
338
339     /* find the next name */
340     if (RegEnumValue(hkey, index, cret, &maxsize, NULL, NULL,
341         NULL, NULL) != ERROR_SUCCESS)
341     {
342         (*env)->ThrowNew(env, (*env)->FindClass(env,
```

```

"Win32RegKeyException"),
343         "Enum value failed");
344     free(cret);
345     RegCloseKey(hkey);
346     (*env)->SetIntField(env, this_obj, id_index, count);
347     return NULL;
348 }
349
350 ret = (*env)->NewStringUTF(env, cret);
351 free(cret);
352
353 /* increment index */
354 index++;
355 (*env)->SetIntField(env, this_obj, id_index, index);
356
357 if (index == count) /* at end */
358 {
359     RegCloseKey(hkey);
360 }
361
362 return ret;
363 }
```

Listing 12.23 win32reg/Win32RegKeyTest.java

[Click here to view code image](#)

```

1 import java.util.*;
2
3 /**
4  * @version 1.04 2021-05-30
5  * @author Cay Horstmann
6 */
7 public class Win32RegKeyTest
8 {
9     public static void main(String[] args)
10    {
11        var key = new Win32RegKey(
```

```

12         Win32RegKey.HKEY_CURRENT_USER,
13         "Software\\JavaSoft\\Java Runtime Environment");
14
15         key.setValue("Default user", "Harry Hacker");
16         key.setValue("Lucky number", Integer.valueOf(13));
17         key.setValue("Small primes", new byte[] { 2, 3, 5, 7, 11
18 });
19
20         Enumeration<String> e = key.names();
21
22         while (e.hasMoreElements())
23         {
24             String name = e.nextElement();
25             System.out.print(name + "=");
26
27             Object value = key.getValue(name);
28
29             if (value instanceof byte[] bytes)
30                 for (byte b : bytes) System.out.print((b & 0xFF) +
31 " ");
32             else
33                 System.out.print(value);
34         }
35     }

```

Type Inquiry Functions

- jboolean IsAssignableFrom(JNIEnv *env, jclass cl1, jclass cl2)

returns JNI_TRUE if objects of the first class can be assigned to objects of the second class, and JNI_FALSE otherwise. This tests if the classes are the same, or cl1 is a subclass of cl2, or cl2

represents an interface implemented by `c11` or one of its superclasses.

- `jclass GetSuperclass(JNIEnv *env, jclass cl)`
returns the superclass of a class. If `cl` represents the class `Object` or an interface, returns `NULL`.

12.11 Foreign Functions: A Glimpse into the Future

When using JNI, you have to write C code to access Java data structures, call the desired C functions, and to convert the result back to Java. Then you have to link the C code into platform-specific libraries. An API for accessing “foreign” functions and memory, developed under the code name “Project Panama,” allows you to write this code in Java.

In Java 17, the API is a preview feature, and the details will change before the final release. The program in [Listing 12.24](#) is a very simple demonstration of the preview API.

The program simply calls the `printf` function. No additional C code is necessary. The function is invoked through a Java `MethodHandle`, which is normally used to call Java functions.

To access C functions, you first create a `CLinker` object. The `CLinker` can produce a Java method handle for a C function, given its address and type description. The details of this API are in flux, so let us not dwell on them.

The API has methods for translating Java objects into memory blocks that you can pass to the C function. In the demo, you need to provide a `char*` with the characters from a Java `String`. The `CLinker` provides this translation.

The memory is allocated in a `ResourceScope`, so that its deallocation can be managed. Here, we use a *confined* scope. It is autocloseable, and the `close` method deallocates all allocated memory.

As you can see, this API is much simpler and more convenient than JNI. This demo only scratches the surface of the API. There are many methods for reading, writing, and managing memory blocks. You can also pass Java functions as callbacks to C functions.

To compile the demo program, use these options:

[Click here to view code image](#)

```
javac --enable-preview --source 17 --add-modules \
       jdk.incubator.foreign panama/PanamaDemo.java
```

The foreign function and memory API is inherently unsafe because it provides access to unmanaged memory. You use a runtime flag to permit a module to use the API. Typically, one would place the bridge code between a Java API and a C library into a separate module. However, in the demo, the native access happens in the unnamed module. Here is the command line to run it:

[Click here to view code image](#)

```
java --add-modules jdk.incubator.foreign \
      --enable-native-access=ALL-UNNAMED panama.PanamaDemo
```

For now, you will still need to use JNI as a stable API for interoperating with native code. As the foreign function and memory API matures, it will provide a superior replacement for JNI.

Listing 12.24 panama/PanamaDemo.java

[Click here to view code image](#)

```
1 package panama;
2
3 import java.lang.reflect.*;
4 import java.lang.invoke.*;
```

```
5 import jdk.incubator.foreign.*;
6 import static jdk.incubator.foreign.MemoryLayouts.*;
7
8 /*
9
10 javac --enable-preview --source 17 --add-modules
jdk.incubator.foreign panama/PanamaDemo.java
11
12 java --add-modules jdk.incubator.foreign --enable-native-
access=ALL-UNNAMED panama.PanamaDemo
13
14 */
15
16 public class PanamaDemo
17 {
18     public static void main(String[] args) throws Throwable
19     {
20         CLinker linker = CLinker.getInstance();
21         MethodHandle printf = linker.downcallHandle(
22             CLinker.systemLookup().lookup("printf").get(),
23             MethodType.methodType(int.class,
MemoryAddress.class),
24             FunctionDescriptor.of(CLinker.C_INT,
CLinker.C_POINTER));
25
26         try (ResourceScope scope =
ResourceScope.newConfinedScope())
27         {
28             var cString = CLinker.toCString("Hello, World!\n",
scope);
29             int result = (int) printf.invoke(cString.address());
30             System.out.println("Printed %d
characters.".formatted(result));
31         }
32     }
33 }
```

You have now reached the end of the second volume of *Core Java*, completing a long journey in which you encountered many advanced APIs. I started out with topics that every Java programmer needs to know: streams, XML, networking, databases, and internationalization. I concluded with very technical chapters on security, annotation processing, advanced graphics, and native methods. I hope that you enjoyed your tour through the vast breadth of the Java APIs, and that you will be able to apply your newly gained knowledge in your projects.

Index

Numbers

- (minus sign)
 - in regular expressions, [144](#)
 - in URLs, [271](#)
- _ (underscore)
 - in native method names, [787–788](#)
 - in SQL, [299, 329](#)
 - in URLs, [271](#)
- , (comma)
 - decimal, [388, 395, 402](#)
 - in DTDs, [178–179](#)
- ; (semicolon)
 - in classpath, [302](#)
 - in decimal formatting, [400](#)
 - in method signatures, [807](#)
 - in SQL, [303](#)
 - not needed, in annotations, [468](#)
- : (colon)
 - in classpath, [302](#)
 - in text files, [72](#)
 - in URLs, [260–261](#)
- [!= operator \(SQL\), 299](#)
- ? (question mark)
 - in DTDs, [178–180](#)

- in glob patterns, [127](#)
- in prepared queries, [319](#)
- in regular expressions, [144–145](#), [147](#)
- in URLs, [270](#)
- / (slash)
 - in method signatures, [807](#)
 - in paths, [64](#), [115](#)
 - in URLs, [260](#)
- . (period)
 - decimal, [388](#), [395](#), [402](#)
 - in method signatures, [807](#)
 - in regular expressions, [144–145](#), [156](#)
 - in URLs, [271](#)
- .., in paths, [116](#)
- ^ (caret), in regular expressions, [144–147](#), [156](#)
- ~ (tilde), in URLs, [271](#)
- ' (apostrophe), entity reference for, [164](#)
- ' . . . ', in SQL, [299](#)
- " . . . ", in XML, [162](#)
- (. . .) (parentheses)
 - in annotations, [477](#)
 - in method signatures, [807](#)
 - in regular expressions, [144–147](#), [151–154](#)
- [(array), type code, [96](#), [806](#)
- [. . .] (square brackets)
 - in DOCTYPE declaration, [177](#)
 - in glob patterns, [127](#)
 - in regular expressions, [144–146](#)
 - in XPath, [195](#)
- { . . . } (curly brackets)
 - in annotations, [478](#)
 - in glob patterns, [127](#)

in message formatting, 413–418
in regular expressions, 144–147, 155

@ (at)

in annotations, 468, 477
in java command-line options, 522
in URIs, 261
in XPath, 195
¤ (currency sign), 401
\$ (dollar sign), 403
in native method names, 787
in regular expressions, 144–145, 147, 155–157

€ (euro sign), 402, 419

* (asterisk)

in DTDs, 178–180
in glob patterns, 127
in regular expressions, 144–147, 152

\ (backslash)

in glob patterns, 127
in paths, 64, 115
in regular expressions, 144–145, 155, 157

\ \ |, in regular expressions, 73

& (ampersand)

in CDATA sections, 165
in entity references, 164
parsing, 179

&&, in regular expressions, 146

&#, &#x, in character references, 164

(number sign)

in decimal formatting, 400
in message formatting, 416–417
in URLs, 260

% (percent sign)

- in locales, 395
- in SQL, 299, 329
- in URLs, 271

+ (plus sign)

- in DTDs, 178–179
- in regular expressions, 144–147
- in URLs, 271
- operator, identity for, 42

< (left angle bracket)

- in CDATA sections, 165
- in message formatting, 417
- parsing, 179

<! -- . . . -->, <? . . . ?>, <! [CDATA[. . .]]>, in XML, 165

< . . . > (angle brackets), in regular expressions, 147

<> operator (SQL), 299

> (right angle bracket), in XML, 165

≤ operator, 417

= operator (SQL), 299

== operator, in enumerations, 105

| (vertical bar)

- in DTDs, 178–180
- in message formatting, 416
- in regular expressions, 144–146
- in text files, 72

\0, in regular expressions, 145

1931 CIE XYZ color specification, 734

2D graphics. *See Java 2D API*

A

\a, \A, in regular expressions, 145, 148

abort method (*LoginModule*), 562
absolute method (*ResultSet*), 333, 337
AbstractCellEditor class, 621–623
 isCellEditable method, 622
AbstractProcessor class, 488
AbstractTableModel class, 596
 getColumnName method, 597–598
 isCellEditable method, 619
accept method (*ServerSocket*), 244, 247–248
acceptChanges method (*CachedRowSet*), 340, 342
Accumulator functions, 42
Action listeners
 annotating, 469–475
 installing, 470
action.properties file, 461
ActionListener interface
 actionPerformed method, 452, 470
 @ActionListenerFor annotation, 469, 485
ActionListenerInstaller class
processAnnotations method, 470
add method
 of Area, 691–692
 of *AttributeSet*, 779, 783
 of DefaultMutableTreeNode, 633, 641
addActionListener method (*ButtonFrame*), 469–470
addAttribute method (*AttributesImpl*), 233
addBatch method (*Statement*), 355–356
addCellEditorListener method (*CellEditor*), 630
addColumn method (*JTable*), 608, 614
addRecipient method (*MimeMessage*), 288
addTreeModelListener method (*TreeModel*), 663, 671

addTreeSelectionListener method (`JTree`), [655](#)
addURLs method (`URLClassLoader`), [537](#)
Adleman, Leonard, [568, 587](#)
AES (Advanced Encryption Standard), [579](#)
 generating keys in, [580–585](#)
`aes/AESTest.java`, [582](#)
`aes/Util.java`, [583](#)
Affine transformations, [706, 740](#)
`AffineTransform` class, [706–709](#)
 constructor, [707–708](#)
 `getXxxInstance` methods, [706–709, 711](#)
 `setToXxx` methods, [707, 709](#)
`AffineTransformOp` class, [740](#)
 constructor, [747](#)
 `TYPE_XXX` fields, [741, 747](#)
`afterLast` method (`ResultSet`), [333, 337](#)
Agent code, [499–500](#)
Aliases, for namespaces, [185, 201](#)
`allMatch` method (`Stream`), [17](#)
`allocate` method (`ByteBuffer`), [138, 140](#)
Alpha channel, [712–716](#)
Alpha composites, [721](#)
`AlphaComposite` class, [715](#)
 `getInstance` method, [715, 721](#)
`&#;`, entity reference, [164](#)
Anchor rectangles, [702](#)
`andFilter` method (`RowFilter`), [607, 616](#)
`AnnotatedConstruct` interface, [489](#)
`AnnotatedElement` interface
 `getAnnotation` method, [470, 474, 488–489](#)
 `getAnnotations` method, [474](#)

`getAnnotationsByType` method, 474, 488–489
`getDeclaredAnnotations` method, 475
`isAnnotationPresent` method, 474

Annotation interface

extending, 475

methods of, 476

Annotation interfaces, 469, 475–476
predefined, 482–488

Annotation processors, 488–489
at bytecode level, 470, 493
at runtime, 470

Annotations, 467–475
applicability of, 484–485
documented, 485–486
elements of, 468, 476
evaluating, 478
for compilation, 483
for local variables, 480
for packages, 479
generating source code with, 490–493
inherited, 487
marker, 477
meta, 469, 483–488
never set to null, 478
no annotations for, 481

no circular dependencies in, 479
processing tools for, 467
repeatable, 488
retaining, 485
single value, 477
source-level, 488–493
standard, 482–488
syntax of, 475–482

transient, 486
vs. Javadoc comments, 468

ANY element content (DTD), 178

anyMatch method (*Stream*), 17

Apache, 159

- Commons CSV library, 519–520
- Derby, 302
 - connecting to, 305
 - drivers for, 302–304
 - populating, 315–318
 - starting, 303
- DOM parser, 166
- Tomcat, 359

Apollo 11, launch of, 366, 375

', entity reference, 164

append method

- of *Appendable*, 62–63
- of *Path2D*, 681, 691, 711

Appendable interface, 61–63

appendChild method (*Node*), 213, 215

Applets

- executing, 562, 577
- security mechanisms in, 533

Application servers, 359

Applications

- business logic vs. visual representation of, 294–295
- client/server, 295
- configuring, 160–161
- enterprise, 358–360
- executing:
 - loading classes for, 534
 - without a separate Java runtime, 530
- localizing, 421–423

monitoring, 499–500

paid, 541

server-side, 269–278

signing, 577

web, 358–360

applyPattern method (`MessageFormat`), 415

apply-templates element (`XSLT`), 225

`Arc2D` class, 674–675, 678

`Arc2D.Double` class, 675, 677, 690

`Arc2D.Float` class, 675, 677

`ArcMaker` class, 682

Arcs

bounding rectangles of, 675, 678

closure types of, 678

computing angles of, 678

Area class

add method, 691–692

exclusiveOr method, 692

intersect method, 692

subtract method, 692

ARGB (Alpha, Red, Green, Blue), 716, 735

ARRAY data type (`SQL`), 357–358

`ArrayIndexOutOfBoundsException`, 820

Arrays

converting to/from streams, 5, 26, 50

getting from a database, 358

in annotation elements, 478

in native code, 816–819

of primitive types, 818

of strings, 154

type code for, 96, 806

type use annotations in, 480

Arrays class
 stream method, 5, 9, 44

ArrayStoreException, 820

asCharBuffer method (ByteBuffer), 138

ASCII encoding, 76, 155
 in property files, 423
 native code and, 795

ASM library, 493–501

asMatchPredicate method (Pattern), 149

ASP (Active Server Pages), 269

asPredicate method (Pattern), 149

Associative operations, 42

Atomic operations, 121

ATTLIST declaration (DTD), 180

attribute element (XML Schema), 187

Attribute interface, 776
 getCategory method, 778, 783
 getName method, 783
 implementing, 778

Attribute sets, 778

Attributes (XML)
 enumerating, 170
 in XML Schema, 187
 legal, 180
 names of, 162
 namespace of, 201
 values of, 162
 accessing in XPath, 195
 copying with XSLT, 226
 default (DTDs), 181
 normalizing, 181

vs. elements, 163–164, 181, 223

Attributes interface
 getXxx methods, 208

AttributeSet interface, 777
 add method, 779, 783
 get method, 779, 783
 remove method, 784
 toArray method, 784

AttributesImpl class
 addAttribute method, 233
 clear method, 233

atZone method (`LocalDateTime`), 375

auth/AuthTest.java, 551

auth/jaas.config, 552

Authentication, 549–562, 572–574
 role-based, 553
 through a trusted intermediary, 572–573

Autoboxing, 593

AutoCloseable interface
 close method, 62

Autocommit mode (databases), 353–355

Autoflushing, 69

Auxiliary files, generated, 467
 available method (`InputStream`), 57–58
 availableCharsets method (`Charset`), 77
 average method (primitive streams), 44, 46–47
 averagingXxx methods (`Collectors`), 36

AWT (Abstract Window Toolkit), 671–721

B

B (`byte`), type code, 96, 806
\b, \B, in regular expressions, 148

Banding, 751

Banner class

- getPageCount method, 760
- layoutPages method, 760

Banners, printing, 759–769

BASE64Encoder class, 510

BaseStream interface

- iterator method, 29
- parallel method, 53
- unordered method, 53

BasicFileAttributes interface, 123

- methods of, 124

BasicStroke class, 693–701

- constructor, 701

Batch updates (databases), 354–357

BCP 47 memo, 390, 393

Bean info classes, generated, 467

beforeFirst method (*ResultSet*), 333, 337

between method (*Duration*), 363, 365

Bevel join, 694

Bézier curves, 680

Bicubic, bilinear interpolations, 741, 747

BIG_ENDIAN constant (*ByteOrder*), 138

Big5 encoding, 418, 421

BigDecimal class, 103

Big-endian order, 76, 79, 420

Binary data

- converting to Unicode code units, 68
- reading/writing, 78–79
- vs. text, 68

Bindings interface, 446

get, put methods, [447](#)
Birthdays, calculating, [367](#)
BitSet interface, [43](#)
BLOB data type (SQL), [301](#), [357](#)
Blob interface, [326](#)
 getBinaryStream method, [326–327](#)
 getBytes method, [326–327](#)
 length method, [327](#)
 setBinaryStream method, [327](#)
BLOBs (binary large objects), [326](#)
 creating empty, [328](#)
 placing in database, [326](#)
Blocking
 by I/O methods, [57](#)
 by network connections, [236](#), [240](#), [252–259](#)
Blur filter, [742](#)
BMP format, [722](#)
body method (`HttpResponse`), [280](#), [286](#)
BodyHandlers class
 discarding method, [281](#)
 ofString method, [280–281](#)
BodyPublishers class
 ofString method, [280](#)
Book class, [759](#)
book/Banner.java, [763](#)
book/BookTestFrame.java, [761](#)
book/PrintPreviewCanvas.java, [767](#)
book/PrintPreviewDialog.java, [766](#)
BOOLEAN data type (SQL), [301](#), [357](#)
boolean type
 printing, [69](#)

streams of, 43–49
type code for, 96, 806
vs. C types, 793
writing in binary format, 78

Bootstrap class loader, 535–536

Bounding rectangles, 675

boxed method (primitive streams), 44, 46–47

Bray, Tim, 161

Breadth-first enumerations, 649–650

breadthFirstEnumeration method
(DefaultMutableTreeNode), 649, 654

Browsers

- forms in, 269–278
- response pages in, 269

Buffer class, 139–141

- capacity method, 141
- clear method, 140
- flip method, 140
- hasRemaining method, 137
- limit method, 137
- mark method, 140–141
- position method, 141
- remaining method, 140–141
- reset method, 140–141
- rewind method, 140–141

BufferedImage class, 702, 732

- constructor, 733, 738
- getColorModel method, 735, 738
- getRaster method, 733, 738
- TYPE_BYTE_GRAY field, 736, 738
- TYPE_BYTE_INDEXED field, 738
- TYPE_INT_ARGB field, 733–734, 738

BufferedImageOp interface, 732
 filter method, 740, 747
 implementing, 740

BufferedReader class
 lines method, 72
 readLine method, 71

BufferedXxxStream classes, 67

Buffers, 139–141
 capacity of, 139
 flushing, 57, 69
 in-memory, 62
 limits of, 139
 marks in, 139
 positions in, 132, 139
 traversing all bytes in, 132
 vs. random access, 131

BufferUnderflowException, 137

@BugReport annotation, 486

build method
 of HttpClient.Builder, 279–280, 285
 of HttpRequest.Builder, 286

Bundle classes, 424–426

Butt cap, 693

ButtonFrame class, 451
 addActionListener method, 469–470

buttons1/ButtonFrame.java, 455

buttons2/action.properties, 465

buttons2/ButtonFrame.java, 464

buttons3/ButtonFrame.java, 473

Byte order mark, 76, 420

byte type
 streams of, 43–49

type code for, 96, 806
vs. C types, 793

BYTE_ARRAY class (DocFlavor), 770

ByteArrayClass class, 459

ByteArrayClassLoader class, 460

ByteArrayOutputStream class, 110

ByteBuffer class, 132, 139–141

- allocate method, 138, 140
- asCharBuffer method, 138
- get, getXxx methods, 133, 137–138
- order method, 133, 138
- put, putXxx methods, 133, 137–138
- wrap method, 138, 140

bytecodeAnnotations/EntryLogger.java, 495

bytecodeAnnotations/EntryLoggingAgent.java, 500

Bytecodes

- engineering, 493–501
 - at load time, 499–500
 - with hex editor, 548
- verifying, 545–549
- writing to memory, 459–460

ByteLookupTable class, 742

- constructor, 748

ByteOrder class

- BIG_ENDIAN, LITTLE_ENDIAN constants, 138

Byte-oriented input/output streams, 56

Bytes, reading/writing, 56–59

C

C (char), type code, 96, 806

C programming language

array types in, 816–819
calling:
 from Java programs, 786–792
 Java methods from, 809–815
database access in, 292
embedding JVM into, 825–830
`FILE*` type in, 59
pointers in, 786
strings in, 795
types, vs. Java types, 793
`\c`, in regular expressions, 145
C++ programming language
 accessing JNI functions in, 796
 array types in, 816
 embedding JVM into, 825–830
 exceptions in, 820
 for native methods, 786, 789
 pointers in, 786, 811
Cached row sets, 339–344
CachedRowSet interface, 339–342
 `acceptChanges` method, 340, 342
 `execute` method, 340, 342
 `getPageSize` method, 340, 342
 `getTableName` method, 341–342
 `nextPage` method, 340, 342
 `populate` method, 339, 342
 `previousPage` method, 342
 `setPageSize` method, 340, 342
 `setTableName` method, 341–342
CachedRowSetImpl class, 510
Caesar cipher, 539–544
Calendar class, 361
 formatting objects of, 404

weekends in, 368

call escape (SQL), 329

call method (*CompilationTask*), 458, 466

Callable interface, 458

Callback interface, 554

CallbackHandler interface

handle method, 561

CallNonvirtualXxxMethod functions (C), 811, 815

CallStaticXxxMethod functions (C), 810, 815

CallXxxMethod functions (C), 809, 814–815

cancelCellEditing method (*CellEditor*), 622–623, 630

cancelRowUpdates method (*ResultSet*), 335, 338

canInsertImage method (*ImageWriter*), 725, 732

capacity method (*Buffer*), 141

Carriage return character, displaying, 170

Casts, type use annotations in, 480

catalog element (XML), 177

CatalogFeatures class

 defaults method, 178, 184

CatalogManager class

 catalogResolver method, 178, 184

Catalogs, 352

CDATA declaration (DTD), 180–181

CDATA sections (XML), 165

Cell editors (Swing), 619–623

Cell renderers (Swing)

 for tables, 600, 617–619

 for trees, 651–654

CellEditor interface

 add/removeCellEditorListener methods, 630

 cancelCellEditing method, 622–623, 630

`getCellEditorValue` method, 620, 622–623, 630
`isCellEditable` method, 630
`shouldSelectCell` method, 622–623, 630
`stopCellEditing` method, 622–623, 630

Cells (Swing)

editing, 619–630
selecting, 604

Certificates, 550, 569–571

for software developers, 577
Java Plug-in and, 577
managing, 575–576
publishing fingerprints of, 570
signing, 574–576

CertificateSigner class, 575

CGI (Common Gateway Interface), 269

Chain of trust, 574

Channels, 253

for files, 132

Channels class

`newInputStream` method, 259
`newOutputStream` method, 253, 259

char type

streams of, 43–49
type code for, 96, 806
vs. C types, 793

CHAR_ARRAY class (DocFlavor), 770

Character classes, 144

CHARACTER data type (SQL), 301, 357

Character encodings, 68, 75–78

character order in, 407
explicitly specified, 77
of source files, 420–421

partial, 77
platform, 77–78, 418

Character references (XML), 164

CharacterData interface
 getData method, 169, 175

Characters
 differences between, 408
 escaping, 73
 normalizing, 409
 outlines of, 710
 printing, 69
 writing in binary format, 78

characters method (ContentHandler), 203, 208

CharBuffer class, 62, 139
 get method, 138
 put method, 139

CharSequence interface, 62
 charAt method, 63
 chars method, 44
 codePoints method, 44, 48
 length method, 63
 splitting, 6
 subSequence method, 63
 toString method, 63

Charset class
 availableCharsets method, 77
 defaultCharset method, 77, 419
 forName method, 77

Checkboxes (Swing), 617

checked attribute (HTML, XML), 162

Checker framework, 480

checkError method (PrintWriter), 69–70

Child elements (XML), [163](#)
namespace of, [200](#)

Child nodes (Swing), [630](#)
adding, [633](#)
connecting lines for, [636–637](#)
children method (*TreeNode*), [649](#)

choice element (XML Schema), [187](#)

choice keyword (message formatting), [416](#)

Church, Alonzo, [366](#)

Cipher class, [579–580](#)
doFinal method, [580, 582, 585–586](#)
getInstance method, [579, 584](#)
getXxxSize methods, [584](#)
init method, [584](#)
update method, [579, 582, 585–586](#)
XXX_MODE modes, [579](#)

CipherInputStream class
read method, [586](#)

CipherOutputStream class, [585](#)
constructor, [586](#)
flush method, [586](#)
write method, [586](#)

Ciphers
Caesar, [539–544](#)
keys for:
generating, [580–585](#)
public, [566–573, 587–590](#)
performance of, [587](#)
streams for, [585–586](#)
symmetric, [579–580, 587](#)

Class class
forName method, [460](#)

`getClassLoader` method, 535, 544
`getFields` method, 665
`getResourceAsStream` method, 517
implementing *AnnotatedElement*, 470
.class file extension, 534
Class files, 534
 corrupted, 546–548
 encrypted, 539–545
 format of, 493
 loading, 534–535
 modifying, 493–499
 portability of, 420
 transformers for, 500
 verifying, 545–549
Class loaders, 461, 534–549
 as namespaces, 538–539
 bootstrap, 535–536
 context, 537
 extension, 535
 hierarchy of, 536–538
 separate for each web page, 539
 specifying, 537
 system, 535
 writing, 539–545
Class path, adding JAR files to, 537
Class references, in native code, 803
Classes
 adding validation to, 101
 annotating, 468, 479, 483
 compiling on the fly, 459
 encapsulation of, 504
 externalizable, 96
 inheritance trees of, 650

loading, 460
nonserializable, 101
platform, 535
resolving, 534
separate for each web page, 539
serializable, 89, 109
 deserializing, 113–114
static inner, 92
versioning, 107–110

Classifier functions, 35

ClassLoader class, 535
 defineClass method, 539, 544–545
 extending, 460, 539
 findClass method, 539, 544
 getParent method, 544
 getSystemClassLoader method, 544
 loadClass method, 537, 539

Classloader inversion, 537
 classLoader/Caesar.java, 543
 classLoader/ClassLoaderTest.java, 541
CLASSPATH environment variable, 535

CLEAR composition rule, 714

clear method
 of AttributesImpl, 233
 of Buffer, 140

clearParameters method (*PreparedStatement*), 325

client/HttpClientTest.java, 282

Client/server applications, 295

Clients
 connecting to servers, 238–240
 multiple, serving, 247–251

CLinker interface, 847

clip method (`Graphics2D`), [672](#), [710–712](#), [752](#)

Clipping shapes, [672](#), [710–712](#)

printing, [752](#)

setting region for, [672](#)

CLOB data type (SQL), [301](#), [357](#)

Clob interface, [326](#)

getCharacterStream method, [326–327](#)

getSubString method, [326–327](#)

length method, [327](#)

setCharacterStream method, [327](#)

CLOBs (character large objects), [326](#)

creating empty, [328](#)

placing in database, [326](#)

clone method (`Object`), [89](#), [110](#)

Cloning, [110–113](#)

close method

of `AutoCloseable`, [62](#)

of `Closeable`, [61–63](#)

of `Connection`, [309](#), [312](#), [360](#)

of `FileLock`, [143](#)

of `Flushable`, [61](#)

of `InputStream`, [57–58](#)

of `OutputStream`, [59](#)

of `ResultSet`, [311–312](#)

of `ServerSocket`, [247](#)

of `Statement`, [310](#), [312](#)

of `XMLStreamWriter`, [222](#)

`Closeable` interface, [61](#)

close method, [61–63](#)

flush method, [61](#)

closeEntry method (`ZipXxxStream`), [85–87](#)

closeOnCompletion method (`Statement`), [310](#), [312](#)

closePath method (`Path2D`), [680](#), [691](#)
Closure types, [678](#)
cmd shell, [419](#)
Code generation, annotated, [467–475](#), [484](#)
Code points, [11](#)
Code units, [44](#)

- in regular expressions, [145](#)
- writing, [82](#)

Codebreakers, The (Kahn), [540](#)
`codePoints` method (`CharSequence`), [44](#), [48](#)
Collation, [407–413](#)
`collation/CollationTest2.java`, [410](#)
CollationKey class

- `compareTo` method, [413](#)

Collator class, [408](#)

- `compare` method, [412](#)
- `equals` method, [412](#)
- get/setDecomposition methods, [413](#)
- get/setStrength methods, [412](#)
- `getAvailableLocales` method, [412](#)
- `getCollationKey` method, [410](#), [413](#)
- `getInstance` method, [412](#)

collect method (`Stream`), [26–29](#), [43](#)
`collecting/CollectingIntoMaps.java`, [32](#)
`collecting/CollectingResults.java`, [27](#)
`collecting/DownstreamCollectors.java`, [38](#)
collectingAndThen method (`Collectors`), [37](#), [40](#)
Collection interface

- `parallelStream` method, [2–4](#), [49–53](#)
- `stream` method, [2–4](#)

Collections

iterating over elements of, 2–4

vs. streams, 3

Collections class

sort method, 408

Collector interface, 26

Collectors, 26–41

composing, 38

downstream, 36–41, 50

Collectors class

averagingXxx methods, 36

collectingAndThen method, 37, 40

counting method, 36, 40

filtering method, 38, 41

flatMapting method, 37, 41

groupingBy method, 35–40

groupingByConcurrent method, 35–36, 50

joining method, 27, 30

mapping method, 37, 41

maxBy, minBy methods, 37, 40

partitioningBy method, 35–36, 38

reducing method, 38

summarizingXxx methods, 27, 30, 37

summingXxx methods, 36, 40

teeing method, 38

toCollection method, 27, 30

toConcurrentMap method, 32, 34

toList method, 26, 30

toMap method, 31–34

toSet method, 26, 30, 36

toUnmodifiableList method, 30

toUnmodifiableMap method, 34

toUnmodifiableSet method, 30

Color choosers, 621
Color class, 701
 constructor, 740
 getRGB method, 740
 translating values into pixel data, 736
Color space conversions, 742
ColorConvertOp class, 740, 742
ColorModel class, 736
 getDataElements method, 739
 getRGB method, 735, 739
Colors
 components of, 712
 composing, 713–716
 interpolating, 701–702
 negating, 741
 solid, 672
Columns (databases)
 accessing by number, in result set, 309
 names of, 295
 number of, 344
Columns (Swing)
 accessing, 601–602
 adding, 608
 detached, 593
 hiding, 608
 names of, 597–598
 rendering, 600
 resizing, 593–594, 602–603
 selecting, 604
com.sun.security.auth.module package, 550–551
Combo box editors, 620
Comments (XML), 165
commit method

of *Connection*, 354–356
of *LoginModule*, 562
commonPool method (`ForkJoinPool`), 51
Commons CSV library, 519–520
Comparable interface, 15
 `compareTo` method, 606
Comparator interface, 15, 408
Comparators, 606
compare method (`Collator`), 412
`compareTo` method
 of `CollationKey`, 413
 of *Comparable*, 606
 of `Instant`, 363
 of `String`, 407
Compilable interface, 450–451
 `compile` method, 451
CompilationTask interface, 457
 `call` method, 458, 466
compile method
 of *Compilable*, 451
 of *Pattern*, 149, 155–156
CompiledScript interface
 `eval` method, 451
Compiler
 annotations for, 483
 invoking, 457
 just-in-time, 825
`compiler/CompilerTest.java`, 462
Complex types, 185
`complexType` element (XML Schema), 186
Composite interface, 715

composite/CompositeComponent.java, 718
composite/CompositeTestFrame.java, 717
composite/Rule.java, 720
Composition rules, 672–673, 712–721
Computer Graphics: Principles and Practice (Hughes et al.), 680, 734
concat method (*Stream*), 14
Confidential information, 578
Configuration files, 114, 141
connect method
 of Socket, 241
 of URLConnection, 262, 264, 268
Connection interface
 close method, 309, 312, 360
 commit method, 354–356
 createBlob, createClob methods, 326, 328
 createStatement method, 308–309, 331–332, 334, 336, 354
 getAutoCommit method, 355–356
 getMetaData method, 343, 352
 getWarnings method, 314
 prepareStatement method, 319–320, 325, 331, 336
 releaseSavepoint method, 354, 356
 rollback method, 354–356
 setAutoCommit method, 353, 355–356
 setSavepoint method, 356
Connections (databases)
 closing, 312
 using row sets after, 339
 debugging, 288
 pooling, 359
 starting new threads, 248
console method (System), 419
Constructive area geometry, 691

`Constructor` class, 470

Constructors

annotating, 479

bypassing, 113–114

invoking from native code, 811

no-argument, 101, 113

type use annotations in, 480

Content types, 262

`ContentHandler` class, 203–204

`characters` method, 203, 208

`startDocument`, `endDocument` methods, 203, 207

`startElement`, `endElement` methods, 203–208

Context class loader, 537

Control points

 dragging, 682

 of curves, 679–680

 of shapes, 681

`convertXxxIndexToModel` methods (`JTable`), 604, 614

Convolution operation, 742

`ConvolveOp` class, 740, 742–743

 constructor, 748

`CookieHandler` class

`setDefault` method, 274

Cookies, 274

Coordinate system

 custom, 673

 translating, 752

Coordinate transformations, 703–709

`Copies` class, 776–779

`getValue` method, 779

`CopiesSupported` class, 776

copy method (`Files`), 120–122, 130

CORBA (Common Object Request Broker Architecture), [504](#), [535](#)
Core Swing (Topley), [592](#), [630](#), [643](#)
count function (XPath), [195](#)
count method (*Stream*), [3–4](#), [16](#)
counting method (Collectors), [36](#), [40](#)
Country codes, [35](#), [390](#)
CRC32 checksum, [88](#), [131](#), [133](#)
CRC32 class, [133](#)
CREATE TABLE statement (SQL), [300](#)
executing, [308](#), [310](#), [326](#)
in batch updates, [355](#)
createBindings method (*ScriptEngine*), [447](#)
createBlob, createClob methods (*Connection*), [326](#), [328](#)
createCachedRowSet method (*RowSetFactory*), [339–340](#), [342](#)
createDirectory, createDirectories methods (*Files*), [119–120](#)
createElement, createElementNS methods (*Document*), [213](#), [215](#)
createFile method (*Files*), [119–120](#)
createFilteredRowSet method (*RowSetFactory*), [342](#)
createImageXxxStream methods (*ImageIO*), [724](#), [730](#)
createJdbcRowSet, createJoinRowSet methods
(*RowSetFactory*), [342](#)
createLSOutput method (*DOMImplementationLS*), [215](#)
createLSSerializer method (*DOMImplementationLS*), [214](#)
createPrintJob method (*PrintService*), [771–772](#)
createStatement method (*Connection*), [308–309](#), [331–332](#), [334](#),
[336](#), [354](#)
createTempXxx methods (*Files*), [120](#)
createTextNode method (*Document*), [213](#), [215](#)
createWebRowSet method (*RowSetFactory*), [342](#)

`createXMLStreamReader` method (`XMLInputFactory`), [211](#)
`createXMLStreamWriter` method (`XMLOutputFactory`), [217](#), [221](#)
`creationTime` method (*BasicFileAttributes*), [124](#)
Credit card numbers, [578](#)
`crypt` program, [582](#)
Cryptography and Network Security (Stallings), [564](#)
CSV files, [519–520](#)
Cubic curves, [679–680](#)
`CubicCurve2D` class, [674](#), [680](#)
`CubicCurve2D.Double` class, [675](#), [677](#), [690](#)
`CubicCurve2D.Float` class, [675](#), [677](#)
Currencies, [402–403](#)

- available, [403](#)
- formatting, [401](#)
- identifiers for, [402](#)

`Currency` class, [402–403](#)

- `getAvailableCurrencies` method, [403](#)
- `getCurrencyCode` method, [403](#)
- `getDefaultFractionDigits` method, [403](#)
- `getInstance` method, [402–403](#)
- `getNumericXxx` methods, [403](#)
- `getSymbol` method, [403](#)
- `toString` method, [403](#)

`curveTo` method (`Path2D.Float`), [680](#), [691](#)
Cyclic references, [113](#)
Cygwin, [790](#)

- compiling invocation API, [830](#)
- OpenSSL in, [576](#)

D

D (`double`), type code, [96](#), [806](#)
d literal (SQL), [328](#)
`\d`, `\D`, in regular expressions, [146](#)
Dashed lines, [694–695](#)
Data
 encrypting/decrypting, [585](#)
 fingerprints of, [563–566](#)
 signed, [566–569](#)
Data sources (for JNDI service), [359](#)
Data types
 codes for, [96](#), [806](#)
 in Java vs. C, [793](#)
 mangling names of, [806](#)
 print services for, [769–770](#)
`database.properties` file, [315](#), [358](#)
DatabaseMetaData interface, [343–353](#)
 `getJDBCXxxVersion` methods, [352](#)
 `getMaxConnection` method, [352](#)
 `getMaxStatements` method, [311](#), [352](#)
 `getSQLStateType` method, [312](#)
 `getTables` method, [343](#), [352](#)
 `supportsBatchUpdates` method, [355](#), [357](#)
 `supportsResultSetXxx` methods, [332](#), [338](#)
Databases, [291–360](#)
 accessing, in C language, [292](#)
 autocommit mode of, [353–355](#)
 batch updates for, [354–357](#)
 caching prepared statements, [320](#)
 changing data with SQL, [300](#)
 connections to, [302](#), [304–307](#), [316](#)
 closing, [312](#), [316](#)
 in web and enterprise applications, [358–360](#)
 pooling, [359](#)

drivers for, 293–294
duplicating data in, 297
error handling in, 355
escape syntax in, 328–329
integrity of, 353
JAR files for, 302
keys in, 330–331
LOBs in, 326–328
metadata for, 343–353
modifying, 339
native storage for XML in, 358
numbering columns in, 309
outer joins in, 328
populating, 315–318
registering classes for, 304
saving objects to, 487
scalar functions in, 328
schemas for, 352
scrollable/updatable result sets in, 332
setting up parameters in, 340
starting, 303
stored procedures in, 329
structure of, 295, 343
synchronization of, 341
tools for, 345
truncated data from, 313
URLs of, 302

`DataFlavor` class, 505

DataInput interface

- `readBoolean` method, 79–80
- `readChar` method, 79–81
- `readDouble` method, 79–80, 90, 102
- `readFloat` method, 79–80
- `readFully` method, 80

readInt method, 79–81, 90
readLong method, 79–80
readShort method, 79–80
readUTF method, 79–80
skipBytes method, 80
DataInputStream class, 60, 65, 79
DataIO class
 xxxFixedString methods, 82
DataOutput interface, 78
 writeBoolean method, 78, 80
 writeByte method, 78, 80
 writeChar method, 78, 80–81
 writeChars method, 78–80
 writeDouble method, 78, 80, 90, 102
 writeFloat method, 78, 80
 writeInt method, 78, 80–81, 90
 writeLong method, 78, 80
 writeShort method, 78, 80
 writeUTF method, 78–80
DataOutputStream class, 60, 79
DataSource interface, 359
DataTruncation class, 313
 getXxx methods, 314
Date and Time API, 361–385
 legacy code and, 384–385
Date class (`java.sql`), 384
 valueOf method, 385
Date class (`java.util`), 96, 103, 361, 384
 formatting objects of, 404
 months and years in, 367
 toInstant method, 384–385
DATE data type (SQL), 301, 328, 357

dateFilter method (`RowFilter`), [607](#), [616](#)
DateFormat class, [381](#), [385](#), [405](#)
`dateFormat/DateTimeFormatTest2.java`, [406](#)
DateFormatter class (`java.text`), [404](#)

Dates

- computing, [367](#), [372–373](#)
- filtering, [607](#)
- formatting, [379–384](#), [388–389](#), [403–407](#), [413–415](#)
- literals for, [328](#)
- local, [366–371](#)
- nonexistent, [404](#)
- parsing, [381](#)

`datesUntil` method (`LocalDate`), [368](#), [371](#)
DateTimeFormatter class, [379–384](#), [403–407](#)

- format method, [379](#), [383](#), [407](#)
- legacy classes and, [384–385](#)
- `ofLocalizedXxx` methods, [380](#), [383](#), [403](#), [407](#)
- `ofPattern` method, [381](#), [384](#)
- parse method, [381](#)
- `toFormat` method, [381](#), [385](#)
- withLocale method, [380](#), [384](#), [404](#), [407](#)

`DateTimeParseException`, [407](#)
DateTimeSyntax class, [779](#)
Daylight savings time, [375–379](#)
DayOfWeek enumeration, [368](#)

- getDisplayName method, [381](#), [405](#)

dayOfWeekInMonth method (`TemporalAdjusters`), [373](#)

Days of week, [405](#)

DBeaver program, [345](#)

DDL statement (SQL), [310](#), [326](#)

Debugging

- in JNI, [826](#)

JDBC-related problems, 306
locales, 394
mail connections, 288
streams, 15
with telnet, 235–238

DECIMAL data type (SQL), 301, 357

Decimal separators, 388, 395, 402

DecimalFormat class, 399–402

DecimalFormatSymbols class, 401

Declaration annotations, 479–481

decode method (URLDecoder), 278

Decomposition, 409

default statement, 475

DefaultCellEditor class, 645

- constructor, 629
- variations of, 619

defaultCharset method (Charset), 77, 419

DefaultHandler class, 204

DefaultMutableTreeNode class, 632, 649–651, 653

- add method, 633, 641
- constructor, 641
- pathFromAncestorEnumeration method, 650
- setAllowsChildren method, 639, 641
- xxxFirstEnumeration methods, 649, 654
- xxxOrderEnumeration methods, 650, 654

defaultPage method (PrinterJob), 758

DefaultRowSorter class

- setComparator method, 606, 615
- setRowFilter method, 606–608, 615
- setSortable method, 605, 615

defaults method (CatalogFeatures), 178, 184

DefaultTableCellRenderer class, 618

`DefaultTableModel` class
 `isCellEditable` method, [619](#)
`DefaultTreeCellRenderer` class, [651–654](#)
 `getTreeCellRendererComponent` method, [652–653](#)
 `setXxxIcon` methods, [652, 654](#)
`DefaultTreeModel` class, [632, 642, 664](#)
 automatic notifications by, [643](#)
 `getPathToRoot` method, [644](#)
 `insertNodeInto` method, [643, 649](#)
 `isLeaf` method, [639](#)
 `nodeChanged` method, [643, 649](#)
 `nodesChanged` method, [649](#)
 `reload` method, [643, 649](#)
 `removeNodeFromParent` method, [643, 649](#)
 `setAsksAllowsChildren` method, [639, 641](#)
`defaultWriteObject` method (`ObjectOutputStream`), [102](#)
`defineClass` method (`ClassLoader`), [539, 544–545](#)
`delete` method (`Files`), [121–122](#)
`DELETE` method (`HttpRequest.Builder`), [286](#)
`DELETE` statement (SQL), [300](#)
 executing, [308, 310, 326](#)
 in batch updates, [355](#)
 vs. methods of `ResultSet`, [335](#)
`DeleteGlobalRef` function (C), [803](#)
`deleteIfExists` method (`Files`), [121–122](#)
`deleteRow` method (`ResultSet`), [335, 337](#)
`Delimiters`, in text files, [72](#)
`@Deprecated` annotation, [483](#)
`Depth-first enumerations`, [649–650](#)
 `depthFirstEnumeration` method
 (`DefaultMutableTreeNode`), [649, 654](#)
`Derby` databases. *See* [Apache, Derby](#)

`derbyclient.jar` file, 302
DES (Data Encryption Standard), 579
Deserialization, 113–114
DestroyJavaVM function (C), 826, 830
Device coordinates, 704
Diagnostic interface, 458
 `getXxx` methods, 466
DiagnosticCollector class, 458
 constructor, 466
 `getDiagnostics` method, 466
DiagnosticListener interface, 458
DialogCallbackHandler class, 554
Dictionary ordering, 408
 `digest` method (`MessageDigest`), 565–566
DigiCert, 570, 574
Digital fingerprints, 95–100, 563–566
 computing, 108
 different for a class and its objects, 98
Digital signatures, 562–577
 verifying, 569–571
Direct buffers, 818
Directories
 creating, 119–120
 current, 129
 hierarchical structure of, 630
 printing all subdirectories of, 128
 traversing, 124–129
 user’s working, 64
DirectoryStream interface, 126
discarding method (`BodyHandlers`), 281
distinct method (`Stream`), 15–16, 50
dividedBy method (`Duration`), 366

Doc interface, 771
DocAttribute interface, 776
 implementing, 778
 printing attributes of, 780–783
DocAttributeSet interface, 777–778
DocFlavor class, 769–770, 772
DocPrintJob interface
 getAttributes method, 784
 print method, 772
DOCTYPE declaration (DTD), 177
 including in output, 214
Document interface, 166
 createXxx methods, 213, 215
 getDocumentElement method, 166, 174
Document flavors, for print services, 769–770
DocumentBuilder class
 newDocument method, 213, 215, 228
 parse method, 173
 setEntityResolver method, 178, 183
 setErrorHandler method, 183
DocumentBuilderFactory class
 isIgnoringElementContentWhitespace method, 185
 isNamespaceAware method, 202
 isValidating method, 185
 newDocumentBuilder method, 166, 173, 213
 newInstance method, 166, 173, 201
 newNSInstance method, 201–202, 205
 setIgnoringElementContentWhitespace method, 182, 185
 setNamespaceAware method, 188, 201–202, 205, 213
 setValidating method, 182, 185
@Documented annotation, 483, 485–486
doFinal method (*Cipher*), 580, 582, 585–586

DOM (Document Object Model) parser, 165–166, 203

namespace-awareness of, 201, 205

trees in:

accessing with XPath, 194–199

analyzing, 168–170

building, 203, 212–223, 228

writing, 214–216

`dom/JSONConverter.java`, 170

DOMImplementationLS interface

`createLSOutput` method, 215

`createLSSerializer` method, 214

`DOMResult` class, 228, 233

`DOMSource` class, 216, 227

`DOUBLE` data type (SQL), 301, 357

`double` type

printing, 69

streams of, 43–49

type code for, 96, 806

vs. C types, 793

writing in binary format, 78

`DoubleBuffer` class, 139

`doubles` method

of `Random`, 45

of `RandomGenerator`, 48

of `SplittableRandom`, 52

DoubleStream interface, 43–49

average method, 44, 47

boxed method, 44, 47

`mapToDouble` method, 44

max, min methods, 44, 47

`of` method, 47

sum, `summaryStatistics` methods, 44, 47

toArray method, 44, 47
DoubleSummaryStatistics class, 27, 30–31, 44, 49
doubleValue method (Number), 396
Downstream collectors, 36–41, 50
draw method (Graphics2D), 673–675, 692–693
Drawings
 creating, 671–721
 printing, 749–759
drawXxx methods (Graphics), 674
DriverManager class, 304
 getConnection method, 305, 307, 316, 360
 setLogWriter method, 306
DROP TABLE statement (SQL), 305
 executing, 308, 310
 in batch updates, 355
dropWhile method (*Stream*), 14
DSA (Digital Signature Algorithm), 567–568
DST, DST_Xxx composition rules, 714
DTDHandler class, 204
DTDs (Document Type Definitions), 176–185
 element content in, 178–179
 entities in, 181
 external, 177
 in XML documents, 162, 176–185
 locating, 177–178
 unambiguous, 180
 URLs for, 177
Duration class
 between method, 363, 365
 dividedBy method, 366
 getSeconds method, 363
 immutability of, 363

`isNegative`, `isZero` methods, 366
`multipliedBy` method, 366
`negated` method, 366
`ofXxx` methods, 365
`toXxx` methods, 363, 365–366
Dynamic links, 826
Dynamic web pages, 461–467

E

\e, \E, in regular expressions, 145
Echo servers, 246–247
Eclipse
 IDE, 513
 Yasson framework, 518
Edge detection, 743
`element` element (XML Schema), 186
`ELEMENT` element content (DTD), 178–179
Element interface, 166, 489
 `getAttribute` method, 170, 174
 `getSimpleNamespace` method, 489
 `getTagName` method, 167, 174, 202
 `setAttribute`, `setAttributeNS` methods, 213–215
Elements (XML)
 `child`, 163
 accessing in XPath, 195
 namespace of, 200
 constructing, 213
 counting, in XPath, 195
 empty, 162
 legal attributes of, 180
 mixed content in, 163, 179
 names of, 167, 202

root, [163](#), [185](#)
trimming whitespace in, [169](#)
vs. attributes, [163–164](#), [181](#), [223](#)

`Ellipse2D` class, [674–675](#)

`Ellipse2D.Double`, `Ellipse2D.Float` classes, [675](#), [677](#)

`Ellipses`, [675](#)

E-mails
 sending, [287–290](#)
 terminating lines in, [287](#)

`employee/Employee.c`, [805](#)
`employee/Employee.java`, [804](#)
`employee/EmployeeTest.java`, [804](#)

EMPTY element content (DTD), [178](#)

`empty` method
 of `Optional`, [21–22](#)
 of `Stream`, [5](#), [9](#)

Empty tags (XML), [162](#)

Encapsulation, [504](#)
 compile-time, [522](#)

`encode` method (`URLEncoder`), [278](#)

Encodings. *See* [Character encodings](#)

Encryption, [578–590](#)
 decryption keys for, [540](#)
 exporting strong methods of, [540](#)
 final block padding in, [580](#)
 of class files, [539–545](#)

`end` method
 of `Matcher`, [157](#)
 of `MatchResult`, [158](#)

End cap styles, [693–695](#)

End points, [679](#)

End tags (XML), [162](#)

endDocument method (ContentHandler), 203, 207
endElement method (ContentHandler), 203–208
End-of-line character. *See* [Line feed](#)
Enterprise applications, 358–360
Enterprise JavaBeans (EJBs), 295
Entity references (XML), 164, 181
Entity resolvers, 166, 177
ENTITY, ENTITIES attribute types (DTDs), 180–181
EntityResolver interface, 184, 204
 resolveEntity method, 177, 183
entries method (ZipFile), 88
Entrust, 574
Entry class, 607
 getXxx methods, 616–617
EntryLogger class, 500
EntryLoggingAgent.mf file, 499
enum keyword, 104
enumeration element (XML Schema), 186
Enumeration interface, 88
 hasMoreElements method, 832–835
 nextElement method, 649, 832–835
Enumerations
 customizing serialization of, 104
 ignoring serialVersionUID fields, 110
 of nodes, in a tree, 649–651
 typesafe, 104–107
 using attributes for, 181
EnumSyntax class, 779
EOFException, 820
Epoch, 103, 362
equals method

of *Annotation*, 476
of *Collator*, 412
of *Instant*, 363
`error` method (*ErrorHandler*), 183–184
Error handlers
 in native code, 819–825
 installing, 183
ErrorHandler class, 204
 `error`, `fatalError` methods, 183–184
 `warning` method, 183–184
Errors
 `OutOfMemoryError`, 821
 `UnsatisfiedLinkError`, 787
Escape hatch mechanism, 641
escape keyword (SQL), 329
Escapes
 in regular expressions, 73
 in SQL, 328–329
Essential XML (Box et al.), 159, 224
Euro symbol, 402, 419
`eval` method
 of *CompiledScript*, 451
 of *ScriptEngine*, 445–447
`evaluate`, `evaluateExpression` methods (*XPath*), 195–196, 199
Event handlers, annotating, 469–475
Event listeners, 468
EventHandler class, 471
EventListenerList class, 664
Evins, Jim, 600
evn pointer (C), 796
Exceptions
 `ArrayIndexOutOfBoundsException`, 820

ArrayStoreException, 820
BufferUnderflowException, 137
DateTimeParseException, 407
EOFException, 820
FileNotFoundException, 274
from native code, 819–825
IllegalArgumentException, 211, 821
IllegalStateException, 31, 724
in C++, 820
in SQL, 312–314
IndexOutOfBoundsException, 724, 731
InvalidObjectException, 110
InvalidPathException, 115
IOException, 62, 239
MissingResourceException, 422
NoSuchAlgorithmException, 566, 584
NoSuchElementException, 835
NotSerializableException, 102
NullPointerException, 821
OverlappingFileLockException, 142
ParseException, 396, 398
ReadOnlyBufferException, 132
SocketTimeoutException, 241, 268
SQLException, 312–314, 332, 354, 356
SQLWarning, 332
SyncProviderException, 341–342
type use annotations in, 480
UnknownHostException, 239
ExceptionXxx functions (C), 820–821, 825
Exclusive lock, 142
exclusiveOr method (Area), 692
exec method (Runtime), 114
exec/ExecSQL.java, 316

ExecutableElement interface, 489
execute method
 of *CachedRowSet*, 340, 342
 of *RowSet*, 341
 of *Statement*, 310, 316, 329, 331
executeBatch method (*Statement*), 355–356
executeLargeBatch method (*Statement*), 356
executeLargeUpdate method (*Statement*), 310
executeQuery method
 of *PreparedStatement*, 320, 326
 of *Statement*, 308, 310, 332, 334
executeUpdate method
 of *PreparedStatement*, 320, 326
 of *Statement*, 308, 310, 331, 354
executor method (*HttpClient.Builder*), 285
ExecutorService interface, 458
exists method (*Files*), 123–124
EXIT statement (SQL), 303
exports keyword, 510, 512–513, 525
Extension class loader, 535
extern "C", in native methods (C++), 789
External entities, 181
Externalizable interface
 methods of, 103–104

F

F (*float*), type code, 96, 806
\f, in regular expressions, 145
Factoring algorithms, 568
fatalError method (*ErrorHandler*), 183–184
Field class

`getName`, `getType` methods, 665
implementing `AnnotatedElement`, 470

Fields

accessing from native code, 801–806
annotating, 468, 483
transient, 101–102

File class

`separator` constant, 64
`toPath` method, 117–118

File pointers, 81

File systems, POSIX-compliant, 123

`file:` (URI scheme), 260
`file.encoding` property, 77

FileChannel class

`lock` method, 141–143
`map` method, 132, 137
`open` method, 132, 137
`tryLock` method, 141–143

FileHandler class, 420

FileInputStream class, 64–67
constructor, 66
`getChannel` method, 136
`read` method, 56
`fileKey` method (*BasicFileAttributes*), 124

FileLock class

`close` method, 143
`isShared` method, 142

FileNotFoundException, 274

FileOutputStream class, 64–67
constructor, 67
`getChannel` method, 136

Files

channels for, 132
closing, 124, 126
configuration, 141
copying, 120–122
creating, 119–120
deleting, 121–122
encrypted data in, 585
filtering, 126–127, 723
generated automatically, 467, 488
hierarchical structure of, 630
I/O modes of, 85
locking, 141–143
memory-mapped, 51, 131–141
MIME type of, 118
missing, 458
moving, 120–122
random-access, 81–85, 131
reading/writing, 65, 118–119
 by one byte, 56–59
total number of bytes in, 81
traversing, 126–130
with multiple images, 724–732

`Files` class, 115, 118–129
 `copy` method, 120–122, 130
 `createXxx` methods, 119–120
 `delete`, `deleteIfExists` methods, 121–122
 `exists` method, 123–124
 `find` method, 125
 `getOwner` method, 123
 `isXxx` methods, 123–124
 `lines` method, 6, 10, 51, 118
 `list` method, 124–125
 `mismatch` method, 118–119
 `move` method, 120–122

`newBufferedXxx` methods, 118–119
`newDirectoryStream` method, 126, 129
`newXxxStream` methods, 118–119
`probeContentType` method, 118–119
`readAllXxx` methods, 118–119
`readAttributes` method, 123–124
`readString` method, 118–119
`size` method, 123–124
`walk` method, 125–126
`walkFileTree` method, 127–129
`write`, `writeString` methods, 118–119

`FileSystem` class
 `getPath` method, 130–131

`FileSystems` class
 `newFileSystem` method, 130–131

`FileTime` class
 `toInstant` method, 385

`FileTypeDetector` class, 118

`FileVisitor` interface, 128–129
 methods of, 127

`fill` method (`Graphics2D`), 673–674, 692

Filling shapes, 673

`fillXxx` methods (`Graphics`), 674

`filter` method
 of `BufferedImageOp`, 740, 747
 of `Optional`, 19–20
 of `Stream`, 3–11, 16

`FilteredRowSet` interface, 339

`filtering` method (`Collectors`), 38, 41

Filters
 for images, 740–749
 for numbers, 606–607

for table rows, 606–608
glob patterns for, 126–127
implementing, 607
`FilterXxxStream` classes, 65
Final block padding, 580
find method
 of `Files`, 125
 of `Matcher`, 157
findAll method (`Scanner`), 158
findAny method (`Stream`), 17
FindClass function (C), 802, 805, 810
findClass method (`ClassLoader`), 539, 544
findColumn method (`ResultSet`), 311
findFirst method (`Stream`), 16–17
Fingerprints. *See* [Digital fingerprints](#)
first method (`ResultSet`), 333, 337
firstDayOfXxx methods (`TemporalAdjuster`), 373
firstValue method (`HttpHeaders`), 281, 286
#FIXED attribute (DTD), 181
flatMap method
 of `Optional`, 22–26
 of `Stream`, 12
flatMapting method (`Collectors`), 37, 41
flip method (`Buffer`), 140
FLOAT data type (SQL), 301, 357
float type
 printing, 69
 streams of, 43–49
 type code for, 96, 806
 vs. C types, 793
 writing in binary format, 78

`FloatBuffer` class, 139
Floating-point numbers, 388, 395–403
flush method
 of `CipherOutputStream`, 586
 of `Closeable`, 61
 of `Flushable`, 61, 63
 of `OutputStream`, 57, 59
`Flushable` interface, 61–62
 close method, 61
 flush method, 61, 63
`fn` keyword (SQL), 328
Folders, icons for, 638–639, 651
`followRedirects` method (`HttpClient.Builder`), 279, 285
Font render context, 710
`forEach` method (`Stream`), 26, 29
`forEachOrdered` method (`Stream`), 26
Foreign functions, 846–847
Forest (Swing), 630, 638
`ForkJoinPool` class
 commonPool method, 51
`forLanguageTag` method (`Locale`), 391, 394
`Format` class, 384, 415
format method
 of `DateTimeFormatter`, 379, 383, 407
 of `Format`, 415
 of `LocalDate`, 404
 of `LocalDateTime`, 404
 of `LocalTime`, 404
 of `MessageFormat`, 413–415
 of `NumberFormat`, 396, 398
 of `String`, 393
 of `ZonedDateTime`, 404

Formatting

dates, 388–389, 403–407, 413–415
messages, 413–418
numbers, 388–389, 395–403, 413–415
`formatting/Formatting.java`, 382
Forms, processing, 269–278
`forName` method
 of Charset, 77
 of Class, 460
`ForwardingJavaFileManager` class
 constructor, 467
 `getFileForOutput` method, 467
`fprintf` function (C), 809
`Frame` class, 461
`from` method
 of Instant, 384–385
 of ZonedDateTime, 384–385
FROM statement (SQL), 298
FTP (File Transfer Protocol), 264
`ftp:` (URI scheme), 260, 264
Function interface
`identity` method, 31
`@FunctionalInterface` annotation, 483

G

`\G`, in regular expressions, 148
Gadget chains, 114
Garbage collection
 arrays and, 818
 native methods and, 797
GB encoding, 421

GeneralPath class, 674–675, 680
 constructor, 690
generate method (*Stream*), 5, 9, 44
@Generated annotation, 483–484
generateKey method (KeyGenerator), 580, 585
Generators, converting to streams, 50
Generic types, type use annotations in, 480
get method
 of *AttributeSet*, 779, 783
 of *Bindings*, 447
 of *ByteBuffer*, 133, 137
 of *CharBuffer*, 138
 of *Optional*, 20–23
 of *Paths*, 115, 117
 of *ScriptEngine*, 447
 of *ScriptEngineManager*, 447
 of *Supplier*, 11
GET method (*HttpRequest.Builder*), 279, 286
GET request (HTML), 270, 272
 building, 279
getAddress method (*InetAddress*), 242–243
getAdvance method (*TextLayout*), 712
getAllByName method (*InetAddress*), 242–243
getAllowsChildren method (*TreeNode*), 640
getAnnotation method (*AnnotatedElement*), 470, 474, 488–489
getAnnotations method (*AnnotatedElement*), 474
getAnnotationsByType method (*AnnotatedElement*), 474, 488–489
GetArrayLength function (C), 816, 819
getAscent method (*TextLayout*), 712
getAsXxx methods (*OptionalXxx*), 44, 48

getAttribute method (*Element*), [170](#), [174](#)
getAttributes method
 of *DocPrintJob*, [784](#)
 of *Node*, [170](#), [174](#)
 of *PrintService*, [784](#)
getAttributeXxx methods (*XMLStreamReader*), [209](#), [212](#)
getAuthority method (*URI*), [261](#)
getAutoCommit method (*Connection*), [355–356](#)
getAutoCreateRowSorter method (*JTable*), [596](#)
getAvailableCurrencies method (*Currency*), [403](#)
getAvailableLocales method
 of *Collator*, [412](#)
 of *Locale*, [31](#)
 of *NumberFormat*, [391](#), [396](#), [398](#)
getAvailableZoneIds method (*ZoneId*), [375](#)
getAverage method (*XxxSummaryStatistics*), [27](#), [30](#), [49](#)
getBinaryStream method (*Blob*), [326–327](#)
getBlob method (*ResultSet*), [326–327](#)
getBlockSize method (*Cipher*), [584](#)
GetBooleanArrayElements function (*C*), [816–819](#)
GetBooleanArrayRegion function (*C*), [818–819](#)
GetBooleanField function (*C*), [806](#)
getBundle method (*ResourceBundle*), [422–425](#)
getByName method (*InetAddress*), [242–243](#)
GetByteArrayElements function (*C*), [816–819](#), [834](#)
GetByteArrayRegion function (*C*), [818–819](#)
GetByteField function (*C*), [806](#)
getBytes method (*Blob*), [326–327](#)
getCandidateLocales method (*ResourceBundle.Control*),
[423](#)
getCategory method (*Attribute*), [778](#), [783](#)

getCellEditorValue method (*CellEditor*), [620, 622–623, 630](#)
getCellRenderer method (*JTable*), [619](#)
getCellSelectionEnabled method (*JTable*), [614](#)
getChannel method
 of *FileXxxStream*, [136](#)
 of *RandomAccessFile*, [136](#)
getChar method (*ByteBuffer*), [133, 138](#)
getCharacterStream method (*Clob*), [326–327](#)
GetCharArrayElements function (C), [816–819](#)
GetCharArrayRegion function (C), [818–819](#)
getCharContent method (*SimpleJavaFileObject*), [467](#)
GetCharField function (C), [806](#)
getChild method (*TreeModel*), [663–665, 670](#)
getChildAt method (*TreeNode*), [648](#)
getChildCount method
 of *TreeModel*, [663–665, 670](#)
 of *TreeNode*, [649](#)
getChildNodes method (*Node*), [167, 174](#)
getClassLoader method (*Class*), [535, 544](#)
getClip method (*Graphics*), [711, 752](#)
getClob method (*ResultSet*), [326–327](#)
getCollationKey method (*Collator*), [410, 413](#)
getColorModel method (*BufferedImage*), [735, 738](#)
getColumn method (*TableColumnModel*), [601, 614](#)
getColumnClass method (*TableModel*), [600, 613](#)
getColumnCount method
 of *ResultSetMetaData*, [344](#)
 of *TableModel*, [596–597, 600](#)
getColumnModel method (*JTable*), [601, 613](#)
getColumnName method (*AbstractTableModel*), [597–598, 600](#)
getColumnNumber method

of *Diagnostic*, 466
of SAXParseException, 184
getColumnSelectionAllowed method (*JTable*), 614
getColumnType method (*TableModel*), 620
getColumnXxx methods (*ResultSetMetaData*), 344, 353
getCommand method (*RowSet*), 341
getCompactNumberInstance method (*NumberFormat*), 398
getConcurrency method (*ResultSet*), 332, 334, 336
getConnection method (*DriverManager*), 305, 307, 316, 360
getConnectTimeout method (*URLConnection*), 268
getContent method (*URLConnection*), 269
getContentEncoding, getContentType methods (*URLConnection*), 262, 265, 269, 274
getContentLength method (*URLConnection*), 262, 265, 268
getContext method (*ScriptEngine*), 448
getContextClassLoader method (*Thread*), 537, 545
getCount method (*XxxSummaryStatistics*), 30, 49
getCountry method (*Locale*), 35, 394
getCrc method (*ZipEntry*), 88
getCurrencyCode method (*Currency*), 403
getCurrencyInstance method (*NumberFormat*), 395, 398, 402
getData method (*CharacterData*), 169, 175
getDataElements method
 of *ColorModel*, 739
 of *Raster*, 735, 738
getDataSize method (*DataTruncation*), 314
getDate method
 of *ResultSet*, 309, 311
 of *URLConnection*, 262, 265, 269
getDayOfXxx methods
 of *LocalDate*, 368, 370

of `ZonedDateTime`, 378
`getDays` method (`Period`), 371
`getDeclaredAnnotations` method (*AnnotatedElement*), 475
`getDecomposition` method (`Collator`), 413
`getDefault` method (`Locale`), 392–394
`getDefaultEditor` method (`JTable`), 628
`getDefaultFractionDigits` method (`Currency`), 403
`getDefaultName` method (`NameCallback`), 561
`getDefaultRenderer` method (`JTable`), 619, 628
`getDescent` method (`TextLayout`), 712
`getDiagnostics` method (`DiagnosticCollector`), 466
`GetDirectBufferXxx` functions (C), 818
`getDisplayCountry`, `getDisplayLanguage` methods (`Locale`), 32, 394
`getDisplayName` method
 of `DayOfWeek`, `Month`, 381, 405
 of `Locale`, 392–394, 396
`getDocumentElement` method (*Document*), 166, 174
`getDoInput`, `getDoOutput` methods (`URLConnection`), 267
`getDouble` method
 of `ByteBuffer`, 133, 138
 of *ResultSet*, 309, 311
`GetDoubleArrayElements` function (C), 816–819
`GetDoubleArrayRegion` function (C), 818–819
`GetDoubleField` function (C), 802, 806
`getEnclosedElements` method (*TypeElement*), 489
`getEngineXxx` methods (`ScriptEngineManager`), 444–445
`getEntry` method (`ZipFile`), 88
`getErrorCode` method (`SQLException`), 312, 314
`getErrorStream` method (`HttpURLConnection`), 274, 278
`getErrorWriter` method (*ScriptContext*), 448

getExpiration method (`URLConnection`), [262](#), [265](#), [269](#)
getExtensions method (`ScriptEngineFactory`), [445](#)
GetFieldID function (C), [802](#), [806](#)
getFields method (`Class`), [665](#)
getFileForOutput method (`ForwardingJavaFileManager`),
[467](#)
getFileName method (`StackTraceElement`), [116–117](#)
getFilePointer method (`RandomAccessFile`), [81](#), [85](#)
getFileSuffixes method (`ImageReaderWriterSpi`), [731](#)
getFillsViewportHeight method (`JTable`), [596](#)
getFirstChild method (`Node`), [169](#), [174](#)
getFloat method (`ByteBuffer`), [133](#), [138](#)
GetFloatArrayElements function (C), [816–819](#)
GetFloatArrayRegion function (C), [818–819](#)
GetFloatField function (C), [806](#)
getFontRenderContext method (`Graphics2D`), [710](#), [712](#)
getFormatNames method (`ImageReaderWriterSpi`), [731](#)
getFragment method (`URI`), [261](#)
getHeaderXxx methods (`URLConnection`), [262–265](#), [268](#)
getHeight method
 of `ImageReader`, [725](#), [731](#)
 of `PageFormat`, [752](#), [759](#)
getHost method (`URI`), [261](#)
getHostXxx methods (`InetAddress`), [243](#)
getHour method
 of `LocalTime`, [374](#)
 of `ZonedDateTime`, [379](#)
getIdentifier method (`Entry`), [616](#)
getIfModifiedSince method (`URLConnection`), [268](#)
getImageableXxx methods (`PageFormat`), [752](#), [759](#)
getImageXxxByXxx methods (`ImageIO`), [723](#), [730](#)

getIndex method (*DataTruncation*), [314](#)
getIndexOfChild method (*TreeModel*), [663](#), [670](#)
getInputStream method
 of *Socket*, [239–240](#), [244](#)
 of *URLConnection*, [262](#), [269](#), [272](#), [274](#)
 of *ZipFile*, [88](#)
getInstance method
 of *AlphaComposite*, [715](#), [721](#)
 of *Cipher*, [579](#), [584](#)
 of *Collator*, [412](#)
 of *Currency*, [402–403](#)
 of *KeyGenerator*, [585](#)
 of *Locale*, [408](#)
 of *MessageDigest*, [564–566](#)
getInt method
 of *ByteBuffer*, [133](#), [138](#)
 of *ResultSet*, [309](#), [311](#)
GetIntArrayElements function (C), [816–819](#)
GetIntArrayRegion function (C), [818–819](#)
getInterface method (*Invocable*), [450](#)
GetIntField function (C), [802](#), [806](#), [834](#)
getISOCountries method (*Locale*), [392](#), [394](#)
getISOLanguages method (*Locale*), [392](#)
getJavaFileObjectsFromXxx methods
(*StandardJavaFileManager*), [466](#)
getJDBCXxxVersion methods (*DatabaseMetaData*), [352](#)
getKeys method (*ResourceBundle*), [425–426](#)
getKind method (*Diagnostic*), [466](#)
getLanguage method (*Locale*), [394](#)
getLargeUpdateCount method (*Statement*), [310](#)
getLastChild method (*Node*), [169–170](#), [174](#)

getLastModified method (`URLConnection`), [262](#), [265](#), [269](#)
getLastPathComponent method (`TreePath`), [642](#), [648](#)
getLastSelectedPathComponent method (`JTree`), [642](#), [648](#)
getLeading method (`TextLayout`), [712](#)
getLength method
 of *Attributes*, [208](#)
 of *NamedNodeMap*, [175](#)
 of *NodeList*, [167](#), [175](#)
getLineNumber method
 of *Diagnostic*, [466](#)
 of `SAXParseException`, [184](#)
getLocale method (`MessageFormat`), [415](#)
getLocalHost method (`InetAddress`), [242](#)–[243](#)
getLocalName method
 of *Attributes*, [208](#)
 of *Node*, [202](#)
 of *XMLStreamReader*, [212](#)
getLong method (`ByteBuffer`), [133](#), [138](#)
GetLongArrayElements function (C), [816](#)–[819](#)
GetLongArrayRegion function (C), [818](#)–[819](#)
GetLongField function (C), [806](#)
getMax method (`XxxSummaryStatistics`), [27](#), [31](#), [49](#)
getMaxConnections method (`DatabaseMetaData`), [352](#)
getMaxStatements method (`DatabaseMetaData`), [311](#), [352](#)
getMessage method (*Diagnostic*), [466](#)
getMetaData method
 of *Connection*, [343](#), [352](#)
 of *ResultSet*, [344](#), [353](#)
getMethodCallSyntax method (`ScriptEngineFactory`), [449](#)
GetMethodID function (C), [811](#), [814](#)
getMimeTypes method (`ScriptEngineFactory`), [445](#)

`getMIMETypes` method (`ImageReaderWriterSpi`), [731](#)
`getMin` method (`XxxSummaryStatistics`), [31](#), [49](#)
`getMinute` method
 of `LocalTime`, [374](#)
 of `ZonedDateTime`, [379](#)
`getModel` method (`Entry`), [617](#)
`getMonth`, `getMonthValue` methods
 of `LocalDate`, [370](#)
 of `ZonedDateTime`, [378](#)
`getMonths` method (`Period`), [371](#)
`getMoreResults` method (`Statement`), [329](#)–[330](#)
`getName` method
 of *Attribute*, [783](#)
 of *Field*, [665](#)
 of *NameCallback*, [561](#)
 of *Principal*, [553](#)
 of *PrintService*, [771](#)
 of *XMLStreamReader*, [212](#)
 of *ZipEntry*, [88](#)
 of *ZipFile*, [88](#)
`getNames` method (`ScriptEngineFactory`), [445](#)
`getNamespaceURI` method (`Node`), [202](#)
`getNano` method
 of `LocalTime`, [374](#)
 of `ZonedDateTime`, [379](#)
`getNextEntry` method (`ZipInputStream`), [85](#)–[87](#)
`getNextException` method (`SQLException`), [312](#), [314](#)
`getNextSibling` method (`Node`), [169](#)–[170](#), [174](#)
`getNextWarning` method (`SQLWarning`), [314](#)
`getNodeXxx` methods (`Node`), [170](#), [174](#), [202](#)
`getNumberInstance` method (`NumberFormat`), [395](#), [398](#)

`getNumericXxx` methods (`Currency`), [403](#)
`getNumXxx` methods (`ImageReader`), [724](#), [731](#)
`getObject` method
 of `ResourceBundle`, [424–425](#)
 of `ResultSet`, [309](#), [311](#)
`GetObjectArrayElement` function (C), [816](#), [819](#)
`GetObjectClass` function (C), [802–803](#)
`GetObjectField` function (C), [802](#), [806](#)
`getOffset` method (`ZonedDateTime`), [379](#)
`getOrientation` method (`PageFormat`), [759](#)
`getOriginatingProvider` method
 of `ImageReader`, [723](#), [731](#)
 of `ImageWriter`, [732](#)
`getOutputStream` method (`Cipher`), [584](#)
`getOutputStream` method
 of `Socket`, [240](#), [244](#)
 of `URLConnection`, [262](#), [269](#), [272](#)
`getOwner` method (`Files`), [123](#)
`getPageCount` method (`Banner`), [760](#)
`getPageSize` method (`CachedRowSet`), [342](#)
`getParameter` method (`DataTruncation`), [314](#)
`getParent` method
 of `ClassLoader`, [544](#)
 of `Path`, [116–117](#)
 of `TreeNode`, [648](#), [650](#)
`getParentNode` method (`Node`), [174](#)
`getPassword` method
 of `PasswordCallback`, [561](#)
 of `RowSet`, [341](#)
`getPath` method
 of `FileSystem`, [130–131](#)

of TreeSelectionEvent, [662](#)
of URI, [261](#)

getPaths method (TreeSelectionEvent), [656](#), [662](#)
getPathToRoot method (DefaultTreeModel), [644](#)
getPercentInstance method (NumberFormat), [395](#), [398](#)
getPixel, getPixels methods (Raster), [734](#), [739](#)
getPointCount method (ShapeMaker), [681](#)
getPort method (URI), [261](#)
getPreviousSibling method (Node), [174](#)
getPrincipals method (Subject), [553](#)
getPrinterJob method (PrinterJob), [749](#), [758](#)
getPrintService method (StreamPrintServiceFactory),
[773](#)

getPrompt method

- of NameCallback, [561](#)
- of PasswordCallback, [561](#)

getQName method (Attribute), [208](#)
getQualifiedName method (*TypeElement*), [489](#)
getQuery method (URI), [261](#)
getRaster method (BufferedImage), [733](#), [738](#)
getReader method (ScriptContext), [448](#)
getReaderXxx methods (ImageIO), [723](#), [730](#)
getReadTimeout method (URLConnection), [268](#)
getRequestProperties method (URLConnection), [268](#)
getResourceAsStream method (Class, Module), [517](#)
getResponseCode method (HttpURLConnection), [275](#)
getResultSet method (Statement), [310](#)

getRGB method

- of Color, [740](#)
- of ColorModel, [735](#), [739](#)

getRoot method

of *Path*, 116–117
of *TreeModel*, 663–665, 670
getRotateInstance method (*AffineTransform*), 706, 708
getRow method (*ResultSet*), 333, 337
getRowCount method (*TableModel*), 596–597, 600
getRowSelectionAllowed method (*JTable*), 614
getRowXxx methods (*JTable*), 613
getSavepointXxx methods (*Savepoint*), 356
getScaleInstance method (*AffineTransform*), 706, 708
getSecond method
 of *LocalTime*, 374
 of *ZonedDateTime*, 379
getSeconds method (*Duration*), 363
getSelectedColumns method (*JTable*), 604, 608
getSelectedRows method (*JTable*), 604
getSelectionModel method (*JTable*), 613
getSelectionPath method (*JTree*), 642, 648, 661
getSelectionPaths method (*JTree*), 656, 661
getShearInstance method (*AffineTransform*), 706, 708
getShort method (*ByteBuffer*), 133, 138
GetShortArrayElements function (C), 816–819
GetShortArrayRegion function (C), 818–819
GetShortField function (C), 806
getSimpleName method (*Element*), 489
getSize method (*ZipEntry*), 88
getSource method (*Diagnostic*), 466
getSQLState method (*SQLException*), 312, 314
getSQLStateType method (*SQLException*), 312
getStandardFileManager method (*JavaCompiler*), 465
GetStaticFieldID, GetStaticXxxField functions (C), 805–806
GetStaticMethodID function (C), 810, 815

getStrength method (*Collator*), [412](#)
getString method
 of *ResourceBundle*, [423](#), [425](#)
 of *ResultSet*, [309](#), [311](#)
getStringArray method (*ResourceBundle*), [426](#)
GetStringChars, GetStringLength functions (C), [798](#)
GetStringRegion function (C), [797](#)
GetStringUTFChars function (C), [796](#), [798–799](#), [834](#)
GetStringUTFLength, GetStringUTFRegion functions (C), [797](#)
getStringValue method (*Entry*), [617](#)
getSubject method (*LoginContext*), [552](#)
getSubString method (*Clob*), [326–327](#)
getSum method (*XxxSummaryStatistics*), [30](#), [49](#)
GetSuperclass function (C), [846](#)
getSymbol method (*Currency*), [403](#)
getSystemClassLoader method (*ClassLoader*), [544](#)
getSystemJavaCompiler method (*ToolProvider*), [457](#)
getTableCellEditorComponent method (*TableCellEditor*),
[621–623](#), [629](#)
getTableCellRendererComponent method
(*TableCellRenderer*), [617](#), [629](#)
getTableHeader method (*JTable*), [594](#)
getTableName method (*CachedRowSet*), [342](#)
getTables method (*DatabaseMetaData*), [343](#), [352](#)
getTagName method (*Element*), [167](#), [174](#), [202](#)
getTask method (*JavaCompiler*), [457–458](#), [465](#)
Getters/setters, generated automatically, [492](#)
getText method (*XMLStreamReader*), [212](#)
getTimeZone method (*TimeZone*), [385](#)
getTransferSize method (*DataTruncation*), [314](#)

`getTranslateInstance` method (`AffineTransform`), [706, 709, 711](#)

`getTreeCellRendererComponent` method

- of `DefaultTreeCellRenderer`, [652–653](#)
- of `TreeCellRenderer`, [652–654](#)

`getType` method

- of `Field`, [665](#)
- of `ResultSet`, [332, 336](#)

`getUpdateCount` method (`Statement`), [310, 330](#)

`getURI` method (`Attribute`), [208](#)

`getURL` method (`RowSet`), [341](#)

`getURLs` method (`URLClassLoader`), [537](#)

`getUserInfo` method (`URI`), [261](#)

`getUsername` method (`RowSet`), [341](#)

`getValue` method

- of `Attributes`, [208](#)
- of `Copies`, [779](#)
- of `Entry`, [617](#)
- of `Win32RegKey`, [832–833](#)

`getValueAt` method (`TableModel`), [596–597, 600, 619](#)

`getValueCount` method (`Entry`), [617](#)

`getVendorName`, `getVersion` methods
(`IIOServiceProvider`), [723, 731](#)

`getWarnings` method (`Connection`, `ResultSet`, `Statement`),
[314](#)

`getWidth` method

- of `ImageReader`, [725, 731](#)
- of `PageFormat`, [752, 759](#)

`getWriter` method (`ScriptContext`), [448](#)

`getWriterXxx` methods (`ImageIO`), [723, 730](#)

`getYear` method

of `LocalDate`, 370
of `ZonedDateTime`, 378
`getYears` method (`Period`), 371
GIF format, 722
 animated, 724
 image manipulations on, 744
 printing, 769
GlassFish server, 359
Glob patterns, 126–127
GlobalSign, 574
GMail, 287–288
Gnu C compiler, 789–790
Gödel’s theorem, 546
Google Maps, 271
GradientPaint class, 701–702
 constructor, 702–703
 cyclic parameter, 702
Graphic Java™ (Geary), 592, 630
Graphics class, 671–672
 `drawXxx`, `fillXxx` methods, 674
 get/setClip methods, 710–711, 752
Graphics2D class, 672
 `clip` method, 672, 710–712, 752
 `draw` method, 673–675, 692–693
 `fill` method, 673–674, 692
 `getFontRenderContext` method, 710, 712
 `rotate` method, 705, 709
 `scale` method, 704–705, 709
 `setComposite` method, 673, 715, 721
 `setPaint` method, 672, 701–703
 `setRenderingHint`, `setRenderingHints` methods, 672
 `setStroke` method, 672, 693, 701

setTransform method, 707, 709
shear method, 705, 709
transform method, 673, 707, 709
translate method, 705, 709, 761
Greenwich Royal Observatory, 362, 375
Gregorian calendar reform, 371
GregorianCalendar class
 toZonedDateTime method, 384–385
Groovy programming language, 444, 451–452
group method
 of Matcher, 157
 of MatchResult, 158
groupCount method (Matcher), 157
Grouping, 35–36
 classifier functions of, 35
 reducing to numbers, 36
groupingBy method (Collectors), 35–40
groupingByConcurrent method (Collectors), 35–36, 50
>, entity reference, 164
GUI (Graphical User Interface), scripting events for, 451–456

H

\h, \H, in regular expressions, 146
Half-closing connections, 251–252
Handbook of Applied Cryptography, The (Menezes et al.), 567
handle method (CallbackHandler), 561
handleGetObject method (ResourceBundle), 425–426
Handles (Swing), 635, 652
hash/Digest.java, 565
hashCode method (Annotation), 476
HashSet class

readObject, writeObject methods, 102
HashXxxAttributeSet classes, 750, 777
Haskell programming language, 444
hasMoreElements method (*Enumeration*), 832–835
hasNext method (*XMLStreamReader*), 211
hasRemaining method (Buffer), 137
Header information, from server, 262
header method (`HttpRequest.Builder`), 286
Headers (Swing tables)
 rendering, 619
 scrolling, 593
headers method (`HttpResponse`), 281, 286
helloNative/HelloNative.c, 789
helloNative/HelloNative.h, 788
helloNative/HelloNative.java, 787
helloNative/HelloNativeTest.java, 790
Hex editors
 creating class files in, 546
 modifying bytecodes with, 548
Hidden commands, in XML comments, 165
Hosts, 242–243
HTML (HyperText Markup Language)
 attributes in, 162, 164
 end and empty tags in, 162
 forms in, 269
 generating from XML files, 223–226
 mixing with JSP, 461
 printing, 769
 vs. XML, 161–162
HTTP (Hypertext Transfer Protocol), 295
 redirects between HTTPS and, 275
 request headers in, 263–264

`http`: (URI scheme), [260](#)
`HttpClient` class, [279–286](#)

- enabling logging for, [282](#)
- `newBuilder` method, [279, 281, 285](#)
- `newHttpClient` method, [279, 285](#)
- `send` method, [285](#)
- `sendAsync` method, [281, 285](#)

`HttpClient.Builder` class

- `build` method, [279–280, 285](#)
- `executor` method, [285](#)
- `followRedirects` method, [279, 285](#)

`HttpHeaders` class

- `firstValue` method, [281, 286](#)
- `map` method, [281, 286](#)

`HttpRequest` class

- `newBuilder` method, [279, 281, 286](#)

`HttpRequest.Builder` class

- `build` method, [286](#)
- `DELETE` method, [286](#)
- `GET` method, [279, 286](#)
- `header` method, [286](#)
- `POST` method, [280, 286](#)
- `PUT` method, [286](#)
- `uri` method, [279–281, 286](#)

`HttpResponse` class

- methods of, [280, 286](#)

`HttpResponse.BodyHandlers` class

- `discarding` method, [281](#)
- `ofString` method, [280–281](#)

`HTTPS` (Hyper Text Transfer Protocol Secure), [275](#)
`https`: (URI scheme), [260](#)
`HttpURLConnection` class, [274](#)

`getErrorStream` method, 274, 278
`getResponseCode` method, 275
`getInstanceFollowRedirects` method, 275

I

`I` (`int`), type code, 96, 806
I/O streams. *See Input streams, Output streams*

IANA (Internet Assigned Numbers Authority), 375

IBM, 159

DB2 database, 301

DOM parser, 166

IBM437 encoding, 419

ICC profiles, 734

Icons

in column headers, 619

in table cells, 617

in trees, 638–639, 651

ID, IDREF, IDREFS attribute types (DTDs), 180–181

Identity (do-nothing) transformation, 216

`identity` method (*Function*), 31

Identity values, 42

IDs, uniqueness of, 181, 189

IETF BCP 47, 390, 393

`ifPresent` method

of `Optional`, 18–19

of `OptionalXxx`, 48

`ifPresentOrElse` method (`Optional`), 19

of `Optional`, 19

`IIOImage` class, 725, 732

`IIOServiceProvider` class

`getXxx` methods, 723, 731

`IllegalAccessException`, 665

`IllegalArgumentException`, 211, 821
`IllegalStateException`, 31, 724
`ImageInputStream` class, 724
“Seek forward only” mode, 724
`ImageIO` class
 `createImageXxxStream` methods, 724, 730
 determining image type, 722–723
 `getImageXxxByXxx` methods, 723, 730
 `getReaderXxx`, `getWriterXxx` methods, 723, 730
 read, write methods, 722, 729
`imageIO/ImageIOFrame.java`, 726
`ImageOutputStream` interface, 725
`imageProcessing/ImageProcessingFrame.java`, 744
`ImageReader` class, 722–723
 `getHeight` method, 725, 731
 `getNumXxx` methods, 724, 731
 `getOriginatingProvider` method, 723, 731
 `getWidth` method, 725, 731
 read, `readThumbnail` methods, 731
 `setInput` method, 730
`ImageReaderWriterSpi` class
 `getXxx` methods, 731

Images

- blurring, 742
- color values of, 735
- edge detection of, 743
- filtering, 740–749
- getting size of, before reading, 725
- incremental rendering of, 732
- manipulating, 732–749
- metadata in, 725
- multiple, in a file, 724–732

printing, 749–759, 769, 773
raster, 721–749
 constructing from pixels, 733–740
 readers/writers for, 722–732
rotating, 741
superimposing, 712–713
thumbnails for, 725
vector, 671–721

ImageWriter class, 722, 725
 canInsertImage method, 725, 732
 getOriginatingProvider method, 732
 setOutput method, 732
 write, writeInsert methods, 725, 732

implements specification, 480

#IMPLIED attribute (DTD), 181

import statement, 538

INCLUDE environment variable, 830

include method (RowFilter), 607, 616

Incremental rendering, 732

Indexed color model, 742

IndexOutOfBoundsException, 724, 731

InetAddress class
 getXxx methods, 242–243

inetAddress/InetAddressTest.java, 242

InetSocketAddress class
 isUnresolved method, 259

Inheritance trees, 312

@Inherited annotation, 483, 487

init method
 of Cipher, 584
 of KeyGenerator, 585

Initialization blocks, for shared libraries, 792

initialize method (*LoginModule*), 562
INPUT_STREAM class (DocFlavor), 770
Input streams, 56–78
 as input source, 166
 buffered, 65–67
 byte processing in, 65
 byte-oriented, 56
 chaining, 65
 closing, 57
 encoding for, 68
 filters for, 64–67
 hierarchy of, 59–63
 keeping open, 251
 objects in, 89–114
 redirecting, 447–448
 Unicode, 56
InputSource class, 184
InputStream class, 56–59, 61
 available method, 57–58
 close method, 57–58
 mark method, 58
 markSupported method, 59
 nullInputStream method, 59
 read method, 56–58
 readAllBytes, readNBytes methods, 56, 58
 reset method, 59
 skip, skipNBytes methods, 58
 transferTo method, 58
InputStreamReader class, 68
INSERT statement (SQL), 300
 autogenerated keys and, 331
 executing, 308, 310, 326
 in batch updates, 355

vs. methods of *ResultSet*, 335
`insertNodeInto` method (`DefaultTreeModel`), 643, 649
`insertRow` method (*ResultSet*), 335, 337
Instance fields
 accessing from native code, 801–805
 annotating, 479
`instanceof` keyword, 480
Instant class, 362
 `compareTo` method, 363
 `equals` method, 363
 `from` method, 384–385
 immutability of, 363
 legacy classes and, 384–385
 minus, `minusXxx` methods, 365–366
 `now` method, 363, 365
 plus, `plusXxx` methods, 365–366
Instrumentation API, 499
int type
 printing, 69
 storing, 79
 streams of, 43–49
 type code for, 96, 806
 vs. C types, 793
 writing in binary format, 78
IntBuffer class, 139
INTEGER data type (SQL), 301, 357
IntegerSyntax class, 779
IntelliJ IDE, 102
@interface declaration, 469, 475
Interfaces
 accessing script classes with, 450
 annotating, 479, 483

- implementing in script engines, 449
- Internationalization, 387–442
- Internet Engineering Task Force, 390
- Interpolation, 741
 - for gradients, 701–702
 - strategies of, 741
 - when transforming images, 741
- Interruptible sockets, 252–259
- interruptible/InterruptibleSocketTest.java, 254
- intersect method (Area), 692
- ints method
 - of Random, 45
 - of RandomGenerator, 48
 - of SplittableRandom, 52
- IntStream* interface, 43–49
 - average method, 44, 46
 - boxed method, 44, 46
 - mapToInt method, 44
 - max, min methods, 44, 46
 - of method, 44, 46
 - range, rangeClosed methods, 44, 46
 - sum, summaryStatistics methods, 44, 46
 - toArray method, 44, 46
- IntSummaryStatistics class, 27, 30–31, 44, 49
- intValue method (Number), 396
- Invalid pointers (C, C++), 786
- InvalidObjectException, 110
- InvalidPathException, 115
- Invocable* interface, 448
 - getInterface method, 450
 - invokeXxx methods, 448, 450
- Invocation API, 825–830

invocation/InvocationTest.c, 826
IOException, 62, 239
IP addresses, 237, 242–243
IPP (Internet Printing Protocol) 1.1, 783
IPv6 addresses, 242
isAfter method
 of LocalDate, 371
 of LocalTime, 374
 of ZonedDateTime, 379
isAfterLast method (*ResultSet*), 333, 337
isAnnotationPresent method (*AnnotatedElement*), 474
IsAssignableFrom function (C), 834, 846
isBefore method
 of LocalDate, 371
 of LocalTime, 374
 of ZonedDateTime, 379
isBeforeFirst method (*ResultSet*), 333, 337
isCellEditable method
 of AbstractCellEditor, 622
 of AbstractTableModel, 619
 of CellEditor, 630
 of DefaultTableModel, 619
 of *TableModel*, 600, 619
isCharacters method (*XMLStreamReader*), 212
isClosed method
 of *ResultSet*, 311
 of Socket, 241
 of *Statement*, 310
isConnected method (*Socket*), 241
isDirectory method
 of *BasicFileAttributes*, 124

of ZipEntry, 88
isEchoOn method (PasswordCallback), 561
isEndElement method (*XMLStreamReader*), 212
isExecutable method (Files), 123–124
isFirst method (*ResultSet*), 333, 337
isGroupingUsed method (NumberFormat), 399
isHidden method (Files), 123–124
isIgnoringElementContentWhitespace method (DocumentBuilderFactory), 185
isInputShutdown method (Socket), 252
isLast method (*ResultSet*), 333, 337
isLeaf method
 of DefaultTreeModel, 639
 of TreeModel, 640, 663, 671
 of TreeNode, 639–640
isLeapYear method (LocalDate), 371
isNamespaceAware method
 of DocumentBuilderFactory, 202
 of SAXParserFactory, 207
isNegative method (Duration), 366
ISO 216 standard, 425
ISO 639-1 standard, 390, 394
ISO 3166-1 standard, 390, 394
ISO 4217 standard, 401, 403
ISO 8601 standard, 328, 484
ISO 8859-1 standard, 68, 77
isOutputShutdown method (Socket), 252
isParseIntegerOnly method (NumberFormat), 399
isPresent method (Optional), 20–23
isReadable method (Files), 123–124
isRegularFile method

of *BasicFileAttributes*, 124
of *Files*, 123–124
isShared method (*FileLock*), 142
isStartElement method (*XMLStreamReader*), 212
isSymbolicLink method
 of *BasicFileAttributes*, 124
 of *Files*, 123–124
isUnresolved method (*InetSocketAddress*), 259
isValidating method
 of *DocumentBuilderFactory*, 185
 of *SAXParserFactory*, 207
isWhiteSpace method (*XMLStreamReader*), 212
isWritable method (*Files*), 123–124
isZero method (*Duration*), 366
item method
 of *NamedNodeMap*, 175
 of *NodeList*, 167, 175, 183
Iterable interface, 126, 457
 spliterator method, 10
iterate method (*Stream*), 5, 9, 15, 44
Iterator interface, 308
iterator method
 of *BaseStream*, 29
 of *SQLException*, 312, 314
 of *Stream*, 26
Iterators, 26
 converting to streams, 6, 50
 splittable, 9–10

J

J (long), type code, 96, 806

JAAS (Java Authentication and Authorization Service), 550–553

 configuration files in, 550, 552

 login modules in, 553–562

 jaas/jaas.config, 560

 jaas/JAATest.java, 560

 jaas/SimpleCallbackHandler.java, 559

 jaas/SimpleLoginModule.java, 557

 jaas/SimplePrincipal.java, 555

JAR files

 adding to class path, 537

 analyzing dependencies of, 528–529

 automatic registration in, 304

 file resources in, 517

 for plugins, 536

 manifest of, 86, 519

 META-INF/services directory, 526

 modular, 514–515, 520

 resources in, 421

 signing, 571

jar program, 514

jar: (URI scheme), 260

jarray type (C), 833

jarsigner program, 571

JarXxxStream classes, 86

Java 2D API, 671–721

 affine transformations in, 706

 colors in, 734

 constructive area geometry operations in, 691

 features supported in, 672

 filters in, 740–749

 paint in, 701–703

 printing in, 760

 rendering pipeline in, 672–674

sample values in, 733
shape classes in, 674–675, 679
strokes in, 693
transparency in, 712–715

Java Bug Database, 742

Java EE (Java Platform, Enterprise Edition), 295

Java Platform Module System, 504–531
migration to, 519–523

Java Plug-in, loading signed code, 577

java program
--add-exports option, 521–523
--add-modules option, 279
--add-opens option, 521–523
--illegal-access option, 521–523
-javaagent option, 499
jdbc.drivers property in, 304
--module, --module-path options, 507
-noverify option, 548
specifying locales in, 392

Java programming language
internationalization support in, 387
platform-independent, 79
vs. SQL, 321

Java Virtual Machine Specification, The, 493, 547

java.awt package, 505
java.awt.AlphaComposite API, 721
java.awt.BasicStroke API, 701
java.awt.Color API, 740
java.awt.font.TextLayout API, 712
java.awt.geom package, 102
java.awt.geom.AffineTransform API, 707–709
java.awt.geom.Arc2D.Double API, 690

`java.awt.geom.Area API`, 692
`java.awt.geom.CubicCurve2D.Double API`, 690
`java.awt.geom.GeneralPath API`, 690
`java.awt.geom.Path2D API`, 691
`java.awt.geom.Path2D.Float API`, 691
`java.awt.geom.QuadCurve2D.Double API`, 690
`java.awt.geom.RoundRectangle2D.Double API`, 690
`java.awt.GradientPaint API`, 703
`java.awt.Graphics API`, 711
`java.awt.Graphics2D API`, 674, 701, 703, 709, 712, 721
`java.awt.image.AffineTransformOp API`, 747
`java.awt.image.BufferedImage API`, 738
`java.awt.image.BufferedImageOp API`, 747
`java.awt.image.ByteLookupTable API`, 748
`java.awt.image.ColorModel API`, 739
`java.awt.image.ConvolveOp API`, 748
`java.awt.image.Kernel API`, 749
`java.awt.image.LookupOp API`, 748
`java.awt.image.Raster API`, 738–739
`java.awt.image.RescaleOp API`, 747
`java.awt.image.ShortLookupTable API`, 748
`java.awt.image.WritableRaster API`, 739
`java.awt.print.PageFormat API`, 759
`java.awt.print.Printable API`, 758
`java.awt.print.PrinterJob API`, 758
`java.awt.TexturePaint API`, 703
`java.base module`, 535
`java.datatransfer module`, 535
`java.desktop module`, 523–524, 535
`java.instrument module`, 535
`java.io package`, 78

`java.io.BufferedXxxStream` APIs, [67](#)
`java.io.Closeable` API, [63](#)
`java.io.DataInput` API, [80](#)
`java.io.DataOutput` API, [80](#)
`java.io.File` API, [118](#)
`java.io.FileInputStream` API, [66](#), [136](#)
`java.io.FileOutputStream` API, [67](#), [136](#)
`java.io.Flushable` API, [63](#)
`java.io.InputStream` API, [58](#)–[59](#)
`java.io.ObjectInputStream` API, [94](#)
`java.io.ObjectOutputStream` API, [94](#)
`java.io.OutputStream` API, [59](#)
`java.io.PrintWriter` API, [70](#)
`java.io.PushbackInputStream` API, [67](#)
`java.io.RandomAccessFile` API, [85](#), [136](#)
`java.lang`, `java.lang.annotation` packages, [482](#)
`java.lang.annotation.Annotation` API, [476](#)
`java.lang.Appendable` API, [63](#)
`java.lang.CharSequence` API, [48](#), [63](#)
`java.lang.Class` API, [544](#)
`java.lang.ClassLoader` API, [544](#)–[545](#)
`java.lang.Iterable` API, [10](#)
`java.lang.Readable` API, [63](#)
`java.lang.reflect.AnnotatedElement` API, [474](#)–[475](#)
`java.lang.System` API, [792](#)
`java.lang.Thread` API, [545](#)
`java.logging` module, [524](#), [535](#)
`java.management` module, [535](#)
`java.management.rmi` module, [535](#)
`java.naming` module, [535](#)
`java.net` package

socket connections in, 240
supporting IPv6 addresses in, 242
URLs vs. URIs in, 260

`java.net.http` package, 279
`java.net.http.HttpClient API`, 285
`java.net.http.HttpClient.Builder API`, 285
`java.net.http.HttpHeaders API`, 286
`java.net.http.HttpRequest API`, 286
`java.net.http.HttpRequest.Builder API`, 286
`java.net.http.HttpResponse API`, 286
`java.net.HttpURLConnection API`, 278
`java.net.InetAddress API`, 243
`java.net.InetSocketAddress API`, 259
`java.net.ServerSocket API`, 247
`java.net.Socket API`, 240–241, 252
`java.net.URL API`, 267
`java.net.URLClassLoader API`, 545
`java.netURLConnection API`, 267–269
`java.net.URLDecoder API`, 278
`java.net.URLEncoder API`, 278
`java.nio` package, 249, 252

- direct buffers in, 818
- memory mapping in, 132

`java.nio.Buffer API`, 137, 140–141
`java.nio.ByteBuffer API`, 137–138
`java.nio.channels.Channels API`, 259
`java.nio.channels.FileChannel API`, 137, 143
`java.nio.channels.FileLock API`, 143
`java.nio.channels.SocketChannel API`, 259
`java.nio.CharBuffer API`, 138–139
`java.nio.file.attribute.BasicFileAttributes API`, 124

`java.nio.file.Files` API, 10, 119–120, 122, 124, 129
`java.nio.file.FileSystem` API, 131
`java.nio.file.FileSystems` API, 131
`java.nio.file.Path` API, 117
`java.nio.file.Paths` API, 117
`java.nio.file.SimpleFileVisitor` API, 129–130
`java.prefs` module, 535
`java.rmi` module, 535
`java.se` module, 524
`java.security` package, 563
`java.security.MessageDigest` API, 566
`java.security.Principal` API, 553
`java.security.sasl` API, 535
`java.sql` package, 384
`java.sql.Blob` API, 327
`java.sql.Clob` API, 327
`java.sql.Connection` API, 309, 314, 325, 328, 336, 352, 356
`java.sql.DatabaseMetaData` API, 338, 352, 357
`java.sql.DataTruncation` API, 314
`java.sql.DriverManager` API, 307
`java.sql.PreparedStatement` API, 325–326
`java.sql.ResultSet` API, 310–311, 314, 327, 336–338, 353
`java.sql.ResultSetMetaData` API, 353
`java.sql.Savepoint` API, 356
`java.sql.SQLException` API, 314
`java.sql.SQLWarning` API, 314
`java.sql.Statement` API, 310, 314, 330–331, 356
`java.text.CollationKey` API, 413
`java.text.Collator` API, 412–413
`java.text.Format` API, 415
`java.text.MessageFormat` API, 415

`java.text.Normalizer API`, 413
`java.text.NumberFormat API`, 398–399
`java.time package`, 403–404
`java.time.Duration API`, 365–366
`java.time.format.DateTimeFormatter API`, 383–384, 407
`java.time.Instant API`, 365
`java.time.LocalDate API`, 370–371, 373, 384, 407
`java.time.LocalDateTime API`, 407
`java.time.LocalTime API`, 374, 407
`java.time.Period API`, 371
`java.time.temporal.TemporalAdjusters API`, 373
`java.time.ZonedDateTime API`, 378–379, 384, 407
`java.util.Arrays API`, 9
`java.util.Collection API`, 4, 53
`java.util.Currency API`, 403
`java.util.DoubleSummaryStatistics API`, 30–31, 49
`java.util.function.Supplier API`, 11
`java.util.IntSummaryStatistics API`, 30–31, 49
`java.util.Locale API`, 393–394
`java.util.LongSummaryStatistics API`, 30–31, 49
`java.util.Optional API`, 18–23, 26
`java.util.OptionalXxx APIs`, 48
`java.util.random.RandomGenerator API`, 48
`java.util.regex.Matcher API`, 157–158
`java.util.regex.MatchResult API`, 158
`java.util.regex.Pattern API`, 10, 156
`java.util.ResourceBundle API`, 425–426
`java.util.Scanner API`, 10, 158
`java.util.Spliterators API`, 9
`java.util.Stream API`, 43
`java.util.stream.BaseStream API`, 29, 53

`java.util.stream.Collectors` API, 30, 34, 36, 40–41
`java.util.stream.DoubleStream` API, 47
`java.util.stream.IntStream` API, 46
`java.util.stream.LongStream` API, 47
`java.util.stream.Stream` API, 4, 13–14, 16–17, 29
`java.util.stream.StreamSupport` API, 10
`java.util.zip.ZipEntry` API, 87–88
`java.util.zip.ZipFile` API, 88
`java.util.zip.ZipInputStream` API, 87
`java.util.zip.ZipOutputStream` API, 87
`java.xml` module, 535
`javac` program
 byte order mark in, 420
 `-encoding` option, 421
 passing parameters to, 457
 `-XprintRounds` option, 492
`JavaCompiler` interface
 `getStandardFileManager` method, 465
 `getTask` method, 457–458, 465
`Javadoc`, 485
`JavaFileObject` interface, 457
`JavaMail`, 287
`javap` program, 808
`JavaScript` programming language, 444, 451–452
`javax.annotation` package, 482
`javax.crypto.Cipher` API, 584–585
`javax.crypto.CipherXxxStream` APIs, 586
`javax.crypto.KeyGenerator` API, 585
`javax.crypto.spec.SecretKeySpec` API, 585
`javax.imageio` package, 722
`javax.imageio.IIOImage` API, 732

`javax.imageio.ImageIO` API, 729–730
`javax.imageio.ImageReader` API, 730–731
`javax.imageio.ImageWriter` API, 732
`javax.imageio.spi.IIOServiceProvider` API, 731
`javax.imageio.spi.ImageReaderWriterSpi` API, 731
`javax.print.attribute.Attribute` API, 783
`javax.print.attribute.AttributeSet` API, 783–784
`javax.print.DocPrintJob` API, 772, 784
`javax.print.PrintService` API, 772, 784
`javax.print.PrintServiceLookup` API, 771
`javax.print.SimpleDoc` API, 772
`javax.print.StreamPrintServiceFactory` API, 773
`javax.script.Bindings` API, 447
`javax.script.Compilable` API, 451
`javax.script.CompiledScript` API, 451
`javax.script.Invocable` API, 450
`javax.script.ScriptContext` API, 448
`javax.script.ScriptEngine` API, 447–448
`javax.script.ScriptEngineFactory` API, 445
`javax.script.ScriptEngineManager` API, 445, 447
`javax.security.auth.callback.CallbackHandler` API, 561
`javax.security.auth.callback.XxxCallback` APIs, 561
`javax.security.auth.login.LoginContext` API, 552
`javax.security.auth.spi.LoginModule` API, 562
`javax.security.auth.Subject` API, 553
`javax.sql` package, 359
`javax.sql.rowset` package, 339
`javax.sql.RowSet` API, 341
`javax.sql.rowset.CachedRowSet` API, 342
`javax.sql.rowset.RowSetFactory` API, 342

`javax.sql.rowset.RowSetProvider API`, [342](#)
`javax.swing.CellEditor API`, [630](#)
`javax.swing.DefaultCellEditor API`, [629](#)
`javax.swing.DefaultRowSorter API`, [615](#)
`javax.swing.event.TreeModelEvent API`, [671](#)
`javax.swing.event.TreeModelListener API`, [671](#)
`javax.swing.event.TreeSelectionEvent API`, [662](#)
`javax.swing.event.TreeSelectionListener API`, [662](#)
`javax.swing.JComponent API`, [641](#)
`javax.swing.JTable API`, [596](#), [613–614](#), [628](#)
`javax.swing.JTree API`, [640](#), [648](#), [661](#)
`javax.swing.ListSelectionModel API`, [615](#)
`javax.swing.RowFilter API`, [616](#)
`javax.swing.RowFilter.Entry API`, [616–617](#)
`javax.swing.table.TableCellEditor API`, [629](#)
`javax.swing.table.TableCellRenderer API`, [629](#)
`javax.swing.table.TableColumn API`, [615](#), [629](#)
`javax.swing.table.TableColumnModel API`, [614](#)
`javax.swing.table.TableModel API`, [600](#), [613](#)
`javax.swing.table.TableRowSorter API`, [615](#)
`javax.swing.table.TableStringConverter API`, [616](#)
`javax.swing.tree.DefaultMutableTreeNode API`, [641](#), [654](#)
`javax.swing.tree.DefaultTreeCellRenderer API`, [654](#)
`javax.swing.tree.DefaultTreeModel API`, [641](#), [649](#)
`javax.swing.tree.MutableTreeNode API`, [640](#)
`javax.swing.tree.TreeCellRenderer API`, [654](#)
`javax.swing.tree.TreeModel API`, [640](#), [670–671](#)
`javax.swing.tree.TreeNode API`, [640](#), [648–649](#)
`javax.swing.tree.TreePath API`, [648](#)
`javax.tools.Diagnostic API`, [466](#)
`javax.tools.DiagnosticCollector API`, [466](#)

`javax.tools.ForwardingJavaFileManager` API, 467
`javax.tools.JavaCompiler` API, 465
`javax.tools.JavaCompiler.CompilationTask` API, 466
`javax.tools.SimpleJavaFileObject` API, 467
`javax.tools.StandardJavaFileManager` API, 466
`javax.tools.Tool` API, 465
`javax.xml.catalog.CatalogFeatures` API, 184
`javax.xml.catalog.CatalogManager` API, 184
`javax.xml.catalog.files` system property, 178
`javax.xml.parsers.DocumentBuilder` API, 173, 183, 215
`javax.xml.parsers.DocumentBuilderFactory` API, 173, 185, 202
`javax.xml.parsers.SAXParser` API, 207
`javax.xml.parsers.SAXParserFactory` API, 207
`javax.xml.stream.XMLInputFactory` API, 211
`javax.xml.stream.XMLOutputFactory` API, 221
`javax.xml.stream.XMLStreamReader` API, 211–212
`javax.xml.stream.XMLStreamWriter` API, 221–222
`javax.xml.transform.dom.DOMResult` API, 233
`javax.xml.transform.dom.DOMSource` API, 216
`javax.xml.transform.sax.SAXSource` API, 233
`javax.xml.transform.stream.StreamResult` API, 216
`javax.xml.transform.stream.StreamSource` API, 233
`javax.xml.transform.Transformer` API, 216
`javax.xml.transform.TransformerFactory` API, 216, 232
`javax.xml.xpath.XPath` API, 199
`javax.xml.xpath.XPathEvaluationResult` API, 199
`javax.xml.xpath.XPathFactory` API, 199
JAXB (Java Architecture for XML Binding), 516
JAXP (Java API for XML Processing) library, 166, 537
jboolean type (C), 793

jbooleanArray type (C), [816](#)
JButton class, [452](#)
jbyte type (C), [793](#)
jbyteArray type (C), [816](#)
jchar type (C), [793, 795](#)
jcharArray type (C), [816](#)
JCheckBox class, [619](#)
jclass type (C), [811](#)
JComboBox class, [619](#)
JCommander framework, [469](#)
JComponent class
 paint method, [617, 672](#)
 paintComponent method, [672](#)
 putClientProperty method, [636, 641](#)
JDBC API, [291–360](#)
 configuration of, [301–307](#)
 debugging, [306](#)
 design of, [292–295](#)
 specification for, [293](#)
 tracing, [306](#)
 uses of, [294–295](#)
 versions of, [291](#)
JDBC API Tutorial and Reference (Fisher et al.), [336, 358](#)
JDBC drivers
 escape syntax in, [328–329](#)
 JAR files for, [302](#)
 registering classes for, [304](#)
 scrollable/updatable result sets in, [332](#)
 types of, [293–294](#)
JDBC/ODBC bridge, [293](#)
JdbcRowSet interface, [339](#)
jdeprscan program, [484](#)

`jdeps` program, 528–529

JDK (Java Development Kit)

DOM parser, 166

`keytool` program, 569

obsolete features in, 504

`serialver` program, 107

`src.jar` file, 826

SunJCE ciphers, 579

`jdk.incubator.http` package, 279

`jdouble` type (C), 793

`jdoubleArray` type (C), 816

JEP 290, JEP 415, 114

`jfloat` type (C), 793

`jfloatArray` type (C), 816

`jimage` command, 530

`jint` type (C), 793

`jintArray` type (C), 816

`JLabel` class, 651–652

`jlink` program, 530

`jlong` type (C), 793

`jlongArray` type (C), 816

JMOD files, 530, 535

`jmod` program, 530

JNDI service, 359, 537

`JndiLoginModule` class, 551

JNI (Java Native Interface), 786–846

accessing:

array elements in, 816–819

functions in C++, 796

calling convention in, 796

debugging mode of, 826

error handling in, 819–825

invoking Java methods in, 809–815
online documentation for, 797
JNI_CreateJavaVM function (C), 825–826, 830
JNI_OnLoad, JNI_OnUnload methods (C), 792
`jni.h` file, 793
JNICALL, JNICALL macros, 788
JobAttributes class (obsolete), 783
jobject type (C), 811, 816, 833
jobjectArray type (C), 816
Join styles, 694
joining method (Collectors), 27, 30
JoinRowSet interface, 339
 JPanel class, 452, 753
JPEG format, 722
 image manipulations on, 744
 printing, 769
 reading, 723
js.properties file, 451
 JScrollPane class, 593
JSF (JavaServer Faces), 269
JShell, loading modules into, 515
jshort type (C), 793
jshortArray type (C), 816
JSON-B (JSON Binding), 516, 518
JSP (JavaServer Pages), 461–467
jstring type (C), 796, 811, 833
JTable class, 591–630
 addColumn method, 608, 614
 constructor, 596
 convertXxxIndexToModel methods, 604, 614
 default rendering actions, 600

`getAutoCreateRowSorter` method, [596](#)
`getCellRenderer` method, [619](#)
`getCellSelectionEnabled` method, [614](#)
`getColumnModel` method, [601](#), [613](#)
`getColumnSelectionAllowed` method, [614](#)
`getDefaultEditor` method, [628](#)
`getDefaultRenderer` method, [619](#), [628](#)
`getFillsViewportHeight` method, [596](#)
`getRowHeight`, `getRowMargin` methods, [613](#)
`getRowSelectionAllowed` method, [614](#)
`getSelectedColumns` method, [604](#), [608](#)
`getSelectedRows` method, [604](#)
`getSelectionModel` method, [613](#)
`getTableHeader` method, [594](#)
installing cell editors automatically, [619](#)
`moveColumn` method, [608](#), [614](#)
`print` method, [594](#), [596](#)
`removeColumn` method, [608](#), [614](#)
resize modes of, [603](#)
`setAutoCreateRowSorter` method, [594](#), [596](#), [605](#)
`setAutoResizeMode` method, [603](#), [613](#)
`setCellSelectionEnabled` method, [604](#), [614](#)
`setColumnSelectionAllowed` method, [604](#), [614](#)
`setDefaultRenderer` method, [618](#)
`setFillsViewportHeight` method, [596](#)
`setRowHeight`, `setRowMargin` methods, [603](#), [613](#)
`setRowSelectionAllowed` method, [604](#), [614](#)
`setRowSorter` method, [605](#), [614](#)
`JTextField` class, [619](#)
`JTree` class, [630–671](#)

- `addTreeSelectionListener` method, [655](#)
- constructor, [632](#), [640](#)
- `getLastSelectedPathComponent` method, [642](#), [648](#)

getSelectionPath method, 642, 648, 661
getSelectionPaths method, 656, 661
identifying nodes, 641
makeVisible method, 644, 648
scrollPathToVisible method, 644, 648
setEditable method, 645
setRootVisible method, 638, 640
setShowsRootHandles method, 637, 640
JUnit tool, 468
Just-in-time compiler, 825
JVM (Java virtual machine)
 class files in, 534
 class loaders in, 535
 creating, 825
 embedding into native code, 825–830
 specification for, 493, 547
 terminating, 826
jvm pointer (C), 825–826

K

\k, in regular expressions, 147
Kerberos protocol, 550
Kernel class, 743, 749
Kernel, of a convolution, 743
Key/value pairs. *See* Property files
Keyboard, reading from, 56, 68
KeyGenerator class, 580
 generateKey method, 580, 585
 getInstance method, 585
 init method, 585
KeyPairGenerator class, 587
KeyStoreLoginModule class, 551

Keystores, [569–571](#)
keytool program, [569–571](#)
Krb5LoginModule class, [551](#)

L

L (object), type code, [96, 806](#)
Lambda expressions, [11](#)
Landscape orientation, [707](#)
Language codes, [35, 390](#)
Language Model API, [489](#)
Language tags, [393](#)
last method (*ResultSet*), [333, 337](#)
lastDayOfXxx, lastInMonth methods (*TemporalAdjuster*), [373](#)
lastXxxTime methods (*BasicFileAttributes*), [124](#)
Layout algorithm, [760](#)
layoutPages method (*Banner*), [760](#)
Lazy operations, [3, 7, 15, 154](#)
LCD displays, [734](#)
LD_LIBRARY_PATH environment variable, [792, 830](#)
Leap seconds, [362](#)
Leap years, [367, 371](#)
Learn SQL The Hard Way (Shaw), [295](#)
Learning SQL (Beaulieu), [295](#)
Leaves (Swing), [630, 638, 663](#)
 icons for, [638–639, 651](#)
Legacy APIs, [117, 384–385](#)
Legacy data, converting into XML, [228](#)
length method
 of *Blob*, [327](#)
 of *CharSequence*, [63](#)

of *Clob*, 327
of *RandomAccessFile*, 81, 85
LIB environment variable, 830
lib/ext directory, 535
LIKE statement (SQL), 299, 329
limit method (*Stream*), 13, 50, 137
Line feed, 69, 418
 in e-mails, 287
 in regular expressions, 148
Line2D class, 674–675
Line2D.Double, Line2D.Float classes, 675, 677
lines method
 of *BufferedReader*, 72
 of *Files*, 6, 10, 51, 118
lineTo method (*Path2D.Float*), 680, 691
Linux operating system
 compiling invocation API, 829
 library path in, 792
 OpenSSL in, 576
 using GNU C compiler, 789
list method (*Files*), 124–125
ListResourceBundle class, 424
Lists, converting to streams, 50
ListSelectionModel interface
 setSelectionMode method, 604, 615
LITTLE_ENDIAN constant (*ByteOrder*), 138
Little-endian order, 76, 79, 133, 420
Load time, 499
loadClass method
 of *ClassLoader*, 537, 539
 of *URLClassLoader*, 536

`loadLibrary` method (`System`), [790](#), [792](#)

LOBs (large objects), [326–328](#)

- creating empty, [328](#)

- placing in database, [326](#)

- reading, [326](#)

Local hosts, [242](#)

Local names, [202](#)

Local variables, annotating, [479](#)

`LocalDate` class

- `datesUntil` method, [368](#), [371](#)

- `format` method, [404](#)

- `getDayOfMonth` methods, [368](#), [370](#)

- `getMonth`, `getMonthValue` methods, [370](#)

- `getYear` method, [370](#)

- `isAfter`, `isBefore`, `isLeapYear` methods, [371](#)

- legacy classes and, [385](#)

- `minus`, `minusXxx` methods, [368](#), [370](#)

- `now` method, [367](#), [370](#)

- `of` method, [367](#), [370](#), [372](#)

- `parse` method, [384](#), [404](#), [407](#)

- `plus`, `plusXxx` methods, [367–368](#), [370](#)

- `toLocalDate` method, [385](#)

- `until` method, [367](#), [370](#)

- weekends in, [368](#)

- `with` method, [372–373](#)

- `withXxx` methods, [370](#)

`localdates/LocalDates.java`, [369](#)

`LocalDateTime` class, [374](#)

- `atZone` method, [375](#)

- `format` method, [404](#)

- legacy classes and, [385](#)

- `parse` method, [404](#), [407](#)

`toLocalDateTime` method, 385
`Locale` class, 389–394
 constructor, 393
 debugging, 394
 `forLanguageTag` method, 391, 394
 `getAvailableLocales` method, 31
 `getCountry` method, 35, 394
 `getDefault` method, 392–394
 `getDisplayCountry`, `getDisplayLanguage` methods, 32, 394
 `getDisplayName` method, 392–394, 396
 `getInstance` method, 408
 `getISOCountries` method, 392, 394
 `getISOLanguages` method, 392
 `getLanguage` method, 394
 predefined objects, 391
 `setDefault` method, 392, 394
 `toLanguageTag` method, 391, 394
 `toString` method, 394
`Locales`, 388–394
 `current`, 415
 date and time formatting in, 403–407
 default, 380, 392
 dictionary ordering in, 408
 display names of, 32, 392–394
 formatting styles for, 381
 grouping, 35–36
 mapping names of, 31–32
 numbers in, 388–389, 395–403
 predefined, 391
 resources bundles and, 422–423
 variants in, 389, 423
`LocalTime` class, 373–374

format method, 404
getXxx methods, 374
isAfter, isBefore methods, 374
legacy classes and, 385
minus, minusXxx methods, 373–374
now method, 373–374
of method, 373–374
parse method, 404, 407
plus, plusXxx methods, 373–374
toLocalTime method, 385
toXxxOfDay methods, 374
withXxx methods, 374
lock method (FileChannel), 141–143
Locks, 141–143
 for the tail portion of a file, 142
 shared, 142
 unlocking, 142
Log files, 420
Log messages, adding to classes, 493–499
@LogEntry annotation, 493
Logging, code generation for, 467
logging.properties file, 282
LoginContext class, 550
 constructor, 552
 getSubject method, 552
 login, logout methods, 550, 552
LoginException, 552
LoginModule interface
 documentation for, 555
 methods of, 562
Logins
 committed, 555

modules for, 550–551
custom, 553–562
separating from action code, 555

Long class

MAX_VALUE constant, 142

LONG NVARCHAR data type (SQL), 357

long type

printing, 69

streams of, 43–49

type code for, 96, 806

vs. C types, 793

writing in binary format, 78

LONG VARCHAR data type (SQL), 357

LongBuffer class, 139

longs method

of Random, 45

of RandomGenerator, 48

of SplittableRandom, 52

LongStream interface, 43–49

average method, 44, 47

boxed method, 44, 47

mapToLong method, 44

max, min methods, 44, 47

of method, 47

range, rangeClosed methods, 44, 47

sum, summaryStatistics methods, 44, 47

toArray method, 44, 47

LongSummaryStatistics class, 27, 30–31, 44, 49

Look-and-feel

displaying trees in, 636

handles for subtrees in, 652

selecting multiple nodes in, 656

lookingAt method (`Matcher`), [157](#)
lookup method (`MethodHandles`), [518](#)
`LookupOp` class, [740–741](#)
 constructor, [748](#)
lookupPrintServices method (`PrintServiceLookup`), [770–771](#)
lookupStreamPrintServiceFactories method (`StreamPrintServiceFactory`), [773](#)
`LookupTable` class, [742](#)
LSB (least significant byte), [79](#)
LSSerializer interface, [215](#)
LSSerializer interface, [214](#)
 `writeToString` method, [215](#)
`<`, entity reference, [164](#)

M

Mac OS X
 character encodings in, [418](#)
 OpenSSL in, [576](#)
 resources in, [421](#)
Mac Roman encoding, [418](#)
`mail/MailTest.java`, [289](#)
main method, [534](#)
`makeShape` method (`ShapeMaker`), [681](#)
`makeVisible` method (`JTree`), [644, 648](#)
Mandelbrot set, [735–736](#)
Mangling names, [789, 806](#)
Manifest files, [86](#)
map method
 of `FileChannel`, [132, 137](#)
 of `HttpHeaders`, [281, 286](#)

of `Optional`, 19–20
of `Stream`, 11
mapping method (`Collectors`), 37, 41
Maps
 concurrent, 32
 of stream elements, 31–34, 50
`mapToInt` method (`Stream`), 42
`mapToXxx` methods (`XxxStream`), 44
mark method
 of `Buffer`, 140–141
 of `InputStream`, 58
Marker annotations, 477
`markSupported` method (`InputStream`), 59
Mastering Regular Expressions (Friedl), 149
match attribute (XSLT), 225
`match/HrefMatch.java`, 150
Matcher class, 149
 `end` method, 157
 `find` method, 157
 `group`, `groupCount` methods, 157
 `lookingAt` method, 157
 `matches` method, 157
 `quoteReplacement` method, 157
 `replaceAll` method, 154, 157–158
 `replaceFirst` method, 155, 157
 `results` method, 158
 `start` method, 157
matcher method (`Pattern`), 149, 156
matches method
 of `Matcher`, 157
 of `Pattern`, 149
`MatchResult` interface, 150

- methods of, 158
- Matrices, transformations of, 706
- max method
 - of primitive streams, 44, 46–47
 - of *Stream*, 16–17
- MAX_VALUE constant (`Long`), 142
- maxBy method (`Collectors`), 37, 40
- maxOccurs attribute (XML Schema), 187
- MD5 algorithm, 564
- Memory addresses, vs. serial numbers, 91
- Memory mapping of files, 131–141
- `memoryMap/MemoryMapTest.java`, 134
- Message digests, 563–566
 - MessageDigest class
 - digest method, 565–566
 - extending, 564
 - getInstance method, 564–566
 - reset method, 566
 - update method, 564, 566
- MessageFormat class, 413–418, 427
 - applyPattern method, 415
 - constructor, 415
 - format method, 413–415
 - get/setLocale methods, 415
 - ignoring the first limit, 417
- Meta-annotations, 469, 484–488
- Metadata (databases), 343–353
- Metal look-and-feel
 - selecting multiple nodes in, 656
 - trees in, 635–636
- Method class, 470
- Method references, type use annotations in, 480

Method verification errors, 548

MethodHandle class, 847

MethodHandles class

- lookup method, 518

Methods

- adding logging messages to, 493–499
- annotating, 468, 479, 483
- calling from native code, 809–815
- getters/setters, generated automatically, 492
- instance, 809–810
- mangling names of, 789, 806
- native, 785–847
- of annotation interfaces, 476
- overriding, 484
- protected, 537
- signatures of:
 - generating, 808
 - mangling, 806–808
 - static, 810–811

Microsoft

- Active Server Pages (ASP), 269
- compiler, 789–790
 - invocation API in, 829
- Notepad, 76
- ODBC API, 292
- SQL Server, 301
- Windows. *See Windows operating system*

MIME (Multipurpose Internet Mail Extensions), 722

- for print services, 770
- getting, of a file, 118

MimeMessage class

- methods of, 288

min method

- of primitive streams, 44, 46–47
- of *Stream*, 16–17
- minBy method (Collectors), 37, 40
- minoccurs attribute (XML Schema), 187
- minus, minusXxx methods
 - of Duration, 366
 - of Instant, 365
 - of LocalDate, 368, 370
 - of LocalTime, 373–374
 - of Period, 371
 - of ZonedDateTime, 378
- mismatch method (Files), 118–119
- MissingResourceException, 422
- Miter join, miter limit, 694
- Mixed content (XML), 163, 179
- Modernist painting example, 222–223
- Modified UTF-8, 79–80, 420
 - native code and, 795–798
- Module class
 - getResourceAsStream method, 517
- module keyword, 507
- module-info.class file, 514, 519
- module-info.java file, 507, 519
- Modules, 504–531
 - accessing, 515–518, 522
 - automatic, 518–521
 - declaration of, 507–508
 - explicit, 521
 - exporting packages, 510–514
 - loading into JShell, 515
 - migration to, 519–523
 - naming, 505–506, 519

not passing access rights, 509
open, 517
opening packages in, 517
packages with the same names in, 514
platform classes in, 535
qualified exports of, 525
requiring, 508–510
service implementations and, 526
tools for, 528–531
unnamed, 521
versioning, 505, 508

Month enumeration, 367
 getDisplayName method, 381, 405

MonthDay class, 368

move method (Files), 120–122

moveColumn method (JTable), 608, 614

moveTo method (Path2D.Float), 680–681, 691

moveToXxxRow methods (*ResultSet*), 335, 337

MSB (most significant byte), 79

Multiple-page printing, 758–761

multipliedBy method (Duration), 366

MutableTreeNode interface

- implementing, 632
- setUserObject method, 632, 640

MySQL database, 301

N

\n

- as line feed, 69, 170, 287, 418
- in regular expressions, 145–147, 156

NameCallback class, 554

- constructor and methods of, 561

NamedNodeMap interface

`getLength` method, 175

`item` method, 175

`names` method (`Win32RegKey`), 832

Namespaces, 199–202

 activating processing of, 188

 aliases (prefixes) for, 185, 201

 of attributes, 201

 of child elements, 200

 using class loaders as, 538–539

National character strings, 358

National Institute of Standards and Technology, 236, 564

`native` keyword, 787

Native methods, 785–847

 array elements in, 816–819

 calling from Java programs, 786–792

 class references in, 803

 compiling, 789

 enumerating keys with, 834

 error handling in, 819–825

 exceptions in, 820

 garbage collection and, 797

 instance fields in, 801–805

 invoking Java constructors in, 811

 linking to Java, 792

 naming, 787–788

 numeric parameters in, 793–795

 overloading, 788

 reasons to use, 786

 registry access functions in, 833–846

 static, 787

 static fields in, 805–806

 strings in, 795

`native.encoding` property, 77
`native2ascii` program, 423
NCHAR, NCLOB data types (SQL), 357–358
negated method (`Duration`), 366
Nervous text applet, 562
`net.properties` file, 282
Networking, 235–290
 connecting to a server, 235–243
 debugging, 235–238
 getting web data, 259–278
 HTTP client for, 279–286
 implementing servers, 244–259
 sending e-mails, 287–290
`newBufferedXxx` methods (`Files`), 118–119
`newBuilder` method
 of `HttpClient`, 279, 285
 of `HttpRequest`, 281, 286
`NewDirectByteBuffer` function (C), 818
`newDirectoryStream` method (`Files`), 126, 129
`newDocument` method (`DocumentBuilder`), 213, 215, 228
`newDocumentBuilder` method (`DocumentBuilderFactory`), 166, 173, 213
`newFactory` method (`RowSetProvider`), 339, 342
`newFileSystem` method (`FileSystems`), 130–131
`NewGlobalRef` function (C), 803
`newHttpClient` method (`HttpClient`), 279, 285
`newInputStream` method
 of `Channels`, 259
 of `Files`, 118–119
`newInstance` method
 of `DocumentBuilderFactory`, 166, 173, 201
 of `SAXParserFactory`, 204, 207

of TransformerFactory, 214, 216
of XMLInputFactory, 211
of XMLOutputFactory, 217, 221
of XPathFactory, 195, 199
newNSInstance method (DocumentBuilderFactory), 201–202, 205
NewObject function (C), 811, 815, 820
newOutputStream method
 of Channels, 253, 259
 of Files, 118–119
newSAXParser method (SAXParserFactory), 204, 207
NewString function (C), 798
NewStringUTF function (C), 796–797, 799, 833
newTransformer method (TransformerFactory), 214, 216, 232
newXpath method (XPathFactory), 199
NewXxxArray functions (C), 818, 833
next method
 of *ResultSet*, 308, 310, 331
 of TemporalAdjusters, 373
 of *XMLStreamReader*, 211–212
nextElement method (*Enumeration*), 649, 832–835
nextOrSame method (TemporalAdjusters), 372–373
nextPage method (*CachedRowSet*), 340, 342
NMOKEN, NMOKENS attribute types (DTDs), 180–181
No-argument constructors, 101, 113
Node interface
 appendChild method, 213, 215
 getAttributes method, 170, 174
 getChildNodes method, 167, 174
 getFirstChild method, 169, 174
 getLastChild method, 169–170, 174
 getLocalName method, 202

getNamespaceURI method, 202
getNextSibling method, 169–170, 174
getNodeXxx methods, 170, 174, 202
getParentNode method, 174
getPreviousSibling method, 174
subinterfaces of, 167

nodeChanged method (`DefaultTreeModel`), 643, 649

NodeList interface, 167

- getLength method, 167, 175
- item method, 167, 175, 183

Nodes (Swing), 630

- adding, 643
- child, 630, 633
- collapsed, 645
- connecting lines for, 636–637
- currently selected, 642
- editing, 645, 664
- enumerating, 649–651
- expanding, 643, 645
- handles for, 635, 637, 652
- highlighting, 652
- identifying, by tree paths, 641
- making visible, 644
- parent, 630, 633
- removing, 643
- rendering, 639, 651–654
- root, 630–638
- row positions of, 643
- searching, 651, 656
- selecting, 655
- user objects for, 632, 643, 651, 656

nodesChanged method (`DefaultTreeModel`), 649

Nondeterministic parsing, 180

noneMatch method (*Stream*), 17
Noninterference, of stream operations, 7
@NonNull annotation, 480–481
Normalization, 409
normalize method
 of *Normalizer*, 413
 of *Path*, 116–117
Normalized color values, 733
Normalizer class, 410
 normalize method, 413
NoSuchAlgorithmException, 566, 584
NoSuchElementException, 20–21, 835
notFilter method (*RowFilter*), 607, 616
NotSerializableException, 102
now method
 of Instant, 363, 365
 of LocalDate, 367, 370
 of LocalTime, 373–374
 of ZonedDateTime, 378
NTLoginModule class, 551
nullInputStream method (*InputStream*), 59
nullOutputStream method (*OutputStream*), 59
NullPointerException, 821
 vs. Optional, 16
Number class
 doubleValue method, 396
 intValue method, 396
numberFilter method (*RowFilter*), 606, 616
NumberFormat class, 395–403
 format method, 396, 398
 get/setXxxDigits methods, 399

getAvailableLocales method, 391, 396, 398
getCompactNumberInstance method, 398
getCurrencyInstance method, 395, 398, 402
getNumberInstance method, 395, 398
getPercentInstance method, 395, 398
is/setGroupingUsed methods, 399
is/setParseIntegerOnly methods, 399
parse method, 395–396, 399
setCurrency method, 402
numberFormat/NumberFormatTest2.java, 397

Numbers

- filtering, 606–607
- floating-point, 388, 395–403
- formatting, 388–389, 395–403, 413–415
 - supported locales for, 396
 - with C, 793
- from grouped elements, 36
- in regular expressions, 146
- printing, 69
- random, 5, 13, 45, 581
- reading:
 - from files, 65
 - from ZIP archives, 66
 - using locales, 395
- storing in memory, 79
- writing in binary format, 78

NUMERIC data type (SQL), 301, 357
NVARCHAR data type (SQL), 357

O

Object class

- clone method, 89, 110

Object inspection tree, 662–671
Object serialization, 89–114
 cloning with, 110–113
 file format for, 94–101
 modifying default, 101–104
 of singletons, 104–107
 serial numbers for, 90–91
ObjectInputStream class, 89
 constructor, 94
 readObject method, 89, 94, 102
ObjectInputValidation interface, 113–114
ObjectOutputStream class, 89–90
 constructor, 94
 defaultWriteObject method, 102
 writeObject method, 89, 94, 102
Object-relational mappers, 516
Objects
 cloning, 110–113
 converting to streams, 6, 24
 fingerprints of, 95
 printing, 69
 reading from an input stream, 89
 saving:
 in database, 487
 in output streams, 89–90
 in text format, 72–75
 serializable, 89–94
 transmitting over network, 91
 type code for, 96, 806
 versioning, 107–110
ODBC API, 292, 294
of method
 of *DoubleStream*, 47

of *IntStream*, 44, 46
of *LocalDate*, 367, 370, 372
of *LocalTime*, 373–374
of *LongStream*, 47
of *Optional*, 21–22
of *Path*, 115
of *Period*, 371
of *Stream*, 5, 9
of *ZonedDateTime*, 375, 378
of *ZoneId*, 375
ofDateAdjuster method (*TemporalAdjusters*), 372
ofDays method
 of *Duration*, 365
 of *Period*, 367, 371, 376
offile, offileDownload methods (*BodyHandlers*), 281
OffsetDateTime class, 376
ofHours method (*Duration*), 365
ofInstant method (*ZonedDateTime*), 378
ofLocalizedXxx methods (*DateTimeFormatter*), 380, 383, 403, 407
ofMillis, ofMinutes methods (*Duration*), 365
ofMonths method (*Period*), 368, 371
ofNanos method (*Duration*), 365
ofNullable method
 of *Optional*, 21–22
 of *Stream*, 6, 9, 24
ofPattern method (*DateTimeFormatter*), 381, 384
ofSeconds method (*Duration*), 365
ofString method (*BodyHandlers*, *BodyPublishers*), 280–281
ofWeeks, ofYears methods (*Period*), 371
obj literal (SQL), 328

open keyword, [517](#)
open method
 of `FileChannel`, [132](#), [137](#)
 of `SocketChannel`, [252](#), [259](#)
openConnection method (`URL`), [262](#), [267](#)
openOutputStream method (`SimpleJavaFileObject`), [467](#)
opens keyword, [517](#), [525](#)
OpenSSL toolkit, [576](#)
openStream method (`URL`), [64](#), [259](#), [267](#)
Operating system
 character encodings in, [77](#), [418](#)
 default locales in, [392](#)
 paths in, [64](#), [115](#)
 resources in, [421](#)
Operations
 associative, [42](#)
 lazy, [3](#), [7](#), [15](#), [154](#)
 stateless, [49](#)
Optional class, [16–23](#)
 creating values of, [21](#)
 empty method, [21–22](#)
 filter method, [19–20](#)
 flatMap method, [22–26](#)
 for empty streams, [41–42](#)
 get method, [20–23](#)
 ifPresent method, [18–19](#)
 ifPresentOrElse method, [19](#)
 isPresent method, [20–23](#)
 map method, [19–20](#)
 of, ofNullable methods, [21–22](#)
 or method, [20](#)
 orElse method, [16](#), [18](#)

orElseGet method, 18
orElseThrow method, 18, 21
stream method, 23–26
optional keyword, 551
optional/OptimalTest.java, 24
OptionalInt, OptionalDouble, OptionalLong classes, 44, 48
Oracle
 JDBC, 292, 301
 JVM implementation, 77, 818
ORDER BY statement (SQL), 309
order method (ByteBuffer), 133, 138
orElse, orElseGet methods (OptionalXxx), 48
orFilter method (RowFilter), 607, 616
org.omg.corba package, 504
org.w3c.dom package, 166
 org.w3c.dom.CharacterData API, 175
 org.w3c.dom.Document API, 174, 215
 org.w3c.dom.Element API, 174, 215
 org.w3c.dom.NamedNodeMap API, 175
 org.w3c.dom.Node API, 174, 202, 215
 org.w3c.dom.NodeList API, 175
 org.xml.sax.Attributes API, 208
 org.xml.sax.ContentHandler API, 207–208
 org.xml.sax.EntityResolver API, 183
 org.xml.sax.ErrorHandler API, 184
 org.xml.sax.helpers.AttributesImpl API, 233
 org.xml.sax.InputSource API, 184
 org.xml.sax.SAXParseException API, 184
 org.xml.sax.XMLReader API, 233
Orientation, 104–105
Outer joins, 328

`OutOfMemoryError`, 821
`output` element (XSLT), 225
Output streams, 56–78
 buffered, 65–67
 byte processing in, 65
 byte-oriented, 56
 closing, 57, 251
 filters for, 64–67
 hierarchy of, 59–63
 objects in, 89–114
 redirecting, 447–448
 Unicode and, 56
OutputStream class, 56, 61–62, 217
 `close` method, 59
 `flush` method, 57, 59
 `nullOutputStream` method, 59
 `write` method, 57, 59
OutputStreamWriter class, 68
OverlappingFileLockException, 142
Overloading, 788
`@Override` annotation, 483–484

P

`\p`, `\P`, in regular expressions, 146
Package class, 470
`package-info.java` file, 479
Packages, 504
 annotating, 479, 483
 avoiding name clashes with, 538–539
 exporting, 510–514
 hidden, 514
 opening, 517

split, 514

Packets, 240

Padding schemes, 580

Page setup dialog box, 753–754

Pageable interface

- implementing, 759
- objects, printing, 769

PageAttributes class (obsolete), 783

pageDialog method (PrinterJob), 753, 755, 758

PageFormat class

- getHeight method, 752, 759
- getImageableXxx methods, 752, 759
- getOrientation method, 759
- getWidth method, 752, 759

Pages

- measurements of, 752–753
- multiple, printing, 759–769
- orientation of, 707, 753, 759

Paint interface, 701–703

paint method (JComponent), 617, 672

paintComponent method

- of JComponent, 672
- of StrokePanel, 696

panama/PanamaDemo.java, 847

Paper

- margins of, 752
- sizes of, 425, 752

parallel method (*BaseStream*), 53

parallel/ParallelStreams.java, 52

parallelStream method (*Collection*), 2–4, 49–53

Parameter variables, annotating, 479

Parent nodes (Swing), 630, 633

`parse` method
 of `DateTimeFormatter`, 381
 of `DocumentBuilder`, 173
 of `LocalDate`, 384, 404, 407
 of `LocalDateTime`, `LocalTime`, 407
 of `NumberFormat`, 395–396, 399
 of `SAXParser`, 204, 207
 of `XMLReader`, 233
 of `ZonedDateTime`, 384, 404, 407

Parsed character data, 179

`ParseException`, 396, 398

Parsers, 165–175
 checking uniqueness of IDs in, 181, 189
 pull, 208
 validating in, 176

Parsing (XML), 165–175
 nondeterministic, 180
 with XML Schema, 188

`partitioningBy` method (`Collectors`), 35–36, 38

`PasswordCallback` class, 554
 constructor and methods of, 561

Password-protected resources, 264

`Path` interface, 115–118
 `getXxx` methods, 116–117
 `normalize` method, 116–117
 `of` method, 115
 `relativize` method, 116–117
 `resolve`, `resolveSibling` methods, 116–117
 `toAbsolutePath`, `toFile` methods, 116–117

`Path2D` class
 `append` method, 681, 691, 711
 `closePath` method, 680, 691

`Path2D.Double` class, 675, 677
`Path2D.Float` class, 675, 677
 `curveTo`, `lineTo`, `moveTo`, `quadTo` methods, 680–681, 691
`pathFromAncestorEnumeration` method
(`DefaultMutableTreeNode`), 650
Paths (file system), 115–118
 absolute vs. relative, 64, 115–116
 checking properties of, 123–124
 filtering, 125
 relativizing, 116
 resolving, 66, 116
 root component of, 115
 separators in, 64, 115
Paths (graphics), 680–681
Paths class, 130
 `get` method, 115, 117
Pattern class, 149
 `asMatchPredicate`, `asPredicate` methods, 149
 `compile` method, 149, 155–156
 `flags`, 155–158
 `matcher` method, 149, 156
 `matches` method, 149
 `split` method, 154, 156
 `splitAsStream` method, 6, 10, 154, 156
Patterns, 143–158
#PCDATA element content (DTD), 178–179
PDF format, 769
 `peek` method (*Stream*), 15–16
PEM (Privacy Enhanced Mail), 576
Pentium processor, little-endian order in, 79
Percentages, formatting, 395–396
Performance

of encryption algorithms, 587

of file operations, 131–139

Period class

getXxx methods, 371

minus, minusXxx methods, 371

of method, 371

ofXxx methods, 367–368, 371, 376

plus, plusXxx methods, 371

using for daylight savings time, 376

withXxx methods, 371

Perl programming language, 149

@Persistent annotation, 487

Personal data, 578

Picocli framework, 469

Pixels

affine transformations on, 740

average value of, 743

composing, 712–721

interpolating, 701–702, 741

sample values of, 733

setting individual, 733–740

Placeholders, in messages, 413–418

Plugins, loading, 536

plus, plusXxx methods

of Duration, 366

of Instant, 365

of LocalDate, 367–368, 370

of LocalTime, 373–374

of Period, 371

of ZonedDateTime, 378

PNG format, 722

printing, 769

Point2D class, [677](#)
Point2D.Double class, [102](#), [675](#), [677](#)
Point2D.Float class, [675](#), [677](#)
Points, in typography, [752](#)
Policy files, [577](#)
Polygons, [675](#), [681](#)
Pools, for parallel streams, [51](#)
populate method (*CachedRowSet*), [339](#), [342](#)
Porter–Duff rules, [713–716](#)
Portrait orientation, [753](#)
Ports, [237](#)

- blocking, [236](#)
- in URIs, [261](#)

position function (XPath), [227](#)
position method (Buffer), [141](#)
POSIX-compliant file systems, [123](#)
PosixFileAttributes interface, [123](#)
POST method (*HttpRequest.Builder*), [280](#), [286](#)
POST request (HTML), [270](#), [272–274](#)

- building, [280](#)

post/*PostTest.java*, [275](#)
@PostConstruct annotation, [483](#)
PostgreSQL database, [301](#)

- connecting to, [305](#)
- drivers for, [302](#)

Postorder traversal, [650](#)
postOrderEnumeration method (*DefaultMutableTreeNode*),
[650](#), [654](#)
PostScript format

- printing, [769](#), [772](#)
- writing to, [772](#)

postVisitDirectory method

of *FileVisitor*, 127
of *SimpleFileVisitor*, 130
Predefined character classes, 144, 146, 148
`@PreDestroy` annotation, 483
Predicate functions, 35
premain method (Instrumentation API), 499
preOrderEnumeration method (*DefaultMutableTreeNode*), 650, 654
Prepared statements, 319–326
 caching, 320
 executing, 320
PreparedStatement interface
 clearParameters method, 325
 executeXxx methods, 320, 326
 setXxx methods, 320, 325
prepareStatement method (*Connection*), 319–320, 325, 331, 336
previous method (*ResultSet*), 332, 336
previous, previousOrSame methods (*TemporalAdjusters*), 373
previousPage method (*CachedRowSet*), 342
preVisitDirectory method
 of *FileVisitor*, 127
 of *SimpleFileVisitor*, 130
Primitive types
 arrays of, 818
 I/O in binary format in, 60
 streams of, 42–49
Principal interface
 getName method, 553
Principals (logins), 551
Print dialog box, 750

displaying page ranges in, 751, 759
native, 751, 755

print method
of *DocPrintJob*, 772
of *JTable*, 594, 596
of *Printable*, 749, 758–759
of *PrintWriter*, 69–70, 809–810

Print services, 769–772
document flavors for, 769–770
for images, 771
stream, 772–775

print, *println* functions (JavaScript), 448

print/*PrintComponent.java*, 756

print/*PrintTestFrame.java*, 755

Printable interface
implementing, 749, 753
objects, printing, 769
print method, 749, 758–759

Printer graphics context, 760

PrinterException, 750

PrinterJob class
defaultPage method, 758
getPrinterJob method, 749, 758
pageDialog method, 753, 755, 758
print method, 750–751, 758
printDialog method, 750–751, 758
setPageable method, 759
setPrintable method, 758

printf function (C), 793

printf method (*PrintWriter*), 69–70, 393

printf/*Printf1.c*, 794

printf/*Printf1.java*, 794

printf1/Printf1Test.java, 795
printf2/Printf2.c, 800
printf2/Printf2.java, 799
printf2/Printf2Test.java, 799
printf3/Printf3.c, 812
printf3/Printf3.java, 812
printf3/Printf3Test.java, 812
printf4/Printf4.c, 821
printf4/Printf4.java, 823
printf4/Printf4Test.java, 824

Printing

clipped areas, 752
counting pages during, 751
images, 749–759
layout of, 760
multipage documents, 758–761
number of copies for, 776
page orientation of, 707, 753
paper sizes in, 752
quality of, 779
selecting settings for, 750
starting, 749
text, 749–759
using:
 banding for, 751
 transformations for, 761

Printing attributes, 776–784

adding, 779
categories of, 778–779
checking values of, 779
hierarchy of, 777
retrieving, 779

PrintJob class (obsolete), 749

PrintJobAttribute interface, 776
printing attributes of, 780–783
PrintJobAttributeSet interface, 777
println method
of *PrintWriter*, 69–70, 72
of *System.out*, 418–419
PrintQuality class, 779
PrintRequestAttribute interface, 776
printing attributes of, 780–783
PrintRequestAttributeSet interface, 750, 777
PrintService interface
createPrintJob method, 771–772
getAttributes method, 784
getName method, 771
printService/PrintServiceTest.java, 774
PrintServiceAttribute interface, 776
printing attributes of, 780–783
PrintServiceAttributeSet interface, 777
PrintServiceLookup class
lookupPrintServices method, 770–771
PrintStream class, 69
PrintWriter class, 68–70
checkError method, 69–70
constructor, 70
print method, 69–70, 809–810
printf method, 69–70, 393
println method, 69–70, 72
Private keys, 566, 587
probeContentType method (*Files*), 118–119
processAnnotations method (*ActionListenerInstaller*),
470

Processing instructions (XML), [165](#)
Processing tools, [467](#)
Processor interface, [488](#)
Programmer’s Day, [367](#)
Programs. *See* [Applications](#)
Project Panama, [846–848](#)
Properties class, [160](#)
Property files, [160](#)
 character encoding of, [423](#)
 event handlers in, [451](#)
 for resources bundles, [422–423](#)
 for string resources, [421](#)
 for strings, [423](#)
 no passwords in, [288](#)
@Property annotation, [492](#)
provides keyword, [528](#)
Proxy objects, [470](#)
PUBLIC identifier (DTD), [214](#)
Public key ciphers, [566–573](#), [587–590](#)
 performance of, [587](#)
Public Key Cryptography Standard (PKCS) #[5](#), [580](#)
Pull parsers, [208](#)
PushbackInputStream class, [65](#)
 constructor, [67](#)
 unread method, [67](#)
put method
 of *Bindings*, [447](#)
 of ByteBuffer, [137–138](#)
 of CharBuffer, [139](#)
 of ScriptEngine, [447](#)
 of ScriptEngineManager, [447](#)
PUT method (`HttpRequest.Builder`), [286](#)

`putClientProperty` method (`JComboBox`), [636](#), [641](#)
`putNextEntry` method (`ZipOutputStream`), [86](#)–[87](#)
`putXxx` methods (`ByteBuffer`), [133](#), [138](#)

Q

\Q, in regular expressions, [145](#)
QBE (query by example) tools, [297](#)–[298](#)
QuadCurve2D class, [674](#), [680](#)
QuadCurve2D.Double class, [675](#), [677](#), [690](#)
QuadCurve2D.Float class, [675](#), [677](#)
Quadratic curves, [679](#)–[680](#)
quadTo method (`Path2D.Float`), [680](#), [691](#)
Qualified exports, [525](#)
Qualified names (XML), [202](#)
Queries (databases), [298](#)–[300](#)

- by example, [297](#)–[298](#)
- executing, [308](#), [319](#)–[331](#)
- multiple, [311](#)
- populating row sets with results of, [340](#)
- preparing, [319](#)–[326](#)
- returning multiple results, [329](#)–[330](#)

query/QueryTest.java, [321](#)
", entity reference, [164](#)
quoteReplacement method (`Matcher`), [157](#)

R

R programming language, [444](#), [451](#)
\r line feed character, [69](#), [170](#), [418](#)

- in e-mails, [287](#)

\r, \R, in regular expressions, [145](#), [148](#)
Race conditions, [49](#)

Random class, 581
methods of, 45

Random numbers, streams of, 5, 13, 45, 48, 52

Random-access files, 81–85

randomAccess/RandomAccessTest.java, 83

RandomAccessFile class, 81–85, 131

- constructor, 85
- getChannel method, 136
- getFilePointer method, 81, 85
- length method, 81, 85
- seek method, 81, 85

RandomGenerator class

- methods of, 48

Randomness, 581

range, rangeClosed methods (*XxxStream*), 44, 46–47

Ranges, converting to streams, 50

Raster class

- getDataElements method, 735, 738
- getPixel, getPixels methods, 734, 739

Raster images, 721–749

- constructing from pixels, 733–740
- filtering, 740–749
- readers/writers for, 722–732

rasterImage/RasterImageFrame.java, 736

read method

- of CipherInputStream, 586
- of FileInputStream, 56
- of ImageIO, 722, 729
- of ImageReader, 731
- of InputStream, 56–58
- of Readable, 62–63
- of Reader, 60

read/config.dtd, 193
read/config.xml, 192
read/config.xsd, 193
read/XMLReadTest.java, 189
Readable interface, 61
 read method, 62–63
ReadableByteChannel interface, 253
readAllBytes method (*InputStream*), 56, 58
readAllXxx methods (*Files*), 118–119
readAttributes method (*Files*), 123–124
readBoolean method (*DataInput*), 79–80
readChar method (*DataInput*), 79–81
readDouble method (*DataInput*), 79–80, 90, 102
Reader class, 56, 61
 read method, 60
READER class (*DocFlavor*), 770
readExternal method (*Externalizable*), 103–104
readFixedString method (*DataIO*), 82
readFloat method (*DataInput*), 79–80
readFully method (*DataInput*), 80
readInt method (*DataInput*), 79–81, 90
readLine method (*Console*), 71
readLong method (*DataInput*), 79–80
readNBytes method (*InputStream*), 56, 58
readObject method
 of *HashSet*, 102
 of *ObjectInputStream*, 89, 94, 102
ReadOnlyBufferException, 132
readResolve method (*Serializable*), 105–107
readShort method (*DataInput*), 79–80
readString method (*Files*), 118–119

readThumbnail method (`ImageReader`), 731
readUTF method (`DataInput`), 79–80
REAL data type (SQL), 301, 357
Receiver parameters, 482
Records, 72–75

- customizing serialization of, 104
- deserializing, 113
- fixed-size, 82–83
- ignoring `serialVersionUID` fields, 110

Rectangle2D class, 674–675
Rectangle2D.Double, Rectangle2D.Float classes, 675
RectangularShape class, 675
Redirects, of URLs, 274–275
reduce method (`Stream`), 41–43
reducing method (`Collectors`), 38
Reductions, 16, 41–43
`ref` attribute (XML Schema), 186
Reflection

- accessing:
 - private members, 515–518, 522
 - protected methods, 537
- constructing class trees, 656
- enumerating fields from a variable, 665

regex/RegexTest.java, 153
regexFilter method (`RowFilter`), 607, 616
Registry editor, 831, 836
Registry keys, 832–834
Regular expressions, 143–158

- escapes in, 73
- filtering, 607
- finding matches of, 149
- flags for, 155–158

groups in, 151–154
in DTDs, 179–180
splitting sequences with, 6
relative method (*ResultSet*), 333, 337
Relativization, in URLs, 261
relativize method (*Path*), 116–117
releaseSavepoint method (*Connection*), 354, 356
ReleaseStringChars function (C), 798
ReleaseStringUTFChars function (C), 797–799
ReleaseXxxArrayElements functions (C), 816–817, 819
reload method (*DefaultTreeModel*), 643, 649
remaining method (*Buffer*), 140–141
remove method (*AttributeSet*), 784
removeCellEditorListener method (*CellEditor*), 630
removeColumn method (*JTable*), 608, 614
removeNodeFromParent method (*DefaultTreeModel*), 643, 649
removeTreeModelListener method (*TreeModel*), 663, 671
RenderableImage interface, 769
Rendering (Swing)
 cells, 617–619
 columns, 600
 headers, 619
 nodes, 651–654
Rendering pipeline (AWT), 672–674
Renjin project, 444, 452
@Repeatable annotation, 483
replaceAll method
 of *Matcher*, 154, 157–158
 of *String*, 155
replaceFirst method (*Matcher*), 157
 of *Matcher*, 155

required keyword, [551](#)
#REQUIRED attribute (DTD), [181](#)
requires keyword, [508](#), [510](#), [512–513](#), [519](#), [523–525](#)
requisite keyword, [551](#)
RescaleOp class, [740](#), [747](#)
Rescaling operation, [741](#)
reset method
 of Buffer, [140–141](#)
 of InputStream, [59](#)
 of MessageDigest, [566](#)
resolve method (*Path*), [116–117](#)
resolveEntity method (*EntityResolver*), [177](#), [183](#)
resolveSibling method (*Path*), [116–117](#)
Resolving
 classes, [534](#)
 relative URLs, [261](#)
Resource bundles, [421–426](#)
 loading, [423–424](#)
 locating, [422–423](#)
 lookup tables for, [424](#)
 naming, [424](#)
 searching for, [424](#)
Resource editors, [421](#)
@Resource annotation, [359](#), [483](#)
 ResourceBundle class
 extending, [424–425](#)
 getBundle method, [422–425](#)
 getKeys method, [425–426](#)
 getObject method, [424–425](#)
 getString method, [423](#), [425](#)
 getStringArray method, [426](#)
 handleGetObject method, [425–426](#)

`ResourceBundle.Control` class
 `getCandidateLocales` method, [423](#)

Resources
 hierarchy of, [422](#)
 in JAR files, [517](#)

`@Resources` annotation, [483](#)

ResourceScope interface, [847](#)

Response headers, [264–265](#)

Response pages, [269](#)

Result interface, [227–228, 358](#)

Result sets (databases)
 accessing columns in, [309](#)
 analyzing, [308](#)
 closing, [312](#)
 for multiple queries, [311](#)
 iterating over rows in, [331](#)
 metadata for, [344](#)
 numbering rows in, [333](#)
 order of rows in, [309](#)
 retrieving multiple, [329–330](#)
 scrollable, [331–333](#)
 updatable, [331, 334–338](#)

`results` method (`Matcher`), [158](#)

ResultSet interface, [338](#)
 `absolute` method, [333, 337](#)
 `afterLast`, `beforeFirst` methods, [333, 337](#)
 `cancelRowUpdates` method, [335, 338](#)
 `close` method, [311–312](#)
 concurrency values, [333–334, 336, 338](#)
 `deleteRow` method, [335, 337](#)
 `findColumn` method, [311](#)
 `first` method, [333, 337](#)
 `getBlob`, `getClob` methods, [326–327](#)

getConcurrency method, 332, 334, 336
getDate, getDouble, getInt methods, 309, 311
getMetaData method, 344, 353
getObject method, 309, 311
getRow method, 333, 337
getString method, 309, 311
getType method, 332, 336
getWarnings method, 314
insertRow method, 335, 337
isAfterLast, isBeforeFirst methods, 333, 337
isClosed method, 311
isFirst, isLast methods, 333, 337
iteration protocol, 308
last method, 333, 337
moveToXxxRow methods, 335, 337
next method, 308, 310, 331
previous method, 332, 336
relative method, 333, 337
type values, 333–334, 336, 338
updateXxx methods, 311, 334–335, 337–338

ResultSetMetaData interface, 344
 getColumnXxx methods, 344, 353

Retention policies, 485
 @Retention annotation, 469, 483, 485
 retire/Retire.java, 428
 retire/RetireResources_de.java, 440
 retire/RetireResources_zh.java, 440
 retire/RetireResources.java, 439
 retire/RetireStrings_de.properties, 441
 retire/RetireStrings_zh.properties, 441
 retire/RetireStrings.properties, 441

Retirement calculator example, 426–442

RETURN_GENERATED_KEYS field (*Statement*), 331
Return values, missing, 16
 rewind method (*Buffer*), 140–141
RFC 821 standard, 287
RFC 822 standard, 380
RFC 1123 standard, 380
RFC 2396 standard, 261
RFC 2616 standard, 263
RFC 2911 standard, 783
RGB color model, 712, 734
Rhino engine, 444, 452
Rivest, Ronald, 564, 568, 587
Role-based authentication, 553
 rollback method (*Connection*), 354–356
Root component (file system), 115
Root element (XML), 163
 referencing schemas in, 185
Root node (Swing), 630–638
 handles for, 637–638
 separating children of, 637
rotate method (*Graphics2D*), 705, 709
Rotation, 704–705
 interpolating pixels and, 741
 with center point, 705
Round cap, 693
Round join, 694
Rounded rectangles, 677
 RoundEnvironment interface, 489
RoundRectangle2D class, 674–675, 677
RoundRectangle2D.Double class, 675, 677, 690
RoundRectangle2D.Float class, 675, 677
Row sets (databases), 338–342

cached, 339–344
constructing, 339
modifying, 339
page size of, 340

RowFilter class, 606–608
 andFilter method, 607, 616
 dateFilter method, 607, 616
 include method, 607, 616
 notFilter method, 607, 616
 numberFilter method, 606, 616
 orFilter method, 607, 616
 regexFilter method, 607, 616

RowFilter.Entry class, 607

ROWID data type (SQL), 357–358

RowId interface, 358

Rows (databases), 295
 deleting/inserting, 335
 iterating through, 334
 order of, in result set, 309
 retrieving, 358
 selecting, 298
 updating, 334–338

Rows (Swing)
 filtering, 606–608
 height of, 603
 hiding, 608
 margins of, 603
 position, in a node, 643
 resizing, 603
 selecting, 593–594, 604
 sorting, 594, 605–606

RowSet interface, 338–341
 execute method, 341

getXxx methods, 341
setXxx methods, 340–341

RowSetFactory interface
 createCachedRowSet method, 339–340, 342
 createXxxRowSet methods, 342

RowSetProvider class
 newFactory method, 339, 342

RSA algorithm, 568, 587

RSA Security, Inc., 580

rsa/RSATest.java, 588

rt.jar file, 530, 535

Ruby programming language, 444

run method (*Tool*), 457, 465

Runnable interface, 248

Runtime class
 exec method, 114

Runtime image file, 530

runtimeAnnotations/ActionListenerFor.java, 474

runtimeAnnotations/ActionListenerInstaller.java, 471

S

S (short), type code, 96, 806
\s, \S, in regular expressions, 146
@SafeVarargs annotation, 483

Sample values of pixels, 733

Sandbox, 577

Save points (databases), 354

Savepoint interface
 getSavepointXxx methods, 356

SAX (Simple API for XML) parser, 165, 203–208

activating namespace processing in, 205
`sax/SAXTest.java`, 206
SAXParseException class
 `getXxxNumber` methods, 184
SAXParser class
 `parse` method, 204, 207
SAXParserFactory class
 `is/setNamespaceAware` methods, 207
 `is/setValidating` methods, 207
 `newInstance`, `newSAXParser` methods, 204, 207
 `setFeature` method, 205
SAXResult class, 228
SAXSource class, 227–228
 constructor, 233
Scalar functions, 328
`scale` method (`Graphics2D`), 704–705, 709
Scaling, 704–705
Scanner class, 70–72
 constructor, 116, 253
 `findAll` method, 158
 `tokens` method, 6, 10
 `useLocale` method, 393, 396
Scheduling applications
 computing dates for, 372–373
 time zones and, 367, 375
schema element (XML Schema), 187
Schemas, 352
Scheme programming language, 444
`script/ScriptTest.java`, 453
ScriptContext interface, 447
 `getXxx/setXxx` methods, 447–448

ScriptEngine interface

- createBindings method, [447](#)
- eval method, [445–447](#)
- get method, [447](#)
- getContext method, [448](#)
- put method, [447](#)

ScriptEngineFactory interface

- getExtension method, [445](#)
- getMethodCallSyntax method, [449](#)
- getMimeTypes method, [445](#)
- getNames method, [445](#)

ScriptEngineManager class, [444](#)

- get method, [447](#)
- getEngineXxx methods, [444–445](#)
- put method, [447](#)

Scripting engines, [444–445](#)

- adding variable bindings to, [446](#)
- calling functions in, [448–450](#)
- implementing Java interfaces, [449](#)
- invoking, [445](#)

Scripting languages, [444–456](#)

Scripts, [444](#)

- accessing classes in, [450](#)
- compiling, [450–451](#)
- executing, [446, 450](#)
- invoking, [445](#)
- redirecting I/O of, [447–448](#)
- using Java method call syntax in, [449](#)

Scroll panes (Swing)

- with tables, [593](#)
- with trees, [644–645](#)

scrollPathToVisible method (*JTree*), [644, 648](#)

SecretKey interface, 581
SecretKeySpec class, 585
Secure random generator, 581
SecureRandom class
 setSeed method, 581
Security, 533–590
 bypassing constructors, 113–114
 bytecode verification, 545–549
 class loaders, 534–549
 code signing, 534
 different levels of, 562
 digital signatures, 562–577
 encryption, 578–590
 user authentication, 549–562
Security manager, 534
“Seek forward only” mode (*ImageInputStream*), 724
seek method (*RandomAccessFile*), 81, 85
select attribute (XSLT), 226
SELECT statement (SQL), 298–299
 executing, 308
 for LOBs, 326
 multiple, in a query, 329
 not supported in batch updates, 355
Selection models, 604
send method (*HttpClient*), 285
sendAsync method (*HttpClient*), 281, 285
separator constant (*File*), 64
Separators (file system), 64, 115
sequence element (XML Schema), 187
Sequences, producing, 5
Serial numbers, 90–91
serial/ObjectStreamTest.java, 93

`@Serial` annotation, 102–103
`serialClone/SerialCloneTest.java`, 110
`Serializable` class, 110
`Serializable` interface, 89, 96, 487
 `readResolve` method, 105–107
 `writeReplace` method, 106–107
`@Serializable` annotation, 487
Serialization, 89–114
 cloning with, 110–113
 file format for, 94–101
 filters for, 114
 modifying default, 101–104
 of singletons, 104–107
 serial numbers for, 90–91
`serialver` program, 107
`serialVersionUID` constant, 107–110
`server/EchoServer.java`, 245
Servers
 accessing, 259–278
 connecting clients to, 238–240
 echo, 246–247
 implementing, 244–259
 invoking programs, 269
Server-side programs, 269–278
 redirecting URLs in, 274–275
`ServerSocket` class, 244–259
 `accept` method, 244, 247–248
 `close` method, 247
 constructor, 247
Service loading, 526–528
Service provider interfaces, 723
`SERVICE_FORMATTED` class (`DocFlavor`), 770

ServiceLoader class, [526](#)
Servlets, [269](#), [461–467](#)
Session class
 setDebug method, [288](#)
 set/Item.java, [497](#)
 set/SetTest.java, [498](#)
 setAllowsChildren method (DefaultMutableTreeNode),
 [639](#), [641](#)
 setAllowUserInteraction method (URLConnection), [262](#)
 setAsksAllowsChildren method (DefaultTreeModel), [639](#),
 [641](#)
 setAttribute, setAttributeNS methods (*Element*), [213–215](#)
 setAutoCommit method (*Connection*), [353](#), [355–356](#)
 setAutoCreateRowSorter method (JTable), [594](#), [596](#), [605](#)
 setAutoResizeMode method (JTable), [603](#), [613](#)
 setBinaryStream method (*Blob*), [327](#)
 SetBooleanArrayRegion function (C), [818](#)
 SetBooleanField function (C), [806](#)
 SetByteArrayRegion function (C), [818–819](#), [833](#)
 SetByteField function (C), [806](#)
 setCellEditor method (TableColumn), [620](#), [629](#)
 setCellRenderer method (TableColumn), [629](#)
 setCellSelectionEnabled method (JTable), [604](#), [614](#)
 setCharacterStream method (*Clob*), [327](#)
 SetCharArrayRegion function (C), [818–819](#)
 SetCharField function (C), [806](#)
 setClip method (Graphics), [710–711](#), [752](#)
 setClosedIcon method (DefaultTreeCellRenderer), [652](#),
 [654](#)
 setColumnSelectionAllowed method (JTable), [604](#), [614](#)
 setCommand method (RowSet), [340–341](#)

`setComparator` method (`DefaultRowSorter`), 606, 615
`setComposite` method (`Graphics2D`), 673, 715, 721
`setConnectTimeout` method (`URLConnection`), 262, 268
`setContentHandler` method (`XMLReader`), 233
`setContextClassLoader` method (`Thread`), 537, 545
`setCrc` method (`ZipEntry`), 88
`setCurrency` method (`NumberFormat`), 402
`setDataElements` method (`WritableRaster`), 735, 739
 `setDate` method (`PreparedStatement`), 320, 325
`setDebug` method (`Session`), 288
`setDecomposition` method (`Collator`), 413
`setDefault` method
 of `CookieHandler`, 274
 of `Locale`, 392, 394
`setDefaultNamespace` method (`XMLStreamWriter`), 221
`setDefaultRenderer` method (`JTable`), 618
`setDoInput` method (`URLConnection`), 262–263, 267
`setDoOutput` method (`URLConnection`), 262–263, 267, 272, 274
`setDouble` method (`PreparedStatement`), 320, 325
`SetDoubleArrayRegion` function (C), 818–819
`SetDoubleField` function (C), 802, 806
`setEditable` method`method` (`JTree`), 645
`setEntityResolver` method (`DocumentBuilder`), 178, 183
`setErrorhandler` method (`DocumentBuilder`), 183
`setErrorWriter` method (`ScriptContext`), 448
`setFeature` method (`SAXParserFactory`), 205
`setFillsViewportHeight` method (`JTable`), 596
`SetFloatArrayRegion` function (C), 818–819
`SetFloatField` function (C), 806
`setFrom` method (`MimeMessage`), 288
`setGroupingUsed` method (`NumberFormat`), 399

`setHeaderXxx` methods (`TableColumn`), [619](#), [629](#)
`setIfModifiedSince` method (`URLConnection`), [262](#)–[263](#), [268](#)
`setIgnoringElementContentWhitespace` method
(`DocumentBuilderFactory`), [182](#), [185](#)
`setInput` method (`ImageReader`), [730](#)
`setInstanceFollowRedirects` method
(`HttpURLConnection`), [275](#)
`setInt` method (*PreparedStatement*), [320](#), [325](#)
`SetIntArrayRegion` function (C), [818](#)–[819](#)
`SetIntField` function (C), [802](#), [806](#), [834](#)
`setLeafIcon` method (`DefaultTreeCellRenderer`), [652](#), [654](#)
`setLevel` method (`ZipOutputStream`), [87](#)
`setLocale` method (`MessageFormat`), [415](#)
`setLogWriter` method (`DriverManager`), [306](#)
`SetLongArrayRegion` function (C), [818](#)–[819](#)
`SetLongField` function (C), [806](#)
`setMaximumXxxDigits` methods (`NumberFormat`), [399](#)
`setMaxWidth` method (`TableColumn`), [602](#), [615](#)
`setMethod` method

- of `ZipEntry`, [88](#)
- of `ZipOutputStream`, [87](#)

`setMinimumXxxDigits` methods (`NumberFormat`), [399](#)
`setMinWidth` method (`TableColumn`), [602](#), [615](#)
`setName` method (`NameCallback`), [561](#)
`setNamespaceAware` method

- of `DocumentBuilderFactory`, [188](#), [201](#)–[202](#), [205](#), [213](#)
- of `SAXParserFactory`, [207](#)

`SetObjectArrayElement` function (C), [816](#), [819](#)–[820](#)
`SetObjectField` function (C), [802](#), [806](#)
`setOpenIcon` method (`DefaultTreeCellRenderer`), [652](#), [654](#)
`setOutput` method (`ImageWriter`), [732](#)

`setOutputProperty` method (`Transformer`), 214, 216
`setPageable` method (`PrinterJob`), 759
`setPageSize` method (`CachedRowSet`), 340, 342
`setPaint` method (`Graphics2D`), 672, 701–703
`setParseIntegerOnly` method (`NumberFormat`), 399
`setPassword` method
 of `PasswordCallback`, 561
 of `RowSet`, 340–341
`setPixel`, `setPixels` methods (`WritableRaster`), 733, 739
`setPreferredWidth` method (`TableColumn`), 602, 615
`setPrefix` method (`XMLStreamWriter`), 221
`setPrintable` method (`PrinterJob`), 758
`setProperty` method (`XMLInputFactory`), 209, 211
`setReader` method (`ScriptContext`), 447–448
`setReadTimeout` method (`URLConnection`), 262, 268
`setRenderingHint`, `setRenderingHints` methods
 (`Graphics2D`), 672
`setRequestProperty` method (`URLConnection`), 262–263, 268
`setResizable` method (`TableColumn`), 602, 615
`setRootVisible` method (`JTree`), 638, 640
`setRowFilter` method (`DefaultRowSorter`), 606–608, 615
`setRowHeight`, `setRowMargin` methods (`JTable`), 603, 613
`setRowSelectionAllowed` method (`JTable`), 604, 614
`setRowSorter` method (`JTable`), 605, 614
`setSavepoint` method (`Connection`), 356
`setSeed` method (`SecureRandom`), 581
`setSelectionMode` method (`ListSelectionModel`), 604, 615
`SetShortArrayRegion` function (C), 818–819
`SetShortField` function (C), 806
`setShowsRootHandles` method (`JTree`), 637, 640
`setSize` method (`ZipEntry`), 88

setSortable method (`DefaultRowSorter`), [605](#), [615](#)
setSoTimeout method (`Socket`), [240–241](#)
SetStaticXxxField functions (C), [805–806](#)
setStrength method (`Collator`), [412](#)
setString method
 of *PreparedStatement*, [320](#), [325](#)
 of *RowSet*, [340](#)
setStringConverter method (`TableRowSorter`), [615](#)
setStroke method (`Graphics2D`), [672](#), [693](#), [701](#)
setSubject method (`MimeMessage`), [288](#)
setTableName method (*CachedRowSet*), [341–342](#)
setText method (`MimeMessage`), [288](#)
setToXxx methods (`AffineTransform`), [707](#), [709](#)
setTransform method (`Graphics2D`), [707](#), [709](#)
setURL method (*RowSet*), [340–341](#)
setUseCaches method (`URLConnection`), [262](#)
setUsername method (*RowSet*), [340–341](#)
setUserObject method (*MutableTreeNode*), [632](#), [640](#)
setValidating method
 of `DocumentBuilderFactory`, [182](#), [185](#)
 of `SAXParserFactory`, [207](#)
setValue method (`Win32RegKey`), [832–834](#)
setValueAt method (*TableModel*), [600](#), [623](#)
setWidth method (`TableColumn`), [602](#), [615](#)
setWriter method (*ScriptContext*), [447–448](#)
SGML (Standard Generalized Markup Language), [161](#)
SHA-1 algorithm, [95](#), [563](#)
Shamir, Adi, [568](#), [587](#)
Shape interface, [675](#), [692](#)
 implementing, [692](#)
shape/ShapeTest.java, [682](#)

`ShapeMaker` class

`getPointCount` method, [681](#)

`makeShape` method, [681](#)

`ShapePanel` class, [682](#)

`Shapes`

 clipping, [672](#), [710–712](#)

 combining, [673](#), [691–692](#)

 control points of, [681–682](#)

 drawing, [672–675](#)

 filling, [672–673](#), [701–703](#)

 rendering, [674](#)

 transforming, [672](#)

`Shared libraries`, [792](#), [830](#)

`Shear`, [704–705](#)

`shear` method (`Graphics2D`), [705](#), [709](#)

`Shift-JIS encoding`, [77](#)

`short` type

 printing, [69](#)

 streams of, [43–49](#)

 type code for, [96](#), [806](#)

 vs. C types, [793](#)

 writing in binary format, [78](#)

`ShortBuffer` class, [139](#)

`ShortLookupTable` class, [742](#), [748](#)

`shouldSelectCell` method (`CellEditor`), [622–623](#), [630](#)

`shutdownXxx` methods (`Socket`), [252](#)

Side files, [488](#)

Signatures. *See* [Digital signatures](#)

Simple types, [185](#)

`SimpleDateFormat` class, [414](#)

`SimpleDoc` class, [771–772](#)

`SimpleFileVisitor` class, [128](#)

visitFile method, 128–129
visitFileFailed method, 128, 130
xxxVisitDirectory methods, 130
SimpleJavaFileObject class, 459
 getCharContent method, 467
 openOutputStream method, 467
SimpleScriptContext class, 447
simpleType element (XML Schema), 186
Single value annotations, 477
Singletons, serializing, 104–107
size method
 of *BasicFileAttributes*, 124
 of Files, 123–124
skip method
 of InputStream, 58
 of Stream, 13
skipBytes method (*DataInput*), 80
skipNBytes method (InputStream), 58
SMALLINT data type (SQL), 301, 357
SMTP (Simple Mail Transport Protocol), 287–290
SOAP (Simple Object Access Protocol), 505
Socket class
 connect method, 241
 constructor, 240–241
 getInputStream method, 239–240, 244
 getOutputStream method, 240, 244
 isClosed, isConnected methods, 241
 isXxxShutdown methods, 252
 setSoTimeout method, 240–241
 shutdownXxx methods, 252
socket/SocketTest.java, 239
SocketChannel class, 252

open method, 252, 259

Sockets

half-closing, 251–252

interrupting, 252–259

opening, 239

server, 244–247

timeouts of, 240–241

SocketTimeoutException, 241, 268

Software developer certificates, 577

sort method (Collections), 408

sorted method (*Stream*), 15–16

Source files

character encoding of, 420–421

reading from memory, 458

Source interface, 227, 358

Source-level annotations, 488–493

Space. *See* Whitespace

SPARC processor, big-endian order in, 79

split method

of Pattern, 154, 156

of String, 72, 154

Split packages, 514

splitAsStream method (Pattern), 6, 10, 154, 156

spliterator method (*Iterable*), 10

Spliterators class

spliteratorUnknownSize method, 6, 9

SplittableRandom class, 45

methods of, 52

sprint, sprintf functions (C), 798

SQL (Structured Query Language), 291, 295–301

changing data inside databases, 300

commands in, 303

data types in, 301, 357–358
equality testing in, 299
escapes in, 328–329
exceptions in, 312–314
executing statements in, 308–311
keywords in, 298
reading instructions from a file, 315
strings in, 299
vs. Java, 321
warnings in, 313
wildcards in, 299

SQLException class, 312–314, 332
 getXxx methods, 312, 314
 iterator method, 312, 314
 rolling back and, 354
 save points and, 356

SQLWarning class, 313, 332
 getNextWarning method, 314

SQLXML data type (SQL), 357–358

Square cap, 693

Square root, computing, 22

SQuirreL program, 345

SRC, SRC_Xxx composition rules, 714–716

src.jar file, 826

sRGB standard, 734

Standard extensions, 535

Standard input, 56

StandardCharsets class, 77–78

StandardJavaFileManager interface, 457–459
 getJavaFileObjectsFromXxx methods, 466

start method
 of Matcher, 157

of *MatchResult*, 158

startDocument method (ContentHandler), 203, 207

startElement method (ContentHandler), 203–208

Stateless operations, 49

Statement interface, 308–311

- addBatch method, 355–356
- close, closeOnCompletion methods, 310, 312
- execute method, 310, 316, 329, 331
- executeBatch method, 355–356
- executeLargeBatch method, 356
- executeLargeUpdate method, 310
- executeQuery method, 308, 310, 332, 334
- executeUpdate method, 308, 310, 331, 354
- getLargeUpdateCount method, 310
- getMoreResults method, 329–330
- getResultSet method, 310
- getUpdateCount method, 310, 330
- getWarnings method, 314
- isClosed method, 310
- RETURN_GENERATED_KEYS field, 331
- using for multiple queries, 311

Statements (databases)

- closing, 312
- complex, 321
- concurrently open, 311
- executing, 308–311
- grouping into transactions, 353–358
- in batch updates, 355
- multiple, 311
- prepared, 319–326
- truncations in, 313
- static access modifier, 524

Static fields, in native code, 805–806

Static initialization blocks, 790
Static inner classes, 92
Static methods, calling from native code, 810–811
statusCode method (`HttpResponse`), 281, 286
StAX parser, 208–212, 217–222

- namespace processing in, 209
- no indented output in, 217–218

`stax/StAXTest.java`, 210
StAXSource class, 227
stopCellEditing method (`CellEditor`), 622–623, 630
Stored procedures, 328–329
Stream interface

- allMatch, anyMatch methods, 17
- collect method, 26–29, 43
- concat method, 14
- count method, 3–4, 16
- distinct method, 15–16, 50
- dropWhile method, 14
- empty method, 5, 9
- filter method, 3–11, 16
- findAny method, 17
- findFirst method, 16–17
- flatMap method, 12
- foreach method, 26, 29
- foreachOrdered method, 26
- generate method, 5, 9, 44
- iterate method, 5, 9, 15, 44
- iterator method, 26
- limit method, 13, 50
- map method, 11
- mapToInt method, 42
- max, min methods, 16–17

noneMatch method, 17
of method, 5, 9
ofNullable method, 6, 9, 24
peek method, 15–16
reduce method, 41–43
skip method, 13
sorted method, 15–16
takeWhile method, 14
toArray method, 26, 29
toList method, 6, 26, 29
unordered method, 50

stream method

- of Arrays, 5, 9, 44
- of Collection, 2–4
- of Optional, 23–26
- of StreamSupport, 6, 10

Streaming parsers, 165, 203–212

StreamPrintService class, 773

StreamPrintServiceFactory class, 772

- getPrintService method, 773
- lookupStreamPrintServiceFactories method, 773

StreamResult class, 216, 228

Streams, 1–53

- collecting results from, 26–31
- computing values from, 41–43
- converting to/from arrays, 5, 26, 50
- creating, 5–11
- debugging, 15
- empty, 5, 16, 41–42
- encrypted, 585–586
- filtering, 23
- finite, 5
- flattening, 12, 23

for print services, 772–775
infinite, 3, 5, 13, 15
intermediate operations for, 3
noninterference of, 7
of primitive types, 42–49
of random numbers, 45
parallel, 2, 17, 26, 32, 35, 38, 42, 49–53
processed lazily, 3, 7, 15
reductions of, 16
removing duplicates from, 15
returned by `Files.lines`, 51
sorted, 15, 50
splitting/combining, 13–14
summarizing, 27
terminal operations for, 3, 16
transformations of, 11–13, 44
vs. collections, 3
`streams/CountLongWords.java`, 3
`streams/CreatingStreams.java`, 7
`streams/PrimitiveTypeStreams.java`, 45
`StreamSource` class, 227
 constructor, 233
 `transform` method, 228
`StreamSupport` class
 `stream` method, 6, 10
`String` class, 62
 `compareTo` method, 407
 `format` method, 393
 `replaceAll` method, 155
 `split` method, 72, 154
 `toLowerCase` method, 11, 393
 `toUpperCase` method, 393
 `trim` method, 169, 396

STRING class (`DocFlavor`), [770](#)
String parameters, [795–801](#)
StringBuffer class, [62, 139](#)
StringBuilder class, [62, 82](#)
Strings
 converting to code points, [11](#)
 encoding, [387, 420](#)
 fixed-size, I/O of, [82–83](#)
 in native code, [795–801](#)
 in SQL, [299](#)
 internationalizing, [421–423](#)
 ordering, [407](#)
 patterns for, [143–158](#)
 printing, [69](#)
 sorting, [408](#)
 splitting, [6](#)
 transforming to lower/uppercase, [11, 393](#)
 writing in binary format, [78](#)
StringSource class, [458](#)
Stroke interface, [693](#)
`stroke/StrokeTest.java`, [696](#)
StrokePanel class, [696](#)
Strokes, [672, 693–701](#)
 dashed, [694–695](#)
 setting, [672](#)
 styling, [693–695](#)
Stylesheets (XSLT), [223–234](#)
Subject class
 `getPrincipals` method, [553](#)
Subjects (logins), [551](#)
`subSequence` method (*CharSequence*), [63](#)
`subtract` method (*Area*), [692](#)

Subtraction operator, not associative, 42

Subtrees (Swing), 635, 652

- adding nodes to, 643
- collapsed and expanded, 635–636

Suetonius, Gaius Tranquillus, 540

sufficient keyword, 551

sum, summaryStatistics methods (primitive streams), 44, 46–47

summarizingXxx methods (Collectors), 27, 30, 37

summingXxx methods (Collectors), 36, 40

Sun, 291

SunJCE ciphers, 579

Superclasses

- adding, 110
- not serializable, 101
- type use annotations in, 480

Supplier interface

- get method, 11
- @SupportedAnnotationTypes annotation, 488
- SupportedValuesAttribute* interface, 776
- supportsBatchUpdates method (*DatabaseMetaData*), 355, 357
- supportsResultSetXxx methods (*DatabaseMetaData*), 332, 338
- @SuppressWarnings annotation, 109, 483–484

SVG (Scalable Vector Graphics), 222–223

Swing, 591–671

- generating dynamic code for, 461
- tables in, 591–630
- trees in, 630–671

Symmetric ciphers, 579–580

- performance of, 587

SyncProviderException interface, 341–342

`System` class

- `console` method, 419
- `loadLibrary` method, 790, 792

`System` class loader, 535

`SYSTEM` identifier (DTD), 177, 214

`System.err` object, 69, 457

`System.in` object, 56, 69

- character encoding and, 419

`System.out` object, 69, 457

- character encoding and, 419

`println` method, 418–419

T

`t` literal (SQL), 328

`\t`, in regular expressions, 145

Table cell renderers, 600

Table models (Swing), 592, 596–600

- updating after cell editing, 623

`table/TableTest.java`, 594

TableCellEditor interface

`getTableCellEditorComponent` method, 621–622–623, 629

 implementing, 621, 623

`tableCellRender/ColorTableCellEditor.java`, 627

`tableCellRender/ColorTableCellRenderer.java`, 626

`tableCellRender/PlanetTableModel.java`, 625

`tableCellRender/TableCellRenderFrame.java`, 624

TableCellRenderer interface

`getTableCellRendererComponent` method, 617, 629

 implementing, 617

`TableColumn` class, 601–603, 608

 constructor, 615

`setCellEditor` method, [620, 629](#)
`setCellRenderer` method, [629](#)
`setHeaderXxx` methods, [619, 629](#)
`setResizable`, `setXxxWidth` methods, [602, 615](#)
`setWidth` method, [602, 615](#)

TableColumnModel interface, [601–602](#)
 `getColumn` method, [601, 614](#)

TableModel interface, [605](#)
 `getColumnClass` method, [600, 613](#)
 `getColumnName` method, [600](#)
 `getColumnType` method, [620](#)
 `getValueAt` method, [596–597, 600, 619](#)
 `getXxxCount` methods, [596–597, 600](#)
 implementing, [596](#)
 `isCellEditable` method, [600, 619](#)
 `setValueAt` method, [600, 623](#)

`tableModel/InvestmentTable.java`, [598](#)
`tableRowColumn/PlanetTableFrame.java`, [609](#)

TableRowSorter class, [605–606](#)
 `setStringConverter` method, [615](#)

Tables (databases), [295](#)
 changing data in, [300](#)
 creating, [300](#)
 duplicating data in, [297](#)
 inspecting, [297–298](#)
 metadata for, [343](#)
 multiple, selecting data from, [299](#)
 removing, [305](#)

Tables (Swing), [591–630](#)
 asymmetric, [600](#)
 cells in:
 editing, [619–620](#)

rendering, 617–619
selecting, 604

columns in:

- accessing, 601–602
- adding/hiding, 608
- naming, 597–598
- rearranging, 593
- rendering, 600
- resizing, 593–594, 602–603
- selecting, 604

combo boxes in, 620

constructing, 593, 597

custom editors in, 621–623

headers in, 593

- rendering, 619

index values in, 604

printing, 594

relationship between classes of, 602

rows in:

- filtering, 606–608
- hiding, 608
- margins of, 603
- resizing, 603
- selecting, 593–594, 604
- sorting, 594, 605–606

scrolling, 593

text fields in, 619

TableStringConverter class

- toString method, 606, 616

takeWhile method (*Stream*), 14

@Target annotation, 469, 483–485

TCP (Transmission Control Protocol), 240

teeing method (Collectors), 38

telnet, 235–238
activating/connecting, 236
windows communicating in, 248–249

template element (XSLT), 225

Temporal interface, 365

TemporalAdjuster interface, 372

TemporalAdjusters class, 372–373
dayOfWeekInMonth method, 373
firstDayOfXxx, lastDayOfXxx methods, 373
lastInMonth method, 373
next method, 373
nextOrSame method, 372–373
ofDateAdjuster method, 372
previous, previousOrSame methods, 373

TemporalAmount interface, 365–366, 370–371

test/TestDB.java, 306

@Test annotation, 468

@TestCase, @TestCases annotations, 487

Text, 68
encoding of, 75–78
generating from XML files, 226–228
output, 68–70
printing, 749–759, 769
reading, 70–72
saving objects in, 72–75
transmitting through sockets, 244–259
vs. binary data, 68

Text fields (Swing), 619

Text files, encoding of, 418, 420

Text nodes (XML)
constructing, 213
retrieving from XML, 169

TextCallbackHandler class, [554](#)
textFile/TextFileTest.java, [73](#)
TextLayout class, [711](#)
 constructor, [712](#)
 getXxx methods, [712](#)
TextStyle enumeration, [405](#)
TextSyntax class, [779](#)
TexturePaint class, [702–703](#)
this keyword, [802](#)
 annotating, [481–482](#)
Thread class
 get/setContextClassLoader methods, [537, 545](#)
threaded/ThreadingEchoServer.java, [249](#)
ThreadedEchoHandler class, [247–251](#)
Threads
 blocking, [57, 252–259](#)
 executing scripts in, [446](#)
 Internet connections with, [247–251](#)
 race conditions in, [49](#)
 referencing class loaders in, [537](#)
Throw, ThrowNew functions (C), [819–820, 824](#)
Throwable class, [820](#)
Thumbnails, [725](#)
Time
 current, [362](#)
 formatting, [379–384, 403–407](#)
 instances of, [373](#)
 literals for, [328](#)
 local, [373–374](#)
 measuring, [363](#)
 parsing, [381](#)
 zoned, [375–379, 403](#)

Time class, 384
 valueOf method, 385
TIME data type (SQL), 301, 328, 357
Time of day service, 236
timeline/TimeLine.java, 364
Timeouts, 240–241
Timestamp class, 384
 toInstant method, 385
 valueOf method, 385
TIMESTAMP data type (SQL), 301, 328, 357
Timestamps, 379
 using instants as, 363
TimeZone class
 getTimeZone method, 385
 toZoneId method, 385
toAbsolutePath method (*Path*), 116–117
toArray method
 of AttributeSet, 784
 of primitive streams, 44, 46–47
 of Stream, 26
 of streams, 29
toCollection method (Collectors), 27, 30
toConcurrentMap method (Collectors), 32, 34
toDays method (Duration), 363, 365–366
toDaysPart method (Duration), 366
toFile method (*Path*), 117
toFormat method (DateTimeFormatter), 381, 385
toHours method (Duration), 363, 365–366
toInstant method
 of Date, 384–385
 of FileTime, 385

- of `Timestamp`, 385
- of `ZonedDateTime`, 375, 379
- `tokens` method (`Scanner`), 6, 10
- `toLanguageTag` method (`Locale`), 391, 394
- `toList` method
 - of `Collectors`, 26, 30
 - of `Stream`, 6, 26, 29
- `toLocalXxx` methods
 - of `LocalXxx`, 385
 - of `ZonedDateTime`, 379
- `toLowerCase` method (`String`), 11, 393
- `toMap` method (`Collectors`), 31–34
- `toMillis`, `toMinutes`, `toNanos` methods (`Duration`), 363, 365–366
- `toNanoOfDay` method (`LocalTime`), 374
- Tool* interface
 - `run` method, 457, 465
- `ToolProvider` class
 - `getSystemJavaCompiler` method, 457
 - `toPath` method (`File`), 117–118
 - `toSecondOfDay` method (`LocalTime`), 374
 - `toSeconds` method (`Duration`), 363, 365–366
 - `toSet` method (`Collectors`), 26, 30, 36
 - `toString` method
 - implementing with annotations, 490–493
 - of `Annotation`, 476
 - of `CharSequence`, 63
 - of `Currency`, 403
 - of `Locale`, 394
 - of `TableStringConverter`, 606, 616
 - of `Variable`, 665

`toUnmodifiableList` method (`Collectors`), 30
`toUnmodifiableMap` method (`Collectors`), 34
`toUnmodifiableSet` method (`Collectors`), 30
`toUpperCase` method (`String`), 393
`toZonedDateTime` method (`GregorianCalendar`), 384–385
`toZoneId` method (`TimeZone`), 385
Transactions, 353–358
 committing, 353
 error handling in, 355
 rolling back, 353
`transferTo` method (`InputStream`), 58
`transform` method
 of `Graphics2D`, 673, 707, 709
 of `StreamSource`, 228
 of `Transformer`, 214, 216, 227
`transform/makehtml.xsl`, 229
`transform/makeprop.xsl`, 229
`transform/TransformTest.java`, 230
Transformations, 672, 703–709
 affine, 706, 740
 composing, 705–706
 fundamental types of, 704–705
 matrices for, 706
 order of, 705
 setting, 673
 using for printing, 761
Transformer class
 `setOutputProperty` method, 214, 216
 `transform` method, 214, 216, 227
TransformerFactory class
 `newInstance` method, 214, 216
 `newTransformer` method, 214, 216, 232

transient keyword, 101–102
transitive keyword, 523–524
translate method (`Graphics2D`), 705, 709, 761
Translation, 704–705
Transparency, 712–721
Traversal order, 649–650
Tree events, 654–662
Tree models
 constructing, 632, 663
 custom, 662–671
 default, 632
Tree parsers, 165
Tree paths, 641–645
 constructing, 644, 650
Tree selection listeners, 655
`tree/SimpleTreeFrame.java`, 634
TreeCellRenderer interface, 651–654
 `getTreeCellRendererComponent` method, 652–654
 implementing, 652
`treeEdit/TreeEditFrame.java`, 645
TreeMap class, 32
TreeModel interface, 632, 642
 `add/removeTreeModelListener` methods, 663, 671
 `getChild`, `getChildCount` methods, 663–665, 670
 `getIndexofChild` method, 663, 670
 `getRoot` method, 663–665, 670
 implementing, 632
 `isLeaf` method, 640, 663, 671
 `valueForPathChanged` method, 664, 671
`treeModel/ObjectInspectorFrame.java`, 666
`treeModel/ObjectTreeModel.java`, 667
`treeModel/Variable.java`, 669

TreeModelEvent class, 671
TreeModelListener interface, 663

- treeNodesXxx methods, 663, 671
- treeStructureChanged method, 663, 671

TreeNode interface, 632, 642

- children method, 649
- getAllowsChildren method, 640
- getChildAt method, 648
- getChildCount method, 649
- getParent method, 648, 650
- isLeaf method, 639–640

TreePath class, 642

- getLastPathComponent method, 642, 648

`treeRender/ClassNameTreeCellRenderer.java`, 661
`treeRender/ClassTreeFrame.java`, 657
Trees (Swing), 630–671

- adding listeners to, 655
- background color for, 652
- connecting lines in, 636–637
- displaying, 632–649
- editing, 641–645, 664
- handles in, 635, 637, 652
- hierarchy of classes for, 633
- indexes in, 643
- infinite, 666
- leaves in, 630, 638–639, 651, 663
- nodes in, 630, 639, 651, 663
- paired with other components, 654
- rendering, 651–654
- scrolling to newly added nodes, 644–645
- structure of, 630
- subtrees in, 635–636
- traversals for, 649–651

updating vs. reloading, 643
user objects for, 632, 643
view of, 643
with horizontal lines, 637

TreeSelectionEvent class
 getPath method, 662
 getPaths method, 656, 662

TreeSelectionListener interface
 implementing, 654–662
 valueChanged method, 655, 657, 662

TreeSelectionModel interface, 655
trim method (String), 169, 396

Troubleshooting. *See* Debugging

True Odds: How Risks Affect Your Everyday Life (Walsh), 563

tryLock method (FileChannel), 141–143

try-with-resources statement, 62
 closing files with, 124, 126
 for database connections, 312
 with locks, 142

ts literal (SQL), 328

Type bounds, type use annotations in, 480

Type codes, 96, 806

Type definitions, 185
 anonymous, 187
 nesting, 186

type method (*XPathEvaluationResult*), 199

Type parameters, annotating, 479

Type use annotations, 480

TYPE_BICUBIC, TYPE_BILINEAR fields (*AffineTransformOp*),
741, 747

TYPE_BYTE_GRAY field (*BufferedImage*), 736, 738

TYPE_BYTE_INDEXED field (*BufferedImage*), 738

TYPE_INT_ARGB field (`BufferedImage`), [733–734](#), [738](#)
TYPE_NEAREST_NEIGHBOR field (`AffineTransformOp`), [741](#), [747](#)
TypeElement interface, [489](#)
Types. *See* [Data types](#)
Typesafe enumerations, [104–107](#)

U

U.S. government on exporting encryption methods, [540](#)
\u, in regular expressions, [145](#)
UDP (User Datagram Protocol), [240](#)
UIManager class, [618](#)
Unicode standard, [44](#), [75](#)
 character order in, [407](#)
 converting to binary data, [68](#)
 in property files, [423](#)
 input/output streams and, [56](#)
 native code and, [795](#)
 normalization forms in, [409](#)
 using for all strings, [387](#)
Units of measurement, [164](#)
UNIX operating system
 authentication in, [550](#)
 line feed in, [69](#), [418](#)
 paths in, [115](#)
 specifying locales in, [392](#)
UnixLoginModule class, [551](#)
UnixNumericGroupPrincipal class, [551](#)
UnixPrincipal class, [551](#)
UnknownHostException, [239](#)
unordered method (*BaseStream*), [50](#), [53](#)
Unparsed external entities, [181](#)

unread method (`PushbackInputStream`), [67](#)
UnsatisfiedLinkError, [787](#)
until method (`LocalDate`), [367](#), [370](#)
update method
 of `Cipher`, [579](#), [582](#), [585–586](#)
 of `MessageDigest`, [564](#), [566](#)
UPDATE statement (SQL), [300](#), [320](#), [334](#)
 executing, [308](#), [310](#), [326](#)
 in batch updates, [355](#)
 truncations in, [313](#)
 vs. methods of `ResultSet`, [335](#)
updateXxx methods (`ResultSet`), [311](#), [334–335](#), [337–338](#)
URI class, [280](#)
 getXxx methods, [261](#)
 no resource accessing with, [260](#)
 uri method (`HttpRequest.Builder`), [279–281](#), [286](#)
URIs (Uniform Resource Identifiers), [200](#), [260](#)
 absolute vs. relative, [260–261](#)
 base, [261](#)
 hierarchical, [260](#)
 namespace, [199–202](#)
 opaque vs. nonopaque, [260](#)
 schemes for, [260](#)
 with HTTP, [280](#)
URISyntax class, [779](#)
URL class (DocFlavor), [770](#)
URL class (`java.lang.Object`), [259–261](#), [280](#)
 accepted schemes for, [260](#)
 openConnection method, [262](#), [267](#)
 openStream method, [64](#), [259](#), [267](#)
URLClassLoader class
 addURLs method, [537](#)

constructor, [545](#)
getURLs method, [537](#)
loadClass method, [536](#)
URLConnection class, [259](#), [262–269](#), [279](#)
 connect method, [262](#), [264](#), [268](#)
 getConnectTimeout method, [268](#)
 getContent method, [269](#)
 getContentEncoding, [getContentType](#) methods, [262](#), [265](#),
 [269](#), [274](#)
 getContentLength method, [262](#), [265](#), [268](#)
 getDate method, [262](#), [265](#), [269](#)
 getDoInput, [getDoOutput](#) methods, [267](#)
 getExpiration method, [262](#), [265](#), [269](#)
 getHeaderXxx methods, [262–265](#), [268](#)
 getIfModifiedSince method, [268](#)
 getInputStream method, [262](#), [269](#), [272](#), [274](#)
 getLastModified method, [262](#), [265](#), [269](#)
 getOutputStream method, [262](#), [269](#), [272](#)
 getReadTimeout method, [268](#)
 getRequestProperty method, [268](#)
 setAllowUserInteraction method, [262](#)
 setConnectTimeout method, [262](#), [268](#)
 setDoInput method, [262–263](#), [267](#)
 setDoOutput method, [262–263](#), [267](#), [272](#), [274](#)
 setIfModifiedSince method, [262–263](#), [268](#)
 setReadTimeout method, [262](#), [268](#)
 setRequestProperty method, [262–263](#), [268](#)
 setUseCaches method, [262](#)
urlConnection/URLConnectionTest.java, [265](#)
URLDecoder class
 decode method, [278](#)
URLEncoder class

encode method, 278

URLs (Uniform Resource Locators), 260

- attaching parameters to, 270
- connections via, 259
- encoding, 271
- for databases, 302
- for namespace identifiers, 200
- redirecting, 274–275
- relative vs. absolute, 177

URNs (Uniform Resource Names), 260

US Letter paper, 752

useLocale method (Scanner), 393, 396

User coordinates, 704

User objects, 632

User-Agent request parameter, 275

Users

- authentication of, 549–562
- preferences of, 141
- uses keyword, 527–528

UTC (Coordinated Universal Time), 375

UTF-8 encoding, 76–79

- byte order in, 76, 420
- for text files, 418
- modified, 79–80, 420, 795–798

UTF-16 encoding, 44, 68, 76, 79

- byte order in, 76
- in regular expressions, 145
- native code and, 795

V

v (void), type code, 806

\v, \V, in regular expressions, 146

`validateObject` method (*ObjectInputValidation*), 113–114
Validation, 175–194
 activating, 182
 adding to classes, 101
`value` method (*XPathEvaluationResult*), 196, 199
`valueChanged` method (*TreeSelectionListener*), 655, 657, 662
`valueForPathChanged` method (*TreeModel*), 664, 671
`value-of` element (XSLT), 226
`valueOf` method (date/time legacy classes), 385
VARCHAR data type (SQL), 301, 357
`VarHandle` class, 518
`Variable` class, 664
`toString` method, 665
Variable handles, 518
`VariableElement` interface, 489
Variables
 annotating, 468, 480
 binding, 446
 fields of, 665
 initializing, 546
 scope of, 447
Vendor name, of a reader, 723
`verifier/VerifierTest.java`, 549
Verifiers, 545–549
Version number, of a reader, 723
Versioning, 107–110
`view/ViewDB.java`, 345
visitFile, visitFileFailed methods
 of `FileVisitor`, 127
 of `SimpleFileVisitor`, 128–130

W

- \w, \W, in regular expressions, [146](#)
- W3C (World Wide Web Consortium), [166](#), [204](#)
- walk method (`Files`), [125–126](#)
- walkFileTree method (`Files`), [127–129](#)
- warning method (`ErrorHandler`), [183–184](#)
- Warnings
 - `SQLWarning`, [313–314](#)
 - suppressing, [484](#)
- WBMP format, [722](#)
- WeakReference object, [666](#)
- Web applications, [358–360](#)
- Web crawlers, [204](#)
 - with SAX parser, [205](#)
 - with StAX parser, [209](#)
- Web pages
 - dynamic, [461–467](#)
 - separating class loaders for, [539](#)
- WebRowSet* interface, [339](#)
- Weekends, [368](#)
- Weeks, [405](#)
- WHERE statement (SQL), [299](#)
- Whitespace
 - ignoring, while parsing, [168–169](#)
 - in e-mail URIs, [271](#)
 - in regular expressions, [146](#)
- Wildcards, type use annotations in, [480](#)
- Wilde, Oscar, [388](#)
- `win32reg/Win32RegKey.c`, [838](#)
- `win32reg/Win32RegKey.java`, [836](#)
- `win32reg/Win32RegKeyTest.java`, [845](#)

Win32RegKey class, [832](#), [835](#)
 getValue method, [832–833](#)
 names method, [832](#)
 setValue method, [832–834](#)

Win32RegKeyNameEnumeration class, [834–835](#)

Windows operating system
 activating telnet in, [236](#)
 authentication in, [550](#)
 character encodings in, [418](#)
 classpath in, [302](#)
 compiling invocation API, [829](#)
 dynamic linking in, [826](#)
 glob syntax in, [127](#)
 line feed in, [69](#), [418](#)
 look-and-feel of, [636](#)
 paths in, [64](#), [115](#)
 registry, accessing from native code, [830–846](#)
 resources in, [421](#)
 using Microsoft compiler, [789–790](#)

Windows-1252 encoding, [418–419](#)

with method (*Temporal*), [372–373](#)

withLocale method (DateTimeFormatter), [380](#), [384](#), [404](#), [407](#)

withXxx methods
 of LocalDate, [370](#)
 of LocalTime, [374](#)
 of Period, [371](#)
 of ZonedDateTime, [378](#)

Words, in regular expressions, [146](#)

Working directory, [64](#)

wrap method (ByteBuffer), [138](#), [140](#)

WritableByteChannel interface, [253](#)

WritableRaster class, [733](#)

setDataElements method, [735](#), [739](#)
setPixel, setPixels methods, [733](#), [739](#)

write method
 of CipherOutputStream, [586](#)
 of Files, [118–119](#)
 of ImageIO, [722](#), [729](#)
 of ImageWriter, [725](#), [732](#)
 of OutputStream, [57](#), [59](#)
 of Writer, [60](#)

write/XMLWriteTest.java, [218](#)

writeAttribute method (*XMLStreamWriter*), [217](#), [222](#)

writeBoolean method (DataOutput), [78](#), [80](#)

writeByte method (DataOutput), [78](#), [80](#)

writeCData method (*XMLStreamWriter*), [222](#)

writeChar method (DataOutput), [78](#), [80–81](#)

writeCharacters method (*XMLStreamWriter*), [217](#), [222](#)

writeChars method (DataOutput), [78–80](#)

writeComment method (*XMLStreamWriter*), [222](#)

writeDouble method (DataOutput), [78](#), [80](#), [90](#), [102](#)

writeDTD method (*XMLStreamWriter*), [222](#)

writeEmptyElement method (*XMLStreamWriter*), [217](#), [221](#)

writeEndXxx methods (*XMLStreamWriter*), [217](#), [221](#)

writeExternal method (*Externalizable*), [103–104](#)

writeFixedString method (DataIO), [82](#)

writeFloat method (DataOutput), [78](#), [80](#)

writeInsert method (ImageWriter), [725](#), [732](#)

writeInt method (DataOutput), [78](#), [80–81](#), [90](#)

writeLong method (DataOutput), [78](#), [80](#)

writeObject method
 of HashSet, [102](#)
 of ObjectOutputStream, [89](#), [94](#), [102](#)

Writer class, 56, 61–62
 write method, 60
 writeReplace method (*Serializable*), 106–107
 writeShort method (DataOutput), 78, 80
 writeStartXxx methods (*XMLStreamWriter*), 217, 221
 writeString method (Files), 118–119
 writeUTF method (DataOutput), 78–80

X

X.509 format, 570
\x, in regular expressions, 145
XHTML (Extensible Hypertext Markup Language), 162, 204
XML (Extensible Markup Language), 159–234
 annotated version of the standard, 161
 attributes in, 162
 case sensitivity of, 162
 end and empty tags in, 162
 in databases, 358
 namespaces in, 199–202
 vs. HTML, 161–162
XML catalogs, 177
XML documents
 DTDs in, 162, 176–185
 format of, 161
 generating, 212–223
 from non-XML legacy data, 228
 HTML files from, 223–226
 plain text from, 226–228
 with StAX, 217–222
 locating information in, 194–199
 malformed, 217–218
 parsing, 165–175

structure of, 162–166, 176
validating, 175–194
with/without namespaces, 213–214

XML Schema, 176, 185–188
 attributes in, 187
 documentation for, 200
 parsing with, 188
 referencing in XML documents, 185
 repeated elements in, 187
 type definitions in, 185–187

XML/JSON binding, 517

XMLInputFactory class
 createXMLStreamReader method, 211
 newInstance method, 211
 setProperty method, 209, 211

xmlns attribute (XSLT), 201

XMLEntryFactory class
 createXMLStreamWriter method, 217, 221
 newInstance method, 217, 221

XMLReader interface
 implementing, 227
 parse method, 233
 setContentHandler method, 233

XMLStreamReader interface
 getAttributeXxx methods, 209, 212
 getName, getLocalName, getText methods, 212
 hasNext method, 211
 isXxx methods, 212
 next method, 212

XMLStreamWriter interface, 217
 close method, 222
 not autocloseable, 217

`setDefaultNamespace`, `setPrefix` methods, 221
`writeAttribute` method, 217, 222
`writeCData` method, 222
`writeCharacters` method, 217, 222
`writeComment` method, 222
`writeDTD` method, 222
`writeEmptyElement` method, 217, 221
`writeEndXxx` methods, 217, 221
`writeStartXxx` methods, 217, 221
XOR composition rule, 714
XPath (XML Path Language), 194–199
 count function, 195
XPath interface
 `evaluate` method, 195–196, 199
 `evaluateExpression` method, 195–196, 199
`xpath/XPathTest.java`, 197
XPathEvaluationResult interface
 `type` method, 199
 `value` method, 196, 199
XPathFactory class
 `newInstance` method, 195, 199
 `newXPath` method, 199
XPathNodes class, 196
`xs:, xsd:` prefixes (XSL Schema), 186
`xsd:attribute` element (XML Schema), 187
`xsd:choice` element (XML Schema), 187
`xsd:complexType` element (XML Schema), 186
`xsd:element` element (XML Schema), 186
`xsd:enumeration` element (XML Schema), 186
`xsd:schema` element (XML Schema), 187
`xsd:sequence` element (XML Schema), 187

`xsd:simpleType` element (XML Schema), 186
`xsl:apply-templates` element (XSLT), 225
`xsl:output` element (XSLT), 225
`xsl:template` element (XSLT), 225
`xsl:value-of` element (XSLT), 226
XSLT (Extensible Stylesheet Language Transformations), 214, 223–234
 copying attribute values in, 226
 templates in, 225
XSLT processors, 223

Y

Yasson framework, 518
Year, YearMonth classes, 368

Z

`Z` (`boolean`), type code, 96, 806
`\z`, `\Z`, in regular expressions, 148
ZIP archives, 85–88
 for JMOD files, 530
 reading, 66, 85–86
 writing, 86
Zip code lookup, 272
ZIP file systems, 130–131
ZipEntry class
 constructor, 87
 `getXxx`, `setXxx` methods, 88
 `isDirectory` method, 88
ZipFile class
 constructor, 88
 `entries` method, 88
 `getXxx` methods, 88

`ZipInputStream` class, 60, 85
 `closeEntry` method, 85–87
 constructor, 87
 `getNextEntry` method, 85–87
 `read` method, 85
`ZipOutputStream` class, 60, 86
 `closeEntry` method, 86–87
 constructor, 87
 `putNextEntry` method, 86–87
 `setLevel`, `setMethod` methods, 87
`ZonedDateTime` class, 375–379
 `format` method, 404
 `from` method, 384–385
 `getXxx` methods, 378–379
 `isAfter`, `isBefore` methods, 379
 legacy classes and, 384–385
 `minus`, `minusXxx` methods, 378
 `now` method, 378
 `of`, `ofInstant` methods, 375, 378
 `parse` method, 384, 404, 407
 `plus`, `plusXxx` methods, 378
 `toInstant` method, 375, 379
 `toLocalXxx` methods, 379
 `withXxx` methods, 378
`zonedtimes/ZonedDateTime.java`, 377
`ZoneId` class, 385
 `getAvailableZoneIds` method, 375
 `of` method, 375

#1 programming
language for today's
tech trends





java

www.oracle.com/java



O




Take your skills to the next level with *Java Magazine*

Written for developers by developers,
new articles are posted every two weeks,
and there's a fresh quiz every Tuesday!

Read all the articles and subscribe
to the newsletter at no cost.

oracle.com/iavamagazine







Exploit the power of modern JavaScript and avoid the pitfalls

Cay S. Horstmann covers all you need to know, provided in small chunks organized for quick access and easy understanding.


- Quickly master Modern JavaScript's implementation of fundamental programming constructs.
- Avoid legacy techniques that create unnecessary complexity and risk.
- Make the most of functional, object-oriented, and asynchronous techniques.
- Use modules to efficiently organize and run complex programs.
- Write more powerful, flexible, and concise programs with metaprogramming.
- Extend JavaScript's power via JavaScript libraries, frameworks, and platforms.



Modern JavaScript for the Impatient

ISBN: 978-0-13-650214-2

Available in print and eBook formats



Modern JavaScript for the Impatient LiveLessons

ISBN: 978-0-13-581269-3

8+ hours of video instruction

informit.com/horstmann



Pearson



Photo by izusek/gettyimages

Register Your Product at informit.com/register

Access additional benefits and **save 35%** on your next purchase

- Automatically receive a coupon for 35% off your next purchase, valid for 30 days. Look for your code in your InformIT cart or the Manage Codes section of your account page.
- Download available product updates.
- Access bonus material if available.*
- Check the box to hear from us and receive exclusive offers on new editions and related products.

*Registration benefits vary by product. Benefits will be listed on your account page under Registered Products.

THE TRUSTED TECHNOLOGY LEARNING SOURCE

InformIT is the online home of information technology brands at Pearson, the world's foremost education company. At InformIT.com, you can:

- Shop our books, eBooks, software, and video training
- Take advantage of our special offers and promotions (informit.com/promotions)
- Sign up for special offers and content newsletter (informit.com/newsletters)
- Access thousands of free chapters and video lessons

Connect with InformIT—Visit informit.com/community



Addison-Wesley • Adobe Press • Cisco Press • Microsoft Press • Pearson IT Certification • Que • Sams • Peachpit Press



Code Snippets

Many titles include programming code or configuration examples. To optimize the presentation of these elements, view the eBook in single-column, landscape mode and adjust the font size to the smallest setting. In addition to presenting code and configurations in the reflowable text format, we have included images of the code that mimic the presentation found in the print book; therefore, where the reflowable format may compromise the presentation of the code listing, you will see a “Click here to view code image” link. Click the link to view the print-fidelity code image. To return to the previous page viewed, click the Back button on your device or app.

```
var contents = Files.readString(Path.of("alice.txt")); // Read file into string
List<String> words = List.of(contents.split("\\PL+"));
// Split into words; nonletters are delimiters

int count = 0;
for (String w : words)
{
    if (w.length() > 12) count++;
}

long count = words.stream()
    .filter(w -> w.length() > 12)
    .count();

long count = words.parallelStream()
    .filter(w -> w.length() > 12)
    .count();

1 package streams;
2
3 import java.io.*;
4 import java.nio.file.*;
5 import java.util.*;
```

```
6
7  /**
8   * @version 1.02 2019-08-28
9   * @author Cay Horstmann
10  */
11 public class CountLongWords
12 {
13     public static void main(String[] args) throws IOException
14     {
15         var contents = Files.readString(
16             Path.of("../gutenberg/alice30.txt"));
17         List<String> words = List.of(contents.split("\\PL+"));
18
19         long count = 0;
20         for (String w : words)
21         {
22             if (w.length() > 12) count++;
23         }
24         System.out.println(count);
25
26         count = words.stream().filter(w -> w.length() > 12).count();
27         System.out.println(count);
28
29         count = words.parallelStream().filter(w -> w.length() > 12).count();
30         System.out.println(count);
31     }
32 }
```

```
Stream<String> words = Stream.of(contents.split("\\PL+"));
// split returns a String[] array

Stream<String> song = Stream.of("gently", "down", "the", "stream");

Stream<String> silence = Stream.empty();
// Generic type <String> is inferred; same as Stream.<String>empty()

Stream<String> echos = Stream.generate(() -> "Echo");

Stream<Double> randoms = Stream.generate(Math::random);
```

```
Stream<BigInteger> integers
    = Stream.iterate(BigInteger.ZERO, n -> n.add(BigInteger.ONE));

var limit = new BigInteger("10000000");
Stream<BigInteger> integers
    = Stream.iterate(BigInteger.ZERO,
        n -> n.compareTo(limit) < 0,
        n -> n.add(BigInteger.ONE));

Stream<String> greetings = "Hello\nGuten Tag\nBonjour".lines()

Stream<String> words = Pattern.compile("\\PL+").splitAsStream(contents);

Stream<String> words = new Scanner(contents).tokens();

try (Stream<String> lines = Files.lines(path))
{
    Process lines
}

System.out.println(Stream.generate(Math::random).limit(10).toList());

StreamSupport.stream(iterablespliterator(), false);

StreamSupport.stream(Spliterators.spliteratorUnknownSize(
    iterator, Spliterator.ORDERED), false);

List<String> wordList = . . .;
Stream<String> words = wordList.stream();
wordList.add("END");
long n = words.distinct().count();

Stream<String> words = wordList.stream();
words.forEach(s -> {if (s.length() < 12) wordList.remove(s);});
// ERROR--interference
```

```
1 package streams;
2
3 import java.io.*;
4 import java.math.*;
5 import java.nio.file.*;
6 import java.util.*;
7 import java.util.regex.Pattern;
8 import java.util.stream.*;
9
10 /**
11  * @version 1.03 2021-09-06
12  * @author Cay Horstmann
13  */
14 public class CreatingStreams
15 {
16     public static <T> void show(String title, Stream<T> stream)
17     {
18         final int SIZE = 10;
```

```
19     List<T> firstElements = stream
20         .limit(SIZE + 1)
21         .toList();
22     System.out.print(title + ": ");
23     for (int i = 0; i < firstElements.size(); i++)
24     {
25         if (i > 0) System.out.print(", ");
26         if (i < SIZE) System.out.print(firstElements.get(i));
27         else System.out.print("...\"");
28     }
29     System.out.println();
30 }
31
32 public static void main(String[] args) throws IOException
33 {
34     Path path = Path.of("../gutenberg/alice30.txt");
35     var contents = Files.readString(path);
36
37     Stream<String> words = Stream.of(contents.split("\\PL+"));
38     show("words", words);
39     Stream<String> song = Stream.of("gently", "down", "the", "stream");
40     show("song", song);
41     Stream<String> silence = Stream.empty();
42     show("silence", silence);
43
44     Stream<String> echos = Stream.generate(() -> "Echo");
45     show("echos", echos);
46
47     Stream<Double> randoms = Stream.generate(Math::random);
48     show("randoms", randoms);
49
50     Stream<BigInteger> integers = Stream.iterate(BigInteger.ONE,
51         n -> n.add(BigInteger.ONE));
52     show("integers", integers);
53
54     Stream<String> greetings = "Hello\nGuten Tag\nBonjour".lines();
55     show("greetings", greetings);
56
57     Stream<String> wordsAnotherWay = Pattern.compile("\\PL+").splitAsStream(contents);
58     show("wordsAnotherWay", wordsAnotherWay);
59
60     try (Stream<String> lines = Files.lines(path))
61     {
62         show("lines", lines);
63     }
64
65     Iterable<Path> iterable = FileSystems.getDefault().getRootDirectories();
```

```
66     Stream<Path> rootDirectories = StreamSupport.stream(iterable.splitter(), false);
67     show("rootDirectories", rootDirectories);
68
69     Iterator<Path> iterator = Path.of("/usr/share/dict/words").iterator();
70     Stream<Path> pathComponents = StreamSupport.stream(Spliterators.spliteratorUnknownSize(
71         iterator, Spliterator.ORDERED), false);
72     show("pathComponents", pathComponents);
73 }
74 }
```

```
List<String> words = . . .;
Stream<String> longWords = words.stream().filter(w -> w.length() > 12);

Stream<String> lowercaseWords = words.stream().map(String::toLowerCase);

Stream<String> firstLetters = words.stream().map(s -> s.substring(0, 1));

Stream<Stream<String>> result = words.stream().map(w -> codePoints(w));

Stream<String> flatResult = words.stream().flatMap(w -> codePoints(w));
    // Calls codePoints on each word and flattens the results

"Hello 🌎".codePoints() // A stream of integers 72, 101, 108, 108, 111, 32, 127760

public static Stream<String> codePoints(String s)
{
    return s.codePoints().mapToObj(cp -> new String(new int [] { cp }, 0, 1));
}

int i = 0;
while (i < s.length())
{
    int cp = sentence.codePointAt(i);
    // Do something with cp
    if (Character.isSupplementaryCodePoint(cp)) i += 2;
    else i++;
}
```

```
Stream<String> result = words.stream().mapMulti((s, collector) ->
{
    int i = 0;
    while (i < s.length())
    {
        int cp = sentence.codePointAt(i);
        collector.accept(cp);
        if (Character.isSupplementaryCodePoint(cp)) i += 2;
        else i++;
    }
});

Stream<Double> randoms = Stream.generate(Math::random).limit(100);

Stream<String> words = Stream.of(contents.split("\\PL+")).skip(1);

Stream<String> initialDigits = codePoints(str).takeWhile(
    s -> "0123456789".contains(s));

Stream<String> withoutInitialWhiteSpace = codePoints(str).dropWhile(
    s -> s.strip().length() == 0);

Stream<String> combined = Stream.concat(
    codePoints("Hello"), codePoints("World"));
// Yields the stream ["H", "e", "l", "l", "o", "W", "o", "r", "l", "d"]

Stream<String> uniqueWords
    = Stream.of("merrily", "merrily", "merrily", "gently").distinct();
// Only one "merrily" is retained

Stream<String> longestFirst
    = words.stream().sorted(Comparator.comparing(String::length).reversed());

Object[] powers = Stream.iterate(1.0, p -> p * 2)
    .peek(e -> System.out.println("Fetching " + e))
    .limit(20).toArray();

.peek(x ->
{
    return;
})
```

```
Optional<String> largest = words.max(String::compareToIgnoreCase);
System.out.println("largest: " + largest.orElse(""));

Optional<String> startsWithQ
    = words.filter(s -> s.startsWith("Q")).findFirst();

Optional<String> startsWithQ
    = words.parallel().filter(s -> s.startsWith("Q")).findAny();

boolean aWordStartsWithQ
    = words.parallel().anyMatch(s -> s.startsWith("Q"));

String result = optionalString.orElse("");
    // The wrapped string, or "" if none

String result = optionalString.orElseGet(() -> System.getProperty("myapp.default"));
    // The function is only called when needed

String result = optionalString.orElseThrow(IllegalStateException::new);
    // Supply a method that yields an exception object

optionalValue.ifPresent(v -> results.add(v));

optionalValue.ifPresent(v -> results.add(v));

optionalValue.ifPresent(results::add);

optionalValue.ifPresentOrElse(
    v -> System.out.println("Found " + v),
    () -> logger.warning("No match"));

Optional<String> transformed = optionalString.map(String::toUpperCase);

optionalValue.map(results::add);

Optional<String> transformed = optionalString
    .filter(s -> s.length() >= 8)
    .map(String::toUpperCase);
```

```
Optional<String> result = optionalString.or(() -> // Supply an Optional
    alternatives.stream().findFirst());

Optional<T> optionalValue = . . .;
optionalValue.get().someMethod()

T value = . . .;
value.someMethod();

if (optionalValue.isPresent()) optionalValue.get().someMethod();

if (value != null) value.someMethod();

public static Optional<Double> inverse(Double x)
{
    return x == 0 ? Optional.empty() : Optional.of(1 / x);
}

Optional<U> result = s.f().flatMap(T::g);

public static Optional<Double> squareRoot(Double x)
{
    return x < 0 ? Optional.empty() : Optional.of(Math.sqrt(x));
}

Optional<Double> result = inverse(x).flatMap(MyMath::squareRoot);

Optional<Double> result
    = Optional.of(-4.0).flatMap(Demo::inverse).flatMap(Demo::squareRoot);

Optional<User> lookup(String id)

Stream<String> ids = . . .;
Stream<User> users = ids.map(Users::lookup)
    .filter(Optional::isPresent)
    .map(Optional::get);

Stream<User> users = ids.map(Users::lookup)
    .flatMap(Optional::stream);
```

```
Stream<User> users = ids.map(Users::classicLookup)
    .filter(Objects::nonNull);

Stream<User> users = ids.flatMap(
    id -> Stream.ofNullable(Users.classicLookup(id)));

Stream<User> users = ids.map(Users::classicLookup)
    .flatMap(Stream::ofNullable);

1 package optional;
2
3 import java.io.*;
4 import java.nio.file.*;
5 import java.util.*;
6
7 /**
8  * @version 1.02 2019-08-28
9  * @author Cay Horstmann
10 */
11 public class OptionalTest
12 {
13     public static void main(String[] args) throws IOException
14     {
15         var contents = Files.readString(
16             Path.of("../gutenberg/alice30.txt"));
17         List<String> wordList = List.of(contents.split("\\PL+"));
18     }
}
```

```
19     Optional<String> optionalValue = wordList.stream()
20         .filter(s -> s.contains("fred"))
21         .findFirst();
22     System.out.println(optionalValue.orElse("No word") + " contains fred");
23
24     Optional<String> optionalString = Optional.empty();
25     String result = optionalString.orElse("N/A");
26     System.out.println("result: " + result);
27     result = optionalString.orElseGet(() -> Locale.getDefault().getDisplayName());
28     System.out.println("result: " + result);
29     try
30     {
31         result = optionalString.orElseThrow(IllegalStateException::new);
32         System.out.println("result: " + result);
33     }
34     catch (Throwable t)
35     {
36         t.printStackTrace();
37     }
38
39     optionalValue = wordList.stream()
40         .filter(s -> s.contains("red"))
41         .findFirst();
42     optionalValue.ifPresent(s -> System.out.println(s + " contains red"));
43
44     var results = new HashSet<String>();
45     optionalValue.ifPresent(results::add);
46     Optional<Boolean> added = optionalValue.map(results::add);
47     System.out.println(added);
48
49     System.out.println(inverse(4.0).flatMap(OptionalTest::squareRoot));
50     System.out.println(inverse(-1.0).flatMap(OptionalTest::squareRoot));
51     System.out.println(inverse(0.0).flatMap(OptionalTest::squareRoot));
52     Optional<Double> result2 = Optional.of(-4.0)
53         .flatMap(OptionalTest::inverse).flatMap(OptionalTest::squareRoot);
54     System.out.println(result2);
55 }
56
57 public static Optional<Double> inverse(Double x)
58 {
59     return x == 0 ? Optional.empty() : Optional.of(1 / x);
60 }
61
62 public static Optional<Double> squareRoot(Double x)
63 {
64     return x < 0 ? Optional.empty() : Optional.of(Math.sqrt(x));
65 }
66 }
```

```
stream.forEach(System.out::println);

String[] result = stream.toArray(String[]::new);
// stream.toArray() has type Object[]

List<String> result = stream.collect(Collectors.toList());

Set<String> result = stream.collect(Collectors.toSet());

TreeSet<String> result = stream.collect(Collectors.toCollection(TreeSet::new));

String result = stream.collect(Collectors.joining());

String result = stream.collect(Collectors.joining(", "));

String result = stream.map(Object::toString).collect(Collectors.joining(", "));

IntSummaryStatistics summary = stream.collect(
    Collectors.summarizingInt(String::length));
double averageWordLength = summary.getAverage();
double maxWordLength = summary.getMax();

1 package collecting;
2
3 import java.io.*;
4 import java.nio.file.*;
5 import java.util.*;
6 import java.util.stream.*;
7
8 /**
9  * @version 1.02 2019-08-28
10 * @author Cay Horstmann
11 */
12 public class CollectingResults
13 {
```

```
14 public static Stream<String> noVowels() throws IOException
15 {
16     var contents = Files.readString(
17         Path.of("../gutenberg/alice30.txt"));
18
19     List<String> wordList = List.of(contents.split("\\PL+"));
20     Stream<String> words = wordList.stream();
21     return words.map(s -> s.replaceAll("[aeiouAEIOU]", ""));
22 }
23
24 public static <T> void show(String label, Set<T> set)
25 {
26     System.out.print(label + ": " + set.getClass().getName());
27     System.out.println("["
28         + set.stream().limit(10).map(Object::toString).collect(Collectors.joining(", "))
29         + "]");
30 }
31
32 public static void main(String[] args) throws IOException
33 {
34     Iterator<Integer> iter = Stream.iterate(0, n -> n + 1).limit(10).iterator();
35     while (iter.hasNext())
36         System.out.println(iter.next());
37
38     Object[] numbers = Stream.iterate(0, n -> n + 1).limit(10).toArray();
39     System.out.println("Object array: " + numbers);
40     // Note it's an Object[] array
41
42     try
43     {
44         var number = (Integer) numbers[0]; // OK
45         System.out.println("number: " + number);
46         System.out.println("The following statement throws an exception:");
47         var numbers2 = (Integer[]) numbers; // Throws exception
48     }
49     catch (ClassCastException e)
50     {
51         System.out.println(e);
52     }
53
54     Integer[] numbers3 = Stream.iterate(0, n -> n + 1)
55         .limit(10)
56         .toArray(Integer[]::new);
57     System.out.println("Integer array: " + numbers3);
58     // Note it's an Integer[] array
59
60     Set<String> noVowelSet = noVowels().collect(Collectors.toSet());
```

```
61     show("noVowelSet", noVowelSet);
62
63     TreeSet<String> noVowelTreeSet = noVowels().collect(
64         Collectors.toCollection(TreeSet::new));
65     show("noVowelTreeSet", noVowelTreeSet);
66
67     String result = noVowels().limit(10).collect(Collectors.joining());
68     System.out.println("Joining: " + result);
69     result = noVowels().limit(10)
70         .collect(Collectors.joining(", "));
71     System.out.println("Joining with commas: " + result);
72
73     IntSummaryStatistics summary = noVowels().collect(
74         Collectors.summarizingInt(String::length));
75     double averageWordLength = summary.getAverage();
76     double maxWordLength = summary.getMax();
77     System.out.println("Average word length: " + averageWordLength);
78     System.out.println("Max word length: " + maxWordLength);
79     System.out.println("forEach:");
80     noVowels().limit(10).forEach(System.out::println);
81 }
82 }
```

```
public record Person(int id, String name) {}

...
Map<Integer, String> idToName = people.collect(
    Collectors.toMap(Person::id, Person::name));

Map<Integer, Person> idToPerson = people.collect(
    Collectors.toMap(Person::id, Function.identity()));

Stream<Locale> locales = Stream.of(Locale.getAvailableLocales());
Map<String, String> languageNames = locales.collect(
    Collectors.toMap(
        Locale::getDisplayLanguage,
        loc -> loc.getDisplayLanguage(loc),
        (existingValue, newValue) -> existingValue));
```

```
Map<String, Set<String>> countryLanguageSets = locales.collect(
    Collectors.toMap(
        Locale::getDisplayCountry,
        l -> Collections.singleton(l.getDisplayLanguage()),
        (a, b) ->
            { // Union of a and b
                var union = new HashSet<String>(a);
                union.addAll(b);
                return union;
            }));
Map<Integer, Person> idToPerson = people.collect(
    Collectors.toMap(
        Person::id,
        Function.identity(),
        (existingValue, newValue) -> { throw new IllegalStateException(); },
        TreeMap::new));
1 package collecting;
2
3 import java.io.*;
```

```
4 import java.util.*;
5 import java.util.function.*;
6 import java.util.stream.*;
7
8 /**
9  * @version 1.01 2021-09-06
10 * @author Cay Horstmann
11 */
12 public class CollectingIntoMaps
13 {
14
15     public record Person(int id, String name) {}
16
17     public static Stream<Person> people()
18     {
19         return Stream.of(new Person(1001, "Peter"), new Person(1002, "Paul"),
20                         new Person(1003, "Mary"));
21     }
22
23     public static void main(String[] args) throws IOException
24     {
25         Map<Integer, String> idToName = people().collect(
26             Collectors.toMap(Person::id, Person::name));
27         System.out.println("idToName: " + idToName);
28
29         Map<Integer, Person> idToPerson = people().collect(
30             Collectors.toMap(Person::id, Function.identity()));
31         System.out.println("idToPerson: " + idToPerson.getClass().getName()
32                         + idToPerson);
33
34         idToPerson = people().collect(
35             Collectors.toMap(Person::id, Function.identity(),
36                             (existingValue, newValue) -> { throw new IllegalStateException(); },
37                             TreeMap::new));
38         System.out.println("idToPerson: " + idToPerson.getClass().getName()
39                         + idToPerson);
40
41         Stream<Locale> locales = Stream.of(Locale.getAvailableLocales());
42         Map<String, String> languageNames = locales.collect(
43             Collectors.toMap(
44                 Locale::getDisplayLanguage,
45                 l -> l.getDisplayLanguage(l),
46                 (existingValue, newValue) -> existingValue));
47         System.out.println("languageNames: " + languageNames);
48
49         locales = Stream.of(Locale.getAvailableLocales());
```

```
50     Map<String, Set<String>> countryLanguageSets = locales.collect(
51         Collectors.toMap(
52             Locale::getDisplayCountry,
53             l -> Set.of(l.getDisplayLanguage()),
54             (a, b) ->
55                 { // union of a and b
56                     Set<String> union = new HashSet<>(a);
57                     union.addAll(b);
58                     return union;
59                 }));
60     System.out.println("countryLanguageSets: " + countryLanguageSets);
61 }
62 }
```

```
Map<String, List<Locale>> countryToLocales = locales.collect(
    Collectors.groupingBy(Locale::getCountry));

List<Locale> swissLocales = countryToLocales.get("CH");
// Yields locales de_CH, fr_CH, it_CH, and maybe more

Map<Boolean, List<Locale>> englishAndOtherLocales = locales.collect(
    Collectors.partitioningBy(l -> l.getLanguage().equals("en")));
List<Locale> englishLocales = englishAndOtherLocales.get(true);

Map<String, Set<Locale>> countryToLocaleSet = locales.collect(
    groupingBy(Locale::getCountry, toSet()));

Map<String, Long> countryToLocaleCounts = locales.collect(
    groupingBy(Locale::getCountry, counting()));

public record City(String name, String state, int population) {}

...
Map<String, Integer> stateToCityPopulation = cities.collect(
    groupingBy(City::state, averagingInt(City::population)));

Map<String, Optional<City>> stateToLargestCity = cities.collect(
    groupingBy(City::state,
        maxBy(Comparator.comparing(City::population))));
```

```
Map<Character, Integer> stringCountsByStartingLetter = strings.collect(
    groupingBy(s -> s.charAt(0),
        collectingAndThen(toSet(), Set::size)));

Map<Character, Set<Integer>> stringLengthsByStartingLetter = strings.collect(
    groupingBy(s -> s.charAt(0),
        mapping(String::length, toSet())));

Map<String, Set<String>> countryToLanguages = locales.collect(
    groupingBy(Locale::getDisplayCountry,
        mapping(Locale::getDisplayLanguage,
            toSet())));

Map<String, IntSummaryStatistics> stateToCityPopulationSummary = cities.collect(
    groupingBy(City::state,
        summarizingInt(City::population)));

Map<String, Set<City>> largeCitiesByState
= cities.collect(
    groupingBy(City::state,
        filtering(c -> c.population() > 500000,
            toSet()))); // States without large cities have empty sets

record Pair<S, T>(S first, T second) {}

Pair<List<String>, Double> result = cities.filter(c -> c.state().equals("NV"))
.collect(teeing(
    mapping(City::name, toList()), // First downstream collector
    averagingDouble(City::population), // Second downstream collector
    (list, avg) -> new Result(list, avg))); // Combining function
```

```
1 package collecting;
2
3 import static java.util.stream.Collectors.*;
4
5 import java.io.*;
6 import java.nio.file.*;
7 import java.util.*;
8 import java.util.stream.*;
9
10 /**
11  * @version 1.01 2021-09-06
12  * @author Cay Horstmann
13  */
```

```
14 public class DownstreamCollectors
15 {
16     public record City(String name, String state, int population) {}
17
18     public static Stream<City> readCities(String filename) throws IOException
19     {
20         return Files.lines(Path.of(filename))
21             .map(l -> l.split(", "))
22             .map(a -> new City(a[0], a[1], Integer.parseInt(a[2])));
23     }
24
25     public static void main(String[] args) throws IOException
26     {
27         Stream<Locale> locales = Stream.of(Locale.getAvailableLocales());
28         Map<String, Set<Locale>> countryToLocaleSet = locales.collect(groupingBy(
29             Locale::getCountry, toSet()));
30         System.out.println("countryToLocaleSet: " + countryToLocaleSet);
31
32         locales = Stream.of(Locale.getAvailableLocales());
33         Map<String, Long> countryToLocaleCounts = locales.collect(groupingBy(
34             Locale::getCountry, counting()));
35         System.out.println("countryToLocaleCounts: " + countryToLocaleCounts);
36
37         Stream<City> cities = readCities("cities.txt");
38         Map<String, Integer> stateToCityPopulation = cities.collect(groupingBy(
39             City::state, summingInt(City::population)));
40         System.out.println("stateToCityPopulation: " + stateToCityPopulation);
41
42         cities = readCities("cities.txt");
43         Map<String, Optional<String>> stateToLongestCityName = cities
44             .collect(groupingBy(City::state,
45                 mapping(City::name, maxBy(Comparator.comparing(String::length)))));
46         System.out.println("stateToLongestCityName: " + stateToLongestCityName);
47
48         locales = Stream.of(Locale.getAvailableLocales());
49         Map<String, Set<String>> countryToLanguages = locales.collect(groupingBy(
50             Locale::getDisplayCountry, mapping(Locale::getDisplayLanguage, toSet())));
51         System.out.println("countryToLanguages: " + countryToLanguages);
52
53         cities = readCities("cities.txt");
54         Map<String, IntSummaryStatistics> stateToCityPopulationSummary = cities
55             .collect(groupingBy(City::state, summarizingInt(City::population)));
56         System.out.println(stateToCityPopulationSummary.get("NY"));
57
58         cities = readCities("cities.txt");
59         Map<String, String> stateToCityNames = cities.collect(groupingBy(
60             City::state,
61             reducing("", City::name, (s, t) -> s.length() == 0 ? t : s + ", " + t)));
62     }
```

```
63     cities = readCities("cities.txt");
64     stateToCityNames = cities.collect(groupingBy(City::state,
65         mapping(City::name, joining(", "))));
66     System.out.println("stateToCityNames: " + stateToCityNames);
67
68     cities = readCities("cities.txt");
69     record Pair<S, T>(S first, T second) {}
70     Pair<List<String>, Double> result = cities.filter(c -> c.state().equals("W"))
71         .collect(teeing(
72             mapping(City::name, toList()),
73             averagingDouble(City::population),
74             (names, avg) -> new Pair<>(names, avg)));
75     System.out.println(result);
76 }
77 }
```

```
List<Integer> values = . . .;
Optional<Integer> sum = values.stream().reduce((x, y) -> x + y);

List<Integer> values = . . .;
Integer sum = values.stream().reduce(0, (x, y) -> x + y);
// Computes  $v_0 + v_1 + v_2 + \dots$ 

int result = words.reduce(0,
    (total, word) -> total + word.length(),
    (total1, total2) -> total1 + total2);

BitSet result = stream.collect(BitSet::new, BitSet::set, BitSet::or);

IntStream stream = IntStream.of(1, 1, 2, 3, 5);
stream = Arrays.stream(values, from, to); // values is an int[] array

IntStream zeroToNinetyNine = IntStream.range(0, 100); // Upper bound is excluded
IntStream zeroToHundred = IntStream.rangeClosed(0, 100); // Upper bound is included

String sentence = "\uD835\uDD46 is the set of octonions.";
// \uD835\uDD46 is the UTF-16 encoding of the letter ℬ, unicode U+1D546

IntStream codes = sentence.codePoints();
// The stream with hex values 1D546 20 69 73 20 . . .
```

```
Stream<String> words = . . .;
IntStream lengths = words.mapToInt(String::length);

Stream<Integer> integers = IntStream.range(0, 100).boxed();
```

```
1 package streams;
2
3 import java.io.*;
4 import java.nio.file.*;
5 import java.util.stream.*;
6
7 /**
8 * @version 1.02 2021-09-09
9 * @author Cay Horstmann
10 */
11 public class PrimitiveTypeStreams
12 {
13     public static void show(String title, IntStream stream)
14     {
15         final int SIZE = 10;
16         int[] firstElements = stream.limit(SIZE + 1).toArray();
17         System.out.print(title + ": ");
18         for (int i = 0; i < firstElements.length; i++)
19         {
20             if (i > 0) System.out.print(", ");
21             if (i < SIZE) System.out.print(firstElements[i]);
22             else System.out.print("...\"");
23         }
24         System.out.println();
25     }
26
27     public static void main(String[] args) throws IOException
28     {
29         IntStream is1 = IntStream.generate(() -> (int) (Math.random() * 100));
30         show("is1", is1);
31         IntStream is2 = IntStream.range(5, 10);
32         show("is2", is2);
33         IntStream is3 = IntStream.rangeClosed(5, 10);
34         show("is3", is3);
35
36         Path path = Path.of("../gutenberg/alice30.txt");
```

```
37     var contents = Files.readString(path);
38
39     Stream<String> words = Stream.of(contents.split("\\PL+"));
40     IntStream is4 = words.mapToInt(String::length);
41     show("is4", is4);
42     String sentence = "\uD835\uDD46 is the set of octonions.";
43     System.out.println(sentence);
44     IntStream codes = sentence.codePoints();
45     System.out.println(codes.mapToObj(c -> "%X ".formatted(c)).collect(
46         Collectors.joining()));
47
48     Stream<Integer> integers = IntStream.range(0, 100).boxed();
49     IntStream is5 = integers.mapToInt(Integer::intValue);
50     show("is5", is5);
51 }
52 }
```

```
Stream<String> parallelWords = words.parallelStream();

Stream<String> parallelWords = Stream.of(wordArray).parallel();

var shortWords = new int[12];
words.parallelStream().forEach(
    s -> { if (s.length() < 12) shortWords[s.length()]++; });
    // ERROR--race condition!
System.out.println(Arrays.toString(shortWords));

Map<Integer, Long> shortWordCounts
    = words.parallelStream()
        .filter(s -> s.length() < 12)
        .collect(groupingBy(
            String::length,
            counting()));

Stream<String> sample = words.parallelStream().unordered().limit(n);

Map<Integer, List<String>> result = words.parallelStream().collect(
    Collectors.groupingByConcurrent(String::length));
    // Values aren't collected in stream order
```

```
Map<Integer, Long> wordCounts
    = words.parallelStream()
        .collect(
            groupingByConcurrent(
                String::length,
                counting()));

ForkJoinPool customPool = . . .;
result = customPool.submit(() ->
    stream.parallel().map(. . .).collect(. . .)).get();

CompletableFuture.supplyAsync(() ->
    stream.parallel().map(. . .).collect(. . .),
    customPool).thenAccept(result -> . . .);
```

```
1 package parallel;
2
3 import static java.util.stream.Collectors.*;
4
5 import java.io.*;
6 import java.nio.file.*;
7 import java.util.*;
8 import java.util.stream.*;
9
10 /**
11  * @version 1.02 2019-08-28
12  * @author Cay Horstmann
13  */
14 public class ParallelStreams
15 {
16     public static void main(String[] args) throws IOException
17     {
18         var contents = Files.readString(
19             Path.of("../gutenberg/alice30.txt"));
20         List<String> wordList = List.of(contents.split("\\PL+"));
21
22         // Very bad code ahead
23         var shortWords = new int[10];
24         wordList.parallelStream().forEach(s ->
25             {
26                 if (s.length() < 10) shortWords[s.length()]++;
27             });
28         System.out.println(Arrays.toString(shortWords));
29
30         // Try again--the result will likely be different (and also wrong)
31         Arrays.fill(shortWords, 0);
32         wordList.parallelStream().forEach(s ->
33             {
34                 if (s.length() < 10) shortWords[s.length()]++;
35             });
36     }
37 }
```

```
36     System.out.println(Arrays.toString(shortWords));
37
38     // Remedy: Group and count
39     Map<Integer, Long> shortWordCounts = wordList.parallelStream()
40         .filter(s -> s.length() < 10)
41         .collect(groupingBy(String::length, counting()));
42
43     System.out.println(shortWordCounts);
44
45     // Downstream order not deterministic
46     Map<Integer, List<String>> result = wordList.parallelStream().collect(
47         Collectors.groupingByConcurrent(String::length));
48
49     System.out.println(result.get(14));
50
51     result = wordList.parallelStream().collect(
52         Collectors.groupingByConcurrent(String::length));
53
54     System.out.println(result.get(14));
55
56     Map<Integer, Long> wordCounts = wordList.parallelStream().collect(
57         groupingByConcurrent(String::length, counting()));
58
59     System.out.println(wordCounts);
60 }
61 }
```

```
byte[] bytes = in.readAllBytes();

abstract void write(int b)

byte[] values = . . .;
out.write(values);

int bytesAvailable = in.available();
if (bytesAvailable > 0)
{
    var data = new byte[bytesAvailable];
    in.read(data);
}

void close() throws IOException

Appendable append(char c)
Appendable append(CharSequence s)

var fin = new FileInputStream("employee.dat");

byte b = (byte) fin.read();

DataInputStream din = . . .;
double x = din.readDouble();

var fin = new FileInputStream("employee.dat");
var din = new DataInputStream(fin);
double x = din.readDouble();

var din = new DataInputStream(
    new BufferedInputStream(
        new FileInputStream("employee.dat")));

var pbin = new PushbackInputStream(
    new BufferedInputStream(
        new FileInputStream("employee.dat")));
```

```
var pbin = new PushbackInputStream(
    new BufferedInputStream(
        new FileInputStream("employee.dat")));
var din = new DataInputStream(pbin);

var zin = new ZipInputStream(new FileInputStream("employee.zip"));
var din = new DataInputStream(zin);

var in = new InputStreamReader(System.in);

var in = new InputStreamReader(new FileInputStream("data.txt"), StandardCharsets.UTF_8);

var out = new PrintWriter("employee.txt", StandardCharsets.UTF_8);

String name = "Harry Hacker";
double salary = 75000;
out.print(name);
out.print(' ');
out.println(salary);

var out = new PrintWriter(
    new OutputStreamWriter(
        new FileOutputStream("employee.txt"), StandardCharsets.UTF_8),
    true); // autoflush

String content = Files.readString(path, charset);

List<String> lines = Files.readAllLines(path, charset);

try (Stream<String> lines = Files.lines(path, charset))
{
    ...
}

Scanner in = . . .;
in.useDelimiter("\\PL+");
```

```
while (in.hasNext())
{
    String word = in.next();
    ...
}

Stream<String> words = in.tokens();

InputStream inputStream = . . .;
try (var in = new BufferedReader(new InputStreamReader(inputStream, charset)))
{
    boolean done = false;
    while (!done)
    {
        String line = in.readLine();
        if (line == null) done = true;
        else
        {
            do something with line
        }
    }
}
```

Harry Hacker|35500|1989-10-01
Carl Cracker|75000|1987-12-15
Tony Tester|38000|1990-03-15

```
public static void writeEmployee(PrintWriter out, Employee e)
{
    out.println(e.getName() + "|" + e.getSalary() + "|" + e.getHireDay());
}
```

```
public static Employee readEmployee(Scanner in)
{
    String line = in.nextLine();
    String[] tokens = line.split("\\|");
    String name = tokens[0];
    double salary = Double.parseDouble(tokens[1]);
    LocalDate hireDate = LocalDate.parse(tokens[2]);
    int year = hireDate.getYear();
    int month = hireDate.getMonthValue();
    int day = hireDate.getDayOfMonth();
    return new Employee(name, salary, year, month, day);
}

void writeData(Employee[] e, PrintWriter out)

Employee[] readData(Scanner in)

int n = in.nextInt();
in.nextLine(); // consume newline
var employees = new Employee[n];
for (int i = 0; i < n; i++)
{
    employees[i] = new Employee();
    employees[i].readData(in);
}
```

```
1 package textfile;
2
3 import java.io.*;
4 import java.nio.charset.*;
5 import java.time.*;
6 import java.util.*;
7
8 /**
9  * @version 1.15 2018-03-17
10 * @author Cay Horstmann
11 */
12 public class TextFileTest
13 {
14     public static void main(String[] args) throws IOException
15     {
16         var staff = new Employee[3];
```

```
17     staff[0] = new Employee("Carl Cracker", 75000, 1987, 12, 15);
18     staff[1] = new Employee("Harry Hacker", 50000, 1989, 10, 1);
19     staff[2] = new Employee("Tony Tester", 40000, 1990, 3, 15);
20
21     // save all employee records to the file employee.dat
22     try (var out = new PrintWriter("employee.dat", StandardCharsets.UTF_8))
23     {
24         writeData(staff, out);
25     }
26
27     // retrieve all records into a new array
28     try (var in = new Scanner(
29             new FileInputStream("employee.dat"), "UTF_8"))
30     {
31         Employee[] newStaff = readData(in);
32
33         // print the newly read employee records
34         for (Employee e : newStaff)
35             System.out.println(e);
36     }
37 }
38
39 /**
40 * Writes all employees in an array to a print writer
41 * @param employees an array of employees
42 * @param out a print writer
43 */
44 private static void writeData(Employee[] employees, PrintWriter out)
45     throws IOException
46 {
47     // write number of employees
48     out.println(employees.length);
49
50     for (Employee e : employees)
51         writeEmployee(out, e);
52 }
53
54 /**
55 * Reads an array of employees from a scanner
56 * @param in the scanner
57 * @return the array of employees
58 */
59 private static Employee[] readData(Scanner in)
60 {
61     // retrieve the array size
```

```
63     int n = in.nextInt();
64     in.nextLine(); // consume newline
65
66     var employees = new Employee[n];
67     for (int i = 0; i < n; i++)
68     {
69         employees[i] = readEmployee(in);
70     }
71     return employees;
72 }
73
74 /**
75 * Writes employee data to a print writer
76 * @param out the print writer
77 */
78 public static void writeEmployee(PrintWriter out, Employee e)
79 {
80     out.println(e.getName() + "|" + e.getSalary() + "|" + e.getHireDay());
81 }
82
83 /**
84 * Reads employee data from a buffered reader
85 * @param in the scanner
86 */
87 public static Employee readEmployee(Scanner in)
88 {
89     String line = in.nextLine();
90     String[] tokens = line.split("\\|");
91     String name = tokens[0];
92     double salary = Double.parseDouble(tokens[1]);
93     LocalDate hireDate = LocalDate.parse(tokens[2]);
94     int year = hireDate.getYear();
95     int month = hireDate.getMonthValue();
96     int day = hireDate.getDayOfMonth();
97     return new Employee(name, salary, year, month, day);
98 }
99 }
```

```
StandardCharsets.UTF_8
StandardCharsets.UTF_16
StandardCharsets.UTF_16BE
StandardCharsets.UTF_16LE
StandardCharsets.ISO_8859_1
StandardCharsets.US_ASCII

Charset shiftJIS = Charset.forName("Shift-JIS");

var str = new String(bytes, StandardCharsets.UTF_8);

readInt          readDouble
readShort         readChar
readLong          readBoolean
readFloat         readUTF

var in = new DataInputStream(new FileInputStream("employee.dat"));

var out = new DataOutputStream(new FileOutputStream("employee.dat"));

var in = new RandomAccessFile("employee.dat", "r");
var inOut = new RandomAccessFile("employee.dat", "rw");

long n = 3;
in.seek((n - 1) * RECORD_SIZE);
var e = new Employee();
e.readData(in);

in.seek((n - 1) * RECORD_SIZE);
e.writeData(out);

long nbytes = in.length(); // length in bytes
int nrecords = (int) (nbytes / RECORD_SIZE);
```

```
public static void writeFixedString(String s, int size, DataOutput out)
    throws IOException
{
    for (int i = 0; i < size; i++)
    {
        char ch = 0;
        if (i < s.length()) ch = s.charAt(i);
        out.writeChar(ch);
    }
}

public static String readFixedString(int size, DataInput in)
    throws IOException
{
    var b = new StringBuilder(size);
    int i = 0;
    var done = false;
    while (!done && i < size)
    {
        char ch = in.readChar();
        i++;
        if (ch == 0) done = true;
        else b.append(ch);
    }
    in.skipBytes(2 * (size - i));
    return b.toString();
}

DataIO.writeFixedString(e.getName(), Employee.NAME_SIZE, out);
out.writeDouble(e.getSalary());
LocalDate hireDay = e.getHireDay();
out.writeInt(hireDay.getYear());

out.writeInt(hireDay.getMonthValue());
out.writeInt(hireDay.getDayOfMonth());

String name = DataIO.readFixedString(Employee.NAME_SIZE, in);
double salary = in.readDouble();
int y = in.readInt();
int m = in.readInt();
int d = in.readInt();
```

```
1 package randomAccess;
2
3 import java.io.*;
4 import java.time.*;
5
6 /**
7  * @version 1.14 2018-05-01
8  * @author Cay Horstmann
9  */
10 public class RandomAccessTest
11 {
12     public static void main(String[] args) throws IOException
13     {
14         var staff = new Employee[3];
15
16         staff[0] = new Employee("Carl Cracker", 75000, 1987, 12, 15);
17         staff[1] = new Employee("Harry Hacker", 50000, 1989, 10, 1);
18         staff[2] = new Employee("Tony Tester", 40000, 1990, 3, 15);
19
20         try (var out = new DataOutputStream(new FileOutputStream("employee.dat")))
21         {
22             // save all employee records to the file employee.dat
```

```
23         for (Employee e : staff)
24             writeData(out, e);
25     }
26
27     try {var in = new RandomAccessFile("employee.dat", "r")}
28     {
29         // retrieve all records into a new array
30
31         // compute the array size
32         int n = (int)(in.length() / Employee.RECORD_SIZE);
33         var newStaff = new Employee[n];
34
35         // read employees in reverse order
36         for (int i = n - 1; i >= 0; i--)
37         {
38             newStaff[i] = new Employee();
39             in.seek(i * Employee.RECORD_SIZE);
40             newStaff[i] = readData(in);
41         }
42
43         // print the newly read employee records
44         for (Employee e : newStaff)
45             System.out.println(e);
46     }
47 }
48
49 /**
50 * Writes employee data to a data output
51 * @param out the data output
52 * @param e the employee
53 */
54 public static void writeData(DataOutput out, Employee e) throws IOException
55 {
56     DataIO.writeFixedString(e.getName(), Employee.NAME_SIZE, out);
57     out.writeDouble(e.getSalary());
58
59     LocalDate hireDay = e.getHireDay();
60     out.writeInt(hireDay.getYear());
61     out.writeInt(hireDay.getMonthValue());
62     out.writeInt(hireDay.getDayOfMonth());
63 }
64
65 /**
66 * Reads employee data from a data input
67 * @param in the data input
68 * @return the employee
69 */
```

```
70     public static Employee readData(DataInput in) throws IOException
71     {
72         String name = DataIO.readFixedString(Employee.NAME_SIZE, in);
73         double salary = in.readDouble();
74         int y = in.readInt();
75         int m = in.readInt();
76         int d = in.readInt();
77         return new Employee(name, salary, y, m - 1, d);
78     }
79 }
```

```
var zin = new ZipInputStream(new FileInputStream(zipname));
boolean done = false;
while (!done)
{
    ZipEntry entry = zin.getNextEntry();
    if (entry == null) done = true;
    else
    {
        read the contents of zin
        zin.closeEntry();
    }
}
zin.close();

var fout = new FileOutputStream("test.zip");
var zout = new ZipOutputStream(fout);
for all files
{
    var ze = new ZipEntry(filename);
    zout.putNextEntry(ze);
    send data to zout
    zout.closeEntry();
}
zout.close();

var out = new ObjectOutputStream(new FileOutputStream("employee.dat"));
```

```
var harry = new Employee("Harry Hacker", 50000, 1989, 10, 1);
var boss = new Manager("Carl Cracker", 80000, 1987, 12, 15);
out.writeObject(harry);
out.writeObject(boss);

var in = new ObjectInputStream(new FileInputStream("employee.dat"));

var e1 = (Employee) in.readObject();
var e2 = (Employee) in.readObject();

class Employee implements Serializable { . . . }

class Manager extends Employee
{
    private Employee secretary;
    . .
}

var harry = new Employee("Harry Hacker", . . .);
var carl = new Manager("Carl Cracker", . . .);
carl.setSecretary(harry);
var tony = new Manager("Tony Tester", . . .);
tony.setSecretary(harry);
```

```
1 package serial;
2
3 import java.io.*;
4
5 /**
6  * @version 1.12 2021-09-10
7  * @author Cay Horstmann
8  */
9 class ObjectStreamTest
10 {
11     public static void main(String[] args) throws IOException, ClassNotFoundException
12     {
13         var harry = new Employee("Harry Hacker", 50000, 1989, 10, 1);
14         var carl = new Manager("Carl Cracker", 80000, 1987, 12, 15);
15         carl.setSecretary(harry);
16         var tony = new Manager("Tony Tester", 40000, 1998, 3, 15);
17         tony.setSecretary(harry);
18
19         var staff = new Employee[3];
20
21         staff[0] = carl;
22         staff[1] = harry;
23         staff[2] = tony;
24
25         // save all employee records to the file employee.ser
26         try (var out = new ObjectOutputStream(new FileOutputStream("employee.ser")))
27         {
28             out.writeObject(staff);
29         }
30
31         try (var in = new ObjectInputStream(new FileInputStream("employee.ser")))
32         {
33             // retrieve all records into a new array
34
35             var newStaff = (Employee[]) in.readObject();
36
37             // raise secretary's salary
38             newStaff[1].raiseSalary(10);
39
40             // print the newly read employee records
41             for (Employee e : newStaff)
42                 System.out.println(e);
43         }
44     }
45 }
```

```
class Person // Not serializable
class Employee extends Person implements Serializable

@Serial private void readObject(ObjectInputStream in)
    throws IOException, ClassNotFoundException;
@Serial private void writeObject(ObjectOutputStream out)
    throws IOException;

public class LabeledPoint implements Serializable
{
    private String label;
    private transient Point2D.Double point;
    . . .

}

private void writeObject(ObjectOutputStream out) throws IOException
{
    out.defaultWriteObject();
    out.writeDouble(point.getX());
    out.writeDouble(point.getY());
}

private void readObject(ObjectInputStream in)
    throws IOException, ClassNotFoundException
{
    in.defaultReadObject();
    double x = in.readDouble();
    double y = in.readDouble();
    point = new Point2D.Double(x, y);
}

@Serial private static final ObjectStreamField[] serialPersistentFields

public void readExternal(ObjectInput in) throws IOException, ClassNotFoundException;
public void writeExternal(ObjectOutput out) throws IOException;
```

```
public class LabeledPixel extends Point implements Externalizable
{
    private String label;

    public LabeledPixel() {} // required for externalizable class

    public void writeExternal(ObjectOutput out) throws IOException
    {
        out.writeInt((int) getX());
        out.writeInt((int) getY());
        out.writeUTF(label);
    }

    public void readExternal(ObjectInput in)
        throws IOException, ClassNotFoundException
    {
        int x = in.readInt();
        int y = in.readInt();
        setLocation(x, y);
        label = in.readUTF();
    }

    ...
}

public class Orientation
{
    public static final Orientation HORIZONTAL = new Orientation(1);
    public static final Orientation VERTICAL = new Orientation(2);

    private int value;

    private Orientation(int v)
    {
        value = v;
    }
}

if (orientation == Orientation.HORIZONTAL) . . .
```

```
Orientation original = Orientation.HORIZONTAL;
ObjectOutputStream out = . . .;
out.write(original);
out.close();
ObjectInputStream in = . . .;
var saved = (Orientation) in.read();

if (saved == Orientation.HORIZONTAL) . . .

@Serial private Object readResolve() throws ObjectStreamException
{
    if (value == 1) return Orientation.HORIZONTAL;
    else if (value == 2) return Orientation.VERTICAL;
    else throw new ObjectStreamException(); // this shouldn't happen
}

public enum MySingleton
{
    INSTANCE;
    MySingleton() { . . . } // automatically private
    // instance fields
    // methods
}

@Serial private Object writeReplace() throws ObjectStreamException

public class ColoredPoint implements Serializable
{
    private Color color;
    private Point location;

    public ColoredPoint(Color color, int x, int y)
    {
        this.color = color;
        this.location = new Point(x, y);
    }

    @Serial private Object writeReplace() throws ObjectStreamException
{
```

```
        return new Ser(color.getRGB(), location.x, location.y);
    }

private record Ser(int rgba, int x, int y) implements Serializable
{
    @Serial private Object readResolve() throws ObjectStreamException
    {
        return new ColoredPoint(new Color(rgba), x, y);
    }
}

serialver serial.Employee

serial.Employee: static final long serialVersionUID = 8367346051156850807L;

class Employee implements Serializable // version 1.1
{
    ...
    @Serial public static final long serialVersionUID = 8367346051156850807L;
}
```

```
1 package serialClone;
2
3 /**
4  * @version 1.22 2018-05-01
5  * @author Cay Horstmann
6  */
7
8 import java.io.*;
9 import java.time.*;
10
11 public class SerialCloneTest
12 {
13     public static void main(String[] args) throws CloneNotSupportedException
14     {
15         var harry = new Employee("Harry Hacker", 35000, 1989, 10, 1);
16         // clone harry
17         var harry2 = (Employee) harry.clone();
18
19         // mutate harry
20         harry.raiseSalary(10);
21
22         // now harry and the clone are different
23         System.out.println(harry);
24         System.out.println(harry2);
25     }
26 }
```

```
27
28 /**
29 * A class whose clone method uses serialization.
30 */
31 class SerialCloneable implements Cloneable, Serializable
32 {
33     public Object clone() throws CloneNotSupportedException
34     {
35         try {
36             // save the object to a byte array
37             var bout = new ByteArrayOutputStream();
38             try (var out = new ObjectOutputStream(bout))
39             {
40                 out.writeObject(this);
41             }
42
43             // read a clone of the object from the byte array
44             try (var bin = new ByteArrayInputStream(bout.toByteArray()))
45             {
46                 var in = new ObjectInputStream(bin);
47                 return in.readObject();
48             }
49         }
50         catch (IOException | ClassNotFoundException e)
51         {
```

```
52         var e2 = new CloneNotSupportedException();
53         e2.initCause(e);
54         throw e2;
55     }
56 }
57 }
58 */
59 /**
60 * The familiar Employee class, redefined to extend the
61 * Serializable class.
62 */
63 class Employee extends Serializable
64 {
65     private String name;
66     private double salary;
67     private LocalDate hireDay;
68
69     public Employee(String n, double s, int year, int month, int day)
70     {
71         name = n;
72         salary = s;
73         hireDay = LocalDate.of(year, month, day);
74     }
75
76     public String getName()
77     {
78         return name;
79     }
80
81     public double getSalary()
82     {
83         return salary;
84     }
```

```
85     public LocalDate getHireDay()
86     {
87         return hireDay;
88     }
89
90
91     /**
92      Raises the salary of this employee.
93      @param byPercent the percentage of the raise
94     */
95     public void raiseSalary(double byPercent)
96     {
97         double raise = salary * byPercent / 100;
98         salary += raise;
99     }
100
101    public String toString()
102    {
103        return getClass().getName()
104            + "{name=" + name
105            + ",salary=" + salary
106            + ",hireDay=" + hireDay
107            + "}";
108    }
109 }



---


public void validateObject() throws InvalidObjectException
{
    System.out.println("validateObject");
    if (salary < 0)
        throw new InvalidObjectException("salary < 0");
}

@Serial private void readObject(ObjectInputStream in)
    throws IOException, ClassNotFoundException
{
    in.registerValidation(this, 0);
    in.defaultReadObject();
}
```

```
java -Djdk.serialFilter='serial.*;java.**;!*' serial.ObjectStreamTest

Path absolute = Path.of("/home", "harry");
Path relative = Path.of("myprog", "conf", "user.properties");

String baseDir = props.getProperty("base.dir");
    // May be a string such as /opt/myprog or c:\Program Files\myprog
Path basePath = Path.of(baseDir); // OK that baseDir has separators

Path workRelative = Path.of("work");
Path workPath = basePath.resolve(workRelative);

Path workPath = basePath.resolve("work");

Path tempPath = workPath.resolveSibling("temp");

Path p = Path.of("/home", "fred", "myprog.properties");
Path parent = p.getParent(); // the path /home/fred
Path file = p.getFileName(); // the path myprog.properties
Path root = p.getRoot(); // the path /

var in = new Scanner(Path.of("/home/fred/input.txt"));

byte[] bytes = Files.readAllBytes(path);
String content = Files.readString(path, charset);
List<String> lines = Files.readAllLines(path, charset);
Stream<String> lineStream = Files.lines(path, charset);

Files.write(path, bytes);
Files.writeString(path, content, charset);
Path.write(path, lines, charset);

Files.write(path, content, charset, StandardOpenOption.APPEND);

long pos = Files.mismatch(path1, path2);

String mimeType = Files.probeContentType(path);
```

```
InputStream in = Files.newInputStream(path);
OutputStream out = Files.newOutputStream(path);
Reader in = Files.newBufferedReader(path, charset);
Writer out = Files.newBufferedWriter(path, charset);

Files.createDirectory(path);

Files.createDirectories(path);

Files.createFile(path);

Path newPath = Files.createTempFile(dir, prefix, suffix);
Path newPath = Files.createTempFile(prefix, suffix);
Path newPath = Files.createTempDirectory(dir, prefix);
Path newPath = Files.createTempDirectory(prefix);

Files.copy(fromPath, toPath);

Files.move(fromPath, toPath);

Files.copy(fromPath, toPath, StandardCopyOption.REPLACE_EXISTING,
          StandardCopyOption.COPY_ATTRIBUTES);

Files.move(fromPath, toPath, StandardCopyOption.ATOMIC_MOVE);

Files.copy(inputStream, toPath);
Files.copy(fromPath, outputStream);

boolean deleted = Files.deleteIfExists(path);

long fileSize = Files.size(path);

BasicFileAttributes attributes = Files.readAttributes(path, BasicFileAttributes.class);

PosixFileAttributes attributes = Files.readAttributes(path, PosixFileAttributes.class);

try (Stream<Path> entries = Files.list(pathToDirectory))
{
    . .
}
```

```
try (Stream<Path> entries = Files.walk(pathToRoot))
{
    // Contains all descendants, visited in depth-first order
}

java
java/nio
java/nio/DirectCharBufferU.java
java/nio/ByteBufferAsShortBufferRL.java
java/nio/MappedByteBuffer.java
...
java/nio/ByteBufferAsDoubleBufferB.java
java/nio/charset
java/nio/charset/CoderMalfunctionError.java
java/nio/charset/CharsetDecoder.java
java/nio/charset/UnsupportedCharsetException.java
java/nio/charset/spi
java/nio/charset/spi/CharsetProvider.java
java/nio/charset/StandardCharsets.java
java/nio/charset/Charset.java
...
java/nio/charset/CoderResult.java
java/nio/HeapFloatBufferR.java
...

Files.walk(source).forEach(p ->
{
    try
    {
        Path q = target.resolve(source.relativize(p));
        if (Files.isDirectory(p))
            Files.createDirectory(q);
        else
            Files.copy(p, q);
    }
    catch (IOException e)
    {
        throw new UncheckedIOException(ex);
    }
});
```

```
try (DirectoryStream<Path> entries = Files.newDirectoryStream(dir))
{
    for (Path entry : entries)
        Process entries
}

try (DirectoryStream<Path> entries = Files.newDirectoryStream(dir, "*.java"))

Files.walkFileTree(Path.of("/"), new SimpleFileVisitor<Path>()
{
    public FileVisitResult preVisitDirectory(Path path, BasicFileAttributes attrs)
        throws IOException
    {
        System.out.println(path);
        return FileVisitResult.CONTINUE;
    }

    public FileVisitResult postVisitDirectory(Path dir, IOException e)
    {
        return FileVisitResult.CONTINUE;
    }

    public FileVisitResult visitFileFailed(Path path, IOException e) throws IOException
    {
        return FileVisitResult.SKIP_SUBTREE;
    }
});
```

```
// Delete the directory tree starting at root
Files.walkFileTree(root, new SimpleFileVisitor<Path>()
{
    public FileVisitResult visitFile(Path file, BasicFileAttributes attrs)
        throws IOException
    {
        Files.delete(file);
        return FileVisitResult.CONTINUE;
    }

    public FileVisitResult postVisitDirectory(Path dir, IOException e) throws IOException
    {
        if (e != null) throw e;
        Files.delete(dir);
        return FileVisitResult.CONTINUE;
    }
});

FileSystem fs = FileSystems.newFileSystem(Path.of(zipname));

Files.copy(fs.getPath(sourceName), targetPath);

FileSystem fs = FileSystems.newFileSystem(Path.of(zipname));
Files.walkFileTree(fs.getPath("/"), new SimpleFileVisitor<Path>()
{
    public FileVisitResult visitFile(Path file, BasicFileAttributes attrs)
        throws IOException
    {
        System.out.println(file);
        return FileVisitResult.CONTINUE;
    }
});

FileChannel channel = FileChannel.open(path, options);

MappedByteBuffer buffer = channel.map(FileChannel.MapMode.READ_ONLY, 0, channel.size());
```

```
while (buffer.hasRemaining())
{
    byte b = buffer.get();
    ...
}

for (int i = 0; i < buffer.limit(); i++)
{
    byte b = buffer.get(i);
    ...
}

get(byte[] bytes)
get(byte[] bytes, int offset, int length)

getInt          getChar
getLong         getFloat
getShort        getDouble

buffer.order(ByteOrder.LITTLE_ENDIAN);

ByteOrder b = buffer.order();

putInt          putChar
putLong         putFloat
putShort        putDouble

var crc = new CRC32();
while (more bytes)
    crc.update(next byte);
long checksum = crc.getValue();

java memoryMap.MemoryMapTest filename
```

```
1 package memoryMap;
2
3 import java.io.*;
4 import java.nio.*;
5 import java.nio.channels.*;
6 import java.nio.file.*;
7 import java.util.zip.*;
8
9 /**
10 * This program computes the CRC checksum of a file in four ways. <br>
11 * Usage: java memoryMap.MemoryMapTest filename
12 * @version 1.03 2018-05-01
13 * @author Cay Horstmann
14 */
15 public class MemoryMapTest
16 {
17     public static long checksumInputStream(Path filename) throws IOException
18     {
19         try (InputStream in = Files.newInputStream(filename))
20         {
21             var crc = new CRC32();
22             boolean done = false;
23             while (!done)
24             {
25                 int c = in.read();
26                 if (c == -1) done = true;
27                 else crc.update(c);
28             }
29             return crc.getValue();
30         }
31     }
32
33     public static long checksumBufferedInputStream(Path filename) throws IOException
34     {
35         try (var in = new BufferedInputStream(Files.newInputStream(filename)))
36         {
37             var crc = new CRC32();
38
39             boolean done = false;
40             while (!done)
41             {
```

```
42         int c = in.read();
43         if (c == -1) done = true;
44         else crc.update(c);
45     }
46     return crc.getValue();
47 }
48 }
49
50 public static long checksumRandomAccessFile(Path filename) throws IOException
51 {
52     try (var file = new RandomAccessFile(filename.toFile(), "r"))
53     {
54         long length = file.length();
55         var crc = new CRC32();
56
57         for (long p = 0; p < length; p++)
58         {
59             int c = file.readByte();
60             crc.update(c);
61         }
62         return crc.getValue();
63     }
64 }
65
66 public static long checksumMappedFile(Path filename) throws IOException
67 {
68     try (FileChannel channel = FileChannel.open(filename))
69     {
70         var crc = new CRC32();
71         int length = (int) channel.size();
72         MappedByteBuffer buffer = channel.map(FileChannel.MapMode.READ_ONLY, 0, length);
73
74         for (int p = 0; p < length; p++)
75         {
76             int c = buffer.get(p);
77             crc.update(c);
78         }
79         return crc.getValue();
80     }
81 }
82
83 public static void main(String[] args) throws IDEException
84 {
85     System.out.println("Input Stream:");
86     long start = System.currentTimeMillis();
87     Path filename = Path.of(args[0]);
88     long crcValue = checksumInputStream(filename);
89     long end = System.currentTimeMillis();
```

```
90     System.out.println(Long.toHexString(crcValue));
91     System.out.println((end - start) + " milliseconds");
92
93     System.out.println("Buffered Input Stream:");
94     start = System.currentTimeMillis();
95     crcValue = checksumBufferedInputStream(filename);
96     end = System.currentTimeMillis();
97     System.out.println(Long.toHexString(crcValue));
98     System.out.println((end - start) + " milliseconds");
99
100    System.out.println("Random Access File:");
101    start = System.currentTimeMillis();
102    crcValue = checksumRandomAccessFile(filename);
103    end = System.currentTimeMillis();
104    System.out.println(Long.toHexString(crcValue));
105    System.out.println((end - start) + " milliseconds");
106
107    System.out.println("Mapped File:");
108    start = System.currentTimeMillis();
109    crcValue = checksumMappedFile(filename);
110    end = System.currentTimeMillis();
111    System.out.println(Long.toHexString(crcValue));
112    System.out.println((end - start) + " milliseconds");
113  }
114 }
```

```
ByteBuffer buffer = ByteBuffer.allocate(RECORD_SIZE);
channel.read(buffer);
channel.position(newpos);
buffer.flip();
channel.write(buffer);

FileChannel = FileChannel.open(path);
FileLock lock = channel.lock();

FileLock lock = channel.tryLock();

FileLock lock(long start, long size, boolean shared)

FileLock tryLock(long start, long size, boolean shared)
```

```
try (FileLock lock = channel.lock())
{
    access the locked file or segment
}

String regex = "-]?\d+";
CharSequence input = . . .;
if (Pattern.matches(regex, input))
{
    . . .
}

Pattern pattern = Pattern.compile(regex);
Matcher matcher = pattern.matcher(input);
if (matcher.matches()) . . .

Stream<String> strings = . . .;
List<String> result = strings.filter(pattern.asPredicate()).toList();

String input = . . .;
Matcher matcher = pattern.matcher(input);
while (matcher.find())
{
    String match = matcher.group();
    int matchStart = matcher.start();

    int matchEnd = matcher.end();
    . . .
}

List<String> matches = pattern.matcher(input)
    .results()
    .map(Matcher::group)
    .toList();

Scanner in = new Scanner(path, "UTF_8");
Stream<String> words = in.findAll("\\pL+")
    .map(MatchResult::group);

java match.HrefMatch http://horstmann.com
```

```
1 package match;
2
3 import java.io.*;
4 import java.net.*;
5 import java.nio.charset.*;
6 import java.util.regex.*;
7
8 /**
9  * This program displays all URLs in a web page by matching a regular expression that
10 * describes the <a href=...> HTML tag. Start the program as <br>
11 * java match.HrefMatch URL
12 * @version 1.04 2019-08-28
13 * @author Cay Horstmann
14 */
15 public class HrefMatch
16 {
```

```
17  public static void main(String[] args)
18  {
19      try
20      {
21          // get URL string from command line or use default
22          String urlString;
23          if (args.length > 0) urlString = args[0];
24          else urlString = "http://openjdk.java.net/";
25
26          // read contents of URL
27          InputStream in = new URL(urlString).openStream();
28          var input = new String(in.readAllBytes(), StandardCharsets.UTF_8);
29
30          // search for all occurrences of pattern
31          String patternString = "<a\\s+href\\s*=\\s*(\"[^\"\\"]*\"|[^\\s]*')\\s*>";
32          Pattern pattern = Pattern.compile(patternString, Pattern.CASE_INSENSITIVE);
33          pattern.matcher(input)
34              .results()
35              .map(MatchResult::group)
36              .forEach(System.out::println);
37      }
38      catch (IOException | PatternSyntaxException e)
39      {
40          e.printStackTrace();
41      }
42  }
43 }
```

Blackwell Toaster USD29.95

(\p{Alnum}+(\s+\p{Alnum}+*)\s+([A-Z]{3})([0-9.]*))

String contents = matcher.group(n);

```
Matcher matcher = pattern.matcher(input);
if (matcher.matches())
{
    item = matcher.group(1);
```

```
currency = matcher.group(3);
price = matcher.group(4);
}

(\p{Alnum}+(:\s+\p{Alnum}+)*)\s+([A-Z]{3})([0-9.]*)
(?<item>\p{Alnum}+(\s+\p{Alnum}+)*)\s+(?<currency>[A-Z]{3})(?<price>[0-9.]*)

item = matcher.group("item");

int itemStart = matcher.start("item");
int itemEnd = matcher.end("item");
```

```
1 package regex;
2
3 /**
4  * This program tests regular expression matching. Enter a pattern and strings to match,
5  * or hit Cancel to exit. If the pattern contains groups, the group boundaries are displayed
6  * in the match.
7  * @version 1.03 2018-05-01
8  * @author Cay Horstmann
9  */
10
11 import java.util.*;
12 import java.util.regex.*;
13
14 public class RegexTest
15 {
16     public static void main(String[] args) throws PatternSyntaxException
17     {
18         var in = new Scanner(System.in);
19         System.out.println("Enter pattern: ");
20         String patternString = in.nextLine();
21
22         Pattern pattern = Pattern.compile(patternString);
23
24         while (true)
25         {
26             System.out.println("Enter string to match: ");
27             String input = in.nextLine();
28             if (input == null || input.equals("")) return;
29             Matcher matcher = pattern.matcher(input);
30             if (matcher.matches())
31             {
32                 System.out.println("Match");
33                 int g = matcher.groupCount();
34                 if (g > 0)
35                 {
36                     for (int i = 0; i < input.length(); i++)
37                     {
38                         // Print any empty groups
39                         for (int j = 1; j <= g; j++)
40                             if (i == matcher.start(j) && i == matcher.end(j))
41                                 System.out.print("()");
42                         // Print { for non-empty groups starting here
43                         for (int j = 1; j <= g; j++)
44                             if (i == matcher.start(j) && i != matcher.end(j))
45                                 System.out.print('(');
46                         System.out.print(input.charAt(i));
47                     }
48                 }
49             }
50         }
51     }
52 }
```

```
47         // Print ) for non-empty groups ending here
48         for (int j = 1; j <= g; j++)
49             if (i + 1 != matcher.start(j) && i + 1 == matcher.end(j))
50                 System.out.print(')');
51         }
52         System.out.println();
53     }
54 }
55 else
56     System.out.println("No match");
57 }
58 }
59 }
```

```
String input = . . .;
Pattern commas = Pattern.compile("\\s*,\\s*");
String[] tokens = commas.split(input);
// "1, 2, 3" turns into ["1", "2", "3"]

Stream<String> tokens = commas.splitAsStream(input);

String[] tokens = input.split("\\s*,\\s*");

Scanner in = new Scanner(path, "UTF_8");
in.useDelimiter("\\s*,\\s*");
Stream<String> tokens = in.tokens();

Matcher matcher = commas.matcher(input);
String result = matcher.replaceAll(",");
// Normalizes the commas

String result = input.replaceAll("\\s*,\\s*", ",");

String result = "3:45".replaceAll(
    "(\\d{1,2}):(?<minutes\\d{2})",
    "$1 hours and ${minutes} minutes");
// Sets result to "3 hours and 45 minutes"

matcher.replaceAll(Matcher.quoteReplacement(str))
```

```
String result = Pattern.compile("\\pL{4,}")
    .matcher("Mary had a little lamb")
    .replaceAll(m -> m.group().toUpperCase());
// Yields "MARY had a LITTLE LAMB"

Pattern pattern = Pattern.compile(regex,
    Pattern.CASE_INSENSITIVE | Pattern.UNICODE_CHARACTER_CLASS);

String regex = "(?iU:expression)";
```

```
<config>
  <entry id="title">
    <font>
      <name>Helvetica</name>
      <size>36</size>
    </font>
  </entry>
  <entry id="body">
    <font>
      <name>Times Roman</name>
      <size>12</size>
    </font>
  </entry>
  <entry id="background">
    <color>
      <red>0</red>
      <green>50</green>
      <blue>100</blue>
    </color>
  </entry>
</config>

<?xml version="1.0" encoding="UTF-8"?>

<!DOCTYPE web-app PUBLIC
  "-//Sun Microsystems, Inc.//DTD Web Application 2.2//EN"
  "http://java.sun.com/j2ee/dtds/web-app_2_2.dtd">

<font name="Helvetica" size="36"/>

<font name="Helvetica" size="36 pt"/>

<a href="http://java.sun.com">Java Technology</a>

<![CDATA[< & > are my favorite delimiters]]>

<?xmlstylesheet href="mystyle.css" type="text/css"?>
```

```
DocumentBuilderFactory factory = DocumentBuilderFactory.newInstance();
DocumentBuilder builder = factory.newDocumentBuilder();

File f = . . .;
Document doc = builder.parse(f);

URL u = . . .;
Document doc = builder.parse(u.toString());

InputStream in = . . .;
Document doc = builder.parse(in);

Element root = doc.getDocumentElement();

NodeList children = root.getChildNodes();
for (int i = 0; i < children.getLength(); i++)
{
    Node child = children.item(i);
    . . .
}

for (int i = 0; i < children.getLength(); i++)
{
    Node child = children.item(i);
    if (child instanceof Element childElement)
    {
        . . .
    }
}
```

```
for (int i = 0; i < children.getLength(); i++)
{
    Node child = children.item(i);
    if (child instanceof Element childElement)
    {
        var textNode = (Text) childElement.getFirstChild();
        String text = textNode.getData().strip();
        if (childElement.getTagName().equals("name"))
            name = text;
        else if (childElement.getTagName().equals("size"))
            size = Integer.parseInt(text);
    }
}

for (Node childNode = element.getFirstChild();
     childNode != null;
     childNode = childNode.getNextSibling())
{
    ...
}

NamedNodeMap attributes = element.getAttributes();
for (int i = 0; i < attributes.getLength(); i++)
{
    Node attribute = attributes.item(i);
    String name = attribute.getNodeName();
    String value = attribute.getNodeValue();
    ...
}

String unit = element.getAttribute("unit");

1 package dom;
2
3 import java.io.*;
4 import java.util.*;
```

```
5 import javax.xml.parsers.*;
6
7
8 import org.w3c.dom.*;
9 import org.xml.sax.*;
10
11 /**
12 * This program displays an XML document as a tree in JSON format.
13 * @version 1.21 2021-05-30
14 * @author Cay Horstmann
15 */
16 public class JSONConverter
17 {
18     public static void main(String[] args)
19         throws SAXException, IOException, ParserConfigurationException
20     {
21         String filename;
22         if (args.length == 0)
23         {
24             try (var in = new Scanner(System.in))
25             {
26                 System.out.print("Input file: ");
27                 filename = in.nextLine();
28             }
29         }
30         else
31             filename = args[0];
32         DocumentBuilderFactory factory = DocumentBuilderFactory.newInstance();
33         DocumentBuilder builder = factory.newDocumentBuilder();
34
35         Document doc = builder.parse(filename);
36         Element root = doc.getDocumentElement();
37         System.out.println(convert(root, 0));
38     }
39
40     public static StringBuilder convert(Node node, int level)
41     {
42         if (node instanceof Element elem)
43         {
44             return elementObject(elem, level);
45         }
46         else if (node instanceof CharacterData cd)
47         {
48             return characterString(cd, level);
49         }
50         else
51         {
52             return pad(new StringBuilder(), level).append(
53                 jsonEscape(node.getClass().getName()));
54         }
55     }
56 }
```

```
54     }
55 }
56
57 private static Map<Character, String> replacements = Map.of('\b', "\b", '\f', "\f",
58   '\n', "\n", '\r', "\r", '\t', "\t", '\"', "\\\"", '\\', "\\\"");
59
60 private static StringBuilder jsonEscape(String str)
61 {
62     var result = new StringBuilder("");
63     for (int i = 0; i < str.length(); i++)
64     {
65         char ch = str.charAt(i);
66         String replacement = replacements.get(ch);
67         if (replacement == null) result.append(ch);
68         else result.append(replacement);
69     }
70     result.append("");
71     return result;
72 }
73
74 private static StringBuilder characterString(CharacterData node, int level)
75 {
76     var result = new StringBuilder();
77     StringBuilder data = jsonEscape(node.getData());
78     if (node instanceof Comment) data.insert(1, "Comment: ");
79     pad(result, level).append(data);
80     return result;
81 }
82
83 private static StringBuilder elementObject(Element elem, int level)
84 {
85     var result = new StringBuilder();
86     pad(result, level).append("{\n");
87     pad(result, level + 1).append("\name": ");
88     result.append(jsonEscape(elem.getTagName()));
89     NamedNodeMap attrs = elem.getAttributes();
90     if (attrs.getLength() > 0)
91     {
92         pad(result.append(",\n"), level + 1).append("\attributes": );
93         result.append(attributeObject(attrs));
94     }
95     NodeList children = elem.getChildNodes();
96     if (children.getLength() > 0)
97     {
98         pad(result.append(",\n"), level + 1).append("\children": [\n");
99         for (int i = 0; i < children.getLength(); i++)
100        {
```

```
101         if (i > 0) result.append(",\n");
102         result.append(convert(children.item(i), level + 2));
103     }
104     result.append("\n");
105     pad(result, level + 1).append("]\n");
106 }
107 pad(result, level).append("}");
108 return result;
109 }
110
111 private static StringBuilder pad(StringBuilder builder, int level)
112 {
113     for (int i = 0; i < level; i++) builder.append("  ");
114     return builder;
115 }
116
117 private static StringBuilder attributeObject(NamedNodeMap attrs)
118 {
119     var result = new StringBuilder("{}");
120     for (int i = 0; i < attrs.getLength(); i++)
121     {
122         if (i > 0) result.append(", ");
123         result.append(jsonEscape(attrs.item(i).getNodeName()));
124         result.append(": ");
125         result.append(jsonEscape(attrs.item(i).getNodeValue()));
126     }
127     result.append("}");
128     return result;
129 }
130 }

<xsd:element name="font">
    <xsd:sequence>
        <xsd:element name="name" type="xsd:string"/>
        <xsd:element name="size" type="xsd:int"/>
    </xsd:sequence>
</xsd:element>

<!DOCTYPE config SYSTEM "config.dtd">

<!DOCTYPE config SYSTEM "http://myserver.com/config.dtd">
```

```
<!DOCTYPE web-app
PUBLIC "-//Sun Microsystems, Inc.//DTD Web Application 2.2//EN"
"http://java.sun.com/j2ee/dtds/web-app_2_2.dtd">

<?xml Version="1.0"?>
<!DOCTYPE catalog PUBLIC "-//OASIS//DTD XML Catalogs V1.0//EN"
"http://www.oasis-open.org/committees/entity/release/1.0/catalog.dtd">
<catalog xmlns="urn:oasis:names:tc:entity:xmlns:xml:catalog" prefer="public">
  <public publicId=". . ." uri=". . ."/>
  .
  .
</catalog>

builder.setEntityResolver(CatalogManager.catalogResolver(
    CatalogFeatures.defaults(),
    Path.of("catalog.xml").toAbsolutePath().toUri()));

<!ELEMENT chapter (intro,(heading,(para|image|table|note)+)+)

<!ELEMENT para (#PCDATA|em|strong|code)*>

<!ELEMENT captionedImage (image,#PCDATA)>

<!ATTLIST font style (plain|bold|italic|bold-italic) "plain">
<!ATTLIST size unit CDATA #IMPLIED>

<menuitem label="&back.label;"/>

factory.setIgnoringElementContentWhitespace(true);

for (int i = 0; i < children.getLength(); i++)
{
  Node child = children.item(i);
  if (child instanceof Element childElement)
  {

    if (childElement.getTagName().equals("name")) . . .;
    else if (childElement.getTagName().equals("size")) . . .;
  }
}
```

```
var nameElement = (Element) children.item(0);
var sizeElement = (Element) children.item(1);

void warning(SAXParseException e)
void error(SAXParseException e)
void fatalError(SAXParseException e)

builder.setErrorHandler(handler);

<?xml version="1.0"?>
<config xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
         xsi:noNamespaceSchemaLocation="config.xsd">
    ...
</config>

<xsd:simpleType name="StyleType">
    <xsd:restriction base="xsd:string">
        <xsd:enumeration value="PLAIN" />
        <xsd:enumeration value="BOLD" />
        <xsd:enumeration value="ITALIC" />
        <xsd:enumeration value="BOLD_ITALIC" />
    </xsd:restriction>
</xsd:simpleType>

<xsd:element name="name" type="xsd:string"/>
<xsd:element name="size" type="xsd:int"/>
<xsd:element name="style" type="StyleType"/>

<xsd:complexType name="FontType">
    <xsd:sequence>
        <xsd:element ref="name"/>
        <xsd:element ref="size"/>
        <xsd:element ref="style"/>
    </xsd:sequence>
</xsd:complexType>

<xsd:complexType name="FontType">
    <xsd:sequence>
        <xsd:element name="name" type="xsd:string"/>
        <xsd:element name="size" type="xsd:int"/>
```

```
<xsd:element name="style">
  <xsd:simpleType>
    <xsd:restriction base="xsd:string">
      <xsd:enumeration value="PLAIN" />
      <xsd:enumeration value="BOLD" />
      <xsd:enumeration value="ITALIC" />
      <xsd:enumeration value="BOLD_ITALIC" />
    </xsd:restriction>
  </xsd:simpleType>
</xsd:element>
</xsd:sequence>
</xsd:complexType>

<xsd:complexType name="contactinfo">
  <xsd:choice>
    <xsd:element ref="email"/>
    <xsd:element ref="phone"/>
  </xsd:choice>
</xsd:complexType>

<xsd:element name="item" type="..." minoccurs="0" maxoccurs="unbounded">
  <xsd:element name="size">
    <xsd:complexType>
      .
      .
      .
      <xsd:attribute name="unit" type="xsd:string" use="optional" default="cm"/>
    </xsd:complexType>
  </xsd:element>
<!ATTLIST size unit CDATA #IMPLIED "cm">

<xsd:schema xmlns:xsd="http://www.w3.org/2001/XMLSchema">
  .
  .
</xsd:schema>

factory.setNamespaceAware(true);

final String JAXP_SCHEMA_LANGUAGE =
  "http://java.sun.com/xml/jaxp/properties/schemaLanguage";
final String W3C_XML_SCHEMA = "http://www.w3.org/2001/XMLSchema";
factory.setAttribute(JAXP_SCHEMA_LANGUAGE, W3C_XML_SCHEMA);
```

```
<construct class="java.awt.Color">
    <int>55</int>
    <int>200</int>
    <int>100</int>
</construct>

<factory class="java.util.logging.Logger" method="getLogger">
    <string>com.horstmann.corejava</string>
</factory>

<config>
    <entry id="background">
        <construct class="java.awt.Color">
            <value type="int">55</value>
            <value type="int">208</value>
            <value type="int">108</value>
        </construct>
    </entry>
    . .
</config>

1 package read;
2
3 import java.io.*;
4 import java.lang.reflect.*;
5 import java.util.*;
6
7 import javax.xml.parsers.*;
8
9 import org.w3c.dom.*;
10 import org.xml.sax.*;
11
12 /**
13  * This program shows how to use an XML file to describe Java objects
14  * @version 1.0 2018-04-03
15  * @author Cay Horstmann
16  */
17 public class XMLReadTest
18 {
```

```
19 public static void main(String[] args) throws ParserConfigurationException,
20         SAXException, IOException, ReflectiveOperationException
21 {
22     String filename;
23     if (args.length == 0)
24     {
25         try (var in = new Scanner(System.in))
26         {
27             System.out.print("Input file: ");
28             filename = in.nextLine();
29         }
30     }
31     else
32         filename = args[0];
33
34     DocumentBuilderFactory factory = DocumentBuilderFactory.newInstance();
35     factory.setValidating(true);
36
37     if (filename.contains("-schema"))
38     {
39         factory.setNamespaceAware(true);
40         final String JAXP_SCHEMA_LANGUAGE =
41             "http://java.sun.com/xml/jaxp/properties/schemaLanguage";
42         final String W3C_XML_SCHEMA = "http://www.w3.org/2001/XMLSchema";
43         factory.setAttribute(JAXP_SCHEMA_LANGUAGE, W3C_XML_SCHEMA);
44     }
45
46     factory.setIgnoringElementContentWhitespace(true);
47
48     DocumentBuilder builder = factory.newDocumentBuilder();
49
50     builder.setErrorHandler(new ErrorHandler()
51     {
52         public void warning(SAXParseException e) throws SAXException
53         {
54             System.err.println("Warning: " + e.getMessage());
55         }
56
57         public void error(SAXParseException e) throws SAXException
58         {
59             System.err.println("Error: " + e.getMessage());
60             System.exit(0);
61         }
62
63         public void fatalError(SAXParseException e) throws SAXException
64         {
65             System.err.println("Fatal error: " + e.getMessage());
```

```
66             System.exit(0);
67         }
68     });
69
70     Document doc = builder.parse(filename);
71     Map<String, Object> config = parseConfig(doc.getDocumentElement());
72     System.out.println(config);
73 }
74
75 private static Map<String, Object> parseConfig(Element e)
76     throws ReflectiveOperationException
77 {
78     var result = new HashMap<String, Object>();
79     NodeList children = e.getChildNodes();
80     for (int i = 0; i < children.getLength(); i++)
81     {
82         var child = (Element) children.item(i);
83         String name = child.getAttribute("id");
84         Object value = parseObject((Element) child.getFirstChild());
85         result.put(name, value);
86     }
87     return result;
88 }
89
90 private static Object parseObject(Element e)
91     throws ReflectiveOperationException
92 {
93     String tagName = e.getTagName();
94     if (tagName.equals("factory")) return parseFactory(e);
95     else if (tagName.equals("construct")) return parseConstruct(e);
96     else
97     {
98         String childData = ((CharacterData) e.getFirstChild()).getData();
99         if (tagName.equals("int"))
100             return Integer.valueOf(childData);
101         else if (tagName.equals("boolean"))
102             return Boolean.valueOf(childData);
103         else
104             return childData;
105     }
106 }
107
108 private static Object parseFactory(Element e)
109     throws ReflectiveOperationException
110 {
111     String className = e.getAttribute("class");
112     String methodName = e.getAttribute("method");
113     Object[] args = parseArgs(e.getChildNodes());
```

```
114     Class<?>[] parameterTypes = getParameterTypes(args);
115     Method method = Class.forName(className).getMethod(methodName, parameterTypes);
116     return method.invoke(null, args);
117 }
118
119 private static Object parseConstruct(Element e)
120     throws ReflectiveOperationException
121 {
122     String className = e.getAttribute("class");
123     Object[] args = parseArgs(e.getChildNodes());
124     Class<?>[] parameterTypes = getParameterTypes(args);
125     Constructor<?> constructor = Class.forName(className).getConstructor(parameterTypes);
126     return constructor.newInstance(args);
127 }
128
129 private static Object[] parseArgs(NodeList elements)
130     throws ReflectiveOperationException
131 {
132     var result = new Object[elements.getLength()];
133     for (int i = 0; i < result.length; i++)
134         result[i] = parseObject((Element) elements.item(i));
135     return result;
136 }
137
138 private static Map<Class<?>, Class<?>> toPrimitive = Map.of(
139     Integer.class, int.class,
140     Boolean.class, boolean.class);
141
142 private static Class<?>[] getParameterTypes(Object[] args)
143 {
144     var result = new Class<?>[args.length];
145     for (int i = 0; i < result.length; i++)
146     {
147         Class<?> cl = args[i].getClass();
148         result[i] = toPrimitive.get(cl);
149         if (result[i] == null) result[i] = cl;
150     }
151     return result;
152 }
153 }
```

```
1 <?xml version="1.0"?>
2 <!DOCTYPE config SYSTEM "config.dtd">
3 <config>
4   <entry id="background">
5     <construct class="java.awt.Color">
6       <int>55</int>
7       <int>200</int>
8       <int>100</int>
9     </construct>
10   </entry>
11   <entry id="currency">
12     <factory class="java.util.Currency">
13       <string>USD</string>
14     </factory>
15   </entry>
16 </config>
```

```
1 <!ELEMENT config (entry)*>
2
3 <!ELEMENT entry (string|int|boolean|construct|factory)>
4 <!ATTLIST entry id ID #IMPLIED>
5
6 <!ELEMENT construct (string|int|boolean|construct|factory)*>
7 <!ATTLIST construct class CDATA #IMPLIED>
8
9 <!ELEMENT factory (string|int|boolean|construct|factory)*>
10 <!ATTLIST factory class CDATA #IMPLIED>
11 <!ATTLIST factory method CDATA "getInstance">
12
13 <!ELEMENT string (#PCDATA)>
14 <!ELEMENT int (#PCDATA)>
15 <!ELEMENT boolean (#PCDATA)>
```

```
1 <xsd:schema xmlns:xsd="http://www.w3.org/2001/XMLSchema">
2   <xsd:element name="config">
3     <xsd:complexType>
4       <xsd:sequence>
5         <xsd:element name="entry" minOccurs="0" maxOccurs="unbounded">
6           <xsd:complexType>
7             <xsd:group ref="Dobject"/>
8             <xsd:attribute name="id" type="xsd:ID"/>
9           </xsd:complexType>
10          </xsd:element>
11        </xsd:sequence>
12      </xsd:complexType>
13    </xsd:element>
14
```

```
15  <xsd:element name="construct">
16      <xsd:complexType>
17          <xsd:group ref="Arguments"/>
18          <xsd:attribute name="class" type="xsd:string"/>
19      </xsd:complexType>
20  </xsd:element>
21
22  <xsd:element name="factory">
23      <xsd:complexType>
24          <xsd:group ref="Arguments"/>
25          <xsd:attribute name="class" type="xsd:string"/>
26          <xsd:attribute name="method" type="xsd:string" default="getInstance"/>
27      </xsd:complexType>
28  </xsd:element>
29
30  <xsd:group name="Dobject">
31      <xsd:choice>
32          <xsd:element ref="construct"/>
33          <xsd:element ref="factory"/>
34          <xsd:element name="string" type="xsd:string"/>
35          <xsd:element name="int" type="xsd:int"/>
36          <xsd:element name="boolean" type="xsd:boolean"/>
37      </xsd:choice>
38  </xsd:group>
39
40  <xsd:group name="Arguments">
41      <xsd:sequence>
42          <xsd:group ref="Object" minOccurs="0" maxOccurs="unbounded"/>
43      </xsd:sequence>
44  </xsd:group>
45 </xsd:schema>
```

```
XPathFactory xpfactory = XPathFactory.newInstance();
path = xpfactory.newXPath();
```

```
String username = path.evaluate("/html/head/title/text()", doc);
```

```
XPathNodes result = path.evaluateExpression("/html/body/form", doc, XPathNodes.class);
```

```
var nodes = (NodeList) path.evaluate("/html/body/form", doc, XPathConstants.NODESET);
```

```
Node node = path.evaluateExpression("/html/body/form[1]", doc, Node.class);
node = (Node) path.evaluate("/html/body/form[1]", doc, XPathConstants.NODE);

int count = path.evaluateExpression("count(/html/body/form)", doc, Integer.class);
count = ((Number) path.evaluate("count(/html/body/form)",
    doc, XPathConstants.NUMBER)).intValue();

String result = path.evaluate(expression, node);

XPathEvaluationResult<?> result = path.evaluateExpression(expression, doc);
```

```
1 package xpath;
2
3 import java.io.*;
4 import java.nio.file.*;
5 import java.util.*;
6
7 import javax.xml.catalog.*;
8 import javax.xml.parsers.*;
9 import javax.xml.xpath.*;
10
11 import org.w3c.dom.*;
12 import org.xml.sax.*;
13
14 /**
15 * This program evaluates XPath expressions.
16 * @version 1.1 2018-04-06
17 * @author Cay Horstmann
18 */
19 public class XPathTest
20 {
21     public static void main(String[] args) throws Exception
22     {
23         DocumentBuilderFactory factory = DocumentBuilderFactory.newInstance();
24         DocumentBuilder builder = factory.newDocumentBuilder();
25
26         // Avoid a delay in parsing an XHTML file--see the first note in
27         // Section 3.4.1
28         builder.setEntityResolver(CatalogManager.catalogResolver(
29             CatalogFeatures.defaults(),
30             Path.of("xpath/catalog.xml").toAbsolutePath().toUri()));
31
32         XPathFactory xpfactory = XPathFactory.newInstance();
33         XPath path = xpfactory.newXPath();
34         try (var in = new Scanner(System.in))
35         {
36             String filename;
37             if (args.length == 0)
38             {
39                 System.out.print("Input file: ");
40                 filename = in.nextLine();
41             }
42         }
43     }
44 }
```

```
42     else
43         filename = args[0];
44
45     Document doc = builder.parse(filename);
46     boolean done = false;
47     while (!done)
48     {
49         System.out.print("XPath expression (empty line to exit): " );
50         String expression = in.nextLine();
51         if (expression.strip().isEmpty()) done = true;
52         else
53         {
54             try
55             {
56                 XPathEvaluationResult<?> result
57                     = path.evaluateExpression(expression, doc);
58                 if (result.type() == XPathEvaluationResult.XPathResultType.NODESET)
59                 {
60                     for (Node n : (XPathNodes) result.value())
61                         System.out.println(description(n));
62                 }
63                 else if (result.type() == XPathEvaluationResult.XPathResultType.NODE)
64                     System.out.println((Node) result.value());
65                 else
66                     System.out.println(result.value());
67             }
68             catch (XPathExpressionException e)
69             {
70                 System.out.println(e.getMessage());
71             }
72         }
73     }
74 }
75 }
76
77 public static String description(Node n)
78 {
79     if (n instanceof Element) return "Element " + n.getNodeName();
80     else if (n instanceof Attr) return 'Attribute ' + n;
81     else return n.toString();
82 }
83 }
```

```
http://www.w3.org/2001/XMLSchema
uuid:1c759aed-b748-475c-ab68-10679700c4f2
urn:com:books-r-us

http://www.horstmann.com/corejava
http://www.horstmann.com/corejava/index.html

<element xmlns="namespaceURI">
    children
</element>

<element xmlns="namespaceURI1">
    <child xmlns="namespaceURI2">
        grandchildren
    </child>
    more children
</element>

<xsd:schema xmlns:xsd="http://www.w3.org/2001/XMLSchema">
    <xsd:element name="config">
        .
    </xsd:element>
</xsd:schema>

<configuration xmlns="http://www.horstmann.com/corejava"
    xmlns:si="http://www.bipm.fr/enus/3_SI/si.html">
    <size value="210" si:unit="mm"/>
    .
</configuration>

DocumentBuilderFactory factory = DocumentBuilderFactory.newInstance();
factory.setNamespaceAware(true);

DocumentBuilderFactory factory = DocumentBuilderFactory.newInstance();

<xsd:schema xmlns:xsd="http://www.w3.org/2001/XMLSchema">

java SAXTest http://www.w3c.org/Consortium

SAXParserFactory factory = SAXParserFactory.newInstance();
SAXParser parser = factory.newSAXParser();
```

```
parser.parse(source, handler);

var handler = new DefaultHandler()
{
    public void startElement(String namespaceURI, String lname, String qname,
                            Attributes attrs) throws SAXException
    {
        if (lname.equalsIgnoreCase("a") && attrs != null)
        {
            for (int i = 0; i < attrs.getLength(); i++)
            {
                String aname = attrs.getLocalName(i);
                if (aname.equalsIgnoreCase("href"))
                    System.out.println(attrs.getValue(i));
            }
        }
    }
};

SAXParserFactory factory = SAXParserFactory.newInstance();
SAXParser saxParser = factory.newSAXParser();

factory.setFeature("http://apache.org/xml/features/nonvalidating/load-external-dtd", false);
```

```
1 package sax;
2
3 import java.io.*;
4 import java.net.*;
5 import javax.xml.parsers.*;
6 import org.xml.sax.*;
7 import org.xml.sax.helpers.*;
8
9 /**
10 * This program demonstrates how to use a SAX parser. The program prints all
11 * hyperlinks of an XHTML web page. <br>
12 * Usage: java sax.SAXTest URL
13 * @version 1.01 2018-05-01
14 * @author Cay Horstmann
15 */
16 public class SAXTest
17 {
18     public static void main(String[] args) throws Exception
19     {
20         String url;
21         if (args.length == 0)
22         {
23             url = "http://www.w3c.org";
24             System.out.println("Using " + url);
25         }
26         else url = args[0];
27
28         var handler = new DefaultHandler()
29         {
30             public void startElement(String namespaceURI, String lname,
31                                     String qname, Attributes attrs)
32             {
33                 if (lname.equals("a") && attrs != null)
34                 {
35                     for (int i = 0; i < attrs.getLength(); i++)
36                     {
37                         String aname = attrs.getLocalName(i);
38                         if (aname.equals("href"))
39                             System.out.println(attrs.getValue(i));
40                     }
41                 }
42             }
43         };
44
45         SAXParserFactory factory = SAXParserFactory.newInstance();
46         factory.setNamespaceAware(true);
47         factory.setFeature(
```

```
48         "http://apache.org/xml/features/nonvalidating/load-external-dtd",
49         false);
50     SAXParser saxParser = factory.newSAXParser();
51     InputStream in = new URL(url).openStream();
52     saxParser.parse(in, handler);
53 }
54 }
```

```
InputStream in = url.openStream();
XMLInputFactory factory = XMLInputFactory.newInstance();

XMLStreamReader parser = factory.createXMLStreamReader(in);
while (parser.hasNext())
{
    int event = parser.next();
    Call parser methods to obtain event details
}

String units = parser.getAttributeValue(null, "units");

XMLInputFactory factory = XMLInputFactory.newInstance();
factory.setProperty(XMLInputFactory.IS_NAMESPACE_AWARE, false);
```

```
1 package stax;
2
3 import java.io.*;
4 import java.net.*;
5 import javax.xml.stream.*;
6
7 /**
8  * This program demonstrates how to use a StAX parser. The program prints all
9  * hyperlinks of an XHTML web page. <br>
10 * Usage: java stax.StAXTest URL
11 * @author Cay Horstmann
12 * @version 1.1 2018-05-01
13 */
14 public class StAXTest
15 {
16     public static void main(String[] args) throws Exception
17     {
18         String urlString;
19         if (args.length == 0)
20         {
21             urlString = "http://www.w3c.org";
22             System.out.println("Using " + urlString);
23         }
24         else urlString = args[0];
25         var url = new URL(urlString);
26         InputStream in = url.openStream();
27         XMLInputFactory factory = XMLInputFactory.newInstance();
28         XMLStreamReader parser = factory.createXMLStreamReader(in);
29         while (parser.hasNext())
30         {
31             int event = parser.next();
32             if (event == XMLStreamConstants.START_ELEMENT)
33             {
34                 if (parser.getLocalName().equals("a"))
35                 {
36                     String href = parser.getAttributeValue(null, "href");
37                     if (href != null)
38                         System.out.println(href);
39                 }
40             }
41         }
42     }
43 }
```

```
Document doc = builder.newDocument();

Element rootElement = doc.createElement(rootName);
Element childElement = doc.createElement(childName);

Text textNode = doc.createTextNode(textContents);

doc.appendChild(rootElement);
rootElement.appendChild(childElement);
childElement.appendChild(textNode);

rootElement.setAttribute(name, value);

DocumentBuilderFactory factory = DocumentBuilderFactory.newInstance();
factory.setNamespaceAware(true);
builder = factory.newDocumentBuilder();

String namespace = "http://www.w3.org/2000/svg";
Element rootElement = doc.createElementNS(namespace, "svg");

Element svgElement = doc.createElement(namespace, "svg:svg")

<svg:svg xmlns:svg="http://www.w3.org/2000/svg">

rootElement.setAttributeNS(namespace, qualifiedName, value);

// construct the do-nothing transformation
Transformer t = TransformerFactory.newInstance().newTransformer();
// set output properties to get a DOCTYPE node
t.setOutputProperty(OutputKeys.DOCTYPE_SYSTEM, systemIdentifier);
t.setOutputProperty(OutputKeys.DOCTYPE_PUBLIC, publicIdentifier);
// set indentation
t.setOutputProperty(OutputKeys.INDENT, "yes");
t.setOutputProperty(OutputKeys.METHOD, "xml");
t.setOutputProperty("{http://xml.apache.org/xslt}indent-amount", "2");
// apply the do-nothing transformation and send the output to a file
t.transform(new DOMSource(doc), new StreamResult(new FileOutputStream(file)));
```

```
DOMImplementation impl = doc.getImplementation();
var implLS = (DOMImplementationLS) impl.getFeature("LS", "3.0");
LSSerializer ser = implLS.createLSSerializer();

ser.getDomConfig().setParameter("format-pretty-print", true);

String str = ser.writeToString(doc);

LSOutput out = implLS.createLSOutput();
out.setEncoding("UTF-8");
out.setByteStream(Files.newOutputStream(path));
ser.write(doc, out);

XMLOutputFactory factory = XMLOutputFactory.newInstance();
XMLStreamWriter writer = factory.createXMLStreamWriter(out);

writer.writeStartDocument();
writer.writeStartElement(name);
writer.writeAttribute(name, value);
```

```
1 package write;
2
3 import java.io.*;
4 import java.nio.file.*;
5 import java.util.*;
6
7 import javax.xml.parsers.*;
8 import javax.xml.stream.*;
9 import javax.xml.transform.*;
10 import javax.xml.transform.dom.*;
11 import javax.xml.transform.stream.*;
12
13 import org.w3c.dom.*;
14
15 /**
16  * This program shows how to write an XML file. It produces modern art in SVG
17  * format.
18  * @version 1.13 2021-09-03
19  * @author Cay Horstmann
20  */
21 public class XMLWriteTest
22 {
23     public static void main(String[] args) throws Exception
24     {
25         Document doc = newDrawing(600, 400);
26         writeDocument(doc, "drawing1.svg");
27         writeNewDrawing(600, 400, "drawing2.svg");
28     }
29
30     private static Random generator = new Random();
31
32     /**
33      * Creates a new random drawing.
34      * @param drawingWidth the width of the drawing in pixels
35      * @param drawingHeight the height of the drawing in pixels
36      * @return the DOM tree of the SVG document
37      */
38     public static Document newDrawing(int drawingWidth, int drawingHeight)
39             throws ParserConfigurationException
40     {
41         DocumentBuilderFactory factory = DocumentBuilderFactory.newInstance();
42         factory.setNamespaceAware(true);
```

```
43     DocumentBuilder builder = factory.newDocumentBuilder();
44     String namespace = "http://www.w3.org/2000/svg";
45     Document doc = builder.newDocument();
46     Element svgElement = doc.createElementNS(namespace, "svg");
47     doc.appendChild(svgElement);
48     svgElement.setAttribute("width", "" + drawingWidth);
49     svgElement.setAttribute("height", "" + drawingHeight);
50     int n = 10 + generator.nextInt(20);
51     for (int i = 1; i <= n; i++)
52     {
53         int x = generator.nextInt(drawingWidth);
54         int y = generator.nextInt(drawingHeight);
55         int width = generator.nextInt(drawingWidth - x);
56         int height = generator.nextInt(drawingHeight - y);
57         int r = generator.nextInt(256);
58         int g = generator.nextInt(256);
59         int b = generator.nextInt(256);
59
60         Element rectElement = doc.createElementNS(namespace, "rect");
61         rectElement.setAttribute("x", "" + x);
62         rectElement.setAttribute("y", "" + y);
63         rectElement.setAttribute("width", "" + width);
64         rectElement.setAttribute("height", "" + height);
65         rectElement.setAttribute("fill",
66             "#%02x%02x%02x".formatted(r, g, b));
67         svgElement.appendChild(rectElement);
68     }
69     return doc;
70 }
71
72 /**
73 * Saves a document using DOM/XSLT.
74 * @param doc the document to be written
75 * @param filename the name of the destination file
76 */
77
78 public static void writeDocument(Document doc, String filename)
79     throws TransformerException, IOException
80 {
81     Transformer t = TransformerFactory.newInstance().newTransformer();
82     t.setOutputProperty(OutputKeys.DOCTYPE_SYSTEM,
83         "http://www.w3.org/TR/2000/CR-SVG-20000802/DTD/svg-20000802.dtd");
84     t.setOutputProperty(OutputKeys.DOCTYPE_PUBLIC,
85         "-//W3C//DTD SVG 20000802//EN");
86     t.setOutputProperty(OutputKeys.INDENT, "yes");
87     t.setOutputProperty(OutputKeys.METHOD, "xml");
88     t.setOutputProperty("{http://xml.apache.org/xslt}indent-amount", "2");
89     t.transform(new DOMSource(doc), new StreamResult(
90         Files.newOutputStream(Path.of(filename))));
```

```
92
93 /**
94  * Uses StAX to write an SVG document with a random drawing.
95  * @param drawingWidth the width of the drawing in pixels
96  * @param drawingHeight the height of the drawing in pixels
97  * @param filename the name of the destination file
98 */
99 public static void writeNewDrawing(int drawingWidth, int drawingHeight,
100     String filename) throws XMLStreamException, IOException
101 {
102     XMLOutputFactory factory = XMLOutputFactory.newInstance();
103     XMLStreamWriter writer = factory.createXMLStreamWriter(
104         Files.newOutputStream(Path.of(filename)));
105     writer.writeStartDocument();
106     writer.writeDTD("""
107 <!DOCTYPE svg PUBLIC "-//W3C//DTD SVG 20000802//EN"
108   "http://www.w3.org/TR/2000/CR-SVG-20000802/DTD/svg-20000802.dtd">
109 """);
110     writer.writeStartElement("svg");
111     writer.writeDefaultNamespace("http://www.w3.org/2000/svg");
112     writer.writeAttribute("width", "" + drawingWidth);
113     writer.writeAttribute("height", "" + drawingHeight);
114     int n = 10 + generator.nextInt(20);
115     for (int i = 1; i <= n; i++)
116     {
117         int x = generator.nextInt(drawingWidth);
118         int y = generator.nextInt(drawingHeight);
119         int width = generator.nextInt(drawingWidth - x);
120         int height = generator.nextInt(drawingHeight - y);
121         int r = generator.nextInt(256);
122         int g = generator.nextInt(256);
123         int b = generator.nextInt(256);
124         writer.writeEmptyElement("rect");
125         writer.writeAttribute("x", "" + x);
126         writer.writeAttribute("y", "" + y);
127         writer.writeAttribute("width", "" + width);
128         writer.writeAttribute("height", "" + height);
129         writer.writeAttribute("fill", "#%02x%02x%02x".formatted(r, g, b));
130     }
131     writer.writeEndDocument(); // closes svg element
132 }
133 }
```

```
<?xml version="1.0" encoding="UTF-8"?>
<!DOCTYPE svg PUBLIC "-//W3C//DTD SVG 20000802//EN"
  "http://www.w3.org/TR/2000/CR-SVG-20000802/DTD/svg-20000802.dtd">
<svg xmlns="http://www.w3.org/2000/svg" width="300" height="150">
  <rect x="231" y="61" width="9" height="12" fill="#6e4a13"/>
  <rect x="107" y="106" width="56" height="5" fill="#c406be"/>
  ...
</svg>

<path d="M 100 100 L 300 100 L 200 300 z">

<staff>
  <employee>
    <name>Carl Cracker</name>
    <salary>75000.0</salary>
    <hiredate year="1987" month="12" day="15"/>
  </employee>
  <employee>
    <name>Harry Hacker</name>
    <salary>50000.0</salary>
    <hiredate year="1989" month="10" day="1"/>
  </employee>
  <employee>
    <name>Tony Tester</name>
    <salary>40000.0</salary>
    <hiredate year="1990" month="3" day="15"/>
  </employee>
</staff>

<table border="1">
<tr>
<td>Carl Cracker</td><td>$75000.0</td><td>1987-12-15</td>
</tr>

<tr>
<td>Harry Hacker</td><td>$50000.0</td><td>1989-10-1</td>
</tr>
<tr>
<td>Tony Tester</td><td>$40000.0</td><td>1990-3-15</td>
</tr>
</table>
```

```
<?xml version="1.0" encoding="ISO-8859-1"?>
<xsl:stylesheet
    xmlns:xsl="http://www.w3.org/1999/XSL/Transform"
    version="1.0">
    <xsl:output method="html"/>
    template1
    template2
    .
    .
    .
</xsl:stylesheet>

<xsl:template match="/staff/employee">
    <tr><xsl:apply-templates/></tr>
</xsl:template>

<xsl:template match="/staff/employee/name">
    <td><xsl:apply-templates/></td>
</xsl:template>

<xsl:template match="/staff/employee/hiredate">
    <td><xsl:value-of select="@year"/>-<xsl:value-of
        select="@month"/>-<xsl:value-of select="@day"/></td>
</xsl:template>

employee.1.name=Carl Cracker
employee.1.salary=75000.0
employee.1.hiredate=1987-12-15
employee.2.name=Harry Hacker
employee.2.salary=50000.0

employee.2.hiredate=1989-10-1
employee.3.name=Tony Tester
employee.3.salary=40000.0
employee.3.hiredate=1990-3-15

var styleSheet = new File(filename);
var styleSource = new StreamSource(styleSheet);
Transformer t = TransformerFactory.newInstance().newTransformer(styleSource);
t.transform(source, result);
```

```
t.transform(new DOMSource(doc), result);

Carl Cracker|75000.0|1987|12|15
Harry Hacker|50000.0|1989|10|1
Tony Tester|40000.0|1990|3|15

var attributes = new AttributesImpl();
handler.startDocument();

handler.startElement("", "staff", "staff", attributes);
boolean done = false;
while (!done)
{
    String line = in.readLine();
    if (line == null) done = true;
    else
    {
        handler.startElement("", "employee", "employee", attributes);
        var tokenizer = new StringTokenizer(line, "|");
        handler.startElement("", "name", "name", attributes);
        String s = tokenizer.nextToken();
        handler.characters(s.toCharArray(), 0, s.length());
        handler.endElement("", "name", "name");
        ...
        handler.endElement("", "employee", "employee");
    }
}
handler.endElement("", rootElement, rootElement);
handler.endDocument();

t.transform(new SAXSource(new EmployeeReader(),
    new InputSource(new FileInputStream(filename))), result);

t.transform(new StreamSource(file), result);

Document doc = builder.newDocument();
t.transform(source, new DOMResult(doc));

t.transform(source, new StreamResult(file));
```

```
1 <?xml version="1.0" encoding="ISO-8859-1"?>
2
3 <xsl:stylesheet
4   xmlns:xsl="http://www.w3.org/1999/XSL/Transform"
5   version="1.0">
6
7   <xsl:output method="html"/>
8
9   <xsl:template match="/staff">
10    <table border="1"><xsl:apply-templates/></table>
11  </xsl:template>
12
13  <xsl:template match="/staff/employee">
14    <tr><xsl:apply-templates/></tr>
15  </xsl:template>
16
17  <xsl:template match="/staff/employee/name">
18    <td><xsl:apply-templates/></td>
19  </xsl:template>
20
21  <xsl:template match="/staff/employee/salary">
22    <td>$<xsl:apply-templates/></td>
23  </xsl:template>
24
25  <xsl:template match="/staff/employee/hiredate">
26    <td><xsl:value-of select="@year"/>-<xsl:value-of
27    select="@month"/>-<xsl:value-of select="@day"/></td>
28  </xsl:template>
29
30 </xsl:stylesheet>
```

```
1 <?xml Version="1.0"?>
2
3 <xsl:stylesheet
4   xmlns:xsl="http://www.w3.org/1999/XSL/Transform"
5   version="1.0">
6
7   <xsl:output method="text" omit-xml-declaration="yes"/>
8
9   <xsl:template match="/staff/employee">
10 employee.<xsl:value-of select="position()">
11 />.name=<xsl:value-of select="name/text()" />
12
13 employee.<xsl:value-of select="position()">
14 />.salary=<xsl:value-of select="salary/text()" />
15 employee.<xsl:value-of select="position()">
16 />.hiredate=<xsl:value-of select="hiredate/@year" />
17 />-<xsl:value-of select="hiredate/@month" />
18 />-<xsl:value-of select="hiredate/@day" />
19
20 </xsl:template>
21
22 </xsl:stylesheet>
```

```
1 package transform;
2
3 import java.io.*;
4 import java.nio.file.*;
5 import java.util.*;
6 import javax.xml.transform.*;
7 import javax.xml.transform.sax.*;
8 import javax.xml.transform.stream.*;
9 import org.xml.sax.*;
10 import org.xml.sax.helpers.*;
11
12 /**
13  * This program demonstrates XSL transformations. It applies a transformation to a set of
14  * employee records. The records are stored in the file employee.dat and turned into XML
15  * format. Specify the stylesheet on the command line, e.g.<br>
16  *     java transform.TransformTest transform/makeprop.xsl
17  * @version 1.05 2021-09-21
18  * @author Cay Horstmann
19  */
20 public class TransformTest
21 {
22     public static void main(String[] args) throws Exception
23     {
24         Path path;
25         if (args.length > 0) path = Path.of(args[0]);
26         else path = Path.of("transform", "makehtml.xsl");
27         try (InputStream styleIn = Files.newInputStream(path))
28         {
29             var styleSource = new StreamSource(styleIn);
30
31             Transformer t = TransformerFactory.newInstance().newTransformer(styleSource);
32             t.setOutputProperty(OutputKeys.INDENT, "yes");
33             t.setOutputProperty(OutputKeys.METHOD, "xml");
```

```
34     t.setOutputProperty("{http://xml.apache.org/xslt}indent-amount", "2");
35
36     try (InputStream docIn = Files.newInputStream(Path.of("transform", "employee.dat")))
37     {
38         t.transform(new SAXSource(new EmployeeReader(), new InputSource(docIn)),
39                     new StreamResult(System.out));
40     }
41 }
42 }
43 }
44
45 /**
46  * This class reads the flat file employee.dat and reports SAX parser events to act as if it
47  * was parsing an XML file.
48 */
49 class EmployeeReader implements XMLReader
50 {
51     private ContentHandler handler;
52
53     public void parse(InputSource source) throws IOException, SAXException
54     {
55         InputStream stream = source.getByteStream();
56         var in = new BufferedReader(new InputStreamReader(stream));
57         var atts = new AttributesImpl();
58
59         if (handler == null) throw new SAXException("No content handler");
60
61         handler.startDocument();
62         handler.startElement("", "staff", "staff", atts);
63         boolean done = false;
64         while (!done)
65         {
66             String line = in.readLine();
67             if (line == null) done = true;
68             else
69             {
70                 handler.startElement("", "employee", "employee", atts);
71                 var t = new StringTokenizer(line, "|");
72
73                 handler.startElement("", "name", "name", atts);
74                 String s = t.nextToken();
75                 handler.characters(s.toCharArray(), 0, s.length());
76                 handler.endElement("", "name", "name");
77
78                 handler.startElement("", "salary", "salary", atts);
79                 s = t.nextToken();
80                 handler.characters(s.toCharArray(), 0, s.length());
81                 handler.endElement("", "salary", "salary");
82             }
83         }
84     }
85 }
```

```
82
83     atts.addAttribute("", "year", "year", "CDATA", t.nextToken());
84     atts.addAttribute("", "month", "month", "CDATA", t.nextToken());
85     atts.addAttribute("", "day", "doy", "CDATA", t.nextToken());
86     handler.startElement("", "hiredate", "hiredate", atts);
87     handler.endElement("", "hiredate", "hiredate");
88     atts.clear();
89
90     handler.endElement("", "employee", "employee");
91 }
92 }
93
94 handler.endElement("", "staff", "staff");
95 handler.endDocument();
96 }
97
98 public void setContentHandler(ContentHandler newValue)
99 {
100     handler = newValue;
101 }
102
103 public ContentHandler getContentHandler()
104 {
105     return handler;
106 }
107
108 // the following methods are just do-nothing implementations
109 public void parse(String systemId) throws IOException, SAXException {}
110 public void setErrorHandler(ErrorHandler handler) {}
111 public ErrorHandler getErrorHandler() { return null; }
112 public void setDTDHandler(DTDHandler handler) {}
113 public DTDHandler getDTDHandler() { return null; }
114 public void setEntityResolver(EntityResolver resolver) {}
115 public EntityResolver getEntityResolver() { return null; }
116 public void.setProperty(String name, Object value) {}
117 public Object getProperty(String name) { return null; }
118 public void setFeature(String name, boolean value) {}
119 public boolean getFeature(String name) { return false; }
120 }
```

57488 16-04-10 04:23:00 50 0 0 610.5 UTC(NIST) *

```
1 package socket;
2
3 import java.io.*;
4 import java.net.*;
5 import java.nio.charset.*;
6 import java.util.*;
7
8 /**
9  * This program makes a socket connection to the atomic clock in Boulder, Colorado, and
10 * prints the time that the server sends.
11 * @version 1.22 2018-03-17
12 * @author Cay Horstmann
13 */
14 public class SocketTest
15 {
16     public static void main(String[] args) throws IOException
17     {
18         try (var s = new Socket("time-a.nist.gov", 13);
19              var in = new Scanner(s.getInputStream(), StandardCharsets.UTF_8))
20         {
21             while (in.hasNextLine())
22             {
23                 String line = in.nextLine();
24                 System.out.println(line);
25             }
26         }
27     }
28 }
```

var s = new Socket("time-a.nist.gov", 13);
InputStream inStream = s.getInputStream();

var s = new Socket(. . .);
s.setSoTimeout(10000); // time out after 10 seconds

```
try
{
    InputStream in = s.getInputStream(); // read from in
    ...
}
catch (SocketTimeoutException e)
{
    react to timeout
}

var s = new Socket();
s.connect(new InetSocketAddress(host, port), timeout);

InetAddress address = InetAddress.getByName("time-a.nist.gov");

byte[] addressBytes = address.getAddress();

InetAddress[] addresses = InetAddress.getAllByName(host);

InetAddress address = InetAddress.getLocalHost();

java inetAddress/InetAddressTest www.horstmann.com
```



```
5
6 /**
7  * This program demonstrates the InetAddress class. Supply a host name as command-line
8  * argument, or run without command-line arguments to see the address of the local host.
9  * @version 1.02 2012-06-05
10 * @author Cay Horstmann
11 */
12 public class InetAddressTest
13 {
14     public static void main(String[] args) throws IOException
15     {
16         if (args.length > 0)
17         {
18             String host = args[0];
19             InetAddress[] addresses = InetAddress.getAllByName(host);
20             for (InetAddress a : addresses)
21                 System.out.println(a);
22         }
23         else
24         {
25             InetAddress localHostAddress = InetAddress.getLocalHost();
26             System.out.println(localHostAddress);
27         }
28     }
29 }

var s = new ServerSocket(8189);

InputStream inStream = incoming.getInputStream();
OutputStream outStream = incoming.getOutputStream();

var in = new Scanner(inStream, StandardCharsets.UTF_8);
var out = new PrintWriter(new OutputStreamWriter(outStream, StandardCharsets.UTF_8),
    true /* autoFlush */);

out.println("Hello! Enter BYE to exit.");

String line = in.nextLine();
out.println("Echo: " + line);
if (line.strip().equals("BYE")) done = true;
```

```
1 package server;
2
3 import java.io.*;
4 import java.net.*;
5 import java.nio.charset.*;
6 import java.util.*;
7
8 /**
9  * This program implements a simple server that listens to port 8189 and echoes back all
10 * client input.
11 * @version 1.22 2018-03-17
12 * @author Cay Horstmann
13 */
14 public class EchoServer
15 {
16     public static void main(String[] args) throws IOException
17     {
```

```
18     // establish server socket
19     try (var s = new ServerSocket(8189))
20     {
21         // wait for client connection
22         try (Socket incoming = s.accept())
23         {
24             InputStream inStream = incoming.getInputStream();
25             OutputStream outStream = incoming.getOutputStream();
26
27             try (var in = new Scanner(inStream, StandardCharsets.UTF_8))
28             {
29                 var out = new PrintWriter(
30                     new OutputStreamWriter(outStream, StandardCharsets.UTF_8),
31                     true /* autoFlush */);
32
33                 out.println("Hello! Enter BYE to exit.");
34
35                 // echo client input
36                 boolean done = false;
37                 while (!done && in.hasNextLine())
38                 {
39                     String line = in.nextLine();
40                     out.println("Echo: " + line);
41                     if (line.strip().equals("BYE")) done = true;
42                 }
43             }
44         }
45     }
46 }
47 }

while (true)
{
    Socket incoming = s.accept();
    var r = new ThreadedEchoHandler(incoming);

    var t = new Thread(r);
    t.start();
}
```

```
1 class ThreadedEchoHandler implements Runnable
2 {
3     ...
4     public void run()
5     {
6         try (InputStream inStream = incoming.getInputStream();
7              OutputStream outStream = incoming.getOutputStream())
8         {
9             Process input and send response
10            }
11        catch(IOException e)
12        {
13            Handle exception
14        }
15    }
16
17
18 package threaded;
19
20
21 import java.io.*;
22 import java.net.*;
23 import java.nio.charset.*;
24 import java.util.*;
25
26 /**
27  * This program implements a multithreaded server that listens to port 8189 and echoes back
28  */
```

```
10 * all client input.
11 * @author Cay Horstmann
12 * @version 1.23 2018-03-17
13 */
14 public class ThreadedEchoServer
15 {
16     public static void main(String[] args )
17     {
18         try (var s = new ServerSocket(8189))
19         {
20             int i = 1;
21
22             while (true)
23             {
24                 Socket incoming = s.accept();
25                 System.out.println("Spawning " + i);
26                 Runnable r = new ThreadedEchoHandler(incoming);
27                 var t = new Thread(r);
28                 t.start();
29                 i++;
30             }
31         }
32         catch (IOException e)
33         {
34             e.printStackTrace();
35         }
36     }
37 }
38 /**
39 * This class handles the client input for one server socket connection.
40 */
41 class ThreadedEchoHandler implements Runnable
42 {
43     private Socket incoming;
44
45     /**
46      * Constructs a handler.
47      * @param incomingSocket the incoming socket
48      */
49     public ThreadedEchoHandler(Socket incomingSocket)
50     {
51         incoming = incomingSocket;
52     }
53
54     public void run()
55     {
```

```
57     try (InputStream inStream = incoming.getInputStream());
58         OutputStream outStream = incoming.getOutputStream();
59         var in = new Scanner(inStream, StandardCharsets.UTF_8);
60         var out = new PrintWriter(
61             new OutputStreamWriter(outStream, StandardCharsets.UTF_8),
62             true /* autoFlush */)
63     {
64         out.println("Hello! Enter BYE to exit.");
65
66         // echo client input
67         boolean done = false;
68         while (!done && in.hasNextLine())
69         {
70             String line = in.nextLine();
71             out.println("Echo: " + line);
72             if (line.strip().equals("BYE"))
73                 done = true;
74         }
75     }
76     catch (IOException e)
77     {
78         e.printStackTrace();
79     }
80 }
81 }
```

```
try (var socket = new Socket(host, port))
{
    var in = new Scanner(socket.getInputStream(), StandardCharsets.UTF_8);
    var writer = new PrintWriter(socket.getOutputStream());
    // send request data
    writer.print(. . .);
    writer.flush();
    socket.shutdownOutput();
```

```
// now socket is half-closed
// read response data
while (in.hasNextLine() != null)
{
    String line = in.nextLine();
    ...
}
}

SocketChannel channel = SocketChannel.open(new InetSocketAddress(host, port));

var in = new Scanner(channel, StandardCharsets.UTF_8);

OutputStream outStream = Channels.newOutputStream(channel);
```

```
1 package interruptible;
2
3 import java.awt.*;
4 import java.awt.event.*;
5 import java.util.*;
6 import java.net.*;
7 import java.io.*;
8 import java.nio.charset.*;
9 import java.nio.channels.*;
10 import javax.swing.*;
11
12 /**
13  * This program shows how to interrupt a socket channel.
14  * @author Cay Horstmann
15  * @version 1.05 2018-03-17
16  */
17 public class InterruptibleSocketTest
18 {
19     public static void main(String[] args)
20     {
21         EventQueue.invokeLater(() ->
22         {
23             var frame = new InterruptibleSocketFrame();
24             frame.setTitle("InterruptibleSocketTest");
25             frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
26             frame.setVisible(true);
27         });
28     }
29 }
30
31 class InterruptibleSocketFrame extends JFrame
32 {
33     private Scanner in;
34     private JButton interruptibleButton;
35     private JButton blockingButton;
36     private JButton cancelButton;
37     private JTextArea messages;
38     private TestServer server;
39     private Thread connectThread;
40
41     public InterruptibleSocketFrame()
42     {
43         var northPanel = new JPanel();
44         add(northPanel, BorderLayout.NORTH);
45
46         final int TEXT_ROWS = 20;
47         final int TEXT_COLUMNS = 60;
48         messages = new JTextArea(TEXT_ROWS, TEXT_COLUMNS);
```

```
49     add(new JScrollPane(messages));
50
51     interruptibleButton = new JButton("Interruptible");
52     blockingButton = new JButton("Blocking");
53
54     northPanel.add(interruptibleButton);
55     northPanel.add(blockingButton);
56
57     interruptibleButton.addActionListener(event ->
58     {
59         interruptibleButton.setEnabled(false);
60         blockingButton.setEnabled(false);
61         cancelButton.setEnabled(true);
62         connectThread = new Thread(() ->
63         {
64             try
65             {
66                 connectInterruptibly();
67             }
68             catch (IOException e)
69             {
70                 messages.append("\nInterruptibleSocketTest.connectInterruptibly: " + e);
71             }
72         });
73         connectThread.start();
74     });
75
76     blockingButton.addActionListener(event ->
77     {
78         interruptibleButton.setEnabled(false);
79         blockingButton.setEnabled(false);
80         cancelButton.setEnabled(true);
81         connectThread = new Thread(() ->
82         {
83             try
84             {
85                 connectBlocking();
86             }
87             catch (IOException e)
88             {
89                 messages.append("\nInterruptibleSocketTest.connectBlocking: " + e);
90             }
91         });
92         connectThread.start();
93     });
94
95     cancelButton = new JButton("Cancel");
96     cancelButton.setEnabled(false);
97     northPanel.add(cancelButton);
```

```
98     cancelButton.addActionListener(event ->
99         {
100             connectThread.interrupt();
101             cancelButton.setEnabled(false);
102         });
103     server = new TestServer();
104     new Thread(server).start();
105     pack();
106 }
107 /**
108 * Connects to the test server, using interruptible I/O
109 */
110 public void connectInterruptibly() throws IOException
111 {
112     messages.append("Interruptible:\n");
113     try (SocketChannel channel
114          = SocketChannel.open(new InetSocketAddress("localhost", 8189)))
115     {
116         in = new Scanner(channel, StandardCharsets.UTF_8);
117         while (!Thread.currentThread().isInterrupted())
118         {
119             messages.append("Reading ");
120             if (in.hasNextLine())
121             {
122                 String line = in.nextLine();
123                 messages.append(line);
124                 messages.append("\n");
125             }
126         }
127     }
128     finally
129     {
130         EventQueue.invokeLater(() ->
131         {
132             messages.append("Channel closed\n");
133             interruptibleButton.setEnabled(true);
134             blockingButton.setEnabled(true);
135         });
136     }
137 }
138 }
139 /**
140 * Connects to the test server, using blocking I/O
141 */
142 public void connectBlocking() throws IOException
143 {
144 }
```

```
145     messages.append("Blocking:\n");
146     try (var sock = new Socket("localhost", 8189))
147     {
148         in = new Scanner(sock.getInputStream(), StandardCharsets.UTF_8);
149         while (!Thread.currentThread().isInterrupted())
150         {
151             messages.append("Reading ");
152             if (in.hasNextLine())
153             {
154                 String line = in.nextLine();
155                 messages.append(line);
156                 messages.append("\n");
157             }
158         }
159     }
160     finally
161     {
162         EventQueue.invokeLater(() ->
163         {
164             messages.append("Socket closed\n");
165             interruptibleButton.setEnabled(true);
166             blocking8Button.setEnabled(true);
167         });
168     }
169 }
170 /**
171 * A multithreaded server that listens to port 8189 and sends numbers to the client,
172 * simulating a hanging server after 10 numbers.
173 */
174 class TestServer implements Runnable
175 {
176     public void run()
177     {
178         try (var s = new ServerSocket(8189))
179         {
180             while (true)
181             {
182                 Socket incoming = s.accept();
183                 Runnable r = new TestServerHandler(incoming);
184                 new Thread(r).start();
185             }
186         }
187     }
188     catch (IOException e)
189     {
190         messages.append("\nTestServer.run: " + e);
191     }
192 }
193 }
```

```
194
195 /**
196 * This class handles the client input for one server socket connection.
197 */
198 class TestServerHandler implements Runnable
199 {
200     private Socket incoming;
201     private int counter;
202
203     /**
204      * Constructs a handler.
205      * @param i the incoming socket
206      */
207     public TestServerHandler(Socket i)
208     {
209         incoming = i;
210     }
211
212     public void run()
213     {
214         try
215         {
216             try
217             {
218                 OutputStream outStream = incoming.getOutputStream();
219                 var out = new PrintWriter(
220                     new OutputStreamWriter(outStream, StandardCharsets.UTF_8),
221                     true /* autoFlush */);
222                 while (counter < 100)
223                 {
224                     counter++;
225                     if (counter <= 10) out.println(counter);
226                     Thread.sleep(100);
227                 }
228             }
229             finally
230             {
231                 incoming.close();
232                 messages.append("Closing server\n");
233             }
234         }
235         catch (Exception e)
236         {
237             messages.append("\nTestServerHandler.run: " + e);
238         }
239     }
240 }
241 }
```

```
InputStream inStream = url.openStream();
var in = new Scanner(inStream, StandardCharsets.UTF_8);

http://google.com?q=Beach+Chalet
ftp://username:password@ftp.yourserver.com/pub/file.txt

http://horstmann.com/index.html
../../java/net/Socket.html#Socket()

http://docs.mycompany.com/api/java/net/ServerSocket.html

../../../../java/net/Socket.html#Socket()

http://docs.mycompany.com/api/java/net/Socket.html#Socket()

http://docs.mycompany.com/api

http://docs.mycompany.com/api/java/lang/String.html

relative = base.relativize(combined);
combined = base.resolve(relative);

URLConnection connection = url.openConnection();

GET www.server.com/index.html HTTP/1.0
Referer: http://www.somewhere.com/links.html
Proxy-Connection: Keep-Alive
User-Agent: Mozilla/5.0 (X11; U; Linux i686; en-US; rv:1.8.1.4)
Host: www.server.com
Accept: text/html, image/gif, image/jpeg, image/png, /*
Accept-Language: en
Accept-Charset: iso-8859-1,* ,utf-8
Cookie: orangemilano=192218887821987

String input = username + ":" + password;

Base64.Encoder encoder = Base64.getEncoder();
String encoding = encoder.encodeToString(input.getBytes(StandardCharsets.UTF_8));

connection.setRequestProperty("Authorization", "Basic " + encoding);
```

```
ftp://username:password@ftp.yourserver.com/pub/file.txt

String key = connection.getHeaderFieldKey(n);

String value = connection.getHeaderField(n);

Map<String,List<String>> headerFields = connection.getHeaderFields();

Date: Wed, 27 Aug 2008 00:15:48 GMT
Server: Apache/2.2.2 (Unix)
Last-Modified: Sun, 22 Jun 2008 20:53:38 GMT
Accept-Ranges: bytes
Content-Length: 4813
Connection: close
Content-Type: text/html
```

```
java urlConnection.URLConnectionTest http://www.yourserver.com user password
```

```
1 package urlConnection;
2
3 import java.io.*;
4 import java.net.*;
5 import java.nio.charset.*;
6 import java.util.*;
7
```

```
8 /**
9  * This program connects to an URL and displays the response header data and the first
10 * 10 lines of the requested data.
11 *
12 * Supply the URL and an optional username and password (for HTTP basic authentication) on
13 * the command line.
14 * @version 1.12 2018-03-17
15 * @author Cay Horstmann
16 */
17 public class URLConnectionTest
18 {
19     public static void main(String[] args)
20     {
21         try
22         {
23             String urlName;
24             if (args.length > 0) urlName = args[0];
25             else urlName = "http://horstmann.com";
26
27             var url = new URL(urlName);
28             URLConnection connection = url.openConnection();
29
30             // set username, password if specified on command line
31
32             if (args.length > 2)
33             {
34                 String username = args[1];
35                 String password = args[2];
36                 String input = username + ":" + password;
37                 Base64.Encoder encoder = Base64.getEncoder();
38                 String encoding = encoder.encodeToString(input.getBytes(StandardCharsets.UTF_8));
39                 connection.setRequestProperty("Authorization", "Basic " + encoding);
40             }
41
42             connection.connect();
43
44             // print header fields
45
46             Map<String, List<String>> headers = connection.getHeaderFields();
47             for (Map.Entry<String, List<String>> entry : headers.entrySet())
48             {
49                 String key = entry.getKey();
50                 for (String value : entry.getValue())
51                     System.out.println(key + ": " + value);
52             }
53
54             // print convenience functions
55 }
```

```
56     System.out.println("-----");
57     System.out.println("getContentType: " + connection.getContentType());
58     System.out.println("getContentLength: " + connection.getContentLength());
59     System.out.println("getContentEncoding: " + connection.getContentEncoding());
60     System.out.println("getDate: " + connection.getDate());
61     System.out.println("getExpiration: " + connection.getExpiration());
62     System.out.println("getLastModified: " + connection.getLastModified());
63     System.out.println("-----");
64
65     String encoding = connection.getContentEncoding();
66     if (encoding == null) encoding = "UTF-8";
67     try (var in = new Scanner(connection.getInputStream(), encoding))
68     {
69         // print first ten lines of contents
70
71         for (int n = 1; in.hasNextLine() && n <= 10; n++)
72             System.out.println(in.nextLine());
73         if (in.hasNextLine()) System.out.println("... ");
74     }
75 }
76 catch (IOException e)
77 {
78     e.printStackTrace();
79 }
80 }
81 }
```

<http://www.google.com/maps?q=1+Market+Street+San+Francisco&hl=de>

```
var url = new URL("http://host/path");
URLConnection connection = url.openConnection();

var out = new PrintWriter(connection.getOutputStream(), StandardCharsets.UTF_8);

out.print(name1 + "=" + URLEncoder.encode(value1, StandardCharsets.UTF_8) + "&");
out.print(name2 + "=" + URLEncoder.encode(value2, StandardCharsets.UTF_8));
```

Content-Type: application/x-www-form-urlencoded

```
url=https://tools.usps.com/tools/app/ziplookup/zipByAddress
User-Agent=HTTPPie/0.9.2
address1=1 Market Street
address2=
city=San Francisco
state=CA
companyName=
. . .

out.print(key);
out.print('=');
out.print(URLEncoder.encode(value, StandardCharsets.UTF_8));
if (more_pairs) out.print('&');

InputStream err = connection.getErrorStream();

cookieHandler.setDefault(new CookieManager(null, CookiePolicy.ACCEPT_ALL));

connection.setInstanceFollowRedirects(false);

int responseCode = connection.getResponseCode();

HttpURLConnection.HTTP_MOVED_PERM
HttpURLConnection.HTTP_MOVED_TEMP
HttpURLConnection.HTTP_SEE_OTHER

String location = connection.getHeaderField("Location");
if (location != null)
{
    URL base = connection.getURL();
    connection.disconnect();
    connection = (HttpURLConnection) new URL(base, location).openConnection();
    . .
}

1 package post;
2
3 import java.io.*;
4 import java.net.*;
```

```
5 import java.nio.charset.*;
6 import java.nio.file.*;
7 import java.util.*;
8
9 /**
10  * This program demonstrates how to use the URLConnection class for a POST request.
11  * @version 1.43 2021-06-17
12  * @author Cay Horstmann
13  */
14 public class PostTest
15 {
16     public static void main(String[] args) throws IOException
17     {
18         String propsFilename = args.length > 0 ? args[0] : "post/post.properties";
19         var props = new Properties();
20         try (Reader in = Files.newBufferedReader(
21             Path.of(propsFilename), StandardCharsets.UTF_8))
22         {
23             props.load(in);
24         }
25         String urlString = props.remove("url").toString();
26         Object userAgent = props.remove("User-Agent");
27         Object redirects = props.remove("redirects");
28         CookieHandler.setDefault(new CookieManager(null, CookiePolicy.ACCEPT_ALL));
29         String result = doPost(new URL(urlString), props,
30             userAgent == null ? null : userAgent.toString(),
31             redirects == null ? -1 : Integer.parseInt(redirects.toString()));
32         System.out.println(result);
33     }
34
35 /**
36  * Do an HTTP POST.
37  * @param url the URL to post to
38  * @param nameValuePairs the query parameters
39  * @param userAgent the user agent to use, or null for the default user agent
40  * @param redirects the number of redirects to follow manually, or -1 for automatic
41  * @param redirects
42  * @return the data returned from the server
43  */
44 public static String doPost(URL url, Map<Object, Object> nameValuePairs, String userAgent,
45     int redirects) throws IOException
46 {
47     var connection = (HttpURLConnection) url.openConnection();
48     if (userAgent != null)
49         connection.setRequestProperty("User-Agent", userAgent);
50 }
```

```
51     if (redirects >= 0)
52         connection.setInstanceFollowRedirects(false);
53
54     connection.setDoOutput(true);
55
56     try (var out = new PrintWriter(connection.getOutputStream()))
57     {
58         boolean first = true;
59         for (Map.Entry<Object, Object> pair : nameValuePairs.entrySet())
60         {
61             if (first) first = false;
62             else out.print('&');
63             String name = pair.getKey().toString();
64             String value = pair.getValue().toString();
65             out.print(name);
66             out.print('=');
67             out.print(URLEncoder.encode(value, StandardCharsets.UTF_8));
68         }
69     }
70     String encoding = connection.getContentEncoding();
71     if (encoding == null) encoding = "UTF-8";
72
73     if (redirects > 0)
74     {
75         int responseCode = connection.getResponseCode();
76         if (responseCode == HttpURLConnection.HTTP_MOVED_PERM
77             || responseCode == HttpURLConnection.HTTP_MOVED_TEMP
78             || responseCode == HttpURLConnection.HTTP_SEE_OTHER)
79         {
80             String location = connection.getHeaderField("Location");
81             if (location != null)
82             {
83                 URL base = connection.getURL();
84                 connection.disconnect();
85                 return doPost(new URL(base, location), nameValuePairs, userAgent,
86                               redirects - 1);
87             }
88         }
89     }
90     else if (redirects == 0)
91     {
92         throw new IOException("Too many redirects");
93     }
94
95     var response = new StringBuilder();
96     try (var in = new Scanner(connection.getInputStream(), encoding))
97     {
98         while (in.hasNextLine())
99         {
```

```
190         response.append(in.nextLine());
191         response.append("\n");
192     }
193 }
194 catch (IOException e)
195 {
196     InputStream err = connection.getErrorStream();
197     if (err == null) throw e;
198     try (var in = new Scanner(err))
199     {
200         response.append(in.nextLine());
201         response.append("\n");
202     }
203 }
204
205     return response.toString();
206 }
207 }
```

```
--add-modules jdk.incubator.httpclient
```

```
HttpClient client = HttpClient.newHttpClient()

HttpClient client = HttpClient.newBuilder()
    .followRedirects(HttpClient.Redirect.ALWAYS)
    .build();

HttpRequest request = HttpRequest.newBuilder()
    .uri(new URI("http://horstmann.com"))
    .GET()
    .build();

HttpRequest request = HttpRequest.newBuilder()
    .uri(new URI(url))
    .header("Content-Type", "application/json")
    .POST(HttpRequest.BodyPublishers.ofString(jsonString))
    .build();
```

```
HttpRequest request2 = HttpRequest.newBuilder(request,
    (name, value) -> !name.equalsIgnoreCase("Content-Type")) // Remove old content type
    .header("Content-Type", "application/xml") // Add new content type
    .build();

HttpResponse<String> response = client.send(request, HttpResponse.BodyHandlers.ofString());

String bodyString = response.body();

int status = response.statusCode();
HttpHeaders responseHeaders = response.headers();

Map<String, List<String>> headerMap = responseHeaders.map();

Optional<String> lastModified = headerMap.firstValue("Last-Modified");

ExecutorService executor = Executors.newCachedThreadPool();
HttpClient client = HttpClient.newBuilder().executor(executor).build();

HttpRequest request = HttpRequest.newBuilder().uri(uri).GET().build();
client.sendAsync(request, HttpResponse.BodyHandlers.ofString())
    thenAccept(response -> . . .);

jdk.httpclient.HttpClient.log=all
```

```
1 package client;
2
3 import java.io.*;
4 import java.math.*;
5 import java.net.*;
6 import java.nio.charset.*;
7 import java.nio.file.*;
8 import java.util.*;
9
10 import java.net.http.*;
11 import java.net.http.HttpRequest.*;
12
13 class MoreBodyPublishers
14 {
15     public static BodyPublisher ofFormData(Map<Object, Object> data)
16     {
17         boolean first = true;
18         var builder = new StringBuilder();
19         for (Map.Entry<Object, Object> entry : data.entrySet())
20         {
21             if (first) first = false;
22             else builder.append("&");
23             builder.append(URLEncoder.encode(entry.getKey().toString(),
24                 StandardCharsets.UTF_8));
25             builder.append("=");
26             builder.append(URLEncoder.encode(entry.getValue().toString(),
27                 StandardCharsets.UTF_8));
28         }
29         return BodyPublishers.ofString(builder.toString());
30     }
31
32     private static byte[] bytes(String s) { return s.getBytes(StandardCharsets.UTF_8); }
```

```
33
34     public static BodyPublisher ofMimeMultipartData(Map<Object, Object> data, String boundary)
35         throws IOException
36     {
37         var byteArrays = new ArrayList<byte[]>();
38         byte[] separator = bytes("--" + boundary + "\nContent-Disposition: form-data; name=");
39         for (Map.Entry<Object, Object> entry : data.entrySet())
40         {
41             byteArrays.add(separator);
42
43             if (entry.getValue() instanceof Path path)
44             {
45                 String mimeType = Files.probeContentType(path);
46                 byteArrays.add(bytes("\r\n" + entry.getKey() + "\r\n; filename=\r\n"
47                     + path.getFileName() + "\r\nContent-Type: " + mimeType + "\r\n\r\n"));
48                 byteArrays.add(Files.readAllBytes(path));
49             }
50             else
51                 byteArrays.add(bytes("\r\n" + entry.getKey() + "\r\n\r\n" + entry.getValue() + "\r\n"));
52         }
53         byteArrays.add(bytes("--" + boundary + "--"));
54         return BodyPublishers.ofByteArrays(byteArrays);
55     }
56
57     public static BodyPublisher ofSimpleJSON(Map<Object, Object> data)
58     {
59         var builder = new StringBuilder();
60         builder.append("{");
61         var first = true;
62         for (Map.Entry<Object, Object> entry : data.entrySet())
63         {
64             if (first) first = false;
65             else
66                 builder.append(",");
67             builder.append(jsonEscape(entry.getKey().toString())).append(": ")
68                 .append(jsonEscape(entry.getValue().toString()));
69         }
70         builder.append("}");
71         return BodyPublishers.ofString(builder.toString());
72     }
73
74     private static Map<Character, String> replacements = Map.of('\b', "\\b", '\f', "\\f",
75         '\n', "\\n", '\r', "\\r", '\t', "\\t", '\"', "\\\"", '\\', "\\\"");
76
77     private static StringBuilder jsonEscape(String str)
78     {
79         var result = new StringBuilder("\\\"");
80         for (int i = 0; i < str.length(); i++)
81         {
```

```
82         char ch = str.charAt(i);
83         String replacement = replacements.get(ch);
84         if (replacement == null) result.append(ch);
85         else result.append(replacement);
86     }
87     result.append("\\\"");
88     return result;
89 }
90
91
92 public class HttpClientTest
93 {
94     public static void main(String[] args)
95         throws IOException, URISyntaxException, InterruptedException
96     {
97         System.setProperty("jdk.httpclient.HttpClient.log", "headers,errors");
98         String propsFilename = args.length > 0 ? args[0] : "client/post.properties";
99         Path propsPath = Path.of(propsFilename);
100        var props = new Properties();
101        try (Reader in = Files.newBufferedReader(propsPath, StandardCharsets.UTF_8))
102        {
103            props.load(in);
104        }
105        String urlString = "" + props.remove("url");
106        String contentType = "" + props.remove("Content-Type");
107        if (contentType.equals("multipart/form-data"))
108        {
109            var generator = new Random();
110            String boundary = new BigInteger(256, generator).toString();
111            contentType += ";boundary=" + boundary;
112            props.replaceAll((k, v) ->
113                v.toString().startsWith("file://")
114                    ? propsPath.getParent().resolve(Path.of(v.toString().substring(7)))
115                    : v);
116        }
117        String result = doPost(urlString, contentType, props);
118        System.out.println(result);
119    }
120
121    public static String doPost(String url, String contentType, Map<Object, Object> data)
122        throws IOException, URISyntaxException, InterruptedException
123    {
124        HttpClient client = HttpClient.newBuilder()
125            .followRedirects(HttpClient.Redirect.ALWAYS).build();
126
127        BodyPublisher publisher = null;
128        if (contentType.startsWith("multipart/form-data"))
129        {
```

```
130     String boundary = contentType.substring(contentType.lastIndexOf('\"') + 1);
131     publisher = MoreBodyPublishers.ofMimeMultipartData(data, boundary);
132 }
133 else if (contentType.equals("application/x-www-form-urlencoded"))
134     publisher = MoreBodyPublishers.ofFormData(data);
135 else
136 {
137     contentType = "application/json";
138     publisher = MoreBodyPublishers.ofSimpleJSON(data);
139 }
140
141 HttpRequest request = HttpRequest.newBuilder()
142     .uri(new URI(url))
143     .header("Content-Type", contentType)
144     .POST(publisher)
145     .build();
146 HttpResponse<String> response
147     = client.send(request, HttpResponse.BodyHandlers.ofString());
148 return response.body();
149 }
150 }
```

jdk.httpclient.HttpClient.level=INFO

```
var s = new Socket("mail.yourserver.com", 25); // 25 is SMTP
var out = new PrintWriter(s.getOutputStream(), StandardCharsets.UTF_8);
```

HELO *sending host*
MAIL FROM: *sender e-mail address*
RCPT TO: *recipient e-mail address*
DATA
Subject: *subject*
(blank line)
mail message (any number of lines)
.QUIT

```
mail.transport.protocol=smt�
mail.smtps.auth=true
mail.smtps.host=smt�.gmail.com
mail.smtps.user=accountname@gmail.com

Session mailSession = Session.getDefaultInstance(props);

var message = new MimeMessage(mailSession);
message.setFrom(new InternetAddress(from));
message.addRecipient(RecipientType.TO, new InternetAddress(to));
message.setSubject(subject);
message.setText(builder.toString());

Transport tr = mailSession.getTransport();
tr.connect(null, password);
tr.sendMessage(message, message.getAllRecipients());
tr.close();

java -classpath .:javax.mail.jar:activation-1.1.1.jar path/to/message.txt
```

```
1 package mail;
2
3 import java.io.*;
4 import java.nio.charset.*;
5 import java.nio.file.*;
6 import java.util.*;
7 import javax.mail.*;
8 import javax.mail.internet.*;
9 import javax.mail.internet.MimeMessage.RecipientType;
10
11 /**
12  * This program shows how to use JavaMail to send mail messages.
13  * @author Cay Horstmann
14  * @version 1.02 2021-06-17
15  */
16 public class MailTest
17 {
18     public static void main(String[] args) throws MessagingException, IOException
19     {
20         var props = new Properties();
21         try (Reader in = Files.newBufferedReader(Path.of("mail",
22             "mail.properties"), StandardCharsets.UTF_8))
23         {
24             props.load(in);
25         }
26         List<String> lines = Files.readAllLines(Path.of(args[0]), StandardCharsets.UTF_8);
27
28         String from = lines.get(0);
29         String to = lines.get(1);
30         String subject = lines.get(2);
31
32         var builder = new StringBuilder();
33         for (int i = 3; i < lines.size(); i++)
34         {
35             builder.append(lines.get(i));
36             builder.append("\n");
37         }
38
39         Console console = System.console();
40         var password = new String(console.readPassword("Password: "));
41
42         Session mailSession = Session.getDefaultInstance(props);
43         // mailSession.setDebug(true);
44         var message = new MimeMessage(mailSession);
45         message.setFrom(new InternetAddress(from));
46         message.addRecipient(RecipientType.TO, new InternetAddress(to));
```

```
47     message.setSubject(subject);
48     message.setText(builder.toString());
49     Transport tr = mailSession.getTransport();
50     try
51     {
52         tr.connect(null, password);
53         tr.sendMessage(message, message.getAllRecipients());
54     }
55     finally
56     {
57         tr.close();
58     }
59 }
60 }
```

```
SELECT Books.Title, Books.Publisher_Id, Books.Price, Publishers.Name, Publishers.URL  
FROM Books, Publishers  
WHERE Books.Publisher_Id = Publishers.Publisher_Id
```

```
SELECT * FROM Books, Publishers
```

```
SELECT * FROM Books, Publishers  
WHERE Books.Publisher_Id = Publishers.Publisher_Id
```

```
INSERT INTO Books  
VALUES ('A Guide to the SQL Standard', '0-201-96426-0', '0201', 47.95)
```

```
jdbc:derby://localhost:1527/COREJAVA;create=true  
jdbc:postgresql:COREJAVA
```

```
java -classpath driverPath:. ProgramName
```

```
java -jar derby/lib/derbyrun.jar server start
```

```
ij.driver=org.apache.derby.jdbc.ClientDriver  
ij.protocol=jdbc:derby://localhost:1527/  
ij.database=COREJAVA;create=true
```

```
java -jar derby/lib/derbyrun.jar ij -p ij.properties
```

```
CREATE TABLE Greetings (Message CHAR(20));  
INSERT INTO Greetings VALUES ('Hello, World!');  
SELECT * FROM Greetings;  
DROP TABLE Greetings;
```

```
java -jar derby/lib/derbyrun.jar server shutdown
```

```
org.apache.derby.jdbc.ClientDriver  
org.postgresql.Driver
```

```
Class.forName("org.postgresql.Driver"); // force loading of driver class
```

```
java -Djdbc.drivers=org.postgresql.Driver ProgramName
```

```
System.setProperty("jdbc.drivers", "org.postgresql.Driver");

org.postgresql.Driver:org.apache.derby.jdbc.ClientDriver

String url = "jdbc:postgresql:COREJAVA";
String username = "dbuser";
String password = "secret";
Connection conn = DriverManager.getConnection(url, username, password);

jdbc.drivers=org.postgresql.Driver
jdbc.url=jdbc:postgresql:COREJAVA
jdbc.username=dbuser
jdbc.password=secret

CREATE TABLE Greetings (Message CHAR(20))
INSERT INTO Greetings VALUES ('Hello, World!')
SELECT * FROM Greetings

java -classpath .:driverJAR test.TestDB
```

```
1 package test;
2
3 import java.nio.file.*;
4 import java.sql.*;
5 import java.io.*;
6 import java.nio.charset.*;
7 import java.util.*;
8
9 /**
10  * This program tests that the database and the JDBC driver are correctly configured.
11  * @version 1.84 2021-06-17
12  * @author Cay Horstmann
13  */
14 public class TestDB
15 {
16     public static void main(String args[]) throws IOException
17     {
18         try
19         {
20             runTest();
21         }
22         catch (SQLException e)
23         {
24             for (Throwable t : e)
25                 t.printStackTrace();
26         }
27     }
28
29 /**
30  * Runs a test by creating a table, adding a value, showing the table contents, and
31  * removing the table.
32  */
33 public static void runTest() throws SQLException, IOException
34 {
35     try (Connection conn = getConnection();
36          Statement stat = conn.createStatement())
37     {
```

```
38     stat.executeUpdate("CREATE TABLE Greetings (Message CHAR(20))");
39     stat.executeUpdate("INSERT INTO Greetings VALUES ('Hello, World!')");
40
41     try (ResultSet result = stat.executeQuery("SELECT * FROM Greetings"))
42     {
43         if (result.next())
44             System.out.println(result.getString(1));
45     }
46     stat.executeUpdate("DROP TABLE Greetings");
47 }
48 }
49
50 /**
51 * Gets a connection from the properties specified in the file database.properties.
52 * @return the database connection
53 */
54 public static Connection getConnection() throws SQLException, IOException
55 {
56     var props = new Properties();
57     try (Reader in = Files.newBufferedReader(
58         Path.of("database.properties"), StandardCharsets.UTF_8))
59     {
60         props.load(in);
61     }
62     String drivers = props.getProperty("jdbc.drivers");
63     if (drivers != null) System.setProperty("jdbc.drivers", drivers);
64     String url = props.getProperty("jdbc.url");
65     String username = props.getProperty("jdbc.username");
66     String password = props.getProperty("jdbc.password");
67
68     return DriverManager.getConnection(url, username, password);
69 }
70 }
```

```
Statement stat = conn.createStatement();

String command = "UPDATE Books"
+ " SET Price = Price - 5.00"
+ " WHERE Title NOT LIKE '%Introduction%'";
```

```
ResultSet rs = stat.executeQuery("SELECT * FROM Books");

String isbn = rs.getString(1);
double price = rs.getDouble("Price");

try (Connection conn = . . .)
{
    Statement stat = conn.createStatement();
    ResultSet result = stat.executeQuery(queryString);
    process query result
}

for (Throwable t : sqlException)
{
    do something with t
}

SQLWarning w = stat.getWarning();
while (w != null)
{
    do something with w
    w = w.nextWarning();
}

CREATE TABLE Publishers (Publisher_Id CHAR(6), Name CHAR(30), URL CHAR(80));
INSERT INTO Publishers VALUES ('0201', 'Addison-Wesley', 'www.aw-bc.com');
INSERT INTO Publishers VALUES ('0471', 'John Wiley & Sons', 'www.wiley.com');
. . .

java -classpath driverPath:. exec.ExecSQL Books.sql
java -classpath driverPath:. exec.ExecSQL Authors.sql
java -classpath driverPath:. exec.ExecSQL Publishers.sql
java -classpath driverPath:. exec.ExecSQL BooksAuthors.sql

java -jar derby/lib/derbyrun.jar ij -p ij.properties Books.sql
```

```
1 package exec;
2
3 import java.io.*;
4 import java.nio.charset.*;
5 import java.nio.file.*;
6 import java.util.*;
7 import java.sql.*;
8
9 /**
10 * Executes all SQL statements in a file. Call this program as <br>
11 * java -classpath driverPath:. ExecSQL commandFile
12 *
13 * @version 1.34 2021-06-17
14 * @author Cay Horstmann
15 */
16 class ExecSQL
17 {
18     public static void main(String args[]) throws IOException
19     {
20         try (Scanner in = args.length == 0 ? new Scanner(System.in)
21              : new Scanner(Path.of(args[0]), StandardCharsets.UTF_8))
```

```
22     {
23         try (Connection conn = getConnection();
24              Statement stat = conn.createStatement())
25         {
26             while (true)
27             {
28                 if (args.length == 0) System.out.println("Enter command or EXIT to exit:");
29
30                 if (!in.hasNextLine()) return;
31
32                 String line = in.nextLine().strip();
33                 if (line.equalsIgnoreCase("EXIT")) return;
34                 if (line.endsWith(";")) // remove trailing semicolon
35                     line = line.substring(0, line.length() - 1);
36                 try
37                 {
38                     boolean isResult = stat.execute(line);
39                     if (isResult)
40                     {
41                         try (ResultSet rs = stat.getResultSet())
42                         {
43                             showResultSet(rs);
44                         }
45                     }
46                     else
47                     {
48                         int updateCount = stat.getUpdateCount();
49                         System.out.println(updateCount + " rows updated");
50                     }
51                 }
52                 catch (SQLException e)
53                 {
54                     for (Throwable t : e)
55                         t.printStackTrace();
56                 }
57             }
58         }
59     }
60     catch (SQLException e)
61     {
62         for (Throwable t : e)
63             t.printStackTrace();
64     }
65 }
66 /**
67 * Gets a connection from the properties specified in the file database.properties
68 * @return the database connection
69 */
70 */
```

```
71     public static Connection getConnection() throws SQLException, IQException
72     {
73         var props = new Properties();
74         try (Reader in = Files.newBufferedReader(
75             Path.of("database.properties"), StandardCharsets.UTF_8))
76         {
77             props.load(in);
78         }
79         String drivers = props.getProperty("jdbc.drivers");
80         if (drivers != null) System.setProperty("jdbc.drivers", drivers);
81
82         String url = props.getProperty("jdbc.url");
83         String username = props.getProperty("jdbc.username");
84         String password = props.getProperty("jdbc.password");
85
86         return DriverManager.getConnection(url, username, password);
87     }
88
89     /**
90      * Prints a result set.
91      * @param result the result set to be printed
92      */
93     public static void showResultSet(ResultSet result) throws SQLException
94     {
95         ResultSetMetaData metaData = result.getMetaData();
96         int columnCount = metaData.getColumnCount();
97
98         for (int i = 1; i <= columnCount; i++)
99         {
100             if (i > 1) System.out.print(", ");
101             System.out.print(metaData.getColumnLabel(i));
102         }
103         System.out.println();
104
105         while (result.next())
106         {
107             for (int i = 1; i <= columnCount; i++)
108             {
109                 if (i > 1) System.out.print(", ");
110                 System.out.print(result.getString(i));
111             }
112             System.out.println();
113         }
114     }
115 }
```

```
SELECT Books.Price, Books.Title  
FROM Books, Publishers  
WHERE Books.Publisher_Id = Publishers.Publisher_Id  
AND Publishers.Name = the name from the list box
```

```
String publisherQuery  
= "SELECT Books.Price, Books.Title"  
+ " FROM Books, Publishers"  
+ " WHERE Books.Publisher_Id = Publishers.Publisher_Id AND Publishers.Name = ?";  
PreparedStatement stat = conn.prepareStatement(publisherQuery);  
  
ResultSet rs = stat.executeQuery();  
  
int r = stat.executeUpdate();  
System.out.println(r + " rows updated");  
  
SELECT Books.Price, Books.Title FROM Books, BooksAuthors, Authors, Publishers  
WHERE Authors.Author_Id = BooksAuthors.Author_Id AND BooksAuthors.ISBN = Books.ISBN  
AND Books.Publisher_Id = Publishers.Publisher_Id AND Authors.Name = ?  
AND Publishers.Name = ?  
  
UPDATE Books  
SET Price = Price + ?  
WHERE Books.Publisher_Id = (SELECT Publisher_Id FROM Publishers WHERE Name = ?)
```

```
1 package query;
2
3 import java.io.*;
4 import java.nio.charset.*;
5 import java.nio.file.*;
6 import java.sql.*;
7 import java.util.*;
8
9 /**
10  * This program demonstrates several complex database queries.
11  * @version 1.32 2021-06-17
12  * @author Cay Horstmann
13  */
14 public class QueryTest
15 {
16     private static final String allQuery = "SELECT Books.Price, Books.Title FROM Books";
```

```
17     private static final String authorPublisherQuery = """
18     SELECT Books.Price, Books.Title
19     FROM Books, BooksAuthors, Authors, Publishers
20     WHERE Authors.Author_Id = BooksAuthors.Author_Id
21         AND BooksAuthors.ISBN = Books.ISBN
22         AND Books.Publisher_Id = Publishers.Publisher_Id
23         AND Authors.Name = ?
24         AND Publishers.Name = ?
25     """;
26
27     private static final String authorQuery = """
28     SELECT Books.Price, Books.Title FROM Books, BooksAuthors, Authors
29     WHERE Authors.Author_Id = BooksAuthors.Author_Id"
30         AND BooksAuthors.ISBN = Books.ISBN"
31         AND Authors.Name = ?
32     """;
33
34
35     private static final String publisherQuery = """
36     SELECT Books.Price, Books.Title FROM Books, Publishers
37     WHERE Books.Publisher_Id = Publishers.Publisher_Id
38         AND Publishers.Name = ?
39     """;
40
41     private static final String priceUpdate = """
42     UPDATE Books SET Price = Price + ? "
43     WHERE Books.Publisher_Id =
44         (SELECT Publisher_Id FROM Publishers WHERE Name = ?)
45     """;
46
47     private static Scanner in;
48     private static ArrayList<String> authors = new ArrayList<>();
49     private static ArrayList<String> publishers = new ArrayList<>();
50
51     public static void main(String[] args) throws IOException
52     {
53         try (Connection conn = getConnection())
54         {
55             in = new Scanner(System.in);
56             authors.add("Any");
57             publishers.add("Any");
58             try (Statement stat = conn.createStatement())
59             {
60                 // Fill the authors array list
61                 String query = "SELECT Name FROM Authors";
62                 try (ResultSet rs = stat.executeQuery(query))
63                 {
```

```
64         while (rs.next())
65             authors.add(rs.getString(1));
66     }
67
68     // Fill the publishers array list
69     query = "SELECT Name FROM Publishers";
70     try (ResultSet rs = stat.executeQuery(query))
71     {
72         while (rs.next())
73             publishers.add(rs.getString(1));
74     }
75 }
76 boolean done = false;
77 while (!done)
78 {
79     System.out.print("Q)uery C)hange prices E)xit: ");
80     String input = in.nextLine().toUpperCase();
81     if (input.equals("Q"))
82         executeQuery(conn);
83     else if (input.equals("C"))
84         changePrices(conn);
85     else
86         done = true;
87 }
88
89 catch (SQLException e)
90 {
91     for (Throwable t : e)
92         System.out.println(t.getMessage());
93 }
94 }
95
96 /**
97 * Executes the selected query.
98 * @param conn the database connection
99 */
100 private static void executeQuery(Connection conn) throws SQLException
101 {
102     String author = select("Authors:", authors);
103     String publisher = select("Publishers:", publishers);
104     PreparedStatement stat;
105     if (!author.equals("Any") && !publisher.equals("Any"))
106     {
107         stat = conn.prepareStatement(authorPublisherQuery);
108         stat.setString(1, author);
109         stat.setString(2, publisher);
110     }
111     else if (!author.equals("Any") && publisher.equals("Any"))
112     {
```

```
113         stat = conn.prepareStatement(authorQuery);
114         stat.setString(1, author);
115     }
116     else if (author.equals("Any") && !publisher.equals("Any"))
117     {
118         stat = conn.prepareStatement(publisherQuery);
119         stat.setString(1, publisher);
120     }
121     else
122         stat = conn.prepareStatement(allQuery);
123
124     try (ResultSet rs = stat.executeQuery())
125     {
126         while (rs.next())
127             System.out.println(rs.getString(1) + ", " + rs.getString(2));
128     }
129 }
130
131 /**
132 * Executes an update statement to change prices.
133 * @param conn the database connection
134 */
135 public static void changePrices(Connection conn) throws SQLException
136 {
137     String publisher = select("Publishers:", publishers.subList(1, publishers.size()));
138     System.out.print("Change prices by: ");
139     double priceChange = in.nextDouble();
140     PreparedStatement stat = conn.prepareStatement(priceUpdate);
141     stat.setDouble(1, priceChange);
142     stat.setString(2, publisher);
143     int r = stat.executeUpdate();
144     System.out.println(r + " records updated.");
145 }
146
147 /**
148 * Asks the user to select a string.
149 * @param prompt the prompt to display
150 * @param options the options from which the user can choose
151 * @return the option that the user chose
152 */
153 public static String select(String prompt, List<String> options)
154 {
155     while (true)
156     {
157         System.out.println(prompt);
158         for (int i = 0; i < options.size(); i++)
159             System.out.printf("%2d) %s%n", i + 1, options.get(i));
160         int sel = in.nextInt();
```

```
161         if (sel > 0 && sel <= options.size())
162             return options.get(sel - 1);
163     }
164 }
165 /**
166 * Gets a connection from the properties specified in the file database.properties.
167 * @return the database connection
168 */
169 public static Connection getConnection() throws SQLException, IOException
170 {
171     var props = new Properties();
172     try (Reader in = Files.newBufferedReader(
173         Path.of("database.properties"), StandardCharsets.UTF_8))
174     {
175         props.load(in);
176     }
177
178     String drivers = props.getProperty("jdbc.drivers");
179     if (drivers != null) System.setProperty("jdbc.drivers", drivers);
180
181     String url = props.getProperty("jdbc.url");
182     String username = props.getProperty("jdbc.username");
183     String password = props.getProperty("jdbc.password");
184
185     return DriverManager.getConnection(url, username, password);
186 }
187 }
188 }
```

```
PreparedStatement stat = conn.prepareStatement("SELECT Cover FROM BookCovers WHERE ISBN=?");
...
stat.set(1, isbn);
try (ResultSet result = stat.executeQuery())
{
    if (result.next())
    {
        Blob coverBlob = result.getBlob(1);
        Image coverImage = ImageIO.read(coverBlob.getBinaryStream());
    }
}
```

```
Blob coverBlob = connection.createBlob();
int offset = 0;
OutputStream out = coverBlob.setBinaryStream(offset);
ImageIO.write(coverImage, "PNG", out);
PreparedStatement stat = conn.prepareStatement("INSERT INTO Cover VALUES (?, ?)");
stat.setInt(1, isbn);

stat.setBinaryStream(2, coverBlob);
stat.executeUpdate();

SELECT * FROM {oj Books LEFT OUTER JOIN Publishers
ON Books.Publisher_Id = Publisher.Publisher_Id}

CallableStatement stat = conn.prepareCall("{call PROC4(?, ?)}")
stat.setInt(1, id);
stat.registerOutParameter(2, java.sql.Types.VARCHAR);
stat.execute();
String name = stat.getString(2);

boolean isResult = stat.execute(command);
boolean done = false;
while (!done)
{
    if (isResult)
    {
        ResultSet result = stat.getResultSet();
        do something with result
    }
    else
    {
        int updateCount = stat.getUpdateCount();
        if (updateCount >= 0)
            do something with updateCount
        else
            done = true;
    }
    if (!done) isResult = stat.getMoreResults();
}
```

```
stat.executeUpdate(insertStatement, Statement.RETURN_GENERATED_KEYS);
ResultSet rs = stat.getGeneratedKeys();

if (rs.next())
{
    int key = rs.getInt(1);
    . .
}

Statement stat = conn.createStatement(type, concurrency);

PreparedStatement stat = conn.prepareStatement(command, type, concurrency);

Statement stat = conn.createStatement(
    ResultSet.TYPE_SCROLL_INSENSITIVE, ResultSet.CONCUR_READ_ONLY);

ResultSet rs = stat.executeQuery(query);

Statement stat = conn.createStatement(
    ResultSet.TYPE_SCROLL_INSENSITIVE, ResultSet.CONCUR_UPDATABLE);

String query = "SELECT * FROM Books";
ResultSet rs = stat.executeQuery(query);
while (rs.next())
{
    if (. . .)
    {
        double increase = . . .;
        double price = rs.getDouble("Price");
        rs.updateDouble("Price", price + increase);
        rs.updateRow(); // make sure to call updateRow after updating fields
    }
}
```

```
rs.moveToInsertRow();
rs.updateString("Title", title);
rs.updateString("ISBN", isbn);
rs.updateString("Publisher_Id", pubid);
rs.updateDouble("Price", price);
rs.insertRow();
rs.moveToCurrentRow();

RowSetFactory factory = RowSetProvider.newFactory();
CachedRowSet crs = factory.createCachedRowSet();

ResultSet result = . . .;
RowSetFactory factory = RowSetProvider.newFactory();

CachedRowSet crs = factory.createCachedRowSet();
crs.populate(result);
conn.close(); // now OK to close the database connection

crs.setURL("jdbc:derby://localhost:1527/COREJAVA");
crs.setUsername("dbuser");
crs.setPassword("secret");

crs.setCommand("SELECT * FROM Books WHERE Publisher_ID = ?");
crs.setString(1, publisherId);

DatabaseMetaData meta = conn.getMetaData();

ResultSet mrs = meta.getTables(null, null, null, new String[] { "TABLE" });

while (mrs.next())
    tableNames.addItem(mrs.getString(3));

meta.supportsCatalogsInPrivilegeDefinitions()
```

```
ResultSet rs = stat.executeQuery("SELECT * FROM " + tableName);
ResultSetMetaData meta = rs.getMetaData();
for (int i = 1; i <= meta.getColumnCount(); i++)
{
    String columnName = meta.getColumnLabel(i);
    int columnWidth = meta getColumnDisplaySize(i);
    ...
}
```

```
1 package view;
2
3 import java.awt.*;
4 import java.awt.event.*;
5 import java.io.*;
6 import java.nio.charset.*;
7 import java.nio.file.*;
8 import java.sql.*;
9 import java.util.*;
10
11 import javax.sql.*;
12 import javax.sql.rowset.*;
13 import javax.swing.*;
14
15 /**
16  * This program uses metadata to display arbitrary tables in a database.
17  * @version 1.35 2021-06-17
18  * @author Cay Horstmann
19  */
20 public class ViewDB
21 {
22     public static void main(String[] args)
23     {
24         EventQueue.invokeLater(() ->
25         {
26             var frame = new ViewDBFrame();
27             frame.setTitle("ViewDB");
28             frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
29             frame.setVisible(true);
30         });
31     }
32 }
33
34 /**
35  * The frame that holds the data panel and the navigation buttons.
36  */
37 class ViewDBFrame extends JFrame
```

```
38  {
39      private JButton previousButton;
40      private JButton nextButton;
41      private JButton deleteButton;
42      private JButton saveButton;
43      private JPanel dataPanel;
44      private Component scrollPane;
45      private JComboBox<String> tableNames;
46      private Properties props;
47      private CachedRowSet crs;
48      private Connection conn;
49
50      public ViewDBFrame()
51      {
52          tableNames = new JComboBox<String>();
53
54          try
55          {
56              readDatabaseProperties();
57              conn = getConnection();
58              DatabaseMetaData meta = conn.getMetaData();
59              try (ResultSet mrs = meta.getTables(null, null, null, new String[] { "TABLE" })) {
60                  while (mrs.next())
61                      tableNames.addItem(mrs.getString(3));
62              }
63          }
64      }
65      catch (SQLException e)
66      {
67          for (Throwable t : e)
68              t.printStackTrace();
69      }
70      catch (IDEException e)
71      {
72          ex.printStackTrace();
73      }
74
75      tableNames.addActionListener(
76          event -> showTable((String) tableNames.getSelectedItem(), conn));
77      add(tableNames, BorderLayout.NORTH);
78      addWindowListener(new WindowAdapter()
79      {
80          public void windowClosing(WindowEvent event)
81          {
82              try
83              {
84                  if (conn != null) conn.close();
85              }
86          }
87      });
88  }
```

```
85     }
86     catch (SQLException e)
87     {
88         for (Throwable t : e)
89             t.printStackTrace();
90     }
91 }
92 });
93
94 var buttonPanel = new JPanel();
95 add(buttonPanel, BorderLayout.SOUTH);
96
97 previousButton = new JButton("Previous");
98 previousButton.addActionListener(event -> showPreviousRow());
99 buttonPanel.add(previousButton);
100
101 nextButton = new JButton("Next");
102 nextButton.addActionListener(event -> showNextRow());
103 buttonPanel.add(nextButton);
104
105 deleteButton = new JButton("Delete");
106 deleteButton.addActionListener(event -> deleteRow());
107 buttonPanel.add(deleteButton);
108
109 saveButton = new JButton("Save");
110 saveButton.addActionListener(event -> saveChanges());
111 buttonPanel.add(saveButton);
112 if (tableNames.getItemCount() > 0)
113     showTable(tableNames.getItemAt(0), conn);
114 }
115
116 /**
117 * Prepares the text fields for showing a new table, and shows the first row.
118 * @param tableName the name of the table to display
119 * @param conn the database connection
120 */
121 public void showTable(String tableName, Connection conn)
122 {
123     try (Statement stat = conn.createStatement();
124          ResultSet result = stat.executeQuery("SELECT * FROM " + tableName))
125     {
126         // get result set
127
128         // copy into cached row set
129         RowSetFactory factory = RowSetProvider.newFactory();
130         crs = factory.createCachedRowSet();
131         crs.setTableName(tableName);
132         crs.populate(result);
133 }
```

```
134         if (scrollPane != null) remove(scrollPane);
135         dataPanel = new DataPanel(crs);
136         scrollPane = new JScrollPane(dataPanel);
137         add(scrollPane, BorderLayout.CENTER);
138         pack();
139         showNextRow();
140     }
141     catch (SQLException e)
142     {
143         for (Throwable t : e)
144             t.printStackTrace();
145     }
146 }
147 /**
148 * Moves to the previous table row.
149 */
150 public void showPreviousRow()
151 {
152     try
153     {
154         if (crs == null || crs.isFirst()) return;
155         crs.previous();
156         dataPanel.showRow(crs);
157     }
158     catch (SQLException e)
159     {
160         for (Throwable t : e)
161             t.printStackTrace();
162     }
163 }
164 }
165 /**
166 * Moves to the next table row.
167 */
168 public void showNextRow()
169 {
170     try
171     {
172         if (crs == null || crs.isLast()) return;
173         crs.next();
174         dataPanel.showRow(crs);
175     }
176     catch (SQLException e)
177     {
178         for (Throwable t : e)
179             t.printStackTrace();
180     }
181 }
```

```
181     }
182 }
183 /**
184  * Deletes current table row.
185 */
186 public void deleteRow()
187 {
188     if (crs == null) return;
189     new SwingWorker<Void, Void>()
190     {
191         public Void doInBackground() throws SQLException
192         {
193             crs.deleteRow();
194             crs.acceptChanges(conn);
195             if (crs.isAfterLast())
196                 if (!crs.last()) crs = null;
197             return null;
198         }
199         public void done()
200         {
201             dataPanel.showRow(crs);
202         }
203     }.execute();
204 }
205 /**
206  * Saves all changes.
207 */
208 public void saveChanges()
209 {
210     if (crs == null) return;
211     new SwingWorker<Void, Void>()
212     {
213         public Void doInBackground() throws SQLException
214         {
215             dataPanel.setRow(crs);
216             crs.acceptChanges(conn);
217             return null;
218         }
219     }.execute();
220 }
221 }
222
223 private void readDatabaseProperties() throws IOException
224 {
225     props = new Properties();
226     try (Reader in = Files.newBufferedReader(
227         Path.of("database.properties"), StandardCharsets.UTF_8))
228     {
229         props.load(in);
```

```
230     }
231     String drivers = props.getProperty("jdbc.drivers");
232     if (drivers != null) System.setProperty("jdbc.drivers", drivers);
233 }
234 /**
235  * Gets a connection from the properties specified in the file database.properties.
236  * @return the database connection
237  */
238 private Connection getConnection() throws SQLException
239 {
240     String url = props.getProperty("jdbc.url");
241     String username = props.getProperty("jdbc.username");
242     String password = props.getProperty("jdbc.password");
243
244     return DriverManager.getConnection(url, username, password);
245 }
246 }
247 /**
248  * This panel displays the contents of a result set.
249  */
250 class DataPanel extends JPanel
251 {
252     private java.util.List<JTextField> fields;
253
254     /**
255      * Constructs the data panel.
256      * @param rs the result set whose contents this panel displays
257      */
258     public DataPanel(ResultSet rs) throws SQLException
259     {
260         fields = new ArrayList<>();
261         setLayout(new GridBagLayout());
262         var gbc = new GridBagConstraints();
263         gbc.gridwidth = 1;
264         gbc.gridheight = 1;
265
266         ResultSetMetaData rsmd = rs.getMetaData();
267         for (int i = 1; i <= rsmd.getColumnCount(); i++)
268         {
269             gbc.gridy = i - 1;
270
271             String columnName = rsmd.getColumnName(i);
272             gbc.gridx = 0;
273             gbc.anchor = GridBagConstraints.EAST;
274             add(new JLabel(columnName), gbc);
275         }
276     }
277 }
```

```
277     int columnWidth = rsmd.getColumnDisplaySize(i);
278     var tb = new JTextField(columnWidth);
279     if (!rsmd.getColumnClassName(i).equals("java.lang.String"))
280         tb.setEditable(false);
281
282     fields.add(tb);
283
284     gbc.gridx = 1;
285     gbc.anchor = GridBagConstraints.WEST;
286     add(tb, gbc);
287 }
288 }
289 */
290 /**
291 * Shows a database row by populating all text fields with the column values.
292 */
293 public void showRow(ResultSet rs)
294 {
295     try
296     {
297         for (int i = 1; i <= fields.size(); i++)
298         {
299             String field = rs == null ? "" : rs.getString(i);
300             JTextField tb = fields.get(i - 1);
301             tb.setText(field);
302         }
303     }
304     catch (SQLException e)
305     {
306         for (Throwable t : e)
307             t.printStackTrace();
308     }
309 }
310 }
311 */
312 /**
313 * Updates changed data into the current row of the row set.
314 */
315 public void setRow(ResultSet rs) throws SQLException
316 {
317     for (int i = 1; i <= fields.size(); i++)
318     {
319         String field = rs.getString(i);
320         JTextField tb = fields.get(i - 1);
321         if (!field.equals(tb.getText()))
322             rs.updateString(i, tb.getText());
323     }
324     rs.updateRow();
325 }
326 }
```

```
Statement stat = conn.createStatement();

Statement stat = conn.createStatement(); // start transaction; rollback() goes here
stat.executeUpdate(command1);
Savepoint svpt = conn.setSavepoint(); // set savepoint; rollback(svpt) goes here
stat.executeUpdate(command2);

if (...) conn.rollback(svpt); // undo effect of command2
. .
conn.commit();

Statement stat = conn.createStatement();

String command = "CREATE TABLE . . ."
stat.addBatch(command);

while (. . .)
{
    command = "INSERT INTO . . . VALUES (" + . . . + ")";
    stat.addBatch(command);
}

int[] counts = stat.executeBatch();

boolean autoCommit = conn.getAutoCommit();
conn.setAutoCommit(false);
Statement stat = conn.createStatement();
. .
// keep calling stat.addBatch(. . .);
. .
stat.executeBatch();
conn.commit(); conn.setAutoCommit(autoCommit);

var jndiContext = new InitialContext();
var source = (DataSource) jndiContext.lookup("java:comp/env/jdbc/corejava");
Connection conn = source.getConnection();

@Resource(name="jdbc/corejava")
private DataSource source;
```

```
Instant start = Instant.now();
runAlgorithm();
Instant end = Instant.now();
Duration timeElapsed = Duration.between(start, end);
long millis = timeElapsed.toMillis();

Duration timeElapsed2 = Duration.between(start2, end2);
boolean overTenTimesFaster
    = timeElapsed.multipliedBy(10).minus(timeElapsed2).isNegative();

boolean overTenTimesFaster = timeElapsed.toNanos() * 10 < timeElapsed2.toNanos();
```

```
1 package timeline;
2
3 /**
4  * @version 1.01 2021-09-06
5  * @author Cay Horstmann
6  */
7
8 import java.time.*;
9 import java.util.*;
10 import java.util.stream.*;
11
12 public class Timeline
13 {
14     public static void main(String[] args)
15     {
16         Instant start = Instant.now();
17         runAlgorithm();
18         Instant end = Instant.now();
19         Duration timeElapsed = Duration.between(start, end);
20         long millis = timeElapsed.toMillis();
21         System.out.printf("%d milliseconds\n", millis);
22
23         Instant start2 = Instant.now();
24         runAlgorithm2();
25         Instant end2 = Instant.now();
26         Duration timeElapsed2 = Duration.between(start2, end2);
27         System.out.printf("%d milliseconds\n", timeElapsed2.toMillis());
28         boolean overTenTimesFaster = timeElapsed.multipliedBy(10)
29             .minus(timeElapsed2).isNegative();
30         System.out.printf("The first algorithm is %smore than ten times faster",
31             overTenTimesFaster ? "" : "not ");
32     }
33
34     public static void runAlgorithm()
35     {
36         int size = 10;
37         ArrayList<Integer> list = new Random().ints().map(i -> i % 100).limit(size)
38             .boxed().collect(Collectors.toCollection(ArrayList::new));
39         Collections.sort(list);
40         System.out.println(list);
41     }
42
43     public static void runAlgorithm2()
44     {
```

```
45     int size = 10;
46     List<Integer> list = new Random().ints().map(i -> i % 100).limit(size)
47         .boxed().collect(Collectors.toCollection(ArrayList::new));
48     while (!IntStream.range(1, list.size())
49             .allMatch(i -> list.get(i - 1).compareTo(list.get(i)) <= 0))
50         Collections.shuffle(list);
51     System.out.println(list);
52 }
53 }
```

```
LocalDate today = LocalDate.now(); // Today's date
LocalDate alonzosBirthday = LocalDate.of(1903, 6, 14);
alonzoBirthday = LocalDate.of(1903, Month.JUNE, 14);
// Uses the Month enumeration

LocalDate programmersDay = LocalDate.of(2014, 1, 1).plusDays(255);
// September 13, but in a leap year it would be September 12

independenceDay.until(christmas)

independenceDay.until(christmas, ChronoUnit.DAYS) // 174 days

LocalDate.of(2016, 1, 31).plusMonths(1)

LocalDate.of(2016, 3, 31).minusMonths(1)

LocalDate.of(1900, 1, 1).getDayOfWeek().getValue()

LocalDate start = LocalDate.of(2000, 1, 1);
LocalDate endExclusive = LocalDate.now();
Stream<LocalDate> allDays = start.datesUntil(endExclusive);
Stream<LocalDate> firstDaysInMonth = start.datesUntil(endExclusive, Period.ofMonths(1));
```

```
1 package localdates;
2
3 /**
4  * @version 1.01 2021-09-06
5  * @author Cay Horstmann
6  */
7 import java.time.*;
8 import java.time.temporal.*;
9 import java.util.stream.*;
10
11 public class LocalDates
12 {
13     public static void main(String[] args)
14     {
15         LocalDate today = LocalDate.now(); // Today's date
16         System.out.println("today: " + today);
17
18         LocalDate alonzosBirthday = LocalDate.of(1903, 6, 14);
19         alonzosBirthday = LocalDate.of(1903, Month.JUNE, 14);
20         // Uses the Month enumeration
21         System.out.println("alonzosBirthday: " + alonzosBirthday);
22
23         LocalDate programmersDay = LocalDate.of(2018, 1, 1).plusDays(255);
24         // September 13, but in a leap year it would be September 12
25         System.out.println("programmersDay: " + programmersDay);
26
27         LocalDate independenceDay = LocalDate.of(2018, Month.JULY, 4);
28         LocalDate christmas = LocalDate.of(2018, Month.DECEMBER, 25);
29
30         System.out.println("Until christmas: " + independenceDay.until(christmas));
31         System.out.println("Until christmas: "
32             + independenceDay.until(christmas, ChronoUnit.DAYS));
33
34         System.out.println(LocalDate.of(2016, 1, 31).plusMonths(1));
35         System.out.println(LocalDate.of(2016, 3, 31).minusMonths(1));
36
37         DayOfWeek startOfLastMillennium = LocalDate.of(1900, 1, 1).getDayOfWeek();
38         System.out.println("startOfLastMillennium: " + startOfLastMillennium);
39         System.out.println(startOfLastMillennium.getValue());
40         System.out.println(DayOfWeek.SATURDAY.plus(3));
41
42         LocalDate start = LocalDate.of(2000, 1, 1);
43         LocalDate endExclusive = LocalDate.now();
44         Stream<LocalDate> firstDaysInMonth = start.datesUntil(endExclusive, Period.ofMonths(1));
45         System.out.println("firstDaysInMonth: "
46             + firstDaysInMonth.toList());
47     }
48 }
```

```
LocalDate firstTuesday = LocalDate.of(year, month, 1).with(
    TemporalAdjusters.nextOrSame(DayOfWeek.TUESDAY));

TemporalAdjuster NEXT_WORKDAY = w ->
{
    var result = (LocalDate) w;
    do
    {
        result = result.plusDays(1);
    }
    while (result.getDayOfWeek().getValue() >= 6);
    return result;
};

LocalDate backToWork = today.with(NEXT_WORKDAY);

TemporalAdjuster NEXT_WORKDAY = TemporalAdjusters.ofDateAdjuster(w ->
{
    LocalDate result = w; // No cast
    do
    {
        result = result.plusDays(1);
    }
    while (result.getDayOfWeek().getValue() >= 6);
    return result;
});

LocalTime rightNow = LocalTime.now();
LocalTime bedtime = LocalTime.of(22, 30); // or LocalTime.of(22, 30, 0)

LocalTime wakeup = bedtime.plusHours(8); // wakeup is 6:30:00

ZonedDateTime apolloLaunch = ZonedDateTime.of(1969, 7, 16, 9, 32, 0, 0,
    ZoneId.of("America/New_York"));
// 1969-07-16T09:32:00[America/New_York]

ZonedDateTime skipped = ZonedDateTime.of(
    LocalDate.of(2013, 3, 31),
    LocalTime.of(2, 30),
    ZoneId.of("Europe/Berlin"));
// Constructs March 31 3:30
```

```
ZonedDateTime ambiguous = ZonedDateTime.of(  
    LocalDate.of(2013, 10, 27), // End of daylight savings time  
    LocalTime.of(2, 30),  
    ZoneId.of("Europe/Berlin"));  
    // 2013-10-27T02:30+02:00[Europe/Berlin]  
ZonedDateTime anHourLater = ambiguous.plusHours(1);  
    // 2013-10-27T02:30+01:00[Europe/Berlin]  
  
ZonedDateTime nextMeeting = meeting.plus(Duration.ofDays(7));  
    // Caution! Won't work with daylight savings time  
  
ZonedDateTime nextMeeting = meeting.plus(Period.ofDays(7)); // OK
```

```
1 package zonedtimes;
2
3 /**
4  * @version 1.0 2016-05-10
5  * @author Cay Horstmann
6  */
7
8 import java.time.*;
9
10 public class ZonedTimes
11 {
12     public static void main(String[] args)
13     {
14         ZonedDateTime apolloLaunch = ZonedDateTime.of(1969, 7, 16, 9, 32, 0, 0,
15             ZoneId.of("America/New_York")); // 1969-07-16T09:32:00[America/New_York]
16         System.out.println("apolloLaunch: " + apolloLaunch);
17
18         Instant instant = apolloLaunch.toInstant();
19         System.out.println("instant: " + instant);
20
21         ZonedDateTime zonedDateTime = instant.atZone(ZoneId.of("UTC"));
22         System.out.println("zonedDateTime: " + zonedDateTime);
23
24         ZonedDateTime skipped = ZonedDateTime.of(LocalDate.of(2013, 3, 31),
25             LocalTime.of(2, 30), ZoneId.of("Europe/Berlin")); // Constructs March 31 3:30
26         System.out.println("skipped: " + skipped);
27
28         ZonedDateTime ambiguous = ZonedDateTime.of(
29             LocalDate.of(2013, 10, 27), // End of daylight savings time
30             LocalTime.of(2, 30), ZoneId.of("Europe/Berlin"));
31             // 2013-10-27T02:30+02:00[Europe/Berlin]
32         ZonedDateTime anHourLater = ambiguous.plusHours(1);
33             // 2013-10-27T02:30+01:00[Europe/Berlin]
34         System.out.println("ambiguous: " + ambiguous);
35         System.out.println("anHourLater: " + anHourLater);
36
37         ZonedDateTime meeting = ZonedDateTime.of(LocalDate.of(2013, 10, 31),
38             LocalTime.of(14, 30), ZoneId.of("America/Los_Angeles"));
39         System.out.println("meeting: " + meeting);
40         ZonedDateTime nextMeeting = meeting.plus(Duration.ofDays(7));
41             // Caution! Won't work with daylight savings time
42         System.out.println("nextMeeting: " + nextMeeting);
43         nextMeeting = meeting.plus(Period.ofDays(7)); // OK
44         System.out.println("nextMeeting: " + nextMeeting);
45     }
46 }
```

```
String formatted = DateTimeFormatter.ISO_OFFSET_DATE_TIME.format(apollo11launch);
// 1969-07-16T09:32:00-04:00

DateTimeFormatter formatter = DateTimeFormatter.ofLocalizedDateTime(FormatStyle.LONG);
String formatted = formatter.format(apollo11launch);
// July 16, 1969 9:32:00 AM EDT

formatted = formatter.withLocale(Locale.FRENCH).format(apollo11launch);
// 16 juillet 1969 09:32:00 EDT

for (DayOfWeek w : DayOfWeek.values())
    System.out.print(w.getDisplayName(TextStyle.SHORT, Locale.ENGLISH) + " ");
// Prints Mon Tue Wed Thu Fri Sat Sun

formatter = DateTimeFormatter.ofPattern("E yyyy-MM-dd HH:mm");

LocalDate churchsBirthday = LocalDate.parse("1903-06-14");
ZonedDateTime apollo11launch =
    ZonedDateTime.parse("1969-07-16 03:32:00-0400",
        DateTimeFormatter.ofPattern("yyyy-MM-dd HH:mm:ssxx"));

1 package formatting;
2
3 /**
4  * @version 1.0 2016-05-10
5  * @author Cay Horstmann
6  */
7
8 import java.time.*;
9 import java.time.format.*;
10 import java.util.*;
11
```

```
12 public class Formatting
13 {
14     public static void main(String[] args)
15     {
16         ZonedDateTime apollo11launch = ZonedDateTime.of(1969, 7, 16, 9, 32, 0, 0,
17             ZoneId.of("America/New_York"));
18
19         String formatted = DateTimeFormatter.ISO_OFFSET_DATE_TIME.format(apollo11launch);
20         // 1969-07-16T09:32:00-04:00
21         System.out.println(formatted);
22
23         DateTimeFormatter formatter = DateTimeFormatter.ofLocalizedDateTime(FormatStyle.LONG);
24         formatted = formatter.format(apollo11launch);
25         // July 16, 1969 9:32:00 AM EDT
26         System.out.println(formatted);
27         formatted = formatter.withLocale(Locale.FRENCH).format(apollo11launch);
28         // 16 juillet 1969 09:32:00 EDT
29         System.out.println(formatted);
30
31         formatter = DateTimeFormatter.ofPattern("E yyyy-MM-dd HH:mm");
32         formatted = formatter.format(apollo11launch);
33         System.out.println(formatted);
34
35         LocalDate churchsBirthday = LocalDate.parse("1983-06-14");
36         System.out.println("churchsBirthday: " + churchsBirthday);
37         apollo11launch = ZonedDateTime.parse("1969-07-16 03:32:00-0400",
38             DateTimeFormatter.ofPattern("yyyy-MM-dd HH:mm:ssxx"));
39         System.out.println("apollo11launch: " + apollo11launch);
40
41         for (DayOfWeek w : DayOfWeek.values())
42             System.out.print(w.getDisplayName(TextStyle.SHORT, Locale.ENGLISH) + " ");
43     }
44 }
```

```
Locale usEnglish = Locale.forLanguageTag("en-US");

Locale displayLocale = Locale.getDefault(Locale.Category.DISPLAY);
Locale formatLocale = Locale.getDefault(Locale.Category.FORMAT);

java -Duser.language=de -Duser.region=CH MyProgram

var loc = new Locale("de", "CH");
System.out.println(loc.getDisplayName(Locale.GERMAN));

String cmd = "QUIT".toLowerCase(Locale.forLanguageTag("tr"));
    // "quit" with a dotless i

Locale loc = Locale.GERMAN;
NumberFormat formatter = NumberFormat.getCurrencyInstance(loc);
double amt = 123456.78;
String result = formatter.format(amt);

formatter = NumberFormat.getCompactNumberInstance(loc, NumberFormat.Style.SHORT);

TextField inputField;
. . .
NumberFormat fmt = NumberFormat.getNumberInstance();
// get the number formatter for default locale
Number input = fmt.parse(inputField.getText().strip());
double x = input.doubleValue();
```

```
1 package numberFormat;
2
3 import java.text.*;
4 import java.util.*;
5 import util.*;
6
7 /**
8 * This program demonstrates formatting numbers under various locales.
9 * @version 2.0 2021-09-22
10 * @author Cay Horstmann
11 */
12 public class NumberFormatTest2
13 {
14     public static void main(String[] args)
15     {
16         Scanner in = new Scanner(System.in);
17         var locales = (Locale[]) NumberFormat.getAvailableLocales().clone();
18         Arrays.sort(locales, Comparator.comparing(Locale::getDisplayName));
19         Locale loc = Choices.choose(in, locales, Locale::getDisplayName);
20
21         var formatters = new LinkedHashMap<NumberFormat, String>();
22         formatters.put(NumberFormat.getNumberInstance(loc), "Number");
23         formatters.put(NumberFormat.getCompactNumberInstance(
24             loc, NumberFormat.Style.SHORT), "Compact Short");
25         formatters.put(NumberFormat.getCompactNumberInstance(
26             loc, NumberFormat.Style.LONG), "Compact Long");
27         formatters.put(NumberFormat.getPercentInstance(loc), "Percent");
28         formatters.put(NumberFormat.getCurrencyInstance(loc), "Currency");
29         NumberFormat formatter = Choices.choose(in, formatters);
30
31         String operation = Choices.choose(in, "Format", "Parse");
32         if (operation.equals("Format"))
33         {
34             System.out.print("Enter a floating-point number to format: ");
35             double number = in.nextDouble();
36             System.out.println(formatter.format(number));
37         }
38     }
39 }
```

```
38     else
39     {
40         System.out.print("Enter a floating-point number to parse: ");
41         String text = in.next();
42         try
43         {
44             System.out.println(formatter.parse(text));
45         }
46         catch (ParseException e)
47         {
48             System.out.println("ParseException " + e.getMessage());
49         }
50     }
51 }
52 }

var formatter = new DecimalFormat("0.00;(#)");

DecimalFormatSymbols symbols = new DecimalFormatSymbols(loc);
symbols.setGroupingSeparator(',');
symbols.setDecimalSeparator('.');
DecimalFormat formatter = (DecimalFormat) NumberFormat.getNumberInstance(loc);
formatter.setDecimalFormatSymbols(symbols);

NumberFormat dollarFormatter = NumberFormat.getCurrencyInstance(Locale.US);
NumberFormat euroFormatter = NumberFormat.getCurrencyInstance(Locale.GERMANY);

NumberFormat dollarFormatter = NumberFormat.getCurrencyInstance(Locale.US);
NumberFormat euroFormatter = NumberFormat.getCurrencyInstance(Locale.GERMANY);

FormatStyle style = . . .; // One of FormatStyle.SHORT, FormatStyle.MEDIUM, . .
DateTimeFormatter dateFormatter = DateTimeFormatter.ofLocalizedDate(style);
DateTimeFormatter timeFormatter = DateTimeFormatter.ofLocalizedTime(style);
DateTimeFormatter dateTimeFormatter = DateTimeFormatter.ofLocalizedDateTime(style);
// or DateTimeFormatter.ofLocalizedDateTime(style1, style2)

DateTimeFormatter dateFormatter =
    DateTimeFormatter.ofLocalizedDate(style).withLocale(locale);
```

```
ZonedDateTime appointment = . . .;
String formatted = formatter.format(appointment);

LocalTime time = LocalTime.parse("9:32 AM", formatter);

for (Month m : Month.values())
    System.out.println(m.getDisplayName(textStyle, locale) + " ");

DayOfWeek first = WeekFields.of(locale).getFirstDayOfWeek();
```

```
1 package dateFormat;
2
3 import java.text.*;
4 import java.time.*;
5 import java.time.format.*;
6 import java.util.*;
7 import util.*;
8
9 /**
10  * This program demonstrates formatting dates under various locales.
11  * @version 2.0 2021-09-23
12  * @author Cay Horstmann
13  */
14 public class DateTimeFormatTest2
15 {
16     public static void main(String[] args)
17     {
18         Scanner in = new Scanner(System.in);
19         var locales = (Locale[]) NumberFormat.getAvailableLocales().clone();
20         Arrays.sort(locales, Comparator.comparing(Locale::getDisplayName));
21         Locale loc = Choices.choose(in, locales, Locale::getDisplayName);
22         FormatStyle style = Choices.choose(in, FormatStyle.class,
23             "Short", "Medium", "Long", "Full");
24         String type = Choices.choose(in, "Date", "Time", "Date and Time");
25
26         if (type.equals("Date"))
27         {
28             DateTimeFormatter formatter = DateTimeFormatter.ofLocalizedDate(
29                 style).withLocale(loc);
30             System.out.println(formatter.format(LocalDate.now()));
31             System.out.print("Enter another date: ");
32             String input = in.nextLine();
33             LocalDate date = LocalDate.parse(input, formatter);
34             System.out.println(formatter.format(date));
35         }
36         else if (type.equals("Time"))
37         {
38             DateTimeFormatter formatter = DateTimeFormatter.ofLocalizedTime(
39                 style).withLocale(loc);
40             System.out.println(formatter.format(LocalTime.now()));
41             System.out.print("Enter another time: ");
42             String input = in.nextLine();
43             LocalTime time = LocalTime.parse(input, formatter);
44             System.out.println(formatter.format(time));
45         }
46         else
47     }
```

```
48     DateTimeFormatter formatter = DateTimeFormatter.ofLocalizedDateTime(
49         style).withLocale(loc);
50     System.out.println(formatter.format(ZonedDateTime.now()));
51     System.out.print("Enter another date and time: ");
52     String input = in.nextLine();
53     ZonedDateTime dateTime = ZonedDateTime.parse(input, formatter);
54     System.out.println(formatter.format(dateTime));
55 }
56 }
57 }

Collator coll = Collator.getInstance(locale);
words.sort(coll); // Collator implements Comparator<Object>

String a = . . .;
CollationKey aKey = coll.getCollationKey(a);
if(aKey.compareTo(coll.getCollationKey(b)) == 0) // fast comparison
    . . .

String name = "Ångström";
String normalized = Normalizer.normalize(name, Normalizer.Form.NFD);
// uses normalization form D

1 package collation;
2
3 import java.text.*;
4 import java.util.*;
5 import util.*;
```

```
6
7  /**
8   * This program demonstrates collating strings under various locales.
9   * @version 2.0 2021-09-23
10  * @author Cay Horstmann
11 */
12 public class CollationTest2
13 {
14     public static void main(String[] args)
15     {
16         Scanner in = new Scanner(System.in);
17         var locales = (Locale[]) NumberFormat.getAvailableLocales().clone();
18         Arrays.sort(locales, Comparator.comparing(Locale::getDisplayName));
19         Locale loc = Choices.choose(in, locales, Locale::getDisplayName);
20
21         Collator coll = Collator.getInstance(loc);
22         int strength = Choices.choose(in, Collator.class,
23             "Primary", "Secondary", "Tertiary", "Identical");
24         int decomposition = Choices.choose(in, Collator.class,
25             "Canonical Decomposition", "Full Decomposition", "No Decomposition");
26
27         List<String> strings = new ArrayList<>();
28         strings.add("America");
29         strings.add("able");
30         strings.add("Zulu");
31         strings.add("zebra");
32         strings.add("\u00C5ngstr\u00D6m");
33         strings.add("A\u0304angstro\u0308m");
34         strings.add("Angstrom");
35         strings.add("Able");
36         strings.add("office");
37         strings.add("o\uFB03ce");
38         strings.add("Java\u2122");
39         strings.add("JavaTM");
40
41         coll.setStrength(strength);
42         coll.setDecomposition(decomposition);
43
44         strings.sort(coll);
45
46         for (int i = 0; i < strings.size(); i++)
47         {
48             String s = strings.get(i);
49             if (i > 0 && coll.compare(s, strings.get(i - 1)) == 0)
50                 System.out.print("= ");
51             System.out.println(s);
52         }
53     }
54 }
```

"On {2}, a {0} destroyed {1} houses and caused {3} of damage."

```
String msg  
= MessageFormat.format("On {2}, a {0} destroyed {1} houses and caused {3} of damage.",  
"hurricane", 99, new GregorianCalendar(1999, 0, 1).getTime(), 10.0E8);
```

On 1/1/99 12:00 AM, a hurricane destroyed 99 houses and caused 100,000,000 of damage.

"On {2,date,long}, a {0} destroyed {1} houses and caused {3,number,currency} of damage."

On January 1, 1999, a hurricane destroyed 99 houses and caused \$100,000,000 of damage.

```
var mf = new MessageFormat(pattern, loc);  
String msg = mf.format(new Object[] { values });
```

"On {2}, a {0} destroyed {1} houses and caused {3} of damage."

On January 1, 1999, a earthquake destroyed . . .

"On {2}, {0} destroyed {1} houses and caused {3} of damage."

"{0} zerstörte am {2} {1} Häuser und richtete einen Schaden von {3} an."

On January 1, 1999, a mudslide destroyed 1 houses and . . .

{1,choice,0#no houses|1#one house|2#{1} houses}

no houses|1|one house|2|{1} houses // not the actual format

-∞<no houses|0<one house|2≤{1} houses

-\u221E<no houses|0<one house|2\u2264{1} houses

```
String pattern = "On {2,date,long}, {0} destroyed {1,choice,0#no houses|1#one house|2#{1}  
houses}" + "and caused {3,number,currency} of damage.";
```

```
String pattern  
= "{0} zerstörte am {2,date,long} {1,choice,0#kein Haus|1#ein Haus|2#{1} Häuser}"  
+ "und richtete einen Schaden von {3,number,currency} an.";
```

```
var out = new PrintWriter(filename, "Windows-1252");

Charset platformEncoding = Charset.defaultCharset();

java -Dfile.encoding=UTF-8 MyProg

java.util.logging.FileHandler.encoding=UTF-8

javac -encoding UTF-8 Myfile.java

ResourceBundle currentResources = ResourceBundle.getBundle(baseName, currentLocale);

baseName_currentLocaleLanguage_currentLocaleCountry
baseName_currentLocaleLanguage
baseName_defaultLocaleLanguage_defaultLocaleCountry
baseName_defaultLocaleLanguage baseName

MyProgramStrings.properties
MyProgramStrings_en.properties
MyProgramStrings_de_DE.properties

ResourceBundle bundle = ResourceBundle.getBundle("MyProgramStrings", locale);

String computeButtonLabel = bundle.getString("computeButton");

MyProgramResources.java
MyProgramResources_en.java
MyProgramResources_de_DE.java

ResourceBundle bundle = ResourceBundle.getBundle("MyProgramResources", locale);

var backgroundColor = (Color) bundle.getObject("backgroundColor");
double[] paperSize = (double[]) bundle.getObject("defaultPaperSize");
```

```
public class baseName_language_country extends ListResourceBundle
{
    private static final Object[][] contents =
    {
        { key1, value2 },
        { key2, value2 },
        ...
    }
    public Object[][] getContents() { return contents; }
}

public class ProgramResources_de extends ListResourceBundle
{
    private static final Object[][] contents =
    {
        { "backgroundColor", Color.black },
        { "defaultPageSize", new double[] { 210, 297 } }
    }

    public Object[][] getContents() { return contents; }
}
public class ProgramResources_en_US extends ListResourceBundle
{
    private static final Object[][] contents =
    {
        { "backgroundColor", Color.blue },
        { "defaultPageSize", new double[] { 216, 279 } }
    }
    public Object[][] getContents() { return contents; }
}

Enumeration<String> getKeys()
Object handleGetObject(String key)
```

```
1 package retire;
2
3 import java.awt.*;
4 import java.awt.geom.*;
5 import java.text.*;
6 import java.util.*;
7
8 import javax.swing.*;
9
10 /**
11  * This program shows a retirement calculator. The UI is displayed in English, German, and
12  * Chinese.
13  * @version 1.25 2018-05-01
14  * @author Cay Horstmann
15  */
16 public class Retire
17 {
18     public static void main(String[] args)
19     {
20         EventQueue.invokeLater(() ->
21         {
22             var frame = new RetireFrame();
23             frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
24             frame.setVisible(true);
25         });
26     }
27 }
```

```
26     }
27 }
28
29 class RetireFrame extends JFrame
30 {
31     private JTextField savingsField = new JTextField(10);
32     private JTextField contribField = new JTextField(10);
33     private JTextField incomeField = new JTextField(10);
34     private JTextField currentAgeField = new JTextField(4);
35     private JTextField retireAgeField = new JTextField(4);
36     private JTextField deathAgeField = new JTextField(4);
37     private JTextField inflationPercentField = new JTextField(6);
38     private JTextField investPercentField = new JTextField(6);
39     private JTextArea retireText = new JTextArea(10, 25);
40     private RetireComponent retireCanvas = new RetireComponent();
41     private JButton computeButton = new JButton();
42     private JLabel languageLabel = new JLabel();
43     private JLabel savingsLabel = new JLabel();
44     private JLabel contribLabel = new JLabel();
45     private JLabel incomeLabel = new JLabel();
46     private JLabel currentAgeLabel = new JLabel();
47     private JLabel retireAgeLabel = new JLabel();
48     private JLabel deathAgeLabel = new JLabel();
49     private JLabel inflationPercentLabel = new JLabel();
50     private JLabel investPercentLabel = new JLabel();
51     private RetireInfo info = new RetireInfo();
52     private Locale[] locales = { Locale.US, Locale.CHINA, Locale.GERMANY };
53     private Locale currentLocale;
54     private JComboBox<Locale> localeCombo = new LocaleCombo(locales);
55     private ResourceBundle res;
56     private ResourceBundle resStrings;
57     private NumberFormat currencyFmt;
58     private NumberFormat numberFmt;
59     private NumberFormat percentFmt;
60
61     public RetireFrame()
62     {
63         setLayout(new GridBagLayout());
64         add(languageLabel, new GBC(0, 0).setAnchor(GBC.EAST));
65         add(savingsLabel, new GBC(0, 1).setAnchor(GBC.EAST));
66         add(contribLabel, new GBC(2, 1).setAnchor(GBC.EAST));
67         add(incomeLabel, new GBC(4, 1).setAnchor(GBC.EAST));
68         add(currentAgeLabel, new GBC(0, 2).setAnchor(GBC.EAST));
69         add(retireAgeLabel, new GBC(2, 2).setAnchor(GBC.EAST));
70         add(deathAgeLabel, new GBC(4, 2).setAnchor(GBC.EAST));
71         add(inflationPercentLabel, new GBC(0, 3).setAnchor(GBC.EAST));
72         add(investPercentLabel, new GBC(2, 3).setAnchor(GBC.EAST));
73         add(localeCombo, new GBC(1, 0, 3, 1));
74         add(savingsField, new GBC(1, 1).setWeight(100, 0).setFill(GBC.HORIZONTAL));
```

```
75     add(contribField, new GBC(3, 1).setWeight(100, 0).setFill(GBC.HORIZONTAL));
76     add(incomeField, new GBC(5, 1).setWeight(100, 0).setFill(GBC.HORIZONTAL));
77     add(currentAgeField, new GBC(1, 2).setWeight(100, 0).setFill(GBC.HORIZONTAL));
78     add(retireAgeField, new GBC(3, 2).setWeight(100, 0).setFill(GBC.HORIZONTAL));
79     add(deathAgeField, new GBC(5, 2).setWeight(100, 0).setFill(GBC.HORIZONTAL));
80     add(inflationPercentField, new GBC(1, 3).setWeight(100, 0).setFill(GBC.HORIZONTAL));
81     add(investPercentField, new GBC(3, 3).setWeight(100, 0).setFill(GBC.HORIZONTAL));
82     add(retireCanvas, new GBC(0, 4, 4, 1).setWeight(100, 100).setFill(GBC.BOTH));
83     add(new JScrollPane(retireText),
84          new GBC(4, 4, 2, 1).setWeight(0, 100).setFill(GBC.BOTH));
85
86     computeButton.setName("computeButton");
87     computeButton.addActionListener(event ->
88     {
89         getInfo();
90         updateData();
91         updateGraph();
92     });
93     add(computeButton, new GBC(5, 3));
94
95     retireText.setEditable(false);
96     retireText.setFont(new Font("Monospaced", Font.PLAIN, 10));
97
98     info.setSavings(0);
99     info.setContrib(9000);
100    info.setIncome(60000);
101    info.setCurrentAge(35);
102    info.setRetireAge(65);
103    info.setDeathAge(85);
104    info.setInvestPercent(0.1);
105    info.setInflationPercent(0.05);
106
107    int localeIndex = 0; // US locale is default selection
108    for (int i = 0; i < locales.length; i++)
109        // if current locale one of the choices, select it
110        if (getLocale().equals(locales[i])) localeIndex = i;
111    setCurrentLocale(locales[localeIndex]);
112
113    localeCombo.addActionListener(event ->
114    {
115        setCurrentLocale((Locale) localeCombo.getSelectedItem());
116        validate();
117    });
118    pack();
119 }
120
```

```
121  /**
122   * Sets the current locale.
123   * @param locale the desired locale
124   */
125  public void setCurrentLocale(Locale locale)
126  {
127      currentLocale = locale;
128      localeCombo.setLocale(currentLocale);
129      localeCombo.setSelectedItem(currentLocale);
130
131      res = ResourceBundle.getBundle("retire.RetireResources", currentLocale);
132      resStrings = ResourceBundle.getBundle("retire.RetireStrings", currentLocale);
133      currencyFmt = NumberFormat.getCurrencyInstance(currentLocale);
134      numberFmt = NumberFormat.getNumberInstance(currentLocale);
135      percentFmt = NumberFormat.getPercentInstance(currentLocale);
136
137      updateDisplay();
138      updateInfo();
139      updateData();
140      updateGraph();
141  }
142
143 /**
144  * Updates all labels in the display.
145  */
146 public void updateDisplay()
147 {
148     languageLabel.setText(resStrings.getString("language"));
149     savingsLabel.setText(resStrings.getString("savings"));
150     contribLabel.setText(resStrings.getString("contrib"));
151     incomeLabel.setText(resStrings.getString("income"));
152     currentAgeLabel.setText(resStrings.getString("currentAge"));
153     retireAgeLabel.setText(resStrings.getString("retireAge"));
154     deathAgeLabel.setText(resStrings.getString("deathAge"));
155     inflationPercentLabel.setText(resStrings.getString("inflationPercent"));
156     investPercentLabel.setText(resStrings.getString("investPercent"));
157     computeButton.setText(resStrings.getString("computeButton"));
158 }
159
160 /**
161  * Updates the information in the text fields.
162  */
163 public void updateInfo()
164 {
165     savingsField.setText(currencyFmt.format(info.getSavings()));
166     contribField.setText(currencyFmt.format(info.getContrib()));
167     incomeField.setText(currencyFmt.format(info.getIncome()));
168     currentAgeField.setText(numberFmt.format(info.getCurrentAge()));
169     retireAgeField.setText(numberFmt.format(info.getRetireAge()));
```

```
170     deathAgeField.setText(numberFmt.format(info.getDeathAge()));
171     investPercentField.setText(percentFmt.format(info.getInvestPercent()));
172     inflationPercentField.setText(percentFmt.format(info.getInflationPercent()));
173 }
174 /**
175  * Updates the data displayed in the text area.
176  */
177 public void updateData()
178 {
179     retireText.setText("");
180     var retireMsg = new MessageFormat("");
181     retireMsg.setLocale(currentLocale);
182     retireMsg.applyPattern(resStrings.getString("retire"));
183
184     for (int i = info.getCurrentAge(); i <= info.getDeathAge(); i++)
185     {
186         Object[] args = { i, info.getBalance(i) };
187         retireText.append(retireMsg.format(args) + "\n");
188     }
189 }
190 /**
191  * Updates the graph.
192  */
193 public void updateGraph()
194 {
195     retireCanvas.setColorPre((Color) res.getObject("colorPre"));
196     retireCanvas.setColorGain((Color) res.getObject("colorGain"));
197     retireCanvas.setColorLoss((Color) res.getObject("colorLoss"));
198     retireCanvas.setInfo(info);
199     repaint();
200 }
201 /**
202  * Reads the user input from the text fields.
203  */
204 public void getInfo()
205 {
206     try
207     {
208         info.setSavings(currencyFmt.parse(savingsField.getText()).doubleValue());
209         info.setContrib(currencyFmt.parse(contribField.getText()).doubleValue());
210         info.setIncome(currencyFmt.parse(incomeField.getText()).doubleValue());
211         info.setCurrentAge(numberFmt.parse(currentAgeField.getText()).intValue());
212         info.setRetireAge(numberFmt.parse(retireAgeField.getText()).intValue());
213         info.setDeathAge(numberFmt.parse(deathAgeField.getText()).intValue());
214     }
215 }
```

```
217         info.setInvestPercent(percentFmt.parse(investPercentField.getText()).doubleValue());
218         info.setInflationPercent(
219             percentFmt.parse(inflationPercentField.getText()).doubleValue());
220     }
221     catch (ParseException e)
222     {
223         e.printStackTrace();
224     }
225 }
226 */
227 /**
228 * The information required to compute retirement income data.
229 */
230 class RetireInfo
231 {
232     private double savings;
233     private double contrib;
234     private double income;
235     private int currentAge;
236     private int retireAge;
237     private int deathAge;
238     private double inflationPercent;
239     private double investPercent;
240     private int age;
241     private double balance;
242
243 /**
244 * Gets the available balance for a given year.
245 * @param year the year for which to compute the balance
246 * @return the amount of money available (or required) in that year
247 */
248 public double getBalance(int year)
249 {
250     if (year < currentAge) return 0;
251     else if (year == currentAge)
252     {
253         age = year;
254         balance = savings;
255         return balance;
256     }
257     else if (year == age) return balance;
258     if (year != age + 1) getBalance(year - 1);
259     age = year;
260     if (age < retireAge) balance += contrib;
261     else balance -= income;
262     balance = balance * (1 + (investPercent - inflationPercent));
263     return balance;
264 }
265 }
```

```
266
267     /**
268      * Gets the amount of prior savings.
269      * @return the savings amount
270      */
271     public double getSavings()
272     {
273         return savings;
274     }
275
276     /**
277      * Sets the amount of prior savings.
278      * @param newValue the savings amount
279      */
280     public void setSavings(double newValue)
281     {
282         savings = newValue;
283     }
284
285     /**
286      * Gets the annual contribution to the retirement account.
287      * @return the contribution amount
288      */
289     public double getContrib()
290     {
291         return contrib;
292     }
293
294     /**
295      * Sets the annual contribution to the retirement account.
296      * @param newValue the contribution amount
297      */
298     public void setContrib(double newValue)
299     {
300         contrib = newValue;
301     }
302
303     /**
304      * Gets the annual income.
305      * @return the income amount
306      */
307     public double getIncome()
308     {
309         return income;
310     }
311
```

```
312     /**
313      * Sets the annual income.
314      * @param newValue the income amount
315      */
316     public void setIncome(double newValue)
317     {
318         income = newValue;
319     }
320
321     /**
322      * Gets the current age.
323      * @return the age
324      */
325     public int getCurrentAge()
326     {
327         return currentAge;
328     }
329
330     /**
331      * Sets the current age.
332      * @param newValue the age
333      */
334     public void setCurrentAge(int newValue)
335     {
336         currentAge = newValue;
337     }
338
339     /**
340      * Gets the desired retirement age.
341      * @return the age
342      */
343     public int getRetireAge()
344     {
345         return retireAge;
346     }
347
348     /**
349      * Sets the desired retirement age.
350      * @param newValue the age
351      */
352     public void setRetireAge(int newValue)
353     {
354         retireAge = newValue;
355     }
356
357     /**
358      * Gets the expected age of death.
359      * @return the age
360      */
```

```
361     public int getDeathAge()
362     {
363         return deathAge;
364     }
365
366     /**
367      * Sets the expected age of death.
368      * @param newValue the age
369      */
370     public void setDeathAge(int newValue)
371     {
372         deathAge = newValue;
373     }
374
375     /**
376      * Gets the estimated percentage of inflation.
377      * @return the percentage
378      */
379     public double getInflationPercent()
380     {
381         return inflationPercent;
382     }
383
384     /**
385      * Sets the estimated percentage of inflation.
386      * @param newValue the percentage
387      */
388     public void setInflationPercent(double newValue)
389     {
390         inflationPercent = newValue;
391     }
392
393     /**
394      * Gets the estimated yield of the investment.
395      * @return the percentage
396      */
397     public double getInvestPercent()
398     {
399         return investPercent;
400     }
401
402     /**
403      * Sets the estimated yield of the investment.
404      * @param newValue the percentage
405      */
```

```
406     public void setInvestPercent(double newValue)
407     {
408         investPercent = newValue;
409     }
410 }
411 /**
412 * This component draws a graph of the investment result.
413 */
414
415 class RetireComponent extends JComponent
416 {
417     private static final int PANEL_WIDTH = 400;
418     private static final int PANEL_HEIGHT = 200;
419     private static final Dimension PREFERRED_SIZE = new Dimension(800, 600);
420     private RetireInfo info = null;
421     private Color colorPre;
422     private Color colorGain;
423     private Color colorLoss;
424
425     public RetireComponent()
426     {
427         setSize(PANEL_WIDTH, PANEL_HEIGHT);
428     }
429
430 /**
431 * Sets the retirement information to be plotted.
432 * @param newInfo the new retirement info.
433 */
434     public void setInfo(RetireInfo newInfo)
435     {
436         info = newInfo;
437         repaint();
438     }
439
440     public void paintComponent(Graphics g)
441     {
442         var g2 = (Graphics2D) g;
443         if (info == null) return;
444
445         double minValue = 0;
446         double maxValue = 0;
447         int i;
448         for (i = info.getCurrentAge(); i <= info.getDeathAge(); i++)
449         {
450             double v = info.getBalance(i);
451             if (minValue > v) minValue = v;
452             if (maxValue < v) maxValue = v;
453         }
454         if (maxValue == minValue) return;
```

```
455
456     int barWidth = getWidth() / (info.getDeathAge() - info.getCurrentAge() + 1);
457     double scale = getHeight() / (maxValue - minValue);
458
459     for (i = info.getCurrentAge(); i <= info.getDeathAge(); i++)
460     {
461         int xl = (i - info.getCurrentAge()) * barWidth + 1;
462         int yl;
463         double v = info.getBalance(i);
464         int height;
465         int yOrigin = (int) (maxValue * scale);
466
467         if (v >= 0)
468         {
469             yl = (int) ((maxValue - v) * scale);
470             height = yOrigin - yl;
471         }
472         else
473         {
474             yl = yOrigin;
475             height = (int) (-v * scale);
476         }
477
478         if (i < info.getRetireAge()) g2.setPaint(colorPre);
479         else if (v >= 0) g2.setPaint(colorGain);
480         else g2.setPaint(colorLoss);
481         var bar = new Rectangle2D.Double(xl, yl, barWidth - 2, height);
482         g2.fill(bar);
483         g2.setPaint(Color.black);
484         g2.draw(bar);
485     }
486 }
487
488 /**
489  * Sets the color to be used before retirement.
490  * @param color the desired color
491  */
492 public void setColorPre(Color color)
493 {
494     colorPre = color;
495     repaint();
496 }
497
498 /**
499  * Sets the color to be used after retirement while the account balance is positive.
500  * @param color the desired color
501  */
```

```
502     public void setColorGain(Color color)
503     {
504         colorGain = color;
505         repaint();
506     }
507
508     /**
509      * Sets the color to be used after retirement when the account balance is negative.
510      * @param color the desired color
511      */
512     public void setColorLoss(Color color)
513     {
514         colorLoss = color;
515         repaint();
516     }
517
518     public Dimension getPreferredSize() { return PREFERRED_SIZE; }
519 }
```

```
1 package retire;
2
3 import java.awt.*;
4
5 /**
6  * These are the English non-string resources for the retirement calculator.
7  * @version 1.21 2001-08-27
8  * @author Cay Horstmann
9  */
10 public class RetireResources extends java.util.ListResourceBundle
11 {
12     private static final Object[][][] contents =
13     {
14         // BEGIN LOCALIZE
15         { "colorPre", Color.blue }, { "colorGain", Color.white }, { "colorLoss", Color.red }
16         // END LOCALIZE
17     };
18
19     public Object[][][] getContents()
20     {
21         return contents;
22     }
23 }
```

```
1 package retire;
2
3 import java.awt.*;
4
5 /**
6  * These are the German non-string resources for the retirement calculator.
7  * @version 1.21 2001-08-27
8  * @author Cay Horstmann
9  */
10 public class RetireResources_de extends java.util.ListResourceBundle
11 {
12     private static final Object[][][] contents =
13     {
14         // BEGIN LOCALIZE
15         { "colorPre", Color.yellow }, { "colorGain", Color.black }, { "colorLoss", Color.red }
16         // END LOCALIZE
17     };
18
19     public Object[][][] getContents()
20     {
21         return contents;
22     }
23 }
```

```
1 package retire;
2
3 import java.awt.*;
4
5 /**
6  * These are the Chinese non-string resources for the retirement calculator.
7  * @version 1.21 2001-08-27
8  * @author Cay Horstmann
9  */
10 public class RetireResources_zh extends java.util.ListResourceBundle
11 {
12     private static final Object[][][] contents =
13     {
14         // BEGIN LOCALIZE
15         { "colorPre", Color.red }, { "colorGain", Color.blue }, { "colorLoss", Color.yellow }
16         // END LOCALIZE
17     };
18
19     public Object[][][] getContents()
20     {
21         return contents;
22     }
23 }
```

```
1 language=Language
2 computeButton=Compute
3 savings=Prior Savings
4 contrib=Annual Contribution
5 income=Retirement Income
6 currentAge=Current Age
7 retireAge=Retirement Age
8 deathAge=Life Expectancy
9 inflationPercent=Inflation
10 investPercent=Investment Return
11 retire=Age: {0,number} Balance: {1,number,currency}
```

```
1 language=Sprache  
2 computeButton=Rechnen  
3 savings=Vorherige Ersparnisse  
4 contrib=Jährliche Einzahlung  
5 income=Einkommen nach Ruhestand  
6 currentAge=Jetziges Alter  
7 retireAge=Ruhestandsalter  
8 deathAge=Lebenserwartung  
9 inflationPercent=Inflation  
10 investPercent=Investitionsgewinn  
11 retire=Alter: {0,number} Guthaben: {1,number,currency}
```

```
var manager = new ScriptEngineManager();
ScriptEngine engine = manager.getEngineByName("javascript");

Object result = engine.eval(scriptString);

Object result = engine.eval(reader);

engine.eval("n = 1728");
Object result = engine.eval("n + 1");

Object param = factory.getParameter("THREADING");

engine.put("k", 1728);
Object result = engine.eval("k + 1");

engine.put("b", new JButton());
engine.eval("b.text = 'Ok'");

engine.eval("n = 1728");
Object result = engine.get("n");

Bindings scope = engine.createBindings();
scope.put("b", new JButton());
engine.eval(scriptString, scope);

var writer = new StringWriter();
engine.getContext().setWriter(new PrintWriter(writer, true));

println('Hello');
java.lang.System.out.println("World");

// Define greet function in JavaScript
engine.eval("function greet(how, whom) { return how + ', ' + whom + '!' }");

// Call the function with arguments "Hello", "World"
result = ((Invocable) engine).invokeFunction("greet", "Hello", "World");
```

```
// Define Greeter class in JavaScript
engine.eval("function Greeter(how) { this.how = how }");
engine.eval("Greeter.prototype.welcome =
    + " function(whom) { return this.how + ', ' + whom + '!' }");

// Construct an instance
Object yo = engine.eval("new Greeter('Yo')");

// Call the welcome method on the instance
result = ((Invocable) engine).invokeMethod(yo, "welcome", "World");

// Define welcome function in JavaScript
engine.eval("function welcome(whom) { return 'Hello, ' + whom + '!' }");

// Get a Java object and call a Java method
Greeter g = ((Invocable) engine).getInterface(Greeter.class);
result = g.welcome("World");

Greeter g = ((Invocable) engine).getInterface(yo, Greeter.class);
result = g.welcome("World");

var reader = new FileReader("myscript.js");
CompiledScript script = null;
if (engine implements Compilable)
    script = ((Compilable) engine).compile(reader);

componentName.eventName = scriptCode

yellowButton.action=panel.background = java.awt.Color.YELLOW
blueButton.action=panel.background = java.awt.Color.BLUE
redButton.action=panel.background = java.awt.Color.RED

yellowButton.action=panel.background = java.awt.Color.YELLOW
panel.background = java.awt.Color.YELLOW

java -classpath .:rhino-version.jar:rhino-engine-version.jar ScriptTest
java -classpath .:groovy/lib/* ScriptTest groovy
```

```
1 package script;
2
3 import java.awt.*;
4 import java.beans.*;
5 import java.io.*;
6 import java.lang.reflect.*;
7 import java.nio.charset.*;
8 import java.util.*;
9 import javax.script.*;
10 import javax.swing.*;
11
12 /**
13 * @version 1.04 2021-06-17
14 * @author Cay Horstmann
15 */
16 public class ScriptTest
17 {
18     public static void main(String[] args)
19     {
20         EventQueue.invokeLater(() ->
21         {
22             try
23             {
24                 var manager = new ScriptEngineManager();
25                 String language;
26                 if (args.length == 0)
27                 {
28                     System.out.println("Available factories: ");
29                     for (ScriptEngineFactory factory : manager.getEngineFactories())
30                         System.out.println(factory.getEngineName());
31
32                     language = "nashorn";
33                 }
34                 else language = args[0];
35
36                 final ScriptEngine engine = manager.getEngineByName(language);
37                 if (engine == null)
38                 {
39                     System.err.println("No engine for " + language);
40                     System.exit(1);
41                 }
42             }
43         }
44     }
45 }
```

```
42
43     final String frameClassName
44         = args.length < 2 ? "buttons1.ButtonFrame" : args[1];
45
46     var frame
47         = (JFrame) Class.forName(frameClassName).getConstructor().newInstance();
48     InputStream in = frame.getClass().getResourceAsStream("init." + language);
49     if (in != null) engine.eval(
50         new InputStreamReader(in, StandardCharsets.UTF_8));
51     var components = new HashMap<String, Component>();
52     getComponentBindings(frame, components);
53     components.forEach((name, c) -> engine.put(name, c));
54
55     var events = new Properties();
56     in = frame.getClass().getResourceAsStream(language + ".properties");
57     events.load(
58         new InputStreamReader(in, StandardCharsets.UTF_8));
59
60     for (Object e : events.keySet())
61     {
62         String[] s = ((String) e).split("\\.");
63         addListener(s[0], s[1], (String) events.get(e), engine, components);
64     }
65     frame.setTitle("ScriptTest");
66     frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
67     frame.setVisible(true);
68 }
69 catch (ReflectiveOperationException | IOException
70         | ScriptException | IntrospectionException e)
71 {
72     e.printStackTrace();
73 }
74 });
75 }
76 /**
77 * Gathers all named components in a container.
78 * @param c the component
79 * @param namedComponents a map into which to enter the component names and components
80 */
81 private static void getComponentBindings(Component c,
82             Map<String, Component> namedComponents)
83 {
84     String name = c.getName();
85     if (name != null) { namedComponents.put(name, c); }
```

```
57     if (c instanceof Container container)
58     {
59         for (Component child : container.getComponents())
60             getComponentBindings(child, namedComponents);
61     }
62 }
63
64 /**
65 * Adds a listener to an object whose listener method executes a script.
66 * @param beanName the name of the bean to which the listener should be added
67 * @param eventName the name of the listener type, such as "action" or "change"
68 * @param scriptCode the script code to be executed
69 * @param engine the engine that executes the code
70 * @param bindings the bindings for the execution
71 * @throws IntrospectionException
72 */
73 private static void addListener(String beanName, String eventName, final String scriptCode,
74     ScriptEngine engine, Map<String, Component> components)
75     throws ReflectiveOperationException, IntrospectionException
76 {
77     Object bean = components.get(beanName);
78     EventSetDescriptor descriptor = getEventSetDescriptor(bean, eventName);
79     if (descriptor == null) return;
80     descriptor.getAddListenerMethod().invoke(bean,
81         Proxy.newProxyInstance(null, new Class[] { descriptor.getListenerType() },
82             (proxy, method, args) ->
83             {
84                 engine.eval(scriptCode);
85                 return null;
86             }));
87 }
88
89 private static EventSetDescriptor getEventSetDescriptor(Object bean, String eventName)
90     throws IntrospectionException
91 {
92     for (EventSetDescriptor descriptor : Introspector.getBeanInfo(bean.getClass())
93         .getEventSetDescriptors())
94         if (descriptor.getName().equals(eventName)) return descriptor;
95     return null;
96 }
97 }
```

```
1 package buttons1;
2
3 import javax.swing.*;
4
5 /**
6  * A frame with a button panel.
7  * @version 1.00 2007-11-02
8  * @author Cay Horstmann
9  */
10 public class ButtonFrame extends JFrame
11 {
12     private static final int DEFAULT_WIDTH = 300;
13     private static final int DEFAULT_HEIGHT = 200;
14
15     private JPanel panel;
16     private JButton yellowButton;
17     private JButton blueButton;
18     private JButton redButton;
19
20     public ButtonFrame()
21     {
22         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
23
24         panel = new JPanel();
25         panel.setName("panel");
26         add(panel);
27
28         yellowButton = new JButton("Yellow");
29         yellowButton.setName("yellowButton");
30         blueButton = new JButton("Blue");
31         blueBntton.setName("blueButton");
32         redButton = new JButton("Red");
33         redButton.setName("redButton");
34
35         panel.add(yellowButton);
36         panel.add(blueButton);
37         panel.add(red8utton);
38     }
39 }
```

```
JavaCompiler compiler = ToolProvider.getSystemJavaCompiler();
OutputStream outStream = . . .;
OutputStream errStream = . . .;
int result = compiler.run(null, outStream, errStream,
    "-sourcepath", "src", "Test.java");

JavaCompiler.CompilationTask task = compiler.getTask(
    errorWriter, // Uses System.err if null
    fileManager, // Uses the standard file manager if null
    diagnostics, // Uses System.err if null
    options, // null if no options
    classes, // For annotation processing; null if none
    sources);

Iterable<String> options = List.of("-d", "bin");

StandardJavaFileManager fileManager = compiler.getStandardFileManager(null, null, null);
Iterable<JavaFileObject> sources
    = fileManager.getJavaFileObjectsFromStrings(List.of("File1.java", "File2.java"));

JavaCompiler.CompilationTask task = compiler.getTask(
    null, null, null, options, null, sources);

DiagnosticCollector<JavaFileObject> collector = new DiagnosticCollector<>();
compiler.getTask(null, fileManager, collector, null, null, sources).call();
for (Diagnostic<? extends JavaFileObject> d : collector.getDiagnostics())
{
    System.out.println(d);
}

StandardJavaFileManager fileManager
    = compiler.getStandardFileManager(diagnostics, null, null);

public class StringSource extends SimpleJavaFileObject
{
    private String code;
```

```
StringSource(String name, String code)
{
    super(URI.create("string:/// " + name.replace('.', '/') + ".java"), Kind.SOURCE);
    this.code = code;
}

public CharSequence getCharContent(boolean ignoreEncodingErrors)
{
    return code;
}
}

List<StringSource> sources = List.of(
    new StringSource(className1, class1CodeString), . . .);
task = compiler.getTask(null, fileManager, diagnostics, null, null, sources);

public class ByteArrayClass extends SimpleJavaFileObject
{
    private ByteArrayOutputStream out;

    ByteArrayClass(String name)
    {
        super(URI.create("bytes:/// " + name.replace('.', '/') + ".class"), Kind.CLASS);
    }

    public byte[] getCode()
    {
        return out.toByteArray();
    }

    public OutputStream openOutputStream() throws IOException
    {
        out = new ByteArrayOutputStream();
        return out;
    }
}

List<ByteArrayClass> classes = new ArrayList<>();
StandardJavaFileManager stdFileManager
```

```
= compiler.getStandardFileManager(null, null, null);
JavaFileManager fileManager
= new ForwardingJavaFileManager<JavaFileManager>(stdFileManager)
{
    public JavaFileObject getJavaFileForOutput(Location location,
                                                String className, Kind kind, FileObject sibling)
        throws IOException
    {
        if (kind == Kind.CLASS)
        {
            ByteArrayClass outfile = new ByteArrayClass(className);
            classes.add(outfile);
            return outfile;
        }
        else
            return super.getJavaFileForOutput(location, className, kind, sibling);
    }
};

public class ByteArrayClassLoader extends ClassLoader
{
    private Iterable<ByteArrayClass> classes;

    public ByteArrayClassLoader(Iterable<ByteArrayClass> classes)
    {
        this.classes = classes;
    }

    public Class<?> findClass(String name) throws ClassNotFoundException
    {
        for (ByteArrayClass cl : classes)
        {
            if (cl.getName().equals("/") + name.replace('.', '/') + ".class"))
            {
                byte[] bytes = cl.getCode();
                return defineClass(name, bytes, 0, bytes.length);
            }
        }
        throw new ClassNotFoundException(name);
    }
}
```

```
ByteArrayClassLoader loader = new ByteArrayClassLoader(classes);
Class<?> cl = Class.forName(className, true, loader);

<p>The current date and time is <b><%= new java.util.Date() %></b>.</p>

package x;
public class Frame extends SuperclassName
{
    protected void addEventHandlers()
    {
        componentName1.addActionListener(event ->
        {
            code for event handler1
        });
        // repeat for the other event handlers . .
    }
}

var loader = new ByteArrayClassLoader(classFileObjects);
var frame = (JFrame) loader.loadClass("x.Frame").getConstructor().newInstance();
frame.setVisible(true);

yellowButton=panel.setBackground(java.awt.Color.YELLOW); yellowButton.setEnabled(false);
```

```
1 package compiler;
2
3 import java.awt.*;
4 import java.io.*;
5 import java.nio.charset.*;
6 import java.nio.file.*;
7 import java.util.*;
8 import java.util.List;
9
10 import javax.swing.*;
11 import javax.tools.*;
12 import javax.tools.JavaFileObject.*;
13
14 /**
15  * @version 1.10 2018-05-01
16  * @author Cay Horstmann
17  */
18 public class CompilerTest
19 {
20     public static void main(final String[] args)
21         throws IOException, ReflectiveOperationException
22     {
23         JavaCompiler compiler = ToolProvider.getSystemJavaCompiler();
24
25         var classFileObjects = new ArrayList<ByteArrayClass>();
26
27         var diagnostics = new DiagnosticCollector<JavaFileObject>();
28
29         JavaFileManager fileManager = compiler.getStandardFileManager(diagnostics, null, null);
30         fileManager = new ForwardingJavaFileManager<JavaFileManager>(fileManager)
31     }
```

```
32     public JavaFileObject getJavaFileForOutput(Location location,
33         String className, Kind kind, FileObject sibling) throws IOException
34     {
35         if (kind == Kind.CLASS)
36         {
37             var fileObject = new ByteArrayClass(className);
38             classFileObjects.add(fileObject);
39             return fileObject;
40         }
41         else return super.getJavaFileForOutput(location, className, kind, sibling);
42     }
43 };
44
45
46 String frameClassName = args.length == 0 ? "buttons2.ButtonFrame" : args[0];
47 //compiler.run(null, null, null, frameClassName.replace(".", "/") + ".java");
48
49 StandardJavaFileManager fileManager2 = compiler.getStandardFileManager(null, null, null);
50 var sources = new ArrayList<JavaFileObject>();
51 for (JavaFileObject o : fileManager2.getJavaFileObjectsFromStrings(
52     List.of(frameClassName.replace(".", "/") + ".java")))
53     sources.add(o);
54
55 JavaFileObject source = buildSource(frameClassName);
56 JavaCompiler.CompilationTask task = compiler.getTask(null, fileManager, diagnostics,
57     null, null, List.of(source));
58 Boolean result = task.call();
59
60 for (Diagnostic<? extends JavaFileObject> d : diagnostics.getDiagnostics())
61     System.out.println(d.getKind() + ": " + d.getMessage(null));
62 fileManager.close();
63 if (!result)
64 {
65     System.out.println("Compilation failed.");
66     System.exit(1);
67 }
68
69 var loader = new ByteArrayClassLoader(classFileObjects);
70 var frame = (JFrame) loader.loadClass("x.Frame").getConstructor().newInstance();
71
72 EventQueue.invokeLater(() ->
73 {
74     frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
75     frame.setTitle("CompilerTest");
76     frame.setVisible(true);
77 });
78 }
79
```

```
80  /*
81   * Builds the source for the subclass that implements the addEventHandlers method.
82   * @return a file object containing the source in a string builder
83   */
84  static JavaFileObject buildSource(String superClass)
85      throws IOException, ClassNotFoundException
86  {
87      var builder = new StringBuilder();
88      builder.append("package x;\n\n");
89      builder.append("public class Frame extends " + superClass + " {\n");
90      builder.append("protected void addEventHandlers() {\n");
91      var props = new Properties();
92      props.load(Files.newBufferedReader(
93          Path.of(superClass.replace(".", "/")).getParent().resolve("action.properties"),
94          StandardCharsets.UTF_8));
95      for (Map.Entry<Object, Object> e : props.entrySet())
96      {
97          var beanName = (String) e.getKey();
98          var eventCode = (String) e.getValue();
99          builder.append(beanName + ".addActionListener(event -> {\n");
100         builder.append(eventCode);
101         builder.append("\n} );\n");
102     }
103     builder.append("}\n");
104     return new StringSource("x.Frame", builder.toString());
105 }
106 }
```

```
1 package buttons2;
2 import javax.swing.*;
3
4 /**
5  * A frame with a button panel.
6  * @version 1.00 2007-11-02
7  * @author Cay Horstmann
8 */
9 public abstract class ButtonFrame extends JFrame
10 {
11     public static final int DEFAULT_WIDTH = 300;
12     public static final int DEFAULT_HEIGHT = 200;
13
14     protected JPanel panel;
15     protected JButton yellowButton;
16     protected JButton blueButton;
17     protected JButton redButton;
18
19     protected abstract void addEventHandlers();
20
21     public ButtonFrame()
22     {
23         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
24
25         panel = new JPanel();
26         add(panel);
27
28         yellowButton = new JButton("Yellow");
29         blueButton = new JButton("Blue");
30         redButton = new JButton("Red");
31
32         panel.add(yellowButton);
33         panel.add(blueButton);
34         panel.add(redButton);
35
36         addEventHandlers();
37     }
38 }
```

```
1 yellowButton=panel.setBackground(java.awt.Color.YELLOW);
2 blueButton=panel.setBackground(java.awt.Color.BLUE);


---


public class MyClass
{
    ...
    @Test public void checkRandomInsertions()
}

@Target(ElementType.METHOD)
@Retention(RetentionPolicy.RUNTIME)
public @interface Test
{
    long timeout() default 0L;
    ...
}

myButton.addActionListener(() -> doSomething());

@ActionListenerFor(source="myButton") void doSomething() { . . . }

ActionListenerInstaller.processAnnotations(this);

Class<?> cl = obj.getClass();
for (Method m : cl.getDeclaredMethods())
{
    ActionListenerFor a = m.getAnnotation(ActionListenerFor.class);
    if (a != null) . . .
}

String fieldName = a.source();
Field f = cl.getDeclaredField(fieldName);
```

```
1 package runtimeAnnotations;
2
3 import java.awt.event.*;
4 import java.lang.reflect.*;
5
6 /**
7  * @version 1.00 2004-08-17
8  * @author Cay Horstmann
9  */
10 public class ActionListenerInstaller
11 {
12     /**
13      * Processes all ActionListenerFor annotations in the given object.
14      * @param obj an object whose methods may have ActionListenerFor annotations
15      */

```

```
16 public static void processAnnotations(Object obj)
17 {
18     try
19     {
20         Class<?> cl = obj.getClass();
21         for (Method m : cl.getDeclaredMethods())
22         {
23             ActionListenerFor a = m.getAnnotation(ActionListenerFor.class);
24             if (a != null)
25             {
26                 Field f = cl.getDeclaredField(a.source());
27                 f.setAccessible(true);
28                 addListener(f.get(obj), obj, m);
29             }
30         }
31     }
32     catch (ReflectiveOperationException e)
33     {
34         e.printStackTrace();
35     }
36 }
37
38 /**
39 * Adds an action listener that calls a given method.
40 * @param source the event source to which an action listener is added
41 * @param param the implicit parameter of the method that the listener calls
42 * @param m the method that the listener calls
43 */
44 public static void addListener(Object source, final Object param, final Method m)
45     throws ReflectiveOperationException
46 {
47     var handler = new InvocationHandler()
48     {
49         public Object invoke(Object proxy, Method mm, Object[] args) throws Throwable
50         {
51             return m.invoke(param);
52         }
53     };
54
55     Object listener = Proxy.newProxyInstance(null,
56         new Class[] { java.awt.event.ActionListener.class }, handler);
57     Method adder = source.getClass().getMethod("addActionListener", ActionListener.class);
58     adder.invoke(source, listener);
59 }
60 }
```

```
1 package buttons3;
2
3 import java.awt.*;
4 import javax.swing.*;
5 import runtimeAnnotations.*;
6
7 /**
8  * A frame with a button panel.
9  * @version 1.00 2004-08-17
10 * @author Cay Horstmann
11 */
12 public class ButtonFrame extends JFrame
13 {
14     private static final int DEFAULT_WIDTH = 300;
15     private static final int DEFAULT_HEIGHT = 200;
16
17     private JPanel panel;
18     private JButton yellowButton;
19     private JButton blueButton;
20     private JButton redButton;
21
22     public ButtonFrame()
23     {
24         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
25
26         panel = new JPanel();
27         add(panel);
28
29         yellowButton = new JButton("Yellow");
30         blueButton = new JButton("Blue");
31         redButton = new JButton("Red");
32
33         panel.add(yellowButton);
34         panel.add(blueButton);
35         panel.add(redButton);
36
37         ActionListenerInstaller.processAnnotations(this);
38     }
39
40     @ActionListenerFor(source = "yellowButton")
41     public void yellowBackground()
42     {
43         panel.setBackground(Color.YELLOW);
44     }
45
46     @ActionListenerFor(source = "blueButton")
47     public void blueBackground()
```

```
48     {
49         panel.setBackground(Color.BLUE);
50     }
51
52     @ActionListenerFor(source = "redButton")
53     public void redBackground()
54     {
55         panel.setBackground(Color.RED);
56     }
57 }
```

```
1 package runtimeAnnotations;
2
3 import java.lang.annotation.*;
4
5 /**
6  * @version 1.00 2004-08-17
7  * @author Cay Horstmann
8  */
9 @Target(ElementType.METHOD)
10 @Retention(RetentionPolicy.RUNTIME)
11 public @interface ActionListenerFor
12 {
13     String source();
14 }
```

modifiers `@interface AnnotationName`
{

elementDeclaration₁
elementDeclaration₂

...

}

type elementName() default value;

`public @interface BugReport`

{

`String assignedTo() default "[none]";`
`int severity();`

}

```
public @interface BugReport
{
    enum Status { UNCONFIRMED, CONFIRMED, FIXED, NOTABUG };
    boolean showStopper() default false;
    String assignedTo() default "[none]";
    Class<?> testCase() default Void.class;
    Status status() default Status.UNCONFIRMED;
    Reference ref() default @Reference(); // an annotation type
    String[] reportedBy();
}

@AnnotationName(elementName1=value1, elementName2=value2, . . .)

@BugReport(assignedTo="Harry", severity=10)

@BugReport(severity=10, assignedTo="Harry")

@BugReport(assignedTo="[none]", severity=0)

public @interface ActionListenerFor
{
    String value();
}

@ActionListenerFor("yellowButton")

@ActionListenerFor(value="yellowButton")

@Test
@BugReport(showStopper=true, reportedBy="Joe")
public void checkRandomInsertions()

@BugReport(showStopper=true, reportedBy="Joe")
@BugReport(reportedBy={"Harry", "Carl"})
public void checkRandomInsertions()

@BugReport(showStopper=true, assignedTo="Harry", testCase=MyTestCase.class,
           status=BugReport.Status.CONFIRMED, . . .)

@BugReport(. . ., reportedBy={"Harry", "Carl"})
```

```
@BugReport( . . . , reportedBy="Joe") // OK, same as {"Joe"}
```

```
@BugReport(ref=@Reference(id="3352627"), . . .)
```

```
@Entity public class User { . . . }
```

```
@SuppressWarnings("unchecked") List<User> users = . . .;
```

```
public User getUser(@Param("id") String userId)
```

```
public class Cache<@Immutable V> { . . . }
```

```
/**  
 * Package-level Javadoc  
 */
```

```
@GPL(version="3")
```

```
package com.horstmann.corejava;
```

```
import org.gnu.GPL;
```

```
public User getUser(@NonNull String userId)
```

```
@NonNull String.class // ERROR: Cannot annotate class literal
```

```
import java.lang.@NonNull String; // ERROR: Cannot annotate import
```

```
private @NonNull String text; // Annotates the type use
```

```
@Id private String userId; // Annotates the variable
```

```
public User getUser(@NonNull String userId)
```

```
public class Point
```

```
{
```

```
    public boolean equals(@ReadOnly Object other) { . . . }
```

```
}
```

```
public class Point
```

```
{
```

```
    public boolean equals(@ReadOnly Point this, @ReadOnly Object other) { . . . }
```

```
}
```

```
public class Sequence
{
    private int from;
    private int to;

    class Iterator implements java.util.Iterator<Integer>
    {
        private int current;
        public Iterator(@ReadOnly Sequence Sequence.this)
        {
            this.current = Sequence.this.from;
        }
        ...
    }
    ...
}

@SuppressWarnings("unchecked")

public MyClass
{
    @Override public boolean equals(MyClass other);
    ...
}

@Generated("com.horstmann.beanproperty", "2008-01-04T12:08:56.235-0700");

@Target({ElementType.TYPE, ElementType.METHOD})
public @interface BugReport

@Documented
@Target(ElementType.METHOD)
@Retention(RetentionPolicy.RUNTIME)
public @interface ActionListenerFor

@Inherited @interface Persistent { }
@Persistent class Employee { . . . }
class Manager extends Employee { . . . } // also @Persistent

javac -processor ProcessorClassName1,ProcessorClassName2,. . . sourceFiles
```

```
@SupportedAnnotationTypes("com.horstmann.annotations.ToString")
@SupportedSourceVersion(SourceVersion.RELEASE_8)
public class ToStringAnnotationProcessor extends AbstractProcessor
{
    public boolean process(Set<? extends TypeElement> annotations,
                          RoundEnvironment currentRound)
    {
        . . .
    }
}

Set<? extends Element> getElementsAnnotatedWith(Class<? extends Annotation> a)

A getAnnotation(Class<A> annotationType)
A[] getAnnotationsByType(Class<A> annotationType)

public class ToStrings
{
    public static String toString(Point obj)
    {
        Generated code
    }
    public static String toString(Rectangle obj)
    {
        Generated code
    }
    . . .

    public static String toString(Object obj)
    {
        return Objects.toString(obj);
    }
}
```

```
@ToString
public class Rectangle
{
    ...
    @ToString(includeName=false) public Point getTopLeft() { return topLeft; }
    @ToString public int getWidth() { return width; }
    @ToString public int getHeight() { return height; }
}

public static String toString(Rectangle obj)
{
    var result = new StringBuilder();
    result.append("Rectangle");
    result.append("[");
    result.append(toString(obj.getTopLeft()));
    result.append(",");
    result.append("width=");
    result.append(toString(obj.getWidth()));
    result.append(",");
    result.append("height=");
    result.append(toString(obj.getHeight()));

    result.append("]");
    return result.toString();
}
```

```
private void writeToStringMethod(PrintWriter out, TypeElement te)
{
    String className = te.getQualifiedName().toString();
    Print method header and declaration of string builder
    ToString ann = te.getAnnotation(ToString.class);
    if (ann.includeName())
        Print code to add class name
    for (Element c : te.getEnclosedElements())
    {
        ann = c.getAnnotation(ToString.class);
        if (ann != null)
        {
            if (ann.includeName()) Print code to add field name
            Print code to append toString(obj.methodName())
        }
    }
    Print code to return string
}

public boolean process(Set<? extends TypeElement> annotations,
                      RoundEnvironment currentRound)
{
    if (annotations.size() == 0) return true;
    try
    {
        JavaFileObject sourceFile = processingEnv.getFiler().createSourceFile(
            "com.horstmann.annotations.ToStrings");
        try (var out = new PrintWriter(sourceFile.openWriter()))
        {
            Print code for package and class
            for (Element e : currentRound.getElementsAnnotatedWith(ToString.class))
                if (e instanceof TypeElement te)
                    writeToStringMethod(out, te);
            Print code for toString(Object)
        }
        catch (IOException e)
        {
            processingEnv.getMessager().printMessage(
                Kind.ERROR, ex.getMessage());
        }
    }
}
```

```
    }
    return true;
}

javac sourceAnnotations/ToStringAnnotationProcessor.java
javac -processor sourceAnnotations.ToStringAnnotationProcessor rect/*.java
java rect.SourceLevelAnnotationDemo
```

Round 1:

```
  input files: {rect.Point, rect.Rectangle,
    rect.SourceLevelAnnotationDemo}
  annotations: [sourceAnnotations.ToString]
  last round: false
```

Round 2:

```
  input files: {sourceAnnotations.ToStrings}
  annotations: []
  last round: false
```

Round 3:

```
  input files: {}
  annotations: []
  last round: true
```

```
@Property private String title;
```

```
public String getTitle() { return title; }
public void setTitle(String title) { this = title; }
```

```
Logger.getLogger(loggerName).entering(className, methodName);
```

```
@LogEntry(logger="global") public int hashCode()
```

```
May 17, 2016 10:57:59 AM Item hashCode
```

```
FINER: ENTRY
```

```
ldc loggerName
invokestatic
  java/util/logging/Logger.getLogger:(Ljava/lang/String;)Ljava/util/logging/Logger;
ldc className
ldc methodName
invokevirtual
  java/util/logging/Logger.entering:(Ljava/lang/String;Ljava/lang/String;)V
```

```
javac set/Item.java
javac -classpath .:asm/* bytecodeAnnotations/EntryLogger.java
java -classpath .:asm/* bytecodeAnnotations.EntryLogger set.Item

public int hashCode();
Code:
 0: ldc #85; // String global
 2: invokestatic #80;
   // Method
   // java/util/logging/Logger.getLogger:(Ljava/lang/String;)Ljava/util/logging/Logger;
 5: ldc #86; //String Item
 7: ldc #88; //String hashCode
 9: invokevirtual #84;
   // Method java/util/logging/Logger.entering:(Ljava/lang/String;Ljava/lang/String;)V
12: bipush 13
14: aload_0
15: getfield #2; // Field description:Ljava/lang/String;
18: invokevirtual #15; // Method java/lang/String.hashCode:()I
21: imul
22: bipush 17
24: aload_0
25: getfield #3; // Field partNumber:I
28: imul
```

```
public int hashCode();
Code:
0: ldc #85; // String global
2: invokestatic #80;
   // Method
   // java/util/logging/Logger.getLogger:(Ljava/lang/String;)Ljava/util/logging/Logger;
5: ldc #86; //String Item
7: ldc #88; //String hashCode
9: invokevirtual #84;
   // Method java/util/logging/Logger.entering:(Ljava/lang/String;Ljava/lang/String;)V
12: bipush 13
14: aload_0
15: getfield #2; // Field description:Ljava/lang/String;
18: invokevirtual #15; // Method java/lang/String.hashCode:()I
21: imul
22: bipush 17
24: aload_0
25: getfield #3; // Field partNumber:I
28: imul
29: iadd
30: ireturn
```

May 17, 2016 10:57:59 AM Item hashCode

FINER: ENTRY

May 17, 2016 10:57:59 AM Item hashCode

FINER: ENTRY

May 17, 2016 10:57:59 AM Item hashCode

FINER: ENTRY

May 17, 2016 10:57:59 AM Item equals

FINER: ENTRY

[[description=Toaster, partNumber=1729], [description=Microwave, partNumber=4104]]

```
1 package bytecodeAnnotations;
2
3 import java.io.*;
4 import java.nio.file.*;
5
6 import org.objectweb.asm.*;
7 import org.objectweb.asm.commons.*;
8
9 /**
10  * Adds "entering" logs to all methods of a class that have the LogEntry annotation.
11  * @version 1.21 2018-05-01
12  * @author Cay Horstmann
13  */
14 public class EntryLogger extends ClassVisitor
15 {
16     private String className;
17
18     /**
19      * Constructs an EntryLogger that inserts logging into annotated methods of a given class.
20      */
21     public EntryLogger(ClassWriter writer, String className)
22     {
23         super(OpcodesASM5, writer);
24         this.className = className;
25     }
}
```

```
26
27     public MethodVisitor visitMethod(int access, String methodName, String desc,
28             String signature, String[] exceptions)
29     {
30         MethodVisitor mv = cv.visitMethod(access, methodName, desc, signature, exceptions);
31         return new AdviceAdapter(Opcodes.ASM5, mv, access, methodName, desc)
32     {
33         private String loggerName;
34
35         public AnnotationVisitor visitAnnotation(String desc, boolean visible)
36         {
37             return new AnnotationVisitor(Opcodes.ASM5)
38             {
39                 public void visit(String name, Object value)
40                 {
41                     if (desc.equals("LbytecodeAnnotations/LogEntry;"))
42                         && name.equals("logger"))
43                     loggerName = value.toString();
44                 }
45             };
46         }
47
48         public void onMethodEnter()
49         {
50             if (loggerName != null)
51             {
52                 visitLdcInsn(loggerName);
53                 visitMethodInsn(INVOKESTATIC, "java/util/logging/Logger", "getLogger",
54                             "(Ljava/lang/String;)Ljava/util/logging/Logger;", false);
55                 visitLdcInsn(className);
56                 visitLdcInsn(methodName);
57                 visitMethodInsn(INVOKEVIRTUAL, "java/util/logging/Logger", "entering",
58                             "(Ljava/lang/String;Ljava/lang/String;)V", false);
59                 loggerName = null;
60             }
61         }
62     };
63 }
64
65 /**
66 * Adds entry logging code to the given class.
67 * @param args the name of the class file to patch
68 */
69 public static void main(String[] args) throws IOException
70 {
71     if (args.length == 0)
72     {
```

```
73     System.out.println("USAGE: java bytecodeAnnotations.EntryLogger classfile");
74     System.exit(1);
75 }
76 Path path = Path.of(args[0]);
77 var reader = new ClassReader(Files.newInputStream(path));
78 var writer = new ClassWriter(
79     ClassWriter.COMPUTE_MAXS | ClassWriter.COMPUTE_FRAMES);
80 var entryLogger = new EntryLogger(writer,
81     path.toString().replace(".class", "").replaceAll("[\\\\\\\\]", "."));
82 reader.accept(entryLogger, ClassReader.EXPAND_FRAMES);
83 Files.write(Path.of(args[0]), writer.toByteArray());
84 }
85 }
```

```
1 package set;
2
3 import java.util.*;
4 import bytecodeAnnotations.*;
5
6 /**
7  * An item with a description and a part number.
8  * @version 1.01 2012-01-26
9  * @author Cay Horstmann
10 */
11 public class Item
12 {
13     private String description;
14     private int partNumber;
15
16     /**
17      * Constructs an item.
18      * @param aDescription the item's description
19      * @param aPartNumber the item's part number
20      */
21     public Item(String aDescription, int aPartNumber)
22     {
23         description = aDescription;
24         partNumber = aPartNumber;
25     }
26
27     /**
28      * Gets the description of this item.
29      * @return the description
30      */
31     public String getDescription()
32     {
```

```
33     return description;
34 }
35
36 public String toString()
37 {
38     return "[description=" + description + ", partNumber=" + partNumber + "]";
39 }
40
41 @LogEntry(logger = "com.horstmann")
42 public boolean equals(Object otherObject)
43 {
44     if (this == otherObject) return true;
45     if (otherObject == null) return false;
46     if (getClass() != otherObject.getClass()) return false;
47     var other = (Item) otherObject;
48     return Objects.equals(description, other.description) && partNumber == other.partNumber;
49 }
50
51 @LogEntry(logger = "com.horstmann")
52 public int hashCode()
53 {
54     return Objects.hash(description, partNumber);
55 }
56 }
```

```
1 package set;
2
3 import java.util.*;
4 import java.util.logging.*;
5
6 /**
7  * @version 1.03 2018-05-01
8  * @author Cay Horstmann
9  */
10 public class SetTest
11 {
12     public static void main(String[] args)
13     {
14         Logger.getLogger("com.horstmann").setLevel(Level.FINEST);
15         var handler = new ConsoleHandler();
16         handler.setLevel(Level.FINEST);
17         Logger.getLogger("com.horstmann").addHandler(handler);
18
19         var parts = new HashSet<Item>();
20         parts.add(new Item("Toaster", 1279));
21
22         parts.add(new Item("Microwave", 4104));
23         parts.add(new Item("Toaster", 1279));
24         System.out.println(parts);
25     }
26 }
```

```
public static void premain(String arg, Instrumentation instr)
```

```
Premain-Class: bytecodeAnnotations.EntryLoggingAgent
```

```
javac -classpath .:asm/* bytecodeAnnotations/EntryLoggingAgent.java
jar cvfm EntryLoggingAgent.jar bytecodeAnnotations/EntryLoggingAgent.mf \
    bytecodeAnnotations/Entry*.class
```

```
java -javaagent:AgentJARFile=agentArgument . . .
```

```
javac set/SetTest.java
```

```
java -javaagent:EntryLoggingAgent.jar=set.Item -classpath .:asm/* set.SetTest
```

```
1 package bytecodeAnnotations;
2
3 import java.lang.instrument.*;
4
5 import org.objectweb.asm.*;
6
7 /**
8  * @version 1.11 2018-05-01
9  * @author Cay Horstmann
10 */
11 public class EntryLoggingAgent
12 {
13     public static void premain(final String arg, Instrumentation instr)
14     {
15         instr.addTransformer(new ClassFileTransformer()
16         {
17             public byte[] transform(ClassLoader loader, String className, Class<?> cl,
18                                     ProtectionDomain pd, byte[] data) throws IllegalClassFormatException
19             {
20
21                 if (!className.replace("/", ".").equals(arg)) return null;
22                 var reader = new ClassReader(data);
23                 var writer = new ClassWriter(
24                     ClassWriter.COMPUTE_MAXS | ClassWriter.COMPUTE_FRAMES);
25                 var el = new EntryLogger(writer, className);
26                 reader.accept(el, ClassReader.EXPAND_FRAMES);
27                 return writer.toByteArray();
28             }
29         });
30     }
31 }
```

```
package com.horstmann.hello;

public class HelloWorld
{
    public static void main(String[] args)
    {
        System.out.println("Hello, Modular World!");
    }
}

javac v2ch09.hellomod/module-info.java v2ch09.hellomod/com/horstmann/hello/HelloWorld.java

java --module-path v2ch09.hellomod --module v2ch09.hellomod/com.horstmann.hello.HelloWorld

java -p v2ch09.hellomod -m v2ch09.hellomod/com.horstmann.hello.HelloWorld

warning: [module] module name component v2ch09 should avoid terminal digits

package com.horstmann.hello;

import javax.swing.JOptionPane;

public class HelloWorld
{
    public static void main(String[] args)
    {
        JOptionPane.showMessageDialog(null, "Hello, Modular World!");
    }
}

error: package javax.swing is not visible
  (package javax.swing is declared in module java.desktop,
  but module v2ch09.requiremod does not read it)
```

```
module java.xml
{
    exports javax.xml;
    exports javax.xml.catalog;
    exports javax.xml.datatype;
    exports javax.xml.namespace;
    exports javax.xml.parsers;
    ...
}

package com.horstmann.greet;

public interface Greeter
{
    static Greeter newInstance()
    {
        return new com.horstmann.greet.internal.GreeterImpl();
    }

    String greet(String subject);
}

package com.horstmann.greet.internal;

import com.horstmann.greet.Greeter;

public class GreeterImpl implements Greeter
{
    public String greet(String subject)
    {
        return "Hello, " + subject + "!";
    }
}
```

```
package com.horstmann.hello;

import com.horstmann.greet.Greeter;

public class HelloWorld
{
    public static void main(String[] args)
    {
        Greeter greeter = Greeter.newInstance();
        System.out.println(greeter.greet("Modular World"));
    }
}

javac com.horstmann.greet/module-info.java \
com.horstmann.greet/com/horstmann/greet/Greeter.java \
com.horstmann.greet/com/horstmann/greet/internal/GreeterImpl.java

javac -p com.horstmann.greet v2ch09.exportedpkg/module-info.java \
v2ch09.exportedpkg/com/horstmann/hello>HelloWorld.java

java -p v2ch09.exportedpkg:com.horstmann.greet \
-m v2ch09.exportedpkg/com.horstmann.hello.HelloWorld

javac -d modules/com.horstmann.greet $(find com.horstmann.greet -name *.java)
jar -c -v -f com.horstmann.greet.jar -C modules/com.horstmann.greet .

javac -p com.horstmann.greet.jar \
-d modules/v2ch09.exportedpkg $(find v2ch09.exportedpkg -name *.java)
jar -c -v -f v2ch09.exportedpkg.jar -e com.horstmann.hello.HelloWorld \
-C modules/v2ch09.exportedpkg .

java -p com.horstmann.greet.jar:v2ch09.exportedpkg.jar -m v2ch09.exportedpkg

jar -c -v -f com.horstmann.greet@1.0.jar --module-version 1.0 -C com.horstmann.greet .

Optional<String> version = Greeter.class.getModule().getDescriptor().rawVersion();

jshell --module-path com.horstmann.greet@1.0.jar --add-modules com.horstmann.greet
```

```
Field f = obj.getClass().getDeclaredField("salary");
f.setAccessible(true);

double value = f.getDouble(obj);
f.setDouble(obj, value * 1.1);

package com.horstmann.places;

public class Country
{
    private String name;
    private double area;

    public Country(String name, double area)
    {
        this.name = name;
        this.area = area;
    }
    // ...
}

package com.horstmann.places;

import com.horstmann.util.*;

public class Demo
{
    public static void main(String[] args) throws ReflectiveOperationException
    {
        var belgium = new Country("Belgium", 30510);
        var analyzer = new ObjectAnalyzer();
        System.out.println(analyzer.toString(belgium));
    }
}

javac com.horstmann.util/module-info.java \
    com.horstmann.util/com/horstmann/util/ObjectAnalyzer.java
javac -p com.horstmann.util v2ch09.openpkg/module-info.java \
    v2ch09.openpkg/com/horstmann/places/*.java
java -p v2ch09.openpkg:com.horstmann.util -m v2ch09.openpkg/com.horstmann.places.Demo
```

```
Exception in thread "main" java.lang.reflect.InaccessibleObjectException:  
  Unable to make field private java.lang.String com.horstmann.places.Country.name  
  accessible: module v2ch09.openpkg does not "opens com.horstmann.places" to module  
  com.horstmann.util  
  
open module v2ch09.openpkg  
{  
    requires com.horstmann.util;  
}  
  
public Object getFieldValue(Object obj, String fieldName, Lookup lookup)  
    throws NoSuchFieldException, IllegalAccessException  
{  
    Class<?> cl = obj.getClass();  
    Field field = cl.getDeclaredField(fieldName);  
    VarHandle handle = MethodHandles.privateLookupIn(cl, lookup)  
        .unreflectVarHandle(field);  
    return handle.get(obj);  
}
```

Automatic-Module-Name: org.apache.commons.csv

```
package com.horstmann.places;

import java.io.*;
import org.apache.commons.csv.*;

public class CSVDemo
{
    public static void main(String[] args) throws IOException
    {
        var in = new FileReader("countries.csv");
        Iterable<CSVRecord> records = CSVFormat.EXCEL.withDelimiter(';')
            .withHeader().parse(in);
        for (CSVRecord record : records)
        {
            String name = record.get("Name");
            double area = Double.parseDouble(record.get("Area"));
            System.out.println(name + " has area " + area);
        }
    }
}
```

```
javac -p v2ch09.automod:commons-csv-1.9.0.jar \
    v2ch09.automod/com/horstmann/places/CSVDemo.java \
    v2ch09.automod/module-info.java
```

```
java -p v2ch09.automod:commons-csv-1.9.0.jar \
    -m v2ch09.automod/com.horstmann.places.CSVDemo
```

```
java --module-path v2ch09.automod \
    --class-path commons-csv-1.9.0.jar \
    -m v2ch09.automod/com.horstmann.places.CSVDemo
```

```
Error occurred during initialization of boot layer
java.lang.module.FindException: Module commons.csv not found, required by v2ch09.automod
```

```
java --add-exports java.sql.rowset/com.sun.rowset=ALL_UNNAMED \
    -jar MyApp.jar
```

```
--add-opens java.base/java.lang=ALL-UNNAMED
```

```
java @options1 @options2 -jar MyProg.java

java.awt.datatransfer.Clipboard java.awt.Toolkit.getSystemClipboard()
java.beans.XMLDecoder(org.xml.sax.InputSource is)

module java.desktop
{
    requires java.prefs;
    requires transitive java.datatransfer;
    requires transitive java.xml;
    ...
}

module java.sql
{
    requires transitive java.logging;
    ...
}

module java.se
{
    requires transitive java.compiler;
    requires transitive java.datatransfer;
    requires transitive java.desktop;
    ...
    requires transitive java.sql;
    requires transitive java.sql.rowset;
    requires transitive java.xml;
    requires transitive java.xml.crypto;
}

try
{
    new oracle.jdbc.driver.OracleDriver();
    ...
}
catch (NoClassDefFoundError er)
{
    Do something else
}
```

```
module v2ch09.openpkg
{
    requires com.horstmann.util;
    opens com.horstmann.places to com.horstmann.util;
}

public interface GreeterService
{
    String greet(String subject);
    Locale getLocale();
}

public class FrenchGreeter implements GreeterService
{
    public String greet(String subject) { return "Bonjour " + subject; }
    public Locale getLocale() { return Locale.FRENCH; }
}

ServiceLoader<GreeterService> greeterLoader = ServiceLoader.load(GreeterService.class);
GreeterService chosenGreeter;
for (GreeterService greeter : greeterLoader)
{
    if (... )
    {
        chosenGreeter = greeter;
    }
}

module jdk.security.auth
{
    ...
    provides javax.security.auth.spi.LoginModule with
        com.sun.security.auth.module.Krb5LoginModule,
        com.sun.security.auth.module.UnixLoginModule,
        com.sun.security.auth.module.JndiLoginModule,
        com.sun.security.auth.module.KeyStoreLoginModule,
        com.sun.security.auth.module.LdapLoginModule,
        com.sun.security.auth.module.NTLoginModule;
}
```

```
module java.base
{
    ...
    uses javax.security.auth.spi.LoginModule;
}

module com.horstmann.greetsvc
{
    exports com.horstmann.greetsvc;

    provides com.horstmann.greetsvc.GreeterService with
        com.horstmann.greetsvc.internal.FrenchGreeter,
        com.horstmann.greetsvc.internal.GermanGreeterFactory;
}

package com.horstmann.hello;

import java.util.*;
import com.horstmann.greetsvc.*;

public class HelloWorld
{
    public static void main(String[] args)
    {

        ServiceLoader<GreeterService> greeterLoader
            = ServiceLoader.load(GreeterService.class);
        String desiredLanguage = args.length > 0 ? args[0] : "de";
        GreeterService chosenGreeter = null;
        for (GreeterService greeter : greeterLoader)
        {
            if (greeter.getLocale().getLanguage().equals(desiredLanguage))
                chosenGreeter = greeter;
        }
        if (chosenGreeter == null)
            System.out.println("No suitable greeter.");
        else
            System.out.println(chosenGreeter.greet("Modular World"));
    }
}
```

```
module v2ch09.usesservice
{
    requires com.horstmann.greetsvc;
    uses com.horstmann.greetsvc.GreeterService;
}

javac com.horstmann.greetsvc/module-info.java \
com.horstmann.greetsvc/com/horstmann/greetsvc/GreeterService.java \
com.horstmann.greetsvc/com/horstmann/greetsvc/internal/*.java

javac -p com.horstmann.greetsvc \
v2ch09.usesservice/com/horstmann/hello/HelloWorld.java \
v2ch09.usesservice/module-info.java
java -p com.horstmann.greetsvc:v2ch09.usesservice \
-m v2ch09.usesservice/com.horstmann.hello.HelloWorld

jdeps -s junit-4.12.jar hamcrest-core-1.3.jar

hamcrest-core-1.3.jar -> java.base
junit-4.12.jar -> hamcrest-core-1.3.jar
junit-4.12.jar -> java.base
junit-4.12.jar -> java.management

jdeps --generate-module-info /tmp/junit junit-4.12.jar hamcrest-core-1.3.jar

jdeps -s -dotoutput /tmp/junit junit-4.12.jar hamcrest-core-1.3.jar
dot -Tpng /tmp/junit/summary.dot > /tmp/junit/summary.png

jlink --module-path com.horstmann.greet.jar:v2ch09.exportedpkg.jar:$JAVA_HOME/jmods \
--add-modules v2ch09.exportedpkg --output /tmp/hello

bin/java -m v2ch09.exportedpkg
```

```
StringBuilder.class.getClassLoader()

var url = new URL("file:///path/to/plugin.jar");
var pluginLoader = new URLClassLoader(new URL[] { url });
Class<?> cl = pluginLoader.loadClass("mypackage.MyClass");

Thread t = Thread.currentThread();
t.setContextClassLoader(loader);

Thread t = Thread.currentThread();
ClassLoader loader = t.getContextClassLoader();
Class<?> cl = loader.loadClass(className);

findClass(String className)
```

```
1 package classLoader;
2
3 import java.io.*;
4 import java.lang.reflect.*;
5 import java.nio.file.*;
6 import java.awt.*;
7 import java.awt.event.*;
8 import javax.swing.*;
9
10 /**
11  * This program demonstrates a custom class loader that decrypts class files.
12  * @version 1.25 2018-05-01
13  * @author Cay Horstmann
14  */
15 public class ClassLoaderTest
16 {
17     public static void main(String[] args)
18     {
19         EventQueue.invokeLater(() ->
20             {
21                 var frame = new ClassLoaderFrame();
22                 frame.setTitle("ClassLoaderTest");
23                 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
24                 frame.setVisible(true);
25             });
26     }
27 }
28
29 /**
30  * This frame contains two text fields for the name of the class to load and the
31  * decryption key.
32  */
33 class ClassLoaderFrame extends JFrame
34 {
35     private JTextField keyField = new JTextField("3", 4);
36     private JTextField nameField = new JTextField("Calculator", 30);
37     private static final int DEFAULT_WIDTH = 300;
38     private static final int DEFAULT_HEIGHT = 200;
39
40     public ClassLoaderFrame()
41     {
```

```
42     setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
43     setLayout(new GridBagLayout());
44     add(new JLabel("Class"), new GBC(0, 0).setAnchor(GBC.EAST));
45     add(nameField, new GBC(1, 0).setWeight(100, 0).setAnchor(GBC.WEST));
46     add(new JLabel("Key"), new GBC(0, 1).setAnchor(GBC.EAST));
47     add(keyField, new GBC(1, 1).setWeight(100, 0).setAnchor(GBC.WEST));
48     var loadButton = new JButton("Load");
49     add(loadButton, new GBC(0, 2, 2, 1));
50     loadButton.addActionListener(
51         event -> runClass(nameField.getText(), keyField.getText()));
52     pack();
53 }
54
55 /**
56  * Runs the main method of a given class.
57  * @param name the class name
58  * @param key the decryption key for the class files
59  */
60 public void runClass(String name, String key)
61 {
62     try
63     {
64         var loader = new CryptoClassLoader(Integer.parseInt(key));
65         Class<?> c = loader.loadClass(name);
66         Method m = c.getMethod("main", String[].class);
67         m.invoke(null, (Object) new String[] {});
68     }
69     catch (Throwable t)
70     {
71         JOptionPane.showMessageDialog(this, t);
72     }
73 }
74 }
75
76 /**
77  * This class loader loads encrypted class files.
78  */
79 class CryptoClassLoader extends ClassLoader
80 {
81     private int key;
82
83     /**
84      * Constructs a crypto class loader.
85      * @param k the decryption key
86      */
87     public CryptoClassLoader(int k)
88     {
```

```
56     key = k;
57 }
58
59 protected Class<?> findClass(String name) throws ClassNotFoundException
60 {
61     try
62     {
63         byte[] classBytes = null;
64         classBytes = loadClassBytes(name);
65         Class<?> cl = defineClass(name, classBytes, 0, classBytes.length);
66         if (cl == null) throw new ClassNotFoundException(name);
67         return cl;
68     }
69     catch (IOException e)
70     {
71         throw new ClassNotFoundException(name);
72     }
73 }
74
75 /**
76 * Loads and decrypt the class file bytes.
77 * @param name the class name
78 * @return an array with the class file bytes
79 */
80 private byte[] loadClassBytes(String name) throws IOException
81 {
82     String cname = name.replace('.', '/') + ".caesar";
83     byte[] bytes = Files.readAllBytes(Path.of(cname));
84     for (int i = 0; i < bytes.length; i++)
85         bytes[i] = (byte) (bytes[i] - key);
86     return bytes;
87 }
88 }
```

```
1 package classLoader;
2
3 import java.io.*;
4
5 /**
6  * Encrypts a file using the Caesar cipher.
7  * @version 1.02 2018-05-01
8  * @author Cay Horstmann
9  */
10 public class Caesar
11 {
12     public static void main(String[] args) throws Exception
13     {
14         if (args.length != 3)
15         {
16             System.out.println("USAGE: java classLoader.Caesar in out key");
17             return;
18         }
19
20         try (var in = new FileInputStream(args[0]);
21              var out = new FileOutputStream(args[1]))
22         {
23             int key = Integer.parseInt(args[2]);
24             int ch;
25             while ((ch = in.read()) != -1)
26             {
27                 byte c = (byte) (ch + key);
28                 out.write(c);
29             }
30         }
31     }
32 }
```

```
javap -c verifier.VerifierTest
```

```
Exception in thread "main" java.lang.VerifyError: (class: VerifierTest, method:fun signature: ()I) Accessing value from uninitialized register 1
```

```
java -noverify verifier.VerifierTest
```

```
1 package verifier;
2
3 import java.awt.*;
4
5 /**
6  * This application demonstrates the bytecode verifier of the virtual machine. If you use a
7  * hex editor to modify the class file, then the virtual machine should detect the tampering.
8  * @version 1.10 2018-05-05
9  * @author Cay Horstmann
10 */
11 public class VerifierTest
12 {
13     public static void main(String[] args)
14     {
15         System.out.println("1 + 2 == " + fun());
16     }
17
18 /**
19  * A function that computes 1 + 2.
20  * @return 3, if the code has not been corrupted
21  */
22     public static int fun()
23     {
24         int m;
25         int n;
26         m = 1;
27         n = 2;
28         // use hex editor to change to "m = 2" in class file
29         int r = m + n;
30         return r;
31     }
32 }
```

```
try
{
    System.setSecurityManager(new SecurityManager());
    var context = new LoginContext("Login1"); // defined in JAAS configuration file
    context.login();
    // get the authenticated Subject
    Subject subject = context.getSubject();
    ...
    context.logout();
}
catch (LoginException e) // thrown if login was not successful
{
    exception.printStackTrace();
}
```

```
Login1
{
    com.sun.security.auth.module.UnixLoginModule required;
    com.whizzbang.auth.module.RetinaScanModule sufficient;
};
```

```
Login2
{
    ...
};
```

```
java -Djava.security.auth.login.config=auth/jaas.config auth.AuthTest
```

```
1 package auth;
2
3 import java.security.*;
4 import javax.security.auth.*;
5 import javax.security.auth.login.*;
6
7 /**
8  * This program obtains information about a user's Unix login
9  * @version 1.03 2021-11-29
10 * @author Cay Horstmann
11 */
12 public class AuthTest
13 {
```

```
14  public static void main(final String[] args)
15  {
16      try
17      {
18          var context = new LoginContext("Login1");
19          context.login();
20          System.out.println("Authentication successful.");
21          Subject subject = context.getSubject();
22          for (Principal p : subject.getPrincipals())
23          {
24              System.out.println(p.getClass().getName() + ":" + p.getName());
25          }
26          context.logout();
27      }
28      catch (LoginException e)
29      {
30          System.out.println("Authentication failed.");
31          e.printStackTrace();
32      }
33  }
34 }

1 Login1
2 {
3     com.sun.security.auth.module.UnixLoginModule required;
4 };

Set<Principal> principals = subject.getPrincipals();
principals.add(new SimplePrincipal("username", username));
principals.add(new SimplePrincipal("role", role));

SimpleLoginModule required pwfile="jaas/password.txt";

var context = new LoginContext("Login1",
    new com.sun.security.auth.callback.DialogCallbackHandler());
```

```
public void handle(Callback[] callbacks)
{
    for (Callback callback : callbacks)
    {
        if (callback instanceof NameCallback) . . .
        else if (callback instanceof PasswordCallback) . . .
        else . . .
    }
}

var nameCall = new NameCallback("username: ");
var passCall = new PasswordCallback("password: ", false);
callbackHandler.handle(new Callback[] { nameCall, passCall });

java -Djava.security.auth.login.config=jaas/jaas.config jaas.JAATest
```

```
1 package jaas;
2
3 import java.security.*;
4 import java.util.*;
5
6 /**
7  * A principal with a named value (such as "role=HR" or "username=harry").
8 */
9 public class SimplePrincipal implements Principal
10 {
11     private String descr;
12     private String value;
13
14     /**
15      * Constructs a SimplePrincipal to hold a description and a value.
16      * @param descr the description
17      * @param value the associated value
18      */
19     public SimplePrincipal(String descr, String value)
20     {
21         this.descr = descr;
22         this.value = value;
23     }
```

```
24
25     public SimplePrincipal(String descrAndValue)
26     {
27         String[] dv = descrAndValue.split("=");
28         this.descr = dv[0];
29         this.value = dv[1];
30     }
31
32     /**
33      * @return the description and value of this simple principal.
34      */
35     public String getName()
36     {
37         return descr + "=" + value;
38     }
39
40     public boolean equals(Object otherObject)
41     {
42         if (this == otherObject) return true;
43         if (otherObject == null) return false;
44         if (getClass() != otherObject.getClass()) return false;
45         var other = (SimplePrincipal) otherObject;
46         return Objects.equals(getName(), other.getName());
47     }
48
49     public int hashCode()
50     {
51         return Objects.hashCode(getName());
52     }
53 }
```

```
1 package jaas;
2
3 import java.io.*;
4 import java.nio.charset.*;
5 import java.nio.file.*;
6 import java.security.*;
7 import java.util.*;
8 import javax.security.auth.*;
9 import javax.security.auth.callback.*;
10 import javax.security.auth.login.*;
11 import javax.security.auth.spi.*;
12
13 /**
14  * This login module authenticates users by reading usernames, passwords, and roles from
15  * a text file.
16  */
17 public class SimpleLoginModule implements LoginModule
18 {
19     private Subject subject;
20     private CallbackHandler callbackHandler;
21     private Map<String, ?> options;
22
23     public void initialize(Subject subject, CallbackHandler callbackHandler,
24                           Map<String, ?> sharedState, Map<String, ?> options)
25     {
26         this.subject = subject;
27         this.callbackHandler = callbackHandler;
28         this.options = options;
29     }
30
31     public boolean login() throws LoginException
32     {
33         if (callbackHandler == null) throw new LoginException("no handler");
34
35         var nameCall = new NameCallback("username: ");
36         var passCall = new PasswordCallback("password: ", false);
37         try
38         {
39             callbackHandler.handle(new Callback[] { nameCall, passCall });
40         }
41         catch (UnsupportedCallbackException e)
42         {
43             var e2 = new LoginException("Unsupported callback");
44             e2.initCause(e);
45             throw e2;
46         }
47     }
48 }
```

```
47     catch (IOException e)
48     {
49         var e2 = new LoginException("I/O exception in callback");
50         e2.initCause(e);
51         throw e2;
52     }
53
54     try
55     {
56         return checkLogin(nameCall.getName(), passCall.getPassword());
57     }
58     catch (IOException e)
59     {
60         var e2 = new LoginException();
61         e2.initCause(e);
62         throw e2;
63     }
64 }
65
66 /**
67 * Checks whether the authentication information is valid. If it is, the subject acquires
68 * principals for the user name and role.
69 * @param username the user name
70 * @param password a character array containing the password
71 * @return true if the authentication information is valid
72 */
73 private boolean checkLogin(String username, char[] password)
74     throws LoginException, IOException
75 {
76     try (var in = new Scanner(
77         Path.of("") + options.get("pwfile"), StandardCharsets.UTF_8))
78     {
79         while (in.hasNextLine())
80         {
81             String[] inputs = in.nextLine().split("\\|");
82             if (inputs[0].equals(username)
83                 && Arrays.equals(inputs[1].toCharArray(), password))
84             {
85                 String role = inputs[2];
86                 Set<Principal> principals = subject.getPrincipals();
87                 principals.add(new SimplePrincipal("username", username));
88                 principals.add(new SimplePrincipal("role", role));
89                 return true;
90             }
91         }
92         return false;
93     }
94 }
```

```
95
96     public boolean logout()
97     {
98         return true;
99     }
100
101    public boolean abort()
102    {
103        return true;
104    }
105
106    public boolean commit()
107    {
108        return true;
109    }
110 }
```

```
1 package jaas;
2
3 import javax.security.auth.callback.*;
4
5 /**
6  * This simple callback handler presents the given user name and password.
7  */
8 public class SimpleCallbackHandler implements CallbackHandler
9 {
10     private String username;
11     private char[] password;
12
13     /**
14      * Constructs the callback handler.
15      * @param username the user name
16      * @param password a character array containing the password
17      */
18     public SimpleCallbackHandler(String username, char[] password)
19     {
20         this.username = username;
21         this.password = password;
22     }
23
24     public void handle(Callback[] callbacks)
25     {
26         for (Callback callback : callbacks)
27         {
28             if (callback instanceof NameCallback c)
29             {
30                 c.setName(username);
31             }
32             else if (callback instanceof PasswordCallback c)
33             {
34                 c.setPassword(password);
35             }
36         }
37     }
38 }
```

```
1 package jaas;
2
3 import java.awt.*;
4 import javax.swing.*;
5
6 /**
7  * This program authenticates a user via a custom login
8  * @version 1.04 2021-05-30
9  * @author Cay Horstmann
10 */
11 public class JAASTest
12 {
13     public static void main(final String[] args)
14     {
15         EventQueue.invokeLater(() ->
16         {
17             var frame = new JAASFrame();
18             frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
19             frame.setTitle("JAASTest");
20             frame.setVisible(true);
21         });
22     }
23 }

1 Login1
2 {
3     jaas.SimpleLoginModule required pwfile="jaas/password.txt" debug=true;
4 };

12 5F 09 03 E7 31 30 19 2E A6 E7 E4 90 43 84 B4 38 99 8F 67
7D F6 AB 08 EB 40 EC CD AB 74 ED E9 86 F9 ED 99 D1 45 B1 57
```

```
MessageDigest alg = MessageDigest.getInstance("SHA-1");
```

```
InputStream in = . . .;
int ch;
while ((ch = in.read()) != -1)
    alg.update((byte) ch);
```

```
java hash.Digest hash/input.txt SHA-1
```

```
1 package hash;
2
3 import java.io.*;
4 import java.nio.file.*;
5 import java.security.*;
6 import java.util.*;
7
8 /**
9  * This program computes the message digest of a file.
10 * @version 1.21 2018-04-10
11 * @author Cay Horstmann
12 */
13 public class Digest
14 {
15     /**
16      * @param args args[0] is the filename, args[1] is optionally the algorithm
17      * (SHA-1, SHA-256, or MD5)
18      */
19     public static void main(String[] args) throws IOException, GeneralSecurityException
20     {
21         var in = new Scanner(System.in);
22         String filename;
23         if (args.length >= 1)
24             filename = args[0];
25         else
26         {
27             System.out.print("File name: ");
28             filename = in.nextLine();
29         }
30         String algname;
31         if (args.length >= 2)
32             algname = args[1];
```

```
33     else
34     {
35         System.out.println("Select one of the following algorithms: ");
36         for (Provider p : Security.getProviders())
37             for (Provider.Service s : p.getServices())
38                 if (s.getType().equals("MessageDigest"))
39                     System.out.println(s.getAlgorithm());
40         System.out.print("Algorithm: ");
41         alname = in.nextLine();
42     }
43     MessageDigest alg = MessageDigest.getInstance(alname);
44     byte[] input = Files.readAllBytes(Path.of(filename));
45     byte[] hash = alg.digest(input);
46     for (int i = 0; i < hash.length; i++)
47         System.out.printf("%02X ", hash[i] & 0xFF);
48     System.out.println();
49 }
50 }
```

p: fca682ce8e12cab26efccf7110e526db078b05edecbcd1eb4a208f3ae1617ae01f35b91a47e6df63413c5e12
ed0899bcd132acd50d99151bdc43ee737592e17

q: 962eddcc369cba8ebb260ee6b6a126d9346e38c5

g: 678471b27a9cf44ee91a49c5147db1a9aaf244f05a434d6486931d2d14271b9e35030b71fd73da179069b32e2
935630e1c2062354d0da20a6c416e50be794ca4

y: c0b6e67b4ac098eb1a32c5f8c4clf0e7e6fb9d832532e27d0bdab9ca2d2a8123ce5a8018b8161a760480fadd0
40b927281ddb22cb9bc4df596d7de4d1b977d50

p: fca682ce8e12cab26efccf7110e526db078b05edecbcd1eb4a208f3ae1617ae01f35b91a47e6df63413c5e12
ed0899bcd132acd50d99151bdc43ee737592e17

q: 962eddcc369cba8ebb260ee6b6a126d9346e38c5

g: 678471b27a9cf44ee91a49c5147db1a9aaf244f05a434d6486931d2d14271b9e35030b71fd73da179069b32e2
935630e1c2062354d0da20a6c416e50be794ca4

x: 146c09f881656cc6c51f27ea6c3a91b85ed1d70a

keytool -genkeypair -keystore alice.certs -alias alice

```
Enter keystore password: secret
Reenter new password: secret
What is your first and last name?
[Unknown]: Alice Lee
What is the name of your organizational unit?
[Unknown]: Engineering
What is the name of your organization?
[Unknown]: ACME Software
What is the name of your City or Locality?

[Unknown]: San Francisco
What is the name of your State or Province?
[Unknown]: CA
What is the two-letter country code for this unit?
[Unknown]: US
Is <CN=Alice Lee, OU=Engineering, O=ACME Software, L=San Francisco, ST=CA, C=US> correct?
[no]: yes
```

```
keytool -exportcert -keystore alice.certs -alias alice -file alice.cer
```

```
keytool -printcert -file alice.cer
```

```
Owner: CN=Alice Lee, OU=Engineering, O=ACME Software, L=San Francisco, ST=CA, C=US
Issuer: CN=Alice Lee, OU=Engineering, O=ACME Software, L=San Francisco, ST=CA, C=US
Serial number: 470835ce
Valid from: Sat Oct 06 18:26:38 PDT 2007 until: Fri Jan 04 17:26:38 PST 2008
Certificate fingerprints:
    MD5: BC:18:15:27:85:69:48:B1:5A:C3:0B:1C:C6:11:B7:81
    SHA1: 31:0A:A0:B8:C2:8B:3B:B6:85:7C:EF:C0:57:E5:94:95:61:47:6D:34
    Signature algorithm name: SHA1withDSA
    Version: 3
```

```
keytool -list -v -keystore jre/lib/security/cacerts
```

Owner: CN=DigiCert Assured ID Root G3, OU=www.digicert.com, O=DigiCert Inc, C=US
Issuer: CN=DigiCert Assured ID Root G3, OU=www.digicert.com, O=DigiCert Inc, C=US
Serial number: ba15afalddfa0b54944afcd24a06cec
Valid from: Thu Aug 01 14:00:00 CEST 2013 until: Fri Jan 15 13:00:00 CET 2038
Certificate fingerprints:
SHA1: F5:17:A2:4F:9A:48:C6:C9:F8:A2:00:26:9F:DC:0F:48:2C:AB:30:89
SHA256: 7E:37:CB:8B:4C:47:09:0C:AB:36:55:1B:A6:F4:5D:B8:40:68:0F:BA:
16:6A:95:2D:B1:00:71:7F:43:05:3F:C2

```
keytool -importcert -keystore bob.certs -alias alice -file alice.cer

jar cvf document.jar document.txt

jarsigner -keystore alice.certs document.jar alice

jarsigner -verify -keystore bob.certs document.jar

keytool -genkeypair -keystore acmesoft.certs -alias acmeroot
keytool -exportcert -keystore acmesoft.certs -alias acmeroot -file acmeroot.cer

keytool -importcert -keystore cindy.certs -alias acmeroot -file acmeroot.cer

java CertificateSigner -keystore acmesoft.certs -alias acmeroot \
    -infile alice.cer -outfile alice_signedby_acmeroot.cer

keytool -importcert -keystore cindy.certs -alias alice -file alice_signedby_acmeroot.cer

/usr/lib/ssl/misc/CA.pl -newca

keytool -importcert -keystore cindy.certs -alias acmeroot -file acmeroot.pem

keytool -certreq -keystore alice.store -alias alice -file alice.pem

openssl ca -in alice.pem -out alice_signedby_acmeroot.pem

keytool -importcert -keystore cindy.certs -alias alice -file alice_signedby_acmeroot.pem

Cipher cipher = Cipher.getInstance(algorithmName);

Cipher cipher = Cipher.getInstance(algorithmName, providerName);
```

```
int blockSize = cipher.getBlockSize();
var inBytes = new byte[blockSize];
. . . // read inBytes
int outputSize= cipher.getOutputSize(blockSize);
var outBytes = new byte[outputSize];
int outLength = cipher.update(inBytes, 0, outputSize, outBytes);
. . . // write outBytes

outBytes = cipher.doFinal(inBytes, 0, inLength);

outBytes = cipher.doFinal();

L 01                      if length(L) = 7
L 02 02                    if length(L) = 6
L 03 03 03                  if length(L) = 5
. .
L 07 07 07 07 07 07 07    if length(L) = 1

KeyGenerator keygen = KeyGenerator.getInstance("AES");
var random = new SecureRandom(); // see below
keygen.init(random);
Key key = keygen.generateKey();

byte[] keyData = . . .; // 16 bytes for AES
var key = new SecretKeySpec(keyData, "AES");

var random = new SecureRandom();
var b = new byte[20];
// fill with truly random bits
random.setSeed(b);

java aes.AESTest -genkey secret.key

java aes.AESTest -encrypt plaintextFile encryptedFile secret.key

java aes.AESTest -decrypt encryptedFile decryptedFile secret.key
```

```
1 package aes;
2
3 import java.io.*;
4 import java.security.*;
5 import javax.crypto.*;
6
7 /**
8  * This program tests the AES cipher. Usage:<br>
9  * java aes.AESTest -genkey keyfile<br>
10 * java aes.AESTest -encrypt plaintext encrypted keyfile<br>
11 * java aes.AESTest -decrypt encrypted decrypted keyfile<br>
12 * @author Cay Horstmann
13 * @version 1.02 2018-05-01
14 */
15 public class AESTest
16 {
17     public static void main(String[] args)
18         throws IOException, GeneralSecurityException, ClassNotFoundException
19     {
20         if (args[0].equals("-genkey"))
21         {
22             KeyGenerator keygen = KeyGenerator.getInstance("AES");

```

```
23     var random = new SecureRandom();
24     keygen.init(random);
25     SecretKey key = keygen.generateKey();
26     try (var out = new ObjectOutputStream(new FileOutputStream(args[1])))
27     {
28         out.writeObject(key);
29     }
30 }
31 else
32 {
33     int mode;
34     if (args[0].equals("-encrypt")) mode = Cipher.ENCRYPT_MODE;
35     else mode = Cipher.DECRYPT_MODE;
36
37     try (var keyIn = new ObjectInputStream(new FileInputStream(args[3]));
38          var in = new FileInputStream(args[1]);
39          var out = new FileOutputStream(args[2]))
40     {
41         var key = (Key) keyIn.readObject();
42         Cipher cipher = Cipher.getInstance("AES");
43         cipher.init(mode, key);
44         Util.crypt(in, out, cipher);
45     }
46 }
47 }
48 }
```

```
1 package aes;
2
3 import java.io.*;
4 import java.security.*;
5 import javax.crypto.*;
6
7 public class Util
8 {
9     /**
10      * Uses a cipher to transform the bytes in an input stream and sends the transformed bytes
11      * to an output stream.
12      * @param in the input stream
13      * @param out the output stream
14      * @param cipher the cipher that transforms the bytes
15      */
16     public static void crypt(InputStream in, OutputStream out, Cipher cipher)
17         throws IOException, GeneralSecurityException
18     {
19
20         int blockSize = cipher.getBlockSize();
21         int outputSize = cipher.getOutputSize(blockSize);
22         var inBytes = new byte[blockSize];
23         var outBytes = new byte[outputSize];
24
25         int inLength = 0;
26         boolean done = false;
27         while (!done)
28         {
29             inLength = in.read(inBytes);
30             if (inLength == blockSize)
31             {
32                 int outLength = cipher.update(inBytes, 0, blockSize, outBytes);
33                 out.write(outBytes, 0, outLength);
34             }
35             else done = true;
36         }
37         if (inLength > 0) outBytes = cipher.doFinal(inBytes, 0, inLength);
38         else outBytes = cipher.doFinal();
39         out.write(outBytes);
40     }
41 }
```

```
Cipher cipher = . . .;
cipher.init(Cipher.ENCRYPT_MODE, key);
var out = new CipherOutputStream(new FileOutputStream(outputFileName), cipher);

var bytes = new byte[BLOCKSIZE];
int inLength = getData(bytes); // get data from data source
while (inLength != -1)
{
    out.write(bytes, 0, inLength);
    inLength = getData(bytes); // get more data from data source
}
out.flush();

Cipher cipher = . . .;
cipher.init(Cipher.DECRYPT_MODE, key);
var in = new CipherInputStream(new FileInputStream(inputFileName), cipher);
var bytes = new byte[BLOCKSIZE];
int inLength = in.read(bytes);
while (inLength != -1)
{
    putData(bytes, inLength); // put data to destination
    inLength = in.read(bytes);
}

KeyPairGenerator pairgen = KeyPairGenerator.getInstance("RSA");
var random = new SecureRandom();
pairgen.initialize(KEYSIZE, random);
KeyPair keyPair = pairgen.generateKeyPair();

Key publicKey = keyPair.getPublic();
Key privateKey = keyPair.getPrivate();

Key key = . . .; // an AES key
Key publicKey = . . .; // a public RSA key
Cipher cipher = Cipher.getInstance("RSA");
cipher.init(Cipher.WRAP_MODE, publicKey);
byte[] wrappedKey = cipher.wrap(key);

java rsa.RSATest -genkey public.key private.key
```

```
java rsa.RSATest -encrypt plaintextFile encryptedFile public.key
```

```
java rsa.RSATest -decrypt encryptedFile decryptedFile private.key
```

```
1 package rsa;  
2  
3 import java.io.*;  
4 import java.security.*;  
5 import javax.crypto.*;  
6  
7 /**  
8  * This program tests the RSA cipher. Usage:<br>  
9  * java rsa.RSATest -genkey public private<br>  
10 * java rsa.RSATest -encrypt plaintext encrypted public<br>  
11 * java rsa.RSATest -decrypt encrypted decrypted private<br>  
12 * @author Cay Horstmann  
13 * @version 1.02 2018-05-01  
14 */
```

```
15 public class RSATest
16 {
17     private static final int KEYSIZE = 512;
18
19     public static void main(String[] args)
20         throws IOException, GeneralSecurityException, ClassNotFoundException
21     {
22         if (args[0].equals("-genkey"))
23         {
24             KeyPairGenerator pairgen = KeyPairGenerator.getInstance("RSA");
25             var random = new SecureRandom();
26             pairgen.initialize(KEYSIZE, random);
27             KeyPair keyPair = pairgen.generateKeyPair();
28             try (var out = new ObjectOutputStream(new FileOutputStream(args[1])))
29             {
30                 out.writeObject(keyPair.getPublic());
31             }
32             try (var out = new ObjectOutputStream(new FileOutputStream(args[2])))
33             {
34                 out.writeObject(keyPair.getPrivate());
35             }
36         }
37         else if (args[0].equals("-encrypt"))
38         {
39             KeyGenerator keygen = KeyGenerator.getInstance("AES");
40             var random = new SecureRandom();
41             keygen.init(random);
42             SecretKey key = keygen.generateKey();
43
44             // wrap with RSA public key
45             try (var keyIn = new ObjectInputStream(new FileInputStream(args[3]));
46                  var out = new DataOutputStream(new FileOutputStream(args[2]));
47                  var in = new FileInputStream(args[1]))
48             {
49                 var publicKey = (Key) keyIn.readObject();
50                 Cipher cipher = Cipher.getInstance("RSA");
51                 cipher.init(Cipher.WRAP_MODE, publicKey);
52                 byte[] wrappedKey = cipher.wrap(key);
53                 out.writeInt(wrappedKey.length);
54                 out.write(wrappedKey);
55
56                 cipher = Cipher.getInstance("AES");
57                 cipher.init(Cipher.ENCRYPT_MODE, key);
58                 Util.crypt(in, out, cipher);
59             }
60         }
61     }
62 }
```

```
63     try (var in = new DataInputStream(new FileInputStream(args[1])));
64         var keyIn = new ObjectInputStream(new FileInputStream(args[3])));
65         var out = new FileOutputStream(args[2]))
66     {
67         int length = in.readInt();
68         var wrappedKey = new byte[length];
69         in.read(wrappedKey, 0, length);
70
71         // unwrap with RSA private key
72         var privateKey = (Key) keyIn.readObject();
73
74         Cipher cipher = Cipher.getInstance("RSA");
75         cipher.init(Cipher.UNWRAP_MODE, privateKey);
76         Key key = cipher.unwrap(wrappedKey, "AES", Cipher.SECRET_KEY);
77
78         cipher = Cipher.getInstance("AES");
79         cipher.init(Cipher.DECRYPT_MODE, key);
80
81         Util.crypt(in, out, cipher);
82     }
83 }
84 }
85 }
```

```
Object[][] cells =
{
    { "Mercury", 2440.0, 0, false, Color.YELLOW },
    { "Venus", 6052.0, 0, false, Color.YELLOW },
    ...
}

String[] columnNames = { "Planet", "Radius", "Moons", "Gaseous", "Color" };

var table = new JTable(cells, columnNames);

var pane = new JScrollPane(table);

table.setAutoCreateRowSorter(true);

add(table.getTableHeader(), BorderLayout.NORTH);

1 package table;
2
3 import java.awt.*;
4 import java.awt.print.*;
5
6 import javax.swing.*;
7
8 /**
9  * This program demonstrates how to show a simple table.
10 * @version 1.14 2018-05-01
11 * @author Cay Horstmann
12 */
```

```
13 public class TableTest
14 {
15     public static void main(String[] args)
16     {
17         EventQueue.invokeLater(() ->
18         {
19             var frame = new PlanetTableFrame();
20             frame.setTitle("TableTest");
21             frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
22             frame.setVisible(true);
23         });
24     }
25 }
26
27 /**
28  * This frame contains a table of planet data.
29 */
30 class PlanetTableFrame extends JFrame
31 {
32     private String[] columnNames = { "Planet", "Radius", "Moons", "Gaseous", "Color" };
33     private Object[][][] cells =
34     {
35         { "Mercury", 2440.0, 0, false, Color.YELLOW },
36         { "Venus", 6052.0, 0, false, Color.YELLOW },
37         { "Earth", 6378.0, 1, false, Color.BLUE },
38         { "Mars", 3397.0, 2, false, Color.RED },
39         { "Jupiter", 71492.0, 16, true, Color.ORANGE },
40         { "Saturn", 60268.0, 18, true, Color.ORANGE },
41         { "Uranus", 25559.0, 17, true, Color.BLUE },
42         { "Neptune", 24766.0, 8, true, Color.BLUE },
43         { "Pluto", 1137.0, 1, false, Color.BLACK }
44     };
45
46     public PlanetTableFrame()
47     {
48         var table = new JTable(cells, columnNames);
49         table.setAutoCreateRowSorter(true);
50         add(new JScrollPane(table), BorderLayout.CENTER);
51         var printButton = new JButton("Print");
52         printButton.addActionListener(event ->
53         {
54             try { table.print(); }
55             catch (SecurityException | PrinterException e) { e.printStackTrace(); }
56         });
57         var buttonPanel = new JPanel();
58         buttonPanel.add(printButton);
59         add(buttonPanel, BorderLayout.SOUTH);
60         pack();
61     }
62 }
```

```
public int getRowCount();
public int getColumnCount();
public Object getValueAt(int row, int column);

public Object getValueAt(int r, int c)
{
    try
    {
        rowSet.absolute(r + 1);
        return rowSet.getObject(c + 1);
    }

    catch (SQLException e)
    {
        e.printStackTrace();
        return null;
    }
}

public Object getValueAt(int r, int c)
{
    double rate = (c + minRate) / 100.0;
    int nperiods = r;
    double futureBalance = INITIAL_BALANCE * Math.pow(1 + rate, nperiods);
    return "%." + 2 + "f".formatted(futureBalance);
}

public int getRowCount() { return years; }
public int getColumnCount() { return maxRate - minRate + 1; }

public String getColumnName(int c) { return (c + minRate) + "%"; }
```

```
1 package tableModel;
2
3 import java.awt.*;
4
5 import javax.swing.*;
6 import javax.swing.table.*;
7
8 /**
9  * This program shows how to build a table from a table model.
10 * @version 1.05 2021-09-09
11 * @author Cay Horstmann
12 */
13 public class InvestmentTable
14 {
15     public static void main(String[] args)
16     {
17         EventQueue.invokeLater(() ->
18         {
19             var frame = new InvestmentTableFrame();
20             frame.setTitle("InvestmentTable");
21             frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
22             frame.setVisible(true);
23         });
24     }
25 }
26
27 /**
28 * This frame contains the investment table.
29 */
30 class InvestmentTableFrame extends JFrame
31 {
32     public InvestmentTableFrame()
33     {
34         var model = new InvestmentTableModel(30, 5, 10);
35         var table = new JTable(model);
36         add(new JScrollPane(table));
37         pack();
38     }
39 }
40
```

```
41 /**
42  * This table model computes the cell entries each time they are requested. The table contents
43  * shows the growth of an investment for a number of years under different interest rates.
44 */
45 class InvestmentTableModel extends AbstractTableModel
46 {
47     private static double INITIAL_BALANCE = 100000.0;
48
49     private int years;
50     private int minRate;
51     private int maxRate;
52
53     /**
54      * Constructs an investment table model.
55      * @param y the number of years
56      * @param r1 the lowest interest rate to tabulate
57      * @param r2 the highest interest rate to tabulate
58      */
59     public InvestmentTableModel(int y, int r1, int r2)
60     {
61         years = y;
62         minRate = r1;
63         maxRate = r2;
64     }
65
66     public int getRowCount()
67     {
68         return years;
69     }
70
71     public int getColumnCount()
72     {
73         return maxRate - minRate + 1;
74     }
75
76     public Object getValueAt(int r, int c)
77     {
78         double rate = (c + minRate) / 100.0;
79         int nperiods = r;
80         double futureBalance = INITIAL_BALANCE * Math.pow(1 + rate, nperiods);
81         return "%.2f".formatted(futureBalance);
82     }
83
84     public String getColumnName(int c)
85     {
86         return (c + minRate) + "%";
87     }
88 }
```

```
Class<?> getColumnClass(int columnIndex)

int columnIndex = . . .;
TableColumn column = table.getColumnModel().getColumn(columnIndex);

void setPreferredWidth(int width)
void setMinWidth(int width)
void setMaxWidth(int width)

void setResizable(boolean resizable)

void setAutoResizeMode(int mode)

table.setRowHeight(height);

table.setRowHeight(row, height);

table.setRowSelectionAllowed(false);

table.getSelectionModel().setSelectionMode(mode);

ListSelectionModel.SINGLE_SELECTION
ListSelectionModel.SINGLE_INTERVAL_SELECTION
ListSelectionModel.MULTIPLE_INTERVAL_SELECTION

table.setColumnSelectionAllowed(true);

table.setCellSelectionEnabled(true);
```

```
1 package TableRowColumn;
2
3 import java.awt.*;
4 import java.util.*;
5
6 import javax.swing.*;
7 import javax.swing.table.*;
8
9 /**
10  * This frame contains a table of planet data.
11  */
12 public class PlanetTableFrame extends JFrame
13 {
14     private static final int DEFAULT_WIDTH = 600;
15     private static final int DEFAULT_HEIGHT = 500;
16
17     public static final int COLOR_COLUMN = 4;
18     public static final int IMAGE_COLUMN = 5;
19
20     private JTable table;
21     private HashSet<Integer> removedRowIndices;
22     private ArrayList<TableColumn> removedColumns;
23     private JCheckBoxMenuItem rowsItem;
24     private JCheckBoxMenuItem columnsItem;
25     private JCheckBoxMenuItem cellsItem;
26
27     private String[] columnNames = { "Planet", "Radius", "Moons", "Gaseous", "Color", "Image" };
28
29     private Object[][][] cells =
30     {
31         { "Mercury", 2440.0, 0, false, Color.YELLOW,
32             new ImageIcon(getClass().getResource("Mercury.gif")) },
33         { "Venus", 6052.0, 0, false, Color.YELLOW,
34             new ImageIcon(getClass().getResource("Venus.gif")) },
35         { "Earth", 6378.0, 1, false, Color.BLUE,
36             new ImageIcon(getClass().getResource("Earth.gif")) },
37         { "Mars", 3397.0, 2, false, Color.RED,
38             new ImageIcon(getClass().getResource("Mars.gif")) },
39         { "Jupiter", 71492.0, 16, true, Color.ORANGE,
40             new ImageIcon(getClass().getResource("Jupiter.gif")) },
41         { "Saturn", 60268.0, 18, true, Color.ORANGE,
42             new ImageIcon(getClass().getResource("Saturn.gif")) },
43     }
44 }
```

```
43         { "Uranus", 25559.0, 17, true, Color.BLUE,
44             new ImageIcon(getClass().getResource("Uranus.gif")) },
45         { "Neptune", 24766.0, 8, true, Color.BLUE,
46             new ImageIcon(getClass().getResource("Neptune.gif")) },
47         { "Pluto", 1137.0, 1, false, Color.BLACK,
48             new ImageIcon(getClass().getResource("Pluto.gif")) }
49     };
50
51     public PlanetTableFrame()
52     {
53         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
54
55         var model = new DefaultTableModel(cells, columnNames)
56         {
57             public Class<?> getColumnClass(int c)
58             {
59                 return cells[0][c].getClass();
60             }
61         };
62
63         table = new JTable(model);
64
65         table.setRowHeight(100);
66         table.getColumnModel().getColumn(COLOR_COLUMN).setMinWidth(250);
67         table.getColumnModel().getColumn(IMAGE_COLUMN).setMinWidth(100);
68
69         var sorter = new TableRowSorter<TableModel>(model);
70         table.setRowSorter(sorter);
71         sorter.setComparator(COLOR_COLUMN, Comparator.comparing(Color::getBlue)
72             .thenComparing(Color::getGreen).thenComparing(Color::getRed));
73         sorter.setSortable(IMAGE_COLUMN, false);
74         add(new JScrollPane(table), BorderLayout.CENTER);
75
76         removedRowIndices = new HashSet<>();
77         removedColumns = new ArrayList<>();
78
79         var filter = new RowFilter<TableModel, Integer>()
80         {
81             public boolean include(Entry<? extends TableModel, ? extends Integer> entry)
82             {
83                 return !removedRowIndices.contains(entry.getIdentifier());
84             }
85         };
86
87         // create menu
88
89         var menuBar = new JMenuBar();
```

```
90     setJMenuBar(menuBar);
91
92     var selectionMenu = new JMenu("Selection");
93     menuBar.add(selectionMenu);
94
95     rowsItem = new JCheckBoxMenuItem("Rows");
96     columnsItem = new JCheckBoxMenuItem("Columns");
97     cellsItem = new JCheckBoxMenuItem("Cells");
98
99     rowsItem.setSelected(table.getRowSelectionAllowed());
100    columnsItem.setSelected(table.getColumnSelectionAllowed());
101    cellsItem.setSelected(table.getCellSelectionEnabled());
102
103    rowsItem.addActionListener(event ->
104    {
105        table.clearSelection();
106        table.setRowSelectionAllowed(rowsItem.isSelected());
107        updateCheckboxMenuItems();
108    });
109    selectionMenu.add(rowsItem);
110
111    columnsItem.addActionListener(event ->
112    {
113        table.clearSelection();
114        table.setColumnSelectionAllowed(columnsItem.isSelected());
115        updateCheckboxMenuItems();
116    });
117    selectionMenu.add(columnsItem);
118
119    cellsItem.addActionListener(event ->
120    {
121        table.clearSelection();
122        table.setCellSelectionEnabled(cellsItem.isSelected());
123        updateCheckboxMenuItems();
124    });
125    selectionMenu.add(cellsItem);
126
127    var tableMenu = new JMenu("Edit");
128    menuBar.add(tableMenu);
129
130    var hideColumnsItem = new JMenuItem("Hide Columns");
131    hideColumnsItem.addActionListener(event ->
132    {
133        int[] selected = table.getSelectedColumns();
134        TableColumnModel columnModel = table.getColumnModel();
135
136        // remove columns from view, starting at the last
137        // index so that column numbers aren't affected
138    });

```

```
139         for (int i = selected.length - 1; i >= 0; i--)
140     {
141         TableColumn column = columnModel.getColumn(selected[i]);
142         table.removeColumn(column);
143
144         // store removed columns for "show columns" command
145
146         removedColumns.add(column);
147     }
148 });
149 tableMenu.add(hideColumnsItem);
150
151 var showColumnsItem = new JMenuItem("Show Columns");
152 showColumnsItem.addActionListener(event ->
153 {
154     // restore all removed columns
155     for (TableColumn tc : removedColumns)
156         table.addColumn(tc);
157     removedColumns.clear();
158 });
159 tableMenu.add(showColumnsItem);
160
161 var hideRowsItem = new JMenuItem("Hide Rows");
162 hideRowsItem.addActionListener(event ->
163 {
164     int[] selected = table.getSelectedRows();
165     for (int i : selected)
166         removedRowIndices.add(table.convertRowIndexToModel(i));
167     sorter.setRowFilter(filter);
168 });
169 tableMenu.add(hideRowsItem);
170
171 var showRowsItem = new JMenuItem("Show Rows");
172 showRowsItem.addActionListener(event ->
173 {
174     removedRowIndices.clear();
175     sorter.setRowFilter(filter);
176 });
177 tableMenu.add(showRowsItem);
178
179 var printSelectionItem = new JMenuItem("Print Selection");
180 printSelectionItem.addActionListener(event ->
181 {
182     int[] selected = table.getSelectedRows();
183     System.out.println("Selected rows: " + Arrays.toString(selected));
184     selected = table.getSelectedColumns();
185     System.out.println("Selected columns: " + Arrays.toString(selected));
186 });

```

```
187     tableMenu.add(printSelectionItem);
188 }
189
190 private void updateCheckboxMenuItems()
191 {
192     rowsItem.setSelected(table.getRowSelectionAllowed());
193     columnsItem.setSelected(table.getColumnSelectionAllowed());
194     cellsItem.setSelected(table.getCellSelectionEnabled());
195 }
196 }

var sorter = new TableRowSorter<TableModel>(model);
table.setRowSorter(sorter);

sorter.setSortable(IMAGE_COLUMN, false);

sorter.setComparator(COLOR_COLUMN, new Comparator<Color>()
{
    public int compare(Color c1, Color c2)
    {
        int d = c1.getBlue() - c2.getBlue();
        if (d != 0) return d;
        d = c1.getGreen() - c2.getGreen();
        if (d != 0) return d;
        return c1.getRed() - c2.getRed();
    }
});

sorter.setStringConverter(new TableStringConverter()
{
    public String toString(TableModel model, int row, int column)
    {
        Object value = model.getValueAt(row, column);
        convert value to a string and return it
    }
});

sorter.setRowFilter(RowFilter.numberFilter(ComparisonType.NOT_EQUAL, 0, MOONS_COLUMN));

sorter.setRowFilter(RowFilter.regexFilter(".*[^\s]$". PLANET_COLUMN));
```

```
sorter.setRowFilter(RowFilter.andFilter(List.of(
    RowFilter.regexFilter(".*[^s]$". PLANET_COLUMN),
    RowFilter.numberFilter(ComparisonType.NOT_EQUAL, 0, MOONS_COLUMN))));

public boolean include(RowFilter.Entry<? extends M, ? extends I> entry)

var filter = new RowFilter<TableModel, Integer>()
{
    public boolean include(Entry<? extends TableModel, ? extends Integer> entry)
    {
        return entry.getIdentifier() % 2 == 0;

    }
};

((Integer) entry.getValue(MOONS_COLUMN)) % 2 == 0

TableColumnModel columnModel = table.getColumnModel();
TableColumn column = columnModel.getColumn(i);
table.removeColumn(column);

table.addColumn(column);

table.addColumn(new TableColumn(modelColumnIndex));

Component getTableCellRendererComponent(JTable table, Object value,
    boolean isSelected, boolean hasFocus, int row, int column)

class ColorTableCellRenderer extends JPanel implements TableCellRenderer
{
    public Component getTableCellRendererComponent(JTable table, Object value,
        boolean isSelected, boolean hasFocus, int row, int column)
    {
        setBackground((Color) value);
        if (hasFocus)
            setBorder(UIManager.getBorder("Table.focusCellHighlightBorder"));
    }
}
```

```
        else
            setBorder(null);
        return this;
    }
}

table.setDefaultRenderer(Color.class, new ColorTableCellRenderer());

moonColumn.setHeaderValue(new ImageIcon("Moons.gif"));

moonColumn.setHeaderRenderer(table.getDefaultRenderer(ImageIcon.class));

public boolean isCellEditable(int r, int c)
{
    return c == PLANET_COLUMN || c == MOONS_COLUMN || c == GASEOUS_COLUMN
           || c == COLOR_COLUMN;
}

var moonCombo = new JComboBox();
for (int i = 0; i <= 20; i++)
    moonCombo.addItem(i);

var moonEditor = new DefaultCellEditor(moonCombo);

moonColumn.setCellEditor(moonEditor);

public boolean isCellEditable(EventObject anEvent)
{
    return true;
}

public boolean shouldSelectCell(EventObject anEvent)
{
    colorDialog.setVisible(true);
    return true;
}
```

```
public void cancelCellEditing()
{
    colorDialog.setVisible(false);
    super.cancelCellEditing();
}

public Object getCellEditorValue()
{
    return colorChooser.getColor();
}

colorDialog = JColorChooser.createDialog(null, "Planet Color", false, colorChooser,
    EventHandler.create(ActionListener.class, this, "stopCellEditing"),
    EventHandler.create(ActionListener.class, this, "cancelCellEditing"));

void setValueAt(Object value, int r, int c)
```

```
1 package tableCellRender;
2
3 import java.awt.*;
4 import javax.swing.*;
5 import javax.swing.table.*;
6
7 /**
8  * This frame contains a table of planet data.
9  */
10 public class TableCellRenderFrame extends JFrame
11 {
12     private static final int DEFAULT_WIDTH = 600;
13     private static final int DEFAULT_HEIGHT = 400;
14
15     public TableCellRenderFrame()
16     {
17         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
18
19         var model = new PlanetTableModel();
20         var table = new JTable(model);
21         table.setRowSelectionAllowed(false);
22
23         // set up renderers and editors
24
25         table.setDefaultRenderer(Color.class, new ColorTableCellRenderer());
26         table.setDefaultEditor(Color.class, new ColorTableCellEditor());
27
28         var moonCombo = new JComboBox<Integer>();
29         for (int i = 0; i <= 20; i++)
30             moonCombo.addItem(i);
31
32         TableColumnModel columnModel = table.getColumnModel();
33         TableColumn moonColumn = columnModel.getColumn(PlanetTableModel.MOONS_COLUMN);
34         moonColumn.setCellEditor(new DefaultCellEditor(moonCombo));
35         moonColumn.setHeaderRenderer(table.getDefaultRenderer(ImageIcon.class));
36         moonColumn.setHeaderValue(new ImageIcon(getClass().getResource("Moons.gif")));
37
38         // show table
39
40         table.setRowHeight(100);
41         add(new JScrollPane(table), BorderLayout.CENTER);
42     }
43 }
```

```
1 package tableCellRender;
2
3 import java.awt.*;
4 import javax.swing.*;
5 import javax.swing.table.*;
6
7 /**
8  * The planet table model specifies the values, rendering and editing properties for the
9  * planet data.
10 */
11 public class PlanetTableModel extends AbstractTableModel
12 {
13     public static final int PLANET_COLUMN = 0;
14     public static final int MOONS_COLUMN = 2;
15     public static final int GASEOUS_COLUMN = 3;
16     public static final int COLOR_COLUMN = 4;
17
18     private Object[][][] cells =
19     {
20         {
21             { "Mercury", 2440.0, 0, false, Color.YELLOW,
22                 new ImageIcon(getClass().getResource("Mercury.gif")) },
23             { "Venus", 6052.0, 0, false, Color.YELLOW,
24                 new ImageIcon(getClass().getResource("Venus.gif")) },
25             { "Earth", 6378.0, 1, false, Color.BLUE,
26                 new ImageIcon(getClass().getResource("Earth.gif")) },
27             { "Mars", 3397.0, 2, false, Color.RED,
28                 new ImageIcon(getClass().getResource("Mars.gif")) },
29             { "Jupiter", 71492.0, 16, true, Color.ORANGE,
30                 new ImageIcon(getClass().getResource("Jupiter.gif")) },
31             { "Saturn", 60268.0, 18, true, Color.ORANGE,
32                 new ImageIcon(getClass().getResource("Saturn.gif")) },
33             { "Uranus", 25559.0, 17, true, Color.BLUE,
34                 new ImageIcon(getClass().getResource("Uranus.gif")) },
35             { "Neptune", 24766.0, 8, true, Color.BLUE,
36                 new ImageIcon(getClass().getResource("Neptune.gif")) },
37             { "Pluto", 1137.0, 1, false, Color.BLACK,
38                 new ImageIcon(getClass().getResource("Pluto.gif")) }
39     };
40
41     private String[] columnNames = { "Planet", "Radius", "Moons", "Gaseous",
42         "Color", "Image" };
43
44     public String getColumnName(int c)
45     {
46         return columnNames[c];
47     }
48 }
```

```
47
48     public Class<?> getColumnClass(int c)
49     {
50         return cells[0][c].getClass();
51     }
52
53     public int getColumnCount()
54     {
55         return cells[0].length;
56     }
57
58     public int getRowCount()
59     {
60         return cells.length;
61     }
62
63     public Object getValueAt(int r, int c)
64     {
65         return cells[r][c];
66     }
67
68     public void setValueAt(Object obj, int r, int c)
69     {
70         cells[r][c] = obj;
71     }
72
73     public boolean isCellEditable(int r, int c)
74     {
75         return c == PLANET_COLUMN || c == MOONS_COLUMN || c == GASEOUS_COLUMN
76             || c == COLOR_COLUMN;
77     }
78 }
```

```
1 package tableCellRender;
2
3 import java.awt.*;
4 import javax.swing.*;
5 import javax.swing.table.*;
6
7 /**
8  * This renderer renders a color value as a panel with the given color.
9  */
10 public class ColorTableCellRenderer extends JPanel implements TableCellRenderer
11 {
12     public Component getTableCellRendererComponent(JTable table, Object value,
13             boolean isSelected, boolean hasFocus, int row, int column)
14     {
15         setBackground((Color) value);
16         if (hasFocus) setBorder(UIManager.getBorder("Table.focusCellHighlightBorder"));
17         else setBorder(null);
18         return this;
19     }
20 }
```

```
1 package tableCellRender;
2
3 import java.awt.*;
4 import java.awt.event.*;
5 import java.beans.*;
6 import java.util.*;
7 import javax.swing.*;
8 import javax.swing.table.*;
9
10 /**
11  * This editor pops up a color dialog to edit a cell value.
12 */
13 public class ColorTableCellEditor extends AbstractCellEditor implements TableCellEditor
14 {
15     private JColorChooser colorChooser;
16     private JDialog colorDialog;
17     private JPanel panel;
18
19     public ColorTableCellEditor()
20     {
21         panel = new JPanel();
22         // prepare color dialog
23
24         colorChooser = new JColorChooser();
25         colorDialog = JColorChooser.createDialog(null, "Planet Color", false, colorChooser,
26             EventHandler.create(ActionListener.class, this, "stopCellEditing"),
27             EventHandler.create(ActionListener.class, this, "cancelCellEditing"));
28     }
29
30     public Component getTableCellEditorComponent(JTable table, Object value,
31         boolean isSelected, int row, int column)
32     {
```

```
33     // this is where we get the current color value. We store it in the dialog in case the
34     // user starts editing
35     colorChooser.setColor((Color) value);
36     return panel;
37 }
38
39 public boolean shouldSelectCell(EventObject anEvent)
40 {
41     // start editing
42     colorDialog.setVisible(true);
43
44     // tell caller it is ok to select this cell
45     return true;
46 }
47
48 public void cancelCellEditing()
49 {
50     // editing is canceled--hide dialog
51     colorDialog.setVisible(false);
52     super.cancelCellEditing();
53 }
54
55 public boolean stopCellEditing()
56 {
57     // editing is complete--hide dialog
58     colorDialog.setVisible(false);
59     super.stopCellEditing();
60
61     // tell caller it is ok to use color value
62     return true;
63 }
64
65 public Object getCellEditorValue()
66 {
67     return colorChooser.getColor();
68 }
69 }
```

```
JTree(Object[] nodes)
JTree(Vector<?> nodes)
JTree(Hashtable<?, ?> nodes) // the values become the nodes

TreeNode root = . . .;
var model = new DefaultTreeModel(root);

var node = new DefaultMutableTreeNode("Texas");
. . .
node.setUserObject("California");

var root = new DefaultMutableTreeNode("World");
var country = new DefaultMutableTreeNode("USA");
root.add(country);
var state = new DefaultMutableTreeNode("California");
country.add(state);

var treeModel = new DefaultTreeModel(root);
var tree = new JTree(treeModel);
```

```
1 package tree;
2
3 import javax.swing.*;
4 import javax.swing.tree.*;
5
6 /**
7  * This frame contains a simple tree that displays a manually constructed tree model.
8  */
9 public class SimpleTreeFrame extends JFrame
10 {
11     private static final int DEFAULT_WIDTH = 300;
12     private static final int DEFAULT_HEIGHT = 200;
13
14     public SimpleTreeFrame()
15     {
16         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
17
18         // set up tree model data
19
20         var root = new DefaultMutableTreeNode("World");
21         var country = new DefaultMutableTreeNode("USA");
22         root.add(country);
```

```
23     var state = new DefaultMutableTreeNode("California");
24     country.add(state);
25     var city = new DefaultMutableTreeNode("San Jose");
26     state.add(city);
27     city = new DefaultMutableTreeNode("Cupertino");
28     state.add(city);
29     state = new DefaultMutableTreeNode("Michigan");
30     country.add(state);
31     city = new DefaultMutableTreeNode("Ann Arbor");
32     state.add(city);
33     country = new DefaultMutableTreeNode("Germany");
34     root.add(country);
35     state = new DefaultMutableTreeNode("Schleswig-Holstein");
36     country.add(state);
37     city = new DefaultMutableTreeNode("Kiel");
38     state.add(city);
39
40     // construct tree and put it in a scroll pane
41
42     var tree = new JTree(root);
43     add(new JScrollPane(tree));
44 }
45 }

tree.putClientProperty("JTree.lineStyle", "None");

tree.putClientProperty("JTree.lineStyle", "Angled");

tree.setShowsRootHandles(true);

node.setAllowsChildren(false);

model.setAsksAllowsChildren(true);

var tree = new JTree(root, true); // nodes that don't allow children get leaf icons

TreePath selectionPath = tree.getSelectionPath();
var selectedNode = (DefaultMutableTreeNode) selectionPath.getLastPathComponent();

var selectedNode = (DefaultMutableTreeNode) tree.getLastSelectedPathComponent();
```

```
selectedNode.addNode(newNode); // No!  
  
model.insertNodeInto(newNode, selectedNode, selectedNode.getChildCount());  
  
model.removeNodeFromParent(selectedNode);  
  
model.nodeChanged(changedNode);  
  
TreeNode[] nodes = model.getPathToRoot(newNode);  
var path = new TreePath(nodes);  
tree.makeVisible(path);  
  
tree.scrollPathToVisible(path);  
  
1 package treeEdit;  
2  
3 import java.awt.*;  
4 import javax.swing.*;  
5 import javax.swing.tree.*;  
6  
7 /**  
8  * A frame with a tree and buttons to edit the tree.  
9  */  
10 public class TreeEditFrame extends JFrame  
11 {  
12     private static final int DEFAULT_WIDTH = 400;  
13     private static final int DEFAULT_HEIGHT = 200;  
14  
15     private DefaultTreeModel model;
```

```
16     private JTree tree;
17
18     public TreeEditFrame()
19     {
20         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
21
22         // construct tree
23
24         TreeNode root = makeSampleTree();
25         model = new DefaultTreeModel(root);
26         tree = new JTree(model);
27         tree.setEditable(true);
28
29         // add scroll pane with tree
30
31         var scrollPane = new JScrollPane(tree);
32         add(scrollPane, BorderLayout.CENTER);
33
34         makeButtons();
35     }
36
37     public TreeNode makeSampleTree()
38     {
39         var root = new DefaultMutableTreeNode("World");
40         var country = new DefaultMutableTreeNode("USA");
41         root.add(country);
42         var state = new DefaultMutableTreeNode("California");
43         country.add(state);
44         var city = new DefaultMutableTreeNode("San Jose");
45         state.add(city);
46         city = new DefaultMutableTreeNode("San Diego");
47         state.add(city);
48         state = new DefaultMutableTreeNode("Michigan");
49         country.add(state);
50         city = new DefaultMutableTreeNode("Ann Arbor");
51         state.add(city);
52         country = new DefaultMutableTreeNode("Germany");
53         root.add(country);
54         state = new DefaultMutableTreeNode("Schleswig-Holstein");
55         country.add(state);
56         city = new DefaultMutableTreeNode("Kiel");
57         state.add(city);
58         return root;
59     }
60
61     /**
62      * Makes the buttons to add a sibling, add a child, and delete a node.
63      */

```

```
64  public void makeButtons()
65  {
66      var panel = new JPanel();
67      var addSiblingButton = new JButton("Add Sibling");
68      addSiblingButton.addActionListener(event ->
69      {
70          var selectedNode = (DefaultMutableTreeNode) tree.getLastSelectedPathComponent();
71
72          if (selectedNode == null) return;
73
74          var parent = (DefaultMutableTreeNode) selectedNode.getParent();
75
76          if (parent == null) return;
77
78          var newNode = new DefaultMutableTreeNode("New");
79
80          int selectedIndex = parent.getIndex(selectedNode);
81          model.insertNodeInto(newNode, parent, selectedIndex + 1);
82
83          // now display new node
84
85          TreeNode[] nodes = model.getPathToRoot(newNode);
86          var path = new TreePath(nodes);
87          tree.scrollPathToVisible(path);
88      });
89      panel.add(addSiblingButton);
90
91      var addChildButton = new JButton("Add Child");
92      addChildButton.addActionListener(event ->
93      {
94          var selectedNode = (DefaultMutableTreeNode) tree.getLastSelectedPathComponent();
95
96          if (selectedNode == null) return;
97
98          var newNode = new DefaultMutableTreeNode("New");
99          model.insertNodeInto(newNode, selectedNode, selectedNode.getChildCount());
100
101         // now display new node
102
103         TreeNode[] nodes = model.getPathToRoot(newNode);
104         var path = new TreePath(nodes);
105         tree.scrollPathToVisible(path);
106     });
107     panel.add(addChildButton);
108
109     var deleteButton = new JButton("Delete");
110     deleteButton.addActionListener(event ->
111     {
112         var selectedNode = (DefaultMutableTreeNode) tree.getLastSelectedPathComponent();
```

```
113
114     if (selectedNode != null && selectedNode.getParent() != null) model
115         .removeNodeFromParent(selectedNode);
116     });
117     panel.add(deleteButton);
118     add(panel, BorderLayout.SOUTH);
119 }
120 }
```

```
Enumeration breadthFirst = node.breadthFirstEnumeration();
while (breadthFirst.hasMoreElements())
    do something with breadthFirst.nextElement();
```

```
public DefaultMutableTreeNode findUserObject(Object obj)
{
    Enumeration e = root.breadthFirstEnumeration();
    while (e.hasMoreElements())
    {
        DefaultMutableTreeNode node = (DefaultMutableTreeNode) e.nextElement();
        if (node.getUserObject().equals(obj))
            return node;
    }
    return null;
}
```

```
var renderer = new DefaultTreeCellRenderer();
renderer.setLeafIcon(new ImageIcon("blue-ball.gif")); // used for leaf nodes
renderer.setClosedIcon(new ImageIcon("red-ball.gif")); // used for collapsed nodes
renderer.setOpenIcon(new ImageIcon("yellow-ball.gif")); // used for expanded nodes
tree.setCellRenderer(renderer);
```

```
Component getTreeCellRendererComponent(JTree tree, Object value, boolean selected,
    boolean expanded, boolean leaf, int row, boolean hasFocus)
```

```
class MyTreeCellRenderer extends DefaultTreeCellRenderer
{
    public Component getTreeCellRendererComponent(JTree tree, Object value, boolean selected,
                                                boolean expanded, boolean leaf, int row, boolean hasFocus)
    {
        Component comp = super.getTreeCellRendererComponent(tree, value, selected,
                                                expanded, leaf, row, hasFocus);
        DefaultMutableTreeNode node = (DefaultMutableTreeNode) value;
        look at node.getUserObject();
        Font font = appropriate font;
        comp.setFont(font);
        return comp;
    }
}

void valueChanged(TreeSelectionEvent event)

tree.addTreeSelectionListener(listener);

int mode = TreeSelectionModel.SINGLE_TREE_SELECTION;
tree.getSelectionModel().setSelectionMode(mode);

TreePath[] selectedPaths = tree.getSelectionPaths();
```

```
1 package treeRender;
2
3 import java.awt.*;
4 import java.awt.event.*;
5 import java.lang.reflect.*;
6 import java.util.*;
7
8 import javax.swing.*;
9 import javax.swing.tree.*;
10
11 /**
12  * This frame displays the class tree, a text field, and an "Add" button to add more classes
13  * into the tree.
14  */
15 public class ClassTreeFrame extends JFrame
16 {
17     private static final int DEFAULT_WIDTH = 400;
18     private static final int DEFAULT_HEIGHT = 300;
19
20     private DefaultMutableTreeNode root;
21     private DefaultTreeModel model;
22     private JTree tree;
23     private JTextField textField;
24     private JTextArea textArea;
25
26     public ClassTreeFrame()
27     {
28         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
29
30         // the root of the class tree is Object
31         root = new DefaultMutableTreeNode(java.lang.Object.class);
32         model = new DefaultTreeModel(root);
33         tree = new JTree(model);
34
35         // add this class to populate the tree with some data
36         addClass(getClass());
37
38         // set up node icons
39         var renderer = new ClassNameTreeCellRenderer();
40         renderer.setClosedIcon(new ImageIcon(getClass().getResource("red-ball.gif")));
41         renderer.setOpenIcon(new ImageIcon(getClass().getResource("yellow-ball.gif")));
42         renderer.setLeafIcon(new ImageIcon(getClass().getResource("blue-ball.gif")));
43     }
44 }
```

```
43     tree.setCellRenderer(renderer);
44
45     // set up selection mode
46     tree.addTreeSelectionListener(event ->
47     {
48         // the user selected a different node--update description
49         TreePath path = tree.getSelectionPath();
50         if (path == null) return;
51         var selectedNode = (DefaultMutableTreeNode) path.getLastPathComponent();
52         Class<?> c = (Class<?>) selectedNode.getUserObject();
53         String description = getFieldDescription(c);
54         textArea.setText(description);
55     });
56     int mode = TreeSelectionModel.SINGLE_TREE_SELECTION;
57     tree.getSelectionModel().setSelectionMode(mode);
58
59     // this text area holds the class description
60     textArea = new JTextArea();
61
62     // add tree and text area
63     var panel = new JPanel();
64     panel.setLayout(new GridLayout(1, 2));
65     panel.add(new JScrollPane(tree));
66     panel.add(new JScrollPane(textArea));
67
68     add(panel, BorderLayout.CENTER);
69
70     addTextField();
71 }
72
73 /**
74 * Add the text field and "Add" button to add a new class.
75 */
76 public void addTextField()
77 {
78     var panel = new JPanel();
79
80     ActionListener addListener = event ->
81     {
82         // add the class whose name is in the text field
83         try
84         {
85             String text = textField.getText();
86             addClass(Class.forName(text)); // clear text field to indicate success
87             textField.setText("");
88         }
89     }
90 }
```

```
89         catch (ClassNotFoundException e)
90         {
91             JOptionPane.showMessageDialog(null, "Class not found");
92         }
93     };
94
95     // new class names are typed into this text field
96     textField = new JTextField(20);
97     textField.addActionListener(addListener);
98     panel.add(textField);
99
100    var addButton = new JButton("Add");
101    addButton.addActionListener(addListener);
102    panel.add(addButton);
103
104    add(panel, BorderLayout.SOUTH);
105}
106
107 /**
108 * Finds an object in the tree.
109 * @param obj the object to find
110 * @return the node containing the object or null if the object is not present in the tree
111 */
112 public DefaultMutableTreeNode findUserObject(Object obj)
113 {
114     // find the node containing a user object
115     var e = (Enumeration<TreeNode>) root.breadthFirstEnumeration();
116     while (e.hasMoreElements())
117     {
118         var node = (DefaultMutableTreeNode) e.nextElement();
119         if (node.getUserObject().equals(obj)) return node;
120     }
121     return null;
122 }
123
124 /**
125 * Adds a new class and any parent classes that aren't yet part of the tree.
126 * @param c the class to add
127 * @return the newly added node
128 */
129 public DefaultMutableTreeNode addClass(Class<?> c)
130 {
131     // add a new class to the tree
132
133     // skip non-class types
134     if (c.isInterface() || c.isPrimitive()) return null;
135
136     // if the class is already in the tree, return its node
```

```
137     DefaultMutableTreeNode node = findUserObject(c);
138     if (node != null) return node;
139
140     // class isn't present--first add class parent recursively
141
142     Class<?> s = c.getSuperclass();
143
144     DefaultMutableTreeNode parent;
145     if (s == null) parent = root;
146     else parent = addClass(s);
147
148     // add the class as a child to the parent
149     var newNode = new DefaultMutableTreeNode(c);
150     model.insertNodeInto(newNode, parent, parent getChildCount());
151
152     // make node visible
153     var path = new TreePath(model.getPathToRoot(newNode));
154     tree.makeVisible(path);
155
156     return newNode;
157 }
158
159 /**
160 * Returns a description of the fields of a class.
161 * @param c the class to be described
162 * @return a string containing all field types and names
163 */
164 public static String getFieldDescription(Class<?> c)
165 {
166     // use reflection to find types and names of fields
167     var r = new StringBuilder();
168     Field[] fields = c.getDeclaredFields();
169     for (int i = 0; i < fields.length; i++)
170     {
171         Field f = fields[i];
172         if ((f.getModifiers() & Modifier.STATIC) != 0) r.append("static ");
173         r.append(f.getType().getName());
174         r.append(" ");
175         r.append(f.getName());
176         r.append("\n");
177     }
178     return r.toString();
179 }
180 }
```

```
1 package treeRender;
2
3 import java.awt.*;
4 import java.lang.reflect.*;
5 import javax.swing.*;
6 import javax.swing.tree.*;
7
8 /**
9  * This class renders a class name either in plain or italic. Abstract classes are italic.
10 */
11 public class ClassNameTreeCellRenderer extends DefaultTreeCellRenderer
12 {
13     private Font plainFont = null;
14     private Font italicFont = null;
15
16     public Component getTreeCellRendererComponent(JTree tree, Object value, boolean selected,
17         boolean expanded, boolean leaf, int row, boolean hasFocus)
18     {
19         super.getTreeCellRendererComponent(tree, value, selected, expanded, leaf,
20             row, hasFocus);
21         // get the user object
22         var node = (DefaultMutableTreeNode) value;
23         Class<?> c = (Class<?>) node.getUserObject();
24
25         // the first time, derive italic font from plain font
26         if (plainFont == null)
27         {
28             plainFont = getFont();
29             // the tree cell renderer is sometimes called with a label that has a null font
30             if (plainFont != null) italicFont = plainFont.deriveFont(Font.ITALIC);
31         }
32
33         // set font to italic if the class is abstract, plain otherwise
34         if ((c.getModifiers() & Modifier.ABSTRACT) == 0) setFont(plainFont);
35         else setFont(italicFont);
36         return this;
37     }
38 }
```

```
Object getRoot()
int getChildCount(Object parent)
Object getChild(Object parent, int index)

int getIndexOfChild(Object parent, Object child)

boolean isLeaf(Object node)

void addTreeModelListener(TreeModelListener l)
void removeTreeModelListener(TreeModelListener l)

void treeNodesChanged(TreeModelEvent e)
void treeNodesInserted(TreeModelEvent e)
void treeNodesRemoved(TreeModelEvent e)
void treeStructureChanged(TreeModelEvent e)

void valueForPathChanged(TreePath path, Object newValue)

Object getRoot()
int getChildCount(Object parent)
Object getChild(Object parent, int index)

var v = new Variable(Employee.class, "joe", joe);

new Variable(double.class, "salary", Double.valueOf(salary));

public Object getRoot()
{
    return root;
}

public int getChildCount(Object parent)
{
    return ((Variable) parent).getFields().size();
}
```

```
public Object getChild(Object parent, int index)
{
    ArrayList fields = ((Variable) parent).getFields();
    var f = (Field) fields.get(index);
    Object parentValue = ((Variable) parent).getValue();
    try
    {
        return new Variable(f.getType(), f.getName(), f.get(parentValue));
    }
    catch (IllegalAccessException e)
    {
        return null;
    }
}
```

```
1 package treeModel;
2
3 import java.awt.*;
4 import javax.swing.*;
5
6 /**
7  * This frame holds the object tree.
8  */
9 public class ObjectInspectorFrame extends JFrame
10 {
11     private JTree tree;
12     private static final int DEFAULT_WIDTH = 400;
13     private static final int DEFAULT_HEIGHT = 300;
14
15     public ObjectInspectorFrame()
16     {
17         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
18
19         // we inspect this frame object
20
21         var v = new Variable(getClass(), "this", this);
22         var model = new ObjectTreeModel();
23         model.setRoot(v);
24
25         // construct and show tree
26
27         tree = new JTree(model);
28         add(new JScrollPane(tree), BorderLayout.CENTER);
29     }
30 }
```

```
1 package treeModel;
2
3 import java.lang.reflect.*;
4 import java.util.*;
5 import javax.swing.event.*;
6 import javax.swing.tree.*;
7
8 /**
9  * This tree model describes the tree structure of a Java object. Children are the objects
10 * that are stored in instance variables.
11 */
12 public class ObjectTreeModel implements TreeModel
13 {
14     private Variable root;
15     private EventListenerList listenerList = new EventListenerList();
16
17     /**
18      * Constructs an empty tree.
19      */
20     public ObjectTreeModel()
21     {
22         root = null;
23     }
24
25     /**
26      * Sets the root to a given variable.
27      * @param v the variable that is being described by this tree
28      */
29     public void setRoot(Variable v)
30     {
31         Variable oldRoot = v;
32         root = v;
33         fireTreeStructureChanged(oldRoot);
34     }
35
36     public Object getRoot()
37     {
38         return root;
39     }
40
41     public int getChildCount(Object parent)
42     {
43         return ((Variable) parent).getFields().size();
44     }
45
46     public Object getChild(Object parent, int index)
```

```
47     {
48         ArrayList<Field> fields = ((Variable) parent).getFields();
49         var f = (Field) fields.get(index);
50         Object parentValue = ((Variable) parent).getValue();
51         try
52         {
53             return new Variable(f.getType(), f.getName(), f.get(parentValue));
54         }
55         catch (IllegalAccessException e)
56         {
57             return null;
58         }
59     }
60
61     public int getIndexOfChild(Object parent, Object child)
62     {
63         int n = getChildCount(parent);
64         for (int i = 0; i < n; i++)
65             if (getChild(parent, i).equals(child)) return i;
66         return -1;
67     }
68
69     public boolean isLeaf(Object node)
70     {
71         return getChildCount(node) == 0;
72     }
73
74     public void valueForPathChanged(TreePath path, Object newValue)
75     {
76     }
77
78     public void addTreeModelListener(TreeModelListener l)
79     {
80         listenerList.add(TreeModelListener.class, l);
81     }
82
83     public void removeTreeModelListener(TreeModelListener l)
84     {
85         listenerList.remove(TreeModelListener.class, l);
86     }
87
88     protected void fireTreeStructureChanged(Object oldRoot)
89     {
90         var event = new TreeModelEvent(this, new Object[] { oldRoot });
91         for (TreeModelListener l : listenerList.getListeners(TreeModelListener.class))
92             l.treeStructureChanged(event);
93     }
94 }
```

```
1 package treeModel;
2
3 import java.lang.reflect.*;
4 import java.util.*;
5
6 /**
7  * A variable with a type, name, and value.
8  */
9 public class Variable
10 {
11     private Class<?> type;
12     private String name;
13     private Object value;
14     private ArrayList<Field> fields;
15
16     /**
17      * Construct a variable.
18      * @param aType the type
19      * @param aName the name
20      * @param aValue the value
21      */
22     public Variable(Class<?> aType, String aName, Object aValue)
23     {
24         type = aType;
25         name = aName;
26         value = aValue;
27         fields = new ArrayList<>();
28
29         // find all fields if we have a class type except we don't expand strings and
30         // null values
31
32         if (!type.isPrimitive() && !type.isArray() && !type.equals(String.class)
33             && value != null)
34         {
35             // get fields from the class and all superclasses
36             for (Class<?> c = value.getClass(); c != null; c = c.getSuperclass())
37             {
38                 Field[] fs = c.getDeclaredFields();
39                 AccessibleObject.setAccessible(fs, true);
40
41                 // get all nonstatic fields
42                 for (Field f : fs)
43                     if ((f.getModifiers() & Modifier.STATIC) == 0) fields.add(f);
44             }
45         }
46     }
```

```
47     /**
48      * Gets the value of this variable.
49      * @return the value
50      */
51     public Object getValue()
52     {
53         return value;
54     }
55
56     /**
57      * Gets all nonstatic fields of this variable.
58      * @return an array list of variables describing the fields
59      */
60     public ArrayList<Field> getFields()
61     {
62         return fields;
63     }
64
65
66     public String toString()
67     {
68         String r = type + " " + name;
69         if (type.isPrimitive()) r += "=" + value;
70         else if (type.equals(String.class)) r += "=" + value;
71         else if (value == null) r += "=null";
72         return r;
73     }
74 }
```

```
public void paintComponent(Graphics g)
```

```
{  
    var g2 = (Graphics2D) g;  
    . . .  
}
```

```
RenderingHints hints = . . .;  
g2.setRenderingHints(hints);
```

```
AffineTransform transform = . . .;  
g2.transform(transform);
```

```
var floatRect = new Rectangle2D.Float(5F, 10F, 7.5F, 15F);
var doubleRect = new Rectangle2D.Double(5, 10, 7.5, 15);

var r = new RoundRectangle2D.Double(150, 200, 100, 50, 20, 20);

var a = new Arc2D(x, y, width, height, startAngle, arcAngle, closureType);

skewedAngle = Math.toDegrees(Math.atan2(-y * height, x * width));

var q = new QuadCurve2D.Double(startX, startY, controlX, controlY, endX, endY);
var c = new CubicCurve2D.Double(startX, startY, control1X, control1Y,
    control2X, control2Y, endX, endY);

var path = new GeneralPath();
path.moveTo(10, 20);

path.lineTo(20, 30);
path.curveTo(control1X, control1Y, control2X, control2Y, endX, endY);

1 package shape;
2
3 import java.awt.*;
4 import java.awt.event.*;
5 import java.awt.geom.*;
6 import java.util.*;
7 import javax.swing.*;
8
9 /**
10  * This program demonstrates the various 2D shapes.
11  * @version 1.04 2018-05-01
12  * @author Cay Horstmann
13 */
```

```
14 public class ShapeTest
15 {
16     public static void main(String[] args)
17     {
18         EventQueue.invokeLater(() ->
19         {
20             var frame = new ShapeTestFrame();
21             frame.setTitle("ShapeTest");
22             frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
23             frame.setVisible(true);
24         });
25     }
26 }
27 /**
28  * This frame contains a combo box to select a shape and a component to draw it.
29  */
30
31 class ShapeTestFrame extends JFrame
32 {
33     public ShapeTestFrame()
34     {
35         var comp = new ShapeComponent();
36         add(comp, BorderLayout.CENTER);
37         var comboBox = new JComboBox<ShapeMaker>();
38         comboBox.addItem(new LineMaker());
39         comboBox.addItem(new RectangleMaker());
40         comboBox.addItem(new RoundRectangleMaker());
41         comboBox.addItem(new EllipseMaker());
42         comboBox.addItem(new ArcMaker());
43         comboBox.addItem(new PolygonMaker());
44         comboBox.addItem(new QuadCurveMaker());
45         comboBox.addItem(new CubicCurveMaker());
46         comboBox.addActionListener(event ->
47         {
48             ShapeMaker shapeMaker = comboBox.getItemAt(comboBox.getSelectedIndex());
49             comp.setShapeMaker(shapeMaker);
50         });
51         add(comboBox, BorderLayout.NORTH);
52         comp.setShapeMaker((ShapeMaker) comboBox.getItemAt(0));
53         pack();
54     }
55 }
56 /**
57  * This component draws a shape and allows the user to move the points that define it.
58  */
59
60 class ShapeComponent extends JComponent
61 {
```

```
52     private static final Dimension PREFERRED_SIZE = new Dimension(300, 200);
53     private Point2D[] points;
54     private static Random generator = new Random();
55     private static int SIZE = 10;
56     private int current;
57     private ShapeMaker shapeMaker;
58
59     public ShapeComponent()
60     {
61         addMouseListener(new MouseAdapter()
62         {
63             public void mousePressed(MouseEvent event)
64             {
65                 Point p = event.getPoint();
66                 for (int i = 0; i < points.length; i++)
67                 {
68                     double x = points[i].getX() - SIZE / 2;
69                     double y = points[i].getY() - SIZE / 2;
70                     var r = new Rectangle2D.Double(x, y, SIZE, SIZE);
71                     if (r.contains(p))
72                     {
73                         current = i;
74                         return;
75                     }
76                 }
77             }
78
79             public void mouseReleased(MouseEvent event)
80             {
81                 current = -1;
82             }
83         });
84         addMouseMotionListener(new MouseMotionAdapter()
85         {
86             public void mouseDragged(MouseEvent event)
87             {
88                 if (current == -1) return;
89                 points[current] = event.getPoint();
90                 repaint();
91             }
92         });
93         current = -1;
94     }
95 }
```

```
106     /**
107      * Set a shape maker and initialize it with a random point set.
108      * @param aShapeMaker a shape maker that defines a shape from a point set
109      */
110     public void setShapeMaker(ShapeMaker aShapeMaker)
111     {
112         shapeMaker = aShapeMaker;
113         int n = shapeMaker.getPointCount();
114         points = new Point2D[n];
115         for (int i = 0; i < n; i++)
116         {
117             double x = generator.nextDouble() * getWidth();
118             double y = generator.nextDouble() * getHeight();
119             points[i] = new Point2D.Double(x, y);
120         }
121         repaint();
122     }
123
124     public void paintComponent(Graphics g)
125     {
126         if (points == null) return;
127         var g2 = (Graphics2D) g;
128         for (int i = 0; i < points.length; i++)
129         {
130             double x = points[i].getX() - SIZE / 2;
131             double y = points[i].getY() - SIZE / 2;
132             g2.fill(new Rectangle2D.Double(x, y, SIZE, SIZE));
133         }
134
135         g2.draw(shapeMaker.makeShape(points));
136     }
137
138     public Dimension getPreferredSize() { return PREFERRED_SIZE; }
139 }
140
141 /**
142  * A shape maker can make a shape from a point set. Concrete subclasses must return a shape in
143  * the makeShape method.
144 */
145 abstract class ShapeMaker
146 {
147     private int pointCount;
148
149     /**
150      * Constructs a shape maker.
151      * @param pointCount the number of points needed to define this shape
152      */

```

```
153     public ShapeMaker(int pointCount)
154     {
155         this.pointCount = pointCount;
156     }
157
158     /**
159      * Gets the number of points needed to define this shape.
160      * @return the point count
161      */
162     public int getPointCount()
163     {
164         return pointCount;
165     }
166
167     /**
168      * Makes a shape out of the given point set.
169      * @param p the points that define the shape
170      * @return the shape defined by the points
171      */
172     public abstract Shape makeShape(Point2D[] p);
173
174     public String toString()
175     {
176         return getClass().getName();
177     }
178 }
179
180 /**
181  * Makes a line that joins two given points.
182  */
183 class LineMaker extends ShapeMaker
184 {
185     public LineMaker()
186     {
187         super(2);
188     }
189
190     public Shape makeShape(Point2D[] p)
191     {
192         return new Line2D.Double(p[0], p[1]);
193     }
194 }
195
196 /**
197  * Makes a rectangle that joins two given corner points.
198  */
199 class RectangleMaker extends ShapeMaker
200 {
```

```
291     public RectangleMaker()
292     {
293         super(2);
294     }
295
296     public Shape makeShape(Point2D[] p)
297     {
298         var s = new Rectangle2D.Double();
299         s setFrameFromDiagonal(p[0], p[1]);
300         return s;
301     }
302 }
303
304 /**
305 * Makes a round rectangle that joins two given corner points.
306 */
307 class RoundRectangleMaker extends ShapeMaker
308 {
309     public RoundRectangleMaker()
310     {
311         super(2);
312     }
313
314     public Shape makeShape(Point2D[] p)
315     {
316         var s = new RoundRectangle2D.Double(0, 0, 0, 0, 20, 20);
317         s setFrameFromDiagonal(p[0], p[1]);
318         return s;
319     }
320 }
321
322 /**
323 * Makes an ellipse contained in a bounding box with two given corner points.
324 */
325 class EllipseMaker extends ShapeMaker
326 {
327     public EllipseMaker()
328     {
329         super(2);
330     }
331
332     public Shape makeShape(Point2D[] p)
333     {
334         var s = new Ellipse2D.Double();
335         s setFrameFromDiagonal(p[0], p[1]);
336         return s;
337     }
338 }
```

```

259 /**
260  * Makes an arc contained in a bounding box with two given corner points, and with starting
261  * and ending angles given by lines emanating from the center of the bounding box and ending
262  * in two given points. To show the correctness of the angle computation, the returned shape
263  * contains the arc, the bounding box, and the lines.
264 */
265 class ArcMaker extends ShapeMaker
266 {
267     public ArcMaker()
268     {
269         super(4);
270     }
271
272     public Shape makeShape(Point2D[] p)
273     {
274         double centerX = (p[0].getX() + p[1].getX()) / 2;
275         double centerY = (p[0].getY() + p[1].getY()) / 2;
276         double width = Math.abs(p[1].getX() - p[0].getX());
277         double height = Math.abs(p[1].getY() - p[0].getY());
278
279         double skewedStartAngle = Math.toDegrees(Math.atan2(-(p[2].getY() - centerY) * width,
280             (p[2].getX() - centerX) * height));
281         double skewedEndAngle = Math.toDegrees(Math.atan2(-(p[3].getY() - centerY) * width,
282             (p[3].getX() - centerX) * height));
283         double skewedAngleDifference = skewedEndAngle - skewedStartAngle;
284         if (skewedStartAngle < 0) skewedStartAngle += 360;
285         if (skewedAngleDifference < 0) skewedAngleDifference += 360;
286
287         var s = new Arc2D.Double(0, 0, 0, 0,
288             skewedStartAngle, skewedAngleDifference, Arc2D.DOPEN);
289         s.setFrameFromDiagonal(p[0], p[1]);
290
291         var g = new GeneralPath();
292         g.append(s, false);
293         var r = new Rectangle2D.Double();
294         r.setFrameFromDiagonal(p[0], p[1]);
295         g.append(r, false);
296         var center = new Point2D.Double(centerX, centerY);
297         g.append(new Line2D.Double(center, p[2]), false);
298         g.append(new Line2D.Double(center, p[3]), false);
299         return g;
300     }
301 }
302 */
303 /**
304  * Makes a polygon defined by six corner points.
305 */
306 class PolygonMaker extends ShapeMaker

```

```
298 {
299     public PolygonMaker()
300     {
301         super(6);
302     }
303
304     public Shape makeShape(Point2D[] p)
305     {
306         var s = new GeneralPath();
307         s.moveTo((float) p[0].getX(), (float) p[0].getY());
308         for (int i = 1; i < p.length; i++)
309             s.lineTo((float) p[i].getX(), (float) p[i].getY());
310         s.closePath();
311         return s;
312     }
313 }
314
315 /**
316 * Makes a quad curve defined by two end points and a control point.
317 */
318 class QuadCurveMaker extends ShapeMaker
319 {
320     public QuadCurveMaker()
321     {
322         super(3);
323     }
324
325     public Shape makeShape(Point2D[] p)
326     {
327         return new QuadCurve2D.Double(p[0].getX(), p[0].getY(), p[1].getX(), p[1].getY(),
328                                         p[2].getX(), p[2].getY());
329     }
330 }
331
332 /**
333 * Makes a cubic curve defined by two end points and two contrnl points.
334 */
335 class CubicCurveMaker extends ShapeMaker
336 {
337     public CubicCurveMaker()
338     {
339         super(4);
340     }
341
342     public Shape makeShape(Point2D[] p)
343     {
344         return new CubicCurve2D.Double(p[0].getX(), p[0].getY(), p[1].getX(), p[1].getY(),
345                                         p[2].getX(), p[2].getY(), p[3].getX(), p[3].getY());
346     }
347 }
```

```
a.add(new Rectangle2D.Double(. . .));
a.subtract(path);
. . .

g2.setStroke(new BasicStroke(10.0F));
g2.draw(new Line2D.Double(. . .));

g2.setStroke(new BasicStroke(10.0F, BasicStroke.CAP_ROUND, BasicStroke.JOIN_ROUND));
g2.setStroke(new BasicStroke(10.0F, BasicStroke.CAP_BUTT, BasicStroke.JOIN_MITER,
    15.0F /* miter limit */));

float[] dashPattern = { 10, 10, 10, 10, 10, 10, 30, 10, 30, . . . };
g2.setStroke(new BasicStroke(10.0F, BasicStroke.CAP_BUTT, BasicStroke.JOIN_MITER,
    10.0F /* miter limit */, dashPattern, 0 /* dash phase */));
```

```
1 package stroke;
2
3 import java.awt.*;
4 import java.awt.event.*;
5 import java.awt.geom.*;
6 import javax.swing.*;
7
8 /**
9  * This program demonstrates different stroke types.
10 * @version 1.05 2018-05-01
11 * @author Cay Horstmann
12 */
13 public class StrokeTest
14 {
15     public static void main(String[] args)
16     {
17         EventQueue.invokeLater(() ->
18         {
19             var frame = new StrokeTestFrame();
20             frame.setTitle("StrokeTest");
21             frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
22             frame.setVisible(true);
23         });
24     }
25 }
26
27 /**
28 * This frame lets the user choose the cap, join, and line style, and shows the resulting
29 * stroke.
30 */
31 class StrokeTestFrame extends JFrame
32 {
33     private StrokeComponent canvas;
34     private JPanel buttonPanel;
```

```
35
36     public StrokeTestFrame()
37     {
38         canvas = new StrokeComponent();
39         add(canvas, BorderLayout.CENTER);
40
41         buttonPanel = new JPanel();
42         buttonPanel.setLayout(new GridLayout(3, 3));
43         add(buttonPanel, BorderLayout.NORTH);
44
45         var group1 = new ButtonGroup();
46         makeCapButton("Butt Cap", BasicStroke.CAP_BUTT, group1);
47         makeCapButton("Round Cap", BasicStroke.CAP_ROUND, group1);
48         makeCapButton("Square Cap", BasicStroke.CAP_SQUARE, group1);
49
50         var group2 = new ButtonGroup();
51         makeJoinButton("Miter Join", BasicStroke.JOIN_MITER, group2);
52         makeJoinButton("Bevel Join", BasicStroke.JOIN_BEVEL, group2);
53         makeJoinButton("Round Join", BasicStroke.JOIN_ROUND, group2);
54
55         var group3 = new ButtonGroup();
56         makeDashButton("Solid Line", false, group3);
57         makeDashButton("Dashed Line", true, group3);
58     }
59
60     /**
61      * Makes a radio button to change the cap style.
62      * @param label the button label
63      * @param style the cap style
64      * @param group the radio button group
65      */
66     private void makeCapButton(String label, final int style, ButtonGroup group)
67     {
68         // select first button in group
69         boolean selected = group.getButtonCount() == 0;
70         var button = new JRadioButton(label, selected);
71         buttonPanel.add(button);
72         group.add(button);
73         button.addActionListener(event -> canvas.setCap(style));
74         pack();
75     }
76
77     /**
78      * Makes a radio button to change the join style.
79      * @param label the button label
80      * @param style the join style
81      * @param group the radio button group
82      */
```

```
83     private void makeJoinButton(String label, final int style, ButtonGroup group)
84     {
85         // select first button in group
86         boolean selected = group.getButtonCount() == 0;
87         var button = new JRadioButton(label, selected);
88         buttonPanel.add(button);
89         group.add(button);
90         button.addActionListener(event -> canvas.setJoin(style));
91     }
92
93 /**
94 * Makes a radio button to set solid or dashed lines.
95 * @param label the button label
96 * @param style false for solid, true for dashed lines
97 * @param group the radio button group
98 */
99     private void makeDashButton(String label, final boolean style, ButtonGroup group)
100    {
101        // select first button in group
102        boolean selected = group.getButtonCount() == 0;
103        var button = new JRadioButton(label, selected);
104        buttonPanel.add(button);
105        group.add(button);
106        button.addActionListener(event -> canvas.setDash(style));
107    }
108 }
109
110 /**
111 * This component draws two joined lines, using different stroke objects, and allows the user
112 * to drag the three points defining the lines.
113 */
114 class StrokeComponent extends JComponent
115 {
116     private static final Dimension PREFERRED_SIZE = new Dimension(400, 400);
117     private static int SIZE = 10;
118
119     private Point2D[] points;
120     private int current;
121     private float width;
122     private int cap;
123     private int join;
124     private boolean dash;
125
126     public StrokeComponent()
127     {
```

```
128     addMouseListener(new MouseAdapter()
129     {
130         public void mousePressed(MouseEvent event)
131         {
132             Point p = event.getPoint();
133             for (int i = 0; i < points.length; i++)
134             {
135                 double x = points[i].getX() - SIZE / 2;
136                 double y = points[i].getY() - SIZE / 2;
137                 var r = new Rectangle2D.Double(x, y, SIZE, SIZE);
138                 if (r.contains(p))
139                 {
140                     current = i;
141                     return;
142                 }
143             }
144         }
145
146         public void mouseReleased(MouseEvent event)
147         {
148             current = -1;
149         }
150     });
151
152     addMouseMotionListener(new MouseMotionAdapter()
153     {
154         public void mouseDragged(MouseEvent event)
155         {
156             if (current == -1) return;
157             points[current] = event.getPoint();
158             repaint();
159         }
160     });
161
162     points = new Point2D[3];
163     points[0] = new Point2D.Double(200, 100);
164     points[1] = new Point2D.Double(100, 200);
165     points[2] = new Point2D.Double(200, 200);
166     current = -1;
167     width = 8.0F;
168 }
169
170 public void paintComponent(Graphics g)
171 {
172     var g2 = (Graphics2D) g;
173     var path = new GeneralPath();
174     path.moveTo((float) points[0].getX(), (float) points[0].getY());
175     for (int i = 1; i < points.length; i++)
176         path.lineTo((float) points[i].getX(), (float) points[i].getY());
```

```
177     BasicStroke stroke;
178     if (dash)
179     {
180         float miterLimit = 10.0F;
181         float[] dashPattern = { 10F, 10F, 10F, 10F, 10F, 10F, 30F, 10F, 30F, 10F, 30F,
182             10F, 10F, 10F, 10F, 10F, 30F };
183         float dashPhase = 0;
184         stroke = new BasicStroke(width, cap, join, miterLimit, dashPattern, dashPhase);
185     }
186     else stroke = new BasicStroke(width, cap, join);
187     g2.setStroke(stroke);
188     g2.draw(path);
189 }
190
191 /**
192 * Sets the join style.
193 * @param j the join style
194 */
195 public void setJoin(int j)
196 {
197     join = j;
198     repaint();
199 }
200
201 /**
202 * Sets the cap style.
203 * @param c the cap style
204 */
205 public void setCap(int c)
206 {
207     cap = c;
208     repaint();
209 }
210
211 /**
212 * Sets solid or dashed lines.
213 * @param d false for solid, true for dashed lines
214 */
215 public void setDash(boolean d)
216 {
217     dash = d;
218     repaint();
219 }
220
221 public Dimension getPreferredSize() { return PREFERRED_SIZE; }
222 }
```

```
g2.setPaint(new GradientPaint(p1, Color.RED, p2, Color.YELLOW));  
  
g2.setPaint(new GradientPaint(p1, Color.RED, p2, Color.YELLOW, true));  
  
g2.setPaint(new TexturePaint(bufferedImage, anchorRectangle));  
  
bufferedImage = ImageIO.read(new File("blue-ball.gif"));  
  
g2.scale(pixelsPerMeter, pixelsPerMeter);  
g2.draw(new Line2D.Double(coordinates in meters)); // converts to pixels and  
// draws scaled line  
  
var t = new AffineTransform(a, b, c, d, e, f);  
  
t = AffineTransform.getScaleInstance(2.0F, 0.5F);  
  
t.setToRotation(angle); // sets t to a rotation  
  
g2.setTransform(t); // replaces current transformation  
  
g2.transform(t); // composes current transformation with t  
  
AffineTransform oldTransform = g2.getTransform(); // save old transform  
g2.transform(t); // apply temporary transform  
draw on g2  
g2.setTransform(oldTransform); // restore old transform  
  
g2.setClip(clipShape); // but see below  
g2.draw(shape); // draws only the part that falls inside the clipping shape  
  
g2.clip(clipShape); // better  
  
Shape oldClip = g2.getClip(); // save old clip  
g2.clip(clipShape); // apply temporary clip  
draw on g2  
g2.setClip(oldClip); // restore old clip  
  
FontRenderContext context = g2.getFontRenderContext();  
  
var layout = new TextLayout("Hello", font, context);
```

```
AffineTransform transform = AffineTransform.getTranslateInstance(0, 100);
Shape outline = layout.getOutline(transform);

var clipShape = new GeneralPath();
clipShape.append(outline, false);

g2.setClip(clipShape);
var p = new Point2D.Double(0, 0);
for (int i = 0; i < NLINES; i++)
{
    double x = . . .;
    double y = . . .;
    var q = new Point2D.Double(x, y);
    g2.draw(new Line2D.Double(p, q)); // lines are clipped
}

int rule = AlphaComposite.SRC_OVER;
float alpha = 0.5f;
g2.setComposite(AlphaComposite.getInstance(rule, alpha));
g2.setPaint(Color.blue);
g2.fill(rectangle);

var image = new BufferedImage(getWidth(), getHeight(), BufferedImage.TYPE_INT_ARGB);
Graphics2D gImage = image.createGraphics();
// now draw to gImage
g2.drawImage(image, null, 0, 0);
```

```
1 package composite;
2
3 import java.awt.*;
4 import javax.swing.*;
5
6 /**
7  * This frame contains a combo box to choose a composition rule, a slider to change the
8  * source alpha channel, and a component that shows the composition.
9  */
10 class CompositeTestFrame extends JFrame
11 {
12     private static final int DEFAULT_WIDTH = 400;
13     private static final int DEFAULT_HEIGHT = 400;
14
15     private CompositeComponent canvas;
16     private JComboBox<Rule> ruleCombo;
17     private JSlider alphaSlider;
18     private JTextField explanation;
19
20     public CompositeTestFrame()
21     {
22         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
23
24         canvas = new CompositeComponent();
25         add(canvas, BorderLayout.CENTER);
26
27         ruleCombo = new JComboBox<(new Rule[]
28             {
29                 new Rule("CLEAR", " ", " "),
30                 new Rule("SRC", " S", " S"), new Rule("DST", " ", "DD"),
31             }
32         );
33
34         explanation = new JTextField("Composition Result");
35         explanation.setEditable(false);
36
37         JSplitPane splitPane = new JSplitPane(JSplitPane.VERTICAL_SPLIT);
38         splitPane.setTopComponent(ruleCombo);
39         splitPane.setBottomComponent(explanation);
40
41         JPanel panel = new JPanel();
42         panel.setLayout(new GridLayout(1, 2));
43         panel.add(splitPane);
44         panel.add(alphaSlider);
45
46         setContentPane(panel);
47     }
48 }
```

```
31         new Rule("SRC_OVER", "S", "DS"), new Rule("DST_OVER", "S", "DD"),
32         new Rule("SRC_IN", " ", "S"), new Rule("SRC_OUT", "S", " "),
33         new Rule("DST_IN", " ", "D"), new Rule("DST_OUT", " ", "D"),
34         new Rule("SRC_ATOP", " ", "DS"), new Rule("DST_ATOP", "S", "D"),
35         new Rule("XOR", "S", "D"),
36     });
37     ruleCombo.addActionListener(event ->
38     {
39         var r = (Rule) ruleCombo.getSelectedItem();
40         canvas.setRule(r.getValue());
41         explanation.setText(r.getExplanation());
42     });
43
44     alphaSlider = new JSlider(0, 100, 75);
45     alphaSlider.addChangeListener(event -> canvas.setAlpha(alphaSlider.getValue()));
46     var panel = new JPanel();
47     panel.add(ruleCombo);
48     panel.add(new JLabel("Alpha"));
49     panel.add(alphaSlider);
50     add(panel, BorderLayout.NORTH);
51
52     explanation = new JTextField();
53     add(explanation, BorderLayout.SOUTH);
54
55     canvas.setAlpha(alphaSlider.getValue());
56     Rule r = ruleCombo.getItemAt(ruleCombo.getSelectedIndex());
57     canvas.setRule(r.getValue());
58     explanation.setText(r.getExplanation());
59 }
60 }
61
62 package composite;
63
64 import java.awt.*;
65 import java.awt.geom.*;
66 import java.awt.image.*;
67 import javax.swing.*;
68
69 /**
70  * This component draws two shapes, composed with a composition rule.
71  */
```

```
11 class CompositeComponent extends JComponent
12 {
13     private int rule;
14     private Shape shape1;
15     private Shape shape2;
16     private float alpha;
17
18     public CompositeComponent()
19     {
20         shape1 = new Ellipse2D.Double(100, 100, 150, 100);
21         shape2 = new Rectangle2D.Double(150, 150, 150, 100);
22     }
23
24     public void paintComponent(Graphics g)
25     {
26         var g2 = (Graphics2D) g;
27
28         var image = new BufferedImage(getWidth(), getHeight(), BufferedImage.TYPE_INT_ARGB);
29         Graphics2D gImage = image.createGraphics();
30         gImage.setPaint(Color.red);
31         gImage.fill(shape1);
32         AlphaComposite composite = AlphaComposite.getInstance(rule, alpha);
33         gImage.setComposite(composite);
34         gImage.setPaint(Color.blue);
35         gImage.fill(shape2);
36         g2.drawImage(image, null, 0, 0);
37     }
38
39     /**
40      * Sets the composition rule.
41      * @param r the rule (as an AlphaComposite constant)
42      */
43     public void setRule(int r)
44     {
45         rule = r;
46         repaint();
47     }
48
49     /**
50      * Sets the alpha of the source.
51      * @param a the alpha value between 0 and 100
52      */
53     public void setAlpha(int a)
54     {
55         alpha = (float) a / 100.0F;
56         repaint();
57     }
58 }
```

```
1 package composite;
2
3 import java.awt.*;
4
5 /**
6  * This class describes a Porter-Duff rule.
7  */
8 class Rule
9 {
10     private String name;
11     private String porterDuff1;
12     private String porterDuff2;
13
14     /**
15      * Constructs a Porter-Duff rule.
16      * @param n the rule name
17      * @param pd1 the first row of the Porter-Duff square
18      * @param pd2 the second row of the Porter-Duff square
19      */
20     public Rule(String n, String pd1, String pd2)
21     {
22         name = n;
23         porterDuff1 = pd1;
24         porterDuff2 = pd2;
25     }
26
27     /**
28      * Gets an explanation of the behavior of this rule.
29      * @return the explanation
30      */
31     public String getExplanation()
32     {
33         var r = new StringBuilder("Source ");
34         if (porterDuff2.equals(" ")) r.append("clears");
35         if (porterDuff2.equals(" S")) r.append("overwrites");
36         if (porterDuff2.equals("DS")) r.append("blends with");
37         if (porterDuff2.equals(" D")) r.append("alpha modifies");
38         if (porterDuff2.equals("D ")) r.append("alpha complement modifies");
39         if (porterDuff2.equals("DD")) r.append("does not affect");
40         r.append(" destination");
41         if (porterDuff1.equals(" S")) r.append(" and overwrites empty pixels");
42         r.append(".");
43         return r.toString();
44     }
45 }
```

```
46     public String toString()
47     {
48         return name;
49     }
50
51     /**
52      * Gets the value of this rule in the AlphaComposite class.
53      * @return the AlphaComposite constant value, or -1 if there is no matching constant
54      */
55     public int getValue()
56     {
57         try
58         {
59             return (Integer) AlphaComposite.class.getField(name).get(null);
60         }
61         catch (Exception e)
62         {
63             return -1;
64         }
65     }
66 }

File f = . . .;
BufferedImage image = ImageIO.read(f);

File f = . . .;
String format = . . .;
ImageIO.write(image, format, f);

ImageReader reader = null;
Iterator<ImageReader> iter = ImageIO.getImageReadersByFormatName("JPEG");
if (iter.hasNext()) reader = iter.next();

ImageReaderSpi spi = reader.getOriginatingProvider();

String vendor = spi.getVendor();
String version = spi.getVersion();

String[] extensions = ImageIO.getWriterFileSuffixes();
chooser.setFileFilter(new FileNameExtensionFilter("Image files", extensions));
```

```
jpg, BMP, bmp, JPG, jpeg, wbmp, png, JPEG, PNG, WBMP, GIF, gif

InputStream in = . . .;
ImageInputStream imageIn = ImageIO.createImageInputStream(in);

File f = . . .;
ImageInputStream imageIn = ImageIO.createImageInputStream(f);
reader.setInput(imageIn);

BufferedImage image = reader.read(index);

int n = reader.getNumImages(true);

int count = reader.getNumThumbnails(index);

BufferedImage thumbnail = reader.getThumbnail(index, thumbnailIndex);

int width = reader.getWidth(index);
int height = reader.getHeight(index);

String format = . . .;
ImageWriter writer = null;
Iterator<ImageWriter> iter = ImageIO.getImageWritersByFormatName(format);
if (iter.hasNext()) writer = iter.next();

File f = . . .;
ImageOutputStream imageOut = ImageIO.createImageOutputStream(f);
writer.setOutput(imageOut);

var iioImage = new IIOMage(images[i], null, null);

writer.write(new IIOMage(images[0], null, null));

if (writer.canInsertImage(i))
    writer.writeInsert(i, iioImage, null);
```

```
1 package imageIO;
2
3 import java.awt.image.*;
4 import java.io.*;
5 import java.util.*;
6
7 import javax.imageio.*;
8 import javax.imageio.stream.*;
9 import javax.swing.*;
10 import javax.swing.filechooser.*;
11
12 /**
13  * This frame displays the loaded images. The menu has items for loading and saving files.
14  */
15 public class ImageIOFrame extends JFrame
16 {
```

```
17     private static final int DEFAULT_WIDTH = 400;
18     private static final int DEFAULT_HEIGHT = 400;
19
20     private static Set<String> writerFormats = getWriterFormats();
21
22     private BufferedImage[] images;
23
24     public ImageIOFrame()
25     {
26         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
27
28         var fileMenu = new JMenu("File");
29         var openItem = new JMenuItem("Open");
30         openItem.addActionListener(event -> openFile());
31         fileMenu.add(openItem);
32
33         var saveMenu = new JMenu("Save");
34         fileMenu.add(saveMenu);
35         Iterator<String> iter = writerFormats.iterator();
36         while (iter.hasNext())
37         {
38             final String formatName = iter.next();
39             var formatItem = new JMenuItem(formatName);
40             saveMenu.add(formatItem);
41             formatItem.addActionListener(event -> saveFile(formatName));
42         }
43
44         var exitItem = new JMenuItem("Exit");
45         exitItem.addActionListener(event -> System.exit(0));
46         fileMenu.add(exitItem);
47
48         var menuBar = new JMenuBar();
49         menuBar.add(fileMenu);
50         setJMenuBar(menuBar);
51     }
52
53 /**
54  * Open a file and load the images.
55  */
56 public void openFile()
57 {
58     var chooser = new JFileChooser();
59     chooser.setCurrentDirectory(new File("."));
60     String[] extensions = ImageIO.getReaderFileSuffixes();
61     chooser.setFileFilter(new FileNameExtensionFilter("Image files", extensions));
62     int r = chooser.showOpenDialog(this);
63     if (r != JFileChooser.APPROVE_OPTION) return;
64     File f = chooser.getSelectedFile();
65     Box box = Box.createVerticalBox();
```

```
66     try
67     {
68         String name = f.getName();
69         String suffix = name.substring(name.lastIndexOf('.') + 1);
70         Iterator<ImageReader> iter = ImageIO.getImageReadersBySuffix(suffix);
71         ImageReader reader = iter.next();
72         ImageInputStream imageIn = ImageIO.createImageInputStream(f);
73         reader.setInput(imageIn);
74         int count = reader.getNumImages(true);
75         images = new BufferedImage[count];
76         for (int i = 0; i < count; i++)
77         {
78             images[i] = reader.read(i);
79             box.add(new JLabel(new ImageIcon(images[i])));
80         }
81     }
82     catch (IOException e)
83     {
84         JOptionPane.showMessageDialog(this, e);
85     }
86     setContentPane(new JScrollPane(box));
87     validate();
88 }
89
90 /**
91 * Save the current image in a file.
92 * @param formatName the file format
93 */
94 public void saveFile(final String formatName)
95 {
96     if (images == null) return;
97     Iterator<ImageWriter> iter = ImageIO.getImageWritersByFormatName(formatName);
98     ImageWriter writer = iter.next();
99     var chooser = new JFileChooser();
100    chooser.setCurrentDirectory(new File("."));
101    String[] extensions = writer.getOriginatingProvider().getFileSuffixes();
102    chooser.setFileFilter(new FileNameExtensionFilter("Image files", extensions));
103
104    int r = chooser.showSaveDialog(this);
105    if (r != JFileChooser.APPROVE_OPTION) return;
106    File f = chooser.getSelectedFile();
107    try
108    {
109        ImageOutputStream imageOut = ImageIO.createImageOutputStream(f);
110        writer.setOutput(imageOut);
111
112        writer.write(new IIOImage(images[0], null, null));
113        for (int i = 1; i < images.length; i++)
```

```
114     {
115         var iioImage = new IIOImage(images[i], null, null);
116         if (writer.canInsertImage(i)) writer.writeInsert(i, iioImage, null);
117     }
118 }
119 catch (IOException e)
120 {
121     JOptionPane.showMessageDialog(this, e);
122 }
123 }
124 /**
125 * Gets a set of "preferred" format names of all image writers. The preferred format name
126 * is the first format name that a writer specifies.
127 * @return the format name set
128 */
129 public static Set<String> getWriterFormats()
130 {
131     var writerFormats = new TreeSet<String>();
132     var formatNames = List.of(ImageIO.getWriterFormatNames());
133     while (formatNames.size() > 0)
134     {
135         String name = formatNames.iterator().next();
136         Iterator<ImageWriter> iter = ImageIO.getImageWritersByFormatName(name);
137         ImageWriter writer = iter.next();
138         String[] names = writer.getOriginatingProvider().getFormatNames();
139         String format = names[0];
140         if (format.equals(format.toLowerCase())) format = format.toUpperCase();
141         writerFormats.add(format);
142         formatNames.removeAll(List.of(names));
143     }
144 }
145 return writerFormats;
146 }
147 }
```

```
image = new BufferedImage(width, height, BufferedImage.TYPE_INT_ARGB);
```

```
WritableRaster raster = image.getRaster();
```

```
int[] black = { 0, 0, 0, 255 };
raster.setPixel(i, j, black);

float[] red = { 1.0F, 0.0F, 0.0F, 1.0F };
raster.setPixel(i, j, red); // ERROR

var pixels = new int[4 * width * height];
pixels[0] = . . .; // red value for first pixel

pixels[1] = . . .; // green value for first pixel
pixels[2] = . . .; // blue value for first pixel
pixels[3] = . . .; // alpha value for first pixel
. . .
raster.setPixels(x, y, width, height, pixels);

var sample = new int[4];
raster.getPixel(x, y, sample);
var color = new Color(sample[0], sample[1], sample[2], sample[3]);

raster.getPixels(x, y, width, height, samples);

ColorModel model = image.getColorModel();

Object data = raster.getDataElements(x, y, null);

int argb = model.getRGB(data);
var color = new Color(argb, true);

int argb = color.getRGB();
Object data = model.getDataElements(argb, null);
raster.setDataElements(x, y, data);

1 package rasterImage;
2
3 import java.awt.*;
4 import java.awt.image.*;
5 import javax.swing.*;
```

```
7  /**
8   * This frame shows an image with a Mandelbrot set.
9  */
10 public class RasterImageFrame extends JFrame
11 {
12     private static final double XMIN = -2;
13     private static final double XMAX = 2;
14     private static final double YMIN = -2;
15     private static final double YMAX = 2;
16     private static final int MAX_ITERATIONS = 16;
17     private static final int IMAGE_WIDTH = 400;
18     private static final int IMAGE_HEIGHT = 400;
19
20     public RasterImageFrame()
21     {
22         BufferedImage image = makeMandelbrot(IMAGE_WIDTH, IMAGE_HEIGHT);
23         add(new JLabel(new ImageIcon(image)));
24         pack();
25     }
26
27     /**
28      * Makes the Mandelbrot image.
29      * @param width the width
30      * @param height the height
31      * @return the image
32      */
33     public BufferedImage makeMandelbrot(int width, int height)
34     {
35         var image = new BufferedImage(width, height, BufferedImage.TYPE_INT_ARGB);
36         WritableRaster raster = image.getRaster();
37         ColorModel model = image.getColorModel();
38
39         Color fractalColor = Color.RED;
40         int argb = fractalColor.getRGB();
41         Object colorData = model.getDataElements(argb, null);
42
43         for (int i = 0; i < width; i++)
44             for (int j = 0; j < height; j++)
45             {
46                 double a = XMIN + i * (XMAX - XMIN) / width;
47                 double b = YMIN + j * (YMAX - YMIN) / height;
48                 if (!escapesToInfinity(a, b)) raster.setDataElements(i, j, colorData);
49             }
50         return image;
51     }
52 }
```

```
53     private boolean escapesToInfinity(double a, double b)
54     {
55         double x = 0.0;
56         double y = 0.0;
57         int iterations = 0;
58         while (x <= 2 && y <= 2 && iterations < MAX_ITERATIONS)
59         {
60             double xnew = x * x - y * y + a;
61             double ynew = 2 * x * y + b;
62             x = xnew;
63             y = ynew;
64             iterations++;
65         }
66         return x > 2 || y > 2;
67     }
68 }
```

```
BufferedImageOp op = . . .;
BufferedImage filteredImage
    = new BufferedImage(image.getWidth(), image.getHeight(), image.getType());
op.filter(image, filteredImage);

AffineTransform transform = AffineTransform.getRotateInstance(Math.toRadians(angle),
    image.getWidth() / 2, image.getHeight() / 2);
var op = new AffineTransformOp(transform, interpolation);
op.filter(image, filteredImage);

float a = 1.1f;
float b = 20.0f;
var op = new RescaleOp(a, b, null);

var negative = new short[256];
for (int i = 0; i < 256; i++) negative[i] = (short) (255 - i);
var table = new ShortLookupTable(0, negative);
var op = new LookupOp(table, null);
```

```
float[] elements =
{
    0.0f, -1.0f, 0.0f,
    -1.0f, 4.0f, -1.0f,
    0.0f, -1.0f, 0.0f
};
var kernel = new Kernel(3, 3, elements);
var op = new ConvolveOp(kernel);
op.filter(image, filteredImage);
```

```
1 package imageProcessing;
2
3 import java.awt.*;
4 import java.awt.geom.*;
5 import java.awt.image.*;
6 import java.io.*;
7
8 import javax.imageio.*;
9 import javax.swing.*;
10 import javax.swing.filechooser.*;
11
12 /**
13  * This frame has a menu to load an image and to specify various transformations, and a
14  * component to show the resulting image.
15  */
16 public class ImageProcessingFrame extends JFrame
17 {
18     private static final int DEFAULT_WIDTH = 400;
19     private static final int DEFAULT_HEIGHT = 400;
20
21     private BufferedImage image;
22
23     public ImageProcessingFrame()
24     {
25         setTitle("ImageProcessingTest");
26         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
27
28         add(new JComponent()
29         {
30             public void paintComponent(Graphics g)
31             {
32                 if (image != null) g.drawImage(image, 0, 0, null);
33             }
34         });
35
36         var fileMenu = new JMenu("File");
37         var openItem = new JMenuItem("Open");
38         openItem.addActionListener(event -> openFileDialog());
39         fileMenu.add(openItem);
40
41         var exitItem = new JMenuItem("Exit");
42         exitItem.addActionListener(event -> System.exit(0));
43         fileMenu.add(exitItem);
44     }
45 }
```

```
44
45     var editMenu = new JMenu("Edit");
46     var blurItem = new JMenuItem("Blur");
47     blurItem.addActionListener(event ->
48     {
49         float weight = 1.0f / 9.0f;
50         float[] elements = new float[9];
51         for (int i = 0; i < 9; i++)
52             elements[i] = weight;
53         convolve(elements);
54     });
55     editMenu.add(blurItem);
56
57     var sharpenItem = new JMenuItem("Sharpen");
58     sharpenItem.addActionListener(event ->
59     {
60         float[] elements = { 0.0f, -1.0f, 0.0f, -1.0f, 5.f, -1.0f, 0.0f, -1.0f, 0.0f };
61         convolve(elements);
62     });
63     editMenu.add(sharpenItem);
64
65     var brightenItem = new JMenuItem("Brighten");
66     brightenItem.addActionListener(event ->
67     {
68         float a = 1.1f;
69         float b = 20.0f;
70         var op = new RescaleOp(a, b, null);
71         filter(op);
72     });
73     editMenu.add(brightenItem);
74
75     var edgeDetectItem = new JMenuItem("Edge detect");
76     edgeDetectItem.addActionListener(event ->
77     {
78         float[] elements = { 0.0f, -1.0f, 0.0f, -1.0f, 4.f, -1.0f, 0.0f, -1.0f, 0.0f };
79         convolve(elements);
80     });
81     editMenu.add(edgeDetectItem);
82
83     var negativeItem = new JMenuItem("Negative");
84     negativeItem.addActionListener(event ->
85     {
86         short[] negative = new short[256 * 1];
87         for (int i = 0; i < 256; i++)
88             negative[i] = (short) (255 - i);
89         var table = new ShortLookupTable(0, negative);
90         var op = new LookupOp(table, null);
91         filter(op);
92     });
93
```

```
93     editMenu.add(negativeItem);
94
95     var rotateItem = new JMenuItem("Rotate");
96     rotateItem.addActionListener(event ->
97     {
98         if (image == null) return;
99         var transform = AffineTransform.getRotateInstance(Math.toRadians(5),
100             image.getWidth() / 2, image.getHeight() / 2);
101         var op = new AffineTransformOp(transform,
102             AffineTransformOp.TYPE_BICUBIC);
103         filter(op);
104     });
105     editMenu.add(rotateItem);
106
107     var menuBar = new JMenuBar();
108     menuBar.add(fileMenu);
109     menuBar.add(editMenu);
110     setJMenuBar(menuBar);
111 }
112 /**
113 * Open a file and load the image.
114 */
115 public void openFile()
116 {
117     var chooser = new JFileChooser(".");
118     chooser.setCurrentDirectory(new File(getClass().getPackage().getName()));
119     String[] extensions = ImageIO.getReaderFileSuffixes();
120     chooser.setFileFilter(new FileNameExtensionFilter("Image files", extensions));
121     int r = chooser.showOpenDialog(this);
122     if (r != JFileChooser.APPROVE_OPTION) return;
123
124     try
125     {
126         Image img = ImageIO.read(chooser.getSelectedFile());
127         image = new BufferedImage(img.getWidth(null), img.getHeight(null),
128             BufferedImage.TYPE_INT_RGB);
129         image.getGraphics().drawImage(img, 0, 0, null);
130     }
131     catch (IOException e)
132     {
133         JOptionPane.showMessageDialog(this, e);
134     }
135     repaint();
136 }
137 /**
138 * Apply a filter and repaint.
139 */
```

```
141     * @param op the image operation to apply
142     */
143     private void filter(BufferedImageOp op)
144     {
145         if (image == null) return;
146         image = op.filter(image, null);
147         repaint();
148     }
149
150 /**
151     * Apply a convolution and repaint.
152     * @param elements the convolution kernel (an array of 9 matrix elements)
153     */
154     private void convolve(float[] elements)
155     {
156         var kernel = new Kernel(3, 3, elements);
157         var op = new ConvolveOp(kernel);
158         filter(op);
159     }
160 }

int print(Graphics g, PageFormat format, int page)

Printable canvas = . . .;
PrinterJob job = PrinterJob.getPrinterJob();
job.setPrintable(canvas);

var attributes = new HashPrintRequestAttributeSet();

if (job.printDialog(attributes))
{
    try
    {
        job.print(attributes);
    }
    catch (PrinterException e)
    {
        . . .
    }
}
```

```
g.translate(pageFormat.getImageableX(), pageFormat.getImageableY());  
  
PageFormat format = job.pageDialog(attributes);  
  
class PrintPanel extends JPanel implements Printable  
{  
    public void paintComponent(Graphics g)  
    {  
        super.paintComponent(g);  
        var g2 = (Graphics2D) g;  
        drawPage(g2);  
    }  
  
    public int print(Graphics g, PageFormat pf, int page) throws PrinterException  
    {  
        if (page >= 1) return Printable.NO_SUCH_PAGE;  
        var g2 = (Graphics2D) g;  
        g2.translate(pf.getImageableX(), pf.getImageableY());  
        drawPage(g2);  
        return Printable.PAGE_EXISTS;  
    }  
  
    public void drawPage(Graphics2D g2)  
    {  
        // shared drawing code goes here  
        . . .  
    }  
    . . .  
}  
  
PageFormat defaultFormat = printJob.defaultPage();  
PageFormat selectedFormat = printJob.pageDialog(defaultFormat);
```

```
1 package print;
2
3 import java.awt.*;
4 import java.awt.print.*;
5
6 import javax.print.attribute.*;
7 import javax.swing.*;
8
9 /**
10  * This frame shows a panel with 2D graphics and buttons to print the graphics and to set up
11  * the page format.
12 */
13 public class PrintTestFrame extends JFrame
14 {
15     private PrintComponent canvas;
16     private PrintRequestAttributeSet attributes;
17
18     public PrintTestFrame()
19     {
20         canvas = new PrintComponent();
21         add(canvas, BorderLayout.CENTER);
22
23         attributes = new HashPrintRequestAttributeSet();
24
25         var buttonPanel = new JPanel();
26         var printButton = new JButton("Print");
27         buttonPanel.add(printButton);
28         printButton.addActionListener(event ->
29             {
30                 try
31                 {
32                     PrinterJob job = PrinterJob.getPrinterJob();
33                     job.setPrintable(canvas);
34                     if (job.printDialog(attributes)) job.print(attributes);
35                 }
36             });
37     }
38 }
```

```
36         catch (PrinterException e)
37         {
38             JOptionPane.showMessageDialog(PrintTestFrame.this, e);
39         }
40     });
41
42     var pageSetupButton = new JButton("Page setup");
43     buttonPanel.add(pageSetupButton);
44     pageSetupButton.addActionListener(event ->
45     {
46         PrinterJob job = PrinterJob.getPrinterJob();
47         job.pageDialog(attributes);
48     });
49
50     add(buttonPanel, BorderLayout.NORTH);
51     pack();
52 }
53 }

1 package print;
2
3 import java.awt.*;
4 import java.awt.font.*;
5 import java.awt.geom.*;
6 import java.awt.print.*;
7 import javax.swing.*;
8
9 /**
10  * This component generates a 2D graphics image for screen display and printing.
11  */
12 public class PrintComponent extends JComponent implements Printable
13 {
14     private static final Dimension PREFERRED_SIZE = new Dimension(300, 300);
15
16     public void paintComponent(Graphics g)
17     {
18         var g2 = (Graphics2D) g;
19         drawPage(g2);
20     }
21
```

```
22 public int print(Graphics g, PageFormat pf, int page) throws PrinterException
23 {
24     if (page >= 1) return Printable.NO_SUCH_PAGE;
25     var g2 = (Graphics2D) g;
26     g2.translate(pf.getImageableX(), pf.getImageableY());
27     g2.draw(new Rectangle2D.Double(0, 0, pf.getImageableWidth(), pf.getImageableHeight()));
28
29     drawPage(g2);
30     return Printable.PAGE_EXISTS;
31 }
32
33 /**
34 * This method draws the page both on the screen and the printer graphics context.
35 * @param g2 the graphics context
36 */
37 public void drawPage(Graphics2D g2)
38 {
39     FontRenderContext context = g2.getFontRenderContext();
40     var f = new Font("Serif", Font.PLAIN, 72);
41     var clipShape = new GeneralPath();
42
43     var layout = new TextLayout("Hello", f, context);
44     AffineTransform transform = AffineTransform.getTranslateInstance(0, 72);
45     Shape outline = layout.getOutline(transform);
46     clipShape.append(outline, false);
47
48     layout = new TextLayout("World", f, context);
49     transform = AffineTransform.getTranslateInstance(0, 144);
50     outline = layout.getOutline(transform);
51     clipShape.append(outline, false);
52
53     g2.draw(clipShape);
54     g2.clip(clipShape);
55
56     final int NLINES = 50;
57     var p = new Point2D.Double(0, 0);
58     for (int i = 0; i < NLINES; i++)
59     {
60         double x = (2 * getWidth() * i) / NLINES;
61         double y = (2 * getHeight() * (NLINES - 1 - i)) / NLINES;
62         var q = new Point2D.Double(x, y);
63         g2.draw(new Line2D.Double(p, q));
64     }
65 }
66
67 public Dimension getPreferredSize() { return PREFERRED_SIZE; }
68 }
```

```
var book = new Book();
Printable coverPage = . . .;
Printable bodyPages = . . .;
book.append(coverPage, pageFormat); // append 1 page
book.append(bodyPages, pageFormat, pageCount);

1 package book;
2
3 import java.awt.*;
4 import java.awt.print.*;
5
6 import javax.print.attribute.*;
7 import javax.swing.*;
8
9 /**
10  * This frame has a text field for the banner text and buttons for printing, page setup, and
11  * print preview.
12 */
13 public class BookTestFrame extends JFrame
```

```
14 {
15     private JTextField text;
16     private PageFormat pageFormat;
17     private PrintRequestAttributeSet attributes;
18
19     public BookTestFrame()
20     {
21         text = new JTextField();
22         add(text, BorderLayout.NORTH);
23
24         attributes = new HashPrintRequestAttributeSet();
25
26         var buttonPanel = new JPanel();
27
28         var printButton = new JButton("Print");
29         buttonPanel.add(printButton);
30         printButton.addActionListener(event ->
31             {
32                 try
33                 {
34                     PrinterJob job = PrinterJob.getPrinterJob();
35                     job.setPageable(makeBook());
36                     if (job.printDialog(attributes))
37                     {
38                         job.print(attributes);
39                     }
40                 }
41                 catch (PrinterException e)
42                 {
43                     JOptionPane.showMessageDialog(BookTestFrame.this, e);
44                 }
45             });
46
47         var pageSetupButton = new JButton("Page setup");
48         buttonPanel.add(pageSetupButton);
49         pageSetupButton.addActionListener(event ->
50             {
51                 PrinterJob job = PrinterJob.getPrinterJob();
52                 pageFormat = job.pageDialog(attributes);
53             });
54
55         var printPreviewButton = new JButton("Print preview");
56         buttonPanel.add(printPreviewButton);
57         printPreviewButton.addActionListener(event ->
58             {
59                 var dialog = new PrintPreviewDialog(makeBook());
60                 dialog.setVisible(true);
61             });
62 }
```

```
57     add(buttonPanel, BorderLayout.SOUTH);
58     pack();
59 }
60
61 /**
62  * Makes a book that contains a cover page and the pages for the banner.
63  */
64 public Book makeBook()
65 {
66     if (pageFormat == null)
67     {
68         PrinterJob job = PrinterJob.getPrinterJob();
69         pageFormat = job.defaultPage();
70     }
71     var book = new Book();
72     String message = text.getText();
73     var banner = new Banner(message);
74     int pageCount = banner.getPageCount((Graphics2D) getGraphics(), pageFormat);
75     book.append(new CoverPage(message + " (" + pageCount + " pages)", pageFormat));
76     book.append(banner, pageFormat, pageCount);
77     return book;
78 }
79 }
```

```
1 package book;
2
3 import java.awt.*;
4 import java.awt.font.*;
5 import java.awt.geom.*;
6 import java.awt.print.*;
7
8 /**
9  * A banner that prints a text string on multiple pages.
10 */
11 public class Banner implements Printable
12 {
13     private String message;
14     private double scale;
15
16     /**
17      * Constructs a banner.
18      * @param m the message string
19      */
```

```
20     public Banner(String m)
21     {
22         message = m;
23     }
24
25     /**
26      * Gets the page count of this section.
27      * @param g2 the graphics context
28      * @param pf the page format
29      * @return the number of pages needed
30      */
31     public int getPageCount(Graphics2D g2, PageFormat pf)
32     {
33         if (message.equals("")) return 0;
34         FontRenderContext context = g2.getFontRenderContext();
35         var f = new Font("Serif", Font.PLAIN, 72);
36         Rectangle2D bounds = f.getStringBounds(message, context);
37         scale = pf.getImageableHeight() / bounds.getHeight();
38         double width = scale * bounds.getWidth();
39         int pages = (int) Math.ceil(width / pf.getImageableWidth());
40         return pages;
41     }
42
43     public int print(Graphics g, PageFormat pf, int page) throws PrinterException
44     {
45         var g2 = (Graphics2D) g;
46         if (page > getPageCount(g2, pf)) return Printable.NO_SUCH_PAGE;
47         g2.translate(pf.getImageableX(), pf.getImageableY());
48
49         drawPage(g2, pf, page);
50         return Printable.PAGE_EXISTS;
51     }
52
53     public void drawPage(Graphics2D g2, PageFormat pf, int page)
54     {
55         if (message.equals("")) return;
56         page--; // account for cover page
57
58         drawCropMarks(g2, pf);
59         g2.clip(new Rectangle2D.Double(0, 0, pf.getImageableWidth(), pf.getImageableHeight()));
60         g2.translate(-page * pf.getImageableWidth(), 0);
61         g2.scale(scale, scale);
62         FontRenderContext context = g2.getFontRenderContext();
63         var f = new Font("Serif", Font.PLAIN, 72);
64         var layout = new TextLayout(message, f, context);
65         AffineTransform transform = AffineTransform.getTranslateInstance(0, layout.getAscent());
66         Shape outline = layout.getOutline(transform);
```

```
67     g2.draw(outline);
68 }
69 
70 /**
71  * Draws 1/2" crop marks in the corners of the page.
72  * @param g2 the graphics context
73  * @param pf the page format
74 */
75 public void drawCropMarks(Graphics2D g2, PageFormat pf)
76 {
77     final double C = 36; // crop mark length = 1/2 inch
78     double w = pf.getImageableWidth();
79     double h = pf.getImageableHeight();
80     g2.draw(new Line2D.Double(0, 0, 0, C));
81     g2.draw(new Line2D.Double(0, 0, C, 0));
82     g2.draw(new Line2D.Double(w, 0, w, C));
83     g2.draw(new Line2D.Double(w, 0, w - C, 0));
84     g2.draw(new Line2D.Double(0, h, 0, h - C));
85     g2.draw(new Line2D.Double(0, h, C, h));
86     g2.draw(new Line2D.Double(w, h, w, h - C));
87     g2.draw(new Line2D.Double(w, h, w - C, h));
88 }
89 }
90 /**
91  * This class prints a cover page with a title.
92  */
93 class CoverPage implements Printable
94 {
95     private String title;
96 
97     /**
98      * Constructs a cover page.
99      * @param t the title
100     */
101    public CoverPage(String t)
102    {
103        title = t;
104    }
105 
106    public int print(Graphics g, PageFormat pf, int page) throws PrinterException
107    {
108        if (page >= 1) return Printable.NO_SUCH_PAGE;
109        var g2 = (Graphics2D) g;
110        g2.setPaint(Color.black);
111        g2.translate(pf.getImageableX(), pf.getImageableY());
112        FontRenderContext context = g2.getFontRenderContext();
113        Font f = g2.getFont();
114        var layout = new TextLayout(title, f, context);
```

```
116     float ascent = layout.getAscent();
117     g2.drawString(title, 0, ascent);
118     return Printable.PAGE_EXISTS;
119 }
120 }
```

```
1 package book;
2
3 import java.awt.*;
4 import java.awt.print.*;
5
6 import javax.swing.*;
7
8 /**
9  * This class implements a generic print preview dialog.
10 */
11 public class PrintPreviewDialog extends JDialog
12 {
13     private static final int DEFAULT_WIDTH = 300;
14     private static final int DEFAULT_HEIGHT = 300;
15
16     private PrintPreviewCanvas canvas;
17
18     /**
19      * Constructs a print preview dialog.
20      * @param p a Printable
21      * @param pf the page format
22      * @param pages the number of pages in p
23      */
24     public PrintPreviewDialog(Printable p, PageFormat pf, int pages)
25     {
26         var book = new Book();
27         book.append(p, pf, pages);
28         layoutUI(book);
29     }
30
31     /**
32      * Constructs a print preview dialog.
33      * @param b a Book
34      */
35     public PrintPreviewDialog(Book b)
36     {
37         layoutUI(b);
38     }
}
```

```
39
40     /**
41      * Lays out the UI of the dialog.
42      * @param book the book to be previewed
43      */
44     public void layoutUI(Book book)
45     {
46         setSize(DEFAULT_WIDTH, DEFAULT_HEIGHT);
47
48         canvas = new PrintPreviewCanvas(book);
49         add(canvas, BorderLayout.CENTER);
50
51         var buttonPanel = new JPanel();
52
53         var nextButton = new JButton("Next");
54         buttonPanel.add(nextButton);
55         nextButton.addActionListener(event -> canvas.flipPage(1));
56
57         var previousButton = new JButton("Previous");
58         buttonPanel.add(previousButton);
59         previousButton.addActionListener(event -> canvas.flipPage(-1));
56
60         var closeButton = new JButton("Close");
61         buttonPanel.add(closeButton);
62         closeButton.addActionListener(event -> setVisible(false));
63
64         add(buttonPanel, BorderLayout.SOUTH);
65     }
66 }
67 }
```

```
1 package book;
2
3 import java.awt.*;
4 import java.awt.geom.*;
5 import java.awt.print.*;
6 import javax.swing.*;
7
8 /**
9  * The canvas for displaying the print preview.
10 */
11 class PrintPreviewCanvas extends JComponent
12 {
13     private Book book;
14     private int currentPage;
15 }
```

```
16  /**
17  * Constructs a print preview canvas.
18  * @param b the book to be previewed
19  */
20  public PrintPreviewCanvas(Book b)
21  {
22      book = b;
23      currentPage = 0;
24  }
25
26  public void paintComponent(Graphics g)
27  {
28      var g2 = (Graphics2D) g;
29      PageFormat pageFormat = book.getPageFormat(currentPage);
30
31      double xoff; // x offset of page start in window
32      double yoff; // y offset of page start in window
33      double scale; // scale factor to fit page in window
34      double px = pageFormat.getWidth();
35      double py = pageFormat.getHeight();
36      double sx = getWidth() - 1;
37      double sy = getHeight() - 1;
38      if (px / py < sx / sy) // center horizontally
39      {
40          scale = sy / py;
41          xoff = 0.5 * (sx - scale * px);
42          yoff = 0;
43      }
44      else
45          // center vertically
46      {
47          scale = sx / px;
48          xoff = 0;
49          yoff = 0.5 * (sy - scale * py);
50      }
51      g2.translate((float) xoff, (float) yoff);
52      g2.scale((float) scale, (float) scale);
53
54      // draw page outline (ignoring margins)
55      var page = new Rectangle2D.Double(0, 0, px, py);
56      g2.setPaint(Color.white);
57      g2.fill(page);
58      g2.setPaint(Color.black);
59      g2.draw(page);
60
61      Printable printable = book.getPrintable(currentPage);
```

```
62     try
63     {
64         printable.print(g2, pageFormat, currentPage);
65     }
66     catch (PrinterException e)
67     {
68         g2.draw(new Line2D.Double(0, 0, px, py));
69         g2.draw(new Line2D.Double(px, 0, 0, py));
70     }
71 }
72 /**
73 * Flip the book by the given number of pages.
74 * @param by the number of pages to flip by. Negative values flip backwards.
75 */
76 public void flipPage(int by)
77 {
78     int newPage = currentPage + by;
79     if (0 <= newPage && newPage < book.getNumberOfPages())
80     {
81         currentPage = newPage;
82         repaint();
83     }
84 }
85 }
86 }

DocFlavor flavor = DocFlavor.INPUT_STREAM.GIF;
PrintService[] services = PrintServiceLookup.lookupPrintServices(flavor, null);

DocPrintJob job = services[i].createPrintJob();

var in = new FileInputStream(fileName);
var doc = new SimpleDoc(in, flavor, null);

DocFlavor flavor = DocFlavor.SERVICE_FORMATTED.PRINTABLE;
String mimeType = "application/postscript";
StreamPrintServiceFactory[] factories
    = StreamPrintServiceFactory.lookupStreamPrintServiceFactories(flavor, mimeType);
```

```
var out = new FileOutputStream(fileName);
StreamPrintService service = factories[0].getPrintService(out);

private static int IMAGE_WIDTH = component.getWidth();
private static int IMAGE_HEIGHT = component.getHeight();
public static void draw(Graphics2D g2) { component.paint(g2); }
```

```
1 package printService;
2
3 import java.awt.*;
4 import java.awt.font.*;
5 import java.awt.geom.*;
6 import java.awt.print.*;
7 import java.io.*;
8 import javax.print.*;
9 import javax.print.attribute.*;

10 /**
11  * This program demonstrates the use of stream print services. The program prints
12  * Java 2D shapes to a PostScript file. If you don't supply a file name on the command
13  * line, the output is saved to out.ps.
14  * @version 1.0 2018-06-01
15  * @author Cay Horstmann
16  */
17
18 public class PrintServiceTest
19 {
20     // Set your image dimensions here
21     private static int IMAGE_WIDTH = 300;
22     private static int IMAGE_HEIGHT = 300;
23
24     public static void draw(Graphics2D g2)
25     {
26         // Your drawing instructions go here
27         FontRenderContext context = g2.getFontRenderContext();
28         var f = new Font("Serif", Font.PLAIN, 72);
29         var clipShape = new GeneralPath();
30
31         var layout = new TextLayout("Hello", f, context);
32         AffineTransform transform = AffineTransform.getTranslateInstance(0, 72);
33         Shape outline = layout.getOutline(transform);
34         clipShape.append(outline, false);
35
36         layout = new TextLayout("World", f, context);
37         transform = AffineTransform.getTranslateInstance(0, 144);
38         outline = layout.getOutline(transform);
39         clipShape.append(outline, false);
40
41         g2.draw(clipShape);
42         g2.clip(clipShape);
43
44         final int N_LINES = 50;
45         var p = new Point2D.Double(0, 0);
```

```
46     for (int i = 0; i < NLINES; i++)
47     {
48         double x = (2 * IMAGE_WIDTH * i) / NLINES;
49         double y = (2 * IMAGE_HEIGHT * (NLINES - 1 - i)) / NLINES;
50         var q = new Point2D.Double(x, y);
51         g2.draw(new Line2D.Double(p, q));
52     }
53 }
54
55 public static void main(String[] args) throws IOException, PrintException
56 {
57     String fileName = args.length > 0 ? args[0] : "out.ps";
58     DocFlavor flavor = DocFlavor.SERVICE_FORMATTED.PRINTABLE;
59     String mimeType = "application/postscript";
60     StreamPrintServiceFactory[] factories
61         = StreamPrintServiceFactory.lookupStreamPrintServiceFactories(flavor, mimeType);
62     var out = new FileOutputStream(fileName);
63     if (factories.length > 0)
64     {
65         PrintService service = factories[0].getPrintService(out);
66         var doc = new SimpleDoc(new Printable()
67         {
68             public int print(Graphics g, PageFormat pf, int page)
69             {
70                 if (page >= 1) return Printable.NO_SUCH_PAGE;
71                 else
72                 {
73                     double sf1 = pf.getImageableWidth() / (IMAGE_WIDTH + 1);
74                     double sf2 = pf.getImageableHeight() / (IMAGE_HEIGHT + 1);
75                     double s = Math.min(sf1, sf2);
76                     var g2 = (Graphics2D) g;
77                     g2.translate((pf.getWidth() - pf.getImageableWidth()) / 2,
78                         (pf.getHeight() - pf.getImageableHeight()) / 2);
79                     g2.scale(s, s);
80
81                     draw(g2);
82                     return Printable.PAGE_EXISTS;
83                 }
84             }
85         }, flavor, null);
86         DocPrintJob job = service.createPrintJob();
87         var attributes = new HashPrintRequestAttributeSet();
88         job.print(doc, attributes);
89     }
90     else
91         System.out.println("No factories for " + mimeType);
92 }
93 }
```

```
PrintRequestAttributeSet  
DocAttributeSet  
PrintServiceAttributeSet  
PrintJobAttributeSet  
  
HashAttributeSet  
HashPrintRequestAttributeSet  
HashDocAttributeSet  
HashPrintServiceAttributeSet  
HashPrintJobAttributeSet  
  
var attributes = new HashPrintRequestAttributeSet();  
  
attributes.add(new Copies(10));  
  
AttributeSet attributes = job.getAttributes();  
var copies = (Copies) attribute.get(Copies.class);  
  
attributes.add(PrintQuality.HIGH);  
  
if (attributes.get(PrintQuality.class) == PrintQuality.HIGH)  
    . . .
```

```
1 /**
2  * @version 1.11 2007-10-26
3  * @author Cay Horstmann
4  */
5 class HelloNative
6 {
7     public static native void greeting();
8 }
```

```
1 /* DO NOT EDIT THIS FILE - it is machine generated */
2 #include <jni.h>
3 /* Header for class HelloNative */
4
5 #ifndef _Included_HelloNative
6 #define _Included_HelloNative
7 #ifdef __cplusplus
8 extern "C" {
9 #endif
10 /*
11  * Class:    HelloNative
12  * Method:   greeting
13  * Signature: ()V
14  */
15 JNIEXPORT void JNICALL Java_HelloNative_greeting
16     (JNIEnv *, jclass);
17
18 #ifdef __cplusplus
19 }
20 #endif
21 #endif
```

```
1 /*
2  * @version 1.10 1997-07-01
3  * @author Cay Horstmann
4 */
5
6 #include "HelloNative.h"
7 #include <stdio.h>
8
9 JNIEXPORT void JNICALL Java_HelloNative_greeting(JNIEnv* env, jclass cl)
10 {
11     printf("Hello, Native World!\n");
12 }
```

```
extern "C"
JNIEXPORT void JNICALL Java_HelloNative_greeting(JNIEnv* env, jclass cl)
{
    cout << "Hello, Native World!" << endl;
}
```

```
gcc -fPIC -I jdk/include -I jdk/include/linux -shared -o libHelloNative.so HelloNative.c
```

```
cl -I jdk\include -I jdk\include\win32 -LD HelloNative.c -FeHelloNative.dll
```

```
gcc -mno-cygwin -D __int64="long long" -I jdk/include/ -I jdk/include/win32 \
    -shared -Wl,--addstdcall-alias -o HelloNative.dll HelloNative.c
```

```
#ifdef __GNUC__
    typedef long long jlong;
#else
    typedef __int64 jlong;
#endif
```

```
1 /**
2  * @version 1.11 2007-10-26
3  * @author Cay Horstmann
4 */
5 class HelloNativeTest
6 {
7     public static void main(String[] args)
8     {
```

```
9     HelloNative.greeting();
10    }
11
12    static
13    {
14        System.loadLibrary("HelloNative");
15    }
16 }
```

```
export LD_LIBRARY_PATH=.:$LD_LIBRARY_PATH

java -Djava.library.path=. HelloNativeTest

jint JNI_OnLoad(JavaVM* vm, void* reserved);
void JNI_OnUnload(JavaVM* vm, void* reserved);

1 /**
2  * @version 1.10 1997-07-01
3  * @author Cay Horstmann
4  */
5 class Printf1
6 {
7     public static native int print(int width, int precision, double x);
8
9     static
10    {
11        System.loadLibrary("Printf1");
12    }
13 }
```

```
1 /**
2  * @version 1.10 1997-07-01
3  * @author Cay Horstmann
4 */
5
6 #include "Printfl.h"
7 #include <stdio.h>
8
9 JNIEXPORT jint JNICALL Java_Printfl_print(JNIEnv* env, jclass cl,
10     jint width, jint precision, jdouble x)
11 {
12     char fmt[30];
13     jint ret;
14     sprintf(fmt, "%%d.%df", width, precision);
15     ret = printf(fmt, x);
16     fflush(stdout);
17     return ret;
18 }
```

```
1 /**
2  * @version 1.10 1997-07-01
3  * @author Cay Horstmann
4 */
5 class PrintflTest
6 {
7     public static void main(String[] args)
8     {
9         int count = Printfl.print(8, 4, 3.14);
10        count += Printfl.print(8, 4, count);
11        System.out.println();
12        for (int i = 0; i < count; i++)
13            System.out.print("-");
14        System.out.println();
15    }
16 }
```

```
JNIEXPORT jstring JNICALL Java_HelloNative_getGreeting(JNIEnv* env, jclass cl)
{
    jstring jstr;
    char greeting[] = "Hello, Native World\n";
    jstr = (*env)->NewStringUTF(env, greeting);
    return jstr;
}
```

```
jstr = env->NewStringUTF(greeting);
```

```
1 /**
2  * @version 1.10 1997-07-01
3  * @author Cay Horstmann
4  */
5 class Printf2Test
6 {
7     public static void main(String[] args)
8     {
9         double price = 44.95;
10        double tax = 7.75;
11        double amountDue = price * (1 + tax / 100);
12
13        String s = Printf2.sprintf("Amount due = %8.2f", amountDue);
14        System.out.println(s);
15    }
16 }
```

```
1 /**
2  * @version 1.10 1997-07-01
3  * @author Cay Horstmann
4  */
5 class Printf2
6 {
7     public static native String sprintf(String format, double x);
8
9     static
10    {
11        System.loadLibrary("Printf2");
12    }
13 }
```

```
JNIEXPORT jstring JNICALL Java_Printf2_sprint(JNIEnv* env, jclass cl,
jstring format, jdouble x)
```

```

1  /**
2   * @version 1.10 1997-07-01
3   * @author Cay Horstmann
4  */
5
6 #include "Printf2.h"
7 #include <string.h>
8 #include <stdlib.h>
9 #include <float.h>
10
11 /**
12  * @param format a string containing a printf format specifier
13  * (such as "%8.2f"). Substrings "%%" are skipped.
14  * @return a pointer to the format specifier (skipping the '%')
15  * or NULL if there wasn't a unique format specifier
16 */
17 char* find_format(const char format[])
18 {
19     char* p;
20     char* q;
21
22     p = strchr(format, '%');
23     while (p != NULL && *(p + 1) == '%') /* skip %% */
24         p = strchr(p + 2, '%');
25     if (p == NULL) return NULL;
26     /* now check that % is unique */
27     p++;
28     q = strchr(p, '%');
29     while (q != NULL && *(q + 1) == '%') /* skip %% */
30         q = strchr(q + 2, '%');
31     if (q != NULL) return NULL; /* % not unique */
32     q = p + strspn(p, "-0+#"); /* skip past flags */
33     q += strspn(q, "0123456789"); /* skip past field width */
34     if (*q == '.') { q++; q += strspn(q, "0123456789"); }
35     /* skip past precision */
36     if (strchr("eEfFgG", *q) == NULL) return NULL;
37     /* not a floating-point format */
38     return p;
39 }
40
41 JNIEXPORT jstring JNICALL Java_Printf2_sprint(JNIEnv* env, jclass cl,
42     jstring format, jdouble x)
43 {
44     const char* cformat;
45     char* fmt;
46     jstring ret;
47
48     cformat = (*env)->GetStringUTFChars(env, format, NULL);

```

```
49     fmt = find_format(cformat);
50     if (fmt == NULL)
51         ret = format;
52     else
53     {
54         char* cret;
55         int width = atoi(fmt);
56         if (width == 0) width = DBL_DIG + 10;
57         cret = (char*) malloc(strlen(cformat) + width);
58         sprintf(cret, cformat, x);
59         ret = (*env)->NewStringUTF(env, cret);
60         free(cret);
61     }
62     (*env)->ReleaseStringUTFChars(env, format, cformat);
63     return ret;
64 }
```

```
public void raiseSalary(double byPercent)
{
    salary *= 1 + byPercent / 100;
}
```

```
JNIEXPORT void JNICALL Java_Employee_raiseSalary(JNIEnv *, jobject, jdouble);
```

```
x = (*env)->GetXxxField(env, this_obj, fieldID);
(*env)->SetXxxField(env, this_obj, fieldID, x);
```

```
jclass class_Employee = (*env)->GetObjectClass(env, this_obj);
```

```
jclass class_String = (*env)->FindClass(env, "java/lang/String");
```

```
jfieldID id_salary = (*env)->GetFieldID(env, class_Employee, "salary", "D");
```

```
JNIEXPORT void JNICALL Java_Employee_raiseSalary(JNIEnv* env, jobject this_obj,
    jdouhle byPercent)
{
    /* get the class */
    jclass class_Employee = (*env)->GetObjectClass(env, this_obj);

    /* get the field ID */
    jfieldID id_salary = (*env)->GetFieldID(env, class_Employee, "salary", "D");

    /* get the field value */
    jdouble salary = (*env)->GetDoubleField(env, this_obj, id_salary);

    salary *= 1 + byPercent / 100;

    /* set the field value */
    (*env)->SetDoubleField(env, this_obj, id_salary, salary);
}

static jclass class_X = 0;
static jfieldID id_a;
. . .
if (class_X == 0)
{
    jclass cx = (*env)->GetObjectClass(env, obj);
    class_X = (*env)->NewGlobalRef(env, cx);
    id_a = (*env)->GetFieldID(env, class_X, "a", ". . .");
}
```

```
1 /**
2  * @version 1.11 2018-05-01
3  * @author Cay Horstmann
4 */
5
6 public class EmployeeTest
7 {
8     public static void main(String[] args)
9     {
10         var staff = new Employee[3];
11
12         staff[0] = new Employee("Harry Hacker", 35000);
13         staff[1] = new Employee("Carl Cracker", 75000);
14         staff[2] = new Employee("Tony Tester", 38000);
15
16         for (Employee e : staff)
17             e.raiseSalary(5);
18         for (Employee e : staff)
19             e.print();
20     }
21 }
```

```
1  /**
2   * @version 1.10 1999-11-13
3   * @author Cay Horstmann
4   */
5
6 public class Employee
7 {
8     private String name;
9     private double salary;
10
11    public native void raiseSalary(double byPercent);
12
13    public Employee(String n, double s)
14    {
15        name = n;
16        salary = s;
17    }
18
19    public void print()
20    {
21        System.out.println(name + " " + salary);
22    }
23
24    static
25    {
26        System.loadLibrary("Employee");
27    }
28 }
```

```
1  /*  
2   * @version 1.10 1999-11-13  
3   * @author Cay Horstmann  
4  */  
5  
6 #include "Employee.h"  
7  
8 #include <stdio.h>  
9  
10 JNIEXPORT void JNICALL Java_Employee_raiseSalary(  
11     JNIEnv* env, jobject this_obj, jdouble byPercent)  
12 {  
13     /* get the class */  
14     jclass class_Employee = (*env)->GetObjectClass(env, this_obj);  
15  
16     /* get the field ID */  
17     jfieldID id_salary = (*env)->GetFieldID(env, class_Employee, "salary", "D");  
18  
19     /* get the field value */  
20     jdouble salary = (*env)->GetDoubleField(env, this_obj, id_salary);  
21  
22     salary *= 1 + byPercent / 100;  
23  
24     /* set the field value */  
25     (*env)->SetDoubleField(env, this_obj, id_salary, salary);  
26 }  
27

---

  
/* get the class */  
jclass class_System = (*env)->FindClass(env, "java/lang/System");  
  
/* get the field ID */  
jfieldID id_out = (*env)->GetStaticFieldID(env, class_System, "out",  
    "Ljava/io/PrintStream;");  
  
/* get the field value */  
jobject obj_out = (*env)->GetStaticObjectField(env, class_System, id_out);  
  
(Ljava/lang/String;D)Ljava/lang/String;
```

```
Employee(java.lang.String, double, java.util.Date)
        "(Ljava/lang/String;DLjava/util/Date;)V"

Compiled from "Employee.java"
public class Employee extends java.lang.Object{
    private java.lang.String name;
        Signature: Ljava/lang/String;
    private double salary;
        Signature: D
    public Employee(java.lang.String, double);
        Signature: (Ljava/lang/String;D)V
    public native void raiseSalary(double);
        Signature: (D)V
    public void print();
        Signature: ()V
    static {};
        Signature: ()V
}

class Printf3
{
    public native static void fprintf(PrintWriter out, String s, double x);
    ...
}

(*env)->CallXxxMethod(env, implicit parameter, methodID, explicit parameters)
/* get the class of the implicit parameter */
class_PrintWriter = (*env)->GetObjectClass(env, out);

/* get the method ID */
id_print = (*env)->GetMethodID(env, class_PrintWriter, "print", "(Ljava/lang/String;)V");

/* call the method */
(*env)->CallVoidMethod(env, out, id_print, str);
```

```
 jobject ToReflectedMethod(JNIEnv* env, jclass class, jmethodID methodID);
    // returns Method object
jmethodID FromReflectedMethod(JNIEnv* env, jobject method);
jobject ToReflectedField(JNIEnv* env, jclass class, jfieldID fieldID);
    // returns Field object
jfieldID FromReflectedField(JNIEnv* env, jobject field);

System.getProperty("java.class.path")

jclass class_System = (*env)->FindClass(env, "java/lang/System");

"(Ljava/lang/String;)Ljava/lang/String;"

jmethodID id_getProperty = (*env)->GetStaticMethodID(env, class_System, "getProperty",
    "(Ljava/lang/String;)Ljava/lang/String;");

jobject obj_ret = (*env)->CallStaticObjectMethod(env, class_System, id_getProperty,
    (*env)->NewStringUTF(env, "java.class.path"));

jstring str_ret = (jstring) obj_ret;

jobject obj_new = (*env)->NewObject(env, class, methodID, construction parameters);

const char[] fileName = "...";
jstring str_fileName = (*env)->NewStringUTF(env, fileName);
jclass class_FileOutputStream = (*env)->FindClass(env, "java/io/FileOutputStream");
jmethodID id_FileOutputStream
    = (*env)->GetMethodID(env, class_FileOutputStream, "<init>", "(Ljava/lang/String;)V");
jobject obj_stream
    = (*env)->NewObject(env, class_FileOutputStream, id_FileOutputStream, str_fileName);
```

```
1 import java.io.*;
2
3 /**
4  * @version 1.11 2018-05-01
5  * @author Cay Horstmann
6  */
7 class Printf3Test
8 {
9     public static void main(String[] args)
10    {
11        double price = 44.95;
12        double tax = 7.75;
13        double amountDue = price * (1 + tax / 100);
14        var out = new PrintWriter(System.out);
15        Printf3.fprintf(out, "Amount due = %8.2f\n", amountDue);
16        out.flush();
17    }
18 }
```

```
1 import java.io.*;
2
3 /**
4  * @version 1.10 1997-07-01
5  * @author Cay Horstmann
6  */
7 class Printf3
8 {
9     public static native void fprintf(PrintWriter out, String format, double x);
10
11     static
12     {
13         System.loadLibrary("Printf3");
14     }
15 }
```

```
1 /**
2  * @version 1.10 1997-07-01
3  * @author Cay Horstmann
4  */
```

```
5
6 #include "Printf3.h"
7 #include <string.h>
8 #include <stdlib.h>
9 #include <float.h>
10
11 /**
12  * @param format a string containing a printf format specifier
13  * (such as "%8.2f"). Substrings "%%" are skipped.
14  * @return a pointer to the format specifier (skipping the '%')
15  * or NULL if there wasn't a unique format specifier
16 */
17 char* find_format(const char format[])
18 {
19     char* p;
20     char* q;
21
22     p = strchr(format, '%');
23     while (p != NULL && *(p + 1) == '%') /* skip %% */
24         p = strchr(p + 2, '%');
25     if (p == NULL) return NULL;
26     /* now check that % is unique */
27     p++;
28     q = strchr(p, '%');
29     while (q != NULL && *(q + 1) == '%') /* skip %% */
30         q = strchr(q + 2, '%');
31     if (q != NULL) return NULL; /* % not unique */
32     q = p + strspn(p, " -0+.#"); /* skip past flags */
33     q += strspn(q, "0123456789"); /* skip past field width */
34     if (*q == '.') { q++; q += strspn(q, "0123456789"); }
35     /* skip past precision */
36     if (strchr("eEfFgG", *q) == NULL) return NULL;
37     /* not a floating-point format */
38     return p;
39 }
40
41 JNIEEXPORT void JNICALL Java_Printf3_fprint(JNIEnv* env, jclass cl,
42     jobject out, jstring format, jdouble x)
43 {
44     const char* cformat;
45     char* fmt;
46     jstring str;
47     jclass class_PrintWriter;
48     jmethodID id_print;
49
50     cformat = (*env)->GetStringUTFChars(env, format, NULL);
51     fmt = find_format(cformat);
52     if (fmt == NULL)
53         str = format;
```

```
54     else
55     {
56         char* cstr;
57         int width = atoi(fmt);
58         if (width == 0) width = DBL_DIG + 10;
59         cstr = (char*) malloc(strlen(cformat) + width);
60         sprintf(cstr, cformat, x);
61         str = (*env)->NewStringUTF(env, cstr);
62         free(cstr);
63     }
64     (*env)->ReleaseStringUTFChars(env, format, cformat);
65
66     /* now call out.print(str) */
67
68     /* get the class */
69     class_PrintWriter = (*env)->GetObjectClass(env, out);
70
71     /* get the method ID */
72     id_print = (*env)->GetMethodID(env, class_PrintWriter, "print", "(Ljava/lang/String;)V");
73
74     /* call the method */
75     (*env)->CallVoidMethod(env, out, id_print, str);
76 }
```

```
jarray array = . . .;
jsize length = (*env)->GetArrayLength(env, array);

jobjectArray array = . . .;
int i, j;
jobject x = (*env)->GetObjectArrayElement(env, array, i);
(*env)->SetObjectArrayElement(env, array, j, x);

jdoubleArray array_a = . . .;
double scaleFactor = . . .;
double* a = (*env)->GetDoubleArrayElements(env, array_a, NULL);
for (i = 0; i < (*env)->GetArrayLength(env, array_a); i++)
    a[i] = a[i] * scaleFactor;
(*env)->ReleaseDoubleArrayElements(env, array_a, a, 0);
```

```
jclass class_Employee = (*env)->FindClass(env, "Employee");
jobjectArray array_e = (*env)->NewObjectArray(env, 100, class_Employee, NULL);

jdoubleArray array_d = (*env)->NewDoubleArray(env, 100);

jobject NewDirectByteBuffer(JNIEnv* env, void* address, jlong capacity)
void* GetDirectBufferAddress(JNIEnv* env, jobject buf)
jlong GetDirectBufferCapacity(JNIEnv* env, jobject buf)

jclass class_EOFException = (*env)->FindClass(env, "java/io/EOFException");
jmethodID id_EOFException = (*env)->GetMethodID(env, class_EOFException, "<init>", "()V");
/* ID of no-argument constructor */
jthrowable obj_exc = (*env)->NewObject(env, class_EOFException, id_EOFException);
(*env)->Throw(env, obj_exc);

(*env)->ThrowNew(env, (*env)->FindClass(env, "java/io/EOFException"),
    "Unexpected end of file");

jthrowable obj_exc = (*env)->ExceptionOccurred(env);

jboolean occurred = (*env)->ExceptionCheck(env);

1 /**
2  *version 1.10 1997-07-01
3  *author Cay Horstmann
4 */
5
6 #include "Printf4.h"
7 #include <string.h>
8 #include <stdlib.h>
9 #include <float.h>
10
11 /**
12  *param format a string containing a printf format specifier
13  *(such as "%8.2f"). Substrings "%%" are skipped.
14  *return a pointer to the format specifier (skipping the '%')
15  *or NULL if there wasn't a unique format specifier
16 */
```

```
17 char* find_format(const char format[])
18 {
19     char* p;
20     char* q;
21
22     p = strchr(format, '%');
23     while (p != NULL && *(p + 1) == '%') /* skip %% */
24         p = strchr(p + 2, '%');
25     if (p == NULL) return NULL;
26     /* now check that % is unique */
27     p++;
28     q = strchr(p, '%');
29     while (q != NULL && *(q + 1) == '%') /* skip %% */
30         q = strchr(q + 2, '%');
31     if (q != NULL) return NULL; /* % not unique */
32     q = p + strspn(p, " -0#"); /* skip past flags */
33     q += strspn(q, "0123456789"); /* skip past field width */
34     if (*q == '.') { q++; q += strspn(q, "0123456789"); }
35     /* skip past precision */
36     if (strchr("eEfFgG", *q) == NULL) return NULL;
37     /* not a floating-point format */
38     return p;
39 }
40
41 JNIEXPORT void JNICALL Java_Printf4_fprint(JNIEnv* env, jclass cl,
42     jobject out, jstring format, jdouble x)
43 {
44     const char* cformat;
45     char* fmt;
46     jclass class_PrintWriter;
47     jmethodID id_print;
48     char* cstr;
49     int width;
50     int i;
51
52     if (format == NULL)
53     {
54         (*env)->ThrowNew(env,
55             (*env)->FindClass(env,
56                 "java/lang/NullPointerException"),
57                 "Printf4.fprint: format is null");
58         return;
59     }
60
61     cformat = (*env)->GetStringUTFChars(env, format, NULL);
62     fmt = find_format(cformat);
63 }
```

```
64     if (fmt == NULL)
65     {
66         (*env)->ThrowNew(env,
67             (*env)->FindClass(env,
68                 "java/lang/IllegalArgumentException"),
69                 "Printf4.fprintf: format is invalid");
70         return;
71     }
72
73     width = atoi(fmt);
74     if (width == 0) width = DBL_DIG + 10;
75     cstr = (char*)malloc(strlen(cformat) + width);
76
77     if (cstr == NULL)
78     {
79         (*env)->ThrowNew(env,
80             (*env)->FindClass(env, "java/lang/DutOfMemoryError"),
81                 "Printf4.fprintf: malloc failed");
82         return;
83     }
84
85     sprintf(cstr, cformat, x);
86
87     (*env)->ReleaseStringUTFChars(env, format, cformat);
88
89     /* now call ps.print(str) */
90
91     /* get the class */
92     class_PrintWriter = (*env)->GetObjectClass(env, out);
93
94     /* get the method ID */
95     id_print = (*env)->GetMethodID(env, class_PrintWriter, "print", "(C)V");
96
97     /* call the method */
98     for (i = 0; cstr[i] != 0 && !(*env)->ExceptionOccurred(env); i++)
99         (*env)->CallVoidMethod(env, out, id_print, cstr[i]);
100
101     free(cstr);
102 }
```

```
1 import java.io.*;
2
3 /**
4  * @version 1.10 1997-07-01
5  * @author Cay Horstmann
6  */
7
7 class Printf4
8 {
9     public static native void fprintf(PrintWriter ps, String format, double x);
10
11    static
12    {
13        System.loadLibrary("Printf4");
14    }
15 }
```

```
1 import java.io.*;
2
3 /**
4  * @version 1.11 2018-05-01
5  * @author Cay Horstmann
6  */
7
7 class Printf4Test
8 {
9     public static void main(String[] args)
10    {
11        double price = 44.95;
12        double tax = 7.75;
13        double amountDue = price * (1 + tax / 100);
14        var out = new PrintWriter(System.out);
15        /* This call will throw an exception--note the %% */
16        Printf4fprintf(out, "Amount due = %%8.2f\n", amountDue);
17        out.flush();
18    }
19 }
```

```
JavaVMOption options[1];
JavaVMInitArgs vm_args;
JavaVM *jvm;
JNINativeInterface *env;

options[0].optionString = "-Djava.class.path=.";

memset(&vm_args, 0, sizeof(vm_args));
vm_args.version = JNI_VERSION_1_2;
vm_args.nOptions = 1;
vm_args.options = options;

JNI_CreateJavaVM(&jvm, (void**) &env, &vm_args);

options[i].optionString = "-Djava.compiler=NONE";

options[i].optionString = "-verbose:jni";

1 /**
2  * @version 1.20 2007-10-26
3  * @author Cay Horstmann
4 */
5
6 #include <jni.h>
7 #include <stdlib.h>
8
9 #ifdef _WINDOWS
10
11 #include <windows.h>
12 static HINSTANCE loadJVMLibrary(void);
13 typedef jint (JNICALL *CreateJavaVM_t)(JavaVM **, void **, JavaVMInitArgs *);
14
```

```
15 #endif
16
17 int main()
18 {
19     JavaVMOption options[2];
20     JavaVMInitArgs vm_args;
21     JavaVM *jvm;
22     JNIEnv *env;
23     long status;
24
25     jclass class_Welcome;
26     jclass class_String;
27     jobjectArray args;
28     jmethodID id_main;
29
30 #ifdef _WIN32
31     HINSTANCE hjvmlib;
32     CreateJavaVM_t createJavaVM;
33 #endif
34
35     options[0].optionString = "-Djava.class.path=.";
36
37     memset(&vm_args, 0, sizeof(vm_args));
38     vm_args.version = JNI_VERSION_1_2;
39     vm_args.nOptions = 1;
40     vm_args.options = options;
41
42 #ifdef _WIN32
43     hjvmlib = loadJVMLibrary();
44     createJavaVM = (CreateJavaVM_t) GetProcAddress(hjvmlib, "JNI_CreateJavaVM");
45     status = (*createJavaVM)(&jvm, (void **) &env, &vm_args);
46 #else
47     status = JNI_CreateJavaVM(&jvm, (void **) &env, &vm_args);
48 #endif
49
50     if (status == JNI_ERR)
51     {
52         fprintf(stderr, "Error creating VM\n");
53         return 1;
54     }
55
56     class_Welcome = (*env)->FindClass(env, "Welcome");
57     id_main = (*env)->GetStaticMethodID(env, class_Welcome, "main", "([Ljava/lang/String;)V");
58
59     class_String = (*env)->FindClass(env, "java/lang/String");
60     args = (*env)->NewObjectArray(env, 0, class_String, NULL);
61     (*env)->CallStaticVoidMethod(env, class_Welcome, id_main, args);
62
```

```
63     (*jvm) ->DestroyJavaVM(jvm);
64
65     return 0;
66 }
67
68 #ifdef _WINDOWS
69
70 static int GetStringFromRegistry(HKEY key, const char *name, char *buf, jint bufsize)
71 {
72     DWORD type, size;
73
74     return RegQueryValueEx(key, name, 0, &type, 0, &size) == 0
75         && type == REG_SZ
76         && size < (unsigned int) bufsize
77         && RegQueryValueEx(key, name, 0, 0, buf, &size) == 0;
78 }
79
80 static void GetPublicJREHome(char *buf, jint bufsize)
81 {
82     HKEY key, subkey;
83     char version[MAX_PATH];
84
85     /* Find the current version of the JRE */
86     char *JRE_KEY = "Software\\JavaSoft\\Java Runtime Environment";
87     if (RegOpenKeyEx(HKEY_LOCAL_MACHINE, JRE_KEY, 0, KEY_READ, &key) != 0)
88     {
89         fprintf(stderr, "Error opening registry key '%s'\n", JRE_KEY);
90         exit(1);
91     }
92
93     if (!GetStringFromRegistry(key, "CurrentVersion", version, sizeof(version)))
94     {
95         fprintf(stderr, "Failed reading value of registry key:\n\t%s\\CurrentVersion\n",
96                 JRE_KEY);
97         RegCloseKey(key);
98         exit(1);
99     }
100
101    /* Find directory where the current version is installed. */
102    if (RegOpenKeyEx(key, version, 0, KEY_READ, &subkey) != 0)
103    {
104        fprintf(stderr, "Error opening registry key '%s\\%s'\n", JRE_KEY, version);
105        RegCloseKey(key);
106        exit(1);
107    }
108
109    if (!GetStringFromRegistry(subkey, "JavaHome", buf, bufsize))
110    {
```

```
111     fprintf(stderr, "Failed reading value of registry key:\n\t%s\\%s\\JavaHome\n",
112             JRE_KEY, version);
113     RegCloseKey(key);
114     RegCloseKey(subkey);
115     exit(1);
116 }
117
118 RegCloseKey(key);
119 RegCloseKey(subkey);
120 }
121
122 static HINSTANCE loadJVMLibrary(void)
123 {
124     HINSTANCE h1, h2;
125     char msvcdll[MAX_PATH];
126     char javadll[MAX_PATH];
127     GetPublicJREHome(msvcdll, MAX_PATH);
128     strcpy(javadll, msvcdll);
129     strncat(msvcdll, "\\bin\\msvcr71.dll", MAX_PATH - strlen(msvcdll));
130     msvcdll[MAX_PATH - 1] = '\0';
131     strncat(javadll, "\\bin\\client\\jvm.dll", MAX_PATH - strlen(javadll));
132     javadll[MAX_PATH - 1] = '\0';
133
134     h1 = LoadLibrary(msvcdll);
135     if (h1 == NULL)
136     {
137         fprintf(stderr, "Can't load library msvcr71.dll\n");
138         exit(1);
139     }
140
141     h2 = LoadLibrary(javadll);
142     if (h2 == NULL)
143     {
144         fprintf(stderr, "Can't load library jvm.dll\n");
145         exit(1);
146     }
147     return h2;
148 }
149
150 #endif
```

```
gcc -I jdk/include -I jdk/include/linux -o InvocationTest \
-L jdk/jre/lib/i386/client -ljvm InvocationTest.c

cl -D WINDOWS -I jdk\include -I jdk\include\win32 InvocationTest.c \
jdk\lib\jvm.lib advapi32.lib

gcc -D_WINDOWS -mno-cygwin -I jdk\include -I jdk\include\win32 -D_int64="long long" \
-I c:\cygwin\usr\include\w32api -o InvocationTest

export LD_LIBRARY_PATH=jdk/jre/lib/i386/client:$LD_LIBRARY_PATH

HKEY_LOCAL_MACHINE\Software\JavaSoft\Java Runtime Environment

public class Win32RegKey
{
    public Win32RegKey(int theRoot, String thePath) { . . . }
    public Enumeration names() { . . . }
    public native Object getValue(String name);
    public native void setValue(String name, Object value);

    public static final int HKEY_CLASSES_ROOT = 0x80000000;
    public static final int HKEY_CURRENT_USER = 0x80000001;
    public static final int HKEY_LOCAL_MACHINE = 0x80000002;
    . .
}

(*env)->IsAssignableFrom(env, class1, class2)

(*env)->IsAssignableFrom(env, (*env)->GetObjectClass(env, value),
    (*env)->FindClass(env, "[B"])

cl -I jdk\include -I jdk\include\win32 -LD Win32RegKey.c advapi32.lib -FeWin32RegKey.dll

gcc -mno-cygwin -D _int64="long long" -I jdk\include -I jdk\include\win32 \
-I c:\cygwin\usr\include\w32api -shared -WL,--add-stdcall-alias -o Win32RegKey.dll
Win32RegKey.c

HKEY_CURRENT_USER\Software\JavaSoft\Java Runtime Environment
```

```
1 import java.util.*;
2
3 /**
4  * A Win32RegKey object can be used to get and set values of a registry key in the Windows
5  * registry.
6  * @version 1.00 1997-07-01
7  * @author Cay Horstmann
8  */
9 public class Win32RegKey
10 {
11     public static final int HKEY_CLASSES_ROOT = 0x80000000;
12     public static final int HKEY_CURRENT_USER = 0x80000001;
13     public static final int HKEY_LOCAL_MACHINE = 0x80000002;
14     public static final int HKEY_USERS = 0x80000003;
15     public static final int HKEY_CURRENT_CONFIG = 0x80000005;
16     public static final int HKEY_DYN_DATA = 0x80000006;
17
18     private int root;
19     private String path;
20
21     /**
22      * Gets the value of a registry entry.
23      * @param name the entry name
24      * @return the associated value
25      */
26     public native Object getValue(String name);
27
28     /**
29      * Sets the value of a registry entry.
30      * @param name the entry name
31      * @param value the new value
32      */
33     public native void setValue(String name, Object value);
34
35     /**
36      * Construct a registry key object.
37      * @param theRoot one of HKEY_CLASSES_ROOT, HKEY_CURRENT_USER, HKEY_LOCAL_MACHINE,
38      * HKEY_USERS, HKEY_CURRENT_CONFIG, HKEY_DYN_DATA
39      * @param thePath the registry key path
40      */
41     public Win32RegKey(int theRoot, String thePath)
42     {
```

```
43     root = theRoot;
44     path = thePath;
45 }
46
47 /**
48 * Enumerates all names of registry entries under the path that this object describes.
49 * @return an enumeration listing all entry names
50 */
51 public Enumeration<String> names()
52 {
53     return new Win32RegKeyNameEnumeration(root, path);
54 }
55
56 static
57 {
58     System.loadLibrary("Win32RegKey");
59 }
60 }
61
62 class Win32RegKeyNameEnumeration implements Enumeration<String>
63 {
64     public native String nextElement();
65     public native boolean hasMoreElements();
66     private int root;
67     private String path;
68     private int index = -1;
69     private int hkey = 0;
70     private int maxsize;
71     private int count;
72
73     Win32RegKeyNameEnumeration(int theRoot, String thePath)
74     {
75         root = theRoot;
76         path = thePath;
77     }
78 }
79
80 class Win32RegKeyException extends RuntimeException
81 {
82     public Win32RegKeyException()
83     {
84     }
85
86     public Win32RegKeyException(String why)
87     {
88         super(why);
89     }
90 }
```

```
1  /**
2   * @version 1.00 1997-07-01
3   * @author Cay Horstmann
4  */
5
6 #include "Win32RegKey.h"
7 #include "Win32RegKeyNameEnumeration.h"
8 #include <string.h>
9 #include <stdlib.h>
10 #include <windows.h>
11
12 JNIEXPORT jobject JNICALL Java_Win32RegKey_getValue(
13     JNIEnv* env, jobject this_obj, jobject name)
14 {
15     const char* cname;
16     jstring path;
17     const char* cpath;
18     HKEY hkey;
19     DWORD type;
20     DWORD size;
21     jclass this_class;
22     jfieldID id_root;
23     jfieldID id_path;
24     HKEY root;
25     jobject ret;
26     char* cret;
27
28     /* get the class */
29     this_class = (*env)->GetObjectClass(env, this_obj);
30
31     /* get the field IDs */
32     id_root = (*env)->GetFieldID(env, this_class, "root", "I");
33     id_path = (*env)->GetFieldID(env, this_class, "path", "Ljava/lang/String;");
34
35     /* get the fields */
36     root = (HKEY) (*env)->GetIntField(env, this_obj, id_root);
37     path = (jstring)(*env)->GetObjectField(env, this_obj, id_path);
38     cpath = (*env)->GetStringUTFChars(env, path, NULL);
39
40     /* open the registry key */
41     if (RegOpenKeyEx(root, cpath, 0, KEY_READ, &hkey) != ERROR_SUCCESS)
42     {
43         (*env)->ThrowNew(env, (*env)->FindClass(env, "Win32RegKeyException"),
44                             "Open key failed");
45         (*env)->ReleaseStringUTFChars(env, path, cpath);
46         return NULL;
47     }
48 }
```

```
49     (*env)->ReleaseStringUTFChars(env, path, cpath);
50     cname = (*env)->GetStringUTFChars(env, name, NULL);
51
52     /* find the type and size of the value */
53     if (RegQueryValueEx(hkey, cname, NULL, &type, NULL, &size) != ERROR_SUCCESS)
54     {
55         (*env)->ThrowNew(env, (*env)->FindClass(env, "Win32RegKeyException"),
56                             "Query value key failed");
57         RegCloseKey(hkey);
58         (*env)->ReleaseStringUTFChars(env, name, cname);
59         return NULL;
60     }
61
62     /* get memory to hold the value */
63     cret = (char*)malloc(size);
64
65     /* read the value */
66     if (RegQueryValueEx(hkey, cname, NULL, &type, cret, &size) != ERROR_SUCCESS)
67     {
68         (*env)->ThrowNew(env, (*env)->FindClass(env, "Win32RegKeyException"),
69                             "Query value key failed");
70         free(cret);
71         RegCloseKey(hkey);
72         (*env)->ReleaseStringUTFChars(env, name, cname);
73         return NULL;
74     }
75
76     /* depending on the type, store the value in a string,
77      integer, or byte array */
78     if (type == REG_SZ)
79     {
80         ret = (*env)->NewStringUTF(env, cret);
81     }
82     else if (type == REG_DWORD)
83     {
84         jclass class_Integer = (*env)->FindClass(env, "java/lang/Integer");
85         /* get the method ID of the constructor */
86         jmethodID id_Integer = (*env)->GetMethodID(env, class_Integer, "<init>", "(I)V");
87         int value = *(int*) cret;
88         /* invoke the constructor */
89         ret = (*env)->NewObject(env, class_Integer, id_Integer, value);
90     }
91     else if (type == REG_BINARY)
92     {
93         ret = (*env)->NewByteArray(env, size);
94         (*env)->SetByteArrayRegion(env, (jarray) ret, 0, size, cret);
95     }
96     else
97     {
```

```
98     (*env)->ThrowNew(env, (*env)->FindClass(env, "Win32RegKeyException"),
99         "Unsupported value type");
100    ret = NULL;
101 }
102
103 free(cret);
104 RegCloseKey(hkey);
105 (*env)->ReleaseStringUTFChars(env, name, cname);
106
107 return ret;
108 }
109
110 JNIEXPORT void JNICALL Java_Win32RegKey_setValue(JNIEnv* env, jobject this_obj,
111 jstring name, jobject value)
112 {
113     const char* cname;
114     jstring path;
115     const char* cpath;
116     HKEY hkey;
117     DWORD type;
118     DWORD size;
119     jclass this_class;
120     jclass class_value;
121     jclass class_Integer;
122     jfieldID id_root;
123     jfieldID id_path;
124     HKEY root;
125     const char* cvalue;
126     int ivalue;
127
128     /* get the class */
129     this_class = (*env)->GetObjectClass(env, this_obj);
130
131     /* get the field IDs */
132     id_root = (*env)->GetFieldID(env, this_class, "root", "I");
133     id_path = (*env)->GetFieldID(env, this_class, "path", "Ljava/lang/String;");
134
135     /* get the fields */
136     root = (HKEY)(*env)->GetIntField(env, this_obj, id_root);
137     path = (jstring)(*env)->GetObjectField(env, this_obj, id_path);
138     cpath = (*env)->GetStringUTFChars(env, path, NULL);
139
140     /* open the registry key */
141     if (RegOpenKeyEx(root, cpath, 0, KEY_WRITE, &hkey) != ERROR_SUCCESS)
142     {
143         (*env)->ThrowNew(env, (*env)->FindClass(env, "Win32RegKeyException"),
144             "Open key failed");
```

```
145     (*env)->ReleaseStringUTFChars(env, path, cpath);
146     return;
147 }
148
149 (*env)->ReleaseStringUTFChars(env, path, cpath);
150 cname = (*env)->GetStringUTFChars(env, name, NULL);
151
152 class_value = (*env)->GetObjectClass(env, value);
153 class_Integer = (*env)->FindClass(env, "java/lang/Integer");
154 /* determine the type of the value object */
155 if ((*env)->IsAssignableFrom(env, class_value, (*env)->FindClass(env, "java/lang/String")))
156 {
157     /* it is a string--get a pointer to the characters */
158     cvalue = (*env)->GetStringUTFChars(env, (jstring) value, NULL);
159     type = REG_SZ;
160     size = (*env)->GetStringLength(env, (jstring) value) + 1;
161 }
162 else if ((*env)->IsAssignableFrom(env, class_value, class_Integer))
163 {
164     /* it is an integer--call intValue to get the value */
165     jmethodID id_intValue = (*env)->GetMethodID(env, class_Integer, "intValue", "()I");
166     ivalue = (*env)->CallIntMethod(env, value, id_intValue);
167     type = REG_DWORD;
168     cvalue = (char*)&ivalue;
169     size = 4;
170 }
171 else if ((*env)->IsAssignableFrom(env, class_value, (*env)->FindClass(env, "[B")))
172 {
173     /* it is a byte array--get a pointer to the bytes */
174     type = REG_BINARY;
175     cvalue = (char*)(*env)->GetByteArrayElements(env, (jarray) value, NULL);
176     size = (*env)->GetArrayLength(env, (jarray) value);
177 }
178 else
179 {
180     /* we don't know how to handle this type */
181     (*env)->ThrowNew(env, (*env)->FindClass(env, "Win32RegKeyException"),
182                     "Unsupported value type");
183     RegCloseKey(hkey);
184     (*env)->ReleaseStringUTFChars(env, name, cname);
185     return;
186 }
187
188 /* set the value */
189 if (RegSetValueEx(hkey, cname, 0, type, cvalue, size) != ERROR_SUCCESS)
190 {
191     (*env)->ThrowNew(env, (*env)->FindClass(env, "Win32RegKeyException"),
192                     "Set value failed");
193 }
```

```
194     RegCloseKey(hkey);
195     (*env)->ReleaseStringUTFChars(env, name, cname);
196
197     /* if the value was a string or byte array, release the pointer */
198     if (type == REG_SZ)
199     {
200         (*env)->ReleaseStringUTFChars(env, (jstring) value, cvalue);
201     }
202     else if (type == REG_BINARY)
203     {
204         (*env)->ReleaseByteArrayElements(env, (jarray) value, (jbyte*) cvalue, 0);
205     }
206 }
207 }
208
209 /* helper function to start enumeration of names */
210 static int startNameEnumeration(JNIEnv* env, jobject this_obj, jclass this_class)
211 {
212     jfieldID id_index;
213     jfieldID id_count;
214     jfieldID id_root;
215     jfieldID id_path;
216     jfieldID id_hkey;
217     jfieldID id_maxsize;
218
219     HKEY root;
220     jstring path;
221     const char* cpath;
222     HKEY hkey;
223     DWORD maxsize = 0;
224     DWORD count = 0;
225
226     /* get the field IDs */
227     id_root = (*env)->GetFieldID(env, this_class, "root", "I");
228     id_path = (*env)->GetFieldID(env, this_class, "path", "Ljava/lang/String;");
229     id_hkey = (*env)->GetFieldID(env, this_class, "hkey", "I");
230     id_maxsize = (*env)->GetFieldID(env, this_class, "maxsize", "I");
231     id_index = (*env)->GetFieldID(env, this_class, "index", "I");
232     id_count = (*env)->GetFieldID(env, this_class, "count", "I");
233
234     /* get the field values */
235     root = (HKEY)(*env)->GetIntField(env, this_obj, id_root);
236     path = (jstring)(*env)->GetObjectField(env, this_obj, id_path);
237     cpath = (*env)->GetStringUTFChars(env, path, NULL);
238
239     /* open the registry key */
```

```
249     if (RegOpenKeyEx(root, cpath, 0, KEY_READ, &hkey) != ERROR_SUCCESS)
250     {
251         (*env)->ThrowNew(env, (*env)->FindClass(env, "Win32RegKeyException"),
252                             "Open key failed");
253         (*env)->ReleaseStringUTFChars(env, path, cpath);
254         return -1;
255     }
256     (*env)->ReleaseStringUTFChars(env, path, cpath);
257
258     /* query count and max length of names */
259     if (RegQueryInfoKey(hkey, NULL, NULL, NULL, NULL, NULL, NULL, &count, &maxsize,
260                         NULL, NULL, NULL) != ERROR_SUCCESS)
261     {
262         (*env)->ThrowNew(env, (*env)->FindClass(env, "Win32RegKeyException"),
263                             "Query info key failed");
264         RegCloseKey(hkey);
265         return -1;
266     }
267
268     /* set the field values */
269     (*env)->SetIntField(env, this_obj, id_hkey, (DWORD) hkey);
270     (*env)->SetIntField(env, this_obj, id_maxsize, maxsize + 1);
271     (*env)->SetIntField(env, this_obj, id_index, 0);
272     (*env)->SetIntField(env, this_obj, id_count, count);
273     return count;
274 }
275
276 JNIEXPORT jboolean JNICALL Java_Win32RegKeyNameEnumeration_hasMoreElements(JNIEnv* env,
277                             jobject this_obj)
278 {
279     jclass this_class;
280     jfieldID id_index;
281     jfieldID id_count;
282     int index;
283     int count;
284     /* get the class */
285     this_class = (*env)->GetObjectClass(env, this_obj);
286
287     /* get the field IDs */
288     id_index = (*env)->GetFieldID(env, this_class, "index", "I");
289     id_count = (*env)->GetFieldID(env, this_class, "count", "I");
290
291     index = (*env)->GetIntField(env, this_obj, id_index);
292     if (index == -1) /* first time */
293     {
294         count = startNameEnumeration(env, this_obj, this_class);
295         index = 0;
296     }
297 }
```

```
288     else
289         count = (*env)->GetIntField(env, this_obj, id_count);
290     return index < count;
291 }
292
293 JNIEXPORT jobject JNICALL Java_Win32RegKeyNameEnumeration.nextElement(JNIEnv* env,
294                         jobject this_obj)
295 {
296     jclass this_class;
297     jfieldID id_index;
298     jfieldID id_hkey;
299     jfieldID id_count;
300     jfieldID id_maxsize;
301
302     HKEY hkey;
303     int index;
304     int count;
305     DWORD maxsize;
306
307     char* cret;
308     jstring ret;
309
310     /* get the class */
311     this_class = (*env)->GetObjectClass(env, this_obj);
312
313     /* get the field IDs */
314     id_index = (*env)->GetFieldID(env, this_class, "index", "I");
315     id_count = (*env)->GetFieldID(env, this_class, "count", "I");
316     id_hkey = (*env)->GetFieldID(env, this_class, "hkey", "I");
317     id_maxsize = (*env)->GetFieldID(env, this_class, "maxsize", "I");
318
319     index = (*env)->GetIntField(env, this_obj, id_index);
320     if (index == -1) /* first time */
321     {
322         count = startNameEnumeration(env, this_obj, this_class);
323         index = 0;
324     }
325     else
326         count = (*env)->GetIntField(env, this_obj, id_count);
327
328     if (index >= count) /* already at end */
329     {
330         (*env)->ThrowNew(env, (*env)->FindClass(env, "java/util/NoSuchElementException"),
331                         "past end of enumeration");
332         return NULL;
333     }
334
335     maxsize = (*env)->GetIntField(env, this_obj, id_maxsize);
```

```
336 hkey = (HKEY)(*env)->GetIntField(env, this_obj, id_hkey);
337 cret = (char*)malloc(maxsize);
338
339 /* find the next name */
340 if (RegEnumValue(hkey, index, cret, &maxsize, NULL, NULL, NULL, NULL) != ERROR_SUCCESS)
341 {
342     (*env)->ThrowNew(env, (*env)->FindClass(env, "Win32RegKeyException"),
343                         "Enum value failed");
344     free(cret);
345     RegCloseKey(hkey);
346     (*env)->SetIntField(env, this_obj, id_index, count);
347     return NULL;
348 }
349
350 ret = (*env)->NewStringUTF(env, cret);
351 free(cret);
352
353 /* increment index */
354 index++;
355 (*env)->SetIntField(env, this_obj, id_index, index);
356
357 if (index == count) /* at end */
358 {
359     RegCloseKey(hkey);
360 }
361
362 return ret;
363 }
```

```
1 import java.util.*;
2
3 /**
4     @version 1.04 2021-05-30
5     @author Cay Horstmann
6 */
7 public class Win32RegKeyTest
8 {
9     public static void main(String[] args)
10    {
11        var key = new Win32RegKey(
12            Win32RegKey.HKEY_CURRENT_USER, "Software\\JavaSoft\\Java Runtime Environment");
13
14        key.setValue("Default user", "Harry Hacker");
15        key.setValue("Lucky number", Integer.valueOf(13));
16        key.setValue("Small primes", new byte[] { 2, 3, 5, 7, 11 });
17
18        Enumeration<String> e = key.names();
19
20        while (e.hasMoreElements())
21        {
22            String name = e.nextElement();
23            System.out.print(name + "=");
24
25            Object value = key.getValue(name);
26
27            if (value instanceof byte[] bytes)
28                for (byte b : bytes) System.out.print((b & 0xFF) + " ");
29            else
30                System.out.print(value);
31
32            System.out.println();
33        }
34    }
35 }
```

```
javac --enable-preview --source 17 --add-modules \
    jdk.incubator.foreign panama/PanamaDemo.java
```

```
java --add-modules jdk.incubator.foreign \
    --enable-native-access=ALL-UNNAMED panama.PanamaDemo

1 package panama;
2
3 import java.lang.reflect.*;
4 import java.lang.invoke.*;
5 import jdk.incubator.foreign.*;

6 import static jdk.incubator.foreign.MemoryLayouts.*;
7
8 /*
9
10 javac --enable-preview --source I7 --add-modules jdk.incubator.foreign panama/PanamaDemo.java
11
12 java --add-modules jdk.incubator.foreign --enable-native-access=ALL-UNNAMED panama.PanamaDemo
13
14 */
15
16 public class PanamaDemo
17 {
18     public static void main(String[] args) throws Throwable
19     {
20         CLinker linker = CLinker.getInstance();
21         MethodHandle printf = linker.downcallHandle(
22             CLinker.systemLookup().lookup("printf").get(),
23             MethodType.methodType(int.class, MemoryAddress.class),
24             FunctionDescriptor.of(CLinker.C_INT, CLinker.C_POINTER));
25
26         try (ResourceScope scope = ResourceScope.newConfinedScope())
27         {
28             var cString = CLinker.toCString("Hello, World!\n", scope);
29             int result = (int) printf.invoke(cString.address());
30             System.out.println("Printed %d characters.".formatted(result));
31         }
32     }
33 }
```
